

An ACI Standard

Building Code for Structural Concrete— Code Requirements and Commentary

Reported by ACI Committee 318

ACI CODE-318-25



American Concrete Institute
Always advancing

Building Code for Structural Concrete—Code Requirements and Commentary (ACI CODE-318-25)

An ACI Standard
Reported by ACI Committee 318

Andrew W. Taylor, Chair

Gregory M. Zeisler, Secretary (Non-voting)

VOTING MEMBERS

Theresa M. Ahlborn
Sergio M. Alcocer
Neal S. Anderson
John F. Bonacci
JoAnn P. Browning
Ned M. Cleland
David Darwin
David C. Fields
Catherine E. French
Robert J. Frosch
Edith Gallandorm
Wassim M. Ghannoum

Satyendra Ghosh
James R. Harris
Carol Hayek
Mary Beth D. Hueste
Shana Kelley
Dominic J. Kelly
Gary J. Klein
Michael E. Kreger
Neven Krstulovic-Opara
Andres Lepage
Colin L. Lobo
Raymond Lui

Frank Stephen Malits
Jack P. Moehle
Miguel Mota
Daniel T. Mullins
Lawrence Novak
Carlos E. Ospina
Gustavo J. Parra-Montesinos
Viral B. Patel
Long T. Phan
Jose A. Pincheira
Randall W. Poston
Carin L. Roberts-Wollmann

David H. Sanders
Thomas C. Schaeffer
Andrea J. Schokker
Stephen J. Seguirant
John F. Silva
Lesley H. Sneed
Amy M.R. Trygstad
John W. Wallace
James K. Wight
Loring A. Wyllie Jr.

SUBCOMMITTEE MEMBERS

Saman Ali Abdullah
Michael E. Ahern
Hamid Ahmady
Rashid Ahmed
Scott D. B. Alexander
Carlos A. Arteta
Suzanne Aultman
Robert W. Barnes
F. Michael Bartlett
Asit N. Baxi
Abdeldjelil Belarbi
Raul D. Bertero
Agnieszka Bigaj-Van Vliet
K. Dirk Bondy
Sergio F. Brena
Jared E. Brewe
Julie K. Buffenbarger
Nicholas J. Carino
Julian Carrillo
Min Yuan Cheng
Eamonn F. Connolly
Juan Francisco Correal Daza
Martin A. Cuadra
Mary Cuthbert
Matthew D. D'Ambrosia
Austin Devin
Jeffrey J. Dragovich

Jason L. Draper
Kenneth J. Elwood
Scott D. Erickson
Robert B. Esplin
Luis B. Fargier-Gabaldon
Lisa R. Feldman
Joe Ferzli
Damon R. Fick
Rudolph P. Frizzi
Werner A. F. Fuchs
Harry A. Gleich
Alana G. Guzzetta
David L. Hartmann
Richard Henry
Robert B. Holland
Terence C. Holland
Augusto H. Holmberg
Robert D. Hooton
Kenneth C. Hover
Matias Hube
Jonathan Hurff
Hyeon Jong Hwang
Jose M. Izquierdo-Encarnacion
Maria G. Juenger
Thomas Kang
Keith E. Kesner
John Kilpatrick

Insung Kim
Ronald Klemencic
Donald P. Kline
James E. Klinger
Larry B. Krauser
Jason J. Krohn
Daniel A. Kuchma
Anthony J. Lamanna
Justin D. Lazenby
Hung-Jen Lee
Dawn E. Lehman
Remy D. Lequesne
Emily B. Lorenz
Laura N. Lowes
Adam S. Lubell
Kevin A. MacDonald
Adolfo B. Matamoros
Ian S. McFarlane
Gregory S. McKinnon
Fred Meyer
Christopher Motter
Antonio Nanni
William H. Oliver
Enrique Pasquel
Conrad Paulson
Santiago Pujol
Jeffrey Rautenberg

Kyle Austin Riding
Kelly Levy Roberts
Mario E. Rodriguez
Bruce W. Russell
Guillermo Santana
Christopher L. Segura, Jr.
Hitoshi Shiohara
Anurag Sinha
Seymour M.J. Spence
John F. Stanton
Roberto Stark
Daniel S. Stevenson
Fernando Reboucas Stucchi
George I. Taylor
Julio Timmerman
Nancy Larson Varney
Jeffery S. Volz
Roman Wan-Wendner
Jason Weiss
Benjamin L. Worsfold
Teng Wu
Zuming Xia
Fernando Yanez
Fouad H. Yazbeck
Alec Zimmer

James R. Cagley

Charles W. Dolan
Neil M. Hawkins

James O. Jirsa
Basile G. Rabbat

Sharon L. Wood

CONSULTING MEMBERS

ACI CODE-318-25 was approved by the ACI Standards Board for publication January 2025, and published January 2025. ACI CODE-318 was first published in 1908, and revised in 1910, 1920, 1927, 1936, 1941, 1947, 1951, 1956, 1963, 1971, 1977, 1983, 1989, 1995, 1999, 2002, 2005, 2011, 2014, and 2019.

Copyright © 2025, American Concrete Institute.

All rights reserved including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction or for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.



Building Code for Structural Concrete—Code Requirements and Commentary

© 2025 American Concrete Institute. All rights reserved.

This material may not be reproduced or copied, in whole or in part, in any form or by any means, including making copies by any photo process, or by electronic or mechanical device, printed, written, graphic, or oral, or recording for sound or visual reproduction for use in any knowledge or retrieval system or device, without the written consent of ACI. This material may not be used by data mining, robots, screen scraping, or similar data gathering and extraction tools such as artificial intelligence (“AI”) for purposes of developing or training a machine learning or AI model, conducting computer analysis or creating derivatives of this material, without the written consent of ACI.

The technical committees responsible for ACI committee reports and standards strive to avoid ambiguities, omissions, and errors in these documents. Despite these efforts, the users of ACI documents occasionally find information or requirements that may be subject to more than one interpretation or may be incomplete or incorrect. Users who have suggestions for the improvement of ACI documents are requested to contact ACI via the errata website at <http://concrete.org/Publications/DocumentErrata.aspx>. Proper use of this document includes periodically checking for errata for the most up-to-date revisions.

ACI committee documents are intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. Individuals who use this publication in any way assume all risk and accept total responsibility for the application and use of this information.

All information in this publication is provided “as is” without warranty of any kind, either express or implied, including but not limited to, the implied warranties of merchantability, fitness for a particular purpose or non-infringement.

ACI and its members disclaim liability for damages of any kind, including any special, indirect, incidental, or consequential damages, including without limitation, lost revenues or lost profits, which may result from the use of this publication.

It is the responsibility of the user of this document to establish health and safety practices appropriate to the specific circumstances involved with its use. ACI does not make any representations regarding health and safety issues and the use of this document. The user must determine the applicability of all regulatory limitations before applying the document and must comply with all applicable laws and regulations, including but not limited to, United States Occupational Safety and Health Administration (OSHA) health and safety standards.

Participation by governmental representatives in the work of the American Concrete Institute and in the development of Institute standards does not constitute governmental endorsement of ACI or the standards that it develops.

ACI documents are written via a consensus-based process. The characteristics of ACI technical committee operations include:

- (a) Open committee membership
- (b) Balance/lack of dominance
- (c) Coordination and harmonization of information
- (d) Transparency of committee activities to public
- (e) Consideration of views and objections
- (f) Resolution through consensus process

The technical committee documents of the American Concrete Institute represent the consensus of the committee and ACI. Technical committee members are individuals who volunteer their services to ACI and specific technical committees.

American Concrete Institute®, ACI®, and Always Advancing® are registered trademarks of American Concrete Institute.

PREFACE TO ACI CODE-318-25

The “Building Code for Structural Concrete” (“Code”) provides minimum requirements for the materials, design, and detailing of structural concrete buildings and, where applicable, nonbuilding structures. The Code was developed using a consensus process and addresses structural systems, members, and connections, including cast-in-place, precast, shotcrete, plain, nonprestressed, and prestressed, construction. Among the subjects covered are: design and construction for strength, serviceability, and durability; load combinations, load factors, and strength reduction factors; structural analysis methods; deflection limits; mechanical and adhesive anchoring to concrete; development and splicing of reinforcement; construction document information; field inspection and testing; methods to evaluate the strength of existing structures; design verification using nonlinear response history analysis in Appendix A; performance-based wind design in Appendix B, and sustainability and resilience in Appendix C.

Uses of the Code include adoption by reference in a general building code, and earlier editions have been widely used in this manner. The Code is written in a format that allows such reference without change to its language. Commentary is provided for background information and further explanation of the code requirements. Cited references provide research data useful in studying technical issues in greater detail. Other references, provide greater insight into the code the requirements. Technical changes from **ACI CODE-318-19** to ACI CODE-318-25 are indicated by change bars in the margins of the print and PDF versions. Technical changes from ACI CODE-318-19 to ACI CODE-318-25 may also be viewed in red highlights within the PLUS version (<https://www.concrete.org/publications/aci318plus.aspx>).

Special thanks to Bentley Systems, Incorporated, for use of their ProConcrete software to produce many of the figures found in the Commentary.

KEYWORDS

admixtures; aggregates; anchorage (structural); beam-column frame; beams (supports); caissons; cements; cold weather; columns (supports); combined stress; composite construction (concrete to concrete); compressive strength; concrete; construction documents; construction joints; continuity (structural); contraction joints; cover; curing; deep beams; deep foundations; deflections; drilled piers; earthquake-resistant structures; flexural strength; floors; footings; formwork (construction); hot weather; inspection; isolation joints; joints (junctions); joists; lightweight concretes; load tests (structural); loads (forces); mixture proportioning; modulus of elasticity; moments; piles; placing; plain concrete; precast concrete; prestressed concrete; prestressing steels; quality control; reinforced concrete; reinforcing steels; resilience; roofs; serviceability; shear strength; shotcrete; spans; splicing; strength analysis; stresses; structural analysis; structural design; structural integrity; structural walls; sustainability; T-beams; torsion; walls; water; welded wire reinforcement.

INTRODUCTION

ACI CODE-318-25, “Building Code for Structural Concrete—Code Requirements and Commentary,” herein-after called the Code or the 2025 Code are presented in a side by- side column format. The Code requirements and Commentary are two separate but coordinated documents, with Code text placed in the left column and the corresponding Commentary text aligned in the right column. Commentary section numbers are preceded by an “R” to further distinguish them from Code section numbers. The two documents are bound together solely for the user’s convenience. Each document carries a separate enforceable and distinct copyright.

As the name implies, “Building Code for Structural Concrete—Code Requirements” is meant to be used as part of a legally adopted building code and as such must differ in form and substance from documents that provide detailed specifications, recommended practice, complete design procedures, or design aids.

The Code is intended to cover all buildings of the usual types, both large and small. Requirements more stringent than the Code provisions may be desirable for different types of construction. The Code and Commentary cannot replace sound engineering knowledge, experience, and judgment.

A building code states only the minimum requirements necessary to provide for public health and safety. The Code is based on this principle. For any structure, the owner or the licensed design professional may require the quality of materials and construction to be higher than the minimum requirements necessary to protect the public as stated in the Code. Lower standards are not permitted.

The Code has no legal status unless it is adopted by the government bodies having the police power to regulate building design and construction. Where the Code has not been adopted, it may serve as a reference to good practice even though it has no legal status.

The Code and Commentary are not intended for use in settling disputes between the owner, engineer, architect, contractor, or their agents, subcontractors, material suppliers, or testing agencies. Therefore, the Code cannot define the contract responsibility of each of the parties in usual construction. General references requiring compliance with the Code in the project specifications should be avoided because the contractor is rarely in a position to accept responsibility for design details or construction requirements that depend on a detailed knowledge of the design. Design-build construction contractors, however, typically combine the design and construction responsibility. Generally, the contract documents should contain all necessary requirements to ensure compliance with the Code. In part, this can be accomplished by reference to specific Code sections in the project specifications. Other ACI publications, such as “Specifications for Concrete Construction” (ACI SPEC-

301), are written specifically for use as contract documents for construction.

The Commentary discusses some of the considerations of Committee 318 in developing the provisions contained in the Code. Emphasis is given to the explanation of new or revised provisions that may be unfamiliar to Code users. In addition, comments are included for some items contained in previous editions of the Code to make the present Commentary independent of the previous editions. Comments on specific provisions are made under the corresponding chapter and section numbers of the Code.

The Commentary is not intended to provide a complete historical background concerning the development of the Code, nor is it intended to provide a detailed résumé of the studies and research data reviewed by the committee in formulating the provisions of the Code. However, references to some of the research data are provided for those who wish to study the background material in depth.

The Commentary directs attention to other documents that provide suggestions for carrying out the requirements and intent of the Code. However, those documents and the Commentary are not a part of the Code.

The Commentary is intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations, and who will accept responsibility for the application of the information it contains. ACI disclaims any and all responsibility for the stated principles. The Institute shall not be liable for any loss or damage arising therefrom. Reference to the Commentary shall not be made in construction documents. If items found in the Commentary are desired by the licensed design professional to be a part of the contract documents, they shall be restated in mandatory language for incorporation by the licensed design professional.

It is recommended to have the materials, processes, quality control measures, and inspections described in this document tested, monitored, or performed by individuals holding the appropriate ACI Certification or equivalent, when available. The personnel certification programs of the American Concrete Institute and the Post-Tensioning Institute; the plant certification programs of the Precast/Prestressed Concrete Institute, the Post-Tensioning Institute, and the National Ready Mixed Concrete Association; and the Concrete Reinforcing Steel Institute’s Voluntary Certification Program for Fusion-Bonded Epoxy Coating Applicator Plants are available for this purpose. In addition, “Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection” (ASTM E329-18) specifies performance requirements for inspection and testing agencies.

Design reference materials illustrating applications of the Code requirements may be found on the ACI website, www.concrete.org.

TABLE OF CONTENTS

PART 1: GENERAL**CHAPTER 1
GENERAL**

- 1.1—Scope of ACI CODE-318, p. 9
- 1.2—General, p. 9
- 1.3—Purpose, p. 10
- 1.4—Applicability, p. 10
- 1.5—Interpretation, p. 12
- 1.6—Building official, p. 13
- 1.7—Licensed design professional, p. 13
- 1.8—Construction documents and design records, p. 13

**CHAPTER 2
NOTATION AND TERMINOLOGY**

- 2.1—Scope, p. 15
- 2.2—Notation, p. 15
- 2.3—Terminology, p. 23

**CHAPTER 3
REFERENCED STANDARDS**

- 3.1—Scope, p. 55
- 3.2—Referenced standards, p. 55

**CHAPTER 4
STRUCTURAL SYSTEM REQUIREMENTS**

- 4.1—Scope, p. 59
- 4.2—Materials, p. 59
- 4.3—Design loads, p. 59
- 4.4—Structural system and load paths, p. 59
- 4.5—Structural analysis, p. 62
- 4.6—Strength, p. 62
- 4.7—Serviceability, p. 64
- 4.8—Durability, p. 64
- 4.9—Sustainability and resilience, p. 64
- 4.10—Structural integrity, p. 64
- 4.11—Fire resistance, p. 65
- 4.12—Requirements for specific types of construction, p. 65
- 4.13—Construction and inspection, p. 68
- 4.14—Strength evaluation of existing structures, p. 68

PART 2: LOADS & ANALYSIS**CHAPTER 5
LOADS**

- 5.1—Scope, p. 69
- 5.2—General, p. 69
- 5.3—Load factors and combinations, p. 69

**CHAPTER 6
STRUCTURAL ANALYSIS**

- 6.1—Scope, p. 75
- 6.2—General, p. 75
- 6.3—Modeling assumptions, p. 81
- 6.4—Arrangement of live load, p. 82

- 6.5—Simplified method of analysis for nonprestressed continuous beams and one-way slabs, p. 83
- 6.6—Linear elastic first-order analysis, p. 84
- 6.7—Linear elastic second-order analysis, p. 95
- 6.8—Inelastic analysis, p. 96
- 6.9—Acceptability of finite element analysis, p. 97

PART 3: MEMBERS**CHAPTER 7
ONE-WAY SLABS**

- 7.1—Scope, p. 99
- 7.2—General, p. 99
- 7.3—Design limits, p. 99
- 7.4—Required strength, p. 101
- 7.5—Design strength, p. 101
- 7.6—Reinforcement limits, p. 102
- 7.7—Reinforcement detailing, p. 105

**CHAPTER 8
TWO-WAY SLABS**

- 8.1—Scope, p. 111
- 8.2—General, p. 111
- 8.3—Design limits, p. 112
- 8.4—Required strength, p. 114
- 8.5—Design strength, p. 120
- 8.6—Reinforcement limits, p. 121
- 8.7—Reinforcement detailing, p. 124
- 8.8—Nonprestressed two-way joist systems, p. 138
- 8.9—Lift-slab construction, p. 139

**CHAPTER 9
BEAMS**

- 9.1—Scope, p. 141
- 9.2—General, p. 141
- 9.3—Design limits, p. 142
- 9.4—Required strength, p. 144
- 9.5—Design strength, p. 147
- 9.6—Reinforcement limits, p. 149
- 9.7—Reinforcement detailing, p. 152
- 9.8—Nonprestressed one-way joist systems, p. 163
- 9.9—Deep beams, p. 164

**CHAPTER 10
COLUMNS**

- 10.1—Scope, p. 169
- 10.2—General, p. 169
- 10.3—Design limits, p. 169
- 10.4—Required strength, p. 170
- 10.5—Design strength, p. 171
- 10.6—Reinforcement limits, p. 171
- 10.7—Reinforcement detailing, p. 172

**CHAPTER 11
WALLS**

- 11.1—Scope, p. 179
- 11.2—General, p. 179

- 11.3—Design limits, p. 180
- 11.4—Required strength, p. 180
- 11.5—Design strength, p. 182
- 11.6—Reinforcement limits, p. 184
- 11.7—Reinforcement detailing, p. 185
- 11.8—Alternative method for out-of-plane slender wall analysis, p. 186

CHAPTER 12

DIAPHRAGMS

- 12.1—Scope, p. 189
- 12.2—General, p. 190
- 12.3—Design limits, p. 192
- 12.4—Required strength, p. 192
- 12.5—Design strength, p. 195
- 12.6—Reinforcement limits, p. 202
- 12.7—Reinforcement detailing, p. 202

CHAPTER 13

FOUNDATIONS

- 13.1—Scope, p. 205
- 13.2—General, p. 207
- 13.3—Shallow foundations, p. 211
- 13.4—Deep foundations, p. 214

PART 4: JOINTS/CONNECTIONS/ANCHORS

CHAPTER 14

PLAIN CONCRETE

- 14.1—Scope, p. 221
- 14.2—General, p. 222
- 14.3—Design limits, p. 222
- 14.4—Required strength, p. 224
- 14.5—Design strength, p. 225
- 14.6—Reinforcement detailing, p. 227

CHAPTER 15

CAST-IN-PLACE JOINTS

- 15.1—Scope, p. 229
- 15.2—General, p. 229
- 15.3—Design limits, p. 229
- 15.4—Required strength, p. 230
- 15.5—Design strength, p. 230
- 15.6—Reinforcement limits, p. 233
- 15.7—Reinforcement detailing, p. 233
- 15.8—Transfer of column axial force through the floor system, p. 234

CHAPTER 16

CONNECTIONS BETWEEN MEMBERS

- 16.1—Scope, p. 235
- 16.2—Connections of precast members, p. 235
- 16.3—Connections to foundations, p. 240
- 16.4—Horizontal shear transfer in composite concrete flexural members, p. 243
- 16.5—Brackets and corbels, p. 246

CHAPTER 17

ANCHORING TO CONCRETE

- 17.1—Scope, p. 253
- 17.2—General, p. 254
- 17.3—Design Limits, p. 255
- 17.4—Required strength, p. 257
- 17.5—Design strength, p. 257
- 17.6—Tensile strength, p. 266
- 17.7—Shear strength, p. 282
- 17.8—Tension and shear interaction, p. 292
- 17.9—Edge distances, spacings, and thicknesses to preclude splitting failure, p. 293
- 17.10—Earthquake-resistant anchor design requirements, p. 295
- 17.11—Attachments with shear lugs, p. 300

PART 5: EARTHQUAKE RESISTANCE

CHAPTER 18

EARTHQUAKE-RESISTANT STRUCTURES

- 18.1—Scope, p. 307
- 18.2—General, p. 308
- 18.3—Ordinary moment frames, p. 315
- 18.4—Intermediate moment frames, p. 316
- 18.5—Intermediate precast structural walls, p. 325
- 18.6—Beams of special moment frames, p. 325
- 18.7—Columns of special moment frames, p. 334
- 18.8—Joints of special moment frames, p. 340
- 18.9—Special moment frames constructed using precast concrete
- 18.10—Special structural walls, p. 346
- 18.11—Special structural walls constructed using precast concrete, p. 374
- 18.12—Diaphragms and trusses, p. 374
- 18.13—Foundations, p. 382
- 18.14—Members not designated as part of the seismic-force-resisting system, p. 390

PART 6: MATERIALS & DURABILITY

CHAPTER 19

CONCRETE: DESIGN AND DURABILITY REQUIREMENTS

- 19.1—Scope, p. 395
- 19.2—Concrete design properties, p. 395
- 19.3—Concrete durability requirements, p. 398
- 19.4—Grout durability requirements, p. 410

CHAPTER 20

STEEL REINFORCEMENT PROPERTIES, DURABILITY, AND EMBEDMENTS

- 20.1—Scope, p. 409
- 20.2—Nonprestressed bars and wires, p. 409
- 20.3—Prestressing strands, wires, and bars, p. 415
- 20.4—Headed shear stud reinforcement, p. 419
- 20.6—Embedments, p. 427

PART 7: STRENGTH & SERVICEABILITY**CHAPTER 21
STRENGTH REDUCTION FACTORS**

- 21.1—Scope, p. 429
- 21.2—Strength reduction factors for structural concrete members and connections, p. 429

**CHAPTER 22
SECTIONAL STRENGTH**

- 22.1—Scope, p. 437
- 22.2—Design assumptions for moment and axial strength, p. 437
- 22.3—Flexural strength, p. 439
- 22.4—Axial strength or combined flexural and axial strength, p. 440
- 22.5—One-way shear strength, p. 441
- 22.7—Torsional strength, p. 459
- 22.8—Bearing, p. 468
- 22.9—Shear friction, p. 470

**CHAPTER 23
STRUT-AND-TIE METHOD**

- 23.1—Scope, p. 477
- 23.2—General, p. 479
- 23.3—Design strength, p. 484
- 23.4—Strength of struts, p. 484
- 23.5—Minimum distributed reinforcement, p. 486
- 23.7—Strength of ties, p. 489
- 23.8—Tie reinforcement detailing, p. 490
- 23.9—Strength of nodal zones, p. 491
- 23.10—Curved-bar nodes, p. 492
- 23.11—Earthquake-resistant design using the strut-and-tie method, p. 494

**CHAPTER 24
SERVICEABILITY**

- 24.1—Scope, p. 497
- 24.2—Deflections due to service-level gravity loads, p. 497
- 24.3—Distribution of flexural reinforcement in one-way slabs and beams, p. 502
- 24.4—Shrinkage and temperature reinforcement, p. 504
- 24.5—Permissible stresses in prestressed concrete flexural members, p. 506

PART 8: REINFORCEMENT**CHAPTER 25
REINFORCEMENT DETAILS**

- 25.1—Scope, p. 509
- 25.2—Minimum spacing of reinforcement, p. 509
- 25.3—Standard hooks, seismic hooks, crossties, and minimum inside bend diameters, p. 511
- 25.5—Splices, p. 534
- 25.6—Bundled reinforcement, p. 542
- 25.7—Transverse reinforcement, p. 544
- 25.8—Post-tensioning anchorages and couplers, p. 556
- 25.9—Anchorage zones for post-tensioned tendons, p. 557

PART 9: CONSTRUCTION**CHAPTER 26
CONSTRUCTION DOCUMENTS AND INSPECTION**

- 26.1—Scope, p. 567
- 26.2—Design criteria, p. 568
- 26.3—Member information, p. 568
- 26.4—Concrete materials, mixture requirements, and grouts, p. 568
- 26.5—Concrete production and construction, p. 578
- 26.6—Reinforcement materials and construction requirements, p. 587
- 26.7—Anchoring to concrete, p. 592
- 26.8—Embedments, p. 595
- 26.9—Additional requirements for precast concrete, p. 595
- 26.10—Additional requirements for post-tensioned concrete, p. 597
- 26.11—Formwork, p. 599
- 26.12—Evaluation and acceptance of hardened concrete, p. 601
- 26.13—Inspection, p. 607

PART 10: EVALUATION**CHAPTER 27
STRENGTH EVALUATION OF EXISTING STRUCTURES**

- 27.1—Scope, p. 613
- 27.2—General, p. 613
- 27.3—Analytical strength evaluation, p. 614
- 27.4—Strength evaluation by load test, p. 615

APPENDICES & REFERENCES**APPENDIX A
DESIGN VERIFICATION USING NONLINEAR RESPONSE HISTORY ANALYSIS**

- A.1—Notation and terminology, p. 621
- A.2—Scope, p. 621
- A.3—General, p. 622
- A.4—Earthquake ground motions, p. 622
- A.5—Load factors and combinations, p. 623
- A.6—Modeling and analysis, p. 623
- A.7—Action classification and criticality, p. 624
- A.8—Effective stiffness, p. 625
- A.9—Expected material strength, p. 627
- A.10—Acceptance criteria for deformation-controlled actions, p. 628
- A.11—Expected strength for force-controlled actions, p. 629
- A.12—Enhanced detailing requirements, p. 631
- A.13—Independent structural design review, p. 632

**APPENDIX B
PERFORMANCE-BASED WIND DESIGN**

- B.1—Notation and Terminology, p. 635
- B.2—Scope, p. 636
- B.3—General, p. 636

- B.4—Wind loading, p. 638
- B.5—Load factors and combinations, p. 639
- B.6—Modeling and analysis, p. 640
- B.7—Action classification and requirements, p. 642
- B.8—Effective stiffness, p. 642
- B.9—Expected material strength, p. 644
- B.10—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective—general, p. 644
- B.11—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Method 1, p. 645
- B.12—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Methods 2 and 3, p. 647
- B.13—Detailing requirements, p. 648
- B.14—Independent structural design review, p. 652

APPENDIX C

SUSTAINABILITY AND RESILIENCE

- C.1—Terminology, p. 655
- C.2—Scope, p. 656
- C.3—Evaluation of Sustainability of Structural Concrete Systems, p. 656
- C.4—Resilience, p. 658
- C.5—Concrete Mixtures, p. 660

APPENDIX D

STEEL REINFORCEMENT INFORMATION, P. 663

APPENDIX E

EQUIVALENCE BETWEEN SI-METRIC, MKS-METRIC, AND U.S. CUSTOMARY UNITS OF NONHOMOGENEOUS EQUATIONS IN THE CODE

COMMENTARY REFERENCES

INDEX

CHAPTER 1—GENERAL

CODE

COMMENTARY

1.1—Scope of ACI CODE-318

1.1.1 This chapter addresses (a) through (h):

- (a) General requirements of this Code
- (b) Purpose of this Code
- (c) Applicability of this Code
- (d) Interpretation of this Code
- (e) Definition and role of the building official and the licensed design professional
- (f) Construction documents
- (g) Testing and inspection
- (h) Approval of special systems of design, construction, or alternative construction materials

1.2—General

1.2.1 ACI CODE-318, “Building Code Requirements for Structural Concrete,” is hereafter referred to as “this Code.”

1.2.2 In this Code, the general building code refers to the building code adopted in a jurisdiction. When adopted, this Code forms part of the general building code.

1.2.3 The official version of this Code is the English language version, using inch-pound units, published by the American Concrete Institute.

1.2.4 In case of conflict between the official version of this Code and other versions of this Code, the official version governs.

1.2.5 This Code provides minimum requirements for the materials, design, construction, and strength evaluation of structural concrete members and systems in any structure designed and constructed under the requirements of the general building code.

1.2.6 Modifications to this Code that are adopted by a particular jurisdiction are part of the laws of that jurisdiction, but are not a part of this Code.

1.2.7 If no general building code is adopted, this Code provides minimum requirements for the materials, design, construction, and strength evaluation of members and systems in any structure within the scope of this Code.

R1.1—Scope of ACI CODE-318

R1.1.1 The Code includes provisions for the design of concrete used for structural purposes, including plain concrete; concrete containing nonprestressed reinforcement, prestressed reinforcement, or both; and anchoring to concrete. This chapter includes a number of provisions that explain where the Code applies and how it is to be interpreted.

R1.2—General

R1.2.1 The commentary refers to ACI CODE-318 as “the Code.”

R1.2.2 The American Concrete Institute recommends that the Code be adopted in its entirety.

R1.2.3 Committee 318 develops the Code in English, using inch-pound units. Two translations are published by ACI:

- (a) In English using SI units (ACI CODE-318-25—Building Code Requirements for Structural Concrete [SI International System of Units])
- (b) In Spanish using SI units (ACI CODE-318-25—Requisitos de Reglamento para Concreto Estructural)

R1.2.5 The Code provides minimum requirements and exceeding these minimum requirements is not a violation of the Code.

The licensed design professional may specify project requirements that exceed the minimum requirements of the Code.

CODE

1.3—Purpose

1.3.1 The purpose of this Code is to provide for public health and safety by establishing minimum requirements for strength, stability, serviceability, durability, and integrity of concrete structures.

1.3.2 This Code does not address all design considerations.

1.3.3 Construction means and methods are not addressed in this Code.

1.4—Applicability

1.4.1 This Code shall apply to concrete structures designed and constructed under the requirements of the general building code.

1.4.2 Provisions of this Code shall be permitted to be used for the assessment, repair, and rehabilitation of existing structures.

1.4.3 Applicable provisions of this Code shall be permitted to be used for structures not governed by the general building code.

1.4.4 The design of thin shells and folded plate concrete structures shall be in accordance with **ACI CODE-318.2**, “Building Code Requirements for Concrete Thin Shells.”

1.4.5 This Code shall apply to the design of slabs cast on stay-in-place, noncomposite steel decks.

COMMENTARY

R1.3—Purpose

R1.3.1 The Code provides a means of establishing minimum requirements for the design and construction of structural concrete, as well as for acceptance of design and construction of concrete structures by the building officials or their designated representatives. The Code does not provide a comprehensive statement of all duties of all parties to a contract or all requirements of a contract for a project constructed under the Code.

R1.3.2 The minimum requirements in the Code do not replace sound professional judgment or the licensed design professional’s knowledge of the specific factors surrounding a project, its design, the project site, and other specific or unusual circumstances of the project.

R1.4—Applicability

R1.4.2 Specific provisions for assessment, repair, and rehabilitation of existing concrete structures are provided in **ACI CODE-562**. Existing structures in ACI CODE-562 are defined as structures that are complete and permitted for use.

R1.4.3 Structures such as arches, bins and silos, blast-resistant structures, chimneys, underground utility structures, gravity walls, and shielding walls involve design and construction requirements that are not specifically addressed by the Code. Many Code provisions, however, such as concrete quality and design principles, are applicable for these structures. Recommendations for design and construction of some of these structures are given in the following:

- “Requirements for Reinforced Concrete Chimneys—Code and Commentary” (**ACI CODE-307**)
- “Design Specification for Concrete Silos and Stacking Tubes for Storing Granular Materials” (**ACI SPEC-313**)
- “Code Requirements for Nuclear Safety-Related Concrete Structures and Commentary” (**ACI CODE-349**)
- “Code for Concrete Containments” (**ASME BPVC III-2**)

R1.4.5 In its most basic application, the noncomposite steel deck serves as a form, and the concrete slab is designed to resist all loads, while in other applications the concrete

CODE

1.4.6 For one- and two-family dwellings, multiple single-family dwellings, townhouses, and accessory structures to these types of dwellings, the design and construction of cast-in-place footings, foundation walls, and slabs-on-ground in accordance with ACI CODE-332 shall be permitted.

1.4.7 This Code does not apply to the design and installation of cast-in-place concrete deep foundation members that are smaller than 10 in. in diameter, or precast concrete deep foundation members with the least side dimension smaller than 10 in.

1.4.8 This Code does not apply to design and construction of slabs-on-ground, unless the slab transmits vertical loads or lateral forces from other portions of the structure to the soil.

1.4.9 This Code does not apply to the design of concrete members reinforced with fiber-reinforced polymer (FRP) bars.

1.4.10 This Code does not apply to the design and construction of tanks and reservoirs.

COMMENTARY

slab may be designed to resist only the superimposed loads. The design of a steel deck in a load-resisting application is given in “Standard for Steel Deck” (SD). The SDI standard refers to the Code for the design and construction of the structural concrete slab.

R1.4.6 **ACI CODE-332** addresses only the design and construction of cast-in-place footings, foundation walls supported on continuous footings, and slabs-on-ground for limited residential construction applications.

The **2021 IBC** requires design and construction of residential post-tensioned slabs on expansive soils to be in accordance with **PTI DC10.5**, which provides requirements for slab-on-ground foundations, including soil investigation, design, and analysis. Guidance for the design and construction of post-tensioned slabs-on-ground that are not on expansive soils can be found in **ACI PRC-360**. Refer to R1.4.8.

R1.4.7 Provisions for the design and construction of small concrete piles, including micropiles, are regulated by the general building code. The least side dimension of 10 in. in precast concrete deep foundation members refers to that of a square, or the shortest side of a rectangular cross section, or, for the case of octagonal piles, the diameter of the largest circle that can be inscribed in the octagon.

R1.4.8 Detailed recommendations for design and construction of slabs-on-ground and floors that do not transmit vertical loads or lateral forces from other portions of the structure to the soil are given in ACI PRC-360. This guide presents information on the design of slabs-on-ground, primarily industrial floors and the slabs adjacent to them. The guide addresses the planning, design, and detailing of the slabs. Background information on the design theories is followed by discussion of the soil support system, loadings, and types of slabs. Design methods are given for structural plain concrete, reinforced concrete, shrinkage-compensating concrete, and post-tensioned concrete slabs.

R1.4.9 **ACI CODE-440.11** provides requirements and recommendations for the design and limited applicability of concrete members reinforced with Glass Fiber-Reinforced Polymer (GFRP) bar reinforcement. In structures containing both steel- and GFRP-reinforced concrete members, design of steel-reinforced members is governed by the Code; the design of GFRP-reinforced members is governed by ACI CODE-440.11. The design of “hybrid” members with mixed reinforcement types (steel and FRP) and members strengthened with FRP are outside the scope of ACI CODE-318 and CODE-440.11.

R1.4.10 Requirements and recommendations for the design and construction of tanks and reservoirs are given in **ACI CODE-350**, **ACI PRC-334.1**, and **ACI PRC-372**.

CODE

1.4.11 This Code does not apply to composite design slabs cast on stay-in-place composite steel deck. Concrete used in the construction of such slabs shall be governed by this Code, where applicable. Portions of such slabs designed as reinforced concrete are governed by this Code.

1.5—Interpretation

1.5.1 The principles of interpretation in this section shall apply to this Code as a whole unless otherwise stated.

1.5.2 This Code consists of chapters and appendixes, including text, headings, tables, figures, footnotes to tables and figures, and referenced standards.

1.5.3 The Commentary consists of a preface, introduction, commentary text, tables, figures, and cited publications. The Commentary is intended to provide contextual information, but is not part of this Code, does not provide binding requirements, and shall not be used to create a conflict with or ambiguity in this Code.

1.5.4 This Code shall be interpreted in a manner that avoids conflict between or among its provisions. Specific provisions shall govern over general provisions.

1.5.5 This Code shall be interpreted and applied in accordance with the plain meaning of the words and terms used. Specific definitions of words and terms in this Code shall be used where provided and applicable, regardless of whether other materials, standards, or resources outside of this Code provide a different definition.

1.5.6 The following words and terms in this Code shall be interpreted in accordance with (a) through (e):

- (a) The word “shall” is always mandatory.
- (b) Provisions of this Code are mandatory even if the word “shall” is not used.
- (c) Words used in the present tense shall include the future.
- (d) The word “and” indicates that all of the connected items, conditions, requirements, or events shall apply.
- (e) The word “or” indicates that the connected items, conditions, requirements, or events are alternatives, at least one of which shall be satisfied.

1.5.7 In any case in which one or more provisions of this Code are declared by a court or tribunal to be invalid, that ruling shall not affect the validity of the remaining provisions.

COMMENTARY

R1.4.11 In this type of construction, the steel deck serves as the positive moment reinforcement. The design and construction of concrete-steel deck slabs is described in “Standard for Steel Deck” (SD). The standard refers to the appropriate portions of the Code for the design and construction of the concrete portion of the composite assembly. SD also provides guidance for design of composite-concrete-steel deck slabs. The design of negative moment reinforcement to create continuity at supports is a common example where a portion of the slab is designed in conformance with the Code.

R1.5—Interpretation

R1.5.4 General provisions are broad statements, such as a building needs to be serviceable. Specific provisions, such as explicit reinforcement distribution requirements for crack control, govern over the general provisions.

R1.5.5 **ACI Concrete Terminology (CT)** is the primary resource to help determine the meaning of words or terms that are not defined in the Code. Dictionaries and other reference materials commonly used by licensed design professionals may be used as secondary resources.

R1.5.7 The Code addresses numerous requirements that can be implemented fully without modification if other requirements in the Code are determined to be invalid. This

CODE

sions of this Code, which are severable. The ruling of a court or tribunal shall be effective only in that court's jurisdiction, and shall not affect the content or interpretation of this Code in other jurisdictions.

1.5.8 If conflicts occur between provisions of this Code and those of standards and documents referenced in **Chapter 3**, this Code shall apply.

1.6—Building official

1.6.1 All references in this Code to the building official shall be understood to mean persons who administer and enforce this Code.

1.6.2 Actions and decisions by the building official affect only the specific jurisdiction and do not change this Code.

1.6.3 The building official shall have the right to order testing of any materials used in concrete construction to determine if materials are of the quality specified.

1.7—Licensed design professional

1.7.1 All references in this Code to the licensed design professional shall be understood to mean the engineer in either 1.7.1.1 or 1.7.1.2.

1.7.1.1 The licensed design professional responsible for, and in charge of, the structural design.

1.7.1.2 A specialty engineer to whom a specific portion of the structural design has been delegated subject to the conditions of (a) and (b).

(a) The authority of the specialty engineer shall be explicitly limited to the delegated design.

(b) The portion of the design delegated shall be well defined such that responsibilities and obligations of the parties are apparent.

1.8—Construction documents and design records

1.8.1 The licensed design professional shall provide in the construction documents the information required in **Chapter 26** and that required by the jurisdiction.

1.8.2 Calculations pertinent to design shall be filed with the construction documents if required by the building official. Analyses and designs using computer programs shall be permitted provided design assumptions, user input, and computer-generated output are submitted. Model analysis shall be permitted to supplement calculations.

COMMENTARY

severability requirement is intended to preserve the Code and allow it to be implemented to the extent possible following legal decisions affecting one or more of its provisions.

R1.6—Building official

R1.6.1 Building official is defined in **2.3**.

R1.6.2 Only the American Concrete Institute has the authority to alter or amend the Code.

R1.7—Licensed design professional

R1.7.1 Licensed design professional is defined in **2.3**.

R1.7.1.2 A portion of the design may be delegated to a specialty engineer during the design phase or to the contractor in the construction documents. Examples of design delegated to a specialty engineer or contractor include elements of precast concrete and post-tensioned concrete design.

R1.8—Construction documents and design records

R1.8.1 The provisions of Chapter 26 for preparing project drawings and specifications are, in general, consistent with those of most general building codes. Additional information may be required by the building official.

R1.8.2 Documented computer output is acceptable instead of manual calculations. The extent of input and output information required will vary according to the specific requirements of individual building officials. However, if a computer program has been used, only skeleton data should normally be required. This should consist of sufficient input and output data and other information to allow the building official to perform a detailed review and make comparisons using another program or manual calculations. Input

CODE

COMMENTARY

1.9—Testing and inspection

1.9.1 Concrete materials shall be tested in accordance with the requirements of [Chapter 26](#).

1.9.2 Concrete construction shall be inspected in accordance with the general building code and in accordance with Chapter 26.

1.9.3 Inspection records shall include information in accordance with Chapter 26.

1.10—Approval of special systems of design, construction, or alternative construction materials

1.10.1 Sponsors of any system of design, construction, or alternative construction materials within the scope of this Code, the adequacy of which has been shown by successful use or by analysis or test, but which does not conform to or is not covered by this Code, shall have the right to present the data on which their design is based to the building official or to a board of examiners appointed by the building official. This board shall be composed of competent engineers and shall have authority to investigate the data so submitted, require tests, and formulate rules governing design and construction of such systems to meet the intent of this Code. These rules, when approved by the building official and promulgated, shall be of the same force and effect as the provisions of this Code.

data should be identified as to member designation, applied loads, and span lengths. The related output data should include member designation and the shears, moments, and reactions at key points in the span. For column design, it is desirable to include moment magnification factors in the output where applicable.

The Code permits model analysis to be used to supplement structural analysis and design calculations. Documentation of the model analysis should be provided with the related calculations. Model analysis should be performed by an individual having experience in this technique.

R1.10—Approval of special systems of design, construction, or alternative construction materials

R1.10.1 New methods of design, new materials, and new uses of materials should undergo a period of development before being covered in a code. Hence, good systems or components might be excluded from use by implication if means were not available to obtain acceptance.

For special systems considered under this section, specific tests, load factors, deflection limits, and other pertinent requirements should be set by the board of examiners, and should be consistent with the intent of the Code.

The provisions of this section do not apply to model tests used to supplement calculations under 1.8.2 or to strength evaluation of existing structures under [Chapter 27](#).

CODE

COMMENTARY

A_h	= total area of shear reinforcement parallel to primary tension reinforcement in a corbel or bracket, in. ²
A_{hs}	= total cross-sectional area of hooked or headed bars being developed at a critical section, in. ²
A_j	= effective cross-sectional area within a joint in a plane parallel to plane of beam reinforcement generating shear in the joint, in. ²
A_ℓ	= total area of longitudinal reinforcement to resist torsion, in. ²
$A_{\ell,min}$	= minimum area of longitudinal reinforcement to resist torsion, in. ²
$A_{\ell d}$	= area of distributed reinforcement parallel to the longitudinal axis of the member within spacing $s_{\ell d}$, in. ²
A_n	= area of reinforcement in bracket or corbel resisting factored restraint force N_{uc} , in. ²
A_{nz}	= area of a face of a nodal zone or a section through a nodal zone, in. ²
A_{Na}	= projected influence area of a single adhesive anchor or group of adhesive anchors, for calculation of bond strength in tension, in. ²
A_{Nao}	= projected influence area of a single adhesive anchor, for calculation of bond strength in tension if not limited by edge distance or spacing, in. ²
A_{Nc}	= projected concrete failure area of a single anchor or group of anchors, for calculation of strength in tension, in. ²
A_{Nco}	= projected concrete failure area of a single anchor, for calculation of strength in tension if not limited by edge distance or spacing, in. ²
A_o	= gross area enclosed by torsional shear flow path, in. ²
A_{oh}	= area enclosed by centerline of the outermost closed transverse torsional reinforcement, in. ²
A_{pd}	= total area occupied by duct, sheathing, and prestressing reinforcement, in. ²
A_{ps}	= area of prestressed longitudinal tension reinforcement, in. ²
A_{pt}	= total area of prestressing reinforcement, in. ²
A_s	= area of nonprestressed longitudinal tension reinforcement, in. ²
A_s'	= area of compression reinforcement, in. ²
$A_{s,min}$	= minimum area of flexural reinforcement, in. ²
A_{sc}	= area of primary tension reinforcement in a corbel or bracket, in. ²
$A_{se,N}$	= effective cross-sectional area of anchor in tension, in. ²
$A_{se,V}$	= effective cross-sectional area of anchor in shear, in. ²
A_{shear}	= cross-sectional area used to calculate the shear stiffness, in. ²
A_{sh}	= total cross-sectional area of transverse reinforcement, including crossties, within spacing s and perpendicular to dimension b_c , in. ²
A_{si}	= total area of surface reinforcement at spacing s_i in the i -th layer crossing a strut, with reinforcement at an angle α_i to the axis of the strut, in. ²
A_{st}	= total area of nonprestressed longitudinal reinforcement

CODE

COMMENTARY

- ment including bars and excluding prestressing reinforcement, in.²
- A_t = area of one leg of a closed stirrup, hoop, or tie resisting torsion within spacing s , in.²
- A_{td} = area of distributed reinforcement transverse to the longitudinal axis of the member within spacing s_{td} , in.²
- A_{tp} = area of prestressing reinforcement in a tie, in.²
- A_{tr} = total cross-sectional area of all transverse reinforcement satisfying 25.4.2.6 within spacing s that crosses the potential plane of splitting through the reinforcement being developed, in.²
- A_{ts} = area of nonprestressed reinforcement in a tie, in.²
- A_{tt} = total cross-sectional area of parallel tie reinforcement to be considered as confining headed bars, in.²
- A_v = area of shear reinforcement within spacing s , in.²
- $A_{v,min}$ = minimum area of shear reinforcement within spacing s , in.²
- A_{vd} = total area of reinforcement in each group of diagonal bars in a diagonally reinforced coupling beam, in.²
- A_{vf} = area of shear-friction reinforcement, in.²
- $A_{vf,min}$ = minimum area of shear-friction reinforcement, in.²
- A_{vh} = area of shear reinforcement parallel to flexural tension reinforcement within spacing s_2 , in.²
- A_{Vc} = projected concrete failure area of a single anchor or group of anchors, for calculation of strength in shear, in.²
- A_{Vco} = projected concrete failure area of a single anchor, for calculation of strength in shear, if not limited by corner influences, spacing, or member thickness, in.²
- b = width of compression face of member, in.
- b_1 = dimension of the critical section b_o measured in the direction of the span for which moments are determined, in.
- b_2 = dimension of the critical section b_o measured in the direction perpendicular to b_1 , in.
- b_c = cross-sectional dimension of member core measured to the outside edges of the transverse reinforcement composing area A_{sh} , in.
- b_{cf} = effective overhanging compression flange width, in.
- b_f = effective flange width, in.
- b_o = perimeter of critical section for two-way shear in slabs and footings, in.
- b_s = width of strut, in.
- b_{sl} = width of shear lug, in.
- b_{slab} = effective slab width, in.
- b_t = width of that part of cross section containing the closed stirrups resisting torsion, in.
- b_v = width of cross section at contact surface being investigated for horizontal shear, in.
- b_w = web width or diameter of circular section, in.
- B = bias factor to adjust nominal strength to seismic target reliabilities (Appendix A)
- B_n = nominal bearing strength, lb
- B_u = factored bearing load, lb

CODE

COMMENTARY

- c = distance from extreme compression fiber to neutral axis, in.
- c_1 = dimension of rectangular or equivalent rectangular column, capital, or bracket measured in the direction of the span for which moments or joint shear forces are being determined, in.
- c_2 = dimension of rectangular or equivalent rectangular column, capital, or bracket measured in the direction perpendicular to c_1 , in.
- $c_{a,max}$ = maximum distance from center of an anchor shaft to the edge of concrete, in.
- $c_{a,min}$ = minimum distance from center of an anchor shaft to the edge of concrete, in.
- c_{a1} = distance from the center of an anchor shaft to the edge of concrete in one direction, in. If shear is applied to anchor, c_{a1} is taken in the direction of the applied shear. If tension is applied to the anchor, c_{a1} is the minimum edge distance. Where anchors subject to shear are located in narrow sections of limited thickness, see 17.7.2.1.2

c'_{a1} = limiting value of c_{a1} where anchors are located less than $1.5c_{a1}$ from three or more edges, in.; see Fig R17.7.2.1.2

- c_{a2} = distance from center of an anchor shaft to the edge of concrete in the direction perpendicular to c_{a1} , in.
- c_{ac} = critical edge distance required to develop the basic strength as controlled by concrete breakout or bond of a post-installed anchor in tension in uncracked concrete without supplementary reinforcement to control splitting, in.
- c_b = lesser of: (a) the distance from center of a bar or wire to nearest concrete surface, and (b) one-half the center-to-center spacing of bars or wires being developed, in.
- c_c = clear cover of reinforcement, in.
- c_{Na} = projected distance from center of an anchor shaft on one side of the anchor required to develop the full bond strength of a single adhesive anchor, in.
- c_{sl} = distance from the centerline of the row of anchors in tension nearest the shear lug to the centerline of the shear lug measured in the direction of shear, in.
- c_t = distance from the interior face of the column to the slab edge measured parallel to c_1 , but not exceeding c_1 , in.

- C_m = factor relating actual moment diagram to an equivalent uniform moment diagram
- d' = distance from extreme compression fiber to centroid of longitudinal compression reinforcement, in.
- d = distance from extreme compression fiber to centroid of longitudinal tension reinforcement, in.
- d'_a = value substituted for d_a if an oversized anchor is used, in.
- d_a = outside diameter of anchor or shaft diameter of headed stud, headed bolt, or hooked bolt, in.

C = compressive force acting on a nodal zone, lb

CODE

COMMENTARY

d_{agg} = nominal maximum size of coarse aggregate, in.
 d_b = nominal diameter of bar, wire, or prestressing strand, in.

d_p = distance from extreme compression fiber to centroid of prestressed reinforcement, in.
 d_{pile} = diameter of pile at footing base, in.
 D = effect of service dead load

D_s = effect of superimposed dead load
 D_u = ultimate deformation capacity; the largest deformation at which the hysteresis model is deemed valid given available laboratory data or other substantiating evidence (**Appendix A**)
 D_w = effect of self-weight dead load of the concrete structural system

d_{burst} = distance from the anchorage device to the centroid of the bursting force, T_{bursts} , in.

D_i = diagonal compression component of shear flow resistance in concrete, lb

e_{anc} = eccentricity of the anchorage device or group of devices with respect to the centroid of the cross section, in.

e_h = distance from the inner surface of the shaft of a J- or L-bolt to the outer tip of the J- or L-bolt, in.

e'_N = distance between resultant tension load on a group of anchors loaded in tension and the centroid of the group of anchors loaded in tension, in.; e'_N is always positive

e'_V = distance between resultant shear load on a group of anchors loaded in shear in the same direction, and the centroid of the group of anchors loaded in shear in the same direction, in.; e'_V is always positive

E = effect of horizontal and vertical earthquake-induced forces

E_c = modulus of elasticity of concrete, psi

E_{cb} = modulus of elasticity of beam concrete, psi

E_{ce} = expected modulus of elasticity of concrete, psi (**Appendix B**)

E_{ce} = expected modulus of elasticity of concrete is calculated using expected compressive strength of concrete. (**Appendix B**)

E_{cs} = modulus of elasticity of slab concrete, psi

E_h = effect of horizontal earthquake-induced forces

EI = flexural stiffness of member, in.²-lb

$(EI)_{eff}$ = effective flexural stiffness of member, in.²-lb

E_{mh} = load effect due to the horizontal seismic force including overstrength, Ω_o , as defined in **ASCE/SEI 7**

E_p = modulus of elasticity of prestressing reinforcement, psi

E_s = modulus of elasticity of reinforcement and structural steel, excluding prestressing reinforcement, psi

f'_c = specified compressive strength of concrete, psi

$\sqrt{f'_c}$ = square root of specified compressive strength of concrete, psi

f_{ce} = effective compressive strength of the concrete in a strut or a nodal zone, psi

f'_{ce} = expected compressive strength of concrete, psi (**Appendix A, B**)

CODE

COMMENTARY

$\sqrt{f'_{ce}}$ = square root of expected compressive strength of concrete, psi

f'_{ci} = specified compressive strength of concrete at transfer of prestress, psi

$\sqrt{f'_{ci}}$ = square root of specified compressive strength of concrete at transfer of prestress, psi

f_{ct} = measured average splitting tensile strength of lightweight concrete, psi

f_d = stress due to unfactored dead load, at extreme fiber of section where tensile stress is caused by externally applied loads, psi

f_{dc} = decompression stress; stress in the prestressed reinforcement if stress is zero in the concrete at the same level as the centroid of the prestressed reinforcement, psi

f_{pc} = compressive stress in concrete, after allowance for all prestress losses, at centroid of cross section resisting externally applied loads or at junction of web and flange where the centroid lies within the flange, psi. In a composite concrete member, f_{pc} is the resultant compressive stress at centroid of composite section, or at junction of web and flange where the centroid lies within the flange, due to both prestress and moments resisted by precast member acting alone

f_{pe} = compressive stress in concrete due only to effective prestress forces, after allowance for all prestress losses, at extreme fiber of section if tensile stress is caused by externally applied loads, psi

f_{ps} = stress in prestressed reinforcement at nominal flexural strength, psi

f_{pu} = specified tensile strength of prestressing reinforcement, psi

f_{py} = specified yield strength of prestressing reinforcement, psi

f_r = modulus of rupture of concrete, psi

f_s = tensile stress in reinforcement at service loads, excluding prestressed reinforcement, psi

f'_s = compressive stress in reinforcement under factored loads, excluding prestressed reinforcement, psi

f_{se} = effective stress in prestressed reinforcement, after allowance for all prestress losses, psi

f_t = extreme fiber stress in the precompressed tension zone calculated at service loads using gross section properties after allowance of all prestress losses, psi

f_u = specified tensile strength of nonprestressed reinforcement, psi

f_{ue} = expected tensile strength for nonprestressed reinforcement, psi (Appendix A, B)

f_{uta} = specified tensile strength of anchor steel, psi

f_y = specified yield strength for nonprestressed reinforcement, psi

f_{ya} = specified yield strength of anchor steel, psi

f_{si} = stress in the i -th layer of surface reinforcement, psi

CODE

COMMENTARY

- f_{ye} = expected yield strength for nonprestressed reinforcement, psi (**Appendix A, B**)
 f_{yt} = specified yield strength of transverse reinforcement, psi
 F = effect of service load due to fluids with well-defined pressures and maximum heights
 F_{nn} = nominal strength at face of a nodal zone, lb
 F_{ns} = nominal strength of a strut, lb
 F_{nt} = nominal strength of a tie, lb
 F_{un} = factored force on the face of a node, lb
 F_{us} = factored compressive force in a strut, lb
 F_{ut} = factored tensile force in a tie, lb
 h = overall thickness, height, or depth of member, in.
 h_a = thickness of member in which an anchor is located, measured parallel to anchor axis, in.

h_{anc} = dimension of anchorage device or single group of closely spaced devices in the direction of bursting being considered, in.

h'_{ef} = limiting value of h_{ef} where anchors are located less than $1.5h_{ef}$ from three or more edges, in.; refer to Fig. R17.6.2.1.2.

- h_{ef} = effective embedment depth of anchor or reinforcing bar, in.
 $h_{ef,sl}$ = effective embedment depth of shear lug, in.
 h_n = structural height from the base to the highest level of the seismic-force-resisting system of the structure, ft, where the base is the level at which the horizontal earthquake ground motions are considered to be imparted to the structure
 h_{sl} = embedment depth of shear lug, in.
 h_{sx} = story height for story x , in. (**Appendix A, B**)
 h_u = laterally unsupported height at extreme compression fiber of wall or wall pier, in., equivalent to ℓ_u for compression members
 h_w = height of entire wall from base to top, or clear height of wall segment or wall pier considered, in.
 h_{wcs} = height of entire structural wall above the critical section for flexural and axial loads, in.
 h_x = maximum center-to-center spacing of longitudinal bars laterally supported by corners of crossties or hoop legs around the perimeter of a column or wall boundary element, in.
 H = effect of service load due to lateral earth pressure, ground water pressure, or pressure of bulk materials, lb
 I = moment of inertia of section about centroidal axis, in.⁴
 I_b = moment of inertia of gross section of beam about centroidal axis, in.⁴
 I_{cr} = moment of inertia of cracked section transformed to concrete, in.⁴
 I_e = effective moment of inertia for calculation of deflection, in.⁴
 I_g = moment of inertia of gross concrete section about centroidal axis, neglecting reinforcement, in.⁴

CODE

COMMENTARY

- I_s = moment of inertia of gross section of slab about centroidal axis, in.⁴
 I_{se} = moment of inertia of reinforcement about centroidal axis of member cross section, in.⁴
 k = effective length factor for compression members
 k_c = coefficient for basic concrete breakout strength in tension
 k_{cp} = coefficient for pryout strength
 k_f = concrete strength factor
 k_n = confinement effectiveness factor

- K_{tr} = transverse reinforcement index, in.
 L = effect of service live load
 L_r = effect of service roof live load
 ℓ = span length of beam or one-way slab; clear projection of cantilever, in.
 ℓ_1 = length of span in direction that moments are being determined, measured center-to-center of supports, in.
 ℓ_2 = length of span in direction perpendicular to ℓ_1 , measured center-to-center of supports, in.
 ℓ_a = additional embedment length beyond centerline of support or point of inflection, in.

- ℓ_{be} = length of boundary element from compression face of member, in.
 ℓ_c = length of compression member, measured center-to-center of the joints, in.
 ℓ_d = development length in tension of deformed bar, deformed wire, plain and deformed welded wire reinforcement, or pretensioned strand, in.
 ℓ_{db} = debonded length of prestressed reinforcement at end of member, in.
 ℓ_{dc} = development length in compression of deformed bars and deformed wire, in.
 ℓ_{dh} = development length in tension of deformed bar or deformed wire with a standard hook, measured from outside end of hook, point of tangency, toward critical section, in.

- ℓ_{dt} = development length in tension of headed deformed bar, measured from the bearing face of the head toward the critical section, in.
 ℓ_e = load bearing length of anchor for shear, in.
 ℓ_{ext} = straight extension at the end of a standard hook, in.
 ℓ_n = length of clear span measured face-to-face of supports, in.
 ℓ_o = length, measured from joint face along axis of member, over which special transverse reinforcement must be provided, in.
 ℓ_p = plastic-hinge length for analysis purposes, in.

(Appendix A)

- K_{05} = coefficient associated with the 5 percent fractile
 K_t = torsional stiffness of member; moment per unit rotation

- ℓ_{anc} = length along which anchorage of a tie must occur, in.
 ℓ_b = width of bearing, in.

- ℓ_{dm} = required development length if bar is not entirely embedded in confined concrete, in.

CODE

COMMENTARY

- ℓ_{sc} = compression lap splice length, in.
 ℓ_{st} = tension lap splice length, in.
 ℓ_t = span of member under load test, taken as the shorter span for two-way slab systems, in. Span is the lesser of: (a) distance between centers of supports, and (b) clear distance between supports plus thickness h of member. Span for a cantilever shall be taken as twice the distance from face of support to cantilever end
 ℓ_{tr} = transfer length of prestressed reinforcement, in.
 ℓ_u = unsupported length of column or wall, in.
 ℓ_{vh} = distance between points of zero and maximum moment along which horizontal shear is transferred across the interface, in.
 ℓ_w = length of entire wall, or length of wall segment or wall pier considered in direction of shear force, in.

M = moment acting on anchor or anchor group, in.-lb

- M_1 = lesser factored end moment on a compression member, in.-lb
 M_{1ns} = factored end moment on a compression member at the end at which M_1 acts, due to loads that cause no appreciable sidesway, calculated using a first-order elastic frame analysis, in.-lb
 M_{1s} = factored end moment on compression member at the end at which M_1 acts, due to loads that cause appreciable sidesway, calculated using a first-order elastic frame analysis, in.-lb
 M_2 = greater factored end moment on a compression member. If transverse loading occurs between supports, M_2 is taken as the largest moment occurring in member. Value of M_2 is always positive, in.-lb
 $M_{2,min}$ = minimum value of M_2 , in.-lb
 M_{2ns} = factored end moment on compression member at the end at which M_2 acts, due to loads that cause no appreciable sidesway, calculated using a first-order elastic frame analysis, in.-lb
 M_{2s} = factored end moment on compression member at the end at which M_2 acts, due to loads that cause appreciable sidesway, calculated using a first-order elastic frame analysis, in.-lb
 M_a = maximum moment in member due to service loads at stage deflection is calculated, in.-lb
 M_c = factored moment amplified for the effects of member curvature used for design of compression member, in.-lb
 M_{cr} = cracking moment, in.-lb
 M_{cre} = moment causing flexural cracking at section due to externally applied loads, in.-lb
 M_{max} = maximum factored moment at section due to externally applied loads, in.-lb
 M_n = nominal flexural strength at section, in.-lb
 M_{nb} = nominal flexural strength of beam including slab where in tension, framing into joint, in.-lb

M_d = moment due to unfactored dead load, in.-lb

CODE

COMMENTARY

M_{nc} = nominal flexural strength of column framing into joint, calculated for factored axial force, consistent with the direction of lateral forces considered, resulting in lowest flexural strength, in.-lb

M_{ne} = flexural strength at section, determined using expected material strengths, in.-lb (**Appendix B**)

M_{pr} = probable flexural strength of members, with or without axial load, determined using the properties of the member at joint faces assuming a tensile stress in the longitudinal bars of at least $1.25f_y$ and a strength reduction factor ϕ of 1.0, in.-lb

M_{sa} = maximum moment in wall due to service loads, excluding $P\Delta$ effects, in.-lb

M_{sc} = factored slab moment that is resisted by the column at a joint, in.-lb

M_u = factored moment at section, in.-lb

M_{ua} = moment at midheight of wall due to factored lateral and eccentric vertical loads, not including $P\Delta$ effects, in.-lb

n = number of items, such as, bars, wires, monostrand anchorage devices, or anchors

n_ℓ = number of longitudinal bars around the perimeter of a column core with rectilinear hoops that are laterally supported by the corner of hoops or by seismic hooks. A bundle of bars is counted as a single bar

n_s = number of stories above the critical section

n_t = number of threads per inch

N = tension force acting on anchor or anchor group, lb

N_a = nominal bond strength in tension of a single adhesive anchor, lb

N_{ag} = nominal bond strength in tension of a group of adhesive anchors, lb

N_b = basic concrete breakout strength in tension of a single anchor in cracked concrete, lb

N_{ba} = basic bond strength in tension of a single adhesive anchor, lb

N_c = resultant tensile force acting on the portion of the concrete cross section that is subjected to tensile stresses due to the combined effects of service loads and effective prestress, lb

N_{cb} = nominal concrete breakout strength in tension of a single anchor, lb

N_{cbg} = nominal concrete breakout strength in tension of a group of anchors, lb

N_{cp} = basic concrete pryout strength of a single anchor, lb

N_{cpg} = basic concrete pryout strength of a group of anchors, lb

N_n = nominal strength in tension, lb

$N_{n,c}$ = nominal strength in tension of a single anchor governed by concrete breakout, pullout, or side-face blowout strength, lb

$N_{n,cg}$ = nominal strength in tension of an anchor group governed by concrete breakout, pullout, or side-face blowout strength, lb

N_i = axial tension component of shear flow resistance in longitudinal reinforcement, lb

$N_{n,c}$ = Nominal strength in tension of a single anchor is given in Table 17.5.2

$N_{n,cg}$ = Refer to the concrete failure modes given in Table 17.5.2

CODE

COMMENTARY

N_p	= pullout strength in tension of a single anchor in cracked concrete, lb
N_{pn}	= nominal pullout strength in tension of a single anchor, lb
N_{rg}	= nominal concrete breakout strength of reinforcing bar group, lb
N_{sa}	= nominal strength of a single anchor or individual anchor in a group of anchors in tension as governed by the steel strength, lb
N_{sb}	= side-face blowout strength of a single anchor, lb
N_{sbg}	= side-face blowout strength of a group of anchors, lb
N_{srg}	= contribution of parallel reinforcement to the nominal breakout strength of a reinforcing bar group, lb
N_u	= factored axial force normal to cross section occurring simultaneously with V_u or T_u ; to be taken as positive for compression and negative for tension, lb
N_{ua}	= factored tensile force applied to anchor or individual anchor in a group of anchors, lb
$N_{ua,g}$	= total factored tensile force applied to anchor group, lb
$N_{ua,i}$	= factored tensile force applied to most highly stressed anchor in a group of anchors, lb
$N_{ua,s}$	= factored sustained tension load, lb
N_{uc}	= factored restraint force applied to a bearing connection acting perpendicular to and simultaneously with V_u , to be taken as positive for tension, lb
$N_{uc,max}$	= maximum restraint force that can be transmitted through the load path of a bearing connection multiplied by the load factor used for live loads in combinations with other factored load effects
p_{cp}	= outside perimeter of concrete cross section, in.
p_h	= perimeter of centerline of outermost closed transverse torsional reinforcement, in.
P_a	= maximum allowable compressive strength of a deep foundation member, lb
P_c	= critical buckling load, lb
P_n	= nominal axial compressive strength of member, lb
P_{ne}	= axial compressive strength of member, determined using expected material strengths, lb (Appendix B)
$P_{n,bal}$	= nominal axial strength at the balanced strain condition, lb
$P_{n,max}$	= maximum nominal axial compressive strength of a member, lb
P_{nte}	= axial tensile strength of member, determined using expected material strengths, lb (Appendix B)
P_{nt}	= nominal axial tensile strength of member, lb
$P_{nt,max}$	= maximum nominal axial tensile strength of member, lb
P_o	= nominal axial strength at zero eccentricity, lb
P_{pu}	= factored prestressing force at anchorage device, lb
P_s	= unfactored axial load at the design, midheight section including effects of self-weight, lb

p_o = perimeter of area A_o , in.

CODE

COMMENTARY

P_u = factored axial force; to be taken as positive for compression and negative for tension, lb

$P\Delta$ = secondary moment due to lateral deflection, in.-lb

q_u = factored load per unit area, lb/ft²

Q = stability index for a story

r = radius of gyration of cross section, in.

r_b = bend radius at the inside of a bar, in.

R = cumulative load effect of service rain load

R_n = nominal strength (**Appendix B**)

R_{ne} = expected yield strength (**Appendix A**)

$R_{ne,w}$ = expected strength of reinforced concrete member using f_{ce}' and f_{ye} (**Appendix B**)

s = center-to-center spacing of items, such as longitudinal reinforcement, transverse reinforcement, tendons, or anchors, in.

s_2 = center-to-center spacing of longitudinal shear or torsional reinforcement, in.

s_i = center-to-center spacing of reinforcement in the i -th direction adjacent to the surface of the member, in.

s_{ld} = center-to-center spacing of longitudinal distributed reinforcement measured over the height of the member, in.

s_o = center-to-center spacing of transverse reinforcement within the length ℓ_o , in.

s_s = sample standard deviation, psi

s_{td} = center-to-center spacing of transverse distributed reinforcement measured in the longitudinal direction of the member, in.

s_w = clear distance between adjacent webs, in.

s_{wd} = center-to-center spacing of curtains or planes of longitudinal or transverse distributed reinforcement measured across the width or thickness of the member, in.

S = effect of service snow load

S_{DS} = 5% damped, spectral response acceleration parameter at short periods determined in accordance with the general building code

S_e = moment, shear, or axial force at connection corresponding to development of probable strength at intended yield locations, based on the governing mechanism of inelastic lateral deformation, considering both gravity and earthquake effects

S_m = elastic section modulus, in.³

S_n = nominal moment, shear, axial, torsion, or bearing strength

S_y = yield strength of connection, based on f_y of the connected part, for moment, shear, torsion, or axial force, psi

t = wall thickness of hollow section, in.

t_{cf} = effective compression flange thickness, in.

t_f = thickness of flange, in.

$P\delta$ = secondary moment due to individual member slenderness, in.-lb

q = shear flow, lb/in.

R = reaction, lb

CODE

t_{sl} = thickness of shear lug, in.
 T = cumulative effects of service temperature, creep, shrinkage, differential settlement, and shrinkage compensating concrete

T_{cr} = cracking torsional moment, in.-lb
 T_n = nominal torsional moment strength, in.-lb
 T_t = total test load, lb
 T_{th} = threshold torsional moment, in.-lb
 T_u = factored torsional moment at section, in.-lb
 U = strength of a member or cross section required to resist factored loads or related internal moments and forces in such combinations as stipulated in this Code
 v_c = stress corresponding to nominal two-way shear strength provided by concrete, psi
 v_n = equivalent concrete stress corresponding to nominal two-way shear strength of slab or footing, psi
 v_s = equivalent concrete stress corresponding to nominal two-way shear strength provided by reinforcement, psi
 v_u = maximum factored two-way shear stress calculated around the perimeter of a given critical section, psi
 v_{ug} = factored shear stress on the slab critical section for two-way action due to gravity loads without moment transfer, psi
 v_{uv} = factored shear stress on the slab critical section for two-way action, from the controlling load combination, without moment transfer, psi

V_b = basic concrete breakout strength in shear of a single anchor in cracked concrete, lb
 $V_{brg,sl}$ = nominal bearing strength of a shear lug in direction of shear, lb
 V_c = nominal shear strength provided by concrete, lb
 V_{cb} = nominal concrete breakout strength in shear of a single anchor, lb
 $V_{cb,sl}$ = nominal concrete breakout strength in shear of attachment with shear lugs, lb
 V_{cbg} = nominal concrete breakout strength in shear of a group of anchors, lb
 V_{ci} = nominal shear strength provided by concrete where diagonal cracking results from combined shear and moment, lb
 V_{cp} = nominal concrete pryout strength of a single anchor, lb

COMMENTARY

T = tension force acting on a nodal zone in a strut-and-tie model, lb (T is also used to define the cumulative effects of service temperature, creep, shrinkage, differential settlement, and shrinkage-compensating concrete in the load combinations defined in 5.3.6)

T_{burst} = tensile force in general zone acting ahead of the anchorage device caused by spreading of the anchorage force, lb

V = shear force acting on anchor or anchor group, lb
 $V_{||}$ = maximum shear force that can be applied parallel to the edge, lb
 $V_{\perp}$ = maximum shear force that can be applied perpendicular to the edge, lb

CODE

COMMENTARY

V_{cpg} = nominal concrete pryout strength of a group of anchors, lb

V_{cw} = nominal shear strength provided by concrete where diagonal cracking results from high principal tensile stress in web, lb

V_d = shear force at section due to unfactored dead load, lb

V_e = design shear force for load combinations including earthquake effects, lb

V_i = factored shear force at section due to externally applied loads occurring simultaneously with M_{max} , lb

V_n = nominal shear strength, lb

$V_{n,c}$ = nominal strength in shear of a single anchor governed by concrete breakout or pryout strength, lb

$V_{n,cg}$ = nominal strength in shear of an anchor group governed by concrete breakout or pryout strength, lb

$V_{n,x}$ = shear strength in the x-direction

$V_{n,y}$ = shear strength in the y-direction

V_{ne} = expected shear strength, lb (Appendix A)

V_{nh} = nominal horizontal shear strength, lb

V_p = vertical component of effective prestress force at section, lb

V_s = nominal shear strength provided by shear reinforcement, lb

V_{sa} = nominal shear strength of a single anchor or individual anchor in a group of anchors as governed by the steel strength, lb

V_u = factored shear force at section, lb

$V_{u,x}$ = factored shear force at section in the x-direction, lb

$V_{u,y}$ = factored shear force at section in the y-direction, lb

V_{ua} = factored shear force applied to a single anchor or group of anchors, lb

$V_{ua,g}$ = total factored shear force applied to anchor group, lb

$V_{ua,i}$ = factored shear force applied to most highly stressed anchor in a group of anchors, lb

V_{uEh} = factored shear force from load combinations including primary load E , considering only horizontal earthquake load effect E_h

V_{uh} = factored shear force along contact surface in composite concrete flexural member, lb

V_{us} = factored horizontal shear in a story, lb

w/cm = water-cementitious material ratio

w_c = density, unit weight, of normalweight concrete or equilibrium density of lightweight concrete, lb/ft³

w_t = effective height or width of concrete concentric with a tie, used to dimension the nodal zone in a strut-and-tie model, in.

w_u = factored load per unit length of beam or one-way slab, lb/in.

W = effect of wind load

$V_{n,c}$ = Refer to the concrete failure modes given in Table 17.5.2

$V_{n,cg}$ = Refer to the concrete failure modes given in Table 17.5.2

V_{uEh} = Refer to 5.3.1(e) and (g)

w_n = length of the side of a nodal zone, in.

w_s = width of a strut perpendicular to the axis of the strut, in.

$w_{t,max}$ = maximum effective height or width of concrete concentric with a tie, in.

CODE

COMMENTARY

W_{MRI} = wind effect with specified mean recurrence interval (MRI) ([Appendix B](#))

y_t = distance from centroidal axis of gross section, neglecting reinforcement, to tension face, in.

z = distance between the tension resultant of anchors loaded in tension and compression resultant acting on the concrete in contact with baseplate

α = angle defining the orientation of reinforcement

α_1 = minimum angle between unidirectional distributed reinforcement and a strut

α_c = coefficient defining the relative contribution of concrete strength to nominal wall shear strength

α_f = ratio of flexural stiffness of beam section to flexural stiffness of a width of slab bounded laterally by centerlines of adjacent panels, if any, on each side of the beam

α_{fm} = average value of α_f for all beams on edges of a panel

α_s = constant used to calculate V_c in slabs and footings

α_{sh} = shape factor to define the shear stress limit for walls

β = ratio of long to short dimensions: clear spans for two-way slabs, sides of column, concentrated load or reaction area; or sides of a footing

β_1 = factor relating depth of equivalent rectangular compressive stress block to depth of neutral axis

β_b = ratio of area of reinforcement cut off to total area of tension reinforcement at section

β_c = confinement modification factor for struts and nodes in a strut-and-tie model

β_{dns} = ratio used to account for reduction of stiffness of columns due to sustained axial loads

β_{ds} = the ratio of maximum factored sustained shear within a story to the maximum factored shear in that story associated with the same load combination

β_n = factor used to account for the effect of the anchorage of ties on the effective compressive strength of a nodal zone

β_s = factor used to account for the effect of cracking and confining reinforcement on the effective compressive strength of the concrete in a strut

γ_f = factor used to determine the fraction of M_{sc} transferred by slab flexure at slab-column connections

γ_p = factor used for type of prestressing reinforcement

γ_s = factor used to determine the portion of reinforcement located in center band of footing

γ_v = factor used to determine the fraction of M_{sc} transferred by eccentricity of shear at slab-column connections

δ = moment magnification factor used to reflect effects of member curvature between ends of a compression member

δ_c = wall displacement capacity at top of wall, in.

W_a = service-level wind load, lb

W_{MRI} = Wind effect with specified mean recurrence interval (MRI) depends on the risk category of the building and is provided in ASCE/SEI Prestandard for Performance-Based Wind Design. ([Appendix B](#))

$$\alpha_f = E_{cb}I_b/E_{cs}I_s$$

CODE

COMMENTARY

- δ_s = moment magnification factor used for frames not braced against sidesway, to reflect lateral drift resulting from lateral and gravity loads
- δ_u = design displacement, in.
- $\delta_{x,w}$ = maximum story drift ratio expected in story x , according to analyses for wind demands. Drift ratio is calculated as relative difference of lateral displacement between the top and bottom of a story, divided by the story height. (Appendix B)
- Δ_1 = maximum deflection, during first load test, measured 24 hours after application of the full test load, in.
- Δ_2 = maximum deflection, during second load test, measured 24 hours after application of the full test load. Deflection is measured relative to the position of the structure at the beginning of the second load test, in.
- Δ_{cr} = calculated out-of-plane deflection at midheight of wall corresponding to cracking moment M_{cr} , in.
- Δ_L = deformation limit (strain, rotation, displacement) (Appendix B)
- Δ_n = calculated out-of-plane deflection at midheight of wall corresponding to nominal flexural strength M_n , in.
- Δ_o = relative lateral deflection between the top and bottom of a story due to V_{us} , in.
- Δ_r = residual deflection measured 24 hours after removal of the test load. For the first load test, residual deflection is measured relative to the position of the structure at the beginning of the first load test. For the second load test, residual deflection is measured relative to the position of the structure at the beginning of the second load test, in.
- Δ_s = out-of-plane deflection due to service loads, in.
- Δ_u = calculated out-of-plane deflection at midheight of wall due to factored loads, in.
- Δ_x = design story drift of story x , in.
- Δf_p = increase in stress in prestressed reinforcement due to factored loads, psi
- Δf_{ps} = stress in prestressed reinforcement at service loads less decompression stress, psi
- ε_t = net tensile strain in extreme layer of longitudinal tension reinforcement at nominal strength, excluding strains due to effective prestress, creep, shrinkage, and temperature
- ε_{ty} = value of net tensile strain in the extreme layer of longitudinal tension reinforcement used to define a compression-controlled section

- Δf_{pt} = difference between the stress that can be developed in the prestressed reinforcement at the section under consideration and the stress required to resist factored bending moment at section, M_u/ϕ , psi
- ε_{cu} = maximum usable strain at extreme concrete compression fiber
- ε_s = strain in steel

CODE

COMMENTARY

ε_{ye}	= expected yield strain of reinforcement (Appendix B)
θ	= angle between axis of strut, compression diagonal, or compression field and the tension chord of the members
θ_y	= yield rotation, radians (Appendix A)
θ_{ye}	= expected yield rotation of member determined using expected material strengths, radians (Appendix B)
λ	= modification factor to reflect the reduced mechanical properties of lightweight concrete relative to normal-weight concrete of the same compressive strength
λ_a	= modification factor to reflect the reduced mechanical properties of lightweight concrete in certain concrete anchorage applications
λ_s	= factor used to modify shear strength based on the effects of member depth, commonly referred to as the size effect factor
λ_Δ	= multiplier used for additional deflection due to long-term effects
μ	= coefficient of friction
ξ	= time-dependent factor for sustained load
ρ'	= ratio of A_s' to bd
ρ	= ratio of A_s to bd
ρ_ℓ	= ratio of area of distributed longitudinal reinforcement to gross concrete area perpendicular to that reinforcement
ρ_p	= ratio of A_{ps} to bd_p
ρ_s	= ratio of volume of spiral reinforcement to total volume of core confined by the spiral, measured out-to-out of spirals
ρ_t	= ratio of area of distributed transverse reinforcement to gross concrete area perpendicular to that reinforcement
ρ_v	= ratio of tie reinforcement area to area of contact surface
ρ_w	= ratio of A_s to $b_w d$
τ_{cr}	= characteristic bond stress of adhesive anchor in cracked concrete, psi
τ_{uncr}	= characteristic bond stress of adhesive anchor in uncracked concrete, psi
ϕ	= strength reduction factor
ϕ_{cc}	= strength reduction factor for compression-controlled sections

ε_y = yield strain of steel

λ = in most cases, the reduction in mechanical properties is caused by the reduced ratio of tensile-to-compressive strength of lightweight concrete compared to normalweight concrete. There are instances in the Code where λ is used as a modifier to reduce expected performance of lightweight concrete where the reduction is not related directly to tensile strength.

σ = wall boundary extreme fiber concrete nominal compressive stress, psi

ζ = exponent symbol in tensile/shear force interaction equation

τ = shear stress, psi

ϕ_K = stiffness reduction factor

CODE

COMMENTARY

- ϕ_p = strength reduction factor for moment in pretensioned member at cross section closest to the end of the member where all strands are fully developed
- ϕ_s = seismic resistance factor for force-controlled actions (**Appendix A**)
- ψ_a = factor used to modify post-installed anchor strength based on assessment in accordance with **ACI CODE-355.2** or **ACI CODE-355.4**
- $\psi_{brg,sl}$ = shear lug bearing factor used to modify bearing strength of shear lugs based on the influence of axial load
- ψ_c = factor used to modify development length based on concrete strength
- ψ_{cc} = factor used to modify development length based on cover
- $\psi_{c,N}$ = breakout cracking factor used to modify tensile strength of anchors based on the influence of cracks in concrete
- $\psi_{c,P}$ = pullout cracking factor used to modify pullout strength of anchors based on the influence of cracks in concrete
- $\psi_{c,V}$ = breakout cracking factor used to modify shear strength of anchors based on the influence of cracks in concrete and presence or absence of supplementary reinforcement
- $\psi_{cm,N}$ = breakout compression field factor used to increase breakout strength for cases where a compression field inhibits concrete fracture development
- $\psi_{cp,N}$ = breakout splitting factor used to modify tensile strength of post-installed anchors intended for use in uncracked concrete without supplementary reinforcement to account for the splitting tensile stresses
- $\psi_{cp,Na}$ = bond splitting factor used to modify tensile strength of adhesive anchors intended for use in uncracked concrete without supplementary reinforcement to account for the splitting tensile stresses due to installation
- ψ_e = factor used to modify development length based on reinforcement coating
- $\psi_{ec,N}$ = breakout eccentricity factor used to modify tensile strength of anchors based on eccentricity of applied loads
- $\psi_{ec,Na}$ = breakout eccentricity factor used to modify tensile strength of adhesive anchors based on eccentricity of applied loads
- $\psi_{ec,V}$ = breakout eccentricity factor used to modify shear strength of anchors based on eccentricity of applied loads
- $\psi_{ed,N}$ = breakout edge effect factor used to modify tensile strength of anchors based on proximity to edges of concrete member
- $\psi_{ed,Na}$ = breakout edge effect factor used to modify tensile strength of adhesive anchors based on proximity to edges of concrete member
- $\psi_{ed,V}$ = breakout edge effect factor used to modify shear strength of anchors based on proximity to edges of concrete member

CODE

- ψ_g = factor used to modify development length based on grade of reinforcement
- $\psi_{h,V}$ = breakout thickness factor used to modify shear strength of anchors located in concrete members with $h_a < 1.5c_{a1}$
- ψ_o = factor used to modify development length of hooked and headed bars based on side cover and confinement
- ψ_p = factor used to modify development length for headed reinforcement based on parallel tie reinforcement
- ψ_r = factor used to modify development length based on confining reinforcement
- ψ_s = factor used to modify development length based on reinforcement size
- ψ_t = factor used to modify development length for casting location in tension
- ψ_w = factor used to modify development length for welded deformed wire reinforcement in tension
- ω_v = factor to account for dynamic shear amplification
- Ω_o = amplification factor to account for overstrength of the seismic-force-resisting system determined in accordance with the general building code
- Ω_v = overstrength factor to account for wall flexural overstrength at the wall critical section

2.3—Terminology

action, deformation-controlled—action allowed to exceed the expected yield deformation of the element being evaluated. (Appendix B)

action, force-controlled—action not allowed to exceed the design strength of the element being evaluated. (Appendix B)

adhesive—chemical components formulated from organic polymers, or a combination of organic polymers and inorganic materials that cure if blended together.

admixture—material other than water, aggregate, cementitious materials, and fiber reinforcement used as an ingredient, which is added to grout, mortar, or concrete, either before or during its mixing, to modify the freshly mixed, setting, or hardened properties of the mixture.

aggregate—granular material such as sand, gravel, crushed stone, iron blast-furnace slag, or recycled aggregates including crushed hydraulic cement concrete, used with a cementing medium to form concrete or mortar.

aggregate, lightweight—aggregate meeting the requirements of ASTM C330 and having a loose bulk density of 70 lb/ft³ or less, determined in accordance with ASTM C29.

COMMENTARY

R2.3—Terminology

action, deformation-controlled—Deformation-controlled actions are those under which elements exhibit acceptable degree of inelastic response and are deemed to have failed upon exceedance of a predefined deformation level or number of cycles. (Appendix B)

action, force-controlled—Force-controlled actions are those under which elements exhibit limited ductility and are deemed to have failed upon exceedance of design strength. (Appendix B)

aggregate—The use of recycled aggregate is addressed in the Code in 2019. The definition of recycled materials in ASTM C33 is very broad and is likely to include materials that would not be expected to meet the intent of the provisions of the Code for use in structural concrete. Use of recycled aggregates including crushed hydraulic-cement concrete in structural concrete requires additional precautions. See 26.4.1.2.1(c).

aggregate, lightweight—In some standards, the term “lightweight aggregate” is being replaced by the term “low-density aggregate.”

CODE

alternative cement—an inorganic cement that can be used as a complete replacement for portland cement or blended hydraulic cement, and that is not covered by applicable specifications for portland or blended hydraulic cements.

anchor—a steel element either cast into concrete or post-installed into a hardened concrete member and used to transmit applied loads to the concrete.

anchor, adhesive—a post-installed anchor, inserted into hardened concrete with an anchor hole diameter not greater than 1.5 times the anchor diameter, that transfers loads to the concrete by bond between the anchor and the adhesive, and bond between the adhesive and the concrete.

COMMENTARY

alternative cement—Alternative cements are described in the references listed in [R26.4.1.1.1\(b\)](#). Refer to 26.4.1.1.1(b) for precautions when using these materials in concrete covered by the Code.

anchor—Cast-in anchors include headed bolts, hooked bolts (J- or L-bolt), and headed studs. Post-installed anchors include expansion anchors, undercut anchors, and adhesive anchors; steel elements for adhesive anchors include threaded rods, deformed reinforcing bars, or internally threaded steel sleeves with external deformations. Anchor types are shown in Fig. R2.1.

anchor, adhesive—The design model included in [Chapter 17](#) for adhesive anchors is based on the behavior of anchors with hole diameters not exceeding 1.5 times the anchor diameter. Anchors with hole diameters exceeding 1.5 times the anchor diameter behave differently and are therefore excluded from the scope of Chapter 17 and [ACI CODE-355.4](#). To limit shrinkage and reduce displacement under load, most adhesive anchor systems require the annular gap to be as narrow as practical while still maintaining sufficient clearance for insertion of the anchor element in the adhesive filled hole and ensuring complete coverage of the bonded area over the embedded length. The annular gap for rein-




Fig. R2.1—Types of anchors.

CODE

anchor, cast-in—headed bolt, headed stud, or hooked bolt installed before placing concrete.

anchor, expansion—post-installed anchor, inserted into hardened concrete that transfers loads to or from the concrete by direct bearing or friction, or both.

anchor group—a number of similar anchors having approximately equal effective embedment depths with spacing s between adjacent anchors such that the projected areas overlap.

anchor, horizontal or upwardly inclined—Anchor installed in a hole drilled horizontally or in a hole drilled at any orientation above horizontal.

anchor, post-installed—anchor installed in hardened concrete; adhesive, expansion, screw, and undercut anchors are examples of post-installed anchors.

anchor pullout strength—the strength corresponding to the anchoring device or a major component of the device sliding out from the concrete without breaking out a substantial portion of the surrounding concrete.

anchor, screw—a post-installed threaded, mechanical anchor inserted into hardened concrete that transfers loads to the concrete by engagement of the hardened threads of the screw with the grooves that the threads cut into the sidewall of a predrilled hole during anchor installation.

anchor, undercut—post-installed anchor that develops its tensile strength from the mechanical interlock provided by undercutting of the concrete at the embedded end of the anchor. Undercutting is achieved with a special drill before installing the anchor or alternatively by the anchor itself during its installation.

anchorage device—in post-tensioned members, the hardware used to transfer force from prestressed reinforcement to the concrete.

COMMENTARY

forcing bars is generally greater than that for threaded rods. The required hole size is provided in the Manufacturer's Printed Installation Instructions (MPII).

anchor, expansion—Expansion anchors may be torque-controlled, where the expansion is achieved by a torque acting on the screw or bolt; or displacement controlled, where the expansion is achieved by impact forces acting on a sleeve or plug and the expansion is controlled by the length of travel of the sleeve or plug.

anchor group—For all potential failure modes (steel, concrete breakout, pullout, side-face blowout, and pryout), only those anchors susceptible to a particular failure mode should be considered when evaluating the strength associated with that failure mode.

anchor, horizontal or upwardly inclined—Figure R2.2 illustrates the potential hole orientations for horizontal or upwardly inclined anchors.




Fig. R2.2—Possible orientations of overhead, upwardly inclined, or horizontal anchors.

anchor, screw—The required predrilled hole size for a screw anchor is provided by the anchor manufacturer.

anchorage device—Most anchorage devices for post-tensioning are standard manufactured devices available from commercial sources. In some cases, non-standard details or assemblages are developed that combine various wedges and wedge plates for anchoring prestressed reinforcement. Both standard and non-standard anchorage devices may be classified as basic anchorage devices or special anchorage devices as defined in the Code and **AASHTO LRFDUS**.

CODE

anchorage device, basic monostrand—anchorage device used with any single strand or a single 5/8 in. or smaller diameter bar that is in accordance with 25.8.1, 25.8.2, and 25.9.3.1(a).

anchorage device, basic multistrand—anchorage device used with multiple strands, bars, or wires, or with single bars larger than 5/8 in. diameter that satisfies 25.8.1, 25.8.2 and 25.9.3.1(b).

anchorage device, special—anchorage device that satisfies tests required in 25.9.3.1(c).

anchorage zone—in post-tensioned members, portion of the member through which the concentrated prestressing force is transferred to concrete and distributed more uniformly across the section; its extent is equal to the largest dimension of the cross section; for anchorage devices located away from the end of a member, the anchorage zone includes the disturbed regions ahead of and behind the anchorage device.

attachment—structural assembly, external to the surface of the concrete, that transmits loads to or receives loads from the anchor.

B-region—portion of a member in which it is reasonable to assume that strains due to flexure vary linearly through section.

balanced strain condition—strain profile in which the extreme tension reinforcement is at the yield strain and the extreme concrete compression fiber is at a strain of 0.003.

base of structure—level at which horizontal earthquake ground motions are assumed to be imparted to a building. This level does not necessarily coincide with the ground level.

basis of design—formal document prepared by the licensed design professional expressing the performance objectives, acceptance criteria, analysis methods, and design methods to be used in the overall building design. (Appendix B)

beam—member subjected primarily to flexure and shear, with or without axial force or torsion; beams in a moment frame that forms part of the lateral-force-resisting system are predominantly horizontal members; a girder is a beam.

boundary element—portion along wall and diaphragm edge, including edges of openings, strengthened by longitudinal and transverse reinforcement.

breakout strength, concrete—strength corresponding to a volume of concrete surrounding the anchor or group of anchors separating from the member.

COMMENTARY

anchorage device, basic monostrand—Devices that are so proportioned that they can be checked analytically for compliance with bearing stress and stiffness requirements without having to undergo the acceptance-testing program required of special anchorage devices.

anchorage device, basic multistrand—Devices that are s_o proportioned that they can be checked analytically for compliance with bearing stress and stiffness requirements without having to undergo the acceptance-testing program required of special anchorage devices.

anchorage device, special—Special anchorage devices are any devices (monostrand or multistrand) that do not meet the relevant PTI or AASHTO LRFDUS bearing stress and, where applicable, stiffness requirements. Most commercially marketed multi-bearing surface anchorage devices are special anchorage devices. As provided in 25.9.3, such devices can be used only if they have been shown experimentally to be in compliance with the AASHTO requirements. This demonstration of compliance will ordinarily be furnished by the device manufacturer.

anchorage zone—In post-tensioned members, the portion of the member through which the concentrated prestressing force is transferred to the concrete and distributed more uniformly across the section. Its extent is equal to the largest dimension of the cross section. For anchorage devices located away from the end of a member, the anchorage zone includes the disturbed regions ahead of and behind the anchorage devices. Refer to Fig. R25.9.1.1b.

CODE

building official—term used to identify the Authority having jurisdiction or individual charged with administration and enforcement of provisions of the building code. Such terms as building commissioner or building inspector are variations of the title, and the term “building official” as used in this Code, is intended to include those variations, as well as others that are used in the same sense.

caisson—see drilled pier.

cementitious materials—materials that have cementing value if used in grout, mortar, or concrete, including portland cement, blended hydraulic cements, expansive cement, fly ash, raw or calcined natural pozzolan, slag cement, silica fume, and ground-glass pozzolan.

class of concrete—characterization of concrete of various qualities or usages, usually by compressive strength. (Appendix C)

collector—element that acts in axial tension or compression to transmit forces between a diaphragm and a vertical element of the lateral-force-resisting system.

column—member, usually vertical or predominantly vertical, used primarily to support axial compressive load, but that can also resist moment, shear, or torsion. Columns used as part of a lateral-force-resisting system resist combined axial load, moment, and shear. See also **moment frame**.

column capital—enlargement of the top of a concrete column located directly below the slab or drop panel that is cast monolithically with the column.

compliance requirements—construction-related code requirements directed to the contractor to be incorporated into construction documents by the licensed design professional, as applicable.

composite concrete flexural members—concrete flexural members of precast or cast-in-place concrete elements, constructed in separate placements but connected so that all elements respond to loads as a unit.

compression-controlled section—cross section in which the net tensile strain in the extreme tension reinforcement at nominal strength is less than or equal to the compression controlled strain limit.

compression-controlled strain limit—net tensile strain at balanced strain conditions.

concrete—mixture of portland cement or any other cementitious material, fine aggregate, coarse aggregate, and water, with or without admixtures.

concrete, all-lightweight—lightweight concrete containing only lightweight coarse and fine aggregates that conform to ASTM C330.

concrete-filled pipe piles—steel pipe with a closed end that is driven for its full length in contact with the surrounding soil, or a steel pipe with an open end that is driven for its full length and the soil cleaned out; for both installation procedures, the pipe is subsequently filled with reinforcement and concrete.

COMMENTARY

cementitious materials—Cementitious materials permitted for use in the Code are addressed in 26.4.1.1. Fly ash, raw or calcined natural pozzolan, slag cement, silica fume, and ground-glass pozzolan are considered supplementary cementitious materials.

compliance requirements—Although primarily directed to the contractor, the compliance requirements are also commonly used by others involved with the project.

CODE

concrete, lightweight—concrete containing lightweight aggregate and having an equilibrium density, as determined by [ASTM C567](#), between 90 and 135 lb/ft³.

concrete, nonprestressed—reinforced concrete with at least the minimum amount of nonprestressed reinforcement and no prestressed reinforcement; or for two-way slabs, with less than the minimum amount of prestressed reinforcement.

concrete, normalweight—concrete containing only coarse and fine aggregates that conform to [ASTM C33](#) and having a density greater than 135 lb/ft³.

concrete, plain—structural concrete with no reinforcement or with less than the minimum amount of reinforcement specified for reinforced concrete.

concrete, precast—structural concrete element cast elsewhere than its final position in the structure.

concrete, prestressed—reinforced concrete in which internal stresses have been introduced by prestressed reinforcement to reduce potential tensile stresses in concrete resulting from loads, and for two-way slabs, with at least the minimum amount of prestressed reinforcement.

concrete, reinforced—structural concrete reinforced with at least the minimum amounts of nonprestressed reinforcement, prestressed reinforcement, or both, as specified in this Code.

concrete, sand-lightweight—lightweight concrete containing only normalweight fine aggregate that conforms to [ASTM C33](#) and lightweight coarse aggregate that conforms to [ASTM C330](#).

concrete, steel fiber-reinforced—concrete containing a prescribed amount of dispersed, randomly oriented, discontinuous deformed steel fibers.

concrete strength, specified compressive, (f'_c)—compressive strength of concrete used in design and evaluated in accordance with provisions of this Code, psi; wherever the quantity f'_c is under a radical sign, the square root of numerical value only is intended, and the result has units of psi.

connection—region of a structure that joins two or more members; a connection also refers to a region that joins members of which one or more is precast.

connection, ductile—connection between one or more precast elements that experiences yielding as a result of the earthquake design displacements.

COMMENTARY

concrete, nonprestressed—Nonprestressed concrete usually contains no prestressed reinforcement. Prestressed two-way slabs require a minimum level of compressive stress in the concrete due to effective prestress in accordance with [8.6.2.1](#). Two-way slabs with less than this minimum level of precompression are required to be designed as nonprestressed concrete.

concrete, normalweight—Normalweight concrete typically has a density (unit weight) between 135 and 160 lb/ft³, and is normally taken as 145 to 150 lb/ft³.

concrete, plain—The presence of reinforcement, nonprestressed or prestressed, does not exclude the member from being classified as plain concrete, provided all requirements of [Chapter 14](#) are satisfied.

concrete, prestressed—Classes of prestressed flexural members are defined in [24.5.2.1](#). Prestressed two-way slabs require a minimum level of compressive stress in the concrete due to effective prestress in accordance with [8.6.2.1](#). Although the behavior of a prestressed member with unbonded tendons may vary from that of members with continuously bonded prestressed reinforcement, bonded and unbonded prestressed concrete are combined with nonprestressed concrete under the generic term “reinforced concrete.” Provisions common to both prestressed and nonprestressed concrete are integrated to avoid overlapping and conflicting provisions.

concrete, reinforced—Includes members satisfying the requirements for nonprestressed and prestressed concrete.

concrete, sand-lightweight—By Code terminology, sand-lightweight concrete is lightweight concrete with all of the fine aggregate replaced by sand. This definition may not be in agreement with usage by some material suppliers or contractors where the majority, but not all, of the lightweight fines are replaced by sand. For proper application of the Code provisions, the replacement limits should be stated, with interpolation if partial sand replacement is used.

CODE

connection, strong—connection between one or more precast elements that remains elastic while adjoining members experience yielding as a result of earthquake design displacements.

construction documents—written and graphic documents and specifications prepared or assembled for describing the location, design, materials, and physical characteristics of the elements of a project necessary for obtaining a building permit and construction of the project.

contraction joint—formed, sawed, or tooled groove in a concrete structure to create a weakened plane and regulate the location of cracking resulting from the dimensional change of different parts of the structure.

contractor—an entity responsible for construction of the Work as required by construction documents.

cover, specified concrete—distance between the outermost surface of embedded reinforcement and the closest outer surface of the concrete.

crosstie—a continuous reinforcing bar having a seismic hook at one end and a hook not less than 90 degrees with at least a $6d_b$ extension at the other end. The hooks shall engage peripheral longitudinal bars. The 90-degree hooks of two successive crossties engaging the same longitudinal bars shall be alternated end for end.

curtain—grid of reinforcement, usually in a vertical orientation.

cutoff point—point where reinforcement is terminated.

D-region—portion of a member within a distance h of a force discontinuity or a geometric discontinuity.

design displacement—total calculated lateral displacement expected for the design-basis earthquake.

design information—project-specific information to be incorporated into construction documents by the licensed design professional, as applicable.

design load combination—combination of factored loads and forces.

design story drift ratio—relative difference of design displacement between the top and bottom of a story, divided by the story height.

development length, nonprestressed reinforcement—length of embedded reinforcement required to develop the specified yield strength f_y or, where specifically required in this Code, $1.25f_y$ at a critical section.

COMMENTARY

design displacement—The design displacement is an index of the maximum lateral displacement expected in design for the design-basis earthquake. In documents such as **ASCE/SEI 7** and the **International Building Code**, the design displacement is calculated using static or dynamic linear elastic analysis under code-specified actions considering effects of cracked sections, effects of torsion, effects of vertical forces acting through lateral displacements, and modification factors to account for expected inelastic response. The design displacement generally is greater than the displacement calculated from design-level forces applied to a linear-elastic model of the building.

development length, nonprestressed reinforcement—development length provisions for nonprestressed reinforcement are generally calibrated to permit the achievement of the specified yield strength at the critical section. There are also sections of the code where it is required to develop the reinforcement for more than f_y , for example, **18.10.2.3(b)**

CODE

COMMENTARY

development length, prestressed reinforcement—length of embedded reinforcement required to develop f_{ps} of prestressing reinforcement at a critical section.

discontinuity—abrupt change in geometry or loading.

distance sleeve—sleeve that encases the center part of an undercut anchor, a torque-controlled expansion anchor, or a displacement-controlled expansion anchor, but does not expand.

distributed plasticity (fiber) model—component model consisting of discrete fibers explicitly representing nonlinear stress-strain or force-deformation responses. (Appendix A)

dowel—a deformed reinforcing bar intended to transmit tension, compression, or shear through a construction joint.

drilled piers or caissons—cast-in-place concrete foundation elements with or without an enlarged base (bell), constructed by excavating a hole in the ground and filling with reinforcement and concrete. Drilled piers or caissons are considered as uncased cast-in-place concrete drilled or augered piles, unless they have permanent steel casing, in which case they are considered as metal cased concrete piles.

drop panel—projection below the slab used to reduce the amount of negative reinforcement over a column or the minimum required slab thickness, and to increase the slab shear strength.

duct—conduit, plain or corrugated, to accommodate prestressing reinforcement for post-tensioning applications.

ductile coupled structural wall—see **structural wall, ductile coupled**.

durability—ability of a structure or member to resist deterioration that impairs performance or limits service life of the structure in the relevant environment considered in design.

edge distance—distance from the edge of the concrete surface to the center of the nearest anchor.

effective depth of section—distance measured from extreme compression fiber to centroid of longitudinal tension reinforcement.

effective embedment depth, anchor—overall depth through which the anchor transfers force to or from the surrounding concrete.

effective embedment depth, reinforcing bar—overall depth from the critical section through which the reinforcing

and 18.10.2.5(a). If it is desired to achieve the expected yield strength of reinforcement, the embedment length may need to be increased beyond the development length. For some cases, sectional strength may be controlled by concrete breakout even though the reinforcing bars are embedded a distance at least equal to the development length in tension.

distributed plasticity (fiber) model—Force-controlled and deformation-controlled actions are classified in A.7 for design using nonlinear analysis of concrete structures. (Appendix A)

effective embedment depth, anchor—Effective embedment depth will normally be the depth of the concrete failure surface in tension applications; for cast-in headed anchor bolts and headed studs, the effective embedment depth is measured from the bearing contact surface of the head. Effective embedment depths for a variety of anchor types are shown in Fig. R2.1. For post-installed mechanical anchors, the value h_{ef} is obtained from the ACI CODE-355.2 product evaluation report provided by the manufacturer.

effective embedment depth, reinforcing bar—Figure R2.3 illustrates effective embedment depth for the purpose

CODE

bar transfers force to or from the surrounding concrete. For straight bars, the effective embedment depth is measured from the end of the bar; for hooked reinforcement, the effective embedment is measured from the outside end of the hook, point of tangency; for headed reinforcement, effective embedment depth is measured from the bearing contact surface of the head.

effective prestress—stress remaining in prestressed reinforcement after losses in 20.3.2.6 have occurred.

effective stiffness—stiffness of a structural member accounting for cracking, creep, and other nonlinear effects.

embedment length—length of embedded reinforcement provided beyond a critical section.

COMMENTARY

of determining concrete breakout strength for various types of reinforcing bar anchorage




Fig. R2.3—Effective embedment depth for reinforcing bars for the purpose of determining concrete breakout strength.

CODE

COMMENTARY

embedments—items embedded in concrete, excluding reinforcement as defined in [Chapter 20](#) and anchors as defined in [Chapter 17](#). Reinforcement or anchors welded, bolted or otherwise connected to the embedded item to develop the strength of the assembly, are considered to be part of the embedment.

embedments, pipe—embedded pipes, conduits, and sleeves.

environmental product declaration (EPD)—declaration providing environmental data using predetermined parameters meeting the requirements of [ISO 21930](#). ([Appendix C](#))

equilibrium density—density of lightweight concrete determined in accordance with [ASTM C567](#).

equivalent static wind load (ESWL)—wind load statically applied to the building, representing the wind-tunnel-determined combination of the background and resonant wind components. ([Appendix B](#))

expansion sleeve—outer part of an expansion anchor that is forced outward by the center part, either by applied torque or impact, to bear against the sides of the predrilled hole. See also **anchor, expansion**.

expected strength, wind—strength of a member or cross section calculated in accordance with provisions and assumptions of this Code using expected material properties as contained in this Code. ([Appendix B](#))

extreme tension reinforcement—layer of prestressed or nonprestressed reinforcement that is the farthest from the extreme compression fiber.

finite element analysis—a numerical modeling technique in which a structure is divided into a number of discrete elements for analysis.

five percent fractile—statistical term meaning 90% confidence that there is 95% probability of the actual strength exceeding the nominal strength.

foundation seismic ties—elements used to sufficiently interconnect foundations to act as a unit. Elements may consist of grade beams, slabs-on-ground, or beams within a slab-on-ground.

global warming potential (GWP)—index used to determine the energy absorption caused by the emissions of different gases associated with a product, normalized to an equivalent mass of carbon dioxide over a period of 100 years. ([Appendix C](#))

hazard event—potential cause of damage to a structure and the magnitude or intensity associated with that cause. ([Appendix C](#))

five percent fractile—The determination of the coefficient K_{05} associated with the 5% fractile, $\bar{x} - K_{05}s_s$, depends on the number of tests, n , used to calculate the sample mean, $\bar{x}$, and sample standard deviation, s_s . Values of K_{05} range, for example, from 1.645 for $n = \infty$, to 2.010 for $n = 40$, and 2.568 for $n = 10$. With this definition of the 5 percent fractile, the nominal strength in [Chapter 17](#) is the same as the characteristic strength in [ACI CODE-355.2](#) and [ACI CODE-355.4](#).

global warming potential (GWP)—This index was developed as a single parameter to estimate the global warming impact of different gaseous emissions. ([Appendix C](#))

hazard event—Selecting the demands for which a structure will be designed requires establishing the hazards to which the structure may be subjected and the intensities of those hazards for target risk levels. For example, a structure might be subjected to frequent earthquakes with small intensities and very infrequent earthquakes with large intensities. ([Appendix C](#))

CODE

headed bolt—cast-in steel anchor that develops its tensile strength from the mechanical interlock provided by either a head or nut at the embedded end of the anchor.

headed deformed bars—deformed bars with heads attached at one or both ends.

headed shear stud reinforcement—reinforcement consisting of individual headed studs or groups of studs, with anchorage provided by a head at each end, or by a head at one end and a common base rail consisting of a steel plate or shape at the other end.

headed stud—a steel anchor conforming to the requirements of **AWS D1.1** and affixed to a plate or similar steel attachment by the stud arc welding process before casting; also referred to as a **welded headed stud**.

hooked bolt—cast-in anchor anchored mainly by bearing of the 90-degree bend (L-bolt) or 180-degree bend (J-bolt) against the concrete, at its embedded end, and having a minimum e_h equal to $3d_a$.

hoop—continuous closed tie or continuously wound tie having seismic hooks at both ends.

inspection—observation, verification, and required documentation of the materials, installation, fabrication, erection, or placement of components and connections to determine compliance with construction documents and referenced standards.

inspection, continuous—the full-time observation, verification, and required documentation of construction being performed.

inspection, periodic—the part-time or intermittent observation, verification, and required documentation of construction being performed.

isolation joint—separation between adjoining parts of a concrete structure, usually a vertical plane at a designed location such as to interfere least with performance of the structure, yet such as to allow relative movement in three directions and avoid formation of cracks elsewhere in the concrete, and through which all or part of the bonded reinforcement is interrupted.

jacking force—in prestressed concrete, temporary force exerted by a device that introduces tension into prestressing reinforcement.

joint—portion of structure common to intersecting members

COMMENTARY

headed deformed bars—The bearing area of a headed deformed bar is, for the most part, perpendicular to the bar axis. In contrast, the bearing area of the head of headed stud reinforcement is a nonplanar spatial surface of revolution, as shown in Fig. R20.4.1. The two types of reinforcement differ in other ways. The shanks of headed studs are smooth, not deformed as with headed deformed bars. The minimum net bearing area of the head of a headed deformed bar is permitted to be as small as four times the bar area. In contrast, the minimum stud head area is not specified in terms of the bearing area, but by the total head area which must be at least 10 times the area of the shank.

hoop—Refer to **25.7.4**.

joint—The effective cross-sectional area of a joint of a special moment frame, A_j , for shear strength calculations is given in **15.5.2.2**.

CODE

joint, corner—joint where two non-colinear members transfer moment and terminate at the joint.

licensed design professional—an individual who is licensed to practice structural design as defined by the statutory requirements of the professional licensing laws of the state or jurisdiction in which the project is to be constructed, and who is in responsible charge for all or part of the structural design.

life cycle assessment (LCA)—compilation and evaluation of the inputs, outputs, and potential environmental impacts of a product throughout its life cycle. (Appendix C)

load—forces or other actions that result from the weight of all building materials, occupants, and their possessions, environmental effects, differential movement, and restrained dimensional changes; permanent loads are those loads in which variations over time are rare or of small magnitude; all other loads are variable loads.

load, dead—(a) the weights of the members, supported structure, and permanent attachments or accessories that are likely to be present on a structure in service; or (b) loads meeting specific criteria found in the general building code; without load factors.

load effects—forces and deformations produced in structural members by applied loads or restrained volume changes.

load, factored—load, multiplied by appropriate load factors.

load, live—(a) load that is not permanently applied to a structure, but is likely to occur during the service life of the structure (excluding environmental loads); or (b) loads meeting specific criteria found in the general building code; without load factors.

load path—sequence of members and connections designed to transfer the factored loads and forces in such combinations as are stipulated in this Code, from the point of application or origination through the structure to the final support location or the foundation.

load, roof live—a load on a roof produced: (a) during maintenance by workers, equipment, and materials, and (b) during the life of the structure by movable objects, such as planters or other similar small decorative appurtenances that are not occupancy related; or loads meeting specific criteria found in the general building code; without load factors.

load, self-weight dead—weight of the structural system, including the weight of any bonded concrete topping.

COMMENTARY

joint, corner—Roof level corner joints are sometimes referred to as knee joints.

licensed design professional—May also be referred to as “registered design professional” in other documents; a licensed design professional in responsible charge of the design is often referred to as the “engineer of record” (EOR).

load—A number of definitions for loads are given as the Code contains requirements that are to be met at various load levels. The terms “dead load” and “live load” refer to the unfactored, sometimes called “service” loads specified or defined by the general building code. Service loads (loads without load factors) are to be used where specified in the Code to proportion or investigate members for adequate serviceability. Loads used to proportion a member for adequate strength are defined as factored loads. Factored loads are service loads multiplied by the appropriate load factors for required strength except wind and earthquake which are already specified as strength loads in ASCE/SEI 7. The factored load terminology clarifies where the load factors are applied to a particular load, moment, or shear value as used in the Code provisions.

load effects—Stresses and strains are directly related to forces and deformations and are considered as load effects.

CODE

load, service—all loads, static or transitory, imposed on a structure or element thereof, during the operation of a facility, without load factors.

load, superimposed dead—dead loads other than the self-weight that are present or are considered in the design.

Manufacturer's Printed Installation Instructions (MPII)—published instructions for the correct installation of a post-installed anchor under all covered installation conditions as supplied in the product packaging.

mechanical splice—region along lengths of two reinforcing bars joined by a mechanical splicing device, including the device.

mechanical splicing device—system used to mechanically join two reinforcing bars for the purpose of transferring axial compression, axial tension, or both from one bar to the other.

metal cased concrete piles—thin-walled steel pipe, steel shell, or spiral-welded metal casing with a closed end that is driven for its full length in contact with the surrounding soil, left permanently in place, and subsequently filled with reinforcement and concrete.

modulus of elasticity—ratio of normal stress to corresponding strain for tensile or compressive stresses below proportional limit of material.

moment frame—frame in which beams, slabs, columns, and joints resist forces predominantly through flexure, shear, and axial force; beams or slabs are predominantly horizontal or nearly horizontal; columns are predominantly vertical or nearly vertical.

moment frame, intermediate—cast-in-place beam-column frame or two-way slab-column frame without beams complying with 18.4.

moment frame, ordinary—cast-in-place or precast concrete beam-column or slab-column frame complying with 18.3.

moment frame, special—cast-in-place beam-column frame complying with 18.2.3 through 18.2.8; and 18.6 through 18.8. A precast beam-column frame complying with 18.2.3 through 18.2.8 and 18.9.

net tensile strain—the tensile strain at nominal strength exclusive of strains due to effective prestress, creep, shrinkage, and temperature.

nodal zone—volume of concrete around a node that is assumed to transfer strut-and-tie forces through the node.

node—point in a strut-and-tie model where the axes of the struts, ties, and concentrated forces acting on the joint intersect.

node, curved-bar—the bend region of a continuous reinforcing bar (or bars) that defines a node in a strut-and-tie model.

COMMENTARY

mechanical splicing device—Mechanical splicing devices are most often commercially-marketed products. Features vary with the particular nature of the mechanical splicing device and may include but are not limited to coupling sleeves, filler materials of various types (such as flowable grouts), bolts, nuts, and threaded studs. Preparation of reinforcing bar ends by threading or other processes, application of friction welds, or other measures, may be required when manufacturing, fabricating, or installing the device.

CODE

one-way construction—members designed to resist out-of-plane loads through bending in a single direction. See also **two-way construction**.

panel, shotcrete mockup—a shotcrete specimen that simulates the size and detailing of reinforcement in a proposed structural member for preconstruction evaluation of the nozzle operator's ability to encase the reinforcement.

panel, shotcrete test—a shotcrete specimen prepared in accordance with **ASTM C1140** for evaluation of shotcrete.

pedestal—member with a ratio of height-to-least lateral dimension less than or equal to 3 used primarily to support axial compressive load; for a tapered member, the least lateral dimension is the average of the top and bottom dimensions of the smaller side.

performance-based wind design (PBWD)—alternative design procedure to the prescriptive provisions in the general building code and referenced standards, which considers direct evaluation of the wind demand on the structure, and evaluates the building performance as it relates to occupant comfort, operational performance, and continuous occupancy, limited interruption performance objectives. (Appendix B)

performance objective—specific desired outcome for an action, element, or system of a building during or following a wind event as chosen by the project stakeholders and licensed design professionals. (Appendix B)

performance objective, continuous occupancy, limited interruption—specific desired outcome in which damage to the main wind-force-resisting system does not significantly disrupt or impair the continued operation and functionality of the structure. (Appendix B)

performance objective, occupant comfort—specific desired outcome in which the accelerations from wind-induced sway motions remain within acceptable limits for occupant comfort and for equipment to maintain the functionality of the building. (Appendix B)

performance objective, operational—specific desired outcome in which the main wind-force-resisting system remains essentially elastic and the building systems remain operational during the designated risk-category-based event. (Appendix B)

plastic hinge region—length of frame element over which flexural yielding is intended to occur due to earthquake design displacements, extending not less than a distance h from the critical section where flexural yielding initiates.

post-installed reinforcing bar—deformed bar installed with adhesive or grout in a hole drilled in hardened concrete.

COMMENTARY

one-way construction—Joists, beams, girders, and some slabs and foundations are considered one-way construction.

panel, shotcrete mockup—Shotcrete mockup panels are used for preconstruction evaluation and are either sawed or cored, or both, to evaluate if the reinforcement has been adequately encased.

panel, shotcrete test—Shotcrete test panels are typically used to evaluate a shotcrete mixture, to qualify a nozzle operator, to verify surface finish, and to provide specimens for compressive or flexural strength testing.

performance objective, continuous occupancy, limited interruption—Continued operation and functionality of the structure is implicitly achieved when the main wind-force-resisting system is designed for a wind event corresponding to the designated building risk category to achieve the target reliability for structural stability that is consistent with the building code. (Appendix B)

performance objective, occupant comfort—Although the occupant comfort performance objective is part of performance-based wind design, it is outside of the scope of Appendix B. (Appendix B)

performance objective, operational—Members in reinforced concrete structures are considered cracked when concrete tensile stresses exceed the stress corresponding to the tensile strength. Even though the force-deformation relationship becomes nonlinear immediately after cracking, when performing the lateral analysis for the operational performance objective, it is assumed that the structure is essentially elastic, and its behavior is adequately represented using the secant stiffness for peak response for the risk category-based event. (Appendix B)

CODE

post-tensioning—method of prestressing in which prestressing reinforcement is tensioned after concrete has hardened.

precast concrete piles—driven piles that may be either prestressed concrete or conventionally reinforced concrete.

precompressed tension zone—portion of a prestressed member where flexural tension, calculated using gross section properties, would occur under service loads if the prestress force was not present.

pretensioning—method of prestressing in which prestressing reinforcement is tensioned before concrete is cast.

projected area—area on the free surface of the concrete member that is used to represent the greater base of the assumed rectilinear failure surface.

projected influence area—rectilinear area on the free surface of the concrete member that is used to calculate the bond strength of adhesive anchors.

pryout strength, concrete—strength corresponding to formation of a concrete spall behind short, stiff anchors displaced in the direction opposite to the applied shear force.

reinforcement—steel element or elements embedded in concrete and conforming to 20.2 through 20.4. Prestressed reinforcement in external tendons is also considered reinforcement.

reinforcement, anchor—reinforcement used to transfer the design load in tension from the anchors into the structural member

reinforcement, bonded prestressed—pretensioned reinforcement or prestressed reinforcement in a bonded tendon.

reinforcement, deformed—deformed bars, welded bar mats, deformed wire, and welded wire reinforcement conforming to 20.2.1.3, 20.2.1.5, or 20.2.1.7, excluding plain wire.

reinforcement, nonprestressed—bonded reinforcement that is not prestressed.

reinforcement, plain—bars or wires conforming to 20.2.1.4 or 20.2.1.7 that do not conform to definition of deformed reinforcement.

reinforcement, prestressed—prestressing reinforcement that has been tensioned to impart forces to concrete.

reinforcement, prestressing—high-strength reinforcement such as strand, wire, or bar conforming to 20.3.1.

reinforcement, supplementary—reinforcement that acts to restrain the potential concrete breakout but is not designed to transfer the design load from the anchors into the structural member.

COMMENTARY

reinforcement, anchor—Anchor reinforcement is designed and detailed specifically for the purpose of transferring anchor loads in tension from the anchors into the member. Hairpins are generally used for this purpose (refer to 17.5.2.1(a) and 17.5.2.1(b)); however, other configurations that can be shown to effectively transfer the anchor load are acceptable.

reinforcement, deformed—Deformed reinforcement is defined as that meeting the reinforcement specifications in the Code. No other reinforcement qualifies. This definition permits accurate statement of development lengths. Bars or wire not meeting the deformation requirements or welded wire reinforcement not meeting the spacing requirements are “plain reinforcement,” for code purposes, and may be used only for spirals.

reinforcement, supplementary—Supplementary reinforcement has a configuration and placement similar to anchor reinforcement but is not specifically designed to transfer loads from the anchors into the member. Stirrups, as used for shear reinforcement, may fall into this category.

CODE


reinforcement, welded deformed steel bar mat—mat conforming to 20.2.1.5 consisting of two layers of deformed bars at right angles to each other welded at the intersections.

reinforcement, welded wire—plain or deformed wire fabricated into sheets or rolls conforming to 20.2.1.7.

reinforcing bar group—parallel reinforcing bars connecting two members, or a member and a joint, and developed in an anchorage region defined by $A_{c,eff}$.

COMMENTARY

reinforcing bar group—Some examples are shown in Fig. R2.4.



Note: Wall reinforcement not shown for clarity.

Fig. R2.4—Breakout failure of bar groups.

CODE

resilient design—design process that anticipates, addresses, and mitigates risks associated with known natural or human-caused hazards by balancing construction cost, material consumption, recovery of functionality, and potential financial loss should a particular hazard event occur. (Appendix C)

Seismic Design Category—classification assigned to a structure based on its occupancy category and the severity of the design earthquake ground motion at the site, as defined by the general building code. Also denoted by the abbreviation SDC.

seismic-force-resisting system—portion of the structure designed to resist earthquake effects required by the general building code using the applicable provisions and load combinations.

seismic hook—hook on a stirrup, hoop, or crosstie having a bend not less than 135 degrees, except that circular hoops shall have a bend not less than 90 degrees; hooks shall have an extension of at least $6d_b$, but not less than 3 in. The hooks shall engage the longitudinal reinforcement and the extension shall project into the interior of the stirrup or hoop.

shear cap—projection below the slab used to increase the slab shear strength.

shear lug—a steel element welded to an attachment base plate to transfer shear to concrete by bearing.

sheathing—material encasing prestressing reinforcement to prevent bonding of the prestressing reinforcement with the surrounding concrete, to provide corrosion protection, and to contain the corrosion-inhibiting coating.

shotcrete—concrete placed pneumatically by high velocity projection from a nozzle onto a surface.

shotcrete, dry-mix—shotcrete in which most of the mixing water is added to the concrete ingredients at the nozzle.

shotcrete, wet-mix—shotcrete in which the concrete ingredients, including water, are mixed before introduction into the delivery hose.

COMMENTARY

resilient design—The design of resilient concrete structural systems includes:

- (a) Assessing the importance of the structure with respect to its functional, social, and economic roles in the community
- (b) Evaluating the hazards to which the structure may be exposed (such as flood or earthquake) and the estimated magnitudes associated with target risk levels in the present and in the future
- (c) Assessing the vulnerability and sensitivity of the structure to damage
- (d) Assessing the consequences of damage to the structure caused by the hazard event(s)
- (e) Evaluating the interdependent effects of the structure on other physical and social systems

In the context of the community of which individual structures are a part, resilience may include the community's ability to absorb disturbances while retaining the same basic structure and functionality, the capacity for self-organization, and the capacity to adapt to stress and change. The hazard design criteria and required recovery time following a hazard event should be based on the use, importance, and occupancy of the structure. (Appendix C)

sheathing—Typically, sheathing is a continuous, seamless, high-density polyethylene material extruded directly on the coated prestressing reinforcement.

shotcrete—Terms such as gunite and sprayed concrete are sometimes used to refer to shotcrete.

CODE

side-face blowout strength, concrete—strength of anchors with deep embedment and thin side-face cover such that spalling occurs on the side face around the embedded head without breakout occurring at the top concrete surface.

slab beam strip—in two-way prestressed slabs, the width of the floor system, including both the slab and beam if applicable, bounded laterally by adjacent panel centerlines for an interior slab-beam strip, or by adjacent panel centerline and slab edge for an exterior slab-beam strip.

spacing—center-to-center distance between adjacent items, such as longitudinal reinforcement, transverse reinforcement, prestressing reinforcement, or anchors.

spacing, clear—least dimension between the outermost surfaces of adjacent items.

span length—distance between supports.

special seismic systems—structural systems that use special moment frames, special structural walls, or both.

specialty engineer—a licensed design professional to whom a specific portion of the design has been delegated.

specialty insert—predesigned and prefabricated cast-in anchors specifically designed for attachment of bolted or slotted connections.

spiral reinforcement—continuously wound reinforcement in the form of a cylindrical helix.

steel element, brittle—element with a tensile test elongation of less than 14%, or reduction in area of less than 30% at failure.

steel element, ductile—element with a tensile test elongation of at least 14 percent and reduction in area of at least 30 percent; steel element meeting the requirements of **ASTM A307** shall be considered ductile; except as modified by for earthquake effects, deformed reinforcing bars meeting the requirements of **ASTM A615**, **A706**, or **A955** shall be considered as ductile steel elements.

stirrup—reinforcement used to resist shear and torsion in a member; deformed bar, deformed wire, or welded wire reinforcement, typically in the form of a single leg or bent into L, U, or rectangular shapes, oriented perpendicular to, or at an angle to, longitudinal reinforcement, and anchored near the extreme compression and tension surfaces of the section by bends, heads, or cross wires. See also **tie**.

structural wall panel zone—portion of a structural wall common to intersecting wall segments where forces from adjacent wall segments are resolved. (**Appendix A**)

strength, design—nominal strength multiplied by a strength reduction factor ϕ .

strength, nominal—strength of a member or cross section calculated in accordance with provisions and assumptions of the strength design method of this Code before application of any strength reduction factors.

COMMENTARY

specialty insert—Specialty inserts are devices often used for handling, transportation, erection, and anchoring elements; specialty inserts are not within the scope of the Code.

steel element, brittle—The 14% elongation should be measured over the gauge length specified in the appropriate ASTM standard for the steel.

steel element, ductile—The 14 percent elongation should be measured over the gauge length specified in the appropriate ASTM standard for steel. Due to concerns over fracture in cut threads, it should be verified that threaded deformed reinforcing bars satisfy the strength requirements of **25.5.7.1**.

stirrup—The term “stirrup” is usually applied to transverse reinforcement in beams or slabs and the term “ties” or “hoops” to transverse reinforcement in compression members.

strength, nominal—Nominal or specified values of material strengths and dimensions are used in the calculation of nominal strength. The subscript n is used to denote the nominal strengths; for example, nominal axial load strength P_n , nominal moment strength M_n , and nominal shear strength V_n . For additional discussion on the concepts and nomenclature for strength design, refer to the Commentary of **Chapter 22**.

CODE

strength, required—strength of a member or cross section required to resist factored loads or related internal moments and forces in such combinations as stipulated in this Code.

stretch length—length of anchor, extending beyond concrete in which it is anchored, subject to full tensile load applied to anchor, and for which cross-sectional area is minimum and constant.

structural concrete—concrete used for structural purposes, including plain and reinforced concrete.

structural diaphragm—member, such as a floor or roof slab, that transmits forces acting in the plane of the member to vertical elements of the lateral-force-resisting system. A structural diaphragm may include chords and collectors as part of the diaphragm.

structural integrity—ability of a structure through strength, redundancy, ductility, and detailing of reinforcement to redistribute stresses and maintain overall stability if localized damage or significant overstress occurs.

structural system—interconnected members designed to meet performance requirements.

structural truss—assemblage of reinforced concrete members subjected primarily to axial forces.

structural wall—wall proportioned to resist combinations of moments, shears, and axial forces in the plane of the wall; a shear wall is a structural wall.

structural wall, ductile coupled—a seismic-force-resisting-system complying with 18.10.9.

structural wall, intermediate precast—a wall complying with 18.5.

structural wall, ordinary plain concrete—a wall complying with Chapter 14.

structural wall, ordinary reinforced concrete—a wall complying with Chapter 11.

structural wall, special—a cast-in-place structural wall in accordance with 18.2.3 through 18.2.8 and 18.10; or a precast structural wall in accordance with 18.2.3 through 18.2.8 and 18.11.

strut—compression member in a strut-and-tie model representing the resultant of a parallel or a fan-shaped compression field.

strut, boundary—strut located along the boundary of a member or discontinuity region.

COMMENTARY

strength, required—The subscript u is used only to denote the required strengths; for example, required axial load strength P_u , required moment strength M_u , and required shear strength V_u , calculated from the applied factored loads and forces. The basic requirement for strength design may be expressed as follows: design strength $\geq$ required strength; for example, $\phi P_n \geq P_u$; $\phi M_n \geq M_u$; $\phi V_n \geq V_u$. For additional discussion on the concepts and nomenclature for strength design, refer to the Commentary of Chapter 22.

stretch length—Length of an anchor over which inelastic elongations are designed to occur under earthquake loadings. Examples illustrating stretch length are shown in Fig. R17.2.3.4.3.

structural wall, intermediate precast—Requirements of 18.5 are intended to result in an intermediate precast structural wall having minimum strength and toughness equivalent to that for an ordinary reinforced concrete structural wall of cast-in-place concrete. A precast concrete wall not satisfying the requirements of 18.5 is considered to have ductility and structural integrity less than that for an intermediate precast structural wall.

structural wall, special—Requirements of 18.2.3 through 18.2.8 and 18.11 are intended to result in a special precast structural wall having minimum strength and toughness equivalent to that for a special reinforced concrete structural wall of cast-in-place concrete.

strut, boundary—A boundary strut is intended to apply to the flexural compression zone of a beam, wall, or other

CODE

strut, interior—strut not located along the boundary of a member or discontinuity region.

strut-and-tie model—truss model of a member or of a D-region in such a member, made up of struts and ties connected at nodes and capable of transferring the factored loads to the supports or to adjacent B-regions.

sustainable design—design process that considers the balance among social, economic, and environmental principles from the Work's conception through the end of its service life ([Appendix C](#)).

tendon—in post-tensioned members, a tendon is a complete assembly consisting of anchorages, prestressing reinforcement, and sheathing with coating for unbonded applications or ducts filled with grout for bonded applications.

tendon finishing—the trimming of tendons, installing watertight encapsulation cap, and filling stressing pockets; for bonded post-tensioning systems, it also includes installing grout caps and closure of grout vents.

tendon, bonded—tendon in which prestressed reinforcement is continuously bonded to the concrete through grouting of ducts embedded within the concrete cross section.

tendon, external—a tendon external to the member concrete cross section in post-tensioned applications.

tendon, unbonded—tendon in which prestressed reinforcement is prevented from bonding to the concrete. The prestressing force is permanently transferred to the concrete at the tendon ends by the anchorages only.

tensile strength, reinforcement—specified minimum tensile strength of reinforcement.

tension-controlled section—a cross section in which the net tensile strain in the extreme tension steel at nominal strength is greater than or equal to $\epsilon_{ty} + 0.003$.

tie—(a) reinforcing bar or wire enclosing longitudinal reinforcement; a continuously wound transverse bar or wire in the form of a circle, rectangle, or other polygonal shape without reentrant corners enclosing longitudinal reinforcement; see also **stirrup, hoop**; (b) tension element in a strut-and-tie model.

COMMENTARY

member. Boundary struts are not subject to transverse tension and are therefore stronger than interior struts (Fig. R23.2.1).

strut, interior—Interior struts are subject to tension, acting perpendicular to the strut in the plane of the model, from shear (Fig. R23.2.1).

sustainable design—The design of sustainable concrete structural systems seeks to achieve balance between the production of concrete elements and the required performance characteristics in all phases of the structural system's life cycle. This approach includes measures to reduce the consumption of resources, including but not limited to water, aggregates, cementitious materials, reinforcing steel, and fuels; considers economic value and societal and cultural impacts; and minimizes impacts on the environment. When considering sustainable design, the Code places emphasis on the environmental impacts. Users should also consider social and economic principles of sustainable design that are not directly addressed by the Code. The principles of resilience and resilient design should be considered in sustainable design ([Appendix C](#)).

tendon, external—In new or existing post-tensioned applications, a tendon totally or partially external to the member concrete cross section, or inside a box section, and attached at the anchor device and deviation points.

CODE

transfer—act of transferring stress in prestressing reinforcement from jacks or pretensioning bed to concrete member.

transfer length—length of embedded pretensioned reinforcement required to transfer the effective prestress to the concrete.

two-way construction—members designed to resist out-of-plane loads through bending in two directions; some slabs and foundations are considered two-way construction. See also **one-way construction**.

uncased cast-in-place concrete drilled or augered piles—piles with or without an enlarged base (bell) that are constructed by either drilling a hole in the ground, or by installing a temporary casing in the ground and cleaning out the soil, and subsequently filling the hole with reinforcement and concrete.

wall—a vertical element designed to resist axial load, lateral load, or both, with a horizontal length-to-thickness ratio greater than 3, used to enclose or separate spaces.

wall pier—a vertical wall segment within a structural wall, bounded horizontally by two openings or by an opening and an edge, with ratio of horizontal length to wall thickness (ℓ_w/b_w) less than or equal to 6.0, and ratio of clear height to horizontal length (h_w/ℓ_w) greater than or equal to 2.0.

wall segment—portion of wall bounded by vertical or horizontal openings or edges.

wall segment, horizontal—segment of a structural wall, bounded vertically by two openings or by an opening and an edge.

wall segment, vertical—segment of a structural wall, bounded horizontally by two openings or by an opening and an edge; wall piers are vertical wall segments.

water-cementitious materials ratio—ratio of mass of water, excluding that absorbed by the aggregate, to the mass of cementitious materials in a mixture, stated as a decimal.

Whole Building Life Cycle Assessment (WBLCA)—life cycle assessment (LCA) of the complete building ([Appendix C](#)).

Work—the entire construction or separately identifiable parts thereof that are required to be furnished under the construction documents.

yield strength, reinforcement—specified minimum yield strength of reinforcement.

COMMENTARY

wall pier—Wall piers are vertical wall segments with dimensions and reinforcement intended to result in shear demand being limited by flexural yielding of the vertical reinforcement in the pier.

wall segment, horizontal—A horizontal wall segment is shown in Fig. R18.10.4.5.

Work—Work is capitalized throughout the Code when used in accordance with this definition.

yield strength, reinforcement—specified yield strength differs from actual yield strength, which is the measured yield strength of the reinforcement

Notes



CHAPTER 3—REFERENCED STANDARDS

CODE	COMMENTARY
------	------------

3.1—Scope

3.1.1 Standards, or specific sections thereof, cited in this Code, including Annex, Appendixes, or Supplements where prescribed, are referenced without exception in this Code, unless specifically noted. Cited standards are listed in the following with their serial designations, including year of adoption or revision.

3.2—Referenced standards

3.2.1 *American Association of State Highway and Transportation Officials (AASHTO)*

LRFDUS-9—LRFD Bridge Design Specifications, 9th Edition, 2020, Articles 5.8.4.4.2, 5.8.4.4.3, and 5.8.4.5

LRFDCONS-4—LRFD Bridge Construction Specifications, Fourth Edition, 2017, Article 10.3.2.3

3.2.2 *American Concrete Institute (ACI)*

ACI SPEC-301-20—Specifications for Concrete Construction, Article 4.2.3

ACI CODE 318-19—Building Code Requirements for Structural Concrete

ACI CODE-318.2-25—Building Code Requirements for Concrete Thin Shells and Commentary

ACI/PCI CODE-319-25—Structural Precast Concrete—Code Requirements and Commentary

ACI/PTI CODE-320-25—Structural Post-Tensioned Concrete—Code Requirements and Commentary

ACI CODE-332-20—Code Requirements for Residential Concrete and Commentary

ACI CODE-355.2-24—Post-Installed Mechanical Anchors in Concrete—Qualification Requirements and Commentary

ACI CODE-355.4-24—Post-Installed Adhesive Anchors in Concrete—Qualification Requirements and Commentary

ACI CODE-355.5-24—Post-Installed Reinforcing Bar Systems in Concrete—Qualification Requirements and Commentary

ACI CODE-369.1-22—Seismic Evaluation and Retrofit of Existing Concrete Buildings—Code and Commentary

ACI CODE-374.1-05(19)—Acceptance Criteria for Moment Frames Based on Structural Testing

ACI SPEC-423.7-14—Specification for Unbonded Single-Strand Tendon Materials

ACI CODE-437.2-22—Load Testing of Existing Concrete Structures—Code and Commentary

ACI CODE-550.4-18—Qualification of Precast Concrete Diaphragm Connections and Reinforcement at Joints for Earthquake Loading and Commentary

ACI CODE-550.5-18—Code Requirements for the Design of Precast Concrete Diaphragms for Earthquake Motions and Commentary

R3.1—Scope

R3.1.1 In the Code, references to standard specifications or other material are to a specific edition of the cited document. This is done by using the complete serial designation for the referenced standard including the title that indicates the subject and year of adoption. All standards referenced in the Code are listed in this chapter, with the title and complete serial designation. In other sections of the Code, referenced standards are abbreviated to include only the serial designation without a title or date. These abbreviated references correspond to specific standards listed in this chapter.

R3.2—Referenced standards

R3.2.1 *American Association of State Highway and Transportation Officials (AASHTO)*

Three articles of the AASHTO LRFD Specifications for Highway Bridge Design (**AASHTO LRFDUS**) and one article of the AASHTO LRFD Construction Specifications (**AASHTO LRFDCONS**) are cited in **Chapters 2** and **25** of the Code.

R3.2.2 *American Concrete Institute (ACI)*

Article 4.2.3 of **ACI SPEC-301** is referenced for the method of mixture proportioning cited in **26.4.3.1(b)**.

Prior to 2014, the provisions of **ACI CODE-318.2** were specified in **Chapter 19** of the ACI 318 Building Code.

ACI CODE-355.2 contains qualification requirements for testing and evaluating post-installed expansion, screw, and undercut anchors for use in both cracked and uncracked concrete.

ACI CODE-355.4 contains qualification requirements for testing and evaluating adhesive anchors for use in both cracked and uncracked concrete.

ACI SPEC-423.7 requires the use of encapsulated tendon systems for applications subject to the Code.

CODE

ACI CODE-550.6-19—Acceptance Criteria for Special Unbonded Post-Tensioned Precast Structural Walls Based on Validation Testing and Commentary

3.2.3 American Society of Civil Engineers (ASCE)

ASCE/SEI 7-22—Minimum Design Loads and Associated Criteria for Buildings and Other Structures including Supplements 1 and 2.

3.2.4 ASTM International

ASTM A184/A184M-24—Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement

ASTM A307-21—Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60000 PSI Tensile Strength

ASTM A370-24—Standard Test Methods and Definitions for Mechanical Testing of Steel Products

ASTM A416/A416M-24—Standard Specification for Low-Relaxation, Seven-Wire Steel Strand for Prestressed Concrete

ASTM A421/A421M-21—Standard Specification for Stress-Relieved Steel Wire for Prestressed Concrete

ASTM A615/A615M-24—Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement

ASTM A706/A706M-24—Standard Specification for Deformed and Plain Low-Alloy Steel Bars for Concrete Reinforcement including Supplementary Requirements S1

ASTM A722/A722M-18—Standard Specification for Uncoated High-Strength Steel Bars for Prestressed Concrete

ASTM A767/A767M-19—Standard Specification for Zinc-Coated (Galvanized) Steel Bars for Concrete Reinforcement

ASTM A775/A775M-22—Standard Specification for Epoxy-Coated Steel Reinforcing Bars

ASTM A820/A820M-22—Standard Specification for Steel Fibers for Fiber-Reinforced Concrete

ASTM A884/A884M-19^{e1}—Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement

ASTM A934/A934M-22—Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars

ASTM A955/A955M-20c—Standard Specification for Deformed and Plain Stainless-Steel Bars for Concrete Reinforcement

ASTM A970/A970M-24—Standard Specification for Headed Steel Bars for Concrete Reinforcement, including Annex A1 Requirements for Class HA Head Dimensions

ASTM A996/A996M-24—Standard Specification for Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement

ASTM A1022/A1022M-22a—Standard Specification for Deformed and Plain Stainless Steel Wire and Welded Wire for Concrete Reinforcement

ASTM A1034/A1034M-24—Standard Specification for Mechanical Splices for Steel Reinforcing Bars

ASTM A1035/A1035M-24—Standard Specification for Deformed and Plain, Low-Carbon, Chromium, Steel Bars for Concrete Reinforcement

COMMENTARY

R3.2.4 ASTM International

The ASTM standards listed are the latest editions at the time these code provisions were adopted. ASTM standards are revised frequently relative to the revision cycle for the Code. Current and historical editions of the referenced standards can be obtained from ASTM International. Use of an edition of a standard other than that referenced in the Code obligates the user to evaluate if any differences in the nonconforming edition are significant to use of the standard.

Many of the ASTM standards are combined standards as denoted by the dual designation, such as **ASTM A36/A36M**. For simplicity, these combined standards are referenced without the metric (M) designation within the text of the Code and Commentary. In this provision, however, the complete designation is given because that is the official designation for the standard.

CODE**COMMENTARY**

ASTM A1044/A1044M-22a—Standard Specification for Steel Stud Assemblies for Shear Reinforcement of Concrete

ASTM A1055/A1055M-22—Standard Specification for Zinc and Epoxy Dual-Coated Steel Reinforcing Bars

ASTM A1060/A1060M-22—Standard Specification for Zinc-Coated (Galvanized) Steel Welded Wire Reinforcement, Plain and Deformed, for Concrete

ASTM A1064/A1064M-24—Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete

ASTM C29/C29M-23—Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate

ASTM C31/C31M-24b—Standard Practice for Making and Curing Concrete Test Specimens in the Field

ASTM C33/C33M-24—Standard Specification for Concrete Aggregates

ASTM C39/C39M-24—Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens

ASTM C42/C42M-20—Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete

ASTM C94/C94M-24b—Standard Specification for Ready-Mixed Concrete

ASTM C138-24a—Standard Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete

ASTM C150/C150M-24—Standard Specification for Portland Cement

ASTM C172/C172M-17—Standard Practice for Sampling Freshly Mixed Concrete

ASTM C173/C173M-24—Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method

ASTM C192/C192M-19—Standard Practice for Making and Curing Concrete Test Specimens in the Laboratory

ASTM C231/C231M-24—Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method

ASTM C260/C260M-10a(2016)—Standard Specification for Air-Entraining Admixtures for Concrete

ASTM C330/C330M-23—Standard Specification for Lightweight Aggregates for Structural Concrete

ASTM C469/C469M-22—Standard Test Method for Static Modulus of Elasticity and Poisson’s Ratio of Concrete in Compression

ASTM C494/C494M-24—Standard Specification for Chemical Admixtures for Concrete

ASTM C567/C567M-19—Standard Test Method for Determining Density of Structural Lightweight Concrete

ASTM C595/C595M-24—Standard Specification for Blended Hydraulic Cements

ASTM C618-23^{e1}—Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete

ASTM C685/C685M-24—Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing

ASTM C845/C845M-18—Standard Specification for Expansive Hydraulic Cement

ASTM C989/C989M-24—Standard Specification for Slag Cement for Use in Concrete and Mortars

CODE**COMMENTARY**

ASTM C1012/C1012M-24—Standard Test Method for Length Change of Hydraulic-Cement Mortars Exposed to a Sulfate Solution

ASTM C1077-24—Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation

ASTM C1107/C1107M-20—Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)

ASTM C1116/C1116M-23—Standard Specification for Fiber-Reinforced Concrete

ASTM C1140/C1140M-11(2019)—Standard Practice for Preparing and Testing Specimens from Shotcrete Test Panels

ASTM C1157/C1157M-23—Standard Performance Specification for Hydraulic Cement

ASTM C1218/C1218M-20—Standard Test Method for Water-Soluble Chloride in Mortar and Concrete

ASTM C1240-20—Standard Specification for Silica Fume Used in Cementitious Mixtures

ASTM C1580-20—Standard Test Method for Water-Soluble Sulfate in Soil

ASTM C1582/C1582M-11(2017)^{e1}—Standard Specification for Admixtures to Inhibit Chloride-Induced Corrosion of Reinforcing Steel in Concrete

ASTM C1602/C1602M-22—Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete

ASTM C1604/C1604M-05(2019)—Standard Test Method for Obtaining and Testing Drilled Cores of Shotcrete

ASTM C1609/C1609M-24—Standard Test Method for Flexural Performance of Fiber-Reinforced Concrete (Using Beam with Third-Point Loading)

ASTM C1797-23a—Standard Specification for Ground Calcium Carbonate and Aggregate Mineral Fillers for use in Hydraulic Cement Concrete

ASTM C1866/C1866M-22—Standard Specification for Ground-Glass Pozzolan for Use in Concrete

ASTM D516-22—Standard Test Method for Sulfate Ion in Water

ASTM E2921-22—Standard Practice for Minimum Criteria for Comparing Whole Building Life Cycle Assessments for Use with Building Codes and Rating Systems

ASTM E329-18—Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection

3.2.5 American Welding Society (AWS)

AWS D1.1/D1.1M: 2020—Structural Welding Code – Steel
AWS D1.4/D1.4M: 2018—Structural Welding Code – Steel Reinforcing Bars

3.2.6 International Organization for Standardization (ISO)

ISO 14044:2006 Environmental management – Life cycle assessment – Requirements and guidelines

ISO 21930:2017 Sustainability in buildings and civil engineering works – Core rules for environmental product declarations of construction products and services

R3.2.6 International Organization for Standardization (ISO)

The ISO standards listed are referenced in **Appendix C**.

CHAPTER 4—STRUCTURAL SYSTEM REQUIREMENTS

CODE

4.1—Scope

4.1.1 This chapter shall apply to design of structural concrete in structures or portions of structures defined in [Chapter 1](#).

4.2—Materials

4.2.1 Design properties of concrete shall be selected to be in accordance with [Chapter 19](#).

4.2.1.1 Design properties of shotcrete shall conform to the requirements for concrete except as modified by provisions of the Code.

4.2.2 Design properties of reinforcement shall be selected to be in accordance with [Chapter 20](#).

4.3—Design loads

4.3.1 Loads and load combinations considered in design shall be in accordance with [Chapter 5](#).

4.4—Structural system and load paths

4.4.1 The structural system shall include (a) through (g), as applicable:

- (a) Floor construction and roof construction, including one-way and two-way slabs
- (b) Beams and joists
- (c) Columns
- (d) Walls
- (e) Diaphragms
- (f) Foundations

COMMENTARY

R4.1—Scope

R4.1.1 This chapter was added to the 2014 Code to introduce structural system requirements. Requirements more stringent than the Code provisions may be desirable for unusual construction or construction where enhanced performance is appropriate. The Code and Commentary must be supplemented with sound engineering knowledge, experience, and judgment.

R4.2—Materials

R4.2.1.1 Shotcrete is considered to behave and have properties similar to concrete unless otherwise noted. Sections where use of shotcrete is specifically addressed in the Code are shown in Table R4.2.1.1. Additional information on shotcrete can be found in [ACI PRC-506](#) and [ACI SPEC-506.2](#).

Table R4.2.1.1—Sections in Code with shotcrete provisions

Topic covered	Section
Freezing and thawing	19.3.3.3 through 19.3.3.6
Reinforcement	25.2.7 through 25.2.10, 25.5.1.6, and 25.5.1.7
Where shotcrete is required or permitted	26.3.1, 26.3.2
Materials	26.4.1.2, 26.4.1.4, and 26.4.1.6
Proportioning mixtures	26.4.3
Documentation of mixtures	26.4.4.1
Placement and consolidation	26.5.2.1
Curing	26.5.3
Joints	26.5.6
Evaluation and acceptance	26.12

R4.4—Structural system and load paths

R4.4.1 Structural concrete design has evolved from emphasizing the design of individual members to designing the structure as an entire system. A structural system consists of structural members, joints, and connections, each performing a specific role or function. A structural member may belong to one or more structural systems, serving different roles in each system and having to meet all the detailing requirements of the structural systems of which they are a part. Joints and connections are locations common to intersecting members or are items used to connect one

CODE

(g) Joints, connections, and anchors as required to transmit forces from one component to another

4.4.2 Design of structural members including joints and connections given in 4.4.1 shall be in accordance with **Chapters 7 through 18**.

4.4.3 It shall be permitted to design a structural system comprising structural members not in accordance with 4.4.1 and 4.4.2, provided the structural system is approved in accordance with **1.10.1**.

4.4.4 The structural system shall be designed to resist the factored loads in load combinations given in 4.3 without exceeding the appropriate member design strengths, considering one or more continuous load paths from the point of load application or origination to the final point of resistance.

4.4.5 Structural systems shall be designed to accommodate anticipated volume change and differential settlement.

4.4.6 Seismic-force-resisting system

4.4.6.1 Every structure shall be assigned to a Seismic Design Category in accordance with the general building code or as determined by the building official in areas without a legally adopted building code.

COMMENTARY

member to another, but the distinction between members, joints, and connections can depend on how the structure is idealized. Throughout this chapter, the term “members” often refers to “structural members, joints, and connections.”

Although the Code is written considering that a structural system comprises these members, many alternative arrangements are possible because not all structural member types are used in all building structural systems. The selection types of the members to use in a specific project and the role or roles these member types play is made by the licensed design professional complying with requirements of the Code.

R4.4.2 In the chapter for each type of structural member, requirements follow the same general sequence and scope, including general requirements, design limits, required strength, design strength, reinforcement limits, reinforcement detailing, and other requirements unique to the type of member.

R4.4.3 Some materials, structural members, or systems that may not be recognized in the prescriptive provisions of the Code may still be acceptable if they meet the intent of the Code. Section 1.10.1 outlines the procedures for obtaining approval of alternative materials and systems.

R4.4.4 The design should be based on members and connections that provide design strengths not less than the strengths required to transfer the loads along the load path. The licensed design professional may need to study one or more alternative paths to identify weak links along the sequence of elements that constitute each load path.

R4.4.5 The effects of column and wall creep and shrinkage, restraint of creep and shrinkage in long roof and floor systems, creep caused by prestress forces, volume changes caused by temperature variation, as well as potential damage to supporting members caused by these volume changes should be considered in design. Reinforcement, closure strips, or expansion joints are common ways of accommodating these effects. Minimum shrinkage and temperature reinforcement controls cracking to an acceptable level in many concrete structures of ordinary proportions and exposures.

Differential settlement or heave may be an important consideration in design. Geotechnical recommendations to allow for nominal values of differential settlement and heave are not normally included in design load combinations for ordinary building structures

R4.4.6 Seismic-force-resisting system

R4.4.6.1 Design requirements in the Code are based on the seismic design category to which the structure is assigned. In general, the seismic design category relates to seismic risk level, soil type, occupancy, and building use. Assignment of

CODE

4.4.6.2 Structural systems designated as part of the seismic-force-resisting system shall be restricted to those systems designated by the general building code or as determined by the building official in areas without a legally adopted building code.

4.4.6.3 Structural systems assigned to Seismic Design Category A shall satisfy the applicable requirements of this Code. Structures assigned to Seismic Design Category A are not required to be designed in accordance with Chapter 18.

4.4.6.4 Structural systems assigned to Seismic Design Category B, C, D, E, or F shall satisfy the requirements of Chapter 18 in addition to applicable requirements of other chapters of this Code.

4.4.6.5 Structural members assumed not to be part of the seismic-force-resisting system shall be permitted, subject to the requirements of 4.4.6.5.1 and 4.4.6.5.2.

4.4.6.5.1 In structures assigned to Seismic Design Category B, C, D, E, or F, the effects of those structural members on the response of the system shall be considered and accommodated in the structural design.

4.4.6.5.2 In structures assigned to Seismic Design Category B, C, D, E, or F, the consequences of damage to those structural members shall be considered.

4.4.6.5.3 In structures assigned to Seismic Design Category D, E, or F, structural members not considered part of the seismic-force-resisting system shall meet the applicable requirements in Chapter 18.

4.4.6.6 Effects of nonstructural members shall be accounted for as described in 18.2.2.1 and consequences of damage to nonstructural members shall be considered.

COMMENTARY

a building to a seismic design category is under the jurisdiction of a general building code rather than ACI CODE-318. In the absence of a general building code, **ASCE/SEI 7** provides the assignment of a building to a seismic design category.

R4.4.6.2 The general building code prescribes, through ASCE/SEI 7, the types of structural systems permitted as part of the seismic-force-resisting system based on considerations such as seismic design category and building height. The seismic design requirements for systems assigned to Seismic Design Categories B through F are prescribed in **Chapter 18**. Other systems can be used if approved by the building official.

R4.4.6.3 Structures assigned to Seismic Design Category A are subject to the lowest seismic hazard. Chapter 18 does not apply.

R4.4.6.4 Chapter 18 contains provisions that are applicable depending on the seismic design category and on the seismic-force-resisting system used. Not all structural member types have specific requirements in all seismic design categories. For example, Chapter 18 does not include requirements for structural walls in Seismic Design Categories B and C, but does include special provisions for Seismic Design Categories D, E, and F.

R4.4.6.5 In Seismic Design Categories D, E, and F, structural members not considered part of the seismic-force-resisting system are required to be designed to accommodate drifts and forces that occur as the building responds to an earthquake.

R4.4.6.6 Although the design of nonstructural elements for earthquake effects is not included in the scope of ACI CODE-318, the potential negative effects of nonstructural elements on the structural behavior need to be considered in Seismic Design Categories B, C, D, E, and F. Interaction of nonstructural elements with the structural system—

CODE

4.4.6.7 Design verification of earthquake-resistant concrete structures using nonlinear response history analysis shall be in accordance with **Appendix A**.

4.4.7 Diaphragms

4.4.7.1 Diaphragms, such as floor or roof slabs, shall be designed to resist simultaneously both out-of-plane gravity loads and in-plane lateral forces in load combinations given in 4.3.

4.4.7.2 Diaphragms and their connections to framing members shall be designed to transfer forces between the diaphragm and framing members.

4.4.7.3 Diaphragms and their connections shall be designed to provide lateral support to vertical, horizontal, and inclined elements.

4.4.7.4 Diaphragms shall be designed to resist applicable lateral loads from soil and hydrostatic pressure and other loads assigned to the diaphragm by structural analysis.

4.4.7.5 Collectors shall be provided where required to transmit forces between diaphragms and vertical elements.

4.4.7.6 Diaphragms that are part of the seismic-force-resisting system shall be designed for the applied forces in accordance with **Chapter 12** and Chapter 18 where applicable.

4.5—Structural analysis

4.5.1 Analytical procedures shall satisfy compatibility of deformations and equilibrium of forces.

4.5.2 The methods of analysis given in **Chapter 6** shall be permitted.

4.6—Strength

4.6.1 Design strength of a member and its joints and connections, in terms of moment, shear, torsional, axial, and bearing strength, shall be taken as the nominal strength S_n multiplied by the applicable strength reduction factor ϕ .

COMMENTARY

for example, the short-column effect—had led to failure of structural members and collapse of some structures during earthquakes in the past.

R4.4.7 Diaphragms

R4.4.7.1 Floor and roof slabs play a dual role by simultaneously supporting gravity loads and transmitting lateral forces in their own plane as a diaphragm. General requirements for diaphragms are provided in **Chapter 12**, and roles of the diaphragm are described in the Commentary to that chapter. Additional requirements for design of diaphragms in structures assigned to Seismic Design Categories D, E, and F, and in some cases Seismic Design Category C, are prescribed in **Chapter 18**.

R4.4.7.5 All structural systems must have a complete load path in accordance with 4.4.4. The load path includes collectors where required.

R4.6—Strength

R4.6.1 The basic requirement for strength design may be expressed as follows:

$$\text{design strength} \geq \text{required strength} \\ \phi S_n \geq U$$

CODE

COMMENTARY

In the strength design procedure, the level of safety is provided by a combination of factors applied to the loads and strength reduction factors ϕ applied to the nominal strengths.

The strength of a member or cross section, calculated using standard assumptions and strength equations, along with nominal values of material strengths and dimensions, is referred to as nominal strength and is generally designated S_n . Design strength or usable strength of a member or cross section is the nominal strength reduced by the applicable strength reduction factor ϕ . The purpose of the strength reduction factor is to account for the probability of under-strength due to variations of in-place material strengths and dimensions, the effect of simplifying assumptions in the design equations, the degree of ductility, potential failure mode of the member, the required reliability, and significance of failure and existence of alternative load paths for the member in the structure.

The Code, or the general building code, prescribes design load combinations, also known as factored load combinations, which define the way different types of loads are multiplied (factored) by individual load factors and then combined to obtain a factored load U . The individual load factors and additive combination reflect the variability in magnitude of the individual loads, the probability of simultaneous occurrence of various loads, and the assumptions and approximations made in the structural analysis when determining required design strengths.

A typical design approach, where linear analysis is applicable, is to analyze the structure for individual unfactored load cases, and then combine the individual unfactored load cases in a factored load combination to determine the design load effects. Where effects of loads are nonlinear—for example, in foundation uplift—the factored loads are applied simultaneously to determine the nonlinear, factored load effect. The load effects relevant for strength design include moments, shears, torsions, axial forces, bearing forces, and punching shear stresses. Sometimes, design displacements are determined for factored loads. The load effects relevant for service design include stresses and deflections.

In the course of applying these principles, the licensed design professional should be aware that providing more strength than required does not necessarily lead to a safer structure because doing so may change the potential failure mode. For example, increasing longitudinal reinforcement area beyond that required for moment strength as derived from analysis without increasing transverse reinforcement could increase the probability of a shear failure occurring prior to a flexural failure. Excess strength may be undesirable for structures expected to behave inelastically during earthquakes.

4.6.2 Structures and structural members shall have design strength at all sections, ϕS_n , greater than or equal to the required strength U calculated for the factored loads and forces in such combinations as required by this Code or the general building code.

CODE

4.7—Serviceability

4.7.1 Evaluation of performance at service load conditions shall consider reactions, moments, shears, torsions, and axial forces induced by prestressing, creep, shrinkage, temperature change, axial deformation, restraint of attached structural members, and foundation settlement.

4.7.2 For structures, structural members, and their connections, the requirements of 4.7.1 shall be deemed to be satisfied if designed in accordance with the provisions of the applicable member chapters.

4.8—Durability

4.8.1 Concrete mixtures shall be designed in accordance with the requirements of 19.3.2 and 26.4, considering applicable environmental exposure to provide required durability.

4.8.2 Reinforcement shall be protected from corrosion in accordance with 20.5.

4.9—Sustainability and resilience

4.9.1 The licensed design professional shall be permitted to incorporate the applicable sustainability and resilience provisions of Appendix C in the design.

4.10—Structural integrity

4.10.1 General

4.10.1.1 Reinforcement and connections shall be detailed to tie the structure together effectively and to improve overall structural integrity.

COMMENTARY

R4.7—Serviceability

R4.7.1 Serviceability refers to the ability of the structural system or structural member to provide appropriate behavior and functionality under the actions affecting the system. Serviceability requirements address issues such as deflections and cracking, among others. Serviceability considerations for vibrations are discussed in R6.6.3.2.2 and R24.1.

Except as stated in Chapter 24, service-level load combinations are not defined in the Code, but are discussed in Appendix C of ASCE/SEI 7. Appendixes to ASCE/SEI 7 are not considered mandatory parts of the standard.

R4.8—Durability

R4.8.1 The environment where the structure will be located will dictate the exposure category for materials selection, design details, and construction requirements to minimize potential for premature deterioration of the structure caused by environmental effects. Durability of a structure is also impacted by the level of preventative maintenance, which is not addressed in the Code.

Chapter 19 provides requirements for protecting concrete against major environmental causes of deterioration.

R4.9—Sustainability and resilience

R4.9.1 Appendix C describes approaches for increasing the sustainability and resilience of concrete structures and includes requirements for concrete mixtures and construction. The licensed design professional and stakeholders should establish the hazard events the design process must consider.

R4.10—Structural integrity

R4.10.1 General

R4.10.1.1 It is the intent of the structural integrity requirements to improve redundancy and ductility through detailing of reinforcement and connections so that, in the event of damage to a major supporting element or an abnormal loading, the resulting damage will be localized and the structure will have a higher probability of maintaining overall stability.

Integrity requirements for selected structural member types are included in the corresponding member chapter in the sections noted.

CODE

4.10.2 *Minimum requirements for structural integrity*

4.10.2.1 Structural members and their connections shall be in accordance with structural integrity requirements in Table 4.10.2.1.

Table 4.10.2.1—Minimum requirements for structural integrity

Member type	Section
Nonprestressed one-way cast-in-place slabs	7.7.7
Nonprestressed two-way slabs	8.7.4.2
Prestressed two-way slabs	8.7.5.6
Nonprestressed two-way joist systems	8.8.1.6
Cast-in-place beam	9.7.7
Nonprestressed one-way joist system	9.8.1.6
Precast joints and connections	16.2.1.8

4.11—Fire resistance

4.11.1 Structural concrete members shall satisfy the fire protection requirements of the general building code.

4.11.2 Where the general building code requires a thickness of concrete cover for fire protection greater than the concrete cover specified in **20.5.1**, such greater thickness shall govern.

4.12—Requirements for specific types of construction**4.12.1** *Precast concrete systems*

4.12.1.1 It shall be permitted to design precast concrete members and connections in accordance with **ACI/PCI CODE-319**, “Building Code Requirements for Structural Precast Concrete—Code and Commentary.”

4.12.1.2 Design of precast concrete members and connections shall include loading and restraint conditions from initial fabrication to end use in the structure, including form removal, storage, transportation, and erection.

COMMENTARY

R4.10.2 *Minimum requirements for structural integrity*

R4.10.2.1 Structural members and their connections referred to in this section include only member types that have specific requirements for structural integrity. Notwithstanding, detailing requirements for other member types address structural integrity indirectly.

R4.11—Fire resistance

R4.11.1 Additional guidance on fire resistance of structural concrete is provided by **ACI/TMS CODE-216.1**.

R4.12—Requirements for specific types of construction**R4.12.1** *Precast concrete systems*

This section contains requirements that are related to specific types of construction. Additional requirements that are specific to member types appear in the corresponding member chapters.

R4.12.1.1 ACI/PCI CODE-319 provides structural concrete code requirements unique to design of precast concrete including pretensioned concrete.

R4.12.1.2 All requirements in the Code apply to precast systems and members unless specifically excluded. In addition, some requirements apply specifically to precast concrete. This section contains specific requirements for precast systems. Other sections of the Code also provide specific requirements, such as required concrete cover, for precast systems.

Precast systems differ from monolithic systems in that the type of restraint at supports, the location of supports, and the induced stresses in the body of the member vary during fabrication, storage, transportation, erection, and the final

CODE

4.12.1.3 Design, fabrication, and construction of precast members and their connections shall include the effects of tolerances.

4.12.1.4 When precast members are incorporated into a structural system, the forces and deformations occurring in and adjacent to connections shall be included in the design.

4.12.1.5 Where system behavior requires in-plane loads to be transferred between the members of a precast floor or wall system, (a) and (b) shall be satisfied:

- (a) In-plane load paths shall be continuous through both connections and members.
- (b) Where tension loads occur, a load path of steel or steel reinforcement, with or without splices, shall be provided.

4.12.1.6 Distribution of forces that act perpendicular to the plane of precast members shall be established by analysis or test.

4.12.2 Prestressed concrete systems

COMMENTARY

interconnected configuration. Consequently, the member design forces to be considered may differ in magnitude and direction with varying critical sections at various stages of construction. For example, a precast flexural member may be simply supported for dead load effects before continuity at the supporting connections is established and may be a continuous member for live or environmental load effects due to the moment continuity created by the connections after erection.

R4.12.1.3 For guidance on including the effects of tolerances, refer to the *PCI Design Handbook* (**PCI MNL 120**).

R4.12.1.6 Concentrated and line loads can be distributed among members provided the members have sufficient torsional stiffness and shear can be transferred across joints. Torsionally stiff members such as hollow-core or solid slabs will provide better load distribution than torsionally flexible members such as double tees with thin flanges. The actual distribution of the load depends on many factors discussed in detail in **LaGue (1971)**, **Johnson and Ghadiali (1972)**, **Pfeifer and Nelson (1983)**, **Stanton (1987, 1992)**, *PCI Manual for the Design of Hollow Core Slabs and Walls* (**PCI MNL 126**), **Aswad and Jacques (1992)**, and the *PCI Design Handbook* (**PCI MNL 120**). Large openings can cause significant changes in distribution of forces.

R4.12.2 Prestressed concrete systems

Prestressing, as used in the Code, may apply to pretensioning, bonded post-tensioning, or unbonded post-tensioning. All requirements in the Code apply to prestressed systems and members, unless specifically excluded. This section contains specific requirements for prestressed concrete systems. Other sections of the Code also provide specific requirements, such as required concrete cover for prestressed systems.

Creep and shrinkage effects may be greater in prestressed than in nonprestressed concrete structures because of the prestressing forces and because prestressed structures typically have less bonded reinforcement. Effects of movements

CODE

4.12.2.1 It shall be permitted to design post-tensioned concrete members in accordance with **ACI/PTI CODE-320**, “Building Code Requirements for Structural Post-Tensioned Concrete—Code and Commentary.”

4.12.2.2 Design of prestressed members and systems shall be based on strength and on behavior at service conditions at all critical stages during the life of the structure from the time prestress is first applied.

4.12.2.3 Provisions shall be made for effects on adjoining construction of elastic and plastic deformations, deflections, changes in length, and rotations due to prestressing. Effects of temperature change, restraint of attached structural members, foundation settlement, creep, and shrinkage shall also be considered.

4.12.2.4 Stress concentrations due to prestressing shall be considered in design.

4.12.2.5 Effect of loss of area due to open ducts shall be considered in computing section properties before grout in post-tensioning ducts has attained design strength.

4.12.2.6 Post-tensioning tendons shall be permitted to be external to any concrete section of a member. Strength and serviceability design requirements of this Code shall be used to evaluate the effects of external tendon forces on the concrete structure.

4.12.3 *Composite concrete flexural members*

4.12.3.1 This Code shall apply to composite concrete flexural members as defined in **Chapter 2**.

4.12.3.2 Individual members shall be designed for all critical stages of loading.

COMMENTARY

due to creep and shrinkage may require more attention than is normally required for nonprestressed concrete. These movements may increase prestress losses.

Design of externally post-tensioned construction should consider aspects of corrosion protection and fire resistance that are applicable to this structural system.

R4.12.2.1 ACI/PTI CODE-320 provides structural concrete code requirements unique to design of post-tensioned concrete.

R4.12.3 *Composite concrete flexural members*

This section addresses structural concrete members, either precast or cast-in-place, prestressed or nonprestressed, consisting of concrete cast at different times intended to act as a composite member when loaded after concrete of the last stage of casting has set. All requirements in the Code apply to these members unless specifically excluded. In addition, some requirements apply specifically to composite concrete flexural members. This section contains requirements that are specific to these elements and are not covered in the applicable member chapters.

CODE

4.12.3.3 Members shall be designed to support all loads introduced prior to full development of design strength of composite members.

4.12.3.4 Reinforcement shall be detailed to minimize cracking and to prevent separation of individual components of composite members.

4.12.4 *Structural plain concrete systems*

4.12.4.1 The design of structural plain concrete members, both cast-in-place and precast, shall be in accordance with **Chapter 14**.

4.13—Construction and inspection

4.13.1 Specifications for construction execution shall be in accordance with **Chapter 26**.

4.13.2 Inspection during construction shall be in accordance with Chapter 26 and the general building code.

4.14—Strength evaluation of existing structures

4.14.1 Strength evaluation of existing structures shall be in accordance with **Chapter 27**.

COMMENTARY**R4.13—Construction and inspection**

R4.13.1 Chapter 26 has been organized to collect into one location the design information, compliance requirements, and inspection provisions from the Code that should be included in construction documents. There may be other information that should be included in construction documents that is not covered in Chapter 26.

R4.14—Strength evaluation of existing structures

R4.14.1 Requirements in Chapter 27 for strength evaluation of existing structures by physical load test address the evaluation of structures subjected to gravity loads only. Chapter 27 also covers strength evaluation of existing structures by analytical evaluation, which may be used for gravity as well as other loadings such as earthquake or wind.

CHAPTER 5—LOADS

CODE

COMMENTARY

5.1—Scope

5.1.1 This chapter shall apply to selection of load factors and combinations used in design, except as permitted in [Chapter 27](#).

5.2—General

5.2.1 Loads shall include self-weight; applied loads; and effects of prestressing, earthquakes, restraint of volume change, and differential settlement.

5.2.2 Loads and Seismic Design Categories (SDCs) shall be in accordance with the general building code, or determined by the building official.

5.2.3 Live load reductions shall be permitted in accordance with the general building code or, in the absence of a general building code, in accordance with ASCE/SEI 7.

5.3—Load factors and combinations

5.3.1 Required strength U shall be at least equal to the effects of factored loads in Table 5.3.1, with exceptions and additions in 5.3.3 through 5.3.16.

R5.1—Scope

R5.1.1 The loading provisions of this chapter are intended for the design of new structures and analytical strength evaluation of existing structures. Loads, load factors, and load combinations for evaluation of structures during construction are presented in [ASCE/SEI 37](#).

R5.2—General

R5.2.1 The loading provisions in this chapter are associated with dead, live, wind, rain, snow, earthquake, lateral earth pressure, fluid, flood, ice, tornado, tsunami, water in soil, restraint of volume change and differential settlement loads such as those recommended in [ASCE/SEI 7](#). The commentary to Appendix C of ASCE/SEI 7 provides service-level wind and snow loads for serviceability checks; however, these loads are not appropriate for strength design.

If the service loads specified by the general building code differ from those of ASCE/SEI 7, the general building code governs. However, if the nature of the loads contained in a general building code differs considerably from ASCE/SEI 7 loads, some provisions of the Code may need modification to reflect the difference.

ASCE/SEI 7 provides maps used to determine wind, snow, ice, seismic, and tornado loads for the United States and its territories. The loads for wind, snow, ice, seismic, and tornadoes are provided at the strength-level. If the Code is used in other locations, the design professional should confirm the loads used in design are strength-level loads.

R5.2.2 Seismic Design Categories (SDCs) in the Code are adopted directly from ASCE/SEI 7.

Design requirements for earthquake-resistant structures in the Code are determined by the SDC to which the structure is assigned. In general, the SDC relates to seismic hazard level, soil type, occupancy, and building use. Assignment of a building to an SDC is under the jurisdiction of the general building code rather than the Code.

In the absence of a general building code that prescribes SDC, it is the intent of Committee 318 that application of provisions for earthquake-resistant design be consistent with national standards or model building codes such as ASCE/SEI 7, [IBC](#), and [NFPA 5000](#).

R5.3—Load factors and combinations

R5.3.1 The required strength U is expressed in terms of factored loads. Factored loads are the loads specified in the general building code multiplied by appropriate load factors. If the load effects such as internal forces and moments are linearly related to the loads, the required strength U may be expressed in terms of load effects multiplied by the appropriate load factors with the identical result. If the load effects

CODE

Table 5.3.1—Load combinations

Load combination	Equation	Primary load
$U = 1.4D$	(5.3.1a)	D
$U = 1.2D + 1.6L + (0.5L_r \text{ or } 0.3S \text{ or } 0.5R)$	(5.3.1b)	L
$U = 1.2D + (1.6L_r \text{ or } 1.0S \text{ or } 1.6R) + (1.0L \text{ or } 0.5W)$	(5.3.1c)	$L_r \text{ or } S \text{ or } R$
$U = 1.2D + 1.0W + 1.0L + (0.5L_r \text{ or } 0.3S \text{ or } 0.5R)$	(5.3.1d)	W
$U = 1.2D + 1.0E + 1.0L + 0.15S$	(5.3.1e)	E
$U = 0.9D + 1.0W$	(5.3.1f)	W
$U = 0.9D + 1.0E$	(5.3.1g)	E

COMMENTARY

are nonlinearly related to the loads, such as frame P-delta effects, the loads are factored before determining the load effects (Rogowsky and Wight 2010). Typical practice for foundation design is discussed in R13.2.6.1. Nonlinear finite element analysis using factored load cases is discussed in R6.9.3.

The factor assigned to each load is influenced by the degree of accuracy to which the load effect usually can be calculated and the variation that might be expected in the load during the lifetime of the structure. Dead loads, because they are more accurately determined and less variable, are assigned a lower load factor than live loads. Load factors also account for variability in the structural analysis used to calculate moments and shears.

The Code gives load factors for specific combinations of loads. In assigning factors to combinations of loading, some consideration is given to the probability of simultaneous occurrence. While most of the usual combinations of loadings are included, it should not be assumed that all cases are covered.

Due regard is to be given to the sign (positive or negative) in determining U for combinations of loadings, as one type of loading may produce effects of opposite sense to that produced by another type. The load combinations with $0.9D$ are included for the case where a higher dead load reduces the effects of other loads. The loading case may also be critical for tension-controlled column sections. In such a case, a reduction in compressive axial load or development of tension with or without an increase in moment may result in a critical load combination.

Consideration should be given to various combinations of loading to determine the most critical design condition. This is particularly true when strength is dependent on more than one load effect, such as strength for combined flexure and axial load or shear strength in members with axial load.

If unusual circumstances require greater reliance on the strength of particular members than circumstances encountered in usual practice, some reduction in the stipulated strength reduction factors ϕ or increase in the stipulated load factors may be appropriate for such members.

Rain load R in Eq. (5.3.1b), (5.3.1c), and (5.3.1d) should account for all likely accumulations of water. Roofs should be designed with sufficient slope or camber to ensure adequate drainage accounting for any long-term deflection of the roof due to the dead loads. If deflection of roof members may result in ponding of water accompanied by increased deflection and additional ponding, the design should ensure that this process is self-limiting.

Model building codes and standards refer to earthquake forces at the strength level, and the corresponding load factor is 1.0 (ASCE/SEI 7; 2021 IBC). In the absence of a general building code that prescribes strength level earthquake effects, a higher load factor on E would be required. The load effect E in model building codes and design load reference standards includes the effect of both horizontal and

CODE

5.3.2 The effect of one or more loads not acting simultaneously shall be investigated.

5.3.3 The load factor on live load L in Eq. (5.3.1c), (5.3.1d), and (5.3.1e) shall be permitted to be reduced to 0.5 except for (a), (b), or (c):

- (a) Garages
- (b) Areas occupied as places of public assembly
- (c) Areas where L is greater than 100 lb/ft²

5.3.4 If applicable, L shall include (a) through (f):

- (a) Concentrated live loads
- (b) Vehicular loads
- (c) Crane loads
- (d) Loads on hand rails, guardrails, and vehicular barrier systems
- (e) Impact effects
- (f) Vibration effects

5.3.5 If wind load W is provided at service-level loads, $1.6W$ shall be used in place of $1.0W$ in Eq. (5.3.1d) and (5.3.1f), and $0.8W$ shall be used in place of $0.5W$ in Eq. (5.3.1c).

5.3.6 The structural effects of forces due to restraint of volume change and differential settlement T shall be considered in combination with other loads if the effects of T can adversely affect structural safety or performance. The load factor for T shall be established considering the uncertainty associated with the likely magnitude of T , the probability that the maximum effect of T will occur simultaneously with other applied loads, and the potential adverse consequences if the effect of T is greater than assumed. The load factor on T shall not have a value less than 1.0.

COMMENTARY

vertical ground motions (as E_h and E_v , respectively). The effect for vertical ground motions is applied as an addition to or subtraction from the dead load effect (D), and it applies to all structural elements, whether part of the seismic force-resisting system or not, unless specifically excluded by the general building code.

In **ASCE/SEI 7-22**, snow loads were changed to strength-level loads from the service-level loads that had been specified in prior versions of **ASCE/SEI 7**. The change from service to strength-level is reflected in the modifications in the load factor for snow loads in Table 5.3.1.

R5.3.3 The load modification factor in this provision is different than the live load reductions based on the loaded area that may be allowed in the general building code. The live load reduction, based on loaded area, adjusts the nominal live load (L_0 in **ASCE/SEI 7**) to L . The live load reduction, as specified in the general building code, can be used in combination with the 0.5 load factor specified in this provision.

R5.3.5 In **ASCE/SEI 7-05**, wind loads are consistent with service-level design; a wind load factor of 1.6 is appropriate for use in Eq. (5.3.1d) and (5.3.1f) and a wind load factor of 0.8 is appropriate for use in Eq. (5.3.1c). **ASCE/SEI 7-22** prescribes wind loads for strength-level design and the wind load factor is 1.0. Design wind speeds for strength-level design are based on storms with mean recurrence intervals of 300, 700, 1700, and 3000 years depending on the risk category of the structure. The higher load factors in 5.3.5 apply where service-level wind loads corresponding to a 50-year mean recurrence interval are used for design.

R5.3.6 Several strategies can be used to accommodate movements due to volume change and differential settlement. Restraint of such movements can cause significant member forces and moments, such as tension in slabs and shear forces and moments in vertical members. Forces due to T effects are not commonly calculated and combined with other load effects. Rather, designs rely on successful past practices using compliant structural members and ductile connections to accommodate differential settlement

CODE

COMMENTARY

5.3.7 If fluid load F is present, it shall be included in the load combination equations of 5.3.1 in accordance with (a), (b), (c), or (d):

- (a) If F acts alone or adds to the effects of D , it shall be included with a load factor of 1.4 in Eq. (5.3.1a).
- (b) If F adds to the primary load, it shall be included with a load factor of 1.2 in Eq. (5.3.1b) through (5.3.1e).
- (c) If the effect of F is permanent and counteracts the primary load, it shall be included with a load factor of 0.9 in Eq. (5.3.1g).
- (d) If the effect of F is not permanent but, when present, counteracts the primary load, F shall not be included in Eq. (5.3.1a) through (5.3.1g).

5.3.8 If lateral earth pressure H is present, it shall be included in the load combination equations of 5.3.1 in accordance with (a), (b), or (c):

- (a) If H acts alone or adds to the primary load effect, it shall be included with a load factor of 1.6.
- (b) If the effect of H is permanent and counteracts the primary load effect, it shall be included with a load factor of 0.9.
- (c) If the effect of H is not permanent but, when present, counteracts the primary load effect, H shall not be included.

5.3.9 If a structure is in a flood zone, the flood loads and the appropriate load factors and combinations of **ASCE/SEI 7** shall be used.

5.3.10 If a structure is subjected to forces from atmospheric ice loads, the ice loads and the appropriate load factors and combinations of **ASCE/SEI 7** shall be used.

and volume change movement while providing the needed resistance to gravity and lateral loads. Expansion joints and construction closure strips are used to limit volume change movements based on the performance of similar structures. Shrinkage and temperature reinforcement, which may exceed the required flexural reinforcement, is commonly proportioned based on gross concrete area rather than calculated force.

Where structural movements can lead to damage of nonductile elements, calculation of the predicted force should consider the inherent variability of the expected movement and structural response.

A long-term study of the volume change behavior of precast concrete buildings (**Klein and Lindenberg 2009**) recommends procedures to account for connection stiffness, thermal exposure, member softening due to creep, and other factors that influence T forces.

Fintel et al. (1986) provides information on the magnitudes of volume change effects in tall structures and recommends procedures for including the forces resulting from these effects in design.

R5.3.8 The required load factors for lateral pressures from soil, water in soil, and other materials, reflect their variability and the possibility that the materials may be removed. The commentary of **ASCE/SEI 7** includes additional useful discussion pertaining to load factors for H .

R5.3.9 Areas subject to flooding are defined by flood hazard maps, usually maintained by local governmental jurisdictions.

R5.3.10 Ice buildup on a structural member increases the applied load and the projected area exposed to wind. **ASCE/SEI 7** provides maps of probable ice thicknesses due to

CODE

COMMENTARY

5.3.11 For structures required to resist loads from tornadoes, the tornado loads and appropriate load factors and combinations of **ASCE/SEI 7** shall be used.

5.3.12 For structures required to resist loads from tsunamis, the loads and appropriate load factors and combinations of **ASCE/SEI 7** shall be used.

5.3.13 For structures subjected to loads from water in soil, the alternate method for loads from water in soil of **ASCE/SEI 7** shall be permitted.

5.3.14 Required strength U shall include internal load effects due to reactions induced by prestressing with a load factor of 1.0.

5.3.15 For post-tensioned anchorage zone design, a load factor of 1.2 shall be applied to the maximum prestressing reinforcement jacking force.

5.3.16 Load factors for the effects of prestressing used with the strut-and-tie method shall be included in the load combination equations of 5.3.1 in accordance with (a) or (b):

- (a) A load factor of 1.2 shall be applied to the prestressing effects where the prestressing effects increase the net force in struts or ties.
- (b) A load factor of 0.9 shall be applied to the prestressing effects where the prestressing effects reduce the net force in struts or ties.

freezing rain, with concurrent 3-second gust speeds, for a 50-year return period.

R5.3.11 For some critical structures, wind loads resulting from tornadoes are included in the basic load combinations of **ASCE/SEI 7**. **ASCE/SEI 7** provides a map and a procedure to estimate loads associated with tornadoes acting on the main wind-force-resisting system, components, and cladding.

R5.3.12 For some structures, loads resulting from tsunamis are considered in design. **ASCE/SEI 7** provides a map and procedures to determine loads associated with tsunamis.

R5.3.13 The alternate method in **ASCE/SEI 7** allows the effect of ground water pressure to be decoupled from soil pressure. The basic method in **ASCE/SEI 7** includes water pressure as a part of the earth pressure and does not account for uncertainty in the groundwater elevation. The load factor on earth pressure effectively increases the density of water, which is technically inconsistent. Additional information on this method is presented in the commentary of **ASCE/SEI 7**.

R5.3.14 For statically indeterminate structures, the internal load effects due to reactions induced by prestressing forces, sometimes referred to as secondary moments, can be significant (**Bondy 2003**; **Lin and Thornton 1972**; **Collins and Mitchell 1997**).

R5.3.15 The load factor of 1.2 applied to the maximum tendon jacking force results in a design load of about 113% of the specified prestressing reinforcement yield strength, but not more than 96% of the nominal tensile strength of the prestressing reinforcement. This compares well with the maximum anchorage capacity, which is at least 95% of the nominal tensile strength of the prestressing reinforcement.

Notes



CHAPTER 6—STRUCTURAL ANALYSIS

CODE

COMMENTARY

6.1—Scope

6.1.1 This chapter shall apply to methods of analysis, modeling of members and structural systems, and calculation of load effects.

R6.1—Scope

R6.1.1 The provisions of this chapter apply to analyses used to determine load effects for design.

Section 6.2 provides general requirements that are applicable for all analysis procedures.

Section 6.2.4 directs the licensed design professional to specific analysis provisions that are not contained in this chapter. Sections 6.2.4.1 and 6.2.4.2 identify analysis provisions that are specific to two-way slabs and walls.

Section 6.3 addresses modeling assumptions used in establishing the analysis model.

Section 6.4 prescribes the arrangements of live loads that are to be considered in the analysis.

Section 6.5 provides a simplified method of analysis for nonprestressed continuous beams and one-way slabs that can be used in place of a more rigorous analysis when the stipulated conditions are satisfied.

Section 6.6 includes provisions for a comprehensive linear elastic first-order analysis. The effects of cracked sections and creep are included in the analysis through the use of effective stiffnesses.

Section 6.7 includes provisions for linear elastic second-order analysis. Inclusion of the effects of cracking and creep is required.

Section 6.8 includes provisions for inelastic analysis.

Section 6.9 includes provisions for the use of the finite element method.

6.2—General

6.2.1 Members and structural systems shall be permitted to be modeled in accordance with 6.3.

6.2.2 All members and structural systems shall be analyzed to determine the maximum load effects including the arrangements of live load in accordance with 6.4.

6.2.3 Methods of analysis permitted by this chapter shall be (a) through (e):

- (a) The simplified method for analysis of continuous beams and one-way slabs for gravity loads in 6.5
- (b) Linear elastic first-order analysis in 6.6
- (c) Linear elastic second-order analysis in 6.7
- (d) Inelastic analysis in 6.8
- (e) Finite element analysis in 6.9

R6.2—General

R6.2.3 A first-order analysis satisfies the equations of equilibrium using the original undeformed geometry of the structure. When only first-order results are considered, slenderness effects are not accounted for. Because these effects can be important, 6.6 provides procedures to calculate both individual member slenderness ($P\delta$) effects and sidesway ($P\Delta$) effects for the overall structure using the first-order results.

A second-order analysis satisfies the equations of equilibrium using the deformed geometry of the structure. If the second-order analysis uses nodes along compression members, the analysis accounts for slenderness effects due to lateral deformations along individual members, as well as sidesway of the overall structure. If the second-order analysis uses nodes at the member intersections only, the analysis captures the sidesway effects for the overall structure but neglects individual member slenderness effects. In this case, the moment magnifier method (6.6.4) is used to determine individual member slenderness effects.

CODE

COMMENTARY

6.2.4 Additional analysis methods that are permitted include 6.2.4.1 through 6.2.4.4.

6.2.4.1 Two-way slabs shall be permitted to be analyzed for gravity loads in accordance with (a) or (b):

- (a) Direct design method for nonprestressed slabs
- (b) Equivalent frame method for nonprestressed and prestressed slabs

6.2.4.2 Slender walls shall be permitted to be analyzed in accordance with 11.8 for out-of-plane effects.

6.2.4.3 Diaphragms shall be permitted to be analyzed in accordance with 12.4.2.

6.2.4.4 A member or region shall be permitted to be analyzed and designed using the strut-and-tie method in accordance with Chapter 23.

6.2.5 Slenderness effects

An inelastic analysis i) represents the nonlinear stress-strain response of the materials composing the structure; ii) satisfies compatibility of deformations; and iii) satisfies equilibrium in the undeformed configuration for first-order analysis or in the deformed configuration for second-order analysis.

Finite element analysis was introduced in the 2014 Code to explicitly recognize a widely used analysis method.

R6.2.4.1 Code editions from 1971 to 2014 contained provisions for use of the direct design method and the equivalent frame method. These methods are well-established and are covered in available texts. These provisions for gravity load analysis of two-way slabs have been removed from the Code because they are considered to be only two of several analysis methods currently used for the design of two-way slabs. The direct design method and the equivalent frame method of the 2014 Code, however, may still be used for the analysis of two-way slabs for gravity loads.

R6.2.5 Slenderness effects

Second-order effects in many structures are negligible. In these cases, it is unnecessary to consider slenderness effects, and compression members, such as columns, walls, or braces, can be designed based on forces determined from first-order analyses. Slenderness effects can be neglected in both braced and unbraced systems, depending on the slenderness ratio ($k\ell_u/r$) of the member.

The sign convention for M_1/M_2 has been updated so that M_1/M_2 is negative if bent in single curvature and positive if bent in double curvature. This reflects a sign convention change from the 2011 Code.

The primary design aid to estimate the effective length factor k is the Jackson and Moreland Alignment Charts (Fig. R6.2.5.1), which provide a graphical determination of k for a column of constant cross section in a multi-bay frame (ACI SP-17(09); Column Research Council 1966).

Equations (6.2.5.1b) and (6.2.5.1c) are based on Eq. (6.6.4.5.1) assuming that a 5 percent increase in moments due to slenderness is acceptable (MacGregor et al. 1970).

CODE

COMMENTARY

As a first approximation, k may be taken equal to 1.0 in Eq. (6.2.5.1b) and (6.2.5.1c).

The stiffness of the lateral bracing is considered based on the principal directions of the framing system. Bracing elements in typical building structures consist of structural walls or lateral braces. Torsional response of the lateral-force-resisting system due to eccentricity of the structural system can increase second-order effects and should be considered.

6.2.5.1 Slenderness effects shall be permitted to be neglected if (a) or (b) is satisfied:

(a) For columns not braced against sidesway

$$\frac{k\ell_u}{r} \leq 22 \quad (6.2.5.1a)$$

(b) For columns braced against sidesway

$$\frac{k\ell_u}{r} \leq 34 + 12(M_1/M_2) \quad (6.2.5.1b)$$

and


$$\frac{k\ell_u}{r} \leq 40 \quad (6.2.5.1c)$$

where M_1/M_2 is negative if the column is bent in single curvature, and positive for double curvature.

If bracing elements resisting lateral movement of a story have a total stiffness of at least 12 times the gross lateral stiffness of the columns in the direction considered, it shall be permitted to consider columns within the story to be braced against sidesway.

CODE

COMMENTARY



Ψ = ratio of $\Sigma(EI/l_c)$ of all columns to $\Sigma(EI/l)$ of beams in a plane at one end of a column

l = span length of beam measured center to center of joints

Fig. R6.2.5.1—Effective length factor k .

6.2.5.2 The radius of gyration, r , shall be permitted to be calculated by (a), (b), or (c):

$$(a) \ r = \sqrt{\frac{I_g}{A_g}} \quad (6.2.5.2)$$

(b) 0.30 times the dimension in the direction stability is being considered for rectangular columns

(c) 0.25 times the diameter of circular columns

6.2.5.3 Unless slenderness effects are neglected as permitted by 6.2.5.1, the design of columns, restraining beams, and other supporting members shall be based on the factored forces and moments considering second-order effects in accordance with 6.6.4, 6.7, or 6.8. M_u of end moments including second-order effects shall not exceed $1.4M_u$ due to first-order effects.

R6.2.5.3 Design considering second-order effects may be based on the moment magnifier approach (MacGregor et al. 1970; MacGregor 1993; Ford et al. 1981), an elastic second-order analysis, or a nonlinear second-order analysis. Figure R6.2.5.3 is intended to assist designers with application of the slenderness provisions of the Code.

End moments in compression members, such as columns, walls, or braces, should be considered in the design of adjacent flexural members. In nonsway frames, the effects of magnifying the end moments need not be considered in the

CODE**COMMENTARY**

design of adjacent beams. In sway frames, the magnified end moments should be considered in designing the adjoining flexural members.

Several methods have been developed to evaluate slenderness effects in compression members subject to biaxial bending. A review of some of these methods is presented in [Furlong et al. \(2004\)](#).

If the weight of a structure is high in proportion to its lateral stiffness, excessive $P\Delta$ effects, where secondary moments are more than 25 percent of the primary moments, may result. The $P\Delta$ effects will eventually introduce singularities into the solution to the equations of equilibrium, indicating physical structural instability ([Wilson 1997](#)). Analytical research ([MacGregor and Hage 1977](#)) on reinforced concrete frames showed that the probability of stability failure increases rapidly when the stability index Q , defined in 6.6.4.4.1, exceeds 0.2, which is equivalent to a secondary-to-primary moment ratio of 1.25. According to [ASCE/SEI 7](#), the maximum value of the stability coefficient θ , which is close to the ACI stability coefficient Q , is 0.25. The value 0.25 is equivalent to a secondary-to-primary moment ratio of 1.33. Hence, the upper limit of 1.4 on the secondary-to-primary moment ratio was chosen.

CODE

COMMENTARY




Fig. R6.2.5.3—Flowchart for determining column slenderness effects.

CODE

6.3—Modeling assumptions**6.3.1 General**

6.3.1.1 Member stiffnesses for analysis of structural systems shall be selected based on a reasonable set of assumptions. The assumptions shall be consistent throughout each analysis.

6.3.1.2 To calculate moments and shears caused by gravity loads in columns, beams, and slabs, it shall be permitted to use a model limited to the members in the level being considered and the columns above and below that level. It shall be permitted to assume far ends of columns built integrally with the structure to be fixed.

6.3.1.3 The analysis model shall consider the effects of variation of member cross-sectional properties, such as that due to haunches.

6.3.2 T-beam geometry

6.3.2.1 For nonprestressed T-beams supporting monolithic or composite concrete slabs, the effective flange width b_f shall include the beam web width b_w plus an effective

COMMENTARY

R6.3—Modeling assumptions**R6.3.1 General**

R6.3.1.1 Separate analyses with different stiffness assumptions may be performed for different objectives such as to check serviceability or strength criteria or to bound the demands on elements where stiffness assumptions are critical.

Ideally, the member stiffnesses $E_c I$ and GJ should reflect the degree of cracking and inelastic action that has occurred along each member before yielding. However, the complexities involved in selecting different stiffnesses for all members of a frame would make frame analyses inefficient in the design process. Simpler assumptions are required to define member stiffnesses.

Relative stiffnesses of members are sufficient to estimate the distribution of load effects for many circumstances, such as, moments and shears in continuous beams. For analyses where deflections, second-order effects, or dynamic response are considered, an estimate of effective stiffness of members is required.

Guidance for the selection of effective stiffness is given in 6.6.3.

Two conditions determine whether it is necessary to consider torsional stiffness in the analysis of a given structure: 1) the relative magnitude of the torsional and flexural stiffnesses; and 2) whether torsion is required for equilibrium of the structure (equilibrium torsion) or is due to members twisting to maintain deformation compatibility (compatibility torsion). In the case of equilibrium torsion, torsional stiffness should be included in the analysis. It is, for example, necessary to consider the torsional stiffnesses of edge beams. In the case of compatibility torsion, torsional stiffness usually is not included in the analysis. This is because the cracked torsional stiffness of a beam is a small fraction of the flexural stiffness of the members framing into it. Torsion should be considered in design as required in [Chapter 9](#).

R6.3.1.3 Stiffness and fixed-end moment coefficients for haunched members may be obtained from the [Portland Cement Association \(1972\)](#).

R6.3.2 T-beam geometry

R6.3.2.1 In [ACI 318-11](#), the width of the slab effective as a T-beam flange was limited to one-fourth the span. The Code now allows one-eighth of the span on each side of the

CODE

overhanging flange width in accordance with Table 6.3.2.1, where h is the slab thickness and s_w is the clear distance to the adjacent web.

Table 6.3.2.1—Dimensional limits for effective overhanging flange width for T-beams

Flange location	Effective overhanging flange width, beyond face of web	
Each side of web	Least of:	$8h$
		$s_w/2$
		$\ell_n/8$
One side of web	Least of:	$6h$
		$s_w/2$
		$\ell_n/12$

6.3.2.2 Isolated nonprestressed T-beams in which the flange is used to provide additional compression area shall have a flange thickness greater than or equal to $0.5b_w$ and an effective flange width less than or equal to $4b_w$.

6.3.2.3 For prestressed T-beams, it shall be permitted to use the geometry provided by 6.3.2.1 and 6.3.2.2.

6.4—Arrangement of live load

6.4.1 For the design of floors or roofs to resist gravity loads, it shall be permitted to assume that live load is applied only to the level under consideration.

6.4.2 For one-way slabs and beams, it shall be permitted to assume (a) and (b):

- (a) Maximum positive M_u near midspan occurs with factored L on the span and on alternate spans
- (b) Maximum negative M_u at a support occurs with factored L on adjacent spans only

6.4.3 For two-way slab systems, factored moments shall be calculated in accordance with 6.4.3.1, 6.4.3.2, or 6.4.3.3, and shall be at least the moments resulting from factored L applied simultaneously to all panels.

6.4.3.1 If the arrangement of L is known, the slab system shall be analyzed for that arrangement.

COMMENTARY

beam web. This was done to simplify Table 6.3.2.1 and has negligible impact on designs.

R6.3.2.3 The empirical provisions of 6.3.2.1 and 6.3.2.2 were developed for nonprestressed T-beams. The flange widths in 6.3.2.1 and 6.3.2.2 should be used unless experience has proven that variations are safe and satisfactory. Although many standard prestressed products in use today do not satisfy the effective flange width requirements of 6.3.2.1 and 6.3.2.2, they demonstrate satisfactory performance. Therefore, determination of an effective flange width for prestressed T-beams is left to the experience and judgment of the licensed design professional. It is not always considered conservative in elastic analysis and design considerations to use the maximum flange width as permitted in 6.3.2.1.

R6.4—Arrangement of live load

R6.4.2 The most demanding sets of design forces should be established by investigating the effects of live load placed in various critical patterns.

CODE

6.4.3.2 If L is variable and does not exceed $0.75D$, or the nature of L is such that all panels will be loaded simultaneously, it shall be permitted to assume that maximum M_u at all sections occurs with factored L applied simultaneously to all panels.

6.4.3.3 For loading conditions other than those defined in 6.4.3.1 or 6.4.3.2, it shall be permitted to assume (a) and (b):

- (a) Maximum positive M_u near midspan of panel occurs with 75% of factored L on the panel and alternate panels
- (b) Maximum negative M_u at a support occurs with 75% of factored L on adjacent panels only

6.4.4 For embedments creating voids parallel to the slab plane with cross-section dimension larger than one-third the slab thickness, or spaced closer than three void diameters or widths on center, the arrangement of live load on only a portion of the slab shall be considered.

COMMENTARY

R6.4.3.3 The use of only 75% of the full factored live load for maximum moment loading patterns is based on the fact that maximum negative and maximum positive live load moments cannot occur simultaneously and that redistribution of maximum moments is thus possible before failure occurs. This procedure, in effect, permits some local over-stress under the full factored live load if it is distributed in the prescribed manner, but still ensures that the design strength of the slab system after redistribution of moment is not less than that required to resist the full factored dead and live loads on all panels.

R6.4.4 If large or closely-spaced embedments are created within slabs, maximum bending and shear stresses may occur near the void. In these cases, the designer should consider the effect of applying the live load to only a portion of the slab (example Fig. R6.4.4) to determine if localized bending and shear behavior controls the design. Effects of concentrated live loads should also be considered.




Fig. R6.4.4—Example of applying live load to a portion of the slab to calculate localized shear at the internal void

6.5—Simplified method of analysis for nonprestressed continuous beams and one-way slabs

6.5.1 It shall be permitted to calculate M_u and V_u due to gravity loads in accordance with this section for continuous beams and one-way slabs satisfying (a) through (e):

- (a) Members are prismatic
- (b) Loads are uniformly distributed
- (c) $L \leq 3D$
- (d) There are at least two spans
- (e) The longer of two adjacent spans does not exceed the shorter by more than 20%

R6.5—Simplified method of analysis for nonprestressed continuous beams and one-way slabs

CODE

6.5.2 M_u due to gravity loads shall be calculated in accordance with Table 6.5.2.

COMMENTARY

R6.5.2 The approximate moments and shears give reasonable values for the stated conditions if the continuous beams and one-way slabs are part of a frame or continuous construction. Because the load patterns that produce critical values for moments in columns of frames differ from those for maximum negative moments in beams, column moments should be evaluated separately.

Table 6.5.2—Approximate moments for nonprestressed continuous beams and one-way slabs

Moment	Location	Condition	M_u
Positive	End span	Discontinuous end integral with support	$w_u \ell_n^2/14$
		Discontinuous end unrestrained	$w_u \ell_n^2/11$
	Interior spans	All	$w_u \ell_n^2/16$
Negative ^[1]	Interior face of exterior support	Member built integrally with supporting spandrel beam	$w_u \ell_n^2/24$
		Member built integrally with supporting column	$w_u \ell_n^2/16$
	Exterior face of first interior support	Two spans	$w_u \ell_n^2/9$
		More than two spans	$w_u \ell_n^2/10$
	Face of other supports	All	$w_u \ell_n^2/11$
	Face of all supports satisfying (a) or (b)	(a) slabs with spans not exceeding 10 ft (b) beams where ratio of sum of column stiffnesses to beam stiffness exceeds 8 at each end of span	$w_u \ell_n^2/12$

^[1]To calculate negative moments, ℓ_n shall be the average of the adjacent clear span lengths.

6.5.3 Moments calculated in accordance with 6.5.2 shall not be redistributed.

6.5.4 V_u due to gravity loads shall be calculated in accordance with Table 6.5.4.

Table 6.5.4—Approximate shears for nonprestressed continuous beams and one-way slabs

Location	V_u
Exterior face of first interior support	$1.15w_u \ell_n/2$
Face of all other supports	$w_u \ell_n/2$

6.5.5 Floor or roof level moments shall be resisted by distributing the moment between columns immediately above and below the given floor in proportion to the relative column stiffnesses considering conditions of restraint.

6.6—Linear elastic first-order analysis

6.6.1 General

6.6.1.1 Slenderness effects shall be considered in accordance with 6.6.4, unless they are allowed to be neglected by 6.2.5.1.

R6.5.5 This section is provided to make certain that moments are included in column design. The moment refers to the difference between the end moments of the members framing into the column and exerted at the column centerline.

R6.6—Linear elastic first-order analysis

R6.6.1 General

R6.6.1.1 When using linear elastic first-order analysis, slenderness effects are calculated using the moment magnifier approach (MacGregor et al. 1970; MacGregor 1993; Ford et al. 1981).

CODE

6.6.1.2 Redistribution of moments calculated by an elastic first-order analysis shall be permitted in accordance with 6.6.5.

6.6.2 Modeling of members and structural systems

6.6.2.1 Floor or roof level moments shall be resisted by distributing the moment between columns immediately above and below the given floor in proportion to the relative column stiffnesses and considering conditions of restraint.

6.6.2.2 For frames or continuous construction, consideration shall be given to the effect of floor and roof load patterns on transfer of moment to exterior and interior columns, and of eccentric loading due to other causes.

6.6.2.3 It shall be permitted to simplify the analysis model by the assumptions of (a), (b), or both:

- (a) Solid slabs or one-way joist systems built integrally with supports, with clear spans not more than 10 ft, shall be permitted to be analyzed as continuous members on knife-edge supports with spans equal to the clear spans of the member and width of support beams otherwise neglected.
- (b) For frames or continuous construction, it shall be permitted to assume the intersecting member regions are rigid.

6.6.3 Section properties**6.6.3.1 Factored load analysis**

6.6.3.1.1 Moment of inertia and cross-sectional area of members shall be calculated in accordance with Tables 6.6.3.1.1(a) or 6.6.3.1.1(b), unless a more rigorous analysis is used. If sustained lateral loads are present, I for columns and walls shall be divided by $(1 + \beta_{ds})$, where β_{ds} is the ratio of maximum factored sustained shear within a story to the maximum factored shear in that story associated with the same load combination.

COMMENTARY

R6.6.2 Modeling of members and structural systems

R6.6.2.1 This section is provided to make certain that moments are included in column design if members have been proportioned using 6.5.1 and 6.5.2. The moment refers to the difference between the end moments of the members framing into the column and exerted at the column centerline.

R6.6.2.3 A common feature of modern frame analysis software is the assumption of rigid connections. Section 6.6.2.3(b) is intended to apply to intersecting elements in frames, such as beam-column joints.

R6.6.3 Section properties**R6.6.3.1 Factored load analysis**

R6.6.3.1.1 The values of I and A have been chosen from the results of frame tests and analyses, and include an allowance for the variability of the calculated deflections. The moments of inertia are taken from MacGregor and Hage (1977), which are multiplied by a stiffness reduction factor $\phi_K = 0.875$ (refer to R6.6.4.5.2). For example, the moment of inertia for columns is $0.875(0.80I_g) = 0.70I_g$.

The moment of inertia of T-beams should be based on the effective flange width defined in 6.3.2.1 or 6.3.2.2. It is generally sufficiently accurate to take I_g of a T-beam as $2I_g$ for the web, $2(b_w h^3/12)$.

If the factored moments and shears from an analysis based on the moment of inertia of a wall, taken equal to $0.70I_g$, indicate that the wall will crack in flexure, based on the modulus of rupture, the analysis should be repeated with $I = 0.35I_g$ in those stories where cracking is predicted using factored loads.

The values of the moments of inertia were derived for nonprestressed members. For prestressed members, the moments of inertia may differ depending on the amount, location, and type of reinforcement, and the degree of

CODE

COMMENTARY

cracking prior to reaching ultimate load. The stiffness values for prestressed concrete members should include an allowance for the variability of the stiffnesses.

Shear area A_{shear} is used to calculate shear deformations. A_{shear} depends on the shape of the gross cross section, the amount of concrete degradation the member has sustained, and is generally less than the gross cross-sectional area. For a rectangular cross section, $A_{shear} \leq 5/6 A_g$.

The equations in Table 6.6.3.1.1(b) provide more refined values of I considering axial load, eccentricity, reinforcement ratio, and concrete compressive strength as presented in [Khuntia and Ghosh \(2004a,b\)](#). The stiffnesses provided in these references are applicable for all levels of loading, including service and ultimate, and consider a stiffness reduction factor ϕ_K comparable to that for the moment of inertias included in Table 6.6.3.1.1(a). For use at load levels other than ultimate, P_u and M_u should be replaced with their appropriate values at the desired load level. For factored lateral load deflection analysis if inelastic behavior is expected, stiffnesses should be calculated according to 6.6.3.1.2.

Table 6.6.3.1.1(a)—Moments of inertia and cross-sectional areas permitted for elastic analysis at factored load level

Member and condition		Moment of inertia	Cross-sectional area for axial deformations	Cross-sectional area for shear deformations
Columns		$0.70I_g$	$1.0A_g$	$1.0A_{shear}$
Walls	Uncracked	$0.70I_g$		
	Cracked	$0.35I_g$		
Beams		$0.35I_g$		
Flat plates and flat slabs		$0.25I_g$		

Table 6.6.3.1.1(b)—Alternative moments of inertia for elastic analysis at factored load

Member	Alternative value of I for elastic analysis		
	Minimum	I	Maximum
Columns and walls	$0.35I_g$	$\left(0.80 + 25 \frac{A_{st}}{A_g}\right) \left(1 - \frac{M_u}{P_u h} - 0.5 \frac{P_u}{P_o}\right) I_g$	$0.875I_g$
Beams, flat plates, and flat slabs	$0.25I_g$	$(0.10 + 25\rho) \left(1.2 - 0.2 \frac{b_w}{d}\right) I_g$	$0.5I_g$

Notes: For continuous flexural members, I shall be permitted to be taken as the average of values obtained for the critical positive and negative moment sections. P_u and M_u shall be calculated from the load combination under consideration, or the combination of P_u and M_u that produces the least value of I .

6.6.3.1.2 For calculation of deflections under factored lateral loads, if inelastic response is expected, member effective stiffness shall be calculated in accordance with (a), (b), or (c) except for two-way slab systems without beams designated as part of the seismic-force-resisting system, where I for slab members shall be defined by a model that is in substantial agreement with results of comprehensive tests and analysis. For all cases, it shall be permitted to calculate cross-sectional area as indicated in Table 6.6.3.1.1(a).

- (a) Section properties defined in Table 6.6.3.1.1(a)
- (b) $I = 0.5I_g$ for all members
- (c) I by a more detailed analysis, considering the effective stiffness of all members under the loading conditions.

R6.6.3.1.2 The lateral deflection of a structure under factored lateral loads can be substantially different from that calculated using linear analysis, in part because of the inelastic response of the members and the decrease in effective stiffness. Selection of the appropriate effective stiffness for reinforced concrete frame members has dual purposes: 1) to provide realistic estimates of lateral deflection; and 2) to determine deflection-imposed actions on the gravity system of the structure. A detailed nonlinear analysis of the structure would adequately capture these two effects. A simple way to estimate an equivalent nonlinear lateral deflection using linear analysis is to reduce the modeled stiffness of the concrete members in the structure. The type of lateral

CODE

COMMENTARY

load analysis affects the selection of appropriate effective stiffness values. For analyses with wind loading, where it is desirable to prevent nonlinear action in the structure, effective stiffnesses representative of pre-yield behavior may be appropriate. For earthquake-induced loading, the level of nonlinear deformation depends on the intended structural performance and earthquake recurrence interval.

Varying degrees of confidence can be obtained from a simple linear analysis based on the computational rigor used to define the effective stiffness of each member. This stiffness can be based on the secant stiffness to a point at or beyond yield or, if yielding is not expected, to a point before yield occurs.

Options (a) and (b) use values that approximate the stiffness for reinforced concrete building systems loaded to near or beyond the yield level, and have been shown to produce reasonable correlation with both experimental and detailed analytical results (Moehle 1992; Lepage 1998). For earthquake-induced loading, the use of option (a) or (b) may require a deflection amplification factor to account for inelastic deformations. In general, for effective section properties, E_c may be calculated or specified in accordance with 19.2.2, the shear modulus may be taken as $0.4E_c$, and cross-sectional areas may be taken as given in Table 6.6.3.1.1(a).

Analysis of buildings with two-way slab systems without beams requires that the model represents the transfer of lateral loads between vertical members. The model should result in prediction of stiffness in substantial agreement with results of comprehensive tests and analysis. Several acceptable models have been proposed to accomplish this objective (Dovich and Wight 2005; Hwang and Moehle 2000; Vanderbilt and Corley 1983).

6.6.3.2 Service load analysis

6.6.3.2.1 Immediate and time-dependent deflections due to gravity loads shall be calculated in accordance with 24.2.

6.6.3.2.2 It shall be permitted to calculate immediate lateral deflections using a moment of inertia of 1.4 times I defined in 6.6.3.1.2, or using a more detailed analysis, but the value shall not exceed I_g .

R6.6.3.2 Service load analysis

R6.6.3.2.2 Analyses of deflections, vibrations, and building periods are needed at various service (unfactored) load levels (Grossman 1987, 1990) to determine the performance of the structure in service. The moments of inertia of the structural members in the service load analyses should be representative of the degree of cracking at the various service load levels investigated. Unless a more accurate estimate of the degree of cracking at service load level is available, it is satisfactory to use $1.0/0.70 = 1.4$ times the moments of inertia provided in 6.6.3.1, not to exceed I_g , for service load analyses. Serviceability considerations for vibrations are discussed in R24.1.

CODE

6.6.4 Slenderness effects, moment magnification method

6.6.4.1 Unless 6.2.5.1 is satisfied, columns and stories in structures shall be designated as being nonsway or sway. Analysis of columns in nonsway frames or stories shall be in accordance with 6.6.4.5. Analysis of columns in sway frames or stories shall be in accordance with 6.6.4.6.

6.6.4.2 The cross-sectional dimensions of each member used in an analysis shall be within 10% of the specified member dimensions in construction documents or the analysis shall be repeated. If the stiffnesses of Table 6.6.3.1.1(b) are used in an analysis, the assumed member reinforcement ratio shall also be within 10% of the specified member reinforcement in construction documents.

6.6.4.3 It shall be permitted to analyze columns and stories in structures as nonsway frames if (a) or (b) is satisfied:

- (a) The increase in column end moments due to second-order effects does not exceed 5% of the first-order end moments
- (b) Q in accordance with 6.6.4.4.1 does not exceed 0.05

COMMENTARY

R6.6.4 Slenderness effects, moment magnification method

R6.6.4.1 This section describes an approximate design procedure that uses the moment magnifier concept to account for slenderness effects. Moments calculated using a first-order frame analysis are multiplied by a moment magnifier that is a function of the factored axial load P_u and the critical buckling load P_c for the column. For the sway case, the moment magnifier is a function of the sum of P_u of the story and the sum of P_c of the sway-resisting columns in the story considered. Nonsway and sway frames are treated separately. A first-order frame analysis is an elastic analysis that excludes the internal force effects resulting from deflections.

The moment magnifier design method requires the designer to distinguish between nonsway frames, which are designed according to 6.6.4.5, and sway frames, which are designed according to 6.6.4.6. Frequently this can be done by comparing the total lateral stiffness of the columns in a story to that of the bracing elements. A compression member, such as a column, wall, or brace, may be assumed nonsway if it is located in a story in which the bracing elements (structural walls, shear trusses, or other types of lateral bracing) have such substantial lateral stiffness to resist the lateral deflections of the story that any resulting lateral deflection is not large enough to affect the column strength substantially. If not readily apparent without calculations, 6.6.4.3 provides two possible ways of determining if sway can be neglected.

R6.6.4.3 In 6.6.4.3(a), a story in a frame is classified as nonsway if the increase in the lateral load moments resulting from $P\Delta$ effects does not exceed 5% of the first-order moments (MacGregor and Hage 1977). Section 6.6.4.3(b) provides an alternative method of determining if a frame is classified as nonsway based on the stability index for a story, Q . In calculating Q , $\sum P_u$ should correspond to the lateral loading case for which $\sum P_u$ is greatest. A frame may contain both nonsway and sway stories.

If the lateral load deflections of the frame are calculated using service loads and the service load moments of inertia given in 6.6.3.2.2, it is permissible to calculate Q in Eq. (6.6.4.4.1) using 1.2 times the sum of the service gravity loads, the service load story shear, and 1.4 times the first-order service load story deflections.

CODE

6.6.4.4 Stability properties

6.6.4.4.1 The stability index for a story, Q , shall be calculated by:

$$Q = \frac{\sum P_u \Delta_o}{V_{us} \ell_c} \quad (6.6.4.4.1)$$

where $\sum P_u$ and V_{us} are the total factored vertical load and horizontal story shear, respectively, in the story being evaluated, and Δ_o is the first-order relative lateral deflection between the top and the bottom of that story due to V_{us} .

6.6.4.4.2 The critical buckling load P_c shall be calculated by:

$$P_c = \frac{\pi^2 (EI)_{eff}}{(k \ell_u)^2} \quad (6.6.4.4.2)$$

6.6.4.4.3 The effective length factor k shall be calculated using E_c in accordance with 19.2.2 and I in accordance with 6.6.3.1.1. For nonsway members, k shall be permitted to be taken as 1.0, and for sway members, k shall be at least 1.0.

6.6.4.4.4 For columns, $(EI)_{eff}$ shall be calculated in accordance with (a), (b), or (c):

$$(a) (EI)_{eff} = \frac{0.4 E_c I_g}{1 + \beta_{dns}} \quad (6.6.4.4.4a)$$

$$(b) (EI)_{eff} = \frac{(0.2 E_c I_g + E_s I_{se})}{1 + \beta_{dns}} \quad (6.6.4.4.4b)$$

$$(c) (EI)_{eff} = \frac{E_c I}{1 + \beta_{dns}} \quad (6.6.4.4.4c)$$

where β_{dns} shall be the ratio of maximum factored sustained axial load to maximum factored axial load associated with the same load combination and I in Eq. (6.6.4.4.4c) is calculated according to Table 6.6.3.1.1(b) for columns and walls.

COMMENTARY

R6.6.4.4 Stability properties

R6.6.4.4.2 In calculating the critical axial buckling load, the primary concern is the choice of a stiffness $(EI)_{eff}$ that reasonably approximates the variations in stiffness due to cracking, creep, and nonlinearity of the concrete stress-strain curve. Section 6.6.4.4.4 may be used to calculate $(EI)_{eff}$.

R6.6.4.4.3 The effective length factor for a compression member, such as a column, wall, or brace, considering braced behavior, ranges from 0.5 to 1.0. It is recommended that a k value of 1.0 be used. If lower values are used, the calculation of k should be based on analysis of the frame using I values given in 6.6.3.1.1. The Jackson and Moreland Alignment Charts (Fig. R6.2.5.1) can be used to estimate appropriate values of k (ACI SP-17(09); Column Research Council 1966).

R6.6.4.4.4 The numerators of Eq. (6.6.4.4.4a) to (6.6.4.4.4c) represent the short-term column stiffness. Equation (6.6.4.4.4b) was derived for small eccentricity ratios and high levels of axial load. Equation (6.6.4.4.4a) is a simplified approximation to Eq. (6.6.4.4.4b) and is less accurate (Mirza 1990). For improved accuracy, $(EI)_{eff}$ can be approximated using Eq. (6.6.4.4.4c).

Creep due to sustained loads will increase the lateral deflections of a column and, hence, the moment magnification. Creep effects are approximated in design by reducing the stiffness $(EI)_{eff}$ used to calculate P_c and, hence, δ , by dividing the short-term EI provided by the numerator of Eq. (6.6.4.4.4a) through (6.6.4.4.4c) by $(1 + \beta_{dns})$. For simplification, it can be assumed that $\beta_{dns} = 0.6$. In this case, Eq. (6.6.4.4.4a) becomes $(EI)_{eff} = 0.25 E_c I_g$.

In reinforced concrete columns subject to sustained loads, creep transfers some of the load from the concrete to the longitudinal reinforcement, increasing the reinforcement stresses. In the case of lightly reinforced columns, this load transfer may cause the compression reinforcement to yield prematurely, resulting in a loss in the effective EI . Accordingly, both the concrete and longitudinal reinforcement terms in Eq. (6.6.4.4.4b) are reduced to account for creep.

CODE

6.6.4.5 Moment magnification method: Nonsway frames

6.6.4.5.1 The factored moment used for design of columns and walls, M_c , shall be the first-order factored moment M_2 amplified for the effects of member curvature.

$$M_c = \delta M_2 \quad (6.6.4.5.1)$$

6.6.4.5.2 Magnification factor δ shall be calculated by:

$$\delta = \frac{C_m}{1 - \frac{P_u}{0.75P_c}} \geq 1.0 \quad (6.6.4.5.2)$$

6.6.4.5.3 C_m shall be in accordance with (a) or (b):

(a) For columns without transverse loads applied between supports

$$C_m = 0.6 - 0.4 \frac{M_1}{M_2} \quad (6.6.4.5.3a)$$

where M_1/M_2 is negative if the column is bent in single curvature, and positive if bent in double curvature. M_1 corresponds to the end moment with the lesser absolute value.

(b) For columns with transverse loads applied between supports.

$$C_m = 1.0 \quad (6.6.4.5.3b)$$

6.6.4.5.4 M_2 in Eq. (6.6.4.5.1) shall be at least $M_{2,min}$ calculated according to Eq. (6.6.4.5.4) about each axis separately.

$$M_{2,min} = P_u(0.6 + 0.03h) \quad (6.6.4.5.4)$$

If $M_{2,min}$ exceeds M_2 , C_m shall be taken equal to 1.0 or calculated based on the ratio of the calculated end moments M_1/M_2 , using Eq. (6.6.4.5.3a).

COMMENTARY

R6.6.4.5 Moment magnification method: Nonsway frames

R6.6.4.5.2 The 0.75 factor in Eq. (6.6.4.5.2) is the stiffness reduction factor ϕ_K , which is based on the probability of understrength of a single isolated slender column. Studies reported in [Mirza et al. \(1987\)](#) indicate that the stiffness reduction factor ϕ_K and the cross-sectional strength reduction ϕ factors do not have the same values. These studies suggest the stiffness reduction factor ϕ_K for an isolated column should be 0.75 for both tied and spiral columns. In the case of a multistory frame, the column and frame deflections depend on the average concrete strength, which is higher than the strength of the concrete in the critical single understrength column. For this reason, the value of ϕ_K implicit in I values in 6.6.3.1.1 is 0.875.

R6.6.4.5.3 The factor C_m is a correction factor relating the actual moment diagram to an equivalent uniform moment diagram. The derivation of the moment magnifier assumes that the maximum moment is at or near midheight of the column. If the maximum moment occurs at one end of the column, design should be based on an equivalent uniform moment $C_m M_2$ that leads to the same maximum moment at or near midheight of the column when magnified ([MacGregor et al. 1970](#)).

The sign convention for M_1/M_2 has been updated to follow the right hand rule convention; hence, M_1/M_2 is negative if bent in single curvature and positive if bent in double curvature. This reflects a sign convention change from the [2011 Code](#).

In the case of columns that are subjected to transverse loading between supports, it is possible that the maximum moment will occur at a section away from the end of the member. If this occurs, the value of the largest calculated moment occurring anywhere along the member should be used for the value of M_2 in Eq. (6.6.4.5.1). C_m is to be taken as 1.0 for this case.

R6.6.4.5.4 In the Code, slenderness is accounted for by magnifying the column end moments. If the factored column moments are small or zero, the design of slender columns should be based on the minimum eccentricity provided in Eq. (6.6.4.5.4). It is not intended that the minimum eccentricity be applied about both axes simultaneously.

The factored column end moments from the structural analysis are used in Eq. (6.6.4.5.3a) in determining the ratio M_1/M_2 for the column when the design is based on the minimum eccentricity. This eliminates what would

CODE

6.6.4.6 Moment magnification method: Sway frames

6.6.4.6.1 Moments M_1 and M_2 at the ends of an individual column shall be calculated by (a) and (b).

$$(a) M_1 = M_{1ns} + \delta_s M_{1s} \quad (6.6.4.6.1a)$$

$$(b) M_2 = M_{2ns} + \delta_s M_{2s} \quad (6.6.4.6.1b)$$

6.6.4.6.2 The moment magnifier δ_s shall be calculated by (a), (b), or (c). If δ_s exceeds 1.5, only (b) or (c) shall be permitted:

$$(a) \delta_s = \frac{1}{1-Q} \geq 1 \quad (6.6.4.6.2a)$$

$$(b) \delta_s = \frac{1}{1 - \frac{\sum P_u}{0.75 \sum P_c}} \geq 1 \quad (6.6.4.6.2b)$$

(c) Second-order elastic analysis

where $\sum P_u$ is the summation of all the factored vertical loads in a story and $\sum P_c$ is the summation for all sway-resisting columns in a story. P_c is calculated using Eq. (6.6.4.4.2) with k determined for sway members from 6.6.4.4.3 and $(EI)_{eff}$ from 6.6.4.4.4 with β_{ds} substituted for β_{dns} .

COMMENTARY

otherwise be a discontinuity between columns with calculated eccentricities less than the minimum eccentricity and columns with calculated eccentricities equal to or greater than the minimum eccentricity.

R6.6.4.6 Moment magnification method: Sway frames

R6.6.4.6.1 The analysis described in this section deals only with plane frames subjected to loads causing deflections in that plane. If the lateral load deflections involve significant torsional displacement, the moment magnification in the columns farthest from the center of twist may be underestimated by the moment magnifier procedure. In such cases, a three-dimensional second-order analysis should be used.

R6.6.4.6.2 Three different methods are allowed for calculating the moment magnifier. These approaches include the Q method, the sum of P concept, and second-order elastic analysis.

(a) Q method:

The iterative $P\Delta$ analysis for second-order moments can be represented by an infinite series. The solution of this series is given by Eq. (6.6.4.6.2a) (MacGregor and Hage 1977). Lai and MacGregor (1983) show that Eq. (6.6.4.6.2a) closely predicts the second-order moments in a sway frame until δ_s exceeds 1.5.

The $P\Delta$ moment diagrams for deflected columns are curved, with Δ related to the deflected shape of the columns. Equation (6.6.4.6.2a) and most commercially available second-order frame analyses have been derived assuming that the $P\Delta$ moments result from equal and opposite forces of $P\Delta/\ell_c$ applied at the bottom and top of the story. These forces give a straight-line $P\Delta$ moment diagram. The curved $P\Delta$ moment diagrams lead to lateral displacements on the order of 15% larger than those from the straight-line $P\Delta$ moment diagrams. This effect can be included in Eq. (6.6.4.6.2a) by writing the denominator as $(1 - 1.15Q)$ rather than $(1 - Q)$. The 1.15 factor has been omitted from Eq. (6.6.4.6.2a) for simplicity.

If deflections have been calculated using service loads, Q in Eq. (6.6.4.6.2a) should be calculated in the manner explained in R6.6.4.3.

The Q factor analysis is based on deflections calculated using the I values from 6.6.3.1.1, which include the equivalent of a stiffness reduction factor ϕ_K . These I values lead to a 20 to 25% over-estimation of the lateral deflections that corresponds to a stiffness reduction factor ϕ_K between 0.80 and 0.85 on the $P\Delta$ moments. As a result, no additional ϕ factor is needed. Once the moments are established using Eq. (6.6.4.6.2a), selection of the cross sections of the columns involves the strength reduction factors ϕ from 21.2.2.

(b) Sum of P concept:

CODE

COMMENTARY

6.6.4.6.3 Flexural members shall be designed for the total magnified end moments of the columns at the joint.

6.6.4.6.4 Second-order effects shall be considered along the length of columns in sway frames. It shall be permitted to account for these effects using 6.6.4.5, where C_m is calculated using M_1 and M_2 from 6.6.4.6.1.

6.6.5 *Redistribution of moments in continuous flexural members*

To check the effects of story stability, δ_s is calculated as an averaged value for the entire story based on use of $\sum P_u / \sum P_c$. This reflects the interaction of all sway-resisting columns in the story on the $P\Delta$ effects because the lateral deflection of all columns in the story should be equal in the absence of torsional displacements about a vertical axis. In addition, it is possible that a particularly slender individual column in a sway frame could have substantial midheight deflections, even if adequately braced against lateral end deflections by other columns in the story. Such a column is checked using 6.6.4.6.4.

The 0.75 in the denominator of Eq. (6.6.4.6.2b) is a stiffness reduction factor ϕ , as explained in R6.6.4.5.2.

In the calculation of $(EI)_{eff}$, β_{ds} will normally be zero for a sway frame because the lateral loads are generally of short duration. Sway deflections due to short-term loads, such as wind or earthquake, are a function of the short-term stiffness of the columns following a period of sustained gravity load.

For this case, the definition of β_{ds} in 6.6.3.1.1 gives $\beta_{ds} = 0$. In the unusual case of a sway frame where the lateral loads are sustained, β_{ds} will not be zero. This might occur if a building on a sloping site is subjected to earth pressure on one side but not on the other.

R6.6.4.6.3 The strength of a sway frame is governed by stability of the columns and the degree of end restraint provided by the beams in the frame. If plastic hinges form in the restraining beam, as the structure approaches a failure mechanism, its axial strength is drastically reduced. This section requires the restraining flexural members to have enough strength to resist the total magnified column end moments at the joint.

R6.6.4.6.4 The maximum moment in a compression member, such as a column, wall, or brace, may occur between its ends. While second-order computer analysis programs may be used to evaluate magnification of the end moments, magnification between the ends may not be accounted for unless the member is subdivided along its length. The magnification may be evaluated using the procedure outlined in 6.6.4.5.

R6.6.5 *Redistribution of moments in continuous flexural members*

Redistribution of moments is dependent on adequate ductility in plastic hinge regions. These plastic hinge regions develop at sections of maximum positive or negative moment and cause a shift in the elastic moment diagram. The usual result is a reduction in the values of maximum negative moments in the support regions and an increase in the values of positive moments between supports from those calculated by elastic analysis. However, because negative moments are typically determined for one loading arrange-

CODE

COMMENTARY

ment and positive moments for another (6.4.3 provides an exception for certain loading conditions), economies in reinforcement can sometimes be realized by reducing maximum elastic positive moments and increasing negative moments, thus narrowing the envelope of maximum negative and positive moments at any section in the span (Bondy 2003). Plastic hinges permit utilization of the full capacity of more cross sections of a flexural member at ultimate loads.

The Code permissible redistribution is shown in Fig. R6.6.5. Using conservative values of limiting concrete strains and lengths of plastic hinges derived from extensive tests, flexural members with small rotation capacities were analyzed for redistribution of moments up to 20%, depending on the reinforcement ratio. As shown, the permissible redistribution percentages are conservative relative to the calculated percentages available for both $f_y = 60$ ksi and 80 ksi. Studies by Cohn (1965) and Mattock (1959) support this conclusion and indicate that cracking and deflection of beams designed for redistribution of moments are not significantly greater at service loads than for beams designed by the distribution of moments according to elastic theory. Also, these studies indicate that adequate rotational capacity for the redistribution of moments allowed by the Code is available if the members satisfy 6.6.5.1. The provisions for redistribution of moments apply equally to prestressed members (Mast 1992). The elastic deformations caused by a nonconcordant tendon change the amount of inelastic rotation required to obtain a given amount of redistribution of moments. Conversely, for a beam with a given inelastic rotational capacity, the amount by which the moment at the support may be varied is changed by an amount equal to the secondary moment at the support due to prestressing. Thus, the Code requires that secondary moments caused by reactions generated by prestressing forces be included in determining design moments. Redistribution of moments as permitted by 6.6.5 is not appropriate where approximate values of bending moments are used, such as provided by the simplified method of 6.5. Redistribution of moments is also not appropriate for two-way slab systems that are analyzed using the pattern loadings given in 6.4.3.3. These loadings use only 75% of the full factored live load, which is based on considerations of moment redistribution.

CODE

COMMENTARY




Fig. R6.6.5—Permissible redistribution of moments for minimum rotation capacity.

6.6.5.1 Except where approximate values for moments are used in accordance with 6.5, where moments have been calculated in accordance with 6.8, or where moments in two-way slabs are determined using pattern loading specified in 6.4.3.3, reduction of moments at sections of maximum negative or maximum positive moment calculated by elastic theory shall be permitted for any assumed loading arrangement if (a) and (b) are satisfied:

- (a) Flexural members are continuous
- (b) $\epsilon_t \geq 0.0075$ at the section at which moment is reduced

6.6.5.2 For prestressed members, moments include those due to factored loads and those due to reactions induced by prestressing.

6.6.5.3 At the section where the moment is reduced, redistribution shall not exceed the lesser of $1000\epsilon_t$ percent and 20%.

6.6.5.4 The reduced moment shall be used to calculate redistributed moments at all other sections within the spans such that static equilibrium is maintained after redistribution of moments for each loading arrangement.

6.6.5.5 Shears and support reactions shall be calculated in accordance with static equilibrium considering the redistributed moments for each loading arrangement

CODE

6.7—Linear elastic second-order analysis**6.7.1 General**

6.7.1.1 A linear elastic second-order analysis shall consider the influence of axial loads, presence of cracked regions along the length of the member, and effects of load duration. These considerations are satisfied using the cross-sectional properties defined in 6.7.2.

6.7.1.2 Slenderness effects along the length of a column shall be considered. It shall be permitted to calculate these effects using 6.6.4.5

6.7.1.3 The cross-sectional dimensions of each member used in an analysis to calculate slenderness effects shall be within 10% of the specified member dimensions in construction documents or the analysis shall be repeated.

6.7.1.4 Redistribution of moments calculated by an elastic second-order analysis shall be permitted in accordance with 6.6.5.

COMMENTARY

R6.7—Linear elastic second-order analysis**R6.7.1 General**

In linear elastic second-order analyses, the deformed geometry of the structure is included in the equations of equilibrium so that $P\Delta$ effects are determined. The structure is assumed to remain elastic, but the effects of cracking and creep are considered by using an effective stiffness EI . In contrast, linear elastic first-order analysis satisfies the equations of equilibrium using the original undeformed geometry of the structure and estimates $P\Delta$ effects by magnifying the column-end sway moments using Eq. (6.6.4.6.2a) or (6.6.4.6.2b).

R6.7.1.1 The stiffnesses EI used in an analysis for strength design should represent the stiffnesses of the members immediately prior to failure. This is particularly true for a second-order analysis that should predict the lateral deflections at loads approaching ultimate. The EI values should not be based solely on the moment-curvature relationship for the most highly loaded section along the length of each member. Instead, they should correspond to the moment-end rotation relationship for a complete member.

To allow for variability in the actual member properties in the analysis, the member properties used in analysis should be multiplied by a stiffness reduction factor ϕ_K less than 1. The cross-sectional properties defined in 6.7.2 already include this stiffness reduction factor. The stiffness reduction factor ϕ_K may be taken as 0.875. Note that the overall stiffness is further reduced considering that the modulus of elasticity of the concrete, E_c , is based on the specified concrete compressive strength, while the sway deflections are a function of the average concrete strength, which is typically higher.

R6.7.1.2 The maximum moment in a compression member may occur between its ends. In computer analysis programs, columns may be subdivided using nodes along their length to evaluate slenderness effects between the ends. If the column is not subdivided along its length, slenderness effects may be evaluated using the nonsway moment magnifier method specified in 6.6.4.5 with member-end moments from the second-order elastic analysis as input. Second-order analysis already accounts for the relative displacement of member ends.

CODE**6.7.2 Section properties****6.7.2.1 Factored load analysis**

6.7.2.1.1 It shall be permitted to use section properties calculated in accordance with 6.6.3.1.

6.7.2.2 Service load analysis

6.7.2.2.1 Immediate and time-dependent deflections due to gravity loads shall be calculated in accordance with 24.2.

6.7.2.2.2 Alternatively, it shall be permitted to calculate immediate deflections using a moment of inertia of 1.4 times I given in 6.6.3.1, or calculated using a more detailed analysis, but the value shall not exceed I_g .

6.8—Inelastic analysis**6.8.1 General**

6.8.1.1 An inelastic analysis shall consider material nonlinearity. An inelastic first-order analysis shall satisfy equilibrium in the undeformed configuration. An inelastic second-order analysis shall satisfy equilibrium in the deformed configuration.

6.8.1.2 An inelastic analysis procedure shall have been shown to result in calculation of strength and deformations that are in substantial agreement with results of physical tests of reinforced concrete components, subassemblages, or structural systems exhibiting response mechanisms consistent with those expected in the structure being designed.

6.8.1.3 Unless slenderness effects are permitted to be neglected in accordance with 6.2.5.1, an inelastic analysis shall satisfy equilibrium in the deformed configuration. It shall be permitted to calculate slenderness effects along the length of a column using 6.6.4.5.

COMMENTARY**R6.7.2 Section properties****R6.7.2.2 Service load analysis**

R6.7.2.2.2 Refer to R6.6.3.2.2.

R6.8—Inelastic analysis**R6.8.1 General**

R6.8.1.1 Material nonlinearity may be affected by multiple factors including duration of loads, shrinkage, and creep.

R6.8.1.2 Substantial agreement should be demonstrated at characteristic points on the reported response. The characteristic points selected should depend on the purpose of the analysis, the applied loads, and the response phenomena exhibited by the component, subassemblage, or structural system. For nonlinear analysis to support design under service-level loading, characteristic points should represent loads and deformations less than those corresponding to yielding of reinforcement. For nonlinear analysis to support design or assess response under design-level loading, characteristic points should represent loads and deformations less than those corresponding to yielding of reinforcement as well as points corresponding to yielding of reinforcement and onset of strength loss. Strength loss need not be represented if design loading does not extend the response into the strength-loss range. Typically, inelastic analysis to support design should employ specified material strengths and mean values of other material properties and component stiffnesses. Nonlinear response history analysis to verify the design of earthquake-resistant concrete structures should employ expected material strengths, expected material properties, and expected component stiffnesses, as specified in A.6.2.

R6.8.1.3 Refer to R6.7.1.2.

CODE

6.8.1.4 The cross-sectional dimensions of each member used in an analysis to calculate slenderness effects shall be within 10% of the specified member dimensions in construction documents or the analysis shall be repeated.

6.8.1.5 Redistribution of moments calculated by an inelastic analysis shall not be permitted.

6.9—Acceptability of finite element analysis

6.9.1 Finite element analysis to determine load effects shall be permitted.

6.9.2 The finite element model shall be appropriate for its intended purpose.

6.9.3 For inelastic analysis, a separate analysis shall be performed for each factored load combination.

6.9.4 The licensed design professional shall confirm that the results are appropriate for the purposes of the analysis.

6.9.5 The cross-sectional dimensions of each member used in an analysis shall be within 10% of the specified member dimensions in construction documents or the analysis shall be repeated.

6.9.6 Redistribution of moments calculated by an inelastic analysis shall not be permitted.

COMMENTARY

R6.8.1.5 Section 6.6.5 allows for redistribution of moments calculated using elastic analysis to account for inelastic response of the system. Moments calculated by inelastic analysis explicitly account for inelastic response; therefore, further redistribution of moments is not appropriate.

R6.9—Acceptability of finite element analysis

R6.9.2 The element types used should be capable of representing the response required. The model mesh size selected should be capable of determining the structural response in sufficient detail. The use of any set of reasonable assumptions for member stiffness is allowed.

R6.9.3 For an inelastic finite element analysis, the rules of linear superposition do not apply. To determine the ultimate member inelastic response, for example, it is not correct to analyze for service loads and subsequently combine the results linearly using load factors. A separate inelastic analysis should be performed for each factored load combination.

Notes



CHAPTER 7—ONE-WAY SLABS

CODE

COMMENTARY

7.1—Scope

7.1.1 This chapter shall apply to the design of nonprestressed and prestressed slabs reinforced for flexure in one direction, including:

- (a) Solid slabs
- (b) Slabs cast on stay-in-place, noncomposite steel deck
- (c) Composite slabs of concrete elements constructed in separate placements but connected so that all elements resist loads as a unit
- (d) Precast, prestressed hollow-core slabs

7.2—General

7.2.1 The effects of concentrated loads, slab openings, and voids within the slab shall be considered in design.

7.2.2 Materials

7.2.2.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

7.2.2.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

7.2.2.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

7.2.3 Connection to other members

7.2.3.1 For cast-in-place construction, joints shall satisfy **Chapter 15**.

7.2.3.2 For precast construction, connections shall satisfy the force transfer requirements of **16.2**.

7.3—Design limits**7.3.1 Minimum slab thickness**

7.3.1.1 For solid nonprestressed slabs not supporting or attached to partitions or other construction likely to be damaged by large deflections, overall slab thickness h shall not be less than the limits in Table 7.3.1.1, unless the calculated deflection limits of 7.3.2 are satisfied.

R7.1—Scope

R7.1.1 Design and construction of composite concrete slabs on steel deck is described in “Standard for Steel Deck” (**SD**).

Provisions for one-way joist systems are provided in **Chapter 9**.

R7.2—General

R7.2.1 Concentrated loads and slab openings create local moments and shears and may cause regions of one-way slabs to have two-way behavior. One-way slabs with concentrated loading may be susceptible to two-way punching shear failure and localized flexural yielding around the loaded area. The influence of openings through the slab and voids within the slab (for example, those created for ducts) and development of additional critical sections for flexural and shear strengths, as well as deflections, are to be considered.

R7.3—Design limits**R7.3.1 Minimum slab thickness**

R7.3.1.1 The basis for minimum thickness for one-way slabs is the same as that for beams. Refer to **R9.3.1** for additional information.

CODE

COMMENTARY

Table 7.3.1.1—Minimum thickness of solid nonprestressed one-way slabs

Support condition	Minimum $h^{[1]}$
Simply supported	$\ell/20$
One end continuous	$\ell/24$
Both ends continuous	$\ell/28$
Cantilever	$\ell/10$

^[1]Expression applicable for normalweight concrete and $f_y = 60,000$ psi. For other cases, minimum h shall be modified in accordance with 7.3.1.1.1 through 7.3.1.1.3, as appropriate.

7.3.1.1.1 For f_y other than 60,000 psi, the expressions in Table 7.3.1.1 shall be multiplied by $(0.4 + f_y/100,000)$.

7.3.1.1.2 For nonprestressed slabs made of lightweight concrete having w_c in the range of 90 to 115 lb/ft³, the expressions in Table 7.3.1.1 shall be multiplied by the greater of (a) and (b):

- (a) $1.65 - 0.005w_c$
- (b) 1.09

7.3.1.1.3 For nonprestressed composite concrete slabs made of a combination of lightweight and normalweight concrete, shored during construction, and where the lightweight concrete is in compression, the modifier of 7.3.1.1.2 shall apply.

7.3.1.2 The thickness of a concrete floor finish shall be permitted to be included in h if it is placed monolithically with the floor slab or if the floor finish is designed to be composite with the floor slab in accordance with 16.4.

7.3.2 Calculated deflection limits

7.3.2.1 For nonprestressed slabs not satisfying 7.3.1 and for prestressed slabs, immediate and time-dependent deflections shall be calculated in accordance with 24.2 and shall not exceed the limits in 24.2.2.

7.3.2.2 For nonprestressed composite concrete slabs satisfying 7.3.1, deflections occurring after the member becomes composite need not be calculated. Deflections occurring before the member becomes composite shall be investigated, unless the precomposite thickness also satisfies 7.3.1.

7.3.3 Reinforcement strain limit in nonprestressed slabs

7.3.3.1 Nonprestressed slabs shall be tension-controlled in accordance with Table 21.2.2.

R7.3.2 Calculated deflection limits

R7.3.2.1 The basis for calculated deflections for one-way slabs is the same as that for beams. Refer to R9.3.2 for additional information.

R7.3.3 Reinforcement strain limit in nonprestressed slabs

R7.3.3.1 The basis for a reinforcement strain limit for one-way slabs is the same as that for beams. Refer to R9.3.3 for additional information.

CODE

COMMENTARY

7.3.4 Stress limits in prestressed slabs

7.3.4.1 Prestressed slabs shall be classified as Class U, T, or C in accordance with **24.5.2**.

7.3.4.2 Stresses in prestressed slabs immediately after transfer and at service loads shall not exceed the permissible stresses in **24.5.3** and **24.5.4**.

7.4—Required strength**7.4.1 General**

7.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in **Chapter 5**.

7.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in **Chapter 6**.

7.4.1.3 For prestressed slabs, effects of reactions induced by prestressing shall be considered in accordance with **5.3.14**.

7.4.2 Factored moment

7.4.2.1 For slabs built integrally with supports, M_u at the support shall be permitted to be calculated at the face of support.

7.4.3 Factored shear

7.4.3.1 For slabs built integrally with supports, V_u at the support shall be permitted to be calculated at the face of support.

7.4.3.2 Sections between the face of support and a critical section located d from the face of support for nonprestressed slabs or $h/2$ from the face of support for prestressed slabs shall be permitted to be designed for V_u at that critical section if (a) through (c) are satisfied:

- (a) Support reaction, in direction of applied shear, introduces compression into the end region of the slab
- (b) Loads are applied at or near the top surface of the slab
- (c) No concentrated load occurs between the face of support and critical section

7.5—Design strength**7.5.1 General**

7.5.1.1 For each applicable factored load combination, design strength at all sections shall satisfy $\phi S_n \geq U$ including (a) and (b). Interaction between load effects shall be considered.

- (a) $\phi M_n \geq M_u$

R7.4—Required strength**R7.4.3 Factored shear**

R7.4.3.2 Requirements for the selection of the critical section for shear in one-way slabs are the same as those for beams. Refer to **R9.4.3.2** for additional information.

R7.5—Design strength**R7.5.1 General**

R7.5.1.1 Refer to **R9.5.1.1**.

CODE

(b) $\phi V_n \geq V_u$

7.5.1.2 ϕ shall be determined in accordance with 21.2.

7.5.2 Moment

7.5.2.1 M_n shall be calculated in accordance with 22.3.

7.5.2.2 For prestressed slabs, external tendons shall be considered as unbonded tendons in calculating flexural strength, unless the external tendons are effectively bonded to the concrete section along the entire length.

7.5.2.3 If primary flexural reinforcement in a slab that is considered to be a T-beam flange is parallel to the longitudinal axis of the beam, reinforcement perpendicular to the longitudinal axis of the beam shall be provided in the top of the slab in accordance with (a) and (b). This provision does not apply to joist construction.

(a) Slab reinforcement perpendicular to the beam shall be designed to resist the factored load on the overhanging slab width assumed to act as a cantilever.

(b) Only the effective overhanging slab width in accordance with 6.3.2 need be considered.

7.5.3 Shear

7.5.3.1 V_n shall be calculated in accordance with 22.5.

7.5.3.2 For composite concrete slabs, horizontal shear strength V_{nh} shall be calculated in accordance with 16.4.

7.6—Reinforcement limits

7.6.1 Minimum flexural reinforcement in nonprestressed slabs

7.6.1.1 A minimum area of flexural reinforcement, $A_{s,min}$, of $0.0018A_g$ shall be provided.

7.6.2 Minimum flexural reinforcement in prestressed slabs

7.6.2.1 For slabs with bonded prestressed reinforcement, total quantity of A_s and A_{ps} shall be adequate to develop a factored load at least 1.2 times the cracking load calculated on the basis of f_r as given in 19.2.3.

COMMENTARY

R7.5.2 Moment

R7.5.2.3 This provision applies only where a T-beam is parallel to the span of a one-way slab. Such a beam might be used to support a wall or concentrated load that the slab alone cannot support. Reinforcement required by this provision is intended to consider “unintended” negative moments that may develop over the beam that exceed requirements for temperature and shrinkage reinforcement alone.

R7.6—Reinforcement limits

R7.6.1 Minimum flexural reinforcement in nonprestressed slabs

R7.6.1.1 Required area of deformed or welded wire reinforcement used as minimum flexural reinforcement is the same as provided for shrinkage and temperature in 24.4.3.2. However, whereas shrinkage and temperature reinforcement is permitted to be distributed between the two faces of the slab as deemed appropriate for specific conditions, minimum flexural reinforcement should be placed as close as practicable to the face of the concrete in tension due to applied loads.

R7.6.2 Minimum flexural reinforcement in prestressed slabs

R7.6.2.1 The minimum flexural reinforcement for prestressed one-way slabs is the same as the minimum for prestressed beams. Refer to R9.6.2 for additional information.

CODE

7.6.2.2 For slabs with both flexural and shear design strength at least twice the required strength, 7.6.2.1 need not be satisfied.

7.6.2.3 For slabs with unbonded tendons, the minimum area of bonded deformed longitudinal reinforcement, $A_{s,min}$, shall be:

$$A_{s,min} \geq 0.004A_{ct} \quad (7.6.2.3)$$

where A_{ct} is the area of that part of the cross section between the flexural tension face and the centroid of the gross section.

7.6.3 Minimum shear reinforcement

7.6.3.1 A minimum area of shear reinforcement, $A_{v,min}$, shall be provided in all regions where $V_u > \phi V_c$. For precast prestressed hollow-core slabs with untopped $h > 12.5$ in., $A_{v,min}$ shall be provided in all regions where $V_u > 0.5\phi V_{cw}$.

7.6.3.2 If shown by testing that the required M_n and V_n can be developed, 7.6.3.1 need not be satisfied. Such tests shall simulate effects of differential settlement, creep, shrinkage, and temperature change, based on a realistic assessment of these effects occurring in service.

7.6.3.3 If shear reinforcement is required, $A_{v,min}$ shall be in accordance with 9.6.3.4.

7.6.4 Minimum shrinkage and temperature reinforcement

7.6.4.1 Reinforcement shall be provided to resist shrinkage and temperature stresses in accordance with 24.4.

7.6.4.2 If prestressed shrinkage and temperature reinforcement in accordance with 24.4.4 is used, 7.6.4.2.1 through 7.6.4.2.3 shall apply.

COMMENTARY

R7.6.3 Minimum shear reinforcement

R7.6.3.1 The basis for minimum shear reinforcement for one-way slabs is the same as that for beams. Refer to R9.6.3 for additional information.

The ratio V_u/V_c at which minimum shear reinforcement is required is generally greater for solid slabs and footings than for beams because, in solid slabs and footings, there is a possibility of load sharing.

Results of tests on precast, prestressed hollow-core units (Becker and Buettner 1985; Anderson 1978) with $h \leq 12.5$ in. have shown shear strengths greater than those calculated by Eq. (22.5.6.2.1a) and Eq. (22.5.6.2.2). Results of tests on hollow-core units with $h > 12.5$ in. have shown that web-shear strengths in end regions can be less than strengths calculated by Eq. (22.5.6.2.2) (Hawkins and Ghosh 2006). In contrast, the test results indicated that flexure-shear strengths in the deeper hollow-core units equaled or exceeded strengths calculated by Eq. (22.5.6.2.1a).

R7.6.3.2 The basis for the testing-based strength evaluation for one-way slabs is the same as that for beams. Refer to R9.6.3.3 for additional information.

R7.6.4 Minimum shrinkage and temperature reinforcement

R7.6.4.2 In prestressed monolithic beam-and-slab construction, at least one shrinkage and temperature tendon is required between beams, even if the beam tendons alone provide at least 100 psi average compressive stress as required by 24.4.4.1 on the gross concrete area as defined in 7.6.4.2.1. A tendon of any size is permissible as long as all other requirements of 7.6.4.2 and 7.7.6.3 are satisfied. Appli-

CODE**COMMENTARY**

cation of the provisions of 7.6.4.2 and 7.7.6.3 to monolithic, cast-in-place, post-tensioned, beam-and-slab construction is illustrated in Fig. R7.6.4.2.

Tendons used for shrinkage and temperature reinforcement should be positioned as close as practicable to the mid-depth of the slab. In cases where the shrinkage and temperature tendons are used for supporting the principal tendons, variations from the slab centroid are permissible; however, the centroid of the shrinkage and temperature tendons should not fall outside the middle third of the slab thickness.

The effects of slab shortening should be evaluated to ensure the effectiveness of the prestressing. In most cases, the low level of prestressing recommended should not cause difficulties in a properly detailed structure. Additional attention may be required where thermal effects become significant.




Fig. R7.6.4.2—Section through beams cast monolithically with slab.

7.6.4.2.1 For monolithic, cast-in-place, post-tensioned beam-and-slab construction, gross concrete area shall consist of the total beam area including the slab thickness and the slab area within half the clear distance to adjacent

CODE

beam webs. It shall be permitted to include the effective force in beam tendons in the calculation of total prestress force acting on gross concrete area.

7.6.4.2.2 If slabs are supported on walls or not cast monolithically with beams, gross concrete area is the slab section tributary to the tendon or tendon group.

7.6.4.2.3 At least one tendon is required in the slab between faces of adjacent beams or walls.

7.7—Reinforcement detailing**7.7.1 General**

7.7.1.1 Concrete cover for reinforcement shall be in accordance with **20.5.1**.

7.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with **25.4**.

7.7.1.3 Splices of deformed reinforcement shall be in accordance with **25.5**.

7.7.1.4 Bundled bars shall be in accordance with **25.6**.

7.7.2 Reinforcement spacing

7.7.2.1 Minimum spacings shall be in accordance with **25.2**.

7.7.2.2 For nonprestressed and Class C prestressed slabs, spacing of bonded longitudinal reinforcement closest to the tension face shall not exceed s given in **24.3**.

7.7.2.3 For nonprestressed and Class T and C prestressed slabs with unbonded tendons, maximum spacing s of deformed longitudinal reinforcement shall be the lesser of $3h$ and 18 in.

7.7.2.4 Maximum spacing, s , of reinforcement required by **7.5.2.3** shall be the lesser of $5h$ and 18 in.

7.7.3 Flexural reinforcement in nonprestressed slabs

7.7.3.1 Calculated tensile or compressive force in reinforcement at each section of the slab shall be developed on each side of that section.

7.7.3.2 Critical locations for development of reinforcement are points of maximum stress and points along the span where bent or terminated tension reinforcement is no longer required to resist flexure.

COMMENTARY**R7.7—Reinforcement detailing****R7.7.2 Reinforcement spacing**

R7.7.2.3 Class T and C slabs prestressed with unbonded tendons rely solely on deformed reinforcement for crack control. Consequently, the requirements of **7.7.2.3** apply to Class T and C slabs prestressed with unbonded tendons.

R7.7.2.4 Spacing limitations for slab reinforcement are based on flange thickness, which for tapered flanges can be taken as the average thickness.

R7.7.3 Flexural reinforcement in nonprestressed slabs

R7.7.3.1 Requirements for development of reinforcement in one-way slabs are similar to those for beams. Refer to **R9.7.3** for additional information.

CODE

COMMENTARY

7.7.3.3 Reinforcement shall extend beyond the point at which it is no longer required to resist flexure for a distance at least the greater of d and $12d_b$, except at supports of simply-supported spans and at free ends of cantilevers.

7.7.3.4 Continuing flexural tension reinforcement shall have an embedment length at least ℓ_d beyond the point where bent or terminated tension reinforcement is no longer required to resist flexure.

7.7.3.5 Flexural tension reinforcement shall not be terminated in a tension zone unless (a), (b), or (c) is satisfied:

- (a) $V_u \leq (2/3)\phi V_n$ at the cutoff point.
- (b) For No. 11 bars and smaller, continuing reinforcement provides double the area required for flexure at the cutoff point and $V_u \leq (3/4)\phi V_n$.
- (c) Stirrup area in excess of that required for shear is provided along each terminated bar or wire over a distance $3/4d$ from the cutoff point. Excess stirrup area shall be not less than $60b_w s / f_{yt}$. Spacing s shall not exceed $d / (8\beta_b)$.

7.7.3.6 Adequate anchorage shall be provided for tension reinforcement where reinforcement stress is not directly proportional to moment, such as in sloped, stepped, or tapered slabs, or where tension reinforcement is not parallel to the compression face.

7.7.3.7 In slabs with spans not exceeding 10 ft, welded wire reinforcement, with wire size not exceeding W5 or D5, shall be permitted to be curved from a point near the top of slab over the support to a point near the bottom of slab at midspan, provided such reinforcement is continuous over, or developed at, the support.

7.7.3.8 Termination of reinforcement

7.7.3.8.1 At simple supports, at least one-third of the maximum positive moment reinforcement shall extend along the slab bottom into the support, except for precast slabs where such reinforcement shall extend at least to the center of the bearing length.

7.7.3.8.2 At other supports, at least one-fourth of the maximum positive moment reinforcement shall extend along the slab bottom into the support at least 6 in.

7.7.3.8.3 At simple supports and points of inflection, d_b for positive moment tension reinforcement shall be limited such that ℓ_d for that reinforcement satisfies (a) or (b). If reinforcement terminates beyond the centerline of supports by a standard hook or a mechanical anchorage at least equivalent to a standard hook, (a) or (b) need not be satisfied.

R7.7.3.8 Termination of reinforcement

R7.7.3.8.1 Requirements for termination of reinforcement in one-way slabs are similar to those for beams. Refer to **R9.7.3.8** for additional information.

CODE

- (a) $\ell_d \leq (1.3M_n/V_u + \ell_a)$ if end of reinforcement is confined by a compressive reaction
 (b) $\ell_d \leq (M_n/V_u + \ell_a)$ if end of reinforcement is not confined by a compressive reaction

M_n is calculated assuming all reinforcement at the section is stressed to f_y and V_u is calculated at the section. At a support, ℓ_a is the embedment length beyond the center of the support. At a point of inflection, ℓ_a is the embedment length beyond the point of inflection, limited to the greater of d and $12d_b$.

7.7.3.8.4 At least one-third of the negative moment reinforcement at a support shall have an embedment length beyond the point of inflection at least the greatest of d , $12d_b$, and $\ell_n/16$.

7.7.4 Flexural reinforcement in prestressed slabs

7.7.4.1 External tendons shall be attached to the member in a manner that maintains the specified eccentricity between the tendons and the concrete centroid through the full range of anticipated member deflections.

7.7.4.2 If nonprestressed reinforcement is required to satisfy flexural strength, the detailing requirements of 7.7.3 shall be satisfied.

7.7.4.3 Termination of prestressed reinforcement

7.7.4.3.1 Post-tensioned anchorage zones shall be designed and detailed in accordance with 25.9.

7.7.4.3.2 Post-tensioning anchorages and couplers shall be designed and detailed in accordance with 25.8.

7.7.4.4 Termination of deformed reinforcement in slabs with unbonded tendons

7.7.4.4.1 Length of deformed reinforcement required by 7.6.2.3 shall be in accordance with (a) and (b):

- (a) At least $\ell_n/3$ in positive moment areas and be centered in those areas
 (b) At least $\ell_n/6$ on each side of the face of support

7.7.5 Shear reinforcement

7.7.5.1 If shear reinforcement is required, transverse reinforcement shall be detailed according to 9.7.6.2.

7.7.6 Shrinkage and temperature reinforcement**COMMENTARY****R7.7.4 Flexural reinforcement in prestressed slabs****R7.7.4.4 Termination of deformed reinforcement in slabs with unbonded tendons**

R7.7.4.4.1 Requirements for termination of deformed reinforcement in one-way slabs with unbonded tendons are the same as those for beams. Refer to R9.7.4.4 for additional information.

R7.7.6 Shrinkage and temperature reinforcement

CODE

7.7.6.1 Shrinkage and temperature reinforcement in accordance with 7.6.4 shall be placed perpendicular to flexural reinforcement.

7.7.6.2 *Nonprestressed reinforcement*

7.7.6.2.1 Spacing of deformed shrinkage and temperature reinforcement shall not exceed the lesser of $5h$ and 18 in.

7.7.6.3 *Prestressed reinforcement*

7.7.6.3.1 Spacing of slab tendons required by 7.6.4.2 and the distance between face of beam or wall to the nearest slab tendon shall not exceed 6 ft.

7.7.6.3.2 If spacing of slab tendons exceeds 4.5 ft, additional deformed shrinkage and temperature reinforcement conforming to 24.4.3 shall be provided parallel to the tendons, except 24.4.3.4 need not be satisfied. In calculating the area of additional reinforcement, it shall be permitted to take the gross concrete area in 24.4.3.2 as the slab area between faces of beams. This shrinkage and temperature reinforcement shall extend from the slab edge for a distance not less than the slab tendon spacing.

COMMENTARY

R7.7.6.3 *Prestressed reinforcement*

R7.7.6.3.2 Widely spaced tendons result in non-uniform compressive stresses near slab edges. Additional deformed reinforcement is used to reinforce regions near the slab edge that may be inadequately compressed. Placement of this reinforcement is illustrated in Fig. R7.7.6.3.2.




Fig. R7.7.6.3.2—Plan view at slab edge showing added shrinkage and temperature deformed reinforcement.

CODE**7.7.7** *Structural integrity reinforcement in cast-in-place one-way slabs*

7.7.7.1 Longitudinal structural integrity reinforcement consisting of at least one-fourth of the maximum positive moment reinforcement shall be continuous.

7.7.7.2 Longitudinal structural integrity reinforcement at noncontinuous supports shall be developed in tension in accordance with **25.4** by substituting a bar stress of $1.25f_y$ for f_y at the face of the support.

7.7.7.3 If splices are necessary in continuous structural integrity reinforcement, the reinforcement shall be spliced near supports. Splices shall be mechanical or welded in accordance with **25.5.7** or Class B tension lap splices in accordance with **25.5.2**.

COMMENTARY**R7.7.7** *Structural integrity reinforcement in cast-in-place one-way slabs*

R7.7.7.1 Positive moment structural integrity reinforcement for one-way slabs is intended to be similar to that for beams. Refer to **R9.7.7** for a discussion of structural integrity reinforcement for beams.



Notes



CHAPTER 8—TWO-WAY SLABS

CODE

COMMENTARY

8.1—Scope

8.1.1 This chapter shall apply to the design of nonprestressed and prestressed slabs reinforced for flexure in two directions, with or without beams between supports, including (a) through (d):

- (a) Solid slabs
- (b) Slabs cast on stay-in-place, noncomposite steel deck
- (c) Composite slabs of concrete elements constructed in separate placements but connected so that all elements resist loads as a unit
- (d) Two-way joist systems in accordance with 8.8

8.2—General

8.2.1 A slab system shall be permitted to be designed by any procedure satisfying equilibrium and geometric compatibility, provided that design strength at every section is at least equal to required strength, and all serviceability requirements are satisfied. The direct design method or the equivalent frame method is permitted.

8.2.2 The effects of concentrated loads, slab openings, and slab voids shall be considered in design.

8.2.3 Slabs prestressed with an average effective compressive stress less than 125 psi shall be designed as nonprestressed slabs.

R8.1—Scope

R8.1.1 The design methods given in this chapter are based on analysis of results of an extensive series of tests (Burns and Hemakom 1977; Gamble et al. 1969; Gerber and Burns 1971; Guralnick and LaFraugh 1963; Hatcher et al. 1965, 1969; Hawkins 1981; Jirsa et al. 1966; PTI DC20.8; Smith and Burns 1974; Scordelis et al. 1959; Vanderbilt et al. 1969; Xanthakis and Sozen 1963) and well-established performance records of various slab systems. The fundamental design principles are applicable to all planar structural systems subjected to transverse loads. Several specific design rules, as well as historical precedents, limit the types of structures to which this chapter applies. General slab systems that may be designed according to this chapter include flat slabs, flat plates, slabs with beams in both directions, and waffle slabs. Slabs with paneled ceilings are two-way, wide-band, beam systems.

Slabs-on-ground that do not transmit vertical loads from other parts of the structure to the soil are excluded.

For slabs with beams, the design procedures of this chapter apply only where beams are located at the panel edges and where beams are supported by columns or other essentially nondeflecting supports at the corners of the panel. Two-way slabs with beams in one direction, with both slab and beams supported by girders in the other direction, may be designed under the general requirements of this chapter. Such designs should be based upon analysis compatible with the deflected position of the supporting beams and girders.

For slabs supported on walls, the design procedures in this chapter treat the wall as a beam of infinite stiffness; therefore, each wall should support the entire length of an edge of the panel (refer to 8.4.1.7). Each wall with a width less than a full panel length can be treated as a column support.

R8.2—General

R8.2.1 This section permits a design to be based directly on fundamental principles of structural mechanics, provided it can be demonstrated all strength and serviceability criteria are satisfied. Design of the slab may be achieved through combined use of classic solutions based on a linearly elastic continuum, numerical solutions based on discrete elements, or yield-line analyses, including, in all cases, evaluation of the stress conditions around supports in relation to shear, torsion, and flexure, as well as the effects of reduced stiffness of elements due to cracking and support geometry.

The direct design method and equivalent frame method are only suitable for orthogonal frames subject to gravity loads.

R8.2.2 Refer to R7.2.1.

CODE

8.2.4 A drop panel in a nonprestressed slab, where used to reduce the minimum required thickness in accordance with 8.3.1.1 or the quantity of deformed negative moment reinforcement at a support in accordance with 8.5.2.2, shall satisfy (a) and (b):

- (a) The drop panel shall project below the slab at least one-fourth of the adjacent slab thickness.
- (b) The drop panel shall extend in each direction from the centerline of support a distance not less than one-sixth the span length measured from center-to-center of supports in that direction.

8.2.5 A shear cap, where used to increase the critical section for shear at a slab-column joint, shall project below the slab soffit and extend horizontally from the face of the column a distance at least equal to the thickness of the projection below the slab soffit.

8.2.6 Materials

8.2.6.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

8.2.6.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

8.2.6.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

8.2.7 Connections to other members

8.2.7.1 For cast-in-place construction, joints shall satisfy **Chapter 15**.

8.3—Design limits

8.3.1 Minimum slab thickness

8.3.1.1 For nonprestressed slabs without interior beams spanning between supports on all sides, having a maximum ratio of long-to-short span of 2, overall slab thickness h shall not be less than the limits in Table 8.3.1.1, and shall be at least the value in (a) or (b), unless the calculated deflection limits of 8.3.2 are satisfied:

- (a) Slabs without drop panels as given in 8.2.4.....5 in.

COMMENTARY

R8.2.4 Drop panel dimensions specified in 8.2.4 are necessary when reducing the amount of negative moment reinforcement following 8.5.2.2 or to satisfy minimum slab thicknesses permitted in 8.3.1.1. If the dimensions are less than specified in 8.2.4, the projection may be used as a shear cap to increase the shear strength of the slab. For slabs with changes in thickness, it is necessary to check the shear strength at multiple sections (refer to **22.6.4.1(b)**).

R8.2.7 Connections to other members

R8.2.7.1 Calculation of the design strength of a slab system requires consideration of the transmission of load from the slab to the columns by moment, torsion, and shear.

R8.3—Design limits

R8.3.1 Minimum slab thickness

Minimum slab thicknesses in 8.3.1.1 and 8.3.1.2 are independent of loading and concrete modulus of elasticity. These minimum thicknesses are not applicable to slabs with unusually heavy superimposed sustained loads or for concrete with modulus of elasticity significantly lower than that of normalweight concrete. Deflections should be calculated for such situations.

R8.3.1.1 Minimum thicknesses in Table 8.3.1.1 are those that have been developed through the years. Use of longitudinal reinforcement with $f_y > 80,000$ psi may result in larger long-term deflections than in the case of $f_y \leq 80,000$ psi unless service stresses in reinforcement calculated for cracked sections are less than 40,000 psi. For $f_y > 80,000$ psi, deflections are required to be calculated.

CODE

COMMENTARY

(b) Slabs with drop panels as given in 8.2.4.....4 in.

For f_y exceeding 80,000 psi, 8.3.2 shall be satisfied.

Table 8.3.1.1—Minimum thickness of nonprestressed two-way slabs without interior beams (in.)^[1]

f_y , psi ^[2]	Without drop panels ^[3]			With drop panels ^[3]		
	Exterior panels		Interior panels	Exterior panels		Interior panels
	Without edge beams	With edge beams ^[4]		Without edge beams	With edge beams ^[4]	
40,000	$\ell_n/33$	$\ell_n/36$	$\ell_n/36$	$\ell_n/36$	$\ell_n/40$	$\ell_n/40$
60,000	$\ell_n/30$	$\ell_n/33$	$\ell_n/33$	$\ell_n/33$	$\ell_n/36$	$\ell_n/36$
80,000	$\ell_n/27$	$\ell_n/30$	$\ell_n/30$	$\ell_n/30$	$\ell_n/33$	$\ell_n/33$

^[1] ℓ_n is the clear span in the long direction, measured face-to-face of supports (in.).

^[2]For f_y between the values given in the table, minimum thickness shall be calculated by linear interpolation. Minimum thickness values shall not be extrapolated for f_y exceeding 80,000 psi.

^[3]Drop panels as given in 8.2.4.

^[4]Slabs with beams between columns along exterior edges. Exterior panels shall be considered to be without edge beams if α_f is less than 0.8.

8.3.1.2 For nonprestressed slabs with beams spanning between supports on all sides, overall slab thickness h shall satisfy the limits in Table 8.3.1.2, unless the calculated deflection limits of 8.3.2 are satisfied.

R8.3.1.2 For panels having a ratio of long-to-short span greater than 2, use of expressions (b) and (d) of Table 8.3.1.2 may give unrealistic results. For such panels, the rules applying to one-way construction in 7.3.1 should be used.

Table 8.3.1.2—Minimum thickness of nonprestressed two-way slabs with beams spanning between supports on all sides

α_{fm} ^[1]	Minimum h , in.	
$\alpha_{fm} \leq 0.2$	8.3.1.1 applies	(a)
$0.2 < \alpha_{fm} \leq 2.0$	Greater of:	$\frac{\ell_n \left(0.8 + \frac{f_y}{200,000} \right)}{36 + 5\beta(\alpha_{fm} - 0.2)}$
		5.0
$\alpha_{fm} > 2.0$	Greater of:	$\frac{\ell_n \left(0.8 + \frac{f_y}{200,000} \right)}{36 + 9\beta}$
		3.5

^[1] α_{fm} is the average value of α_f for all beams on edges of a panel.

^[2] ℓ_n is the clear span in the long direction, measured face-to-face of beams (in.).

^[3] β is the ratio of clear spans in long to short directions of slab.

8.3.1.2.1 At discontinuous edges of slabs conforming to 8.3.1.2, an edge beam with $\alpha_f \geq 0.80$ shall be provided, or the minimum thickness required by (b) or (d) of Table 8.3.1.2 shall be increased by at least 10% in the panel with a discontinuous edge.

8.3.1.3 The thickness of a concrete floor finish shall be permitted to be included in h if it is placed monolithically with the floor slab, or if the floor finish is designed to be composite with the floor slab in accordance with 16.4.

R8.3.1.3 A concrete floor finish may be considered for strength purposes only if it is cast monolithically with the slab. A bonded concrete overlay or other separate concrete finish is permitted to be included in h if composite action is provided in accordance with 16.4.

CODE

8.3.1.4 If single- or multiple-leg stirrups are used as shear reinforcement, the slab thickness shall be sufficient to satisfy the requirements for d in **22.6.7.1**.

8.3.2 Calculated deflection limits

8.3.2.1 Immediate and time-dependent deflections shall be calculated in accordance with **24.2** and shall not exceed the limits in **24.2.2** for two-way slabs given in (a) through (c):

- (a) Nonprestressed slabs not satisfying 8.3.1
- (b) Nonprestressed slabs without interior beams spanning between the supports on all sides and having a ratio of long-to-short span exceeding 2.0
- (c) Prestressed slabs

8.3.2.2 For nonprestressed composite concrete slabs satisfying 8.3.1.1 or 8.3.1.2, deflections occurring after the member becomes composite need not be calculated. Deflections occurring before the member becomes composite shall be investigated, unless the precomposite thickness also satisfies 8.3.1.1 or 8.3.1.2.

8.3.3 Reinforcement strain limit in nonprestressed slabs

8.3.3.1 Nonprestressed slabs shall be tension-controlled in accordance with Table 21.2.2.

8.3.4 Stress limits in prestressed slabs

8.3.4.1 Prestressed slabs shall be designed as Class U with $f_t \leq 6\sqrt{f'_c}$. Other stresses in prestressed slabs immediately after transfer and at service loads shall not exceed the permissible stresses in **24.5.3** and **24.5.4**.

8.4—Required strength

8.4.1 General

8.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in **Chapter 5**.

8.4.1.2 Required strength shall be calculated in accordance with the analysis procedures given in **Chapter 6**.

COMMENTARY

R8.3.2 Calculated deflection limits

R8.3.2.1 For prestressed flat slabs continuous over two or more spans in each direction, the span-thickness ratio generally should not exceed 42 for floors and 48 for roofs; these limits may be increased to 48 and 52, respectively, if calculations verify that both short- and long-term deflection, camber, and vibration frequency and amplitude are not objectionable.

R8.3.2.2 If any portion of a composite concrete member is prestressed, or if the member is prestressed after the components have been cast, the provisions of 8.3.2.1 apply and deflections are to be calculated. For nonprestressed concrete composite members, deflections need to be calculated and compared with the limiting values in Table 24.2.2, only when the thickness of the member or the precast part of the member is less than the minimum thickness given in Table 8.3.1.1. In unshored construction, the thickness of concern depends on whether the deflection before or after the attainment of effective composite action is being considered.

R8.3.3 Reinforcement strain limit in nonprestressed slabs

R8.3.3.1 The basis for a reinforcement strain limit for two-way slabs is the same as that for beams. Refer to **R9.3.3** for additional information.

R8.4—Required strength

R8.4.1 General

R8.4.1.2 To determine service and factored moments as well as shears in prestressed slab systems, numerical analysis is required rather than simplified approaches such as the direct design method. The equivalent frame method of analysis as contained in the **2014 edition of the Code** is a numerical method that has been shown by tests of large structural models to satisfactorily predict factored moments and shears in prestressed slab systems (**Smith and Burns 1974; Burns and Hemakom**

CODE

COMMENTARY

8.4.1.3 For prestressed slabs, effects of reactions induced by prestressing shall be considered in accordance with 5.3.14.

8.4.1.4 For a slab system supported by columns or walls, dimensions c_1 , c_2 , and ℓ_n shall be based on an effective support area. The effective support area is the intersection of the bottom surface of the slab, or drop panel or shear cap if present, with the largest right circular cone, right pyramid, or tapered wedge whose surfaces are located within the column and the capital or bracket and are oriented no greater than 45 degrees to the axis of the column.

8.4.1.5 A column strip is a design strip with a width on each side of a column centerline equal to the lesser of $0.25\ell_2$ and $0.25\ell_1$. A column strip shall include beams within the strip, if present.

8.4.1.6 A middle strip is a design strip bounded by two column strips.

8.4.1.7 A panel is bounded by column, beam, or wall centerlines on all sides.

8.4.1.8 For monolithic or composite concrete construction supporting two-way slabs, a beam includes that portion of slab, on each side of the beam extending a distance equal to the projection of the beam above or below the slab, whichever is greater, but not greater than four times the slab thickness.

1977; Hawkins 1981; PTI DC20.8; Gerber and Burns 1971; Scordelis et al. 1959). The referenced research also shows that analysis using prismatic sections or other approximations of stiffness may provide erroneous and unsafe results. Moment redistribution for prestressed slabs is permitted in accordance with 6.6.5. PTI DC20.8 provides guidance for prestressed concrete slab systems.

R8.4.1.7 A panel includes all flexural elements between column centerlines. Thus, the column strip includes the beam, if any.

R8.4.1.8 Two examples of monolithic or composite concrete beams, including the slab as a flange, are provided in Fig. R8.4.1.8.

CODE

COMMENTARY




Fig. R8.4.1.8—Examples of the portion of slab to be included with the beam under 8.4.1.8.

8.4.1.9 Combining the results of a gravity load analysis with the results of a lateral load analysis shall be permitted.

8.4.2 Factored moment

8.4.2.1 For slabs built integrally with supports, M_u at the support shall be permitted to be calculated at the face of support.

8.4.2.2 Factored slab moment resisted by the column

8.4.2.2.1 If gravity, wind, earthquake, or other loads cause a transfer of moment between the slab and column, a fraction of M_{sc} , the factored slab moment resisted by the column at a joint, shall be transferred by flexure in accordance with 8.4.2.2.2 through 8.4.2.2.5.

8.4.2.2.2 The fraction of factored slab moment resisted by the column, $\gamma_f M_{sc}$, shall be assumed to be transferred by flexure, where γ_f shall be calculated by:

$$\gamma_f = \frac{1}{1 + \left(\frac{2}{3}\right)\sqrt{\frac{b_1}{b_2}}} \quad (8.4.2.2.2)$$

8.4.2.2.3 The effective slab width b_{slab} for resisting $\gamma_f M_{sc}$ shall be the width of column, capital, or shear cap plus $1.5h$

R8.4.2 Factored moment

R8.4.2.2 Factored slab moment resisted by the column

R8.4.2.2.1 This section is concerned primarily with slab systems without beams.

R8.4.2.2.3 All reinforcement resisting that part of the moment to be transferred to the column by flexure should be placed within b_{slab} .

CODE

of slab or $1.5h$ of slab plus drop panel if present, on each side of the column, capital, or shear cap.

8.4.2.2.4 For nonprestressed slabs, where the limitations on v_{uv} and ε_t in Table 8.4.2.2.4 are satisfied, γ_f shall be permitted to be increased to the maximum modified values provided in Table 8.4.2.2.4, where v_c is calculated in accordance with 22.6.5.

COMMENTARY

R8.4.2.2.4 Some modification in the distribution of M_{sc} transferred by shear and flexure at both exterior and interior columns is possible. Interior, exterior, and corner columns refer to slab-column connections for which the critical perimeter for rectangular columns has four, three, and two sides, respectively.

At exterior columns, for M_{sc} resisted about an axis parallel to the edge, the portion of moment transferred by eccentricity of shear $\gamma_v M_{sc}$ may be reduced, provided that the factored shear at the column (excluding the shear produced by moment transfer) does not exceed the limits given in Table 8.4.2.2.4. Tests (Moehle 1988; ACI PRC-352.1) indicate that there is no significant interaction between shear and M_{sc} at the exterior column in such cases. Note that as $\gamma_v M_{sc}$ is decreased, $\gamma_f M_{sc}$ is increased.

At interior columns, some modification in the distribution of M_{sc} transferred by shear and flexure is possible, but with more severe limitations than for exterior columns with the slab span perpendicular to the edge. For interior columns and for exterior columns with the slab span parallel to the edge, M_{sc} transferred by flexure is permitted to be increased following the limits given in Table 8.4.2.2.4.

If the factored shear for a slab-column connection is larger than the shear limits in Table 8.4.2.2.4, the permitted increase in $\gamma_f M_{sc}$ may lead to brittle behavior of the slab-column connection because all of the reinforcement provided cannot be developed. Modifications for interior slab-column connections in this provision are permitted only where the slab has flexural ductility. So, the reinforcement required to develop $\gamma_f M_{sc}$ within the effective slab width should have a net tensile strain ε_t not less than $\varepsilon_{ty} + 0.008$, where the value of ε_{ty} is determined in 21.2.2. The use of Eq. (8.4.2.2) without the modification permitted in this provision will generally indicate overstress conditions on the connection. If reversal of moments occurs at opposite faces of an interior column, both top and bottom reinforcement should be concentrated within b_{slab} . A ratio of top-to-bottom reinforcement of approximately 2 is appropriate.

Table 8.4.2.2.4—Maximum modified values of γ_f for nonprestressed two-way slabs

Column location	Span direction	v_{uv}	ε_t (within b_{slab})	Maximum modified γ_f
Corner column	Either direction	$\leq 0.5\phi v_c$	$\geq \varepsilon_{ty} + 0.003$	1.0
Edge column	Perpendicular to the edge	$\leq 0.75\phi v_c$	$\geq \varepsilon_{ty} + 0.003$	1.0
	Parallel to the edge	$\leq 0.4\phi v_c$	$\geq \varepsilon_{ty} + 0.008$	$\frac{1.25}{1 + \left(\frac{2}{3}\right)\sqrt{\frac{b_1}{b_2}}} \leq 1.0$
Interior column	Either direction	$\leq 0.4\phi v_c$	$\geq \varepsilon_{ty} + 0.008$	$\frac{1.25}{1 + \left(\frac{2}{3}\right)\sqrt{\frac{b_1}{b_2}}} \leq 1.0$

8.4.2.2.5 Concentration of reinforcement over the column by closer spacing or additional reinforcement shall be used

CODE**COMMENTARY**

to resist moment on the effective slab width defined in 8.4.2.2.2 and 8.4.2.2.3.

8.4.2.2.6 The fraction of M_{sc} not calculated to be resisted by flexure shall be assumed to be resisted by eccentricity of shear in accordance with 8.4.4.2.

8.4.3 Factored one-way shear

8.4.3.1 For slabs built integrally with supports, V_u at the support shall be permitted to be calculated at the face of support.

8.4.3.2 Sections between the face of support and a critical section located d from the face of support for nonprestressed slabs and $h/2$ from the face of support for prestressed slabs shall be permitted to be designed for V_u at that critical section if (a) through (c) are satisfied:

- (a) Support reaction, in direction of applied shear, introduces compression into the end regions of the slab.
- (b) Loads are applied at or near the top surface of the slab.
- (c) No concentrated load occurs between the face of support and critical section.

8.4.4 Factored two-way shear**R8.4.4 Factored two-way shear****8.4.4.1 Critical section**

8.4.4.1.1 Slabs shall be evaluated for two-way shear in the vicinity of columns, concentrated loads, and reaction areas at critical sections in accordance with 22.6.4.

8.4.4.1.2 Slabs reinforced with stirrups or headed shear stud reinforcement shall be evaluated for two-way shear at critical sections in accordance with 22.6.4.2.

8.4.4.2 Factored two-way shear stress due to shear and factored slab moment resisted by the column**R8.4.4.2 Factored two-way shear stress due to shear and factored slab moment resisted by the column**

8.4.4.2.1 For two-way shear with factored slab moment resisted by the column, factored shear stress v_u shall be calculated at critical sections in accordance with 8.4.4.1. Factored shear stress v_u corresponds to a combination of v_{uv} and the shear stress produced by $\gamma_v M_{sc}$, where γ_v is given in 8.4.4.2.2 and M_{sc} is given in 8.4.2.2.1

8.4.4.2.2 The fraction of M_{sc} transferred by eccentricity of shear, $\gamma_v M_{sc}$, shall be applied at the centroid of the critical section in accordance with 8.4.4.1, where:

$$\gamma_v = 1 - \gamma_f \quad (8.4.4.2.2)$$

R8.4.4.2.2 Hanson and Hanson (1968) found that where moment is transferred between a column and a slab, 60% of the moment should be considered transferred by flexure across the perimeter of the critical section defined in 22.6.4.1, and 40% by eccentricity of the shear about the centroid of the critical section. For rectangular columns, the portion of moment transferred by flexure increases as the width of the face of the critical section resisting moment increases.

CODE

8.4.4.2.3 The factored shear stress resulting from $\gamma_v M_{sc}$ shall be assumed to vary linearly about the centroid of the critical section in accordance with 8.4.4.1.

COMMENTARY

Most of the data in Hanson and Hanson (1968) were obtained from tests of square columns. Limited information is available for round columns; however, these can be approximated as square columns having the same cross-sectional area.

R8.4.4.2.3 The shear stress distribution is assumed as illustrated in Fig. R8.4.4.2.3 for an interior or exterior column. The perimeter of the critical section, $ABCD$, is determined in accordance with 22.6.4.1. The factored shear stress v_{uv} and factored slab moment resisted by the column M_{sc} are determined at the centroidal axis $c-c$ of the critical section. The maximum factored shear stress may be calculated from:

$$v_{u,AB} = v_{uv} + \frac{\gamma_v M_{sc} c_{AB}}{J_c}$$

or

$$v_{u,CD} = v_{uv} - \frac{\gamma_v M_{sc} c_{CD}}{J_c}$$

where γ_v is given by Eq. (8.4.4.2.2).

For an interior column, J_c may be calculated by:

J_c = property of assumed critical section analogous to polar moment of inertia

$$= \frac{d(c_1 + d)^3}{6} + \frac{(c_1 + d)d^3}{6} + \frac{d(c_2 + d)(c_1 + d)^2}{2}$$


Similar equations may be developed for J_c for columns located at the edge or corner of a slab.

The fraction of M_{sc} not transferred by eccentricity of shear should be transferred by flexure in accordance with 8.4.2.2. A conservative method assigns the fraction transferred by flexure over an effective slab width defined in 8.4.2.2.3. Often, column strip reinforcement is concentrated near the column to resist M_{sc} . Available test data (Hanson and Hanson 1968) indicate that this practice does not increase shear strength but may increase stiffness of the slab-column junction.


Test data (Hawkins 1981) indicate prestressed slab-to-column connections can possess adequate strength to transfer the fractions of slab moment resisted by the column as required by 8.4.2.2 and 8.4.4.2.

Where shear reinforcement has been used, the critical section beyond the shear reinforcement generally has a polygonal shape (Fig. R8.7.6(d) and (e)). Equations for calculating shear stresses on such sections are given in ACI PRC-421.1.

CODE





(a) Interior column



(b) Edge column

Fig. R8.4.4.2.3—Assumed distribution of shear stress.



8.5—Design strength

8.5.1 General

8.5.1.1 For each applicable factored load combination, design strength shall satisfy $\phi S_n \geq U$, including (a) through (d). Interaction between load effects shall be considered.

- (a) $\phi M_n \geq M_u$ at all sections along the span in each direction
- (b) $\phi M_n \geq \gamma_f M_{sc}$ within b_{slab} as defined in 8.4.2.2.3
- (c) $\phi V_n \geq V_u$ at all sections along the span in each direction for one-way shear
- (d) $\phi v_n \geq v_u$ at the critical sections defined in 8.4.4.1 for two-way shear

8.5.1.2 ϕ shall be in accordance with 21.2.

8.5.2 Moment

8.5.2.1 M_n shall be calculated in accordance with 22.3.

8.5.2.2 In calculating M_n for nonprestressed slabs with a drop panel, the thickness of the drop panel below the slab shall not be assumed to be greater than one-fourth the distance from the edge of drop panel to the face of column or column capital.

COMMENTARY

R8.5—Design strength

R8.5.1 General

R8.5.1.1 Refer to R9.5.1.1.

CODE

8.5.2.3 In calculating M_n for prestressed slabs, external tendons shall be considered as unbonded unless the external tendons are effectively bonded to the slab along its entire length.

8.5.3 Shear

8.5.3.1 Design shear strength of slabs in the vicinity of columns, concentrated loads, or reaction areas shall be the more severe of 8.5.3.1.1 and 8.5.3.1.2.

8.5.3.1.1 For one-way shear, where each critical section to be investigated extends in a plane across the entire slab width, V_n shall be calculated in accordance with 22.5.

8.5.3.1.2 For two-way shear, v_n shall be calculated in accordance with 22.6.

8.5.3.2 For composite concrete slabs, horizontal shear strength V_{nh} shall be calculated in accordance with 16.4.

8.5.4 Openings in slab systems

8.5.4.1 Openings of any size shall be permitted in slab systems if shown by analysis that all strength and serviceability requirements, including the limits on deflections, are satisfied.

8.5.4.2 As an alternative to 8.5.4.1, openings shall be permitted in slab systems without beams in accordance with (a) through (d).

(a) Openings of any size shall be permitted in the area common to intersecting middle strips, but the total quantity of reinforcement in the panel shall be at least that required for the panel without the opening.

(b) At two intersecting column strips, not more than one-eighth the width of column strip in either span shall be interrupted by openings. A quantity of reinforcement at least equal to that interrupted by an opening shall be added on the sides of the opening.

(c) At the intersection of one column strip and one middle strip, not more than one-fourth of the reinforcement in either strip shall be interrupted by openings. A quantity of reinforcement at least equal to that interrupted by an opening shall be added on the sides of the opening.

(d) If an opening is located closer than $4h$ from the periphery of a column, concentrated load or reaction area, 22.6.4.3 shall be satisfied.

8.6—Reinforcement limits

8.6.1 *Minimum flexural reinforcement in nonprestressed slabs*

COMMENTARY

R8.5.3 Shear

R8.5.3.1 Differentiation should be made between a narrow slab acting as a beam, and a slab subject to two-way action where failure may occur by punching along a truncated cone or pyramid around a concentrated load or reaction area.

CODE

8.6.1.1 A minimum area of flexural reinforcement, $A_{s,min}$ of $0.0018A_g$, or as defined in 8.6.1.2, shall be provided near the tension face of the slab in the direction of the span under consideration.

COMMENTARY

R8.6.1.1 The required area of deformed or welded wire reinforcement used as minimum flexural reinforcement is the same as that required for shrinkage and temperature in 24.4.3.2. However, whereas shrinkage and temperature reinforcement is permitted to be distributed between the two faces of the slab as deemed appropriate for specific conditions, minimum flexural reinforcement should be placed as close as practicable to the face of the concrete in tension due to applied loads.

Figure R8.6.1.1 illustrates the arrangement of minimum reinforcement required near the top of a two-way slab supporting uniform gravity load. The bar cutoff points are based on the requirements shown in Fig. 8.7.4.1.3.

To improve crack control and to intercept potential punching shear cracks with tension reinforcement, the licensed design professional should consider specifying continuous reinforcement in each direction near both faces of thick two-way slabs, such as transfer slabs, podium slabs, and mat foundations. Also refer to R8.7.4.1.3.




Fig. R8.6.1.1—Arrangement of minimum reinforcement near the top of a two-way slab.

8.6.1.2 If $v_{uv} > \phi 2\sqrt{f_c}\lambda_s\lambda$ on the critical section for two-way shear surrounding a column, concentrated load, or reaction area, $A_{s,min}$, provided over the width b_{slab} , shall satisfy Eq. (8.6.1.2)

$$A_{s,min} = \frac{5v_{uv}b_{slab}b_o}{\phi\alpha_s f_y} \quad (8.6.1.2)$$

where b_{slab} is the width specified in 8.4.2.2.3, α_s is given in 22.6.5.3, ϕ is the value for shear, and λ_s is given in 22.5.5.1.3.

R8.6.1.2 Tests on interior column-to-slab connections with and without shear reinforcement, where the slabs are lightly reinforced for flexure (Peiris and Ghali 2012; Hawkins and Ospina 2017; Widiyanto et al. 2009; Muttoni 2008; Dam et al. 2017), have shown that yielding of the slab flexural tension reinforcement in the vicinity of the column or loaded area leads to increased local rotations and opening of any inclined crack existing within the slab. In such cases, sliding along the inclined crack can cause a flexure-driven punching failure. $A_{s,min}$ is intended to prevent a brittle punching failure if the maximum factored two-way shear stress is less than the stress corresponding to the design strength calculated

CODE

8.6.2 Minimum flexural reinforcement in prestressed slabs

8.6.2.1 For prestressed slabs, the effective prestress force $A_{ps}f_{se}$ shall provide a minimum average compressive stress of 125 psi on the slab section tributary to the tendon or tendon group. For slabs with varying cross section along the slab span, either parallel or perpendicular to the tendon or tendon group, the minimum average effective prestress of 125 psi is required at every cross section tributary to the tendon or tendon group along the span.

8.6.2.2 For slabs with bonded prestressed reinforcement, total quantity of A_s and A_{ps} shall be adequate to develop a factored load at least 1.2 times the cracking load calculated on the basis of f_r defined in 19.2.3.

8.6.2.2.1 For slabs with both flexural and shear design strength at least twice the required strength, 8.6.2.2 need not be satisfied.

8.6.2.3 For prestressed slabs, a minimum area of bonded deformed longitudinal reinforcement, $A_{s,min}$, shall be provided in the precompressed tension zone in the direction of the span under consideration in accordance with Table 8.6.2.3.

COMMENTARY

by the two-way shear equations of Table 22.6.5.2 for slabs without shear reinforcement and less than $v_c + v_s$ with v_c calculated in accordance with Table 22.6.6.1 for slabs with shear reinforcement.

To derive Eq. (8.6.1.2), the shear force associated with local yielding around the column, taken as $8A_{s,min}f_yd/b_{slab}$ for an interior column connection (Hawkins and Ospina 2017) and generalized as $(\alpha_s/5)A_{s,min}f_yd/b_{slab}$ to account for edge and corner conditions, was set equal to the factored shear on the slab critical section. $A_{s,min}$ also needs to be provided at the periphery of drop panels and shear caps.

Commentary on size effect factor is provided in R22.5.5.1 and R22.6.5.2.

R8.6.2 Minimum flexural reinforcement in prestressed slabs

R8.6.2.1 The minimum average effective prestress of 125 psi was used in two-way test panels in the early 1970s to address punching shear concerns of lightly reinforced slabs. For this reason, the minimum effective prestress is required to be provided at every cross section.

If the slab thickness varies along the span of a slab or perpendicular to the span of a slab, resulting in a varying slab cross section, the 125 psi minimum effective prestress and maximum tendon spacing is required at every cross section tributary to the tendon or group of tendons along the span, considering both the thinner and thicker slab sections. This may result in higher than the minimum f_{pc} in thinner cross sections, and tendons spaced at less than the maximum in thicker cross sections along a span with varying thickness, due to the practical aspects of tendon placement in the field.

R8.6.2.2 Minimum flexural reinforcement is required for reasons similar to those discussed in R9.6.1.1 for nonprestressed beams.

R8.6.2.3 Some bonded reinforcement is required by the Code in prestressed slabs to limit crack width and spacing at service-level load when concrete tensile stresses exceed the modulus of rupture and, for slabs with unbonded tendons, to ensure flexural behavior at nominal strength, rather than tied-arch behavior. Providing the minimum bonded reinforcement as stipulated in this provision helps to ensure the desired behavior.

The minimum amount of bonded reinforcement in two-way flat slab systems is based on reports by Joint ACI-ASCE Committee 423 (1958) and ACI PRC-423.3. Limited research available for two-way flat slabs with drop panels (Odello and Mehta 1967) indicates that behavior of these particular systems is similar to the behavior of flat plates.

CODE

Table 8.6.2.3—Minimum bonded deformed longitudinal reinforcement $A_{s,min}$ in two-way slabs with bonded or unbonded tendons

Region	Calculated ft after all losses, psi	$A_{s,min}$ in. ²	
Positive moment	$f_t \leq 2\sqrt{f'_c}$	Not required	(a)
	$2\sqrt{f'_c} < f_t \leq 6\sqrt{f'_c}$	$\frac{N_c}{0.5f_y}$	(b) ^{[1],[2]}
Negative moment at columns	$f_t \leq 6\sqrt{f'_c}$	$0.00075A_{cf}$	(c) ^[2]

^[1]The value of f_y shall not exceed 60,000 psi.

^[2]For slabs with bonded tendons, it shall be permitted to reduce $A_{s,min}$ by the area of the bonded prestressed reinforcement located within the area used to determine N_c for positive moment, or within the width of slab defined in 8.7.5.3(a) for negative moment.

COMMENTARY

For usual loads and span lengths, flat plate tests (Joint ACI-ASCE Committee 423 (1958)) indicate satisfactory performance without bonded reinforcement in positive moment regions where $f_t \leq 2\sqrt{f'_c}$. In positive moment regions where $2\sqrt{f'_c} < f_t \leq 6\sqrt{f'_c}$, a minimum bonded reinforcement area proportioned to resist N_c according to Eq. (8.6.2.3(b)) is required. The tensile force N_c is calculated at service load on the basis of an uncracked, homogeneous section.

Research on unbonded post-tensioned two-way flat slab systems (Joint ACI-ASCE Committee 423 [1958], [1974]; ACI PRC-423.3; Odello and Mehta [1967]) shows that bonded reinforcement in negative moment regions, proportioned on the basis of 0.075 percent of the cross-sectional area of the slab-beam strip reduces crack width and spacing. The same area of bonded reinforcement is required in slabs with either bonded or unbonded tendons. The minimum bonded reinforcement area required by Eq. (8.6.2.3(c)) is a minimum area independent of grade of reinforcement or design yield strength. To account for different adjacent tributary spans, this equation is given on the basis of slab-beam strips as defined in 2.3. For rectangular slab panels, this equation is conservatively based on the greater of the cross-sectional areas of the two intersecting slab-beam strips at the column. This ensures that the minimum percentage of reinforcement recommended by research is provided in both directions. Concentration of this reinforcement in the top of the slab directly over and immediately adjacent to the column is important. Research also shows that where low tensile stresses occur at service loads, satisfactory behavior has been achieved at factored loads without bonded reinforcement. However, the Code requires minimum bonded reinforcement regardless of service load stress levels to help ensure flexural continuity and ductility, and to limit crack widths and spacing due to overload, temperature, or shrinkage. Research on post-tensioned flat plate-to-column connections is reported in Smith and Burns (1974), Burns and Hemakom (1977), Hawkins (1981), PTI TAB.1, and Foutch et al. (1990).

Unbonded post-tensioned members do not inherently provide large capacity for energy dissipation under severe earthquake loadings because the member response is primarily elastic. For this reason, unbonded post-tensioned structural members reinforced in accordance with the provisions of this section should be assumed to resist only vertical loads and to act as horizontal diaphragms between energy-dissipating elements under earthquake loadings of the magnitude defined in 18.2.1.

8.7—Reinforcement detailing**8.7.1 General**

8.7.1.1 Concrete cover for reinforcement shall be in accordance with 20.5.1.

8.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with 25.4.

R8.7—Reinforcement detailing

CODE

COMMENTARY

8.7.1.3 Splice lengths of deformed reinforcement shall be in accordance with **25.5**.

8.7.1.4 Bundled bars shall be detailed in accordance with **25.6**.

8.7.2 *Flexural reinforcement spacing*

8.7.2.1 Minimum spacings shall be in accordance with **25.2**.

8.7.2.2 For nonprestressed solid slabs, maximum spacing s of deformed longitudinal reinforcement shall be the lesser of $2h$ and 18 in. at critical sections, and the lesser of $3h$ and 18 in. at other sections.

8.7.2.3 For prestressed slabs with uniformly distributed loads, maximum spacing s of tendons or groups of tendons in at least one direction shall be the lesser of $8h$ and 5 ft.

8.7.2.4 Concentrated loads and openings shall be considered in determining tendon spacing.

8.7.3 *Corner restraint in slabs*

8.7.3.1 At exterior corners of slabs supported by edge walls or where one or more edge beams have a value of α_f greater than 1.0, reinforcement at top and bottom of slab shall be designed to resist M_u per unit width due to corner effects equal to the maximum positive M_u per unit width in the slab panel.

R8.7.2 *Flexural reinforcement spacing*

R8.7.2.2 The requirement that center-to-center spacing of longitudinal reinforcement be not more than twice the slab thickness at critical sections applies only to reinforcement in solid slabs, and not to reinforcement in joists or waffle slabs. This limit is to ensure uniform flexural action, control cracking, and provide strength for loads concentrated on small areas of the slab. Refer also to **R24.3**.


R8.7.2.3 This section provides spacing of tendons in one direction that will permit use of banded tendon distributions in the perpendicular direction, based on results reported by **Burns and Hemakom (1977)**.

R8.7.3 *Corner restraint in slabs*


R8.7.3.1 Unrestrained corners of two-way slabs tend to lift when loaded. If this lifting tendency is restrained by edge walls, columns, or stiff beams, bending moments will develop in the corner of the slab. This section requires reinforcement, equivalent to that required for positive moment in the primary direction, to resist these moments and control cracking. Refer to Fig. R8.7.3.1.

CODE

COMMENTARY



OPTION 1



OPTION 2

Notes:

1. Applies where B-1 or B-2 has $\alpha_f > 1.0$
2. Max. bar spacing $2h$, where h = slab thickness

Fig. R8.7.3.1—Slab corner reinforcement.

8.7.3.1.1 Factored moment due to corner effects, M_u , shall be assumed to be about an axis perpendicular to the diagonal from the corner in the top of the slab and about an axis parallel to the diagonal from the corner in the bottom of the slab.

8.7.3.1.2 Reinforcement shall be provided for a distance in each direction from the corner equal to one-fifth the longer span.

8.7.3.1.3 Reinforcement shall be placed parallel to the diagonal in the top of the slab and perpendicular to the diagonal in the bottom of the slab. Alternatively, reinforcement

CODE

shall be placed in two layers parallel to the sides of the slab in both the top and bottom of the slab.

8.7.4 Flexural reinforcement in nonprestressed slabs**8.7.4.1 Termination of reinforcement**

8.7.4.1.1 Where a slab is supported on spandrel beams, columns, or walls, reinforcement perpendicular to a discontinuous edge shall satisfy (a) and (b):

- (a) Positive moment reinforcement shall extend to the edge of slab and have embedment, straight or hooked, at least 6 in. into spandrel beams, columns, or walls
- (b) Negative moment reinforcement shall be bent, hooked, or otherwise embedded into spandrel beams, columns, or walls, to develop f_y in tension at the face of support

8.7.4.1.2 Where a slab is not supported by a spandrel beam or wall at a discontinuous edge, or where a slab cantilevers beyond the support, it shall be permitted to develop the reinforcement within the slab.

8.7.4.1.3 For slabs without beams, reinforcement extensions shall be in accordance with (a) through (c):

- (a) Reinforcement lengths shall be at least in accordance with Fig. 8.7.4.1.3, and if slabs act as primary members resisting lateral loads, reinforcement lengths shall be at least those required by analysis.
- (b) If adjacent spans are unequal, extensions of negative moment reinforcement beyond the face of support in accordance with Fig. 8.7.4.1.3 shall be based on the longer span.
- (c) Bent bars shall be permitted only where the depth-to-span ratio permits use of bends of 45 degrees or less.

COMMENTARY**R8.7.4 Flexural reinforcement in nonprestressed slabs****R8.7.4.1 Termination of reinforcement**

R8.7.4.1.1 If spandrel beams are built solidly into walls, the slab edge support approaches complete fixity. Without an integral wall, the slab edge support could approach being a free edge or simply supported, depending on the flexural and torsional rigidity of the spandrel beam. These requirements provide for unknown edge support conditions that might occur in a structure.

R8.7.4.1.2 If spandrel beams are built solidly into walls, the slab edge support approaches complete fixity. Without an integral wall, the slab edge support could approach being a free edge or simply supported, depending on the flexural and torsional rigidity of the spandrel beam. These requirements provide for unknown edge support conditions that might occur in a structure.

R8.7.4.1.3 The minimum lengths and extensions of reinforcement expressed as a fraction of the clear span in Fig. 8.7.4.1.3 were developed for slabs of ordinary proportions supporting gravity loads. These minimum lengths and extensions of bars may not be sufficient to intercept potential punching shear cracks in thick two-way slabs such as transfer slabs, podium slabs, and mat foundations. Therefore, the Code requires extensions for at least half of the column strip top bars to be at least $5d$. For slabs with drop panels, d is the effective depth within the drop panel. In these thick two-way slabs, continuous reinforcement in each direction near both faces is desirable to improve structural integrity, control cracking, and reduce creep deflections. As illustrated in Fig. R8.7.4.1.3, punching shear cracks, which can develop at angles as low as approximately 20 degrees, may not be intercepted by the tension reinforcement in thick slabs if this reinforcement does not extend to at least $5d$ beyond the face of the support. For moments resulting from combined lateral and gravity loadings, these minimum lengths and extensions may not be sufficient.

Bent bars are seldom used and are difficult to place properly. Bent bars, however, are permitted provided they comply with 8.7.4.1.3(c). Guidance on the use of bent bar systems can be found in 13.4.8 of the **1983 Code**.

CODE			COMMENTARY	
Strip	Location	Minimum A_s at section	Without drop panels	With drop panels
Column strip	Top	50% Remainder		
	Bottom	100%		
Middle strip	Top	100%		
	Bottom	50% Remainder		

Fig. 8.7.4.1.3—Minimum extensions for deformed reinforcement in two-way slabs without beams.

CODE

COMMENTARY





Fig. R8.7.4.1.3—Punching shear cracks in ordinary and thick slabs.

8.7.4.2 Structural integrity

8.7.4.2.1 All bottom deformed bars or deformed wires within the column strip, in each direction, shall be continuous or spliced using mechanical or welded splices in accordance with 25.5.7 or Class B tension lap splices in accordance with 25.5.2. Splices shall be located in accordance with Fig. 8.7.4.1.3.

8.7.4.2.2 At least two of the column strip bottom bars or wires in each direction shall pass within the region bounded by the longitudinal reinforcement of the column and shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at exterior supports.

8.7.5 Flexural reinforcement in prestressed slabs

8.7.5.1 External tendons shall be attached to the slab in a manner that maintains the specified eccentricity between the tendons and the concrete centroid through the full range of anticipated member deflections.

R8.7.4.2 Structural integrity

R8.7.4.2.1 The continuous column strip bottom reinforcement provides the slab some residual ability to span to adjacent supports should a single support be damaged. The two continuous column strip bottom bars or wires through the column are termed “integrity reinforcement,” and give the slab some residual strength following a punching shear failure at a single support (Mitchell and Cook 1984). Joint ACI-ASCE Committee 352 (ACI PRC-352.1) provides further guidance on design of integrity reinforcement at slab-column connections. Similar provisions for slabs with unbonded tendons are provided in 8.7.5.6.

R8.7.5 Flexural reinforcement in prestressed slabs

CODE

8.7.5.2 If bonded deformed longitudinal reinforcement is required to satisfy flexural strength or for tensile stress conditions in accordance with Eq. (8.6.2.3(b)), the detailing requirements of **7.7.3** shall be satisfied.

8.7.5.3 Bonded longitudinal reinforcement required by Eq. (8.6.2.3(c)) shall be placed in the top of the slab, and shall be in accordance with (a) through (c):

- (a) Reinforcement shall be distributed between lines that are $1.5h$ outside opposite faces of the column support.
- (b) At least four deformed bars, deformed wires, or bonded strands shall be provided in each direction.
- (c) Maximum spacing s between bonded longitudinal reinforcement shall not exceed 12 in.

8.7.5.4 *Termination of prestressed reinforcement*

8.7.5.4.1 Post-tensioned anchorage zones shall be designed and detailed in accordance with **25.9**.

8.7.5.4.2 Post-tensioning anchorages and couplers shall be designed and detailed in accordance with **25.8**.

8.7.5.5 *Termination of deformed reinforcement in slabs with unbonded tendons*

8.7.5.5.1 Length of deformed reinforcement required by 8.6.2.3 shall be in accordance with (a) and (b):

- (a) In positive moment areas, length of reinforcement shall be at least $\ell_n/3$ and be centered in those areas
- (b) In negative moment areas, reinforcement shall extend at least $\ell_n/6$ on each side of the face of support

8.7.5.6 *Structural integrity*

8.7.5.6.1 Except as permitted in 8.7.5.6.3, at least two tendons with 1/2 in. diameter or larger strand shall be placed in each direction at columns in accordance with (a) or (b):

- (a) Tendons shall pass through the region bounded by the longitudinal reinforcement of the column.
- (b) Tendons shall be anchored within the region bounded by the longitudinal reinforcement of the column, and the anchorage shall be located beyond the column centroid and away from the anchored span.

8.7.5.6.2 Outside of the column and shear cap faces, the two structural integrity tendons required by 8.7.5.6.1 shall pass under any orthogonal tendons in adjacent spans.

COMMENTARY

R8.7.5.2 Bonded reinforcement should be developed for the required strength to resist factored loads. The requirements of 7.7.3 are intended to develop bonded reinforcement for tensile or compressive forces resulting from flexure under factored loads in accordance with **22.3.2**, or by tensile stresses at service load in accordance with Eq. (8.6.2.3(b)).

R8.7.5.5 *Termination of deformed reinforcement in slabs with unbonded tendons*

R8.7.5.5.1 The minimum lengths apply to bonded reinforcement required by 8.6.2.3, but not required for flexural strength in accordance with **22.3.2**. Research (Odello and Mehta 1967) on continuous spans shows that these minimum lengths provide adequate behavior under service load and factored load conditions.

R8.7.5.6 *Structural integrity*

R8.7.5.6.1 Prestressing tendons that pass through the slab-column joint at any location over the depth of the slab are assumed to suspend the slab following a punching shear failure, provided the tendons are continuous through or anchored within the region bounded by the longitudinal reinforcement of the column and are prevented from bursting through the top surface of the slab (**ACI PRC-352.1**).

R8.7.5.6.2 Outside of column and shear cap faces, structural integrity tendons should pass below orthogonal tendons from adjacent spans so that vertical movements of the integrity tendons are restrained by the orthogonal tendons. Where tendons are distributed in one direction and banded in the orthogonal direction, this requirement can be satisfied by first

CODE

8.7.5.6.3 Slabs with tendons not satisfying 8.7.5.6.1 shall be permitted if bonded bottom deformed reinforcement is provided in each direction in accordance with 8.7.5.6.3.1 through 8.7.5.6.3.3.

8.7.5.6.3.1 Minimum bottom deformed reinforcement A_s in each direction shall be the larger of (a) and (b). The value of f_y shall be limited to a maximum of 80,000 psi:

$$(a) A_s = \frac{4.5\sqrt{f'_c}c_2d}{f_y} \quad (8.7.5.6.3.1a)$$

$$(b) A_s = \frac{300c_2d}{f_y} \quad (8.7.5.6.3.1b)$$

where c_2 is measured at the column faces through which the reinforcement passes.

8.7.5.6.3.2 Bottom deformed reinforcement calculated in 8.7.5.6.3.1 shall pass within the region bounded by the longitudinal reinforcement of the column and shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at exterior supports.

8.7.5.6.3.3 Bottom deformed reinforcement shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y beyond the column or shear cap face.

8.7.6 Shear reinforcement – stirrups

COMMENTARY

placing the integrity tendons for the distributed tendon direction and then placing the banded tendons. Where tendons are distributed in both directions, weaving of tendons is necessary and use of 8.7.5.6.3 may be an easier approach.

R8.7.5.6.3 In some prestressed slabs, tendon layout constraints make it difficult to provide the structural integrity tendons required by 8.7.5.6.1. In such situations, the structural integrity tendons can be replaced by deformed bar bottom reinforcement. The equations given in 8.7.5.6.3.1 are the equivalent of 1.5 times the minimum flexural reinforcement area required for nonprestressed beams (9.6.1.2).

R8.7.6 Shear reinforcement – stirrups

Research (Hawkins 1974; Broms 1990; Yamada et al. 1991; Hawkins et al. 1975; ACI PRC-421.1) has shown that shear reinforcement consisting of properly anchored bars or wires and single- or multiple-leg stirrups, or closed stirrups, can increase punching shear resistance of slabs. Spacing limits given in 8.7.6.3 correspond to slab shear reinforcement details that have been shown to be effective. Anchorage requirements for stirrup-type shear reinforcement, which should also be applied for bars or wires used as slab shear reinforcement, are given in 25.7.1. It is essential that this shear reinforcement engage longitudinal reinforcement at both the top and bottom of the slab, as shown for typical details in Fig. R8.7.6(a) to (d). Anchorage of shear reinforcement with hooks according to 25.7.1 is difficult in slabs thinner than 10 in. Shear reinforcement consisting of headed studs in accordance with 8.7.7 has been used successfully (ACI PRC-421.1). Heads conforming to 20.2.1.6 are

CODE**COMMENTARY**

permitted in 25.7.1 as an alternative to hooks at one or both ends for anchorage of shear reinforcement in slabs.


In a slab-column connection for which moment transfer is negligible, the shear reinforcement should be symmetrical about the centroid of the critical section (Fig. R8.7.6(e)). Spacing limits defined in 8.7.6.3 are also shown in Fig. R8.7.6(e) and (f).

At exterior connections or for interior connections where moment transfer is significant, closed stirrups are recommended in a pattern as symmetrical as possible. Although the average shear stresses on faces *AD* and *BC* of the exterior connection in Fig. R8.7.6(f) are lower than on face *AB*, the closed stirrups extending from faces *AD* and *BC* provide some torsional strength along the edge of the slab.




CODE


COMMENTARY




(a) single-leg stirrup or bar



(b) single-leg stirrup or bar with heads



(c) multiple-leg stirrup or bar



(d) closed stirrup

Fig. R8.7.6(a)-(d)—Single- or multiple-leg stirrup-type slab shear reinforcement.

CODE

COMMENTARY




Fig. R8.7.6(e)—Arrangement of stirrup shear reinforcement, interior connection.

CODE

COMMENTARY




Fig. R8.7.6(f)—Arrangement of stirrup shear reinforcement, edge connection.

8.7.6.1 Single-leg, simple-U, multiple-U, and closed stirrups shall be permitted as shear reinforcement.

8.7.6.2 Stirrup anchorage and geometry shall be in accordance with 25.7.1.

8.7.6.3 If stirrups are provided, location and spacing shall be in accordance with Table 8.7.6.3.

Table 8.7.6.3—First stirrup location and spacing limits


Direction of measurement	Description of measurement	Maximum distance or spacing, in.
Perpendicular to column face	Distance from column face to first stirrup	$d/2$
	Spacing between stirrups	$d/2$
Parallel to column face	Spacing between vertical legs of stirrups	$2d$

CODE**8.7.7 Shear reinforcement – headed studs****COMMENTARY****R8.7.7 Shear reinforcement – headed studs**

Using headed stud assemblies as shear reinforcement in slabs requires specifying the stud shank diameter, spacing of the studs, and height of the assemblies for the particular applications.

Tests ([ACI PRC-421.1](#)) have shown that vertical studs mechanically anchored close to the top and bottom of slabs are effective in resisting punching shear. The specified height to achieve this objective while providing a reasonable tolerance in specifying the height, as shown in Fig. R20.5.1.3.6.

Compared with a leg of a stirrup having bends at the ends, in a thin slab a stud head exhibits smaller slip and results in smaller shear crack widths. The improved performance results in increased limits for shear strength and spacing between peripheral lines of headed shear stud reinforcement. Typical arrangements of headed shear stud reinforcement are shown in Fig. R8.7.7. The critical section beyond the shear reinforcement generally has a polygonal shape. Equations for calculating shear stresses on such sections are given in [ACI PRC-421.1](#).






Fig. R8.7.7—Typical arrangements of headed shear stud reinforcement and critical sections.

8.7.7.1 Headed shear stud reinforcement shall be permitted if placed perpendicular to the plane of the slab.

8.7.7.1.1 The overall height of the shear stud assembly shall be at least the thickness of the slab minus the sum of (a) through (c):

- (a) Concrete cover on the top flexural reinforcement
- (b) Concrete cover on the base rail
- (c) One-half the bar diameter of the flexural tension reinforcement

8.7.7.1.2 Headed shear stud reinforcement location and spacing shall be in accordance with Table 8.7.7.1.2.

R8.7.7.1.2 The specified spacings between peripheral lines of shear reinforcement are justified by experiments

CODE

COMMENTARY

Table 8.7.7.1.2—Shear stud location and spacing limits

Direction of measurement	Description of measurement	Condition		Maximum distance or spacing, in.
Perpendicular to column face	Distance from column face to first peripheral line of shear studs	All		$d/2$
		Nonprestressed slab with	$v_u \leq \phi 6 \sqrt{f'_c}$	$3d/4$
	Constant spacing between peripheral lines of shear studs	Nonprestressed slab with	$v_u > \phi 6 \sqrt{f'_c}$	$d/2$
		Prestressed slabs conforming to 22.6.5.4		$3d/4$
Parallel to column face	Spacing between adjacent shear studs on peripheral line nearest to column face	All		$2d$

(ACI PRC-421.1). Clear spacing between the heads of studs should be adequate to permit placing flexural reinforcement.

8.8—Nonprestressed two-way joist systems

8.8.1 General

R8.8—Nonprestressed two-way joist systems

R8.8.1 General

The empirical limits established for nonprestressed reinforced concrete joist floors are based on successful past performance of joist construction using common joist forming systems. For prestressed joist construction, these limits may be used as a guide.

8.8.1.1 Nonprestressed two-way joist construction consists of a monolithic combination of regularly spaced ribs and a top slab designed to span in two orthogonal directions.

8.8.1.2 Width of ribs shall be at least 4 in. at any location along the depth.

8.8.1.3 Overall depth of ribs, excluding slab thickness, shall not exceed 3.5 times the minimum width.

8.8.1.4 Clear spacing between ribs shall not exceed 30 in.

8.8.1.5 V_c shall be permitted to be taken as 1.1 times the values calculated in 22.5.

8.8.1.6 For structural integrity, at least one bottom bar in each joist shall be continuous and shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at the face of supports.

8.8.1.7 Reinforcement area perpendicular to the ribs shall satisfy slab moment strength requirements, considering load concentrations, and shall be at least the shrinkage and temperature reinforcement area in accordance with 24.4.

R8.8.1.4 A limit on maximum spacing of ribs is required because of the provisions permitting higher shear strengths and less concrete cover for the reinforcement for these relatively small, repetitive members.

R8.8.1.5 The increase in shear strength is justified on the basis of: 1) satisfactory performance of joist construction designed with higher calculated shear strengths; and 2) potential for redistribution of local overloads to adjacent joists.

CODE

COMMENTARY

8.8.1.8 Two-way joist construction not satisfying the limitations of 8.8.1.1 through 8.8.1.4 shall be designed as slabs and beams.

8.8.2 Joist systems with structural fillers

8.8.2.1 If permanent burned clay or concrete tile fillers of material having a unit compressive strength at least equal to f_c' in the joists are used, 8.8.2.1.1 and 8.8.2.1.2 shall apply.

8.8.2.1.1 Slab thickness over fillers shall be at least the greater of one-twelfth the clear distance between ribs and 1.5 in.

8.8.2.1.2 For calculation of shear and negative moment strength, it shall be permitted to include the vertical shells of fillers in contact with the ribs. Other portions of fillers shall not be included in strength calculations.

8.8.3 Joist systems with other fillers

8.8.3.1 If fillers not complying with 8.8.2.1 or removable forms are used, slab thickness shall be at least the greater of one-twelfth the clear distance between ribs and 2 in.

8.9—Lift-slab construction

8.9.1 In slabs constructed with lift-slab methods where it is impractical to pass the tendons required by 8.7.5.6.1 or the bottom bars required by 8.7.4.2 or 8.7.5.6.3 through the column, at least two post-tensioned tendons or two bonded bottom bars or wires in each direction shall pass through the lifting collar as close to the column as practicable, and be continuous or spliced using mechanical or welded splices in accordance with 25.5.7 or Class B tension lap splices in accordance with 25.5.2. At exterior columns, the reinforcement shall be anchored at the lifting collar.

Notes



CHAPTER 9—BEAMS

CODE

COMMENTARY

9.1—Scope

9.1.1 This chapter shall apply to the design of nonprestressed and prestressed beams, including:

- (a) Composite beams of concrete elements constructed in separate placements but connected so that all elements resist loads as a unit
- (b) One-way joist systems in accordance with 9.8
- (c) Deep beams in accordance with 9.9

9.2—General**9.2.1 Materials**

9.2.1.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

9.2.1.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

9.2.1.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

9.2.2 Connection to other members

9.2.2.1 For cast-in-place construction, joints shall satisfy **Chapter 15**.

9.2.2.2 For precast construction, connections shall satisfy the force transfer requirements of **16.2**.

9.2.3 Stability

9.2.3.1 If a beam is not continuously laterally braced, (a) and (b) shall be satisfied:

- (a) Spacing of lateral bracing shall not exceed 50 times the least width of compression flange or face.
- (b) Spacing of lateral bracing shall take into account effects of eccentric loads.

9.2.3.2 In prestressed beams, buckling of thin webs and flanges shall be considered. If there is intermittent contact between prestressed reinforcement and an oversize duct, member buckling between contact points shall be considered.

R9.1—Scope

R9.1.1 Composite structural steel-concrete beams are not covered in this chapter. Design provisions for composite beams are covered in **ANSI/AISC 360**.

R9.2—General**R9.2.3 Stability**

R9.2.3.1 Tests (**Hansell and Winter 1959**; **Sant and Bletzacker 1961**) have shown that laterally unbraced reinforced concrete beams, even when very deep and narrow, will not fail prematurely by lateral buckling, provided the beams are loaded without lateral eccentricity that causes torsion.

If laterally unbraced beams are loaded eccentrically or with slight inclination, stresses and deformations from such loading can become detrimental for narrow, deep beams with long unsupported lengths. Lateral supports spaced closer than $50b$ may be required for such loading conditions.

R9.2.3.2 In post-tensioned beams where the prestressed reinforcement has intermittent contact with an oversize duct, the beam can buckle due to the axial prestressing force, as the beam can deflect laterally while the prestressed reinforcement does not. If the prestressed reinforcement is in continuous contact with the beam being prestressed or is part of an unbonded tendon with the sheathing not excessively larger than the prestressed reinforcement, the prestressing force cannot buckle the beam.

CODE

9.2.4 T-beam construction

9.2.4.1 In T-beam construction, flange and web concrete shall be placed monolithically or made composite in accordance with 16.4.

9.2.4.2 Effective flange width shall be in accordance with 6.3.2.

9.2.4.3 For T-beam flanges where the primary flexural slab reinforcement is parallel to the longitudinal axis of the beam, reinforcement in the flange perpendicular to the longitudinal axis of the beam shall be in accordance with 7.5.2.3.

9.2.4.4 For torsional design according to 22.7, the overhanging flange width used to calculate A_{cp} , A_g , and p_{cp} shall be in accordance with (a) and (b):

(a) The overhanging flange width shall include that portion of slab on each side of the beam extending a distance equal to the projection of the beam above or below the slab, whichever is greater, but not greater than four times the slab thickness.

(b) The overhanging flanges shall be neglected in cases where the parameter A_{cp}^2/p_{cp} for solid sections or A_g^2/p_{cp} for hollow sections calculated for a beam with flanges is less than that calculated for the same beam ignoring the flanges.

COMMENTARY

R9.2.4 T-beam construction

R9.2.4.1 For monolithic or composite concrete construction, the beam includes a portion of the slab as a flange.

R9.2.4.3 Refer to R7.5.2.3.

R9.2.4.4 Two examples of the section to be considered in torsional design are provided in Fig. R9.2.4.4.




Fig. R9.2.4.4—Examples of the portion of slab to be included with the beam for torsional design.

9.3—Design limits

9.3.1 Minimum beam depth

9.3.1.1 For nonprestressed beams not supporting or attached to partitions or other construction likely to be damaged by large deflections, overall beam depth h shall

R9.3—Design limits

R9.3.1 Minimum beam depth

Minimum depths in 9.3.1.1 are independent of loading. These minimum depths are not applicable to beams with unusually heavy superimposed sustained loads. Deflections should be calculated for such situations.

R9.3.1.1 For application of this provision to composite concrete beams, refer to R9.3.2.2.

CODE

satisfy the limits in Table 9.3.1.1, unless the calculated deflection limits of 9.3.2 are satisfied.

Table 9.3.1.1—Minimum depth of nonprestressed beams

Support condition	Minimum $h^{(1)}$
Simply supported	$\ell/16$
One end continuous	$\ell/18.5$
Both ends continuous	$\ell/21$
Cantilever	$\ell/8$

⁽¹⁾Expressions applicable for normalweight concrete and $f_y = 60,000$ psi. For other cases, minimum h shall be modified in accordance with 9.3.1.1.1 through 9.3.1.1.3, as appropriate.

9.3.1.1.1 For f_y other than 60,000 psi, the expressions in Table 9.3.1.1 shall be multiplied by $(0.4 + f_y/100,000)$.

9.3.1.1.2 For nonprestressed beams made of lightweight concrete having w_c in the range of 90 to 115 lb/ft³, the expressions in Table 9.3.1.1 shall be multiplied by the greater of (a) and (b):

- (a) $1.65 - 0.005w_c$
- (b) 1.09

9.3.1.1.3 For nonprestressed composite concrete beams made of a combination of lightweight and normalweight concrete, shored during construction, and where the lightweight concrete is in compression, the modifier of 9.3.1.1.2 shall apply.

9.3.1.2 The thickness of a concrete floor finish shall be permitted to be included in h if it is placed monolithically with the beam or if the floor finish is designed to be composite with the beam in accordance with 16.4.

9.3.2 Calculated deflection limits

9.3.2.1 For nonprestressed beams not satisfying 9.3.1 and for prestressed beams, immediate and time-dependent deflections shall be calculated in accordance with 24.2 and shall not exceed the limits in 24.2.2.

9.3.2.2 For nonprestressed composite concrete beams satisfying 9.3.1, deflections occurring after the member becomes composite need not be calculated. Deflections occurring before the member becomes composite shall be investigated unless the precomposite depth also satisfies 9.3.1.

COMMENTARY

R9.3.1.1.1 The modification for f_y should provide conservative results for typical reinforcement ratios and for values of f_y between 40,000 and 100,000 psi.

R9.3.1.1.2 The modification for lightweight concrete is based on the results and discussions in ACI PRC-213. No correction is given for concretes with w_c greater than 115 lb/ft³ because the correction term would be close to unity in this range.

R9.3.2 Calculated deflection limits

R9.3.2.2 The limits in Table 9.3.1.1 apply to the entire depth of nonprestressed composite concrete beams shored during construction so that, after removal of temporary supports, the dead load is resisted by the full composite section. In unshored construction, the beam depth of concern depends on if the deflection being considered occurs before or after the attainment of effective composite action.

Additional deflections due to excessive creep and shrinkage caused by premature loading should be considered. This is especially important at early ages when the moisture content is high and the strength is low.

CODE

9.3.3 Reinforcement strain limit in nonprestressed beams

9.3.3.1 Nonprestressed beams with $P_u < 0.10f'_cA_g$ shall be tension controlled in accordance with Table 21.2.2.

9.3.4 Stress limits in prestressed beams

9.3.4.1 Prestressed beams shall be classified as Class U, T, or C in accordance with 24.5.2.

9.3.4.2 Stresses in prestressed beams immediately after transfer and at service loads shall not exceed permissible stresses in 24.5.3 and 24.5.4.

9.4—Required strength**9.4.1 General**

9.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in Chapter 5.

9.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in Chapter 6.

9.4.1.3 For prestressed beams, effects of reactions induced by prestressing shall be considered in accordance with 5.3.14.

9.4.2 Factored moment

9.4.2.1 For beams built integrally with supports, M_u at the support shall be permitted to be calculated at the face of support.

9.4.3 Factored shear

9.4.3.1 For beams built integrally with supports, V_u at the support shall be permitted to be calculated at the face of support.

9.4.3.2 Sections between the face of support and a critical section located d from the face of support for nonprestressed beams and $h/2$ from the face of support for prestressed beams shall be permitted to be designed for V_u at that critical section if (a) through (c) are satisfied:

- (a) Support reaction, in direction of applied shear, introduces compression into the end region of the beam
- (b) Loads are applied at or near the top surface of the beam
- (c) No concentrated load occurs between the face of support and critical section

COMMENTARY

R9.3.3 Reinforcement strain limit in nonprestressed beams

R9.3.3.1 The effect of this limitation is to restrict the reinforcement ratio in nonprestressed beams to mitigate brittle flexural behavior in case of an overload. In the 2019 Code, the previous minimum strain limit of 0.004 for nonprestressed flexural members was replaced with the requirement that beams be tension-controlled.

R9.4—Required strength**R9.4.3 Factored shear**

R9.4.3.2 The closest inclined crack to the support of the beam in Fig. R9.4.3.2a will extend upward from the face of the support reaching the compression zone approximately d from the face of the support. If loads are applied to the top of the beam, the stirrups across this crack need only resist the shear force due to loads acting beyond d (right free body in Fig. R9.4.3.2a). Loads applied to the beam between the face of the support and the point d away from the face are transferred directly to the support by compression in the web above the crack. Accordingly, the Code permits design for a maximum factored shear V_u at a distance d from the

CODE

COMMENTARY

support for nonprestressed beams and at a distance $h/2$ for prestressed beams.

In Fig. R9.4.3.2b, loads are shown acting near the bottom of a beam. In this case, the critical section is taken at the face of the support. Loads acting near the support should be transferred across the inclined crack extending upward from the support face. The shear force acting on the critical section should include all loads applied below the potential inclined crack.

Typical support conditions where the shear force at a distance d from the support may be used include:

- (a) Beams supported by bearing at the bottom of the beam, such as shown in Fig. R9.4.3.2(c)
- (b) Beams framing monolithically into a column, as illustrated in Fig. R9.4.3.2(d)

Typical support conditions where the critical section is taken at the face of support include:

- (a) Beams framing into a supporting member in tension, such as shown in Fig. R9.4.3.2(e). Shear within the connection should also be investigated and special corner reinforcement should be provided.
- (b) Beams for which loads are not applied at or near the top, as shown in Fig. R9.4.3.2b.
- (c) Beams loaded such that the shear at sections between the support and a distance d from the support differs radically from the shear at distance d . This commonly occurs in brackets and in beams where a concentrated load is located close to the support, as shown in Fig. R9.4.3.2(f).




Fig. R9.4.3.2a—Free body diagrams of the end of a beam.

CODE

COMMENTARY




Fig. R9.4.3.2b—Location of critical section for shear in a beam loaded near bottom.




Fig. R9.4.3.2(c), (d), (e), (f)—Typical support conditions for locating factored shear force V_u .

9.4.4 Factored torsion

9.4.4.1 Unless determined by a more detailed analysis, it shall be permitted to take the torsional loading from a slab as uniformly distributed along the beam.

9.4.4.2 For beams built integrally with supports, T_u at the support shall be permitted to be calculated at the face of support.

9.4.4.3 Sections between the face of support and a critical section located d from the face of support for nonprestressed beams or $h/2$ from the face of support for prestressed beams shall be permitted to be designed for T_u at that critical section unless a concentrated torsional moment occurs within this distance. In that case, the critical section shall be taken at the face of the support.

R9.4.4 Factored torsion

R9.4.4.3 A beam framing into one side of a girder near its support causes a concentrated shear and torsional moment on the girder at that location.

CODE

9.4.4.4 It shall be permitted to reduce T_u in accordance with **22.7.3**.

9.5—Design strength**9.5.1 General**

9.5.1.1 For each applicable factored load combination, design strength at all sections shall satisfy $\phi S_n \geq U$ including (a) through (d). Interaction between load effects shall be considered.

- (a) $\phi M_n \geq M_u$
- (b) $\phi V_n \geq V_u$
- (c) $\phi T_n \geq T_u$
- (d) $\phi P_n \geq P_u$

9.5.1.2 ϕ shall be determined in accordance with **21.2**.

9.5.2 Moment

9.5.2.1 If $P_u < 0.10f_c'A_g$, M_n shall be calculated in accordance with **22.3**.

9.5.2.2 If $P_u \geq 0.10f_c'A_g$, M_n shall be calculated in accordance with **22.4**.

9.5.2.3 For prestressed beams, external tendons shall be considered as unbonded tendons in calculating flexural strength, unless the external tendons are effectively bonded to the concrete along the entire length.

9.5.3 Shear

9.5.3.1 V_n shall be calculated in accordance with **22.5**.

9.5.3.2 For composite concrete beams, horizontal shear strength V_{nh} shall be calculated in accordance with **16.4**.

9.5.4 Torsion

9.5.4.1 If $T_u < \phi T_{th}$, where T_{th} is given in **22.7**, it shall be permitted to neglect torsional effects. The minimum reinforcement requirements of 9.6.4 and the detailing requirements of 9.7.5 and 9.7.6.3 need not be satisfied.

9.5.4.2 T_n shall be calculated in accordance with **22.7**.

9.5.4.3 Longitudinal and transverse reinforcement required for torsion shall be added to that required for the V_u , M_u , and P_u that act in combination with the torsion.

COMMENTARY

R9.5—Design strength**R9.5.1 General**

R9.5.1.1 The general condition $\phi S_n \geq U$ indicates that all forces and moments that are relevant for a given structure need to be considered.

R9.5.2 Moment

R9.5.2.2 Beams resisting significant axial forces require consideration of the combined effects of axial forces and moments. These beams are not required to satisfy the provisions of **Chapter 10**, but are required to satisfy the requirements for ties or spirals defined in Table 22.4.2.1. For slender beams with significant axial loads, consideration should be given to slenderness effects as required for columns in **6.2.5**.

R9.5.4 Torsion

R9.5.4.3 The requirements for torsional reinforcement and shear reinforcement are added and stirrups are provided to supply at least the total amount required. Because the

CODE

COMMENTARY

reinforcement area A_v for shear is defined in terms of all the legs of a given stirrup while the reinforcement area A_t for torsion is defined in terms of one leg only, the addition of transverse reinforcement area is calculated as follows:

$$\text{Total} \left(\frac{A_{v+t}}{s} \right) = \frac{A_v}{s} + 2 \frac{A_t}{s} \quad (\text{R9.5.4.3})$$

If a stirrup group has more than two legs for shear, only legs adjacent to the sides of the beam are included in this summation because inner legs would be ineffective for resisting torsion.

Torsion causes an axial tensile force in the longitudinal reinforcement balanced by the force in the diagonal concrete compression struts. In a nonprestressed beam, the tensile force must be resisted by longitudinal reinforcement having an axial tensile strength of $A_t f_y$. This reinforcement is in addition to the required flexural reinforcement and is distributed uniformly inside and around the perimeter of the closed transverse reinforcement so that the resultant of $A_t f_y$ acts along the axis of the member.

The longitudinal reinforcement required for torsion is added at each section to the longitudinal reinforcement required for bending moment that acts concurrently with torsion. If the maximum bending moment occurs at one section, while the maximum torsional moment occurs at another, the total longitudinal reinforcement required may be less than that obtained by adding the maximum flexural reinforcement, plus the maximum torsional reinforcement. In such a case, the required longitudinal reinforcement should be evaluated at multiple locations.

9.5.4.4 For prestressed beams, the total area of longitudinal reinforcement, A_s and A_{ps} , at each section shall be designed to resist M_u at that section, plus an additional concentric longitudinal tensile force equal to $A_t f_y$, based on T_u at that section.

R9.5.4.4 In a prestressed beam, reinforcing bars with strength $A_t f_y$ may be added, or overstrength of the prestressed reinforcement can be used to resist some of the axial force $A_t f_y$. The stress in the prestressed reinforcement at nominal strength will be between f_{se} and f_{ps} . A portion of the $A_t f_y$ force can be resisted by a force of $A_{ps} \Delta f_{pt}$ in the prestressed reinforcement. The stress required to resist the bending moment can be calculated as $M_u / (\phi 0.9 d_p A_{ps})$. For pretensioned strands, the stress that can be developed near the free end of the strand can be calculated using the procedure illustrated in Fig. R25.4.8.3.

9.5.4.5 It shall be permitted to reduce the area of longitudinal torsional reinforcement in the flexural compression zone by an amount equal to $M_u / (0.9 d f_y)$, where M_u occurs simultaneously with T_u at that section, except that the longitudinal reinforcement area shall not be less than the minimum required in 9.6.4.

R9.5.4.5 Longitudinal tension due to torsion is offset in part by compression in the flexural compression zone, allowing a reduction in longitudinal torsional reinforcement required in the compression zone.

9.5.4.6 For solid sections with an aspect ratio $h/b_t \geq 3$, it shall be permitted to use an alternative design procedure, provided the adequacy of the procedure has been shown by analysis and substantial agreement with results of comprehensive tests. The minimum reinforcement requirements of

R9.5.4.6 An example of an alternative design that satisfies this provision can be found in [Zia and Hsu \(2004\)](#), which has been extensively used for design of precast, prestressed concrete spandrel beams with $h/b_t \geq 3$ and closed stirrups. The *PCI Design Handbook* ([PCI MNL-120](#)) describes

CODE

9.6.4 need not be satisfied, but the detailing requirements of 9.7.5 and 9.7.6.3 apply.

9.5.4.7 For solid precast sections with an aspect ratio $h/b_t \geq 4.5$, it shall be permitted to use an alternative design procedure and open web reinforcement, provided the adequacy of the procedure and reinforcement have been shown by analysis and substantial agreement with results of comprehensive tests. The minimum reinforcement requirements of 9.6.4 and detailing requirements of 9.7.5 and 9.7.6.3 need not be satisfied.

9.6—Reinforcement limits**9.6.1** *Minimum flexural reinforcement in nonprestressed beams*

9.6.1.1 A minimum area of flexural reinforcement, $A_{s,min}$, shall be provided at every section where tension reinforcement is required by analysis.

9.6.1.2 $A_{s,min}$ shall be the larger of (a) and (b), except as provided in 9.6.1.3. For a statically determinate beam with a flange in tension, the value of b_w shall be the smaller of b_f and $2b_w$. The value of f_y shall be limited to a maximum of 80,000 psi.

$$(a) \frac{3\sqrt{f'_c}}{f_y} b_w d$$

$$(b) \frac{200}{f_y} b_w d$$

9.6.1.3 If A_s provided at every section is at least one-third greater than A_s required by analysis, 9.6.1.1 and 9.6.1.2 need not be satisfied.

9.6.2 *Minimum flexural reinforcement in prestressed beams*

9.6.2.1 For beams with bonded prestressed reinforcement, total quantity of A_s and A_{ps} shall be adequate to develop a factored load at least 1.2 times the cracking load calculated on the basis of f_r defined in 19.2.3.

COMMENTARY

this procedure, which was experimentally verified by tests described in Klein (1986).

R9.5.4.7 Tests (Lucier et al. 2011a) demonstrate that properly designed open web reinforcement is an effective alternative to traditional closed stirrups for precast spandrels with $h/b_t \geq 4.5$. Lucier et al. (2011b) presents a design procedure that satisfies this provision for slender spandrels and describes the limited conditions to which the procedure applies.

R9.6—Reinforcement limits**R9.6.1** *Minimum flexural reinforcement in nonprestressed beams*

R9.6.1.1 This provision is intended to result in flexural strength exceeding the cracking strength by a margin. The objective is to produce a beam that will be able to sustain loading after the onset of flexural cracking, with visible cracking and deflection, thereby warning of possible overload. Beams with less reinforcement may sustain sudden failure with the onset of flexural cracking.

In practice, this provision controls reinforcement design only for beams with cross sections larger than those required for flexural strength. With a small amount of tension reinforcement required for strength, the calculated moment strength using cracked section analysis becomes less than that of the corresponding unreinforced concrete section calculated from its modulus of rupture. To prevent a sudden failure after cracking, a minimum amount of tension reinforcement is required in both positive and negative moment regions.

R9.6.1.2 If the flange of a section is in tension, the amount of tension reinforcement needed to make the strength of the reinforced section equal that of the unreinforced section is approximately twice that for a rectangular section or that of a flanged section with the flange in compression. A larger amount of minimum tension reinforcement is particularly necessary in cantilevers and other statically determinate beams where there is no possibility for redistribution of moments.

R9.6.2 *Minimum flexural reinforcement in prestressed beams*

R9.6.2.1 Minimum flexural reinforcement is required for reasons similar to those discussed in R9.6.1.1 for nonprestressed beams.

CODE

9.6.2.2 For beams with both flexural and shear design strength at least twice the required strength, 9.6.2.1 need not be satisfied.

9.6.2.3 For beams with unbonded tendons, the minimum area of bonded deformed longitudinal reinforcement $A_{s,min}$ shall be:

$$A_{s,min} = 0.004A_{ct} \quad (9.6.2.3)$$

where A_{ct} is the area of that part of the cross section between the flexural tension face and the centroid of the gross section.

9.6.3 Minimum shear reinforcement

9.6.3.1 For nonprestressed beams, minimum area of shear reinforcement, $A_{v,min}$, shall be provided in all regions where $V_u > \phi\lambda\sqrt{f_c'}b_wd$ except for the cases in Table 9.6.3.1. For these cases, at least $A_{v,min}$ shall be provided where $V_u > \phi V_c$.

Table 9.6.3.1—Cases where $A_{v,min}$ is not required if $V_u \leq \phi V_c$

Beam type	Conditions	
Shallow depth	$h \leq 10$ in.	(a)
Integral with slab	$h \leq$ greater of $2.5t_f$ or $0.5b_w$ and $h \leq 24$ in.	(b)
Constructed with steel fiber-reinforced concrete conforming to 26.4.1.6.1(a), 26.4.2.2(h), and 26.12.8.1(a) and $V_u < \phi V_c$, where V_c is computed in accordance with 22.5.5.1.4	For normalweight concrete with $f_c' < 10,000$ psi and Grade 60 or Grade 80 longitudinal reinforcement: $h \leq 40$ in.	(c)
	For lightweight concrete with $f_c' \leq 6000$ psi and Grade 60 longitudinal reinforcement: $h \leq 24$ in.	(d)
One-way joist system	In accordance with 9.8	(e)

COMMENTARY

Abrupt flexural failure immediately after cracking does not occur when the prestressed reinforcement is unbonded (ACI PRC-423.3); therefore, this requirement does not apply to members with unbonded tendons.

R9.6.2.3 Minimum bonded reinforcement is required by the Code in beams prestressed with unbonded tendons to ensure flexural behavior at ultimate beam strength, rather than tied arch behavior, to limit crack width and spacing at service load when concrete tensile stresses exceed the modulus of rupture, and to ensure acceptable behavior at all loading stages. The minimum amount of bonded reinforcement is based on research comparing the behavior of bonded and unbonded post-tensioned beams (Mattock et al. 1971) and is independent of reinforcement f_y .

R9.6.3 Minimum shear reinforcement

R9.6.3.1 Shear reinforcement restrains the growth of inclined cracking so that ductility of the beam is improved and a warning of failure is provided. In an unreinforced web, the formation of inclined cracking might lead directly to failure without warning. Such reinforcement is of great value if a beam is subjected to an unexpected tensile force or overload.

The exception for beams constructed using steel fiber-reinforced concrete is intended to provide a design alternative to the use of shear reinforcement, as defined in 22.5.8.5, for beams with longitudinal flexural reinforcement in which V_u does not exceed ϕV_c , where V_c is the greater of Eq. (a) and 1.3 times Eq. (b) of Table 22.5.5.1. Chapter 26 specifies design information and compliance requirements that need to be incorporated into the construction documents when steel fiber-reinforced concrete is used for this purpose. Fiber-reinforced concrete beams with hooked or crimped steel fibers, in dosages as required by 26.4.2.2(h), have been shown through laboratory tests to exhibit shear strengths greater than $3.5\sqrt{f_c'}b_wd$ (Parra-Montesinos 2006). Shear strengths exceeding V_c can be obtained in steel fiber-reinforced concrete beams without stirrups meeting the criteria in Rows (c) and (d) of Table 9.6.3.1. A smaller depth and a concrete strength limit of 6000 psi for lightweight concrete used in steel fiber-reinforced concrete beams are specified due to limited experimental data (Shoab et al. 2014; Zarrin-pour and Chao 2017). There are no data for the use of steel fibers as shear reinforcement in concrete beams exposed to chlorides from deicing chemicals, salt, salt water, brackish water, seawater, or spray from these sources. Where steel fibers are used as shear reinforcement in corrosive environments, corrosion protection should be considered.

Joists are excluded from the minimum shear reinforcement requirement as indicated because there is a possibility of load sharing between weak and strong areas.

For repeated loading of beams, the possibility of inclined diagonal tension cracks forming at stresses smaller than

CODE

9.6.3.2 For prestressed beams, a minimum area of shear reinforcement, $A_{v,min}$, shall be provided in all regions where $V_u > 0.5\phi V_c$ except for the cases in Table 9.6.3.1. For these cases, at least $A_{v,min}$ shall be provided where $V_u > \phi V_c$.

9.6.3.3 If shown by testing that the required M_n and V_n can be developed, 9.6.3.1 and 9.6.3.2 need not be satisfied. Such tests shall simulate effects of differential settlement, creep, shrinkage, and temperature change, based on a realistic assessment of these effects occurring in service.

9.6.3.4 If shear reinforcement is required and torsional effects can be neglected according to 9.5.4.1, $A_{v,min}$ shall be in accordance with Table 9.6.3.4.

Table 9.6.3.4—Required $A_{v,min}$

Beam type	$A_{v,min}/s$	
Nonprestressed and prestressed with $A_{ps}f_{se} < 0.4(A_{ps}f_{pu} + A_s f_y)$	Greater of:	$0.75 \sqrt{f_c} \frac{b_w}{f_{yt}}$ (a)
		$50 \frac{b_w}{f_{yt}}$ (b)
Prestressed with $A_{ps}f_{se} \geq 0.4(A_{ps}f_{pu} + A_s f_y)$	Lesser of:	Greater of: $0.75 \sqrt{f_c} \frac{b_w}{f_{yt}}$ (c)
		$50 \frac{b_w}{f_{yt}}$ (d)
		$\frac{A_{ps}f_{pu}}{80f_{yt}d} \sqrt{\frac{d}{b_w}}$ (e)

COMMENTARY

under static loading should be taken into account in design. In these instances, use of at least the minimum shear reinforcement expressed by 9.6.3.4 is recommended even though tests or calculations based on static loads show that shear reinforcement is not required.

R9.6.3.2 Even when V_u is less than $0.5\phi V_c$, the use of some web reinforcement is recommended in all thin-web, post-tensioned members such as joists, waffle slabs, beams, and T-beams, to reinforce against tensile forces in webs resulting from local deviations from the design tendon profile and to provide a means of supporting the tendons during construction. If sufficient support is not provided, lateral wobble and local deviations from the parabolic tendon profile assumed in design may result during placement of the concrete. In such cases, deviations in the tendons tend to straighten out when tendons are stressed. This process may impose large tensile stresses in webs, and severe cracking may develop if no web reinforcement is provided. Unintended curvature of tendons, and resulting tensile stresses in webs, may be minimized by securely tying tendons to stirrups that are rigidly held in place by other elements of the reinforcement cage. The recommended maximum spacing of stirrups used for this purpose is the smaller of $1.5h$ or 4 ft. If applicable, the shear reinforcement provisions of 9.6.3 and 9.7.6.2.2 will require closer stirrup spacings.

R9.6.3.3 When a beam is tested to demonstrate that its shear and flexural strengths are adequate, the test strengths are considered the nominal strengths V_n and M_n . Considering these strengths as nominal values ensures that if actual material strengths in the field were less than specified, or the member dimensions were in error such as to result in a reduced member strength, a satisfactory margin of safety will be retained due to the strength reduction factor ϕ .

R9.6.3.4 Tests (Roller and Russell 1990) have indicated the need to increase the minimum area of shear reinforcement as concrete strength increases to prevent sudden shear failures when inclined cracking occurs. Therefore, expressions (a) and (c) in Table 9.6.3.4 provide for a gradual increase in the minimum area of transverse reinforcement with increasing concrete strength. Expressions (b) and (d) in Table 9.6.3.4 provide for a minimum area of transverse reinforcement independent of concrete strength and govern for concrete strengths less than 4400 psi.

Tests (Olesen et al. 1967) of prestressed beams with minimum web reinforcement based on 9.6.3.4 indicate that the lesser of $A_{v,min}$ from expressions (c) and (e) is sufficient to develop ductile behavior. Expression (e) is discussed in Olesen et al. (1967).

CODE**9.6.4 Minimum torsional reinforcement**

9.6.4.1 A minimum area of torsional reinforcement shall be provided in all regions where $T_u \geq \phi T_{th}$ in accordance with 22.7.

9.6.4.2 If torsional reinforcement is required, minimum transverse reinforcement $(A_v + 2A_t)_{min}/s$ shall be the greater of (a) and (b):

$$(a) 0.75 \sqrt{f'_c} \frac{b_w}{f_{yt}}$$

$$(b) 50 \frac{b_w}{f_{yt}}$$

9.6.4.3 If torsional reinforcement is required, minimum area of longitudinal reinforcement $A_{l,min}$ shall be the lesser of (a) and (b):

$$(a) \frac{5\sqrt{f'_c} A_{cp}}{f_y} - \left(\frac{A_t}{s} \right) p_h \frac{f_{yt}}{f_y}$$

$$(b) \frac{5\sqrt{f'_c} A_{cp}}{f_y} - \left(\frac{25b_w}{f_{yt}} \right) p_h \frac{f_{yt}}{f_y}$$

COMMENTARY**R9.6.4 Minimum torsional reinforcement**

R9.6.4.2 Although there are a limited number of tests of high-strength concrete beams in torsion, the equation for the minimum area of transverse closed stirrups has been made consistent with calculations required for minimum shear reinforcement discussed in R9.6.3.4.

R9.6.4.3 Under combined torsion and shear, the torsional cracking moment decreases with applied shear, which leads to a reduction in torsional reinforcement required to prevent brittle failure immediately after cracking. When subjected to pure torsion, reinforced concrete beam specimens with less than 1 percent torsional reinforcement by volume have failed at first torsional cracking (MacGregor and Ghoneim 1995). Equation 9.6.4.3(a) is based on a 2:1 ratio of torsion stress to shear stress and results in a torsional reinforcement volumetric ratio of approximately 0.5 percent (Hsu 1968). Tests of prestressed concrete beams have shown that a similar amount of longitudinal reinforcement is required.

9.7—Reinforcement detailing**9.7.1 General**

9.7.1.1 Concrete cover for reinforcement shall be in accordance with 20.5.1.

9.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with 25.4.

9.7.1.3 Splices of deformed reinforcement shall be in accordance with 25.5.

9.7.1.4 Along development and lap splice lengths of longitudinal bars with $f_y \geq 80,000$ psi, transverse reinforcement shall be provided such that K_{tr} shall not be smaller than $0.5d_b$.

9.7.1.5 Bundled bars shall be in accordance with 25.6.

9.7.2 Reinforcement spacing

9.7.2.1 Minimum spacings shall be in accordance with 25.2.

9.7.2.2 For nonprestressed and Class C prestressed beams, spacing of bonded longitudinal reinforcement closest to the tension face shall not exceed s given in 24.3.

R9.7—Reinforcement detailing**R9.7.2 Reinforcement spacing**

CODE

9.7.2.3 For nonprestressed and Class C prestressed beams with h exceeding 36 in., longitudinal skin reinforcement shall be uniformly distributed on both side faces of the beam for a distance $h/2$ from the tension face. Spacing of skin reinforcement shall not exceed s given in 24.3.2, where c_c is the clear cover from the skin reinforcement to the side face. It shall be permitted to include skin reinforcement in strength calculations if a strain compatibility analysis is made.

COMMENTARY

R9.7.2.3 For relatively deep beams, skin reinforcement should be placed near vertical faces of the tension zone to control cracking in the web (Frantz and Breen 1980; Frosch 2002), as shown in Fig. R9.7.2.3. Without skin reinforcement, the width of cracks in the web may exceed the crack widths at the level of the flexural tension reinforcement.

The size of skin reinforcement is not specified; research has indicated that the spacing rather than bar size is of primary importance (Frosch 2002). Bar sizes No. 3 to No. 5, or welded wire reinforcement with a minimum area of 0.1 in.^2 per foot of depth, are typically provided.




Fig. R9.7.2.3—Skin reinforcement for beams and joists with $h > 36 \text{ in.}$

9.7.3 Flexural reinforcement in nonprestressed beams

9.7.3.1 Calculated tensile or compressive force in reinforcement at each section of the beam shall be developed on each side of that section.

9.7.3.2 Critical locations for development of reinforcement are points of maximum stress and points along the span where bent or terminated tension reinforcement is no longer required to resist flexure.

R9.7.3 Flexural reinforcement in nonprestressed beams

R9.7.3.2 Critical sections for a typical continuous beam are indicated with a “c” for points of maximum stress or an “x” for points where bent or terminated tension reinforcement is no longer required to resist flexure (Fig. R9.7.3.2). For uniform loading, the positive reinforcement extending into the support is more likely governed by the requirements of 9.7.3.8.1 or 9.7.3.8.3 than by development length measured from a point of maximum moment or the bar cutoff point.

CODE

COMMENTARY




Fig. R9.7.3.2—Development of flexural reinforcement in a typical continuous beam.

9.7.3.3 Reinforcement shall extend beyond the point at which it is no longer required to resist flexure for a distance equal to the greater of d and $12d_b$, except at supports of simply-supported spans and at free ends of cantilevers.

R9.7.3.3 Moment diagrams customarily used in design are approximate; some shifting of the location of maximum moments may occur due to changes in loading, settlement of supports, lateral loads, or other causes. A diagonal tension crack in a flexural member without stirrups may shift the location of the calculated tensile stress approximately a distance d toward a point of zero moment. If stirrups are provided, this effect is less severe, although still present to some extent.

To provide for shifts in the location of maximum moments, the Code requires the extension of reinforcement a distance d or $12d_b$ beyond the point at which it is calculated to be no longer required to resist flexure, except as noted. Cutoff points of bars to meet this requirement are illustrated in Fig. R9.7.3.2. If different bar sizes are used, the extension should be in accordance with the diameter of the bar being terminated.

9.7.3.4 Continuing flexural tension reinforcement shall have an embedment length at least ℓ_d beyond the point where bent or terminated tension reinforcement is no longer required to resist flexure.

R9.7.3.4 Local peak stresses exist in the remaining bars wherever adjacent bars are cut off in tension regions. In Fig. R9.7.3.2, an “x” is used to indicate the point where terminated tension reinforcement is no longer required to resist flexure. If bars were cut off at this location (the required cutoff point is beyond location “x” in accordance with 9.7.3.3), peak stresses in the continuing reinforcement (bars b) would reach f_y at “x”. Therefore, the continuing reinforcement is required to have a full ℓ_d extension as indicated.

CODE

9.7.3.5 Flexural tension reinforcement shall not be terminated in a tension zone unless (a), (b), or (c) is satisfied:

- (a) $V_u \leq (2/3)\phi V_n$ at the cutoff point
- (b) For No. 11 bars and smaller, continuing reinforcement provides double the area required for flexure at the cutoff point and $V_u \leq (3/4)\phi V_n$
- (c) Stirrup or hoop area in excess of that required for shear and torsion is provided along each terminated bar or wire over a distance $(3/4)d$ from the cutoff point. Excess stirrup or hoop area shall be at least $60b_w s/f_{yt}$. Spacing s shall not exceed $d/(8\beta_b)$

9.7.3.6 Adequate anchorage shall be provided for tension reinforcement where reinforcement stress is not directly proportional to moment, such as in sloped, stepped, or tapered beams, or where tension reinforcement is not parallel to the compression face.

9.7.3.7 Development of tension reinforcement by bending across the web to be anchored or made continuous with reinforcement on the opposite face of beam shall be permitted.

9.7.3.8 Termination of reinforcement

9.7.3.8.1 At simple supports, at least one-third of the maximum positive moment reinforcement shall extend along the beam bottom into the support at least 6 in., except for precast beams where such reinforcement shall extend at least to the center of the bearing length.

9.7.3.8.2 At other supports, at least one-fourth of the maximum positive moment reinforcement shall extend along the beam bottom into the support at least 6 in. and, if the beam is part of the primary lateral-load-resisting system, shall develop f_y in tension at the face of the support.

9.7.3.8.3 At simple supports and points of inflection, d_b for positive moment tension reinforcement shall be limited such that ℓ_d for that reinforcement satisfies (a) or (b). If reinforcement terminates beyond the centerline of supports by a standard hook, head, or mechanical anchorage in accordance with 25.4.5, (a) or (b) need not be satisfied.

- (a) $\ell_d \leq (1.3M_n/V_u + \ell_a)$ if end of reinforcement is confined by a compressive reaction
- (b) $\ell_d \leq (M_n/V_u + \ell_a)$ if end of reinforcement is not confined by a compressive reaction

M_n is calculated assuming all reinforcement at the section is stressed to f_y , and V_u is calculated at the section. At a support, ℓ_a is the embedment length beyond the center of the

COMMENTARY

R9.7.3.5 Reduced shear strength and loss of ductility can occur where bars are cut off in a tension zone, such as in Fig. R9.7.3.2 (Ferguson and Matloob 1959). Flexural cracks tend to open at low load levels wherever any reinforcement is terminated in a tension zone. If stress in the continuing reinforcement and shear strength are each near their limiting values, diagonal tension cracking tends to develop prematurely from these flexural cracks. Diagonal cracks are less likely to form where shear stress is low (9.7.3.5(a)) or flexural reinforcement stress is low (9.7.3.5(b)). Diagonal cracks can be restrained by closely spaced stirrups (9.7.3.5(c)). These requirements are not intended to apply to tension splices that are covered by 25.5.

R9.7.3.7 A bar bent to the far face of a beam and continued there may be considered effective in satisfying 9.7.3.3 to the point where the bar crosses the mid-depth of the member.

R9.7.3.8 Termination of reinforcement

R9.7.3.8.1 Positive moment reinforcement is extended into the support to provide for shifting of moments due to changes in loading, settlement of supports, and lateral loads. It also enhances structural integrity.

For precast beams, tolerances and reinforcement cover should be considered to avoid bearing on plain concrete where reinforcement has been discontinued.

R9.7.3.8.2 Development of positive moment reinforcement at the support is required for beams that are part of the primary lateral-load-resisting system to provide ductility in the event of moment reversal.

R9.7.3.8.3 The diameter of positive moment tension reinforcement is limited to ensure that the bars are developed in a length short enough such that the moment capacity is greater than the applied moment over the entire length of the beam. As illustrated in the moment diagram of Fig. R9.7.3.8.3(a), the slope of the moment diagram is V_u , while the slope of moment development is M_n/ℓ_d , where M_n is the nominal flexural strength of the cross section. By sizing reinforcement such that the capacity slope M_n/ℓ_d equals or exceeds the demand slope V_u , proper development is provided. Therefore, M_n/V_u represents the available development length. Under favorable support conditions, a 30% increase for M_n/V_u is permitted when the ends of reinforcement are confined by a compressive reaction.

CODE

support. At a point of inflection, ℓ_a is the embedment length beyond the point of inflection limited to the greater of d and $12d_b$.

COMMENTARY


Application of this provision is illustrated in Fig. R9.7.3.8.3(b) for simple supports and in Fig. R9.7.3.8.3(c) for points of inflection.

The ℓ_a limitation at points of inflection is provided because test data are not available to show that a long end anchorage length will be effective in developing a bar that has only a short length between a point of inflection and a point of maximum stress.



CODE


COMMENTARY



Capacity slope $\left(\frac{M_n}{\ell_d}\right) \geq$ Demand slope (V_u)


$$\ell_d \leq \frac{M_n}{V_u}$$

(a) Positive M_u Diagram



Note: The 1.3 factor is applicable only if the reaction confines the ends of the reinforcement

(b) Maximum ℓ_d at simple support



(c) Maximum ℓ_d for bars "a" at point of inflection

Fig. R9.7.3.8.3—Determination of maximum bar size according to 9.7.3.8.3.

9.7.3.8.4 At least one-third of the negative moment reinforcement at a support shall have an embedment length beyond the point of inflection at least the greatest of d , $12d_b$, and $\ell_n/16$.

CODE

9.7.4 Flexural reinforcement in prestressed beams

9.7.4.1 External tendons shall be attached to the member in a manner that maintains the specified eccentricity between the tendons and the concrete centroid through the full range of anticipated member deflections.

9.7.4.2 If nonprestressed reinforcement is required to satisfy flexural strength, the detailing requirements of 9.7.3 shall be satisfied.

9.7.4.3 Termination of prestressed reinforcement

9.7.4.3.1 Post-tensioned anchorage zones shall be designed and detailed in accordance with 25.9.

9.7.4.3.2 Post-tensioning anchorages and couplers shall be designed and detailed in accordance with 25.8.

9.7.4.4 Termination of deformed reinforcement in beams with unbonded tendons

9.7.4.4.1 Length of deformed reinforcement required by 9.6.2.3 shall be in accordance with (a) and (b):

- (a) At least $\ell_n/3$ in positive moment areas and be centered in those areas
- (b) At least $\ell_n/6$ on each side of the face of support in negative moment areas

9.7.5 Longitudinal torsional reinforcement

9.7.5.1 If torsional reinforcement is required, longitudinal torsional reinforcement shall be distributed around the perimeter of closed stirrups that satisfy 25.7.1.6 or hoops with a spacing not greater than 12 in. The longitudinal reinforcement shall be inside the stirrup or hoop, and at least one longitudinal bar or tendon shall be placed in each corner.

9.7.5.2 Longitudinal torsional reinforcement shall have a diameter at least 0.042 times the transverse reinforcement spacing, but not less than 3/8 in.

9.7.5.3 Longitudinal torsional reinforcement shall extend for a distance of at least $(b_t + d)$ beyond the point required by analysis.

COMMENTARY

R9.7.4 Flexural reinforcement in prestressed beams

R9.7.4.1 External tendons are often attached to the concrete beam at various locations between anchorages, such as midspan, quarter points, or third points, for desired load balancing effects, for tendon alignment, or to address tendon vibration concerns. Consideration should be given to effects caused by the tendon profile shifting in relationship to the concrete centroid as the member deforms under effects of post-tensioning and applied load.

R9.7.4.2 The requirements of 9.7.3 provide that bonded reinforcement required for flexural strength under factored loads is developed to achieve tensile or compressive forces.

R9.7.4.4 Termination of deformed reinforcement in beams with unbonded tendons

R9.7.4.4.1 Research (Odello and Mehta 1967) on continuous spans shows that minimum lengths required by 9.6.2.3 provide satisfactory behavior under service load and factored load conditions.

R9.7.5 Longitudinal torsional reinforcement

R9.7.5.1 Longitudinal reinforcement is needed to resist the sum of the longitudinal tensile forces due to torsion. The centroid of the additional longitudinal reinforcement for torsion should approximately coincide with the centroid of the section. The Code accomplishes this by requiring the longitudinal torsional reinforcement be distributed around the perimeter of the closed stirrups. Longitudinal bars or tendons are required in each corner of the stirrups to provide anchorage for the stirrup legs. Corner bars have also been found to be effective in developing torsional strength and controlling cracks.

R9.7.5.3 The distance $(b_t + d)$ beyond the point at which longitudinal torsional reinforcement is no longer required is greater than that used for shear and flexural reinforcement.

CODE

9.7.5.4 Longitudinal torsional reinforcement shall be developed at the face of the support at both ends of the beam.

9.7.6 Transverse reinforcement

9.7.6.1 General

9.7.6.1.1 Transverse reinforcement shall be in accordance with this section. The most restrictive requirements shall apply.

9.7.6.1.2 Details of transverse reinforcement shall be in accordance with 25.7.

9.7.6.2 Shear

9.7.6.2.1 If required, shear reinforcement shall be provided using stirrups, hoops, or longitudinal bent bars.

COMMENTARY

ment because torsional diagonal tension cracks develop in a helical form. The same distance is required by 9.7.6.3.2 for transverse torsional reinforcement.

R9.7.5.4 Development length should be provided beyond the interior face of the support. For bars, this may require hooks or heads. Alternatively, horizontal U-shaped bars may be lapped with the longitudinal torsional reinforcement.

R9.7.6 Transverse reinforcement

R9.7.6.2 Shear

R9.7.6.2.1 If a reinforced concrete beam is cast monolithically with a supporting beam and intersects one or both side faces of a supporting beam, the soffit of the supporting beam may be subject to premature failure unless additional transverse reinforcement, commonly referred to as hanger reinforcement, is provided (Mattock and Shen 1992). The hanger reinforcement (Fig. R9.7.6.2.1), placed in addition to other transverse reinforcement, is provided to transfer shear from the end of the supported beam. Research indicates that if the bottom of the supported beam is at or above middepth of the supporting beam or if the factored shear transferred from the supported beam is less than $3\sqrt{f'_c}b_wd$, hanger reinforcement is not required.




Fig. R9.7.6.2.1—Hanger reinforcement for shear transfer.

CODE

9.7.6.2.2 Maximum spacing of legs of shear reinforcement along the length of the member and across the width of the member shall be in accordance with Table 9.7.6.2.2.

Table 9.7.6.2.2—Maximum spacing of legs of shear reinforcement

Required V_s	Maximum s , in.				
		Nonprestressed beam		Prestressed beam	
		Along length	Across width	Along length	Across width
$\leq 4\sqrt{f_c'} b_w d$	Lesser of:	$d/2$	d	$3h/4$	$3h/2$
		24 in.			
$> 4\sqrt{f_c'} b_w d$	Lesser of:	$d/4$	$d/2$	$3h/8$	$3h/4$
		12 in.			

9.7.6.2.3 Inclined stirrups and longitudinal bars bent to act as shear reinforcement shall be spaced so that every 45-degree line, extending $d/2$ toward the reaction from mid-depth of member to longitudinal tension reinforcement, shall be crossed by at least one line of shear reinforcement.

9.7.6.2.4 Longitudinal bars bent to act as shear reinforcement, if extended into a region of tension, shall be continuous with longitudinal reinforcement and, if extended into a region of compression, shall be anchored $d/2$ beyond mid-depth of member.

9.7.6.3 Torsion

9.7.6.3.1 If required, transverse torsional reinforcement shall be closed stirrups satisfying 25.7.1.6 or hoops.

9.7.6.3.2 Transverse torsional reinforcement shall extend a distance of at least $(b_t + d)$ beyond the point required by analysis.

9.7.6.3.3 Spacing of transverse torsional reinforcement shall not exceed the lesser of $p_h/8$ and 12 in.

9.7.6.3.4 For hollow sections, the distance from the centerline of the transverse torsional reinforcement to the inside face of the wall of the hollow section shall be at least $0.5A_{oh}/p_h$.

COMMENTARY

R9.7.6.2.2 Reduced stirrup spacing across the beam width provides a more uniform transfer of diagonal compression across the beam web, enhancing shear capacity. Laboratory tests (Leonhardt and Walther 1964; Anderson and Ramirez 1989; Lubell et al. 2009) of wide members with large spacing of legs of shear reinforcement across the member width indicate that the nominal shear capacity is not always achieved. The intent of this provision is to provide multiple stirrup legs across wide beams and one-way slabs that require stirrups.

R9.7.6.3 Torsion

R9.7.6.3.1 Stirrups are required to be closed because inclined cracking due to torsion may occur on all faces of a member, and because the concrete cover spalls off at high torsional moments. Guidance on designing stirrups for torsion is provided in R25.7.1.6.

R9.7.6.3.2 The distance $(b_t + d)$ beyond the point at which transverse torsional reinforcement is no longer required is greater than that used for shear and flexural reinforcement because torsional diagonal tension cracks develop in a helical form. The same distance is required by 9.7.5.3 for longitudinal torsional reinforcement.

R9.7.6.3.3 Spacing of transverse torsional reinforcement is limited to ensure development of torsional strength of the beam, prevent excessive loss of torsional stiffness after cracking, and control crack widths. For a square cross section, the $p_h/8$ limitation requires stirrups at approximately $d/2$, which corresponds to 9.7.6.2.

R9.7.6.3.4 Transverse torsional reinforcement in a hollow section should be located in the outer half of the wall thickness effective for torsion where the wall thickness can be taken as A_{oh}/p_h .

CODE**9.7.6.4 Lateral support of compression reinforcement**

9.7.6.4.1 Transverse reinforcement shall be provided throughout the distance where longitudinal compression reinforcement is required. Lateral support of longitudinal compression reinforcement shall be provided by closed stirrups or hoops in accordance with 9.7.6.4.2 through 9.7.6.4.4.

9.7.6.4.2 Size of transverse reinforcement shall be at least (a) or (b). Deformed wire or welded wire reinforcement of equivalent area shall be permitted.

- (a) No. 3 for longitudinal bars No. 10 and smaller
- (b) No. 4 for longitudinal bars No. 11 and larger and for longitudinal bundled bars

9.7.6.4.3 Spacing of transverse reinforcement shall not exceed the least of (a) through (c):

- (a) $16d_b$ of longitudinal reinforcement
- (b) $48d_b$ of transverse reinforcement
- (c) Least dimension of beam

9.7.6.4.4 Longitudinal compression reinforcement shall be arranged such that every corner and alternate compression bar shall be enclosed by the corner of the transverse reinforcement with an included angle of not more than 135 degrees, and no bar shall be farther than 6 in. clear on each side along the transverse reinforcement from such an enclosed bar.

9.7.7 Structural integrity reinforcement in cast-in-place beams**COMMENTARY****R9.7.6.4 Lateral support of compression reinforcement**

R9.7.6.4.1 Compression reinforcement in beams should be enclosed by transverse reinforcement to prevent buckling.

R9.7.7 Structural integrity reinforcement in cast-in-place beams

Experience has shown that overall integrity of a structure can be substantially enhanced by minor changes in detailing of reinforcement and connections. It is the intent of this section of the Code to improve redundancy and ductility in structures so that in the event of damage to a major supporting element or an abnormal loading event, resulting damage may be localized and the structure will have a higher probability of maintaining overall stability.

With damage to a support, top reinforcement that is continuous over the support, but not confined by stirrups, will tend to tear out of the concrete and will not provide the catenary action required to bridge the damaged support. By making a portion of the bottom reinforcement continuous, catenary action can be provided.

If the depth of a continuous beam changes at a support, bottom reinforcement in the deeper member should be terminated into the support with a standard hook or headed bar to develop in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y and the bottom reinforcement in the shallower member should also extend into the joint and be similarly developed.

CODE

9.7.7.1 For beams along the perimeter of the structure, structural integrity reinforcement shall be in accordance with (a) through (c):

- (a) At least one-fourth of the maximum positive moment reinforcement, but not less than two bars or strands, shall be continuous
- (b) At least one-sixth of the negative moment reinforcement at the support, but not less than two bars or strands, shall be continuous
- (c) Longitudinal structural integrity reinforcement shall be enclosed by closed stirrups in accordance with 25.7.1.6 or hoops along the clear span of the beam with a spacing not greater than $d/2$ for nonprestressed beams or $3h/4$ for prestressed beams. At each supported end of the beam, the closed stirrup or hoop spacing shall not exceed the least of (i) through (iv) over a length of at least $2h$ from the face of the support.
 - (i) $d/4$ for nonprestressed beams or $3h/8$ for prestressed beams
 - (ii) $8d_b$ of the smallest longitudinal bar enclosed
 - (iii) $24d_b$ of the closed stirrup or hoop
 - (iv) 12 in.

9.7.7.2 For other than perimeter beams, structural integrity reinforcement shall be in accordance with (a) or (b):

- (a) At least one-quarter of the maximum positive moment reinforcement, but not less than two bars or strands, shall be continuous.
- (b) Longitudinal reinforcement shall be enclosed by closed stirrups in accordance with 25.7.1.6 or hoops along the clear span of the beam.

9.7.7.3 Longitudinal structural integrity reinforcement shall pass through the region bounded by the longitudinal reinforcement of the column.

9.7.7.4 Longitudinal structural integrity reinforcement at noncontinuous supports shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at the face of the support.

9.7.7.5 If splices are necessary in continuous structural integrity reinforcement, the reinforcement shall be spliced in accordance with (a) and (b):

COMMENTARY

Development of bottom bars for structural integrity is clarified in the 2025 Code to develop $1.25f_y$, recognizing that standard development is intended to develop the specified f_y .

R9.7.7.1 Requiring continuous top and bottom reinforcement in perimeter or spandrel beams provides a continuous tie around the structure. One-half of the top flexural reinforcement is required to extend past the point of inflection by 9.7.3.8.4 and be further extended and spliced at or near midspan as required by 9.7.7.5. Similarly, the bottom reinforcement required to extend into the support in 9.7.3.8.2 should be made continuous or spliced with bottom reinforcement from the adjacent span. At noncontinuous supports, longitudinal reinforcement is anchored as required by 9.7.7.4.

The spacing limits of transverse reinforcement enclosing integrity reinforcement are intended to allow beams to accommodate the rotational demands associated with large vertical displacements that occur after the unintended loss of a vertical-load-carrying member. Tests by [Rivera-Cruz et al. \(2021\)](#) demonstrated that beams with spacing of transverse reinforcement in compliance with SDC A or B may form wide diagonal cracks in the hinge region that limit the rotational capacity of beams experiencing large vertical displacements. Beams with spacing of transverse reinforcement in compliance with the requirements for SDC C through F were observed to develop end rotations associated with large vertical displacements, allowing the development of alternate load paths after loss of a vertical load carrying member ([Lew et al. 2014](#)).

R9.7.7.2 At noncontinuous supports, longitudinal reinforcement is anchored as required by 9.7.7.4.

R9.7.7.3 In the case of walls providing vertical support, longitudinal reinforcement should pass through or be anchored in the wall.

CODE

- (a) Positive moment reinforcement shall be spliced at or near the support
- (b) Negative moment reinforcement shall be spliced at or near midspan

9.7.7.6 Splices shall be mechanical or welded in accordance with **25.5.7** or Class B tension lap splices in accordance with **25.5.2**.

9.8—Nonprestressed one-way joist systems**9.8.1 General**

9.8.1.1 Nonprestressed one-way joist construction consists of a monolithic combination of regularly spaced ribs and a top slab designed to span in one direction.

9.8.1.2 Width of ribs shall be at least 4 in. at any location along the depth.

9.8.1.3 Overall depth of ribs, excluding slab thickness, shall not exceed 3.5 times the minimum width.

9.8.1.4 Clear spacing between ribs shall not exceed 30 in.

9.8.1.5 V_c shall be permitted to be taken as 1.1 times the value calculated in **22.5**.

9.8.1.6 For structural integrity, at least one bottom bar in each joist shall be continuous and shall be developed in tension in accordance with **25.4** by substituting a bar stress of $1.25f_y$ for f_y at the face of supports.

9.8.1.7 Reinforcement perpendicular to the ribs shall be provided in the slab as required for flexure, considering load concentrations, and shall be at least that required for shrinkage and temperature in accordance with **24.4**.

9.8.1.8 One-way joist construction not satisfying the limitations of 9.8.1.1 through 9.8.1.4 shall be designed as slabs and beams.

COMMENTARY**R9.8—Nonprestressed one-way joist systems****R9.8.1 General**

Empirical limits established for nonprestressed reinforced concrete joist floors are based on successful past performance of joist construction using common joist forming systems. For prestressed joist construction, this section may be used as a guide.

R9.8.1.4 A limit on maximum spacing of ribs is required because of provisions permitting higher shear strengths and less concrete cover for the reinforcement for these relatively small, repetitive members.

R9.8.1.5 This increase in shear strength is justified on the basis of: 1) satisfactory performance of joist construction designed with higher calculated shear strengths specified in previous Codes which allowed comparable shear stresses; and 2) potential for redistribution of local overloads to adjacent joists.

CODE

9.8.2 Joist systems with structural fillers

9.8.2.1 If permanent burned clay or concrete tile fillers of material having a unit compressive strength at least equal to f'_c in the joists are used, 9.8.2.1.1 and 9.8.2.1.2 shall apply.

9.8.2.1.1 Slab thickness over fillers shall be at least the greater of one-twelfth the clear distance between ribs and 1.5 in.

9.8.2.1.2 For calculation of shear and negative moment strength, it shall be permitted to include the vertical shells of fillers in contact with the ribs. Other portions of fillers shall not be included in strength calculations.

9.8.3 Joist systems with other fillers

9.8.3.1 If fillers not complying with 9.8.2.1 or removable forms are used, slab thickness shall be at least the greater of one-twelfth the clear distance between ribs and 2 in.

9.9—Deep beams**9.9.1 General**

9.9.1.1 Deep beams are members that are loaded on one face and supported on the opposite face such that strut-like compression elements can develop between the loads and supports and that satisfy (a) or (b):

- (a) Clear span does not exceed four times the overall member depth h
- (b) Concentrated loads exist within a distance $2h$ from the face of the support

9.9.1.2 Deep beams shall be designed taking into account nonlinear distribution of longitudinal strain over the depth of the beam.

9.9.1.3 The strut-and-tie method in accordance with Chapter 23 is deemed to satisfy 9.9.1.2.

9.9.2 Dimensional limits

9.9.2.1 Except as permitted by 23.4.4, deep beam dimensions shall be selected such that:

$$V_u \leq \phi 10 \sqrt{f'_c} b_w d \quad (9.9.2.1)$$

COMMENTARY

R9.9—Deep beams**R9.9.1 General**

R9.9.1.1 Behavior of deep beams is discussed in Schlaich et al. (1987), Rogowsky and MacGregor (1986), Marti (1985), and Crist (1966). This provision applies if loads are applied on the top of the beam and the beam is supported on its bottom face. If loads are applied through the sides or bottom of such a member, the strut-and-tie method, as defined in Chapter 23, should be used to design reinforcement to internally transfer the loads to the top of the beam and distribute them to adjacent supports.

R9.9.1.2 The Code does not contain detailed requirements for designing deep beams for moment, except that a nonlinear strain distribution should be considered. Guidance for design of deep beams for flexure is given in Chow et al. (1953), Portland Cement Association (1946), and Park and Paulay (1975).

R9.9.2 Dimensional limits

R9.9.2.1 This limit imposes a dimensional restriction to control cracking under service loads and to guard against diagonal compression failures in deep beams.

CODE

9.9.3 Reinforcement limits

9.9.3.1 Distributed reinforcement in deep beams shall be at least that required in (a) and (b):

- (a) The area of transverse distributed reinforcement over the longitudinal distance s_{td} shall be $A_{td} \geq 0.0025b_ws_{td}$
- (b) The area of longitudinal distributed reinforcement in each layer spaced over the vertical distance s_{td} shall be $A_{td} \geq 0.0025b_ws_{td}$

9.9.3.2 The minimum area of flexural tension reinforcement, $A_{s,min}$, shall be determined in accordance with 9.6.1.

9.9.4 Reinforcement detailing

9.9.4.1 Concrete cover shall be in accordance with 20.5.1.

9.9.4.2 Minimum spacing for longitudinal reinforcement shall be in accordance with 25.2.

9.9.4.3 Spacing of distributed reinforcement required in 9.9.3.1 shall not exceed the lesser of $d/5$ and 12 in.

COMMENTARY

R9.9.3 Reinforcement limits

R9.9.3.1 The minimum reinforcement requirements of this section are intended to control the width and propagation of inclined cracks. Tests (Rogowsky and MacGregor 1986; Marti 1985; Crist 1966) have shown that in a deep beam, reinforcement perpendicular to the longitudinal axis of the member is more effective for member shear strength than shear reinforcement parallel to the longitudinal axis of the member; however, the specified minimum reinforcement is the same in both directions to control the growth and width of diagonal cracks.

R9.9.4 Reinforcement detailing

R9.9.4.3 Figure R9.9.4.3 illustrates the spacing requirements for the distributed reinforcement defined in 9.9.3.1. Spacing determined by the requirements of 9.9.4.3 and 9.9.4.4 is dependent on the cross-sectional dimensions and can be more stringent than the requirements in 23.5.

CODE

COMMENTARY




Fig. R9.9.4.3—Distributed reinforcement in deep beams

9.9.4.4 For deep beams having a width > 8 in., distributed reinforcement required by 9.9.3.1 shall be placed in accordance with (a) and (b):

- (a) At least two curtains of reinforcement shall be provided with one near each side face.
- (b) Spacing s_{wd} between any adjacent curtains shall not exceed 24 in.

9.9.4.5 Development of tension reinforcement shall account for distribution of stress in reinforcement that is not directly proportional to the bending moment.

R9.9.4.4 To the extent practicable, multiple curtains of reinforcement, whether parallel with the beam depth or width, should be placed symmetrically with respect to the center planes of the beam. The spacing limit of 24 in. is consistent with the maximum spacing of shear reinforcement legs in 9.7.6.2.2.

R9.9.4.5 In deep beams, stress in longitudinal reinforcement is more uniform along the length than that of a beam that is not deep. High reinforcement stresses normally limited to the center region of a beam can extend to the supports in deep beams. Thus, ends of longitudinal reinforcement in

CODE

9.9.4.6 At simple supports, positive moment tension reinforcement shall develop f_y in tension at the face of the support. If a deep beam is designed using **Chapter 23**, the positive moment tension reinforcement shall be anchored in accordance with **23.8.4** and **23.8.5**.

9.9.4.7 At interior supports, (a) and (b) shall be satisfied:

- (a) Negative moment tension reinforcement shall be continuous with that of the adjacent spans.
- (b) Positive moment tension reinforcement shall be continuous or spliced with that of the adjacent spans.

COMMENTARY

deep beams may require positive anchorage in the form of standard hooks, bar heads, or other mechanical anchorage at supports.

R9.9.4.6 Use of the strut-and-tie method for design of deep beams illustrates that tensile forces in the bottom tie reinforcement need to be anchored at the face of the support. From this consideration, tie reinforcement should be continuous or developed at the face of the support (**Rogowsky and MacGregor 1986**).



Notes



CHAPTER 10—COLUMNS

CODE

COMMENTARY

10.1—Scope

10.1.1 This chapter shall apply to the design of nonprestressed and prestressed columns, including reinforced concrete pedestals.

10.1.2 Design of plain concrete pedestals shall be in accordance with **Chapter 14**.

10.2—General**10.2.1 Materials**

10.2.1.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

10.2.1.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

10.2.1.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

10.2.2 Connection to other members

10.2.2.1 For cast-in-place construction, joints shall satisfy **Chapter 15**.

10.2.2.2 For precast construction, connections shall satisfy the force transfer requirements of **16.2**.

10.2.2.3 Connections of columns to foundations shall satisfy **16.3**.

10.3—Design limits**10.3.1 Dimensional limits**

10.3.1.1 For columns with a square, octagonal, or other shaped cross section, it shall be permitted to base gross area considered, required reinforcement, and design strength on a circular section with a diameter equal to the least lateral dimension of the actual shape.

10.3.1.2 For columns with cross sections larger than required by considerations of loading, it shall be permitted to base gross area considered, required reinforcement, and design strength on a reduced effective area, not less than one-half the total area. This provision shall not apply to columns in special moment frames or columns not part of the seismic-force-resisting system required to be designed in accordance with **Chapter 18**.

10.3.1.3 For columns built monolithically with a concrete wall, the outer limits of the effective cross section of the column shall not be taken greater than 1.5 in. outside the transverse reinforcement.

R10.1—Scope

R10.1.1 Composite structural steel-concrete columns are not covered in this chapter. Design provisions for composite columns are covered in **ANSI/AISC 360**.

R10.3—Design limits**R10.3.1 Dimensional limits**

R10.3.1.1 Explicit minimum sizes for columns are not specified to permit the use of reinforced concrete columns with small cross sections in lightly loaded structures. If small cross sections are used, **ACI SPEC-117** and **ACI ITG-7** specify more restrictive tolerances on reinforcement placement and member dimensions.

R10.3.1.2 In some cases, the gross area of a column is larger than necessary to resist the factored load. In those cases, the minimum reinforcement percentage is given in **10.6.1.1** and may be calculated on the basis of the required area rather than the provided area, but the area of reinforcement cannot be less than 0.5 percent of the actual cross-sectional area.

CODE

10.3.1.4 For columns with two or more interlocking spirals, outer limits of the effective cross section shall be taken at a distance outside the spirals equal to the minimum required concrete cover.

10.3.1.5 If a reduced effective area is considered according to 10.3.1.1 through 10.3.1.4, structural analysis and design of other parts of the structure that interact with the column shall be based on the actual cross section.

10.4—Required strength

10.4.1 General

10.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in [Chapter 5](#).

10.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in [Chapter 6](#).

10.4.2 Factored axial force and moment

10.4.2.1 P_u and M_u occurring simultaneously for each applicable factored load combination shall be considered.

COMMENTARY

R10.4—Required strength

R10.4.2 Factored axial force and moment

R10.4.2.1 The critical load combinations may be difficult to discern without checking each combination. As illustrated in Fig. R10.4.2.1, considering only the factored load combinations associated with maximum axial force (LC1) and maximum bending moment (LC2) does not necessarily provide a code-compliant design for other load combinations such as LC3.




Fig. R10.4.2.1—Critical column load combination.

CODE

10.5—Design strength**10.5.1 General**

10.5.1.1 For each applicable factored load combination, design strength at all sections shall satisfy $\phi S_n \geq U$, including (a) through (d). Interaction between load effects shall be considered:

- (a) $\phi P_n \geq P_u$
- (b) $\phi M_n \geq M_u$
- (c) $\phi V_n \geq V_u$
- (d) $\phi T_n \geq T_u$

10.5.1.2 ϕ shall be determined in accordance with 21.2.

10.5.2 Axial force and moment

10.5.2.1 P_n and M_n shall be calculated in accordance with 22.4.

10.5.3 Shear

10.5.3.1 V_n shall be calculated in accordance with 22.5.

10.5.4 Torsion

10.5.4.1 If $T_u \geq \phi T_{th}$, where T_{th} is given in 22.7, torsion shall be considered in accordance with Chapter 9.

10.6—Reinforcement limits**10.6.1 Minimum and maximum longitudinal reinforcement**

10.6.1.1 For nonprestressed columns and for prestressed columns with an average compressive stress, due to effective prestress force only, less than 225 psi, area of longitudinal reinforcement shall be at least $0.01A_g$ but shall not exceed $0.08A_g$.

COMMENTARY

R10.5—Design strength**R10.5.1 General**

R10.5.1.1 Refer to R9.5.1.1.

R10.5.4 Torsion

R10.5.4.1 Torsion acting on columns in buildings is typically negligible and is rarely a governing factor in the design of columns.

R10.6—Reinforcement limits**R10.6.1 Minimum and maximum longitudinal reinforcement**

R10.6.1.1 Minimum longitudinal reinforcement is necessary to provide resistance to bending and axial load, and to reduce the effects of creep and shrinkage of the concrete under sustained compressive stresses. Creep and shrinkage effects cause force transfer from the concrete to the reinforcement, and the resultant increase in reinforcement stress becomes greater as the reinforcement ratio decreases. A minimum limit is placed on the reinforcement ratio to prevent reinforcement from yielding under sustained service loads (Richart 1933).

The maximum longitudinal reinforcement ratio is provided to ensure that concrete can be effectively consolidated around the bars and to ensure that columns designed according to the Code are similar to the test specimens by which the Code was calibrated. The 0.08 limit applies at all sections, including splice regions and joints, which may include dowels. Longitudinal reinforcement in columns should usually not exceed 4 percent if the column bars are required to be lap spliced, as the lap splice zone will have twice as much reinforcement if all lap splices occur at the same location.

CODE

COMMENTARY

10.6.1.2 For oversized columns, as permitted in 10.3.1.2, the minimum area of longitudinal reinforcement shall not be less than $0.005A_g$.

10.6.2 Minimum shear reinforcement

10.6.2.1 A minimum area of shear reinforcement, A_v , shall be provided in all regions where $V_u > 0.5\phi V_c$.

10.6.2.2 If shear reinforcement is required, $A_{v,min}$ shall be the greater of (a) and (b):

(a) $0.75\sqrt{f'_c} \frac{b_ws}{f_{yt}}$

(b) $50 \frac{b_ws}{f_{yt}}$

10.7—Reinforcement detailing**10.7.1 General**

10.7.1.1 Concrete cover for reinforcement shall be in accordance with 20.5.1.

10.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with 25.4.

10.7.1.3 Along development and lap splice lengths of longitudinal bars with $f_y \geq 80,000$ psi, transverse reinforcement shall be provided such that K_{tr} shall not be smaller than $0.5d_b$.

10.7.1.4 Bundled bars shall be in accordance with 25.6.

10.7.2 Reinforcement spacing

10.7.2.1 Minimum spacing s shall be in accordance with 25.2.

10.7.3 Longitudinal reinforcement

10.7.3.1 For nonprestressed columns and for prestressed columns with an average compressive stress, due to effective prestress force only, less than 225 psi, the minimum number of longitudinal bars shall be (a), (b), or (c):

- (a) Three within triangular ties
- (b) Four within rectangular or circular ties
- (c) Six enclosed by spirals or for columns of special moment frames enclosed by circular hoops

10.7.4 Offset bent longitudinal reinforcement

10.7.4.1 The slope of the inclined portion of an offset bent longitudinal bar relative to the longitudinal axis of the

R10.6.2 Minimum shear reinforcement

R10.6.2.1 The basis for minimum shear reinforcement is the same for columns and beams. Refer to R9.6.3 for more information.

R10.7—Reinforcement detailing**R10.7.3 Longitudinal reinforcement**

R10.7.3.1 At least four longitudinal bars are required when bars are enclosed by rectangular ties or circular ties. For other tie shapes, one bar should be provided at each apex or corner. For bars enclosed by spirals, at least six bars are required.

If the number of bars in a circular arrangement is less than eight, the orientation of the bars may significantly affect the moment strength of eccentrically loaded columns and should be considered in design.

CODE

column shall not exceed 1 in 6. Portions of bar above and below an offset shall be parallel to axis of column.

10.7.4.2 If the column face is offset 3 in. or more, longitudinal bars shall not be offset bent and separate dowels, lap spliced with the longitudinal bars adjacent to the offset column faces, shall be provided.

10.7.5 Splices of longitudinal reinforcement**10.7.5.1 General**

10.7.5.1.1 Lap splices, mechanical splices, butt-welded splices, and end-bearing splices shall be permitted.

10.7.5.1.2 Splices shall satisfy requirements for all factored load combinations.

10.7.5.1.3 Splices of deformed reinforcement shall be in accordance with 25.5 and, if applicable, shall satisfy the requirements of 10.7.5.2 for lap splices or 10.7.5.3 for end-bearing splices.

10.7.5.2 Lap splices**COMMENTARY****R10.7.5 Splices of longitudinal reinforcement****R10.7.5.1 General**

R10.7.5.1.2 Frequently, the basic gravity load combination will govern the design of the column itself, but a load combination including wind or earthquake effects may induce greater tension in some column bars. Each bar splice should be designed for the maximum calculated bar tensile force.

R10.7.5.1.3 For the purpose of calculating ℓ_d for tension lap splices in columns with offset bars, Fig. R10.7.5.1.3 illustrates the clear spacing to be used.




Fig. R10.7.5.1.3—Offset column bars.

R10.7.5.2 Lap splices

In columns subject to moment and axial force, tensile stresses may occur on one face of the column for moderate and large eccentricities as shown in Fig. R10.7.5.2. If such stresses occur, 10.7.5.2.2 requires tension splices to be used.

The splice requirements have been formulated on the basis that a compression lap splice has a tensile strength of at least $0.25f_y$. Therefore, even if column bars are designed for compression according to 10.7.5.2.1, some tensile strength is inherently provided.

CODE

COMMENTARY




Fig. R10.7.5.2—Lap splice requirements for columns.


10.7.5.2.1 If the bar force due to factored loads is compressive, compression lap splices shall be permitted. It shall be permitted to decrease the compression lap splice length in accordance with (a) or (b), but the lap splice length shall be at least 12 in.

(a) For tied columns, where ties throughout the lap splice length have an effective area not less than $0.0015h_s$ in both directions, lap splice length shall be permitted to be multiplied by 0.83. Tie legs perpendicular to dimension h shall be considered in calculating effective area.

(b) For spiral columns, where spirals throughout the lap splice length satisfy 25.7.3, lap splice length shall be permitted to be multiplied by 0.75.

R10.7.5.2.1 Reduced lap lengths are permitted if the lap splice is enclosed throughout its length by sufficient ties. The tie leg areas perpendicular to each direction are calculated separately. An example is provided in Fig. R10.7.5.2.1, where four legs are effective in one direction and two legs in the other direction.

Compression lap lengths may also be reduced if the lap splice is enclosed throughout its length by spirals that provide increased splitting resistance.



$$\text{Direction 1: } 4A_b \geq 0.0015h_1s$$

$$\text{Direction 2: } 2A_b \geq 0.0015h_2s$$

where A_b is the area of the tie

Fig. R10.7.5.2.1—Example of application of 10.7.5.2.1(a).

CODE

COMMENTARY

10.7.5.2.2 If the bar force due to factored loads is tensile, tension lap splices shall be in accordance with Table 10.7.5.2.2.

Table 10.7.5.2.2—Tension lap splice class

Tensile bar stress	Splice details	Splice type
$\leq 0.5f_y$	$\leq 50\%$ bars spliced at any section and lap splices on adjacent bars staggered by at least ℓ_d	Class A
	Other	Class B
$> 0.5f_y$	All cases	Class B

10.7.5.3 End-bearing splices

10.7.5.3.1 If the bar force due to factored loads is compressive, end-bearing splices shall be permitted provided the splices are staggered or additional bars are provided at splice locations. The continuing bars in each face of the column shall have a tensile strength at least $0.25f_y$ times the area of the vertical reinforcement along that face.

10.7.6 Transverse reinforcement

10.7.6.1 General

10.7.6.1.1 Transverse reinforcement shall satisfy the most restrictive requirements for reinforcement spacing.

10.7.6.1.2 Details of transverse reinforcement shall be in accordance with 25.7.2 for ties, 25.7.3 for spirals, or 25.7.4 for hoops.

10.7.6.1.3 For prestressed columns with an average compressive stress, due to effective prestress force only, greater than or equal to 225 psi, transverse ties or hoops need not satisfy the $16d_b$ spacing requirement of 25.7.2.1.

10.7.6.1.4 Longitudinal reinforcement shall be laterally supported using ties or hoops in accordance with 10.7.6.2 or spirals in accordance with 10.7.6.3, unless tests and structural analyses demonstrate adequate strength and feasibility of construction.

R10.7.5.3 End-bearing splices

R10.7.5.3.1 Details for end-bearing splices are provided in 25.5.6.

R10.7.6 Transverse reinforcement

R10.7.6.1 General

R10.7.6.1.4 All longitudinal bars in compression should be enclosed within transverse reinforcement. Where longitudinal bars are arranged in a circular pattern, only one circular tie per specified spacing is required. This requirement can be satisfied with a continuous circular tie (helix), that has a maximum pitch equal to the required tie spacing.

It is prudent to provide ties at each end of lap spliced bars, above and below end-bearing splices, and at minimum spacing immediately below sloping regions of offset bent bars.

Precast columns with cover less than 1-1/2 in., prestressed columns without nonprestressed longitudinal bars, columns constructed with concrete using coarse aggregate with a nominal maximum size of 3/8 in., wall-like columns, and other unusual columns may require closer spacing of transverse reinforcement.

CODE

10.7.6.1.5 If anchor bolts are placed in the top of a column or pedestal, the bolts shall be enclosed by transverse reinforcement that also surrounds at least four longitudinal bars within the column or pedestal. The transverse reinforcement shall be distributed within 5 in. of the top of the column or pedestal and shall consist of at least two No. 4 or three No. 3 ties or hoops.

10.7.6.1.6 If mechanical couplers or extended bars for connection to a precast element are placed in the ends of columns or pedestals, the mechanical couplers or extended bars shall be enclosed by transverse reinforcement. The transverse reinforcement shall be distributed within 5 in. of the ends of the column or pedestal and shall consist of at least two No. 4 or three No. 3 ties or hoops.

10.7.6.2 *Lateral support of longitudinal bars using ties or hoops*

10.7.6.2.1 In any story, the bottom tie or hoop shall be located not more than one-half the tie or hoop spacing above the top of footing or slab.

10.7.6.2.2 In any story, the top tie or hoop shall be located not more than one-half the tie or hoop spacing below the lowest horizontal reinforcement in the slab, drop panel, or shear cap. If beams or brackets frame into all sides of the column, the top tie or hoop shall be located not more than 3 in. below the lowest horizontal reinforcement in the shallowest beam or bracket.

10.7.6.3 *Lateral support of longitudinal bars using spirals*

10.7.6.3.1 In any story, the bottom of the spiral shall be located at the top of footing or slab.

10.7.6.3.2 In any story, the top of the spiral shall be located in accordance with Table 10.7.6.3.2.

Table 10.7.6.3.2 —Spiral extension requirements at top of column

Framing at column end	Extension requirements
Beams or brackets frame into all sides of the column	Extend to the level of the lowest horizontal reinforcement in members supported above.
Beams or brackets do not frame into all sides of the column	Extend to the level of the lowest horizontal reinforcement in members supported above. Additional column ties shall extend above termination of spiral to bottom of slab, drop panel, or shear cap.
Columns with capitals	Extend to the level at which the diameter or width of capital is twice that of the column.

COMMENTARY

R10.7.6.1.5 and **R10.7.6.1.6** Confinement improves load transfer from the anchor bolts and mechanical couplers to the column or pedestal where concrete may crack in the vicinity of the bolts and mechanical couplers. Such cracking may occur due to unanticipated forces caused by temperature, restrained shrinkage, and accidental impact during construction.

R10.7.6.2 *Lateral support of longitudinal bars using ties or hoops*

R10.7.6.2.2 For rectangular columns, beams or brackets framing into all four sides at the same elevation are considered to provide restraint over a joint depth equal to that of the shallowest beam or bracket. For columns with other shapes, four beams framing into the column from two orthogonal directions are considered to provide equivalent restraint.

R10.7.6.3 *Lateral support of longitudinal bars using spirals*

R10.7.6.3.2 Refer to R10.7.6.2.2.

CODE

COMMENTARY

10.7.6.4 Lateral support of offset bent longitudinal bars

10.7.6.4.1 Where longitudinal bars are offset, horizontal support shall be provided by ties, hoops, spirals, or parts of the floor construction and shall be designed to resist 1.5 times the horizontal component of the calculated force in the inclined portion of the offset bar.

10.7.6.4.2 If transverse reinforcement is provided to resist forces that result from offset bends, ties, hoops, or spirals shall be placed not more than 6 in. from points of bend.

10.7.6.5 Shear

10.7.6.5.1 If required, shear reinforcement shall be provided using ties, hoops, or spirals.

10.7.6.5.2 Maximum spacing of shear reinforcement shall be in accordance with Table 10.7.6.5.2.

Table 10.7.6.5.2—Maximum spacing of shear reinforcement

V_s		Maximum s , in.	
		Nonprestressed column	Prestressed column
$\leq 4\sqrt{f'_c} b_w d$	Lesser of:	$d/2$	$3h/4$
		24	
$> 4\sqrt{f'_c} b_w d$	Lesser of:	$d/4$	$3h/8$
		12	

Notes



CHAPTER 11—WALLS

CODE

COMMENTARY

11.1—Scope

11.1.1 This chapter shall apply to the design of nonprestressed and prestressed walls including (a) through (c):

- (a) Cast-in-place
- (b) Precast in-plant
- (c) Precast on-site including tilt-up

11.1.2 Design of special structural walls shall be in accordance with **Chapter 18**.

11.1.3 Design of plain concrete walls shall be in accordance with **Chapter 14**.

11.1.4 Design of cantilever retaining walls shall be in accordance with **Chapter 13**.

11.1.5 Design of walls as grade beams shall be in accordance with **13.3.5**.

11.1.6 Cast-in-place walls with insulating forms shall be permitted by this Code.

11.2—General**11.2.1 Materials**

11.2.1.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

11.2.1.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

11.2.1.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

11.2.2 Connection to other members

11.2.2.1 For precast walls, connections shall be designed in accordance with **16.2**.

11.2.2.2 Connections of walls to foundations shall satisfy **16.3**.

R11.1—Scope

R11.1.1 This chapter applies to walls as vertical and lateral force-resisting members. Provisions for in-plane lateral loads in ordinary structural walls are included in this chapter.

R11.1.2 Requirements for special structural walls are in **18.10**. Requirements for intermediate precast structural walls and special structural walls constructed using precast concrete are in **18.5** and **18.11**, respectively.

ASCE/SEI 7 defines a structural wall as a wall that meets the definition for a bearing wall or a shear wall. A bearing wall is defined as a wall that supports vertical load beyond a certain threshold value. A shear wall is defined as a wall, bearing or nonbearing, designed to resist lateral forces acting in the plane of the wall.

R11.1.6 Cast-in-place walls with insulating forms should be designed in accordance with the Code. Specific design recommendations can be found in **ACI PRC-560**.

The licensed design professional should specify requirements to verify consolidation of concrete cast in insulated concrete forms (ICF) as provided in **26.5.2.1**.

R11.2—General

CODE

COMMENTARY

11.2.3 Load distribution

11.2.3.1 Unless otherwise demonstrated by an analysis, the horizontal length of wall considered as effective for resisting each concentrated load shall not exceed the lesser of the center-to-center distance between loads, and the bearing width plus four times the wall thickness. Effective horizontal length for bearing shall not extend beyond vertical wall joints unless design provides for transfer of forces across the joints.

11.2.4 Intersecting elements

11.2.4.1 Walls shall be anchored to intersecting elements, such as floors and roofs; columns, pilasters, buttresses, or intersecting walls; and to footings.

11.2.4.2 For cast-in-place walls having $P_u > 0.2f'_cA_g$, the portion of the wall within the thickness of the floor system shall have specified compressive strength at least $0.8f'_c$ of the wall.

11.3—Design limits**11.3.1 Minimum solid wall thickness**

11.3.1.1 Minimum solid wall thicknesses shall be in accordance with Table 11.3.1.1. Thinner walls are permitted if adequate strength and stability can be demonstrated by structural analysis.

Table 11.3.1.1—Minimum solid wall thickness h

Wall type	Minimum thickness h		
Bearing ^[1]	Greater of:	4 in.	(a)
		1/25 the lesser of unsupported length and unsupported height	(b)
Nonbearing	Greater of:	4 in.	(c)
		1/30 the lesser of unsupported length and unsupported height	(d)
Exterior basement and foundation ^[1]		7.5 in.	(e)

^[1]Only applies to walls designed in accordance with the simplified design method of 11.5.3.

11.4—Required strength**11.4.1 General**

11.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in [Chapter 5](#).

R11.2.4 Intersecting elements

R11.2.4.1 Walls that do not depend on intersecting elements for support, do not have to be connected to those elements. It is not uncommon to separate massive retaining walls from intersecting walls to accommodate differences in deformations.

R11.2.4.2 The 0.8 factor reflects reduced confinement in floor-wall joints compared with floor-column joints under gravity loads. ®

R11.4—Required strength**R11.4.1 General**

CODE

11.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in [Chapter 6](#).

11.4.1.3 Slenderness effects shall be calculated in accordance with [6.6.4](#), [6.7](#), or [6.8](#). Alternatively, out-of-plane slenderness analysis shall be permitted using [11.8](#) for walls meeting the requirements of that section.

COMMENTARY

R11.4.1.3 The forces typically acting on a wall are illustrated in Fig. R11.4.1.3.




Fig. R11.4.1.3—In-plane and out-of-plane forces.

11.4.1.4 Walls shall be designed for eccentric axial loads and any lateral or other loads to which they are subjected.

11.4.1.5 Design of basement walls to resist out-of-plane lateral earth pressure shall be in accordance with [Section 13.3.7](#).

11.4.2 Factored axial force and moment

11.4.2.1 Walls shall be designed for the maximum factored moment M_u that can accompany the factored axial force for each applicable load combination. The factored axial force P_u at given eccentricity shall not exceed $\phi P_{n,max}$, where $P_{n,max}$ shall be as given in [22.4.2.1](#) and strength reduction factor ϕ shall be that for compression-controlled sections in [21.2.2](#). The maximum factored moment M_u shall be magnified for slenderness effects in accordance with [6.6.4](#), [6.7](#), or [6.8](#).

11.4.3 Factored shear

11.4.3.1 Walls shall be designed for the maximum in-plane V_u and out-of-plane V_u .

CODE

11.5—Design strength**11.5.1 General**

11.5.1.1 For each applicable factored load combination, design strength at all sections shall satisfy $\phi S_n \geq U$, including (a) through (c). Interaction between axial load and moment shall be considered.

- (a) $\phi P_n \geq P_u$
- (b) $\phi M_n \geq M_u$
- (c) $\phi V_n \geq V_u$

11.5.1.2 ϕ shall be determined in accordance with 21.2.

11.5.2 Axial load and in-plane or out-of-plane flexure

11.5.2.1 For bearing walls, P_n and M_n (in-plane or out-of-plane) shall be calculated in accordance with 22.4. Alternatively, axial load and out-of-plane flexure shall be permitted to be considered in accordance with 11.5.3.

11.5.2.2 For nonbearing walls, M_n shall be calculated in accordance with 22.3.

11.5.3 Axial load and out-of-plane flexure – simplified design method

11.5.3.1 If the resultant of all factored loads is located within the middle third of the thickness of a solid wall with a rectangular cross section, P_n shall be permitted to be calculated by:

$$P_n = 0.55f'_cA_g \left[1 - \left(\frac{k\ell_c}{32h} \right)^2 \right] \quad (11.5.3.1)$$

COMMENTARY

R11.5—Design strength**R11.5.2 Axial load and in-plane or out-of-plane flexure**

R11.5.2.2 Nonbearing walls, by definition, are not subject to any significant axial force; therefore, flexural strength is not a function of axial force.

R11.5.3 Axial load and out-of-plane flexure – simplified design method

R11.5.3.1 The simplified design method applies only to solid rectangular cross sections; all other shapes should be designed in accordance with 11.5.2.

Eccentric axial loads and moments due to out-of-plane forces are used to determine the maximum total eccentricity of the factored axial force P_u . When the resultant axial force for all applicable load combinations falls within the middle third of the wall thickness (eccentricity not greater than $h/6$) at all sections along the length of the undeformed wall, no tension is induced in the wall and the simplified design method may be used. The design is then carried out considering P_u as a concentric axial force.

Equation (11.5.3.1) results in strengths comparable to those determined in accordance with 11.5.2 for members loaded at the middle third of the thickness with different braced and restrained end conditions. Refer to Fig. R11.5.3.1.

CODE

COMMENTARY




Fig. R11.5.3.1—Simplified design of walls, Eq. (11.5.3.1) versus 11.5.2.

11.5.3.2 Effective length factor k for use with Eq. (11.5.3.1) shall be in accordance with Table 11.5.3.2.

Table 11.5.3.2—Effective length factor k for walls

Boundary conditions	k
Walls braced top and bottom against lateral translation and:	
(a) Restrained against rotation at one or both ends (top, bottom, or both)	0.8
(b) Unrestrained against rotation at both ends	1.0
Walls not braced against lateral translation	2.0

11.5.3.3 P_n from Eq. (11.5.3.1) shall be reduced by ϕ for compression-controlled sections in 21.2.2.

11.5.3.4 Wall reinforcement shall be at least that required by 11.6.

11.5.4 In-plane shear

11.5.4.1 V_n shall be calculated in accordance with 11.5.4.2 through 11.5.4.4. Alternatively, for walls with $h_w/\ell_w < 2$, it shall be permitted to design for in-plane shear in accordance with the strut-and-tie method of Chapter 23. In all cases, reinforcement shall satisfy the limits of 11.6, 11.7.2, and 11.7.3.

R11.5.4 In-plane shear

R11.5.4.1 In-plane shear is primarily of importance for structural walls with a small height-to-length ratio ($h_w/\ell_w < 2$). The design of taller walls, particularly walls with uniformly distributed reinforcement, will likely be controlled by flexural considerations. Possible exceptions may occur in tall structural walls subject to strong earthquake excitation.

CODE

11.5.4.2 V_n at any horizontal section shall not exceed $8\sqrt{f'_c}A_{cv}$.

11.5.4.3 V_n shall be calculated by:

$$V_n = (\alpha_c \lambda \sqrt{f'_c} + \rho_t f_{yt}) A_{cv} \quad (11.5.4.3)$$

where:

$\alpha_c = 3$ for $h_w/\ell_w \leq 1.5$

$\alpha_c = 2$ for $h_w/\ell_w \geq 2.0$

α_c varies linearly between 3 and 2 for $1.5 < h_w/\ell_w < 2.0$

11.5.4.4 For walls subject to a net axial tension, α_c in Eq. (11.5.4.3) shall be taken as:

$$\alpha_c = 2 \left(1 + \frac{N_u}{500A_g} \right) \geq 0.0 \quad (11.5.4.4)$$

where N_u is negative for tension.

11.5.5 Out-of-plane shear

11.5.5.1 V_n shall be calculated in accordance with **22.5**.

11.6—Reinforcement limits

11.6.1 If in-plane $V_u \leq 0.5\phi\alpha_c\lambda\sqrt{f'_c}A_{cv}$, minimum ρ_t and minimum ρ_l shall be in accordance with Table 11.6.1. These limits need not be satisfied if adequate strength and stability can be demonstrated by structural analysis.

COMMENTARY

R11.5.4.2 This limit is imposed to guard against diagonal compression failure in structural walls.

R11.5.4.4 For structural walls where a net axial tension force is calculated for the entire wall section, the shear strength contribution attributed to the concrete is reduced and may be negligible. For these members, wall transverse reinforcement must be designed to resist most, if not all, of the factored shear force.

R11.6—Reinforcement limits

R11.6.1 Both horizontal and vertical shear reinforcement are required for all walls. The distributed reinforcement is identified as being oriented parallel to either the longitudinal or transverse axis of the wall. Therefore, for vertical wall segments, the notation used to describe the horizontal distributed reinforcement ratio is ρ_b , and the notation used to describe the vertical distributed reinforcement ratio is ρ_l .

The reduced minimum reinforcement for precast walls recognizes that precast members have less restraint to shrinkage during curing and are usually not as rigidly connected as monolithic concrete, resulting in reduced restraint stresses due to both shrinkage and temperature change (**PCI Committee on Precast Concrete Bearing Wall Buildings 1976; Portland Cement Association 1980**). Reduced minimum reinforcement and greater spacings in 11.7.2.2 are allowed because precast wall panels have very little restraint at their edges during early stages of curing and develop less shrinkage stress than comparable cast-in-place walls.

Transverse reinforcement is not required in precast, prestressed walls equal to or less than 12 ft wide because this width is less than that in which shrinkage and temperature stresses can build up to a magnitude requiring transverse reinforcement. In addition, much of the shrinkage occurs before the members are connected into the structure. Once in the final structure, the members are usually not as rigidly connected transversely as monolithic concrete; thus, the transverse restraint stresses due to both shrinkage and temperature change are significantly reduced.

CODE

COMMENTARY

Table 11.6.1—Minimum reinforcement for walls with in-plane $V_u \leq 0.5\phi\alpha_c\lambda\sqrt{f'_c}A_{cv}$

Wall type	Type of nonprestressed reinforcement	Bar/wire size	f_y , psi	Minimum longitudinal ^[1] , ρ_t	Minimum transverse, ρ_t
Cast-in-place	Deformed bars	$\leq$ No. 5	$\geq 60,000$	0.0012	0.0020
			$< 60,000$	0.0015	0.0025
	Welded-wire reinforcement	$\leq$ W31 or D31	Any	0.0015	0.0025
Precast ^[2]	Deformed bars or welded-wire reinforcement	Any	Any	0.0010	0.0010

^[1]Walls with an average compressive stress, due to effective prestress force only, of at least 225 psi need not meet the requirement for minimum longitudinal reinforcement ρ_t .

^[2]In one-way precast, prestressed walls not wider than 12 ft and not mechanically connected to cause restraint in the transverse direction, the minimum reinforcement requirement in the direction normal to the flexural reinforcement need not be satisfied.

11.6.2 If in-plane $V_u > 0.5\phi\alpha_c\lambda\sqrt{f'_c}A_{cv}$, (a) and (b) shall be satisfied:

(a) ρ_t shall be at least the greater of the value calculated by Eq. (11.6.2) and 0.0025, but need not exceed ρ_t required for strength by 11.5.4.3.

$$\rho_t \geq 0.0025 + 0.5(2.5 - h_w/\ell_w)(\rho_t - 0.0025) \quad (11.6.2)$$

(b) ρ_t shall be at least 0.0025.

R11.6.2 For monotonically loaded walls with low height-to-length ratios, test data (Barda et al. 1977) indicate that horizontal shear reinforcement becomes less effective for shear resistance than vertical reinforcement. This change in effectiveness of the horizontal versus vertical reinforcement is recognized in Eq. (11.6.2); if h_w/ℓ_w is less than 0.5, the amount of vertical reinforcement is equal to the amount of horizontal reinforcement. If h_w/ℓ_w is greater than 2.5, only a minimum amount of vertical reinforcement is required ($0.0025sh$).

11.7—Reinforcement detailing**11.7.1 General**

11.7.1.1 Concrete cover for reinforcement shall be in accordance with 20.5.1.

11.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with 25.4.

11.7.1.3 Splice lengths of deformed reinforcement shall be in accordance with 25.5.

11.7.2 Spacing of longitudinal reinforcement

11.7.2.1 Spacing s of longitudinal bars in cast-in-place walls shall not exceed the lesser of $3h$ and 18 in. If shear reinforcement is required for in-plane strength, spacing of longitudinal reinforcement shall not exceed $\ell_w/3$.

11.7.2.2 Spacing s of longitudinal bars in precast walls shall not exceed the lesser of (a) and (b):

- (a) $5h$
- (b) 18 in. for exterior walls or 30 in. for interior walls

If shear reinforcement is required for in-plane strength, s shall not exceed the smallest of $3h$, 18 in., and $\ell_w/3$.

11.7.2.3 For walls with thickness greater than 10 in., except single story basement walls and cantilever retaining

CODE**COMMENTARY**

walls, distributed reinforcement in each direction shall be placed in at least two curtains, one near each face.

11.7.2.4 Flexural tension reinforcement shall be well distributed and placed as close as practicable to the tension face.

11.7.3 Spacing of transverse reinforcement

11.7.3.1 Spacing s of transverse reinforcement in cast-in-place walls shall not exceed the lesser of $3h$ and 18 in. If shear reinforcement is required for in-plane strength, s shall not exceed $\ell_w/5$.

11.7.3.2 Spacing s of transverse bars in precast walls shall not exceed the lesser of (a) and (b):

(a) $5h$

(b) 18 in. for exterior walls or 30 in. for interior walls

If shear reinforcement is required for in-plane strength, s shall not exceed the least of $3h$, 18 in., and $\ell_w/5$.

11.7.4 Through-thickness shear reinforcement

11.7.4.1 Shear reinforcement required for out-of-plane strength shall extend as close to the extreme compression and tension surfaces of the wall as practicable, and satisfy the requirements of **25.7.1.3** or **25.7.1.8**.

11.7.5 Lateral support of longitudinal reinforcement

11.7.5.1 If longitudinal reinforcement is required for compression and if A_{st} exceeds $0.01A_g$, longitudinal reinforcement shall be laterally supported by transverse ties.

11.7.6 Reinforcement around openings

11.7.6.1 In addition to the minimum reinforcement required by 11.6, at least two No. 5 bars in walls having two layers of reinforcement in both directions and one No. 5 bar in walls having a single layer of reinforcement in both directions shall be provided around window, door, and similarly sized openings. Such bars shall develop f_y in tension at the corners of the openings.

11.8—Alternative method for out-of-plane slender wall analysis**11.8.1 General**

11.8.1.1 It shall be permitted to analyze out-of-plane slenderness effects in accordance with this section for walls satisfying (a) through (e):

(a) Cross section is constant over the height of the wall

R11.8—Alternative method for out-of-plane slender wall analysis**R11.8.1 General**

R11.8.1.1 This procedure is presented as an alternative to the requirements of 11.5.2.1 for the out-of-plane design of slender wall panels, where the panels are restrained against overturning at the top.

Panels that have windows or other large openings are not considered to have constant cross section over the height of

CODE

- (b) Wall is tension-controlled for out-of-plane moment effect
- (c) ϕM_n is at least M_{cr} , where M_{cr} is calculated using f_r as provided in 19.2.3
- (d) P_u at the midheight section does not exceed $0.06f'_c A_g$
- (e) Calculated out-of-plane deflection due to service loads, Δ_s , including $P\Delta$ effects, does not exceed $\ell_c/150$

11.8.2 Modeling

11.8.2.1 The wall shall be analyzed as a simply supported, axially loaded member subject to an out-of-plane uniformly distributed lateral load, with maximum moments and deflections occurring at midheight.

11.8.2.2 Concentrated gravity loads applied to the wall above any section shall be assumed to be distributed over a width equal to the bearing width, plus a width on each side that increases at a slope of 2 vertical to 1 horizontal, but not extending beyond (a) or (b):

- (a) The spacing of the concentrated loads
- (b) The edges of the wall panel

11.8.3 Factored moment

11.8.3.1 M_u at midheight of wall due to combined flexure and axial loads shall include the effects of wall deflection in accordance with (a) or (b):

- (a) By iterative calculation using

$$M_u = M_{ua} + P_u \Delta_u \quad (11.8.3.1a)$$

where M_{ua} is the maximum factored moment at midheight of wall due to lateral and eccentric vertical loads, not including $P\Delta$ effects. Δ_u shall be calculated by:

$$\Delta_u = \frac{5M_u \ell_c^2}{(0.75)48E_c I_{cr}} \quad (11.8.3.1b)$$

where I_{cr} shall be calculated by:

$$I_{cr} = \frac{E_s}{E_c} \left(A_s + \frac{P_u}{f_y} \frac{h}{2d} \right) (d - c)^2 + \frac{\ell_w c^3}{3} \quad (11.8.3.1c)$$

and the value of E_s/E_c shall be at least 6.

- (b) By direct calculation using:

$$M_u = \frac{M_{ua}}{\left(1 - \frac{5P_u \ell_c^2}{(0.75)48E_c I_{cr}} \right)} \quad (11.8.3.1d)$$

COMMENTARY

the panel. Such walls are to be designed taking into account the effects of openings.

Many aspects of the design of tilt-up walls and buildings are discussed in ACI PRC-551.2, ACI PRC-551.3, and Carter et al. (1993).

R11.8.3 Factored moment

R11.8.3.1 The neutral axis depth c in Eq. (11.8.3.1c) corresponds to the following effective area of longitudinal reinforcement.

$$A_{se,w} = A_s + \frac{P_u}{f_y} \left(\frac{h/2}{d} \right)$$

CODE

11.8.4 Out-of-plane deflection – service loads

11.8.4.1 Out-of-plane deflection due to service loads, Δ_s , shall be calculated in accordance with Table 11.8.4.1, where M_a is calculated by 11.8.4.2.

Table 11.8.4.1—Calculation of Δ_s

M_a	Δ_s	
$\leq (2/3)M_{cr}$	$\Delta_s = \left(\frac{M_a}{M_{cr}}\right)\Delta_{cr}$	(a)
$> (2/3)M_{cr}$	$\Delta_s = \frac{2}{3}\Delta_{cr} + \frac{\left(M_a - \frac{2}{3}M_{cr}\right)}{\left(M_a - \frac{2}{3}M_{cr}\right)}\left(\Delta_n - \frac{2}{3}\Delta_{cr}\right)$	(b)

11.8.4.2 The maximum moment M_a at midheight of wall due to service lateral and eccentric vertical loads, including $P_s\Delta_s$ effects, shall be calculated by Eq. (11.8.4.2) with iteration of deflections.

$$M_a = M_{sa} + P_s\Delta_s \quad (11.8.4.2)$$

11.8.4.3 Δ_{cr} and Δ_n shall be calculated by (a) and (b):

$$(a) \Delta_{cr} = \frac{5M_{cr}\ell_c^2}{48E_cI_g} \quad (11.8.4.3a)$$

$$(b) \Delta_n = \frac{5M_n\ell_c^2}{48E_cI_{gr}} \quad (11.8.4.3b)$$

11.8.4.4 I_{cr} shall be calculated by Eq. (11.8.3.1c).

COMMENTARY

R11.8.4 Out-of-plane deflection – service loads

R11.8.4.1 Test data (Athey 1982) demonstrate that out-of-plane deflections increase rapidly when the service-level moment exceeds $2/3M_{cr}$. A linear interpolation between Δ_u and Δ_n is used to determine Δ_s to simplify the design of slender walls if $M_a > 2/3M_{cr}$.

Service-level load combinations are not defined in Chapter 5 of the Code but are discussed in Appendix C of ASCE/SEI 7. Appendices to ASCE/SEI 7 are not considered mandatory parts of that standard. For calculating service-level lateral deflections of structures, Appendix C of ASCE/SEI 7 recommends using the following load combination:

$$D + 0.5L + W_a$$

in which W_a is wind load based on serviceability wind speeds provided in the commentary to Appendix C of ASCE/SEI 7. If the slender wall is designed to resist earthquake effects E , and E is based on strength-level earthquake effects, the following load combination is considered to be appropriate for evaluating service-level lateral deflections

$$D + 0.5L + 0.7E$$

CHAPTER 12—DIAPHRAGMS

CODE

COMMENTARY

12.1—Scope

12.1.1 This chapter shall apply to the design of nonprestressed and prestressed diaphragms, including (a) through (d):

- (a) Diaphragms that are cast-in-place slabs
- (b) Diaphragms that comprise a cast-in-place topping slab on precast elements
- (c) Diaphragms that comprise precast elements with end strips formed by either a cast-in-place concrete topping slab or edge beams
- (d) Diaphragms of interconnected precast elements without cast-in-place concrete topping

R12.1—Scope

R12.1.1 Diaphragms typically are horizontal or nearly horizontal planar elements that serve to transfer lateral forces to vertical elements of the lateral-force-resisting system (Fig. R12.1.1). Diaphragms also tie the building elements together into a complete three-dimensional system and provide lateral support to those elements by connecting them to the lateral-force-resisting system. Typically, diaphragms also serve as floor and roof slabs, or as parking structure ramps and, therefore, support gravity loads. A diaphragm may include chords and collectors.

When subjected to lateral loads, such as the in-plane inertial loads acting on the roof diaphragm of Fig. R12.1.1, a diaphragm acts essentially as a beam spanning horizontally between vertical elements of the lateral-force-resisting system. The diaphragm thus develops in-plane bending moments, shears, and possibly other actions. Where vertical elements of the lateral-force-resisting system do not extend along the full depth of the diaphragm, collectors may be required to collect the diaphragm shear and transfer it to the vertical elements. The term “distributor” is sometimes used to describe a collector that transfers force from a vertical element of the lateral-force-resisting system into the diaphragm. This chapter describes minimum requirements for diaphragm and collector design and detailing, including configuration, analysis models, materials, and strength.

This chapter covers only the types of diaphragms listed in this provision. Other diaphragm types, such as horizontal trusses, are used successfully in buildings, but this chapter does not include prescriptive provisions for those other types.




Fig. R12.1.1—Typical diaphragm actions.

12.1.2 Diaphragm types defined in 12.1.1 that form part of the seismic-force resisting system shall also satisfy requirements of 18.12 where applicable.

12.2—General

12.2.1 Design shall consider forces (a) through (e):

- (a) Diaphragm in-plane forces due to lateral loads acting on the building
- (b) Diaphragm transfer forces
- (c) Connection forces between the diaphragm and vertical framing or nonstructural elements
- (d) Forces resulting from bracing vertical or sloped building elements
- (e) Diaphragm out-of-plane forces due to gravity and other loads applied to the diaphragm surface

R12.2—General

R12.2.1 As partially illustrated in Fig. R12.1.1, diaphragms resist forces from several types of actions (Moehle et al. 2010):

- (a) **Diaphragm in-plane forces**—Lateral forces from load combinations including wind, earthquake, and horizontal fluid or soil pressure generate in-plane shear, axial, and bending actions in diaphragms as they span between, and transfer forces to, vertical elements of the lateral-force-resisting system. For wind loading, lateral force is generated by wind pressure acting on building cladding that is transferred by diaphragms to the vertical elements. For earthquake loading, inertial forces are generated within the diaphragm and tributary portions of walls, columns, and other elements, and then transferred by diaphragms to the vertical elements. For buildings with subterranean levels, lateral forces are generated by soil pressure bearing against the basement walls; in a typical system, the base-

CODE

12.2.2 The effects of slab openings and slab voids shall be considered in design.

12.2.3 Materials

12.2.3.1 Design properties for concrete shall be selected to be in accordance with [Chapter 19](#).

12.2.3.2 Design properties for steel reinforcement shall be selected to be in accordance with [Chapter 20](#).

COMMENTARY

ment walls span vertically between floors also serving as diaphragms, which in turn distribute the lateral soil forces to other force-resisting elements.

(b) **Diaphragm transfer forces**—Vertical elements of the lateral-force-resisting system may have different properties over their height, or their planes of resistance may change from one story to another, creating force transfers between vertical elements. A common location where planes of resistance change is at grade level of a building with an enlarged subterranean plan; at this location, forces may transfer from the narrower tower into the basement walls through a podium diaphragm (refer to Fig. R12.1.1).

(c) **Connection forces**—Wind pressure acting on exposed building surfaces generates out-of-plane forces on those surfaces. Similarly, earthquake shaking can produce inertial forces in vertical framing and nonstructural elements such as cladding. These forces are transferred from the elements where the forces are developed to the diaphragm through connections.

(d) **Column bracing forces**—Architectural configurations sometimes require inclined columns, which can result in large horizontal thrusts acting within the plane of the diaphragms due to gravity and overturning actions. The thrusts can act in different directions depending on orientation of the column and whether it is in compression or tension. Where these thrusts are not balanced locally by other elements, the forces have to be transferred into the diaphragm so they can be transmitted to other suitable elements of the lateral-force-resisting system. Such forces are common and may be significant with eccentrically loaded precast concrete columns that are not monolithic with adjacent framing. The diaphragm also provides lateral support to columns not designed as part of the lateral-force-resisting system by connecting them to other elements that provide lateral stability for the structure.

(e) **Diaphragm out-of-plane forces**—Most diaphragms are part of floor and roof framing and, therefore, support gravity loads. The general building code may also require consideration of out-of-plane forces due to wind uplift pressure on a roof slab and vertical acceleration due to earthquake effects.

R12.2.2 Refer to [R7.2.1](#).

CODE

12.3—Design limits**12.3.1** *Minimum diaphragm thickness*

12.3.1.1 Diaphragms shall have thickness as required for stability, strength, and stiffness under factored load combinations.

12.3.1.2 Floor and roof diaphragms shall have a thickness not less than that required for floor and roof elements in other parts of this Code.

12.4—Required strength**12.4.1** *General*

12.4.1.1 Required strength of diaphragms, collectors, and their connections shall be calculated in accordance with the factored load combinations in **Chapter 5**.

12.4.1.2 Required strength of diaphragms that are part of floor or roof construction shall include effects of out-of-plane loads simultaneous with other applicable loads.

12.4.2 *Diaphragm modeling and analysis*

12.4.2.1 Diaphragm modeling and analysis requirements of the general building code shall govern where applicable. Otherwise, diaphragm modeling and analysis shall be in accordance with 12.4.2.2 through 12.4.2.4.

12.4.2.2 Modeling and analysis procedures shall satisfy requirements of **Chapter 6**.

COMMENTARY

R12.3—Design limits**R12.3.1** *Minimum diaphragm thickness*

R12.3.1.1 Diaphragms may be required to resist in-plane moment, shear, and axial force. For diaphragms that are entirely cast-in-place or comprise topping slabs composite with precast members, thickness of the entire diaphragm must be sufficient to resist these actions. For noncomposite topping slabs, thickness of the cast-in-place topping alone must be sufficient to resist these actions. **Section 18.12** contains specific requirements for diaphragms in buildings assigned to Seismic Design Categories D, E, and F.

In addition to requirements for in-plane force resistance, diaphragms that are part of floor or roof construction must satisfy applicable requirements for slab or flange thickness.

R12.4—Required strength

R12.4.1 Factored load combinations generally require consideration of out-of-plane loads that act simultaneously with diaphragm in-plane forces. For example, this is required where a floor beam also serves as a collector, in which case the beam is to be designed to resist axial forces acting as a collector and bending moments acting as a floor beam supporting gravity loads.

R12.4.2 *Diaphragm modeling and analysis*

R12.4.2.1 **ASCE/SEI 7** includes diaphragm modeling requirements for some design conditions, such as design to resist wind and earthquake loads. Where ASCE/SEI 7 is adopted as part of the general building code, those requirements govern over provisions of ACI CODE-318.

R12.4.2.2 Chapter 6 contains general requirements for analysis that are applicable to diaphragms. Diaphragms are usually designed to remain elastic or nearly elastic for forces acting within their plane under factored load combinations. Therefore, analysis methods satisfying theory of elastic analysis are generally acceptable. The provisions for elastic analysis in **6.6.1** through **6.6.3** can be applied.

Diaphragm in-plane stiffness affects not only the distribution of forces within the diaphragm, but also the distribution of displacements and forces among the vertical

CODE

12.4.2.3 Any set of reasonable and consistent assumptions for diaphragm stiffness shall be permitted.

COMMENTARY

elements. Thus, the diaphragm stiffness model should be consistent with characteristics of the building. Where the diaphragm is very stiff compared to the vertical elements, as in a low aspect ratio, cast-in-place diaphragm supported by moment frames, it is acceptable to model the diaphragm as a completely rigid element. Where the diaphragm is flexible compared with the vertical elements, as in some jointed precast systems supported by structural walls, it may be acceptable to model the diaphragm as a flexible beam spanning between rigid supports. In other cases, it may be advisable to adopt a more detailed analytical model to account for the effects of diaphragm flexibility on the distribution of displacements and forces. Examples include buildings in which diaphragm and vertical element stiffnesses have approximately the same value, buildings with large force transfers, and parking structures in which ramps connect between floors and act essentially as bracing elements within the building.

For diaphragms constructed of concrete slabs, **ASCE/SEI 7** permits the assumption of a rigid diaphragm if the diaphragm aspect ratio falls within a prescribed limit, which is different for wind and earthquake loads, and if the structure has no horizontal irregularities. ASCE/SEI 7 provisions do not prohibit the rigid diaphragm assumption for other conditions, provided the rigid diaphragm assumption is reasonably consistent with anticipated behavior. Cast-in-place concrete diaphragms designed with the rigid-diaphragm assumption have a long history of satisfactory performance even though they may fall outside the ASCE/SEI 7 index values.

R12.4.2.3 For low-aspect-ratio diaphragms that are entirely cast-in-place or comprise a cast-in-place topping slab on precast elements, the diaphragm is often modeled as a rigid element supported by flexible vertical elements. However, effects of diaphragm flexibility should be considered where such effects will materially affect calculated design actions. Such effects should be considered for diaphragms that use precast elements, with or without a cast-in-place topping. Where large transfer forces occur, as outlined in R12.2.1(b), more realistic design forces can be obtained by modeling diaphragm in-plane stiffness. Diaphragms with long spans, large cutout areas, or other irregularities may develop in-plane deformations that should be considered in design (refer to Fig. R12.4.2.3a).

For a diaphragm considered rigid in its own plane, and for semi-rigid diaphragms, the diaphragm internal force distribution can be obtained by modeling it as a horizontal rigid beam supported on springs representing lateral stiffnesses of the vertical elements (refer to Fig. R12.4.2.3b). Effects of in-plane eccentricity between applied forces and vertical element resistances, resulting in overall building torsion, should be included in the analysis. Elements of the lateral-force-resisting system aligned in the orthogonal direction can participate in resisting diaphragm plan rotation (**Moehle et al. 2010**).

CODE

COMMENTARY





Fig. R12.4.2.3a—Example of diaphragm that might not be considered rigid in its plane.



Plan




Fig. R12.4.2.3b—Diaphragm in-plane actions obtained by modeling the diaphragm as a horizontal rigid beam on flexible supports.

12.4.2.4 Calculation of diaphragm in-plane design moments, shears, and axial forces shall be consistent with requirements of equilibrium and with design boundary

R12.4.2.4 The rigid diaphragm model is widely used for diaphragms that are entirely cast-in-place and for diaphragms that comprise a cast-in-place topping slab on precast

CODE

conditions. It shall be permitted to calculate design moments, shears, and axial forces in accordance with one of (a) through (e):

- (a) A rigid diaphragm model if the diaphragm can be idealized as rigid
- (b) A flexible diaphragm model if the diaphragm can be idealized as flexible
- (c) A bounding analysis in which the design values are the envelope of values obtained by assuming upper bound and lower bound in-plane stiffnesses for the diaphragm in two or more separate analyses
- (d) A finite element model considering diaphragm flexibility
- (e) A strut-and-tie model in accordance with 23.2

12.5—Design strength**12.5.1 General**

12.5.1.1 For each applicable factored load combination, design strengths of diaphragms and connections shall satisfy $\phi S_n \geq U$. Interaction between load effects shall be considered.

12.5.1.2 ϕ shall be determined in accordance with 21.2.

12.5.1.3 Design strengths shall be in accordance with (a), (b), (c), or (d):

COMMENTARY

elements, provided flexible conditions are not created by a long span, by a large aspect ratio, or by diaphragm irregularity. For more flexible diaphragms, a bounding analysis is sometimes done in which the diaphragm is analyzed as a stiff or rigid element on flexible supports and as a flexible diaphragm on rigid supports, with the design values taken as the envelope of values from the two analyses. Finite element models can be suitable for any diaphragm, but are especially useful for irregularly shaped diaphragms and diaphragms resisting large transfer forces. Stiffness should be adjusted to account for expected concrete cracking under design loads. For jointed precast concrete diaphragms that rely on mechanical connectors, it may be necessary to include the joints and connectors in the finite element model. Strut-and-tie models may be used for diaphragm design. The strut-and-tie models should include considerations of force reversals that may occur under design load combinations.

R12.5—Design strength**R12.5.1 General**

R12.5.1.1 Design actions commonly include in-plane moment, with or without axial force; in-plane shear; and axial compression and tension in collectors and other elements acting as struts or ties. Some diaphragm configurations may result in additional types of design actions. For example, a diaphragm vertical step can result in out-of-plane bending, torsion, or both. The diaphragm is required to be designed for such actions where they occur in elements that are part of the load path.

Nominal strengths are prescribed in Chapter 22 for a diaphragm idealized as a beam or solid element resisting in-plane moment, axial force, and shear; and in Chapter 23 for a diaphragm or diaphragm segment idealized as a strut-and-tie system. Collectors and struts around openings can be designed as compression members subjected to axial force using provisions of 10.5.2 with the strength reduction factor for compression-controlled members in 21.2.2. For axial tension in such members, nominal tensile strength is $A_s f_y$, and the strength reduction factor is 0.90 as required for tension-controlled members in 21.2.2.

Diaphragms are designed under load combinations of 5.3. Where a diaphragm or part of a diaphragm is subjected to multiple load effects, the interaction of the load effects is to be considered. A common example is where a collector is built within a beam or slab that also resists gravity loads, in which case the element is designed for combined moment and axial force. Another example is where a connection is subjected to simultaneous tension and shear.

R12.5.1.3 Different design strength requirements apply depending on how the diaphragm load-path is idealized.

CODE

- (a) For a diaphragm idealized as a beam whose depth is equal to the full diaphragm depth, with moment resisted by boundary reinforcement concentrated at the diaphragm edges, design strengths shall be in accordance with 12.5.2 through 12.5.4.
- (b) For a diaphragm or a diaphragm segment modeled as a strut-and-tie system, design strengths shall be in accordance with 23.3.
- (c) For a diaphragm idealized with a finite-element model, design strengths shall be in accordance with Chapter 22. Nonuniform shear distributions shall be considered in design for shear. Collectors, where needed to transfer diaphragm shears to the vertical elements of the lateral-force-resisting system, shall be designed in accordance with 12.5.4.
- (d) For a diaphragm designed by alternative methods, such methods shall satisfy the requirements of equilibrium and shall provide design strengths at least equal to required strengths for all elements in the load path.

12.5.1.4 It shall be permitted to use precompression from prestressed reinforcement to resist diaphragm forces.

12.5.1.5 If nonprestressed, bonded prestressing reinforcement is designed to resist collector forces, diaphragm shear, or tension due to in-plane moment, the value of steel stress used to calculate resistance shall not exceed the lesser of the specified yield strength and 60,000 psi.

12.5.2 Moment and axial force

12.5.2.1 It shall be permitted to design a diaphragm to resist in-plane moment and axial force in accordance with 22.3 and 22.4.

COMMENTARY

Section 12.5.1.3(a) addresses requirements for the common case where a diaphragm is idealized as a beam spanning between supports and resisting forces within its plane, with chord reinforcement at the boundaries to resist in-plane moment and axial force. If diaphragms are designed according to this model, then it is appropriate to assume that shear flow is uniform through the diaphragm depth. Diaphragm depth refers to the dimension measured in the direction of lateral forces within the plane of the diaphragm (refer to Fig. R12.4.2.3a). If vertical elements of the lateral-force-resisting system do not extend the full depth of the diaphragm, then collectors are required to transfer shear acting along the remaining portions of the diaphragm depth to the vertical elements. Sections 12.5.2 through 12.5.4 are based on this model. This design approach is acceptable even if some of the moment is resisted by precompression as provided by 12.5.1.4.

Sections 12.5.1.3(b) through (d) permit alternative methods for design of diaphragms. If diaphragms are designed to resist moment through distributed chords, or if diaphragms are designed according to stress fields determined by finite-element analysis, then non-uniform shear flow should be taken into account.

R12.5.1.4 In the typical case of a prestressed floor slab, prestressing is required, at a minimum, to resist the factored load combination $1.2D + 1.6L$, where L may have been reduced as permitted by the general building code. For wind or earthquake design, however, the gravity load to be resisted by prestressing is reduced because the governing load combination is $1.2D + f_1L + (W \text{ or } E)$, where f_1 is either 1.0 or 0.5 depending on the nature of L . Thus, only a portion of the effective prestress is required to resist the reduced gravity loads. The remainder of the effective prestress can be used to resist in-plane diaphragm moments. Additional moment, if any, is resisted by added reinforcement.

R12.5.1.5 Nonprestressed bonded prestressing reinforcement, either strand or bars, is sometimes used to resist diaphragm design forces. The imposed limit on assumed yield strength is to control crack width and joint opening. The Code does not include provisions for developing nonprestressed, bonded prestressing reinforcement. Stress limits for other provided reinforcement are prescribed in Chapter 20.

R12.5.2 Moment and axial force

R12.5.2.1 This section permits design for moment and axial force in accordance with the usual assumptions of 22.3 and 22.4, including the assumption that strains vary linearly through the depth of the diaphragm. In most cases, design for moment and axial force can be accomplished satisfactorily using an approximate tension-compression couple with the strength reduction factor equal to 0.90.

CODE

12.5.2.2 It shall be permitted to resist tension due to moment by (a), (b), (c), or (d), or those methods in combination:

- (a) Deformed bars conforming to 20.2.1
- (b) Strands or bars conforming to 20.3.1, either prestressed or nonprestressed
- (c) Mechanical connectors crossing joints between precast elements
- (d) Precompression from prestressed reinforcement

12.5.2.3 Nonprestressed reinforcement and mechanical connectors resisting tension due to moment shall be located within $h/4$ of the tension edge of the diaphragm, where h is diaphragm depth measured in the plane of the diaphragm at that location. Where diaphragm depth changes along the span, it shall be permitted to develop reinforcement into adjacent diaphragm segments that are not within the $h/4$ limit.

COMMENTARY

R12.5.2.2 Bonded prestressing reinforcement used to resist in-plane moment and axial force can be either prestressed or nonprestressed. Mechanical connectors crossing joints between precast concrete elements are provided to complete a continuous load path for reinforcement embedded in those elements. The use of precompression from prestressed reinforcement is discussed in R12.5.1.4


R12.5.2.3 Figure R12.5.2.3 illustrates permitted locations of nonprestressed reinforcement resisting tension due to moment and axial force. Where diaphragm depth changes along the span, it is permitted to develop tension reinforcement in adjacent sections even if the reinforcement falls outside the $h/4$ limit of the adjacent section. In such cases, the strut-and-tie method or elastic plane stress analysis can be used to determine bar extensions and other reinforcement requirements to provide continuity across the step. The restriction on location of nonprestressed reinforcement and mechanical connectors is intended to control cracking and excessive joint opening that might occur near the edges if reinforcement or mechanical connectors were distributed throughout the diaphragm depth. The concentration of flexural tension reinforcement near the edge of the diaphragm also results in more uniform shear flow through the depth of the diaphragm.

There are no restrictions on placement of prestressed reinforcement provided to resist moment through precompression. In effect, the precompression determines a moment that the prestressed reinforcement can resist, with the remainder of the moment resisted by reinforcement or mechanical connectors placed in accordance with 12.5.2.3.

The Code does not require that diaphragm boundary elements resisting design flexural compression forces be detailed as columns. However, where a boundary element resists a large compressive force compared with axial strength, or is designed as a strut adjacent to an edge or opening, detailing with transverse reinforcement similar to column hoops should be considered.

CODE

COMMENTARY



Plan

Fig. R12.5.2.3—Locations of nonprestressed reinforcement resisting tension due to moment and axial force according to 12.5.2.3.

12.5.2.4 Mechanical connectors crossing joints between precast elements shall be designed to resist required tension under the anticipated joint opening.

R12.5.2.4 In an untopped precast diaphragm resisting in-plane forces and responding in the linear range, some joint opening (on the order of 0.1 in. or less) should be anticipated. A larger joint opening may occur under earthquake motions exceeding the design level. Mechanical connectors should be capable of maintaining design strength under the anticipated joint opening.

12.5.3 Shear

12.5.3.1 This section shall apply to diaphragm in-plane shear strength.

12.5.3.2 ϕ shall be 0.75, unless a lesser value is required by 21.2.4.

12.5.3.3 For a diaphragm that is entirely cast-in-place, V_n shall be calculated by Eq. (12.5.3.3).

$$V_n = A_{cv}(2\lambda\sqrt{f'_c} + \rho_t f_y) \quad (12.5.3.3)$$

R12.5.3 Shear

R12.5.3.1 These provisions assume that diaphragm shear flow is approximately uniform over the diaphragm depth, as is the case where design is in accordance with 12.5.1.3(a). Where alternative approaches are used, local variations of in-plane shear through the diaphragm depth should be considered.

R12.5.3.2 A lower strength reduction factor may be required in Seismic Design Categories D, E, or F, or where special systems for earthquake resistance are used.

R12.5.3.3 This provision was adapted from the earthquake-resistant design provisions of 18.12.9. The term A_{cv} refers to the cross-sectional area of the effective deep beam that forms the diaphragm.

CODE

where A_{cv} is the gross area of concrete bounded by diaphragm web thickness and depth, reduced by void areas if present; the value of $\sqrt{f'_c}$ used to calculate V_n shall not exceed 100 psi; and ρ_t refers to the distributed reinforcement oriented parallel to the in-plane shear.

12.5.3.4 For a diaphragm that is entirely cast-in-place, cross-sectional dimensions shall be selected to satisfy Eq. (12.5.3.4).

$$V_u \leq \phi 8 A_{cv} \sqrt{f'_c} \quad (12.5.3.4)$$

where the value of $\sqrt{f'_c}$ used to calculate V_n shall not exceed 100 psi.

12.5.3.5 For diaphragms that are cast-in-place concrete topping slabs on precast elements, (a) and (b) shall be satisfied:

(a) V_n shall be calculated in accordance with Eq. (12.5.3.3), and cross-sectional dimensions shall be selected to satisfy Eq. (12.5.3.4). A_{cv} shall be calculated using the thickness of the topping slab for noncomposite topping slab diaphragms and the combined thickness of cast-in-place and precast elements for composite topping slab diaphragms. For composite topping slab diaphragms, the value of f'_c in Eq. (12.5.3.3) and (12.5.3.4) shall not exceed the lesser of f'_c for the precast members and f'_c for the topping slab.

(b) V_n shall not exceed the value calculated in accordance with the shear-friction provisions of 22.9 considering the thickness of the topping slab above joints between precast elements in noncomposite and composite topping slab diaphragms and the reinforcement crossing the joints between the precast members.

12.5.3.6 For diaphragms that are interconnected precast elements without a concrete topping, and for diaphragms that are precast elements with end strips formed by either a cast-in-place concrete topping slab or edge beams, it shall be permitted to design for shear in accordance with (a), (b), or both.

(a) The nominal strength of grouted joints shall not exceed 80 psi. Reinforcement shall be designed to resist shear through shear-friction in accordance with 22.9. Shear-friction reinforcement shall be in addition to reinforcement designed to resist tension due to moment and axial force.

(b) Mechanical connectors crossing joints between precast elements shall be designed to resist required shear under anticipated joint opening.

12.5.3.7 For any diaphragm, where shear is transferred from the diaphragm to a collector, or from the diaphragm or

COMMENTARY

R12.5.3.5 For diaphragms with cast-in-place topping slab on precast elements, the effective thickness in 12.5.3.5(a) is reduced to the topping slab thickness if the topping slab is not composite with the precast elements. Topping slabs tend to develop cracks above and along the joints between precast elements. Thus, 12.5.3.5(b) limits the shear strength to the shear-friction strength of the topping slab above the joints between the precast elements.

R12.5.3.6 ACI CODE-318 does not contain provisions for untopped diaphragms in buildings assigned to Seismic Design Categories D, E, and F. Diaphragm shear in untopped diaphragms can be resisted by using shear-friction reinforcement in grouted joints (**FEMA P-751**). Required shear-friction reinforcement is in addition to reinforcement required by design to resist other tensile forces in the diaphragm, such as those due to diaphragm moment and axial force, or due to collector tension. The intent is to reduce joint opening while simultaneously resisting shear through shear-friction. Alternatively, or additionally, mechanical connectors can be used to transfer shear across joints of precast elements. In this case, some joint opening should be anticipated. The mechanical connectors should be capable of maintaining design strength under anticipated joint opening.

R12.5.3.7 In addition to having adequate shear strength within its plane, a diaphragm should be reinforced to transfer shear through shear-friction or mechanical connectors to

CODE

collector to a vertical element of the lateral-force-resisting system, (a) or (b) shall apply:

- (a) Where shear is transferred through concrete, the shear-friction provisions of 22.9 shall be satisfied.
- (b) Where shear is transferred through mechanical connectors or dowels, effects of uplift and rotation of the vertical element of the lateral-force-resisting system shall be considered.

COMMENTARY

collectors and to vertical elements of the lateral-force-resisting system. In diaphragms that are entirely cast-in-place, reinforcement provided for other purposes usually is adequate to transfer force from the diaphragm into the collectors through shear-friction. However, additional reinforcement may be required to transfer diaphragm or collector shear into vertical elements of the lateral-force-resisting system through shear-friction. Figure R12.5.3.7 illustrates a common detail of dowels provided for this purpose.




Fig. R12.5.3.7—Typical detail showing dowels provided for shear transfer to a structural wall through shear-friction.

12.5.4 Collectors

12.5.4.1 Collectors shall extend from the vertical elements of the lateral-force-resisting system across all or part of the diaphragm depth as required to transfer shear from the diaphragm to the vertical element. It shall be permitted to discontinue a collector along lengths of vertical elements of the lateral-force-resisting system where transfer of design collector forces is not required.

R12.5.4 Collectors

A collector is a region of a diaphragm that transfers forces between the diaphragm and a vertical element of the lateral-force-resisting system. A collector can extend transversely into the diaphragm to reduce nominal stresses and reinforcement congestion, as shown in Fig. R12.5.3.7. Where a collector width extends into the slab, the collector width on each side of the vertical element should not exceed approximately one-half the contact length between the collector and the vertical element.

R12.5.4.1 The design procedure in 12.5.1.3(a) models the diaphragm as a full-depth beam with uniform shear flow. If vertical elements of the lateral-force-resisting system do not extend the full depth of the diaphragm, then collectors are required to transfer shear acting along the remaining portions of the diaphragm depth to the vertical element, as shown in Fig. R12.5.4.1. Partial-depth collectors can also be considered, but a complete force path should be designed that is capable of transmitting all forces from the diaphragm to the collector and into the vertical elements (Moeble et al. 2010).

CODE

12.5.4.2 Collectors shall be designed as tension members, compression members, or both, in accordance with 22.4.

12.5.4.3 Where a collector is designed to transfer forces to a vertical element, collector reinforcement shall extend along the vertical element at least the greater of (a) and (b):

- (a) The length required to develop the reinforcement in tension
- (b) The length required to transmit the design forces to the vertical element through shear-friction in accordance with 22.9, through mechanical connectors, or through other force transfer mechanisms

COMMENTARY




Fig. R12.5.4.1—Full-depth collector and shear-friction reinforcement required to transfer collector force into wall.

R12.5.4.2 Tension and compression forces in a collector are determined by the diaphragm shear forces they transmit to the vertical elements of the lateral-force-resisting system (refer to Fig. R12.5.4.1). Except as required by 18.12.7.6, the Code does not require that collectors resisting design compressive forces be detailed as columns. However, in structures where collectors resist large compressive forces compared with axial strength, or are designed as struts passing adjacent to edges or openings, detailing with transverse reinforcement similar to column hoops should be considered. Such detailing is required by 18.12.7.6 for some diaphragms in buildings assigned to Seismic Design Categories D, E, and F.

R12.5.4.3 In addition to having sufficient development length, the collector reinforcement should be extended as needed to fully transfer its forces into the vertical elements of the lateral-force-resisting system. A common practice is to extend some of the collector reinforcement the full length of the vertical element, such that collector forces can be transmitted uniformly through shear-friction (refer to Fig. R12.5.4.1). Figure R12.5.4.3 shows an example of collector reinforcement extended as required to transfer forces into three frame columns.

CODE

COMMENTARY

Note: Collector reinforcement should extend as required to transfer forces into the vertical element and should be developed at critical sections.




Fig. R12.5.4.3—Schematic force transfer from collector into vertical element of the lateral-force-resisting system.

12.6—Reinforcement limits

12.6.1 Except for slabs-on-ground, diaphragms shall satisfy reinforcement limits for one-way slabs in accordance with 7.6 or two-way slabs in accordance with 8.6, as applicable.

12.6.2 For diaphragms that comprise a cast-in-place topping slab on precast elements, the topping slab shall be reinforced in accordance with 24.4 in each direction.

12.6.3 Reinforcement designed to resist diaphragm in-plane forces shall be in addition to reinforcement designed to resist other load effects, except reinforcement designed to resist shrinkage and temperature load effects shall be permitted to also resist diaphragm in-plane forces

R12.6—Reinforcement limits

R12.6.1 Minimum reinforcement for diaphragms that comprise a cast-in-place topping on steel decking can be found in SDI SD.

12.7—Reinforcement detailing

12.7.1 General

12.7.1.1 Concrete cover for reinforcement shall be in accordance with 20.5.1.

12.7.1.2 Development lengths of deformed and prestressed reinforcement shall be in accordance with 25.4, unless longer lengths are required by Chapter 18.

12.7.1.3 Splices of deformed reinforcement shall be in accordance with 25.5.

12.7.1.4 Bundled bars shall be in accordance with 25.6.

12.7.2 Reinforcement spacing

12.7.2.1 Minimum spacing s of reinforcement shall be in accordance with 25.2.

R12.7—Reinforcement detailing

R12.7.1 General

R12.7.1.1 For a structure assigned to Seismic Design Category D, E, or F, concrete cover may be governed by the requirements of 18.12.7.7.

R12.7.2 Reinforcement spacing

R12.7.2.1 For a structure assigned to Seismic Design Category D, E, or F, spacing of confining reinforcement in collectors may be governed by the requirements of 18.12.7.6

CODE

12.7.2.2 Maximum spacing s of deformed reinforcement shall be the lesser of five times the diaphragm thickness and 18 in.

12.7.3 *Diaphragm and collector reinforcement*

12.7.3.1 Except for slabs-on-ground, diaphragms shall satisfy reinforcement detailing of one-way slabs in accordance with 7.7 or two-way slabs in accordance with 8.7, as applicable.

12.7.3.2 Calculated tensile or compressive force in reinforcement at each section of the diaphragm or collector shall be developed on each side of that section.

12.7.3.3 Reinforcement provided to resist tension shall extend beyond the point at which it is no longer required to resist tension at least ℓ_d , except at diaphragm edges and at expansion joints.

COMMENTARY

R12.7.3 *Diaphragm and collector reinforcement*

R12.7.3.2 Critical sections for development of reinforcement generally are at points of maximum stress, at points where adjacent terminated reinforcement is no longer required to resist design forces, and at other points of discontinuity in the diaphragm.

R12.7.3.3 For a beam, the Code requires flexural reinforcement to extend the greater of d and $12d_b$ past points where it is no longer required for flexure. These extensions are important for a beam to protect against development or shear failure that could result from inaccuracies in calculated locations of tensile stress. Similar failures in diaphragms have not been reported. To simplify design and avoid excessively long bar extensions that could result if the beam provisions were applied to diaphragms, this provision only requires that tension reinforcement extend ℓ_d beyond points where it is no longer required to resist tension.

Notes



CHAPTER 13—FOUNDATIONS

CODE

COMMENTARY

13.1—Scope

13.1.1 This chapter shall apply to the design of nonprestressed and prestressed foundations, including shallow foundations (a) through (e), deep foundations (f) through (i), cantilever retaining walls (j) and (k), and basement walls (l):

- (a) Strip footings
- (b) Isolated footings
- (c) Combined footings
- (d) Mat foundations
- (e) Grade beams
- (f) Pile caps
- (g) Piles
- (h) Drilled piers
- (i) Caissons
- (j) Cantilever retaining walls
- (k) Counterfort and buttressed cantilever retaining walls
- (l) Basement walls

R13.1—Scope









R13.1.1 Examples of foundation types covered by this chapter are illustrated in Fig. R13.1.1. Stepped and sloped footings are considered to be subsets of other footing types.

The Code contains provisions for the design of deep foundations. These provisions are based in part on similar provisions that were previously included in **ASCE/SEI 7** and the **IBC**.



CODE

COMMENTARY

*Strip footing**Isolated footing**Stepped footing**Combined footing**Mat foundation**Deep foundation system with piles and pile cap**Counterfort/butressed**Fig. R13.1.1—Types of foundations.*

13.1.2 Foundations excluded by 1.4.7 are excluded from this chapter.

CODE

13.2—General**13.2.1 Materials**

13.2.1.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

13.2.1.2 Design properties for steel reinforcement shall be selected to be in accordance with **Chapter 20**.

13.2.1.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

13.2.2 Connection to other members

13.2.2.1 Design and detailing of cast-in-place and precast column, pedestal, and wall connections to foundations shall be in accordance with **16.3**.

13.2.3 Earthquake effects

13.2.3.1 Structural members extending below the base of the structure that are required to transmit forces resulting from earthquake effects to the foundation shall be designed in accordance with **18.2.2.3**.

13.2.3.2 For structures assigned to Seismic Design Category (SDC) C, D, E, or F, foundations resisting earthquake-induced forces or transferring earthquake-induced forces between structure and ground shall be designed in accordance with **18.13**.

13.2.4 Slabs-on-ground

13.2.4.1 Slabs-on-ground that transmit vertical loads or lateral forces from other parts of the structure to the ground shall be designed and detailed in accordance with applicable provisions of this Code.

13.2.4.2 Slabs-on-ground that transmit lateral forces as part of the seismic-force-resisting system shall be designed in accordance with **18.13**.

COMMENTARY

R13.2—General**R13.2.3 Earthquake effects**

R13.2.3.1 The base of a structure, as defined in analysis, does not necessarily correspond to the foundation or ground level, or to the base of a building as defined in the general building code for planning (for example, for height limits or fire protection requirements). Details of columns and walls extending below the base of a structure to the foundation are required to be consistent with those above the base of the structure. For additional discussion of the design of foundations for earthquake effects, see **R18.13.1**.

R13.2.4 Slabs-on-ground

Slabs-on-ground often act as a diaphragm to hold the building together at the ground level and minimize the effects of out-of-phase ground motion that may occur over the footprint of the building. In these cases, the slab-on-ground should be adequately reinforced and detailed. As required in **Chapter 26**, construction documents should clearly state that these slabs-on-ground are structural members so as to prohibit sawcutting of such slabs.

CODE

13.2.5 Plain concrete

13.2.5.1 Plain concrete foundations shall be designed in accordance with **Chapter 14**.

13.2.6 Design criteria

13.2.6.1 Foundations shall be proportioned for bearing effects, stability against overturning and sliding at the soil-foundation interface in accordance with the general building code.

13.2.6.2 For shallow foundation members continuously supported by soil and designed based on the assumption of rigid behavior of the shallow member, (a) and (b) shall be permitted:

(a) For one-way shear strength, V_c shall be taken as:

$$V_c = 2\lambda\sqrt{f'_c}b_wd$$

(b) For two-way shear strength, the size effect factor, λ_s , specified in **22.6**, shall be taken equal to 1.0.

13.2.6.3 Foundation members shall be designed to resist factored loads and corresponding induced reactions except as permitted by 13.4.2.

COMMENTARY

R13.2.6 Design criteria

R13.2.6.1 Permissible soil pressures or permissible deep foundation strengths are determined by principles of soil mechanics and in accordance with the general building code. The size of the base area of a footing on soil or the number and arrangement of deep foundation members are established by using allowable geotechnical strength and service-level load combinations or by using nominal geotechnical strength with resistance factor and factored load combinations.

Only the calculated end moments at the base of a column or pedestal require transfer to the footing. The minimum moment requirement for slenderness considerations given in **6.6.4.5** need not be considered for transfer of forces and moments to footings.

R13.2.6.2 Both (a) and (b) are permitted because shallow foundation members directly bearing on soil or supported on closely spaced piles, and designed under previous editions of the Code, have exhibited satisfactory behavior, without consideration of the influence of size effect or flexural reinforcement effect on shear strength. This differs from the observed shear behavior of concrete members not directly bearing on soil, which is the type of member investigated in the body of laboratory research that formed the basis of the size effect and flexural reinforcement effect provisions introduced in **ACI CODE-318-19**.

The reasons for such differences may be due to many factors. Influencing factors may include the overestimation of the design shear forces generated by soil bearing pressures, the development of stiffer and stronger shear transfer mechanisms including arching action, or the development of friction forces or passive pressures that mitigate cracking as a result of the interaction of the shallow foundation member with the soil. Approximate methods traditionally used to estimate soil bearing pressures acting on shallow foundation members, and the assumed uniform distribution of those pressures beneath the foundation, may overestimate design shear forces in common types of shallow foundations.

This provision is based on the assumption of rigid member behavior. Shallow foundation members or portions of these members that are designed considering the stiffness interaction between the soil and the member may not benefit from the conservative stress distributions resulting from the rigid foundation assumption.

R13.2.6.3 To design a footing or pile cap for strength, the induced reactions due to factored loads applied to the foundation should be determined. For a single concentrically-loaded spread footing, the soil pressure due to factored

CODE

13.2.6.4 Foundation systems shall be permitted to be designed by any procedure satisfying equilibrium and geometric compatibility.

13.2.6.5 Foundation design in accordance with the strut-and-tie method, **Chapter 23**, shall be permitted.

COMMENTARY

loading is calculated as the factored load divided by the base area of the footing. For the case of footings or mats with eccentric loading, applied factored loads may be used to determine soil pressures. For pile caps or mats supported by deep foundations, applied factored loads may be used to determine member reactions. However, the resulting pressures or reactions may be incompatible with the geotechnical design resulting in unacceptable subgrade reactions or instability (**Rogowsky and Wight 2010**). In such cases, the design should be adjusted in coordination with the geotechnical engineer.

Only the calculated end moments at the base of a column or pedestal require transfer to the footing. The minimum moment requirements for slenderness considerations given in **6.6.4.5** need not be considered for transfer of forces and moments to footings.

R13.2.6.4 Foundation design is permitted to be based directly on fundamental principles of structural mechanics, provided it can be demonstrated that all strength and serviceability criteria are satisfied. Design of the foundation may be achieved through the use of classic solutions based on a linearly elastic continuum, numerical solutions based on discrete elements, or yield-line analyses. In all cases, analyses and evaluation of the stress conditions at points of load application or pile reactions in relation to shear and torsion, as well as flexure, should be included.

R13.2.6.5 An example of the application of this provision is a pile cap similar to that shown in Fig. R13.1.1. Pile caps may be designed using a three-dimensional strut-and-tie model satisfying Chapter 23 (**Adebar et al. 1990**) provided the shear force limits of **23.4.4** are also satisfied.

Figure R13.2.6.5 illustrates the application of the shear force limits of **23.4.4** and the provisions of **13.2.7.2** for one-way shear design of a spread footing using the strut-and-tie method. Soil pressure within d from the face of the column or wall does not contribute to shear across the critical crack (**Uzel et al. 2011**), but the soil pressure within d contributes to the bending moment at the face of the column or wall.

CODE

COMMENTARY




Fig. R13.2.6.5—One-way shear design of a spread footing using the strut-and-tie method.

13.2.6.6 External moment on any section of a strip footing, isolated footing, or pile cap shall be calculated by passing a vertical plane through the member and calculating the moment of the forces acting over the entire area of member on one side of that vertical plane.

13.2.7 Critical sections for shallow foundations and pile caps

13.2.7.1 M_u at the supported member shall be permitted to be calculated at the critical section defined in accordance with Table 13.2.7.1.

Table 13.2.7.1—Location of critical section for M_u

Supported member	Location of critical section
Column or pedestal	Face of column or pedestal
Column with steel base plate	Halfway between face of column and edge of steel base plate
Concrete wall	Face of wall
Masonry wall	Halfway between center and face of masonry wall

13.2.7.2 The location of critical section for factored shear in accordance with 7.4.3 and 8.4.3 for one-way shear or 8.4.4.1 for two-way shear shall be measured from the location of the critical section for M_u in 13.2.7.1.

R13.2.7 Critical sections for shallow foundations and pile caps

R13.2.7.2 The shear strength of a footing is determined for the more severe condition of 8.5.3.1.1 and 8.5.3.1.2. The critical section for shear is measured from the face of the supported member (column, pedestal, or wall), except for masonry walls and members supported on steel base plates.

Calculation of shear requires that the soil reaction be obtained from factored loads, and the design strength be in accordance with Chapter 22.

Where necessary, shear around individual piles may be investigated in accordance with 8.5.3.1.2. If shear perimeters overlap, the modified critical perimeter b_o should be taken as that portion of the smallest envelope of individual shear perimeters that will actually resist the critical shear for the group under consideration. One such situation is illustrated in Fig. R13.2.7.2.

CODE

COMMENTARY




Fig. R13.2.7.2—Modified critical perimeter for shear with overlapping critical perimeters.

13.2.7.3 Circular or regular polygon-shaped concrete columns or pedestals shall be permitted to be treated as square members of equivalent area when locating critical sections for moment, shear, and development of reinforcement.

13.2.8 *Development of reinforcement in shallow foundations and pile caps*

13.2.8.1 Development of reinforcement shall be in accordance with **Chapter 25**.

13.2.8.2 Calculated tensile or compressive force in reinforcement at each section shall be developed on each side of that section.

13.2.8.3 Critical sections for development of reinforcement shall be assumed at the same locations as given in 13.2.7.1 for maximum factored moment and at all other vertical planes where changes of section or reinforcement occur.

13.2.8.4 Adequate embedment shall be provided for tension reinforcement where reinforcement stress is not directly proportional to moment, such as in sloped, stepped, or tapered foundations; or where tension reinforcement is not parallel to the compression face.

13.2.9 *Concrete cover*

13.2.9.1 Concrete cover for reinforcement in foundation members shall be in accordance with **20.5.1.3**.

13.3—Shallow foundations

13.3.1 *General*

13.3.1.1 Minimum base area of foundation shall be proportioned to not exceed the permissible bearing pressure when

R13.2.9 *Concrete cover*

R13.2.9.1 Specific cover requirements for deep foundation members are given in **20.5.1.3.4**.

R13.3—Shallow foundations

R13.3.1 *General*

R13.3.1.1 General discussion on the sizing of shallow foundations is provided in R13.2.6.1.

CODE**COMMENTARY**

subjected to forces and moments applied to the foundation. Permissible bearing pressures shall be determined through principles of soil or rock mechanics in accordance with the general building code, or other requirements as determined by the building official.

13.3.1.2 Overall depth of foundation shall be selected such that the effective depth of bottom reinforcement is at least 6 in.

13.3.1.3 In sloped, stepped, or tapered foundations, depth and location of steps or angle of slope shall be such that design requirements are satisfied at every section.

13.3.2 *One-way shallow foundations*

13.3.2.1 The design and detailing of one-way shallow foundations, including strip footings, combined footings, and grade beams, shall be in accordance with this section and the applicable provisions of **Chapter 7** and **Chapter 9**.

13.3.2.2 Reinforcement shall be distributed uniformly across entire width of one-way footings.

13.3.3 *Two-way isolated footings*

13.3.3.1 The design and detailing of two-way isolated footings shall be in accordance with this section and the applicable provisions of **Chapter 7** and **Chapter 8**.

13.3.3.2 In square two-way footings, reinforcement shall be distributed uniformly across entire width of footing in both directions.

13.3.3.3 In rectangular footings, reinforcement shall be distributed in accordance with (a) and (b):

- (a) Reinforcement in the long direction shall be distributed uniformly across entire width of footing.
- (b) For reinforcement in the short direction, a portion of the total reinforcement, $\gamma_s A_s$, shall be distributed uniformly over a band width equal to the length of short side of footing, centered on centerline of column or pedestal. Remainder of reinforcement required in the short direction, $(1 - \gamma_s)A_s$, shall be distributed uniformly outside the center band width of footing, where γ_s is calculated by:

$$\gamma_s = \frac{2}{(\beta + 1)} \quad (13.3.3.3)$$

where β is the ratio of long to short side of footing.

R13.3.1.3 Anchorage of reinforcement in sloped, stepped, or tapered foundations is addressed in 13.2.8.4.

R13.3.3 *Two-way isolated footings*

R13.3.3.3 To minimize potential construction errors in placing bars, a common practice is to increase the amount of reinforcement in the short direction by $2\beta/(\beta + 1)$ and space it uniformly along the long dimension of the footing (*CRSI Handbook 1984; Fling 1987*).

CODE

13.3.4 *Two-way combined footings and mat foundations*

13.3.4.1 The design and detailing of combined footings and mat foundations shall be in accordance with this section and the applicable provisions of **Chapter 8**.

13.3.4.2 The direct design method shall not be used to design combined footings and mat foundations.

13.3.4.3 Distribution of bearing pressure under combined footings and mat foundations shall be consistent with properties of the soil or rock and the structure, and with established principles of soil or rock mechanics.

13.3.4.4 Minimum reinforcement in nonprestressed mat foundations shall be in accordance with **8.6.1.1**.

13.3.5 *Walls as grade beams*

13.3.5.1 The design of walls as grade beams shall be in accordance with the applicable provisions of **Chapter 9**.

13.3.5.2 If a grade beam wall is considered a deep beam in accordance with **9.9.1.1**, design shall satisfy the requirements of **9.9**.

13.3.5.3 Grade beam walls shall satisfy the minimum reinforcement requirements of **11.6**.

13.3.6 *Wall components of cantilever retaining walls*

13.3.6.1 The stem of a cantilever retaining wall shall be designed as a one-way slab in accordance with the applicable provisions of **Chapter 7**.

13.3.6.1.1 It shall be permitted to calculate V_c for cantilever retaining walls as:

$$V_c = 2\lambda\sqrt{f'_c}b_wd$$

13.3.6.2 The stem of a counterfort or buttressed cantilever retaining wall shall be designed as a two-way slab in accordance with the applicable provisions of **Chapter 8**.

13.3.6.3 For walls of uniform thickness, the critical section for shear and flexure shall be at the interface between the stem and the footing. For walls with a tapered or varied thickness, shear and moment shall be investigated throughout the height of the wall.

COMMENTARY

R13.3.4 *Two-way combined footings and mat foundations*

R13.3.4.1 Detailed recommendations for design of combined footings and mat foundations are reported by **ACI PRC-336.2**. Also refer to **Kramrisch and Rogers (1961)**.

R13.3.4.2 The direct design method is a method used for the design of two-way slabs. Refer to **R6.2.4.1**.

R13.3.4.3 Design methods using factored loads and strength reduction factors ϕ can be applied to combined footings or mat foundations, regardless of the bearing pressure distribution.

R13.3.4.4 To improve crack control due to thermal gradients and to intercept potential punching shear cracks with tension reinforcement, the licensed design professional should consider specifying continuous reinforcement in each direction near both faces of mat foundations.

R13.3.6 *Wall components of cantilever retaining walls*

R13.3.6.1.1 This provision is supported by a history of successful performance of cantilever retaining walls designed using the 2014 and earlier editions of the Code (**Lew et al. 2010**). This provision does not apply to wall footings.

R13.3.6.2 Counterfort or buttressed cantilever retaining walls tend to behave more in two-way action than in one-way action; therefore, additional care should be given to crack control in both directions.

R13.3.6.3 In general, the joint between the wall stem and the footing will be opening under lateral loads; therefore, the critical section should be at the face of the joint. If hooks are required to develop the wall flexural reinforcement, hooks should be located near the bottom of the footing with the free

CODE

COMMENTARY

end of the bars oriented toward the opposite face of the wall (Nilsson and Losberg 1976).

13.3.7 Basement walls

13.3.7.1 The design of basement walls to resist out-of-plane lateral earth pressure shall satisfy (a) through (e):

- (a) Basement walls shall be designed as one-way slabs in accordance with the applicable provisions of **Chapter 7** or as two-way slabs in accordance with the applicable provisions of **Chapter 8**.
- (b) Basement walls shall be designed to resist hydrostatic pressure, if applicable.
- (c) It shall be permitted to calculate the one-way shear strength of concrete as $V_c = 2\lambda\sqrt{f'_c}b_wd$
- (d) For two-way shear strength, the size effect factor λ_{ss} , as specified in **22.6**, shall be taken equal to 1.0.
- (e) Basement walls shall satisfy the applicable provisions of **Chapter 18**.

13.3.7.2 For loads other than out-of-plane lateral earth pressure, basement walls shall satisfy the applicable provisions of **Chapter 11**.

13.4—Deep foundations**13.4.1 General**

13.4.1.1 Number and arrangement of deep foundation members shall be determined such that forces and moments applied to the foundation do not exceed the permissible deep foundation strength. Permissible deep foundation strength shall be determined through principles of soil or rock mechanics in accordance with the general building code, or other requirements as determined by the building official.

13.4.1.2 Portions of deep foundation members in air, water, or soils not capable of providing adequate lateral restraint to prevent buckling shall be designed as a column or pedestal, in accordance with the applicable provisions of **Chapter 10** and **Chapter 14**, where ϕ shall be determined in accordance with 13.4.3.2.

13.4.1.3 The least side dimension of precast deep foundation members shall not be smaller than 10 in. The diameter of cast-in-place deep foundation members shall not be smaller than 12 in., except 10 in. diameter members are permissible for residential and utility use and occupancy classifications with stud bearing wall construction two stories or less above grade.

13.4.1.4 Design shall consider the effects of potential mislocation of any deep foundation member by at least 3 in. Where the effects of mislocation are being considered, it shall be permitted to increase the axial compressive strength of the deep foundation members by 10%.

R13.3.7 Basement walls

R13.3.7.1 Historically, in the design of basement walls, a two-dimensional analysis is performed and the design lateral earth pressure is not reduced to take advantage of soil arching. This practice has contributed to the successful performance of basement walls designed under previous editions of the Code (Lew et al. 2010). There is a lack of experimental data on the shear strength of basement walls under lateral earth pressure, and there is uncertainty as to the actual load demand on basement walls. If alternative analysis methods are used to reduce the design lateral earth pressure or to obtain a more favorable load distribution, it may be more appropriate to calculate shear strengths according to **22.5.5**.

R13.4—Deep foundations**R13.4.1 General**

R13.4.1.1 General discussion on selecting the number and arrangement of piles, drilled piers, and caissons is provided in R13.2.6.1.

R13.4.1.3 The least side dimension of 10 in. refers to that of a square, or the shortest side of a rectangular cross section, or, for the case of octagonal piles, the diameter of the largest circle that can be inscribed in the octagon.

R13.4.1.4 Due to subsurface obstructions or other reasons, deep foundation members are not always installed within the specified tolerance from their design location. In such cases, the axial load distribution in a group of deep foundation members may cause some of the members to be overloaded.

CODE

13.4.1.5 Design of deep foundation members shall be in accordance with 13.4.2 or 13.4.3.

13.4.2 Allowable axial strength

13.4.2.1 It shall be permitted to design a deep foundation member using load combinations for allowable stress design in **ASCE/SEI 7**, Section 2.4, and the allowable strength specified in Table 13.4.2.1 if (a) and (b) are satisfied:

- (a) The deep foundation member is laterally supported for its entire height
- (b) The applied forces cause bending moments in the deep foundation member less than the moment due to an accidental eccentricity of 5% of the member diameter or width

Table 13.4.2.1—Maximum allowable compressive strength for deep foundation members

Deep foundation member type	Maximum allowable compressive strength ^[1]	
Uncased cast-in-place concrete drilled or augered pile	$P_a = 0.33f'_c A_g + 0.4f_y A_s$	(a)
Cast-in-place concrete pile in rock or within a pipe, tube, or other permanent metal casing that does not satisfy 13.4.2.3	$P_a = 0.33f'_c A_g + 0.4f_y A_s$ ^[2]	(b)
Metal cased concrete pile confined in accordance with 13.4.2.3	$P_a = 0.4f'_c A_g$	(c)
Precast nonprestressed concrete pile	$P_a = 0.33f'_c A_g + 0.4f_y A_s$	(d)
Precast prestressed concrete pile	$P_a = (0.33f'_c - 0.27f_{pc})A_g$	(e)

^[1] A_g applies to the gross cross-sectional area. If a temporary or permanent casing is used, the inside face of the casing shall be considered the concrete surface.

^[2] A_s does not include the steel casing, pipe, or tube.

COMMENTARY

Members installed exceeding this mislocation limit may require further remediation such as installation of additional deep foundation members. When deep foundation members are installed out of position, the resulting eccentricity can produce additional bending moments in the deep foundation member, the structure above, or both. Design should consider how the mislocation of deep foundation members will impact the deep foundation members and any components of the superstructure above.

R13.4.1.5 In addition to the provisions in the Code, recommendations for concrete piles are given in **ACI PRC-543**, recommendations for drilled piers are given in **ACI PRC-336.3**, and recommendations for precast prestressed concrete piles are given in “Recommended Practice for Design, Manufacture, and Installation of Prestressed Concrete Piling” (**PCI 2019**).

R13.4.2 Allowable axial strength

R13.4.2.1 Potential changes to lateral support of the deep foundation member due to liquefaction, excavation, scour, or other causes, should be considered.

The values in Table 13.4.2.1 represent an upper bound for well understood soil conditions and quality workmanship. A lower value for the maximum allowable compressive strength may be appropriate, depending on soil conditions and the construction and quality control procedures used. For augered cast-in-place piles, where grout is placed through the stem of a hollow-stem auger as it is withdrawn from the soil, the strength coefficient of 0.3 is based on a strength reduction factor of 0.6. The designer should carefully consider the reliable grout strength, grout strength testing methods, and the minimum cross-sectional area of the member, accounting for soil conditions and construction procedures. Additional information is provided in **ACI PRC-543**.

CODE

13.4.2.2 If 13.4.2.1(a) or 13.4.2.1(b) is not satisfied, a deep foundation member shall be designed using strength design in accordance with 13.4.3.

13.4.2.3 Metal cased cast-in-place concrete deep foundation members shall be considered to be confined if (a) through (f) are satisfied:

- (a) Design shall not use the casing to resist any portion of the axial load imposed.
- (b) Casing shall have a sealed tip and shall be mandrel-driven.
- (c) Thickness of the casing shall not be less than manufacturer's standard gauge No. 14 (0.068 in.).
- (d) Casing shall be seamless, or provided with seams of strength equal to the basic material, and be of a configuration that will provide confinement to the cast-in-place concrete.
- (e) Ratio of yield strength of the steel casing to f'_c shall be at least 6, and yield strength shall be at least 30,000 psi.
- (f) Nominal diameter of the member shall be less than or equal to 16 in.

13.4.2.4 The use of allowable strengths greater than those specified in Table 13.4.2.1 shall be permitted if accepted by the building official in accordance with 1.10 and justified by load tests.

13.4.3 Strength design

13.4.3.1 Strength design in accordance with this section is permitted for all deep foundation members.

13.4.3.2 The strength design of deep foundation members shall be in accordance with 10.5 using the compressive strength reduction factors of Table 13.4.3.2 for axial load without moment, and the strength reduction factors of Table 21.2.1 for tension, shear, and combined axial force and moment. The provisions of 22.4.2.4 and 22.4.2.5 shall not apply to deep foundations.

COMMENTARY

R13.4.2.3 The basis for this allowable strength is the added strength provided to the concrete by the confining action of the steel casing. This strength applies only to non-axial load-bearing steel where the stress in the steel is taken in hoop tension instead of axial compression. In this Code, steel pile casing is not to be considered in the design of the pile to resist a portion of the pile axial load. Provisions for members designed to be composite with steel pipe or casing are covered in [ANSI/AISC 360](#).

Potential corrosion of the metal casing should be considered; provision is based on a non-corrosive environment.

R13.4.2.4 Geotechnical and load test requirements for deep foundation members can be found in the [IBC](#).

R13.4.3 Strength design

R13.4.3.2 The strength design of deep foundation members is discussed in detail in [ACI PRC-543](#).

If cast-in-place concrete drilled or augered piles are subject to flexure, shear, or tension loads, the strength reduction factors should be adjusted accordingly, considering the soil conditions, quality-control procedures that will be implemented, likely workmanship quality, and local experience. Guidance for adjustment factors is provided in [ACI PRC-543](#).

CODE

COMMENTARY

Table 13.4.3.2—Compressive strength reduction factors ϕ for deep foundation members

Deep foundation member type	Compressive strength reduction factors ϕ	
Uncased cast-in-place concrete drilled or augered pile ^[1]	0.55	(a)
Cast-in-place concrete pile in rock or within a pipe, tube, ^[2] or other permanent casing that does not satisfy 13.4.2.3	0.60	(b)
Cast-in-place concrete-filled steel pipe pile ^[3]	0.70	(c)
Metal cased concrete pile confined in accordance with 13.4.2.3	0.65	(d)
Precast-nonprestressed concrete pile	0.65	(e)
Precast-prestressed concrete pile	0.65	(f)

^[1]The factor of 0.55 represents an upper bound for well understood soil conditions with quality workmanship. A lower value for the strength reduction factor may be appropriate, depending on soil conditions and the construction and quality control procedures used.

^[2]For wall thickness of the steel pipe or tube less than 0.25 in.

^[3]Wall thickness of the steel pipe shall be at least 0.25 in.

13.4.4 Cast-in-place deep foundations**R13.4.4 Cast-in-place deep foundations**

13.4.4.1 Cast-in-place deep foundation members subject to uplift or $M_u \geq 0.4M_{cr}$ shall be reinforced, unless enclosed by a structural steel pipe or tube. Where required, reinforcement shall be provided in accordance with 13.4.4.1.1 and 13.4.4.2.

13.4.4.1.1 Minimum reinforcement for deep foundation members supporting structures assigned to SDC A or B shall be in accordance with (a) through (f), except as permitted by 13.4.4.1.2.

- (a) Minimum number of longitudinal bars shall be in accordance with 10.7.3.1.
- (b) The area of longitudinal reinforcement shall be at least $0.0025 A_g$ unless both the design axial and flexural strength are at least 4/3 of the required strengths and $M_u \leq 0.4M_{cr}$.
- (c) Longitudinal reinforcement shall extend from the top of the deep foundation member to a distance of 10 ft or 3 times the member diameter but shall not exceed the length of the member.
- (d) Transverse reinforcement shall be provided over the minimum longitudinal reinforcement length required by (c).
- (e) Transverse reinforcement shall be ties or spirals with a minimum 3/8 in. diameter. Anchorage of ties shall be in accordance with 25.7.2.4.1, welded lap splices in accordance with 25.5.7, or Class B tension lap splices in

R13.4.4.1.1 Minimum longitudinal reinforcement is necessary to provide some flexural strength in situations such as: 1) where the lateral strength is decreased near the top of the deep foundation member in disturbed soil; 2) where accidental eccentricity is caused by installation tolerances; and 3) where the deep foundation member may be susceptible to accidental damage caused during excavation to the pile cut-off elevation.

It is common for deep foundation members to be installed with a diameter larger than the specified diameter. The minimum reinforcement requirements given in 13.4.4.1.1 apply to the specified diameter, and do not need to be increased if the installed diameter exceeds the specified diameter. Longitudinal reinforcement equal to $0.0025A_g$ provides a moment capacity (without axial load) that is at least equal to the cracking moment of a circular section considering a modulus of rupture equal to $7.5\sqrt{f'_c}$.

This limit was originally required by ATC 3-06 (1978) for high Seismic Design Category C. It is intended to provide a ductile response after flexural cracking for members with normal strength concrete. Although flexural tests on lightly reinforced deep foundation members are not available, the licensed design professional should be aware that other

CODE

accordance with 25.5.2. Continuously wound ties shall be anchored with one extra turn of the bar or wire at each end. Anchorage of spirals shall be in accordance with 25.7.3.4.

(f) If longitudinal reinforcement is required for compression and if A_{st} exceeds $0.01A_g$, spacing of transverse reinforcement shall be in accordance with 25.7.2.1.

COMMENTARY

members with small amounts of flexural reinforcement and subjected to tensile stresses caused by moment or combinations of axial force and moment have been observed to behave in a brittle fashion, tending to fail when the concrete first cracks (Leonhardt 1961; Puranam and Pujol 2017).

Minimum requirements for cast-in-place deep foundation members supporting structures assigned to SDC C, D, E, and F are provided in 18.13.5.

13.4.4.1.2 For members 24 in. in nominal diameter or smaller, if $P_u < 0.75\phi P_n$ or if the member is designed in accordance with 13.4.2 and the axial load resulting from the allowable stress load combinations is smaller than $0.75P_a$, minimum reinforcement shall be permitted to be in accordance with (a) and (b).

(a) One or more longitudinal bars placed at the center of the member with $A_{st} \geq 0.0025A_g$

(b) Longitudinal reinforcement shall extend from the top of the deep foundation member to a distance of at least 10 ft but shall not exceed the length of the member.

13.4.4.2 Placement of reinforcement in deep foundation members shall be in accordance with 26.5.8.

R13.4.4.1.2 For small diameter piles with low axial loads, a single center bar can provide resistance to bending attributable to accidental eccentricity. A full-length center bar with a centering device is recommended as additional quality control to verify installed pile length and diameter.

13.4.5 Precast concrete piles**R13.4.5 Precast concrete piles**

13.4.5.1 Precast concrete piles supporting buildings assigned to SDC A or B shall satisfy the requirements of 13.4.5.2 through 13.4.5.6.

13.4.5.2 Longitudinal reinforcement shall be arranged in a symmetrical pattern.

13.4.5.3 For precast nonprestressed piles, longitudinal reinforcement shall be provided according to (a) and (b):

(a) Minimum of 4 bars

(b) Minimum area of $0.008A_g$

13.4.5.4 For precast prestressed piles, the effective prestress in the pile shall provide a minimum average compressive stress in the concrete in accordance with Table 13.4.5.4.

Table 13.4.5.4—Minimum compressive stress in precast prestressed piles

Pile length, ft	Minimum compressive stress, psi
Pile length ≤ 30	400
$30 < \text{Pile length} \leq 50$	550
Pile length > 50	700

13.4.5.5 For precast prestressed piles, the effective prestress in the pile shall be calculated based on an assumed total loss of 30,000 psi in the prestressed reinforcement.

CODE

13.4.5.6 The longitudinal reinforcement shall be enclosed by transverse reinforcement according to Table 13.4.5.6(a) and shall be spaced according to Table 13.4.5.6(b):

Table 13.4.5.6(a)—Minimum transverse reinforcement size

Least horizontal pile dimension h , in.	Minimum wire size transverse reinforcement ^[1]
$h \leq 16$	W4, D4
$16 < h < 20$	W4.5, D5
$h \geq 20$	W5.5, D6

^[1]If bars are used, minimum of No. 3 bar applies to all values of h .

Table 13.4.5.6(b)—Maximum transverse reinforcement spacing

Reinforcement location in the pile	Maximum center-to-center spacing, in.
First five ties or spirals at each end of pile	1
24 in. from each end of pile	4
Remainder of pile	6

13.4.6 Pile caps

13.4.6.1 Pile caps shall meet the requirements of 13.4.6.2 through 13.4.6.7. Requirements for pile caps apply to all foundation elements to which deep foundation members connect, including grade beams and mats, except as permitted by 13.4.6.3.1.

13.4.6.2 Overall depth of pile cap shall be selected such that the effective depth of bottom reinforcement is at least 12 in.

13.4.6.3 Deep foundation members shall be embedded into a pile cap at least 3 in. The pile cap shall extend beyond the edge of the deep foundation member by at least 4 in.

COMMENTARY

R13.4.5.6 The minimum transverse reinforcement required in this section is typically sufficient for driving and handling stresses. These provisions for precast concrete piles in SDC A and B are based on information from the **2024 IBC**. Minimum reinforcement requirements for precast concrete piles supporting buildings assigned to SDC C, D, E, and F are defined in **18.13.5.10**.

R13.4.6 Pile caps

R13.4.6.3 **ACI PRC-543** contains further guidance on pile-to-pile cap connection considerations.




Fig. R13.4.6.3—Deep foundation member embedment in pile cap.

CODE

COMMENTARY

13.4.6.3.1 Foundation elements supported on deep foundation members shall be exempt from the requirements of 13.4.6.3, provided that analysis demonstrates that the forces and moments calculated with the factored load combinations of **Chapter 5**, including design for potential mislocation of deep foundation members in accordance with 13.4.1.4, can be adequately transferred from the foundation elements to the deep foundation members.

13.4.6.4 Factored moments and shears shall be permitted to be calculated with the reaction from any pile assumed to be concentrated at the centroid of the pile section

13.4.6.5 Except for pile caps designed in accordance with 13.2.6.5, the pile cap shall be designed such that (a) is satisfied for one-way foundations and (a) and (b) are satisfied for two-way foundations.

(a) $\phi V_n \geq V_u$, where V_n shall be calculated in accordance with **22.5** for one-way shear, V_u shall be calculated in accordance with 13.4.6.7, and ϕ shall be in accordance with 21.2

(b) $\phi v_n \geq v_u$, where v_n shall be calculated in accordance with **22.6** for two-way shear, v_u shall be calculated in accordance with 13.4.6.7, and ϕ shall be in accordance with **21.2**

13.4.6.6 If the pile cap is designed in accordance with the strut-and-tie method as permitted in 13.2.6.5, the effective concrete compressive strength of the struts, f_{ce} , shall be calculated in accordance with **23.4.3**.

13.4.6.7 Calculation of factored shear on any section through a pile cap shall be in accordance with (a) through (c):

(a) Entire reaction from any pile with its center located $d_{pile}/2$ or more outside the section shall be considered as producing shear on that section.

(b) Reaction from any pile with its center located $d_{pile}/2$ or more inside the section shall be considered as producing no shear on that section.

(c) For intermediate positions of pile center, the portion of the pile reaction to be considered as producing shear on the section shall be based on a linear interpolation between full value at $d_{pile}/2$ outside the section and zero value at $d_{pile}/2$ inside the section.

13.4.6.8 For pile caps with piles spaced at 4 pile diameters or less, and for mat foundations with piles spaced at 5 pile diameters or less, (a) and (b) shall be permitted:

(a) For one-way shear strength, calculate V_c as:

$$V_c = 2\lambda\sqrt{f'_c}b_wd$$

(b) For two-way shear strength, calculate v_c as specified in 22.6, with the size effect factor, λ_s , taken equal to 1.0.

R13.4.6.6 It is typically necessary to take the effective concrete compressive strength from expression (d) or (f) in Table 23.4.3(a) because it is generally not practical to provide confining reinforcement satisfying **23.5** in a pile cap.

R13.4.6.7 If piles are located inside the critical sections d or $d/2$ from face of column, for one-way or two-way shear, respectively, an upper limit on the shear strength at a section adjacent to the face of the column should be considered. The *CRSI Handbook (1984)* offers guidance for this situation.

R13.4.6.8 Pile caps and mat foundations with closely-spaced piles exhibit increased shear strength compared with those with widely-spaced piles due to arching action.

CHAPTER 14—PLAIN CONCRETE

CODE

COMMENTARY

14.1—Scope

14.1.1 This chapter shall apply to the design of plain concrete members, including (a) and (b):

- (a) Members in building structures
- (b) Members in non-building structures such as arches, underground utility structures, gravity walls, and shielding walls

14.1.2 Plain concrete shall be permitted only in cases (a) through (e):

- (a) Members that are continuously supported by soil or supported by other structural members capable of providing continuous vertical support
- (b) Members for which arch action provides compression under all conditions of loading
- (c) Walls
- (d) Pedestals
- (e) Cast-in-place concrete deep foundation members designed in accordance with 13.4.4 where the unsupported height of the member does not exceed three times the least horizontal dimension of the member and the member is not required to resist lateral loads

14.1.3 Plain concrete shall be permitted for a structure assigned to Seismic Design Category (SDC) D, E, or F, only in cases (a) and (b):

- (a) Footings supporting cast-in-place reinforced concrete or reinforced masonry walls, provided the footings are reinforced longitudinally with at least two continuous reinforcing bars. Bars shall be at least No. 4 and have a total area of not less than 0.002 times the gross cross-sectional area of the footing. Continuity of reinforcement shall be provided at corners and intersections.
- (b) Foundation elements (i) through (iii) for detached one- and two-family dwellings not exceeding three stories and constructed with stud bearing walls:
 - (i) Footings supporting walls
 - (ii) Isolated footings supporting columns or pedestals
 - (iii) Foundation or basement walls not less than 7-1/2 in. thick and retaining no more than 4 ft of unbalanced fill.

14.1.4 Plain concrete shall not be permitted for columns and pile caps.

R14.1—Scope

R14.1.2 Because strength and structural integrity of structural plain concrete members are based solely on member size, concrete strength, and other concrete properties, use of structural plain concrete should be limited to members:

- (a) That are primarily in a state of compression
- (b) That can tolerate random cracks without detriment to their structural integrity
- (c) For which ductility is not an essential feature of design

The tensile strength of concrete can be used in design of structural plain concrete members. Tensile stresses due to restraint from creep, shrinkage, or temperature effects are to be considered to avoid uncontrolled cracks or structural failure. For residential construction within the scope of ACI CODE-332, refer to 1.4.6.

R14.1.4 Unreinforced columns and pile caps are not permitted because plain concrete lacks the necessary ductility for adequate performance. The Code does allow use of plain concrete for pedestals limited to a ratio of unsupported height to least lateral dimension of 3 or less (refer to 14.1.2(d) and 14.3.3).

CODE

14.2—General**14.2.1 Materials**

14.2.1.1 Design properties for concrete shall be selected to be in accordance with **Chapter 19**.

14.2.1.2 Steel reinforcement, if required, shall be selected to be in accordance with **Chapter 20**.

14.2.1.3 Materials, design, and detailing requirements for embedments in concrete shall be in accordance with **20.6**.

14.2.2 Connection to other members

14.2.2.1 Tension shall not be transmitted through outside edges, construction joints, contraction joints, or isolation joints of an individual plain concrete element.

14.2.2.2 Walls shall be braced against lateral translation.

14.2.3 Precast

14.2.3.1 Design of precast members shall consider all loading conditions from initial fabrication to completion of the structure, including form removal, storage, transportation, and erection.

14.2.3.2 Precast members shall be connected to transfer lateral forces into a structural system capable of resisting such forces.

14.3—Design limits**14.3.1 Bearing walls**

14.3.1.1 Minimum bearing wall thickness shall be in accordance with Table 14.3.1.1.

Table 14.3.1.1—Minimum thickness of bearing walls

Wall type	Minimum thickness	
General	Greater of:	5.5 in.
		1/24 the lesser of unsupported length and unsupported height
Exterior basement	7.5 in.	
Foundation	7.5 in.	

COMMENTARY

R14.2—General**R14.2.2 Connection to other members**

R14.2.2.2 Provisions for plain concrete walls are intended only for walls laterally supported in such a manner as to prohibit relative lateral displacement at top and bottom of individual wall elements.®

R14.2.3 Precast

R14.2.3.1 Precast structural plain concrete members are considered subject to all limitations and provisions for cast-in-place concrete contained in this chapter.

The approach to contraction or isolation joints is expected to be somewhat different than for cast-in-place concrete because the major portion of shrinkage in precast members occurs prior to erection. To ensure stability, precast members should be connected to other members. The connection should transfer no tension.

R14.3—Design limits**R14.3.1 Bearing walls**

R14.3.1.1 Plain concrete walls are commonly used for basement wall construction for residential and light commercial buildings located in areas of low seismic risk. Although the Code imposes no absolute maximum height limitation on the use of plain concrete walls, experience with use of plain concrete in relatively minor structures should not be extrapolated to using plain concrete walls in multistory construction and other major structures where differential settlement, wind, earthquake, or other unforeseen loading conditions require the walls to possess some ductility and ability to maintain integrity when cracked. For such conditions, the Code encourages the use of walls designed in accordance with **Chapter 11**.

CODE

COMMENTARY

14.3.2 Footings

14.3.2.1 Footing thickness shall be at least 8 in.

14.3.2.2 Base area of footing shall be determined from unfactored forces and moments transmitted by footing to soil and permissible soil pressure selected through principles of soil mechanics.

14.3.3 Pedestals

14.3.3.1 Ratio of unsupported height to average least lateral dimension shall not exceed 3.

14.3.4 Contraction and isolation joints

14.3.4.1 Contraction or isolation joints shall be provided to divide structural plain concrete members into flexurally discontinuous elements. The size of each element shall be selected to limit stress caused by restraint to movements from creep, shrinkage, and temperature effects.

14.3.4.2 The number and location of contraction or isolation joints shall be determined considering (a) through (f):

- (a) Influence of climatic conditions
- (b) Selection and proportioning of materials
- (c) Mixing, placing, and curing of concrete
- (d) Degree of restraint to movement
- (e) Stresses due to loads to which an element is subjected
- (f) Construction techniques

R14.3.2 Footings

R14.3.2.1 Thickness of plain concrete footings of usual proportions will typically be controlled by flexural strength (extreme fiber stress in tension not greater than $(\phi 5\lambda \sqrt{f'_c})$) rather than shear strength. For footings cast against soil, overall thickness h used for strength calculations is specified in 14.5.1.7.

R14.3.3 Pedestals

R14.3.3.1 The height-thickness limitation for plain concrete pedestals does not apply for portions of pedestals embedded in soil capable of providing lateral restraint.

R14.3.4 Contraction and isolation joints

R14.3.4.1 Joints in plain concrete construction are an important design consideration. In reinforced concrete, reinforcement is provided to resist the stresses due to restraint of creep, shrinkage, and temperature effects. In plain concrete, joints are the only means of controlling, and thereby relieving, the buildup of such tensile stresses. A plain concrete member should be small enough, or divided into smaller elements by joints, to control the buildup of internal stresses. The joint may be a contraction joint or isolation joint. A minimum 25 percent reduction of member thickness is typically sufficient for contraction joints to be effective. The jointing should be such that no axial tension or flexural tension can be developed by reinforcement across a joint after cracking. Where random cracking due to creep, shrinkage, and temperature effects will not affect structural integrity and is otherwise acceptable (such as transverse cracks in a continuous wall footing), transverse contraction or isolation joints are not necessary.

CODE

14.4—Required strength**14.4.1 General**

14.4.1.1 Required strength shall be calculated in accordance with the factored load combinations defined in [Chapter 5](#).

14.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in [Chapter 6](#).

14.4.1.3 No flexural continuity due to tension shall be assumed between adjacent structural plain concrete elements.

14.4.2 Walls

14.4.2.1 Walls shall be designed for an eccentricity corresponding to the maximum moment that can accompany the axial load but not less than $0.10h$, where h is the wall thickness.

14.4.3 Footings**14.4.3.1 General**

14.4.3.1.1 For footings supporting circular or regular polygon-shaped concrete columns or pedestals, it shall be permitted to assume a square section of equivalent area for determining critical sections.

14.4.3.2 Factored moment

14.4.3.2.1 The critical section for M_u shall be located in accordance with Table 14.4.3.2.1.

Table 14.4.3.2.1—Location of critical section for M_u

Supported member	Location of critical section
Column or pedestal	Face of column or pedestal
Column with steel base plate	Halfway between face of column and edge of steel base plate
Concrete wall	Face of wall
Masonry wall	Halfway between center and face of masonry wall

14.4.3.3 Factored one-way shear

14.4.3.3.1 For one-way shear, critical sections shall be located h from (a) and (b), where h is the footing thickness.

(a) Location defined in Table 14.4.3.2.1

COMMENTARY

R14.4—Required strength**R14.4.1 General**

R14.4.1.1 Plain concrete members are proportioned for adequate strength using factored loads and forces. When the design strength is exceeded, the cross section should be increased or the specified strength of concrete increased, or both, or the member designed as a reinforced concrete member in accordance with the Code. An increase in concrete section may have a detrimental effect; stress due to load will decrease but stresses due to creep, shrinkage, and temperature effects may increase.

CODE

(b) Face of concentrated loads or reaction areas

14.4.3.3.2 Sections between (a) or (b) of 14.4.3.3.1 and the critical section for shear shall be permitted to be designed for V_u at the critical section for shear.

14.4.3.4 Factored two-way shear

14.4.3.4.1 For two-way shear, critical sections shall be located so that the perimeter b_o is a minimum but need not be closer than $h/2$ to (a) through (c):

- (a) Location defined in Table 14.4.3.2.1
- (b) Face of concentrated loads or reaction areas
- (c) Changes in footing thickness

14.4.3.4.2 For square or rectangular columns, concentrated loads, or reaction areas, the critical section for two-way shear shall be permitted to be calculated assuming straight sides.

14.5—Design strength**14.5.1 General**

14.5.1.1 For each applicable factored load combination, design strength at all sections shall satisfy $\phi S_n \geq U$, including (a) through (d). Interaction between load effects shall be considered.

- (a) $\phi M_n \geq M_u$
- (b) $\phi P_n \geq P_u$
- (c) $\phi V_n \geq V_u$
- (d) $\phi B_n \geq B_u$

14.5.1.2 ϕ shall be determined in accordance with 21.2.

14.5.1.3 Tensile strength of concrete shall be permitted to be considered in design.

14.5.1.4 Flexure and axial strength calculations shall be based on a linear stress-strain relationship in both tension and compression.

14.5.1.5 λ for lightweight concrete shall be in accordance with 19.2.4.

14.5.1.6 No strength shall be assigned to steel reinforcement.

COMMENTARY**R14.4.3.4 Factored two-way shear**

R14.4.3.4.1 The critical section defined in this provision is similar to that defined for reinforced concrete elements in 22.6.4.1, except that for plain concrete, the critical section is based on h rather than d .

R14.5—Design strength**R14.5.1 General**

R14.5.1.1 Refer to R9.5.1.1.

R14.5.1.2 With no reserve strength or ductility possible due to the absence of reinforcement, equal strength reduction factors for both bending and shear are considered appropriate.

R14.5.1.3 Flexural tension may be considered in design of plain concrete members to resist loads, provided the calculated stress does not exceed the permissible stress, and construction, contraction, or isolation joints are provided to relieve resulting tensile stresses due to restraint of creep, shrinkage, and temperature effects.

CODE

14.5.1.7 When calculating member strength in flexure, combined flexure and axial load, or shear, the entire cross section shall be considered in design, except for concrete cast against soil where overall thickness h shall be taken as 2 in. less than the specified thickness.

14.5.1.8 Unless demonstrated by analysis, horizontal length of wall to be considered effective for resisting each vertical concentrated load shall not exceed center-to-center distance between loads, or bearing width plus four times the wall thickness.

14.5.2 Flexure

14.5.2.1 M_n shall be the lesser of Eq. (14.5.2.1a) calculated at the tension face and Eq. (14.5.2.1b) calculated at the compression face:

$$M_n = 5\lambda\sqrt{f'_c}S_m \quad (14.5.2.1a)$$

$$M_n = 0.85f'_cS_m \quad (14.5.2.1b)$$

where S_m is the corresponding elastic section modulus.

14.5.3 Axial compression

14.5.3.1 P_n shall be calculated by:

$$P_n = 0.60f'_cA_g \left[1 - \left(\frac{\ell_c}{32h} \right)^2 \right] \quad (14.5.3.1)$$

14.5.3.2 For cast-in-place deep foundation members embedded in soil capable of providing lateral support, it shall be permitted to use $\ell_c = 0$ in Eq. (14.5.3.1).

14.5.4 Flexure and axial compression

14.5.4.1 Unless permitted by 14.5.4.2, member dimensions shall be proportioned to be in accordance with Table 14.5.4.1, where M_n is calculated in accordance with Eq. (14.5.2.1b) and P_n is calculated in accordance with Eq. (14.5.3.1).

Table 14.5.4.1—Combined flexure and axial compression

Location	Interaction equation	
Tension face	$\frac{M_u}{S_m} - \frac{P_u}{A_g} \leq \phi 5\lambda\sqrt{f'_c}$	(a)
Compression face	$\frac{M_u}{\phi M_n} + \frac{P_u}{\phi P_n} \leq 1.0$	(b)

COMMENTARY

R14.5.1.7 The reduced overall thickness h for concrete cast against earth is to allow for unevenness of excavation and for some contamination of the concrete adjacent to the soil.

R14.5.2 Flexure

R14.5.2.1 Equation (14.5.2.1b) may control for nonsymmetrical cross sections.

R14.5.3 Axial compression

R14.5.3.1 Equation (14.5.3.1) reflects the range of braced and restrained end conditions encountered in plain concrete elements. The effective length factor was omitted as a modifier of ℓ , the vertical distance between supports, because this is conservative for walls with assumed pin supports that are required by 14.2.2.2 to be braced against lateral translation.

R14.5.3.2 Even if the soil is capable of providing lateral support against buckling, it may be necessary to consider combined flexure and axial compression when evaluating P_n . In accordance with 14.1.3, this evaluation is not permitted in SDC D, E, or F.

R14.5.4 Flexure and axial compression

CODE

14.5.4.2 For walls of solid rectangular cross section where $M_u \leq P_u(h/6)$, M_u need not be considered in design and P_n is calculated by:

$$P_n = 0.45f'_c A_g \left[1 - \left(\frac{\ell_c}{32h} \right)^2 \right] \quad (14.5.4.2)$$

14.5.5 Shear

14.5.5.1 V_n shall be calculated in accordance with Table 14.5.5.1.

Table 14.5.5.1—Nominal shear strength

Shear action	Nominal shear strength V_n	
One-way	$\frac{4}{3}\lambda\sqrt{f'_c} b_o h$	
Two-way	Lesser of:	$\left(1 + \frac{2}{\beta}\right) \left(\frac{4}{3}\lambda\sqrt{f'_c} b_o h\right)^{[1]}$
		$2\left(\frac{4}{3}\lambda\sqrt{f'_c} b_o h\right)$

^[1] β is the ratio of long side to short side of concentrated load or reaction area.

COMMENTARY

R14.5.4.2 If the resultant load falls within the middle third of the wall thickness, plain concrete walls may be designed using the simplified Eq. (14.5.4.2). Eccentric loads and lateral forces are used to determine the total eccentricity of the factored axial force P_u . Equation (14.5.4.2) reflects the range of braced and restrained end conditions encountered in wall design. The limitations of 14.2.2.2, 14.3.1.1, and 14.5.1.8 apply whether the wall is proportioned by 14.5.4.1 or by 14.5.4.2.

R14.5.5 Shear

R14.5.5.1 Proportions of plain concrete members usually are controlled by tensile strength rather than shear strength. Shear stress (as a substitute for principal tensile stress) rarely will control. However, because it is difficult to foresee all possible conditions where shear may have to be investigated, such as shear keys, the Code requires the investigation of this basic stress condition.

The shear requirements for plain concrete assume an uncracked section. Shear failure in plain concrete will be a diagonal tension failure, occurring when the principal tensile stress near the centroidal axis becomes equal to the tensile strength of the concrete. Because the major portion of the principal tensile stress results from shear, the Code safeguards against tension failure by limiting the permissible shear at the centroidal axis as calculated for a section of homogeneous material.

14.5.6 Bearing

14.5.6.1 B_n shall be calculated in accordance with Table 14.5.6.1.

Table 14.5.6.1—Nominal bearing strength

Relative geometric conditions	B_n	
Supporting surface is wider on all sides than the loaded area	Lesser of:	$\sqrt{A_2/A_1}(0.85f'_c A_1)$
		$2(0.85f'_c A_1)$
Other	$0.85f'_c A_1$	

14.6—Reinforcement detailing

14.6.1 At least two No. 5 bars shall be provided around window, door, and similarly sized openings. Such bars shall extend at least 24 in. beyond the corners of openings or shall develop f_y in tension at the corners of the openings.

Notes



CHAPTER 15—CAST-IN-PLACE JOINTS

CODE

COMMENTARY

15.1—Scope

15.1.1 This chapter shall apply to the design and detailing of cast-in-place joints including:

- (a) Beam-column joints
- (b) Slab-column joints.

15.1.2 Transfer of axial force through the floor system shall be in accordance with 15.8.

15.2—General

15.2.1 Shear resulting from moment transfer in beam-column joints shall be considered in the design of the joint.

15.2.2 At corner joints, the effects of closing and opening moments within the joint shall be considered.

15.2.3 Materials

15.2.3.1 Design properties for concrete shall be selected to be in accordance with [Chapter 19](#).

15.2.3.2 Design properties for steel reinforcement shall be selected to be in accordance with [Chapter 20](#).

15.3—Design limits

15.3.1 For a beam framing into the joint and generating joint shear, if the beam depth exceeds twice the column depth in the direction of joint shear, analysis and design of the joint shall be based on the strut-and-tie method in accordance with [Chapter 23](#) and (a) and (b) shall be satisfied:

- (a) Design joint shear strength determined in accordance with [Chapter 23](#) shall not exceed ϕV_n calculated in accordance with 15.5.
- (b) Detailing provisions of 15.7 shall be satisfied.

R15.1—Scope

R15.1.1 A joint is the portion of a structure common to intersecting members, whereas a connection consists of a joint and portions of adjoining members. Chapter 15 is focused on design requirements for beam-to-column and slab-to-column joints. Transfer of moment and shear between slabs and columns is covered in [Chapter 8](#) and [22.6](#).

For structures assigned to Seismic Design Categories (SDC) B through F, joints may be required to withstand several reversals of loading. [Chapter 18](#) provides requirements for earthquake-resistant structures that are applied in addition to the basic requirements for joints in Chapter 15.

R15.2—General

R15.2.2 Corner joints are vulnerable to flexural failure from either closing or opening moments even if flexural strengths at the joint faces are sufficient. Considering transfer of moment across a diagonal section through a corner joint connecting to a cantilevered member is critical because the moment acting through the joint cannot be redistributed. [Chapter 23](#) provides requirements for design and detailing of beam-column corner joints when using the strut-and-tie method. [Klein \(2008\)](#) provides additional guidance on design of corner joints using the strut-and-tie method. The requirements for transverse reinforcement in corner joints are given in 15.7. [ACI PRC-352](#) provides additional guidance on detailing of joints.

R15.3—Design limits

R15.3.1 For joints in which the beam depth exceeds twice the column depth, a diagonal strut between the joint corners, as is assumed in the design method of 15.4, may not be effective. Therefore, the Code requires that such joints be designed using the strut-and-tie method considering the strut and tie angle limitations of [23.2.7](#).

CODE

15.4—Required strength**15.4.1 General**

15.4.1.1 Required strength shall be calculated in accordance with the factored load combinations in **Chapter 5** and 15.4.2.

15.4.1.2 Required strength shall be calculated in accordance with the analysis procedures in **Chapter 6**.

15.4.2 Factored shear in beam-column joint

15.4.2.1 V_u for a beam-column joint shall be calculated on a plane at midheight of the joint using flexural tensile and compressive beam forces and column shear consistent with (a) or (b):

- (a) The maximum moment transferred between the beam and column as determined from factored-load analysis for beam-column joints with continuous beams in the direction of joint shear considered
- (b) Beam nominal moment strength M_n

15.5—Design strength**15.5.1 General**

15.5.1.1 Design shear strength of cast-in-place beam-column joints shall satisfy:

$$\phi V_n \geq V_u$$

COMMENTARY

R15.4—Required strength**R15.4.2 Factored shear in beam-column joint**

R15.4.2.1 Joint shear strength is evaluated separately in each principal direction of loading in accordance with 15.4.

R15.5—Design strength**R15.5.1 General**

R15.5.1.1 Joint shear strength is evaluated separately in each principal direction of loading in accordance with 15.4.

In the **2019 Code**, classification of beam and column members framing into joint faces was modified to distinguish those members contributing to joint shear from those that do not contribute to joint shear but may serve to confine the joint. For a given joint shear direction, lateral confinement is provided by transverse beams while the width of the beams generating joint shear is accounted for through the effective joint width in 15.5.2.2. The minimum cross-section requirements of transverse beams in 15.5.2.5(a) and (b) are illustrated in Fig. R15.5.1.1. These classifications are made for the purpose of establishing nominal joint shear strength in Tables 15.5.2.1 and 18.8.4.3. For beam-column joints with circular columns, the column width and depth may be taken as those of a square section of equivalent area.

CODE

COMMENTARY




Fig. R15.5.1.1—Minimum cross-section requirements of transverse beams for confinement purposes

15.5.1.2 ϕ shall be determined in accordance with 21.2.1 for shear.

15.5.2 Shear strength of beam-column joints

R15.5.2 Shear strength of beam-column joints

15.5.2.1 V_n of a beam-column joint shall be calculated in accordance with Table 15.5.2.1.

Table 15.5.2.1—Beam-column joint nominal shear strength V_n

Column	Beam in direction of V_u	Confinement by transverse beams according to 15.5.2.5	V_n , lb ⁽¹⁾
Continuous or meets 15.5.2.3	Continuous or meets 15.5.2.4	Confined	$24\lambda\sqrt{f'_c}A_j$
		Not confined	$20\lambda\sqrt{f'_c}A_j$
	Other	Confined	$20\lambda\sqrt{f'_c}A_j$
		Not confined	$15\lambda\sqrt{f'_c}A_j$
Other	Continuous or meets 15.5.2.4	Confined	$20\lambda\sqrt{f'_c}A_j$
		Not confined	$15\lambda\sqrt{f'_c}A_j$
	Other	Confined	$15\lambda\sqrt{f'_c}A_j$
		Not confined	$12\lambda\sqrt{f'_c}A_j$

⁽¹⁾ λ shall be 0.75 for lightweight concrete and 1.0 for normalweight concrete.

15.5.2.2 Effective cross-sectional area within a beam-column joint, A_j , shall be calculated as the product of joint

R15.5.2.2 The effective area of the joint, A_j , is illustrated in Fig. R15.5.2.2. In no case is A_j greater than the column


CODE

depth and effective joint width. Joint depth shall be the overall depth of the column, h , in the direction of joint shear considered. Effective joint width shall be the overall width of the column where the beam is wider than the column. Where the column is wider than the beam, effective joint width shall not exceed the lesser of (a) and (b):

- (a) Beam width plus joint depth
- (b) Twice the perpendicular distance from longitudinal axis of beam to nearest side face of the column

COMMENTARY

cross-sectional area. A circular column may be considered as having a square section of equal area. The varied levels of shear strength provided by 15.5.2.1 are based on the recommendations of ACI PRC-352, although it is noted that the ACI PRC-352 definition of effective cross sectional joint area is sometimes different than A_j . Values of effective joint width calculated using ACI PRC-352 and ACI CODE-318, however, are the same or similar for many design situations.



Note: Effective area of joint for forces in each direction of framing is to be considered separately.

Fig. R15.5.2.2—Effective joint area.

15.5.2.3 A column extension assumed to provide continuity through a beam-column joint in the direction of joint shear considered shall satisfy (a) and (b):

- (a) The column extends above the joint at least one column depth, h , measured in the direction of joint shear considered.
- (b) Longitudinal and transverse reinforcement from the column below the joint is continued through the extension.

15.5.2.4 A beam extension assumed to provide continuity through a beam-column joint in the direction of joint shear considered shall satisfy (a) and (b):

- (a) The beam extends at least one beam depth h beyond the joint face.

R15.5.2.3 and **R15.5.2.4** Tests of joints with extensions of beams with lengths at least equal to their depths have indicated similar joint shear strengths to those of joints with continuous beams. These findings suggest that extensions of beams and columns, when properly dimensioned and reinforced with longitudinal and transverse bars, provide effective confinement to the joint faces (Meinheit and Jirsa 1981). Extensions that provide beam and column continuity through a joint do not contribute to joint shear force if they do not support externally applied loads.

CODE

(b) Longitudinal and transverse reinforcement from the beam on the opposite side of the joint is continued through the extension.

15.5.2.5 A beam-column joint shall be considered to be confined for the direction of joint shear considered if two transverse beams satisfying (a) through (d) are provided:

- (a) Each transverse beam covers at least three-quarters of the width of the column face into which it frames.
- (b) Each transverse beam covers an area on the joint face that is at least three-quarters of the product of the width of the column face into which the transverse beam frames and the depth of the deeper beam in the direction of joint shear considered.
- (c) Transverse beams extend at least one beam depth h beyond the joint faces.
- (d) Transverse beams contain at least two continuous top and bottom bars satisfying 9.6.1.2 and No. 3 or larger stirrups satisfying 9.6.3.4 and 9.7.6.2.2.

15.6—Reinforcement limits

15.6.1 Column longitudinal reinforcement in joints shall satisfy 10.6.1.1. If the joint includes dowel reinforcement, the area of column longitudinal reinforcement considered shall include the area of the dowel bars.

15.7—Reinforcement detailing**15.7.1** *Beam-column joint transverse reinforcement*

15.7.1.1 Beam-column joints shall satisfy 15.7.1.2 through 15.7.1.4 unless (a) through (c) are satisfied:

- (a) Joint is considered confined by transverse beams in accordance with 15.5.2.5 for all shear directions considered
- (b) Joint is not part of a designated seismic-force-resisting system
- (c) Joint is not part of a structure assigned to SDC D, E, or F

15.7.1.2 Joint transverse reinforcement shall consist of ties, spirals, or hoops satisfying the requirements of 25.7.2 for ties, 25.7.3 for spirals, and 25.7.4 for hoops.

15.7.1.3 At least two layers of horizontal transverse reinforcement shall be provided within the depth of the shallowest beam framing into the joint.

15.7.1.4 Spacing of joint transverse reinforcement s shall not exceed 8 in. within the depth of the deepest beam framing into the joint.

COMMENTARY

R15.5.2.5 Tests under reversed cyclic loading (Hanson and Conner 1967) have shown that beam-column joints laterally supported on four sides by beams of approximately equal depth exhibit superior behavior compared to joints without all four faces confined by beams.

R15.6—Reinforcement limits

R15.6.1 Refer to R10.6.1.1.

R15.7—Reinforcement detailing**R15.7.1** *Beam-column joint transverse reinforcement*

R15.7.1.1 Tests (Hanson and Connor 1967) have shown that the joint region of a beam-to-column connection in the interior of a building does not require shear reinforcement if the joint is laterally supported on four sides by beams of approximately equal depth. However, joints that are not restrained in this manner, such as at the exterior of a building, require shear reinforcement to prevent deterioration due to shear cracking (ACI PRC-352). These joints may also require transverse reinforcement to prevent buckling of longitudinal column reinforcement.

CODE

15.7.2 Slab-column joint transverse reinforcement

15.7.2.1 Except where laterally supported on four sides by a slab, column transverse reinforcement shall be continued through a slab-column joint, including column capital, drop panel, and shear cap, in accordance with **25.7.2** for ties, **25.7.3** for spirals, and **25.7.4** for hoops.

15.7.3 Beam-column joint longitudinal reinforcement

15.7.3.1 Development of longitudinal reinforcement terminated in the joint or within a column or beam extension, as defined in 15.5.2.3(a) and 15.5.2.4(a), shall be in accordance with **25.4**.

15.7.3.2 Longitudinal reinforcement terminated by a hook or a head in a joint shall extend as close as practicable to the far face of the joint core.

15.7.3.3 Longitudinal reinforcement terminated in the joint with a standard hook shall have the hook turned toward middepth of the beam or column.

15.8—Transfer of column axial force through the floor system

15.8.1 If f_c' of a floor system is less than $0.7f_c'$ of a column, transmission of axial force through the floor system shall be in accordance with (a), (b), or (c):

- (a) Concrete of compressive strength specified for the column shall be placed in the floor system at the column location. Column concrete shall extend outward at least 2 ft into the floor system from face of column for the full depth of the floor system and be integrated with floor concrete.
- (b) Design axial strength of a column through a floor system shall be calculated using the lower value of concrete strength with vertical dowels that satisfy 15.6.1 and transverse reinforcement as required to achieve design strength.
- (c) For beam-column joints laterally supported on four sides by beams that satisfy (i) or slab-column joints that satisfy (ii), design axial strength of the column through the floor system shall be permitted to be calculated using a concrete strength in the column joint equal to 75 percent of column concrete strength plus 35 percent of floor system concrete strength, where the value of column concrete strength used in the calculation shall not exceed 2.5 times the floor system concrete strength.
 - (i) Each beam covers at least three-quarters of the column face width and at least 75 percent of an area equal to the product of the width of the column face into which it frames and the depth of the deepest beam framing into the joint.
 - (ii) Slab confines all four faces of the slab-column joint.

COMMENTARY

R15.7.3 Beam-column joint longitudinal reinforcement

R15.7.3.1 Where bars are continued through an unloaded extension at the opposite face, the bar length within the extension can be considered as part of the development length.

R15.7.3.2 Extending the bar to the far side of the column core helps engage the entire joint in resisting the anchorage forces and improves joint performance.

R15.8—Transfer of column axial force through the floor system

R15.8.1 The requirements of this section consider the effect of floor system concrete strength on column axial strength (Bianchini et al. 1960). If floor system concrete strength is less than 70 percent of column concrete strength, methods in 15.8.1(a) or 15.8.1(b) may be applied to corner or edge columns. Methods in 15.8.1(a), (b), or (c) may be applied to interior columns.

Application of the concrete placement procedure described in 15.8.1(a) requires the placing of two different concrete mixtures in the floor system. The Code requires that column concrete be placed through the thickness of the floor system and that mixtures be placed and remain plastic such that the two can be vibrated so they are well integrated. Additional inspection may be required for this process. As required in **Chapter 26**, it is the responsibility of the licensed design professional to indicate on the construction documents where the higher- and lower-strength concretes are to be placed.

In joints with f_c' less than $0.7f_c'$ of the column, dowel reinforcement may be required for transmission of axial force in accordance with 15.8.1(b).

Research (Ospina and Alexander 1998) has shown that heavily loaded slabs do not provide as much confinement as lightly loaded slabs when ratios of column concrete strength to slab concrete strength exceed approximately 2.5. Consequently, a limit is given in 15.8.1(c) on the ratio of concrete strengths assumed in design.

As an alternative to 15.8.1(a) or 15.8.1(c), 15.8.1(b) permits the use of dowel bars and confinement reinforcement to increase the effective compressive strength of concrete in the column core (Paultre and Légeron 2008; Richart et al. 1929).

CHAPTER 16—CONNECTIONS BETWEEN MEMBERS

CODE

COMMENTARY

16.1—Scope

16.1.1 This chapter shall apply to the design of joints and connections at the intersection of concrete members and for load transfer between concrete surfaces, including (a) through (d):

- (a) Connections of precast members
- (b) Connections between foundations and either cast-in-place or precast members
- (c) Horizontal shear strength of composite concrete flexural members
- (d) Brackets and corbels

16.2—Connections of precast members

16.2.1 *General*

16.2.1.1 Transfer of forces by means of grouted joints, shear keys, bearing, anchors, mechanical connectors, steel reinforcement, reinforced topping, or a combination of these, shall be permitted.

16.2.1.2 Adequacy of connections shall be verified by analysis or test.

16.2.1.3 Connection details that rely solely on friction caused by gravity loads shall not be permitted.

16.2.1.4 Connections, and regions of members adjacent to connections, shall be designed to resist forces and accommodate deformations due to all load effects in the precast structural system.

16.2.1.5 Design of connections shall consider structural effects of restraint of volume change in accordance with **5.3.6**.

16.2.1.6 Design of connections shall consider the effects of tolerances specified for fabrication and erection of precast members.

R16.2—Connections of precast members

R16.2.1 *General*

Connection details should be arranged to minimize the potential for cracking due to restrained creep, shrinkage, and temperature movements. The Precast/Prestressed Concrete Institute (**MNL 123**) provides information on recommended connection details for precast concrete structures.

R16.2.1.1 If two or more connection methods are used to satisfy the requirements for force transfer, their individual load-deformation characteristics should be considered to confirm that the mechanisms work together as intended.

R16.2.1.4 The structural behavior of precast members may differ substantially from that of similar members that are cast-in-place. Design of connections to minimize or transmit forces due to shrinkage, creep, temperature change, elastic deformation, differential settlement, wind, and earthquake require particular consideration in precast construction.

R16.2.1.5 Connections should be designed to either permit the displacements or resist the forces induced by lack of fit, volume changes caused by shrinkage, creep, thermal, and other environmental effects. Connections intended to resist the forces should do so without loss of strength. Restraint assumptions should be consistent in all interconnected members. There are also cases in which the intended force may be in one direction, but it may affect the strength of the connection in another. For example, shrinkage-induced longitudinal tension in a precast beam may affect the vertical shear strength on the corbel supporting it.

R16.2.1.6 Refer to **R26.9.1(a)**.

CODE

16.2.1.7 Design of a connection with multiple components shall consider the differences in stiffness, strength, and ductility of the components.

16.2.1.8 Integrity ties shall be provided in the vertical, longitudinal, and transverse directions and around the perimeter of a structure in accordance with 16.2.4 or 16.2.5.

16.2.2 Required strength

16.2.2.1 Required strength of connections and adjacent regions shall be calculated in accordance with the factored load combinations in [Chapter 5](#).

16.2.2.2 Required strength of connections and adjacent regions shall be calculated in accordance with the analysis procedures in [Chapter 6](#).

16.2.2.3 For bearing connections, N_{uc} shall be (a) or (b), but need not exceed $N_{uc,max}$, where $N_{uc,max}$ is the maximum restraint force that can be transmitted through the load path of a bearing connection multiplied by the load factor used for live loads in combinations with other factored load effects.

(a) For connections not on bearing pads, N_{uc} shall be calculated simultaneously with V_u using factored load combinations in accordance with [5.3.6](#). The restraint force shall be treated as a live load.

(b) For connections on bearing pads, N_{uc} shall be 20% of the sustained unfactored vertical reaction multiplied by a load factor of 1.6.

16.2.2.4 If the friction coefficient for a bearing material has been determined by results of tests, N_{uc} shall be permitted to be determined by multiplying the sustained unfactored vertical reaction by the friction coefficient and a load factor of 1.6.

COMMENTARY

R16.2.1.8 Appendix B of the *PCI Design Handbook* ([PCI MNL 120](#)) provides a review of structural integrity and minimum integrity ties for precast concrete bearing wall structures.

R16.2.2 Required strength

R16.2.2.3 Bearing connections subjected to sustained loads will experience volume change restraint forces due to the effects of creep, shrinkage, and temperature change. Sustained loads are dead loads and any other permanent loads such as soil loads or equipment loads that may be included with live loads. Section 5.3.6 prescribes the general consideration for restraint of volume change and differential settlement in combination with other loading but does not define a specific load factor for precast concrete bearing conditions. Load factors are provided with these provisions. N_{uc} provides a capacity-design limit.

For mechanical connections, steel-to-steel contact, or other high-friction bearings, the horizontal force is usually due to volume change restraint. Such bearing connections will experience volume change restraint forces due to the effects of creep, shrinkage, and temperature change. Because the magnitude of volume change restraint forces acting on bearing connections cannot usually be determined with a high degree of accuracy, it is required to treat the restraint force N_{uc} as a live load in 16.2.2.3(a) when using the factored load combinations of 5.3.6 and multiplied by 1.6 in 16.2.2.3(b).

Common precast concrete bearing connections use elastomeric pads or other structural bearing media that limit transferred forces by pad deformation or slip. The limiting load of such connections can be taken as 20% of the sustained unfactored reaction, as recognized by 16.2.2.3(b).

R16.2.2.4 Bearings explicitly designed for low friction, such as polytetrafluoroethylene (PTFE)-faced sliding bearings, may reduce volume change restraint forces. If the friction coefficient has been reliably determined for a bearing material considering service conditions such as temperature, aging, and exposure, that information can be used to calculate the maximum restraint force.

CODE

COMMENTARY

16.2.3 Design strength

16.2.3.1 For each applicable load combination, design strengths of precast member connections shall satisfy

$$\phi S_n \geq U \quad (16.2.3.1)$$

16.2.3.2 ϕ shall be determined in accordance with 21.2.

16.2.3.3 At the contact surface between supported and supporting members, or between a supported or supporting member and an intermediate bearing element, nominal bearing strength for concrete surfaces, B_n , shall be calculated in accordance with 22.8. B_n shall be the lesser of the nominal concrete bearing strengths for the supported or supporting member surface, and shall not exceed the strength of intermediate bearing elements, if present.

16.2.3.4 If shear is the primary result of imposed loading and shear transfer occurs across a given plane, it shall be permitted to calculate V_n in accordance with the shear-friction provisions in 22.9.

16.2.4 Minimum connection strength and integrity tie requirements

16.2.4.1 Except where the provisions of 16.2.5 govern, longitudinal and transverse integrity ties shall connect precast members to a lateral-force-resisting system, and vertical integrity ties shall be provided in accordance with 16.2.4.3 to connect adjacent floor and roof levels.

16.2.4.2 Where precast members form floor or roof diaphragms, the connections between the diaphragm and those members being laterally supported by the diaphragm shall have a nominal tensile strength of not less than 300 lb per linear ft.

16.2.4.3 Vertical integrity ties shall be provided at horizontal joints between all vertical precast structural members, except cladding, and shall satisfy (a) or (b):

(a) Connections between precast columns shall have vertical integrity ties, with a nominal tensile strength of at least $200A_g$ lb, where A_g is the gross area of the column. For columns with a larger cross section than required by consideration of loading, a reduced effective area based on the cross section required shall be permitted. The reduced effective area shall be at least one-half the gross area of the column.

R16.2.4 Minimum connection strength and integrity tie requirements

R16.2.4.1 It is not intended that these minimum requirements supersede other applicable provisions of the Code for design of precast concrete structures.

The overall integrity of a structure can be substantially enhanced by minor changes in the amount, location, and detailing of member reinforcement and in the detailing of connection hardware. The integrity ties should constitute a complete load path, and load transfers along that load path should be as direct as possible. Eccentricity of the load path, especially within any connection, should be minimized.

R16.2.4.2 The connection between the diaphragm and the member laterally supported by the diaphragm may be direct or indirect. For example, a column may be connected directly to the diaphragm, or it may be connected to a span-drel beam, which is connected to the diaphragm.

R16.2.4.3 Base connections and connections at horizontal joints in precast columns and wall panels, including structural walls, are designed to transfer all design forces and moments. The minimum integrity tie requirements of this provision are not additive to these design requirements. Common practice is to place the wall integrity ties symmetrically about the vertical centerline of the wall panel and within the outer quarters of the panel width, wherever possible.

CODE

(b) Connections between precast wall panels shall have at least two vertical integrity ties, with a nominal tensile strength of at least 10,000 lb per tie.

16.2.5 *Integrity tie requirements for precast concrete bearing wall structures three stories or more in height*

COMMENTARY

R16.2.5 *Integrity tie requirements for precast concrete bearing wall structures three stories or more in height*

Section 16.2.4 gives requirements for integrity ties that apply to all precast concrete structures. The specific requirements in this section apply only to precast concrete bearing wall structures with three or more stories, often called large panel structures. If the requirements of this section conflict with the requirements of 16.2.4, the requirements in this section control.

These minimum provisions for structural integrity ties in large panel bearing wall structures are intended to provide an alternate load path in case of loss of a bearing wall support ([Portland Cement Association 1980](#)). Tie requirements calculated for specific load effects may exceed these minimum provisions. The minimum integrity tie requirements are illustrated in Fig. R16.2.5, and are based on PCI's recommendations for design of precast concrete bearing wall buildings ([PCI Committee on Precast Concrete Bearing Wall Buildings 1976](#)). Integrity tie strength is based on yield strength. Appendix B of the *PCI Design Handbook* ([PCI MNL 120](#)) provides a review of structural integrity and minimum integrity ties for precast concrete bearing wall structures.

CODE

COMMENTARY




Fig. R16.2.5—Typical arrangement of integrity ties in large panel structures.

16.2.5.1 Integrity ties in floor and roof systems shall satisfy (a) through (f):

R16.2.5.1

(a) Longitudinal and transverse integrity ties shall be provided in floor and roof systems to provide a nominal tensile strength of at least 1500 lb per foot of width or length.

(a) Longitudinal integrity ties may project from slabs and be lap spliced, welded, mechanically connected, or embedded in grout joints with sufficient length and cover to develop the required force. Bond length for non-tensioned prestressing reinforcement, if used, should be sufficient to develop the yield strength (Salmons and McCrate 1977; PCA 1980).

(b) Longitudinal and transverse integrity ties shall be provided over interior wall supports and between the floor or roof system and exterior walls.

(c) It is not uncommon to have integrity ties positioned in the walls reasonably close to the plane of the floor or roof system.

(c) Longitudinal and transverse integrity ties shall be positioned in or within 2 ft of the plane of the floor or roof system.
(d) Longitudinal integrity ties shall be oriented parallel to floor or roof slab spans and shall be spaced not greater than 10 ft on center. Provisions shall be made to transfer forces around openings.

(e) Transverse integrity ties shall be oriented perpendicular to floor or roof slab spans and shall be spaced not greater than the bearing wall spacing.

(e) Transverse integrity ties may be uniformly spaced and either encased in the panels or in a topping, or they may be concentrated at the transverse bearing walls.

(f) Integrity ties at the perimeter of each floor and roof, within 4 ft of the edge, shall provide a nominal tensile strength of at least 16,000 lb.

(f) The perimeter integrity tie requirements need not be additive with the longitudinal and transverse integrity tie requirements.

CODE

16.2.5.2 Vertical integrity ties shall satisfy (a) through (c):

- (a) Integrity ties shall be provided in all wall panels and shall be continuous over the height of the building.
- (b) Integrity ties shall provide a nominal tensile strength of at least 3000 lb per horizontal foot of wall.
- (c) At least two integrity ties shall be provided in each wall panel.

16.2.6 *Minimum dimensions at bearing connections*

16.2.6.1 Dimensions of bearing connections shall satisfy 16.2.6.2 or 16.2.6.3 unless shown by analysis or test that lesser dimensions will not impair performance.

16.2.6.2 For precast slabs, beams, or stemmed members, minimum design dimensions from the face of support to end of precast member in the direction of the span, considering specified tolerances, shall be in accordance with Table 16.2.6.2.

Table 16.2.6.2—Minimum design dimensions from face of support to end of precast member

Member type	Minimum distance, in.	
Solid or hollow-core slab	Greater of:	$\ell_n/180$
		2
Beam or stemmed member	Greater of:	$\ell_n/180$
		3

16.2.6.3 Bearing pads adjacent to unarmored faces shall be set back from the face of the support and the end of the supported member a distance not less than 0.5 in. or the chamfer dimension at a chamfered face.

16.3—Connections to foundations

16.3.1 *General*

16.3.1.1 Factored forces and moments at base of columns, walls, or pedestals shall be transferred to supporting foundations by bearing on concrete and by reinforcement, dowels, anchor bolts, or mechanical connectors.

COMMENTARY

R16.2.6 *Minimum dimensions at bearing connections*

This section differentiates between bearing length and length of the end of a precast member over the support (refer to Fig. R16.2.6).

Bearing pads distribute concentrated loads and reactions over the bearing area, and allow limited horizontal and rotational movements for stress relief. To prevent spalling under heavily loaded bearing areas, bearing pads should not extend to the edge of the support unless the edge is armored. Edges can be armored with anchored steel plates or angles. Section 16.5 gives requirements for bearing on brackets or corbels.




Fig. R16.2.6—Bearing length on support.

R16.3—Connections to foundations

R16.3.1 The requirements of 16.3.1 through 16.3.3 apply to both cast-in-place and precast construction. Additional requirements for cast-in-place construction are given in 16.3.4 and 16.3.5, while additional requirements for precast construction are given in 16.3.6.

CODE**COMMENTARY**

16.3.1.2 Reinforcement, dowels, or mechanical connectors between a supported member and foundation shall be designed to transfer (a) and (b):

- (a) Compressive forces that exceed the lesser of the concrete bearing strengths of either the supported member or the foundation, calculated in accordance with 22.8
- (b) Any calculated tensile force across the interface

16.3.1.3 At the base of a composite column with a structural steel core, (a) or (b) shall be satisfied:

- (a) Base of structural steel section shall be designed to transfer the total factored forces from the entire composite member to the foundation.
- (b) Base of structural steel section shall be designed to transfer the factored forces from the steel core only, and the remainder of the total factored forces shall be transferred to the foundation by compression in the concrete and by reinforcement.

16.3.2 Required strength

16.3.2.1 Factored forces and moments transferred to foundations shall be calculated in accordance with the factored load combinations in Chapter 5 and analysis procedures in Chapter 6.

16.3.3 Design strength

16.3.3.1 Design strengths of connections between columns, walls, or pedestals and foundations shall satisfy Eq. (16.3.3.1) for each applicable load combination. For connections between precast members and foundations, requirements for vertical integrity ties in 16.2.4.3 or 16.2.5.2 shall be satisfied.

$$\phi S_n \geq U \quad (16.3.3.1)$$

where S_n is the nominal flexural, shear, axial, torsional, or bearing strength of the connection.

16.3.3.2 ϕ shall be determined in accordance with 21.2.

16.3.3.3 Combined moment and axial strength of connections shall be calculated in accordance with 22.4.

16.3.3.4 At the contact surface between a supported member and foundation, or between a supported member or foundation and an intermediate bearing element, nominal bearing strength B_n shall be calculated in accordance with 22.8 for concrete surfaces. B_n shall be the lesser of the nominal concrete bearing strengths for the supported member or foundation surface, and shall not exceed the strength of intermediate bearing elements, if present.

R16.3.3 Design strength

R16.3.3.4 In the common case of a column bearing on a footing, where the area of the footing is larger than the area of the column, the bearing strength should be checked at the base of the column and the top of the footing. In the absence of dowels or column reinforcement that continue into the foundation, the strength of the lower part of the column should be checked using the strength of the concrete alone.

CODE

16.3.3.5 At the contact surface between supported member and foundation, V_n shall be calculated in accordance with the shear-friction provisions in 22.9 or by other appropriate means.

16.3.3.6 At the base of a precast column, pedestal, or wall, anchor bolts and anchors for mechanical connections shall be designed in accordance with Chapter 17. Forces developed during erection shall be considered.

16.3.3.7 At the base of a precast column, pedestal, or wall, mechanical connectors shall be designed to reach their design strength before anchorage failure or failure of surrounding concrete.

16.3.4 *Minimum reinforcement for connections between cast-in-place members and foundation*

16.3.4.1 For connections between a cast-in-place column or pedestal and foundation, A_s crossing the interface shall be at least $0.005A_g$, where A_g is the gross area of the supported member.

16.3.4.2 For connections between a cast-in-place wall and foundation, area of vertical reinforcement crossing the interface shall satisfy 11.6.1.

16.3.5 *Details for connections between cast-in-place members and foundation*

16.3.5.1 At the base of a cast-in-place column, pedestal, or wall, reinforcement required to satisfy 16.3.3 and 16.3.4 shall be provided either by extending longitudinal bars into the supporting foundation or by dowels. The reinforcement extended into the supporting foundation shall be developed in accordance with 25.4.

16.3.5.2 Where continuity is required, splices and mechanical connectors for the longitudinal reinforcement or dowels shall satisfy 10.7.5 and, if applicable, 18.13.2.2.

16.3.5.3 If a pinned or rocker connection is used at the base of a cast-in-place column or pedestal, the connection to foundation shall satisfy 16.3.3.

COMMENTARY

R16.3.3.5 Shear-friction may be used to check for transfer of lateral forces to the supporting pedestal or footing. As an alternative to using shear-friction across a shear plane, shear keys may be used, provided that the reinforcement crossing the joint satisfies 16.3.4.1 for cast-in-place construction or 16.3.6.1 for precast construction. In precast construction, resistance to lateral forces may be provided by mechanical or welded connections.

R16.3.3.6 Chapter 17 covers anchor design, including seismic design requirements. In precast concrete construction, erection considerations may control base connection design and need to be considered.

R16.3.4 *Minimum reinforcement for connections between cast-in-place members and foundation*

The Code requires a minimum amount of reinforcement between all supported and supporting members to ensure ductile behavior. This reinforcement is required to provide a degree of structural integrity during the construction stage and during the life of the structure.

R16.3.4.1 The Code does not require that all bars in a column be extended through and be anchored into a footing. However, reinforcement with an area of 0.005 times the column area or an equal area of properly spliced dowels is required to extend into the footing with proper anchorage.

R16.3.5 *Details for connections between cast-in-place members and foundation*

CODE

16.3.5.4 At footings, compression lap splices of No. 14 and No. 18 bars that are in compression for all factored load combinations shall be permitted in accordance with **25.5.5.3**.

16.3.6 *Details for connections between precast members and foundation*

16.3.6.1 At the base of a precast column, pedestal, or wall, the connection to the foundation shall satisfy 16.2.4.3 or 16.2.5.2.

16.3.6.2 If the applicable load combinations of 16.3.3 result in no tension at the base of precast walls, vertical integrity ties required by 16.2.4.3(b) shall be permitted to be developed into an adequately reinforced concrete slab-on-ground.

16.4—Horizontal shear transfer in composite concrete flexural members

16.4.1 *General*

16.4.1.1 In a composite concrete flexural member, full transfer of horizontal shear forces shall be provided at contact surfaces of interconnected elements.

16.4.1.2 Where tension exists across any contact surface between interconnected concrete elements, horizontal shear transfer by contact shall be permitted only where transverse reinforcement is provided in accordance with 16.4.6 and 16.4.7.

16.4.1.3 Surface preparation assumed for design shall be specified in the construction documents.

16.4.2 *Required strength*

16.4.2.1 Except as permitted by 16.4.5.3, factored forces transferred along the contact surface in composite concrete flexural members shall be calculated in accordance with the factored load combinations in **Chapter 5**.

16.4.2.2 Required strength shall be calculated in accordance with the analysis procedures in **Chapter 6**.

16.4.3 *Design strength*

16.4.3.1 Design strength for horizontal shear transfer shall satisfy Eq. (16.4.3.1) at all locations along the contact surface in a composite concrete flexural member, unless 16.4.5 is satisfied:

$$\phi V_{nh} \geq V_u \quad (16.4.3.1)$$

where nominal horizontal shear strength V_{nh} is calculated in accordance with 16.4.4.

COMMENTARY

R16.3.5.4 Satisfying 16.3.3.1 might require that each No. 14 or 18 bar be spliced in compression to more than one No. 11 or smaller dowel bar.

R16.4—Horizontal shear transfer in composite concrete flexural members

R16.4.1 *General*

R16.4.1.1 Full transfer of horizontal shear forces between segments of composite concrete members can be provided by horizontal shear strength at contact surfaces through interface shear, properly anchored ties, or both.

R16.4.1.3 **Section 26.5.6** requires the licensed design professional to specify the surface preparation in the construction documents.

CODE

16.4.3.2 ϕ shall be determined in accordance with 21.2.

16.4.4 Nominal horizontal shear strength

16.4.4.1 Nominal horizontal shear strength V_{nh} shall be calculated in accordance with one of the shear transfer mechanisms in Table 16.4.4.1.

COMMENTARY

R16.4.4 Nominal horizontal shear strength

R16.4.4.1 Rows (a) and (c) of Table 16.4.4.1 correspond to the transverse shear force associated with the nominal horizontal shear stress capacity assuming the horizontal shear stress at the contact surface in a cracked flexural member is equal to $V_u/b_v d$ (Park and Paulay 1975). This allows the comparison with the factored transverse shear V_u in Eq. (16.4.3.1). V_n calculated in accordance with rows (b) and (d) is intended to be taken as V_{nh} for use in Eq. (16.4.3.1). The permitted horizontal shear strength in (a) of Table 16.4.4.1 is appropriate for bonded topping slabs. The 80 psi shear stress limit is based on tests by Mones and Brena (2013). To promote bond, a surface that is at least lightly textured is specified, but surface texture alone does not ensure adequate bond. Proven mixture design, placement and curing practices are needed to avoid debonding and curling of topping slabs. If the horizontal shear stress exceeds $\phi 80$ psi, the required shear transfer mechanism is shear-friction across a cracked interface.

The permitted horizontal shear strengths and the requirement of 1/4 in. amplitude for intentional roughness are based on tests discussed in Kaar et al. (1960), Saemann and Washa (1964), and Hanson (1960).

Table 16.4.4.1—Nominal horizontal shear strength

Shear transfer mechanism	Contact surface preparation	$A_{vf,min}$	V_{nh}		
Cementitious bond	Concrete placed against hardened concrete that is clean, free of laitance, and at least lightly textured ^[1]	A_{vf} not required	$80b_v d$		(a)
Shear-friction	Concrete placed against hardened concrete that is clean and free of laitance	In accordance with 16.4.6.1	Determined in accordance with 22.9 assuming a horizontal shear plane over a distance of d where $A_c = b_v d$		(b)
	Concrete placed against hardened concrete that is clean, free of laitance, and intentionally roughened to a trough-to-peak amplitude of approximately 1/4 in. ^[2]		Either	$\lambda \left(260 + 0.6 \frac{A_{vf,nt}}{b_v s} \right) b_v d \leq 500 b_v d$	(c)
				Determined in accordance with 22.9 assuming a horizontal shear plane over a distance of d where $A_c = b_v d$	(d)

^[1]Refer to 26.5.6.2(f).

^[2]Refer to 26.5.6.2(e) for compliance requirements for intentional roughening.

CODE

16.4.4.2 Transverse reinforcement in the previously cast concrete that extends into the cast-in-place concrete and is detailed to develop f_y in tension on both sides of the interface shall be permitted to be included as A_{vf} .

16.4.4.3 In Table 16.4.4.1, d shall be the distance from extreme compression fiber for the entire composite concrete section to the centroid of prestressed and nonprestressed longitudinal tension reinforcement, if any, but need not be taken less than $0.80h$ for prestressed concrete members.

16.4.5 *Alternative method for calculating design horizontal shear strength*

16.4.5.1 As an alternative to 16.4.3.1, it shall be permitted to provide for horizontal shear transfer between points of zero and maximum moment in accordance with 16.4.5.2 through 16.4.5.5.

16.4.5.2 Horizontal shear shall be transferred by shear-friction and shall satisfy $\phi V_{nh} \geq V_{uh}$.

16.4.5.3 Factored horizontal shear V_{uh} applied over width b_v and length ℓ_{vh} shall be taken as the lesser of (a) and (b):

(a) Force corresponding to nominal compressive strength of the concrete and longitudinal reinforcement on the compression side of the interface. The nominal compressive strength shall be calculated in accordance with Eq. (22.4.2.2) using the effective compression flange width defined in 6.3.2.

(b) Force in prestressed and nonprestressed reinforcement on the tension side of the interface at nominal flexural strength, $A_s f_y + A_{ps} f_{ps}$.

16.4.5.4 Horizontal shear strength V_{nh} shall be calculated in accordance with (b), (c) or (d) of Table 16.4.4.1 with $b_v \ell_{vh}$ substituted for $b_v d$.

16.4.5.5 A_{vf} shall be detailed such that A_{vf} per unit length is proportional to the vertical shear force in the member.

COMMENTARY

R16.4.4.3 In composite prestressed concrete members, the depth of the tension reinforcement may vary along the member. The definition of d used in Chapter 22 for determining the vertical shear strength is also appropriate for determining the horizontal shear strength.

R16.4.5 *Alternative method for calculating design horizontal shear strength*

The alternative method differs from the method in 16.4.3 in two ways: 1) the alternative method is based on development of forces corresponding to development of nominal flexural strength, and 2) the strength over the entire distance between points of zero and maximum moment is considered, although distribution of reinforcement in proportion to shear force is required. This method is often used for simply supported precast beams intended to act compositely with topping slabs. An example is provided in the *PCI Design Handbook* (PCI MNL 120). The alternative method is not considered suitable for overlays relying on cementitious bond because redistribution of horizontal shear after interface separation is not possible.

R16.4.5.5 Detailing of shear-friction reinforcement in proportion to shear force is required because horizontal

CODE

16.4.6 *Minimum reinforcement for horizontal shear transfer*

16.4.6.1 Where shear transfer reinforcement is designed to resist horizontal shear, $A_{vf,min}$ shall be $50(b_{vs}/f_y)$.

16.4.7 *Reinforcement detailing for horizontal shear transfer*

16.4.7.1 Shear transfer reinforcement shall consist of single bars or wire, multiple leg stirrups, or vertical legs of welded wire reinforcement.

16.4.7.2 Where shear transfer reinforcement is designed to resist horizontal shear, longitudinal spacing of shear transfer reinforcement shall not exceed the lesser of 24 in. and four times the least dimension of the supported element.

16.4.7.3 Shear transfer reinforcement shall be developed in interconnected elements in accordance with [25.7.1](#).

16.5—Brackets and corbels**16.5.1** *General*

COMMENTARY

shear stresses along the contact surface in a composite member will reflect the distribution of vertical shear along the member. This requirement is usually satisfied by specifying zones of reinforcement within which groups of bars are consistently spaced. Horizontal shear failure is most likely to initiate where the horizontal shear stress is a maximum and will spread to regions of lower stress. Because the slip at peak horizontal shear resistance is small for a concrete-to-concrete contact surface, longitudinal redistribution of horizontal shear resistance is very limited. Therefore, the spacing of ties along the contact surface should provide horizontal shear resistance distributed approximately the same as the distribution of shear stress along the contact surface.

R16.4.6 *Minimum reinforcement for horizontal shear transfer*

R16.4.6.1 The requirements for minimum area of shear transfer reinforcement are based on test data given in [Kaar et al. \(1960\)](#), [Saemann and Washa \(1964\)](#), [Hanson \(1960\)](#), [Grossfield and Birnstiel \(1962\)](#), and [Mast \(1968\)](#). Beginning with the 2025 Code, minimum reinforcement for horizontal shear is independent of minimum vertical shear reinforcement and is based on the width of the interface through which the reinforcement extends, b_v , which may exceed the web width, b_w .

R16.4.7 *Reinforcement detailing for horizontal shear transfer*

R16.4.7.3 Proper anchorage of ties extending across the interface is required to maintain contact along the interface.

R16.5—Brackets and corbels**R16.5.1** *General*

Brackets and corbels are short cantilevers that tend to act as simple trusses or deep beams, rather than beams, which are designed for shear according to [22.5](#). The corbel shown in Fig. R16.5.1a and Fig. 16.5.1b may fail by shearing along the interface between the column and the corbel, yielding of the tension tie, crushing or splitting of the compression strut, or localized bearing or shearing failure under the loading plate. These failure modes are illustrated and discussed in [Elzanaty et al. \(1986\)](#).

The method of design addressed in this section has only been validated experimentally for $a_v/d \leq 1.0$. In addition, an upper limit is provided for N_{uc} because this method of design has only been validated experimentally for $N_{uc} \leq V_u$.

CODE

COMMENTARY




Fig. R16.5.1a—Structural action of a corbel.




Fig. R16.5.1b—Notation used in Section 16.5.

16.5.1.1 Brackets and corbels with shear span-to-depth ratio $a_v/d \leq 1.0$ and with factored restraint force $N_{uc} \leq V_u$ shall be permitted to be designed in accordance with 16.5.

16.5.2 Dimensional limits

16.5.2.1 Effective depth d for a bracket or corbel shall be calculated at the face of the support.

16.5.2.2 Overall depth of bracket or corbel at the outside edge of the bearing area shall be at least $0.5d$.

R16.5.1.1 Design of brackets and corbels in accordance with [Chapter 23](#) is permitted, regardless of shear span.

R16.5.2 Dimensional limits

R16.5.2.2 A minimum depth, as shown in Fig. R16.5.1a and R16.5.1b, is required at the outside edge of the bearing area so that a premature failure will not occur due to a major

CODE

16.5.2.3 No part of the bearing area on a bracket or corbel shall project farther from the face of support than (a) or (b):

- (a) End of the straight portion of the primary tension reinforcement
- (b) Interior face of the transverse anchor bar, if one is provided

16.5.2.4 For normalweight concrete, the bracket or corbel dimensions shall be selected such that V_u/ϕ shall not exceed the least of (a) through (c):

- (a) $0.2f'_c b_w d$
- (b) $(480 + 0.08f'_c)b_w d$
- (c) $1600b_w d$

16.5.2.5 For lightweight concrete, the bracket or corbel dimensions shall be selected such that V_u/ϕ shall not exceed the lesser of (a) and (b):

- (a) $(0.2 - 0.07\frac{a_v}{d})f'_c b_w d$
- (b) $(800 - 280\frac{a_v}{d})b_w d$

16.5.3 Required strength

16.5.3.1 The section at the face of the support shall be designed to resist simultaneously the factored shear V_u , the factored restraint force N_{uc} , and the factored moment M_u .

16.5.3.2 Factored restraint force, N_{uc} , and shear, V_u , shall be the maximum values calculated in accordance with the factored load combinations in **Chapter 5**. It shall be permitted to calculate N_{uc} in accordance with 16.2.2.3 or 16.2.2.4, as appropriate.

16.5.3.3 Required strength shall be calculated in accordance with the analysis procedures in **Chapter 6**, and the requirements in this section.

16.5.4 Design strength

16.5.4.1 Design strength at all sections shall satisfy $\phi S_n \geq U$, including (a) through (c). Interaction between load effects shall be considered.

- (a) $\phi N_n \geq N_{uc}$
- (b) $\phi V_n \geq V_u$
- (c) $\phi M_n \geq M_u$

COMMENTARY

crack propagating from below the bearing area to the sloping face of the corbel or bracket. Failures of this type have been observed (**Kriz and Raths 1965**) in corbels having depths at the outside edge of the bearing area less than required in 16.5.2.2.

R16.5.2.3 The restriction on the location of the bearing area is necessary to ensure development of the specified yield strength of the primary tension reinforcement near the load.

If the corbel is designed to resist restraint force N_{uc} , a bearing plate should be provided and anchored to the primary tension reinforcement (Fig. R16.5.1b).

R16.5.2.4 These limits impose dimensional restrictions on brackets and corbels necessary to comply with the maximum shear friction strength allowed on the critical section at the face of support.

R16.5.2.5 Tests (**Mattock et al. 1976a**) have shown that the maximum shear friction strength of lightweight concrete brackets and corbels is a function of both f'_c and a_v/d .

R16.5.3 Required strength

R16.5.3.1 Figure R16.5.1b shows the forces applied to the corbel. M_u can be calculated as $[V_u a_v + N_{uc}(h - d)]$.

R16.5.3.2 In editions of the Code prior to **ACI 318-19**, specific provisions for restraint forces at bearing connections were included only for corbels and brackets. In 2019, 16.2.2.3 and 16.2.2.4 were added to include consideration of restraint forces at all bearing connections. Consequently the provisions applicable only to brackets or corbels were removed and a reference made to 16.2.2.3 or 16.2.2.4.

CODE

COMMENTARY

16.5.4.2 ϕ shall be determined in accordance with 21.2.

16.5.4.3 Nominal tensile strength N_n provided by A_n shall be calculated by

$$N_n = A_n f_y \quad (16.5.4.3)$$

16.5.4.4 Nominal shear strength V_n provided by A_{vf} shall be calculated in accordance with provisions for shear-friction in 22.9, where A_{vf} is the area of reinforcement that crosses the assumed shear plane.

16.5.4.5 Nominal flexural strength M_n provided by A_f shall be calculated in accordance with the design assumptions in 22.2.

16.5.5 Reinforcement limits

16.5.5.1 Area of primary tension reinforcement, A_{sc} , shall be at least the greatest of (a) through (c):

- (a) $A_f + A_n$
- (b) $(2/3)A_{vf} + A_n$
- (c) $0.04(f'_c/f_y)(b_w d)$

16.5.5.2 Total area of closed stirrups or ties parallel to primary tension reinforcement, A_h , shall be at least:

$$A_h = 0.5(A_{sc} - A_n) \quad (16.5.5.2)$$

16.5.6 Reinforcement detailing

16.5.6.1 Concrete cover shall be in accordance with 20.5.1.3.

16.5.6.2 Minimum spacing for deformed reinforcement shall be in accordance with 25.2.

R16.5.5 Reinforcement limits

R16.5.5.1 Test results (Mattock et al. 1976a) indicate that the total amount of primary tension reinforcement, A_{sc} , required to cross the face of the support should be the greatest of:

- (a) The sum of the amount of reinforcement needed to resist demands from flexure, A_f , plus the amount of reinforcement needed to resist the axial force, A_n , as determined by 16.5.4.3.
- (b) The sum of two-thirds of the total required shear-friction reinforcement, A_{vf} , as determined by 16.5.4.4, plus the amount of reinforcement needed to resist the axial force, A_n , determined by 16.5.4.3. The remaining $A_{vf}/3$ should be provided as closed stirrups parallel to A_{sc} as required by 16.5.5.2.
- (c) A minimum amount of reinforcement, multiplied by the ratio of concrete strength to steel strength. This amount is required to prevent the possibility of sudden failure should the bracket or corbel crack under the action of flexure and outward tensile force.

R16.5.5.2 Closed stirrups parallel to the primary tension reinforcement are necessary to prevent a premature diagonal tension failure of the corbel or bracket. Distribution of A_h is required to be in accordance with 16.5.6.6. The total amount of reinforcement required to cross the face of the support, as shown in Fig. R16.5.1b, is the sum of A_{sc} and A_h .

R16.5.6 Reinforcement detailing

CODE

16.5.6.3 At the front face of a bracket or corbel, primary tension reinforcement shall be anchored by (a), (b), or (c):

- (a) A weld to a transverse bar of at least equal size that is designed to develop f_y of primary tension reinforcement
- (b) Bending the primary tension reinforcement back to form a horizontal loop
- (c) Other means of anchorage to develop f_y

COMMENTARY

R16.5.6.3 For brackets and corbels of variable depth (refer to Fig. R16.5.1a), the stress at ultimate in the reinforcement is almost constant at approximately f_y from the face of support to the load point. This is because the horizontal component of the inclined concrete compression strut is transferred to the primary tension reinforcement at the location of the vertical load. Therefore, reinforcement should be anchored at its outer end (refer to 16.5.6.3) and extended beyond the face of the support to be developed in tension at the face of the support. Satisfactory anchorage at the outer end can be obtained by bending the primary tension reinforcement bars in a horizontal loop as specified in 16.5.6.3b, or by welding a bar of equal diameter or a suitably sized angle across the ends of the primary tension reinforcement bars. The weld detail used successfully in the corbel tests reported in [Mattock et al. \(1976a\)](#) is shown in Fig. R16.5.6.3b. Refer to [ACI Committee 408 \(1966\)](#).

An end hook in the vertical plane, with the minimum diameter bend, is not totally effective because a zone of unreinforced concrete beneath the point of loading will exist for loads applied close to the end of the bracket or corbel. For wide brackets (perpendicular to the plane of the figure) and loads not applied close to the end, U-shaped bars in a horizontal plane provide effective end hooks.




Fig. R16.5.6.3a—Member largely dependent on support and end anchorages.

CODE

COMMENTARY




Fig. R16.5.6.3b—Weld details used in tests of Mattock et al. (1976a).

16.5.6.4 Primary tension reinforcement shall be developed at the face of the support.

16.5.6.5 Development of tension reinforcement shall account for distribution of stress in reinforcement that is not directly proportional to the bending moment.

16.5.6.6 Closed stirrups or ties shall be spaced such that A_h is uniformly distributed within $(2/3)d$ measured from the primary tension reinforcement.

R16.5.6.5 Calculated stress in reinforcement at service loads, f_s , does not decrease linearly in proportion to a decreasing moment in brackets, corbels, and members of variable depth. Additional consideration is required for proper development of the flexural reinforcement.

R16.5.6.6 Refer to R16.5.5.2.

Notes



CHAPTER 17—ANCHORING TO CONCRETE

CODE

COMMENTARY

17.1—Scope

17.1.1 This chapter shall apply to the design of anchors in concrete used to transmit loads by means of tension, shear, or a combination of tension and shear between: (a) connected structural elements; or (b) safety-related attachments and structural elements. Safety levels specified are intended for in-service conditions rather than for short-term handling and construction conditions.

17.1.2 Provisions of this chapter shall apply to the following anchor types (a) through (g):

- (a) Headed studs and headed bolts having a geometry that has been demonstrated to result in a pullout strength in uncracked concrete equal to or exceeding $1.4N_p$, where N_p is given in Eq. (17.6.3.2.2a).
- (b) Hooked bolts having a geometry that has been demonstrated to result in a pullout strength without the benefit of friction in uncracked concrete equal to or exceeding $1.4N_p$, where N_p is given in Eq. (17.6.3.2.2b)
- (c) Post-installed expansion (torque-controlled and displacement-controlled) anchors that meet the assessment criteria of **ACI CODE-355.2**.
- (d) Post-installed undercut anchors that meet the assessment criteria of ACI CODE-355.2.
- (e) Post-installed adhesive anchors that meet the assessment criteria of **ACI CODE-355.4**.
- (f) Post-installed screw anchors that meet the assessment criteria of ACI CODE-355.2.
- (g) Attachments with shear lugs.

17.1.3 If post-installed deformed reinforcing bars qualified in accordance with **ACI CODE-355.5** are used as tension or compression reinforcement, development length shall be in accordance with **25.4.2** and **25.4.9**.

R17.1—Scope

R17.1.1 This chapter is restricted in scope to anchoring devices used to transmit loads into concrete and whose use is related to strength, stability, or life safety. Two main types of applications are envisioned. The first is connections between structural elements where the failure of an anchor or anchor group could result in loss of equilibrium or stability of any portion of the structure. The second is where safety-related attachments that are not part of the structure (such as sprinkler systems, heavy suspended pipes, or barrier rails) are attached to structural elements. The levels of safety defined by the factored load combinations and ϕ -factors are appropriate for structural applications. Other standards may require more stringent safety levels during temporary handling.

R17.1.2 Typical cast-in headed studs and headed bolts with head geometries consistent with **ASME B1.1**, **B18.2.1**, and **B18.2.6** have been tested and proven to behave predictably; therefore, calculated pullout strengths are acceptable.

Post-installed expansion, screw, and undercut anchors do not have predictable pullout strengths, and therefore qualification tests to establish the pullout strengths according to ACI CODE-355.2 are required. For post-installed expansion, screw, and undercut anchors to be used in conjunction with the requirements of this chapter, the results of the ACI CODE-355.2 tests have to indicate that pullout failures exhibit acceptable load-displacement characteristics or that pullout failures are precluded by another failure mode.

In accordance with ACI CODE-355.4, steel elements for adhesive anchors may include threaded rods, deformed reinforcing bars, or internally threaded steel sleeves with external deformations. For adhesive anchors, the characteristic bond stress and suitability for structural applications are established by testing in accordance with ACI CODE-355.4. Adhesive anchors are particularly sensitive to a number of factors including installation direction and load type. If adhesive anchors are used to resist sustained tension, the provisions include testing requirements for horizontal or upwardly inclined installations in 17.2.3, design requirements in 17.5.2.2, certification requirements in **26.7**, and inspection requirements in **26.13**. Adhesive anchors qualified in accordance with ACI CODE-355.4 are tested in concrete with compressive strengths within two ranges: 2500 to 4000 psi and 6500 to 8500 psi. Bond strength is, in general, not highly sensitive to concrete compressive strength.

R17.1.3 Post-installed deformed reinforcing bar systems tested and assessed in accordance with ACI CODE-355.5 are suitable for use in accordance with the provisions for straight deformed reinforcing bars in the Code. Refer to **R25.4.1.6**. Post-installed reinforcing bar dowels are designed using the provisions for adhesive anchors in Chapter 17. In this case, qualification of the adhesive is performed in accordance with ACI CODE-355.4.

CODE

17.1.4 The removal and resetting of post-installed mechanical anchors is prohibited.

17.1.5 This chapter does not apply for load applications that are predominantly high-cycle fatigue or due to impact.

17.1.6 This chapter does not apply to specialty inserts, through-bolts, multiple anchors connected to a single steel plate at the embedded end of the anchors, grouted anchors, or power driven anchors such as powder or pneumatic actuated fasteners.

17.1.7 Reinforcement used as part of an embedment shall have development length established in accordance with other parts of this Code. If reinforcement is used as anchorage, concrete breakout failure shall be considered. Alternatively, anchor reinforcement in accordance with 17.5.2.1 shall be provided.

17.1.8 To evaluate the anchorage of bar groups in tension, it shall be permitted to use the procedures of 25.4.11 to evaluate concrete breakout strength.

17.1.9 To evaluate the strength of anchor groups in tension, it shall be permitted to apply the procedure of 25.4.11 except that the values of N_{cbg} and N_{ag} shall be determined in accordance with 17.6.2 and 17.6.5.

17.2—General

17.2.1 Anchors and anchor groups shall be designed for critical effects of factored loads calculated by elastic analysis. If nominal strength is controlled by ductile steel elements, plastic analysis is permitted provided that deformation compatibility is taken into account.

COMMENTARY

R17.1.4 **ACI CODE-355.2** prohibits reuse of post-installed mechanical anchors.

R17.1.5 The exclusion of load applications producing high-cycle fatigue or extremely short duration impact (such as blast or shock wave) from the scope of this chapter is not meant to exclude earthquake loads. Section 17.10 presents additional requirements for design when earthquake loads are included.

R17.1.6 The wide variety of shapes and configurations of specialty inserts precludes prescription of generalized tests and design equations.

R17.1.7 Under certain conditions, multiple closely spaced bars can generate concrete breakout failure even if reinforcement meets the development length requirements of **Chapter 25**. For reinforcing bar groups, **25.4.11** provides a procedure for determining the concrete breakout strength of the group.

As an alternative to explicit determination of the concrete breakout strength of a group, anchor reinforcement provided in accordance with 17.5.2.1 may be used.

R17.1.8 The development of reinforcing bar groups in tension requires an evaluation that the breakout strength of the member in which the bars are terminated is adequate. Modifications to the breakout provisions of Chapter 17 are provided in 25.4.11 to enable this evaluation.

R17.1.9 The procedure of 25.4.11 can also be applied to the tension breakout strength of anchors in concrete as determined in accordance with Chapter 17. In this case, the breakout strength is based on the 5 percent fractile and cracked concrete is considered in accordance with 17.6.2 and 17.6.5. For specific cases, this may have advantages over the use of anchor reinforcement in accordance with 17.5.2.1(a).

R17.2—General

R17.2.1 If the strength of an anchor group is governed by concrete breakout, the behavior is brittle, and there is limited redistribution of forces between the highly stressed and less stressed anchors. In this case, the theory of elasticity is required to be used, assuming the attachment that distributes loads to the anchors is sufficiently stiff. The forces in the anchors are considered to be proportional to the external load and its distance from the neutral axis of the anchor group.

If anchor strength is governed by ductile yielding of the anchor steel, significant redistribution of anchor forces can occur. In this case, an analysis based on the theory of elasticity will be conservative. **Cook and Klingner (1992a,b)** and **Lotze et al. (2001)** discuss nonlinear analysis, using theory of plasticity, for the determination of the strengths of ductile anchor groups.

CODE

17.2.1.1 Anchor group effects shall be considered if two or more anchors loaded by a common structural element are spaced closer than the spacing required for unreduced breakout strength. If adjacent anchors are not loaded by a common structural element, group effects shall consider simultaneous maximum loading of adjacent anchors.

17.2.2 Adhesive anchors shall be installed in concrete having a minimum age of 21 days at time of anchor installation.

17.2.3 Adhesive anchors installed horizontally or upwardly inclined shall be qualified in accordance with **ACI CODE-355.4** requirements for sensitivity to installation direction.

17.2.4 *Lightweight concrete modification factor, λ_a*

17.2.4.1 Modification factor λ_a for lightweight concrete shall be in accordance with Table 17.2.4.1. It shall be permitted to use an alternate value of λ_a if tests are performed and evaluated in accordance with **ACI CODE-355.2** or **ACI CODE-355.4**.

Table 17.2.4.1—Modification factor λ_a for lightweight concrete

Case	$\lambda_a^{(1)}$
Cast-in and undercut anchor concrete failure	1.0 λ
Expansion, screw, and adhesive anchor concrete failure	0.8 λ
Adhesive anchor bond failure per Eq. (17.6.5.2.1)	0.6 λ

⁽¹⁾ λ shall be in accordance with 19.2.4.

17.2.5 Anchors shall be installed and inspected in accordance with the requirements of **26.7** and **26.13**.

17.3—Design Limits

17.3.1 The value of f'_c used for calculation purposes in this chapter shall not exceed 10,000 psi for cast-in anchors and 8000 psi for post-installed anchors. Post-installed anchors shall not be used in concrete with a strength greater than 8000 psi without testing to verify acceptable performance.

COMMENTARY

R17.2.2 The design performance of adhesive anchors cannot be ensured by establishing a minimum concrete compressive strength at the time of installation in early-age concrete. Therefore, a concrete age of at least 21 days at the time of adhesive anchor installation was adopted.

R17.2.3 **ACI CODE-355.4** includes optional tests to confirm the suitability of adhesive anchors for horizontal or upwardly inclined installations.

R17.2.4 *Lightweight concrete modification factor, λ_a*

R17.2.4.1 The number of tests available to establish the strength of anchors in lightweight concrete is limited. Tests of headed studs cast in lightweight concrete indicate that the present reduction factor λ adequately represents the influence of lightweight concrete (**Shaikh and Yi 1985; Anderson and Meinheit 2005**). Anchor manufacturer data developed for evaluation reports on post-installed expansion, screw, undercut, and adhesive anchors indicate that a reduced λ is needed to provide the necessary safety factor for the respective design strength. **ACI CODE-355.2** and **ACI CODE-355.4** provide procedures whereby a specific value of λ_a can be used based on testing, assuming the lightweight concrete is similar to the reference test material.

R17.3—Design Limits

R17.3.1 A limited number of tests of cast-in and post-installed anchors in high-strength concrete (**Primavera et al. 1997**) indicate that the design procedures contained in this chapter become unconservative with increasing concrete strength, particularly for cast-in anchors in concrete with compressive strengths in the range of 11,000 to 12,000 psi. Until further tests are available, an upper limit on f'_c of 10,000 psi has been imposed for the design of cast-in anchors. This limitation is consistent with those for shear strength, torsion strength, and reinforcement development length in the Code (**22.5.3.1, 22.6.3.1, 22.7.2.1, 25.4.1.4**). For some post-installed anchors, the capacity may be negatively affected by very high-strength concrete. These effects are associated with difficulty in fully expanding expansion anchors, cutting grooves in the sidewall of the predrilled hole by the screw anchor's threads, and reduced bond strength of adhesive anchors. The 8000 psi limit for post-installed anchors reflects

CODE

17.3.2 For anchors with diameters $d_a \leq 4$ in., concrete breakout strength requirements shall be considered satisfied by the design procedures of 17.6.2 and 17.7.2.

17.3.3 For adhesive anchors with embedment depths $4d_a \leq h_{ef} \leq 20d_a$, bond strength requirements shall be considered satisfied by the design procedure of 17.6.5.

17.3.4 For screw anchors with embedment depths $5d_a \leq h_{ef} \leq 10d_a$, and $h_{ef} \geq 1.5$ in., concrete breakout strength requirements shall be considered satisfied by the design procedures of 17.6.2 and 17.7.2.

COMMENTARY

the current concrete strength range for testing specified in [ACI CODE-355.2](#) and [ACI CODE-355.4](#). The 8000 psi limit may be exceeded if verified with tests.

R17.3.2 The limitation on anchor diameter is based on the current range of test data. In the 2002 through 2008 editions of the Code, there were limitations on the diameter and embedment of anchors to calculate the concrete breakout strength. These limitations were necessitated by the lack of test results on anchors with diameters larger than 2 in. and embedment lengths longer than 24 in. In 2011, limitations on anchor diameter and embedment length were revised to limit the diameter to 4 in. based on the results of tension and shear tests on large-diameter anchors with deep embedments ([Lee et al. 2007, 2010](#)). These tests included 4.25 in. diameter anchors, embedded 45 in., tested in tension and 3 in. diameter anchors tested in shear. The 4 in. diameter limit was selected to maintain consistency with the largest diameter anchor permitted in [ASTM F1554](#). Other ASTM specifications permit up to 8 in. diameter anchors; however, they have not been tested to ensure applicability of the 17.6.2 and 17.7.2 concrete breakout provisions.

R17.3.3 ACI CODE-355.4 limits the embedment depth of adhesive anchors to $4d_a \leq h_{ef} \leq 20d_a$, which represents the theoretical limits of the bond model ([Eligehausen et al. 2006a](#)).

R17.3.4 Screw anchor research by [Olsen et al. \(2012\)](#) is based on the nominal screw anchor diameter corresponding to the nominal drill bit size (for example, a 5/8 in. screw anchor installs in a hole drilled by a 5/8 in. ANSI drill bit). This definition of screw anchor size is approximately the diameter of the core or shank of the screw rather than the size of the larger external diameter of the thread. This definition differs from the diameter of standard anchors with [ASME B1.1](#) threads that have a reduced shaft area and smaller effective area. The effective area of the screw anchor, as with other post-installed mechanical anchors, is provided by the manufacturer.

The Olsen et al. (2012) empirical design model was derived from a database of tests in cracked and uncracked concrete on metric-sized screw anchors tested in Europe and inch-sized anchors tested by independent laboratories in accordance with [ICC-ES AC193](#).

For concrete screw anchors, the effective embedment depth, h_{ef} , is determined as a reduction from the nominal embedment based on geometric characteristics of the screw. The effective embedment is verified during the qualification testing under ACI CODE-355.2 and provided by the manufacturer for use in design. Using the reduced, effective embedment depth with the concrete capacity design (CCD) method is shown to adequately represent the behavior of concrete screws in the current concrete screw database and also validates the effects and limitations of certain relevant parameters, such as the effective embedment depth and spacing of anchors (17.9).

CODE

17.3.5 Anchors shall satisfy the edge distances, spacings, and thicknesses in 17.9 unless supplementary reinforcement is provided to control splitting failure.

17.4—Required strength

17.4.1 Required strength shall be calculated in accordance with the factored load combinations in **Chapter 5**.

17.4.2 For anchors in structures assigned to SDC C, D, E, and F, the additional requirements of 17.10 shall apply.

17.5—Design strength

17.5.1 For each applicable factored load combination, design strength of individual anchors and anchor groups shall satisfy $\phi\psi_a S_n \geq U$. Interaction between load effects shall be considered in accordance with 17.8.1.

17.5.1.1 Strength reduction factor, ϕ , shall be determined in accordance with 17.5.3.

17.5.1.2 ψ_a shall be determined in accordance with 17.5.4.1.

17.5.1.3 Nominal strength for an anchor or anchor groups shall be based on design models that result in predictions of strength in substantial agreement with results of comprehensive tests. The materials used in the tests shall be compatible with the materials used in the structure. The nominal strength shall be based on the 5 percent fractile of the basic individual anchor strength. For nominal strengths related to concrete strength, modifications for size effects, number of anchors, effects of close spacing of anchors, proximity to edges, depth of the concrete member, eccentric loadings of anchor groups, and influence of cracking shall be taken into account. Limits on edge distance and anchor spacing in the design models shall be consistent with the tests that verified the model. Strength of anchors shall be based on design models that satisfy 17.5.1.3 for the following:

- (a) Steel strength of anchor in tension
- (b) Concrete breakout strength of anchor in tension
- (c) Pullout strength of a single cast-in anchor and single post-installed expansion, screw, and undercut anchor in tension
- (d) Concrete side-face blowout strength of headed anchor in tension
- (e) Bond strength of adhesive anchor in tension
- (f) Steel strength of anchor in shear
- (g) Concrete breakout strength of anchor in shear
- (h) Concrete pryout strength of anchor in shear

COMMENTARY

R17.4—Required strength**R17.5—Design strength**

R17.5.1.3 This section provides requirements for establishing the strength of anchors in concrete. The various types of steel and concrete failure modes for anchors are shown in Fig. R17.5.1.3(a) and R17.5.1.3(b). Comprehensive discussions of anchor failure modes are included in **CEB (1997)**, **Fuchs et al. (1995)**, **Eligehausen and Balogh (1995)**, and **Cook et al. (1998)**. Tension failure modes related to concrete include concrete breakout failure (applicable to all anchor types), pullout failure (applicable to cast-in anchors, post-installed expansion, screw, and undercut anchors), side-face blowout failure (applicable to headed anchors), and bond failure (applicable to adhesive anchors). Shear failure modes related to concrete include concrete breakout failure and concrete pryout (applicable to all anchor types). These failure modes are described in the deemed-to-comply provisions of 17.6.2, 17.6.3, 17.6.4, 17.6.5, 17.7.2, and 17.7.3.

Any model that complies with the requirements of 17.5.1.3 and 17.5.2.3 can be used to establish the concrete-related strengths. Additionally, anchor tensile and shear strengths are limited by the minimum spacings and edge distances of 17.9 to preclude splitting. The design of post-installed anchors recognizes that the strength of anchors is sensitive to appropriate installation; installation requirements are included in **Chapter 26**. Some post-installed anchors are less sensitive to installation errors and tolerances. This is reflected in various ϕ -factors given in 17.5.3 and based on the assessment criteria of **ACI CODE-355.2** and **ACI CODE-355.4**.

The breakout strength of an unreinforced connection can be taken as an indication of the load at which significant cracking will occur. Such cracking can represent a serviceability problem if not controlled (refer to R17.7.2.1).

CODE

COMMENTARY




Fig. R17.5.1.3—Failure modes for anchors.

17.5.1.4 Strength of anchors shall be permitted to be determined in accordance with 17.6 for 17.5.1.3(a) through (e), and 17.7 for 17.5.1.3(f) through (h). For adhesive anchors that resist sustained tension, the requirements of 17.5.2.2 shall apply.

R17.5.1.4 The method for concrete breakout design deemed to comply with the requirements of 17.5.1.3 was developed from the concrete capacity design (CCD) Method (Fuchs et al. (1995); Eligehausen and Balogh (1995)), which was an adaptation of the Kappa Method (Eligehausen and Fuchs 1988; Eligehausen et al. 2006a) with a breakout failure

CODE

17.5.1.4.1 Anchor group effects shall be considered whenever two or more anchors have spacing less than the critical spacing in Table 17.5.1.4.1, where only those anchors susceptible to the particular failure mode under investigation shall be included in the group.

Table 17.5.1.4.1—Critical spacing

Failure mode under investigation	Critical spacing
Concrete breakout in tension	$3h_{ef}$
Bond strength in tension	$2c_{Na}$
Concrete breakout in shear	$3c_{a1}$

COMMENTARY

surface angle of approximately 35 degrees (Fig. 17.5.1.4a and b). It is considered to be sufficiently accurate, relatively easy to apply, and capable of extension to irregular layouts. The CCD Method predicts the strength of an anchor or anchor group by using a basic equation for tension in cracked concrete, which is multiplied by factors that account for the number of anchors, edge distance, spacing, eccentricity, and absence of cracking. For shear, a similar approach is used. Experimental and numerical investigations have demonstrated the applicability of the CCD Method to adhesive anchors as well (Eligehausen et al. 2006a).




Fig. R17.5.1.4a—Breakout cone for tension.




Fig. R17.5.1.4b—Breakout cone for shear.

17.5.1.5 Strength of anchors shall be permitted to be based on test evaluation using the 5% fractile of applicable test results for 17.5.1.3 (a) through (h).

R17.5.1.5 Sections 17.5.1.3 and 17.5.2.3 establish the performance factors for which anchor design models are required to be verified. Many possible design approaches exist, and the user is always permitted to “design by test” using 17.5.1.5 as long as sufficient data are available to verify the model. Test procedures can be used to determine the single-anchor breakout strength in tension and in shear. The test results, however, are required to be evaluated on a basis statistically equivalent to that used to select the values for the concrete breakout method considered to satisfy provi-

CODE

COMMENTARY

17.5.2 For each applicable factored load combination, design strength of anchors shall satisfy the criteria in Table 17.5.2. Design strength of anchors loaded in both tension and shear shall be in accordance with 17.8.

Table 17.5.2—Design strength requirements of anchors

Failure mode	Single anchor	Anchor group ^[1]	
		Individual anchor in a group	Anchors as a group
Steel strength in tension (17.6.1) ^[2]	$\phi N_{sa} \geq N_{ua}$	$\phi N_{sa} \geq N_{ua,i}$	
Concrete breakout strength in tension ^[3] (17.6.2)	$\phi N_{cb} \geq N_{ua}$		$\phi N_{cbg} \geq N_{ua,g}$
Pullout strength in tension (17.6.3)	$\phi N_{pn} \geq N_{ua}$	$\phi N_{pn} \geq N_{ua,i}$	
Concrete side-face blowout strength in tension (17.6.4)	$\phi N_{sb} \geq N_{ua}$		$\phi N_{sbg} \geq N_{ua,g}$
Bond strength of adhesive anchor in tension (17.6.5)	$\phi N_a \geq N_{ua}$		$\phi N_{ag} \geq N_{ua,g}$
Steel strength in shear (17.7.1)	$\phi V_{sa} \geq V_{ua}$	$\phi V_{sa} \geq V_{ua,i}$	
Concrete breakout strength in shear ^[3] (17.7.2)	$\phi V_{cb} \geq V_{ua}$		$\phi V_{cbg} \geq V_{ua,g}$
Concrete pryout strength in shear (17.7.3)	$\phi V_{cp} \geq V_{ua}$		$\phi V_{cpg} \geq V_{ua,g}$

^[1]Design strengths for steel and pullout failure modes shall be calculated for the most highly stressed anchor in the group.

^[2]Sections referenced in parentheses are pointers to models that are permitted to be used to evaluate the nominal strengths.

^[3]If anchor reinforcement is provided in accordance with 17.5.2.1, the design strength of the anchor reinforcement shall be permitted to be used instead of the concrete breakout strength.

sions of 17.5.1.3. The basic strength cannot be taken greater than the 5% fractile. The number of tests has to be sufficient for statistical validity and should be considered in the determination of the 5% fractile.

R17.5.2 Under combined tension and bending, individual anchors in a group may be required to resist different magnitudes of tensile force. Similarly, under combined shear and torsion, individual anchors in a group may be required to resist different magnitudes of shear. Table 17.5.2 includes requirements to design single anchors and individual anchors in a group to safeguard against all potential failure modes. For steel and pullout failure modes, the most highly stressed anchor in the group should be checked to ensure it has sufficient strength to resist its required load. For concrete breakout, the anchors should be checked as a group. Elastic analysis or plastic analysis of ductile anchors as described in 17.2.1 may be used to determine the loads resisted by each anchor.

The addition of reinforcement in the direction of the load to restrain concrete breakout can enhance the strength and deformation capacity of the anchor connection. Such enhancement is practical with cast-in anchors such as those used in precast sections. [Klingner et al. \(1982\)](#), [fib \(2011\)](#), [ACI CODE-349](#), and [Eligehausen et al. \(2006b\)](#) provide information regarding the effect of reinforcement on the behavior of anchors. The effect of reinforcement is not included in the [ACI CODE-355.2](#) and [ACI CODE-355.4](#) anchor acceptance tests or in the concrete breakout calculation method of 17.6.2 and 17.7.2. Anchor reinforcement may be provided in accordance with 17.5.2.1 and developed according to [Chapter 25](#) instead of calculating breakout strength.

17.5.2.1 Anchor reinforcement

R17.5.2.1 Anchor reinforcement

For conditions where the factored tensile or shear force exceeds the concrete breakout strength of the anchor(s) or if the breakout strength is not evaluated, the nominal strength can be based on developed anchor reinforcement as illustrated in Fig. R17.5.2.1a for tension and Fig. R17.5.2.1b(i) and Fig. R17.5.2.1b(ii) for shear. If anchor reinforcement is provided in accordance with 17.5.2.1.1 or 17.5.2.1.2, the strength of the connection is assumed to be controlled by yielding of the anchor reinforcement as opposed to concrete breakout, and the strength reduction factor applied to these cases is given in Table 21.2.1. Because anchor rein-

CODE

COMMENTARY

forcement is placed below where the shear is applied (refer to Fig. R17.5.2.1b), the force in the anchor reinforcement will be larger than the shear force. Anchor reinforcement is distinguished from supplementary reinforcement in that it is designed exclusively for the anchor loads and is intended to preclude concrete breakout. Strut-and-tie models may be used to design anchor reinforcement. For practical reasons, anchor reinforcement is only used for cast-in anchor applications.




Fig. R17.5.2.1a—Anchor reinforcement for tension.

CODE

COMMENTARY






Fig. R17.5.2.1b(i)—Hairpin anchor reinforcement for shear.

CODE

COMMENTARY




Fig. R17.5.2.1b(ii)—Edge reinforcement and anchor reinforcement for shear.

17.5.2.1.1 For anchors in tension, the design strength of anchor reinforcement shall be permitted to be used instead of the concrete tensile breakout strength of 17.6.2 if (a) and (b) are satisfied.

- (a) Anchor reinforcement is developed in accordance with Chapter 25 on both sides of the concrete breakout surface
- (b) Anchor reinforcement legs crossing the breakout failure plane are parallel to the applied tension force.

R17.5.2.1.1 Care needs to be taken in the selection and positioning of anchor reinforcement for tension. Ideally tension anchor reinforcement should consist of stirrups, ties, or hairpins placed as close as practicable to the anchor. It is beneficial for the anchor reinforcement to enclose the surface reinforcement where applicable. Anchor reinforcement spaced less than $0.5h_{ef}$ from the anchor centerline may be considered as effective. The research (Eligehausen et al. 2006b) on which these provisions are based was limited to anchor reinforcement with maximum diameter equivalent to a No. 5 bar.

17.5.2.1.2 For anchors in shear, the design strength of anchor reinforcement shall be permitted to be used instead of the concrete shear breakout strength of 17.7.2 if (a) and (b) are satisfied.

R17.5.2.1.2 To ensure development of anchor reinforcement for shear, the enclosing anchor reinforcement shown in Fig. R17.5.2.1(b)(i) should be in contact with the anchor and placed as close as practicable to the concrete surface. The research (Eligehausen et al. 2006b) on which the provi-

CODE

(a) Anchor reinforcement is developed in accordance with **Chapter 25** on both sides of the concrete breakout surface, or encloses and contacts the anchor or anchors and is developed beyond the breakout surface.

(b) Anchor reinforcement legs crossing the breakout failure plane are parallel to the applied shear force.

COMMENTARY

sions for enclosing reinforcement are based was limited to anchor reinforcement with maximum diameter equivalent to a No. 5 bar. The larger bend radii associated with larger bar diameters may significantly reduce the effectiveness of the anchor reinforcement for shear; therefore, anchor reinforcement larger than a No. 6 bar is not recommended. Because development for full f_y is required, the use of excess reinforcement to reduce development length is not permitted for anchor reinforcement.

The anchor reinforcement for shear may also consist of stirrups, ties, hoops, or hairpins enclosing the edge reinforcement embedded in the breakout volume and placed as close to the anchors as practicable (refer to Fig. R17.5.2.1b(ii)). Generally, reinforcement spaced less than the smaller of $0.5c_{a1}$ and $0.3c_{a2}$ from the anchor centerline should be included as anchor reinforcement. In this case, the anchor reinforcement must be developed on both sides of the breakout surface. For equilibrium, edge reinforcement is required. The research on which these provisions are based was limited to anchor reinforcement with maximum diameter equivalent to a No. 6 bar.

17.5.2.1.3 The resistance of anchor reinforcement not parallel to the force applied shall be resolved into parallel and perpendicular components. Only the parallel component shall be permitted to contribute to the resistance in tension.

17.5.2.1.4 Shear friction provisions of **22.9** shall not be used for the design of anchor reinforcement.

R17.5.2.1.4 Surface reinforcement, as illustrated in Fig. R17.5.2.1a, is ineffective as anchor reinforcement for force components perpendicular to the surface and does not contribute to breakout resistance by the shear friction model described in 22.9. Anchor reinforcement prevents concrete breakout by establishing a tensile load path directly from the anchor to the anchor reinforcement and to the supporting member (**Eligehausen et al. 2006b**).

17.5.2.1.5 ϕ for anchor reinforcement shall be in accordance with Table 21.2.1.

17.5.2.2 Design of adhesive anchors to resist sustained tension shall satisfy Eq. (17.5.2.2)

$$0.55\psi_a\phi N_{ba} \geq N_{ua,s} \quad (17.5.2.2)$$

where N_{ba} is basic bond strength in tension of a single adhesive anchor and $N_{ua,s}$ is the factored sustained tensile load.

R17.5.2.2 For adhesive anchors that resist sustained tensile load, an additional calculation for the sustained portion of the factored load for a reduced bond resistance is required to account for possible bond strength reductions under sustained tension. The resistance of adhesive anchors to sustained tension is particularly dependent on correct installation, including hole cleaning, adhesive metering and mixing, and prevention of voids in the adhesive bond line (annular gap). In addition, care should be taken in the selection of the correct adhesive and bond strength for the expected on-site conditions such as the concrete condition during installation (dry or saturated, cold or hot), the drilling method used (rotary impact drill, rock drill, or core drill), and anticipated in-service temperature variations in the concrete.

The 0.55 factor used for the additional calculation for sustained tension is correlated with **ACI CODE-355.4** test

CODE

COMMENTARY

17.5.2.2.1 For groups of adhesive anchors subject to sustained tension, Eq. (17.5.2.2) shall be satisfied for the anchor that resists the highest sustained tension.

17.5.2.3 If both N_{ua} and V_{ua} are present, interaction effects shall be considered using interaction expressions resulting in calculated strengths in substantial agreement with results of comprehensive tests. This requirement shall be considered satisfied by 17.8 for interaction effects associated with concrete strength and steel strength.

17.5.2.4 Anchors shall satisfy the edge distances, spacings, and thicknesses in 17.9 to preclude splitting failure.

17.5.2.5 Anchors in structures assigned to Seismic Design Category C, D, E, or F shall satisfy the additional requirements of 17.10.

17.5.2.6 Attachments with shear lugs used to transfer structural loads shall satisfy the requirements of 17.11.

17.5.3 ϕ for anchors in concrete and anchor reinforcement shall be in accordance with Table 21.2.1.

requirements and provides satisfactory performance of adhesive anchors under sustained tensile loads in accordance with **ACI CODE-355.4**. Product evaluation according to ACI CODE-355.4 is based on sustained tensile loads being present for 50 years at a standard temperature of 70°F and 10 years at a temperature of 110°F. For longer life spans (for example, greater than 50 years) or higher temperatures, lower factors should be considered. Additional information on use of adhesive anchors for such conditions can be found by consulting with the adhesive manufacturer.

Adhesive anchors are particularly sensitive to installation direction and load type. Adhesive anchors installed overhead that resist sustained tension are of concern because previous applications of this type have led to failures (**National Transportation Safety Board 2007**). Other anchor types may be more appropriate for such cases. For adhesive anchors that resist sustained tension in horizontal or upwardly inclined orientations, it is essential to meet test requirements of ACI CODE-355.4 for sensitivity to installation direction, use certified installers, and require special inspection. Inspection and installation requirements are provided in **Chapter 26**.

R17.5.2.2.1 The check for anchor groups is limited to the highest loaded anchor in the group, analogous to the design for pullout.

R17.5.2.3 Section 17.8 considers interaction effects for concrete and steel strength separately.

R17.5.3 The ϕ -factors for anchors in concrete have been simplified and consolidated in Table 21.2.1 in the 2025 Code. The following adjustments have been implemented: 1) Separate strength reduction factors for anchors have been replaced with a new ψ_a factor (refer to 17.5.4) corresponding to evaluation results in accordance with the relevant standard and whether supplementary reinforcement is present, and 2) the Code distinguishes between redundant and nonredundant anchorages. Redundancy may be assumed where it can be shown that failure of a single anchor or anchorage point does not result in loss of position retention or progressive collapse. The reliability index (target reliability) associated with the

CODE

17.5.4 Anchor strength modification factor ψ_a

17.5.4.1 In addition to the strength reduction factor ϕ , the strength of anchors associated with concrete failure modes shall be modified by the factor ψ_a in accordance with Table 17.5.4.1.

Table 17.5.4.1—Anchor strength modification factor ψ_a

Anchor type	Anchor Category ^[1] from ACI 355.2 or ACI 355.4	ψ_a concrete failure			
		supplementary reinforcement not present		supplementary reinforcement present	
		Tension	Shear	Tension	Shear
Cast-in	not applicable	0.95	0.95	1.00	1.00
Post-installed	1	0.85		1.00	
	2	0.75		0.85	
	3	0.60		0.75	

^[1]Anchor Category 1 indicates low installation sensitivity and high reliability; Anchor Category 2 indicates medium installation sensitivity and medium reliability; Anchor Category 3 indicates high installation sensitivity and lower reliability.

COMMENTARY

provisions in Chapter 17 has traditionally been interpreted as corresponding to a condition where: a) warning of failure is minimal (concrete failure); b) failure of the anchorage will result in collapse of the supported element (nonredundant); and c) the consequences of failure are significant. For anchorages in tension where redundancy is inherent in the connection, an increased ϕ as provided in Table 21.2.1 is acceptable.

R17.5.4 Anchor strength modification factor ψ_a

R17.5.4.1 Tests described in **ACI CODE-355.2** and **ACI CODE-355.4** to assess sensitivity to installation procedures are used to establish the Anchor Categories listed in Table 17.5.4.1 for proprietary post-installed expansion, screw, undercut, and adhesive anchors. ACI CODE-355.2 tests for installation sensitivity measure effects of variability in anchor torque during installation, tolerance on drilled hole size, and energy level used in setting anchors. For expansion, screw, and undercut anchors intended for use in cracked concrete, the effects of cracks passing through or near the anchor location are measured. ACI CODE-355.4 tests for installation sensitivity assess the influence of adhesive mixing and hole cleaning in dry, saturated, and water-filled/underwater bore holes on the performance of adhesive anchors. In addition, for adhesive anchors intended for use in cracked concrete, the effect of concrete cracking on anchor behavior is assessed.

Applications with supplementary reinforcement provide more deformation capacity, permitting the ψ_a -factors to be increased. An explicit design of supplementary reinforcement for anchor-related forces is not required; however, the arrangement of supplementary reinforcement should generally conform to that of the anchor reinforcement shown in Fig. R17.5.2.1(a) and R17.5.2.1(b)(i) and (ii). Unlike anchor reinforcement, development of supplementary reinforcement beyond the assumed breakout failure plane is not required. Refer also to R17.5.2.1.

17.6—Tensile strength**17.6.1 Steel strength of anchors in tension, N_{sa}**

17.6.1.1 Nominal steel strength of anchors in tension as governed by the steel, N_{sa} , shall be evaluated based on the properties of the anchor material and the physical dimensions of the anchors.

17.6.1.2 Nominal steel strength of an anchor in tension, N_{sa} , shall be calculated by:

$$N_{sa} = A_{se,N} f_{uta} \quad (17.6.1.2)$$

where $A_{se,N}$ is the effective cross-sectional area of an anchor in tension, in.², and f_{uta} used for calculations shall not exceed either $1.9f_{ya}$ or 125,000 psi.

R17.6—Tensile strength**R17.6.1 Steel strength of anchors in tension, N_{sa}**

R17.6.1.2 The nominal strength of anchors in tension is best represented as a function of f_{uta} rather than f_{ya} because the large majority of anchor materials do not exhibit a well-defined yield point. AISC has based tension strength of anchors on $A_{se,N} f_{uta}$ since the 1986 edition of their specifications. The use of Eq. (17.6.1.2) with the load factors provided in 5.3 and the ϕ -factors provided in 17.5.3 result in design strengths consistent with **ANSI/AISC 360**.

CODE

COMMENTARY

The limitation of $1.9f_{ya}$ on f_{uta} is to ensure that, under service load conditions, the anchor does not exceed f_{ya} . Although not a concern for standard structural steel anchors (maximum value of f_{uta}/f_{ya} is 1.6 for **ASTM A307**), the limitation is applicable to some stainless steels. The limit on f_{uta} of $1.9f_{ya}$ was determined by converting the LRFD provisions to corresponding service level conditions. From **5.3**, the average load factor of 1.4 (from $1.2D + 1.6L$) divided by the highest ϕ -factor (0.75 for tension) results in a limit of f_{uta}/f_{ya} of $1.4/0.75 = 1.87$.

For post-installed anchors having a reduced cross-sectional area anywhere along the anchor length, such as wedge-type anchors, the effective cross-sectional area of the anchor should be provided by the manufacturer. For threaded rods and headed bolts, **ASME B1.1** defines $A_{se,N}$ as

$$A_{se,N} = \frac{\pi}{4} \left(d_a - \frac{0.9743}{n_t} \right)^2$$

where n_t is the number of threads per inch.

17.6.2 Concrete breakout strength of anchors in tension, N_{cb}

17.6.2.1 Nominal concrete breakout strength in tension, N_{cb} of a single anchor or N_{cbg} of an anchor group satisfying 17.5.1.4.1, shall be calculated by (a) or (b), respectively:

(a) For a single anchor

$$N_{cb} = \frac{A_{Nc}}{A_{Nco}} \psi_a \psi_{ed,N} \psi_{c,N} \psi_{cp,N} \psi_{cm,N} N_b \quad (17.6.2.1a)$$

(b) For an anchor group

$$N_{cbg} = \frac{A_{Nc}}{A_{Nc}} \psi_a \psi_{ec,N} \psi_{ed,N} \psi_{c,N} \psi_{cp,N} \psi_{cm,N} N_b \quad (17.6.2.1b)$$

where ψ_a , $\psi_{ec,N}$, $\psi_{ed,N}$, $\psi_{c,N}$, $\psi_{cp,N}$, and $\psi_{cm,N}$ are given in 17.5.4.1, 17.6.2.3, 17.6.2.4, 17.6.2.5, 17.6.2.6, and 17.6.2.7, respectively.



R17.6.2 Concrete breakout strength of anchors in tension, N_{cb}

R17.6.2.1 The effects of multiple anchors, spacing of anchors, and edge distance on the nominal concrete breakout strength in tension are included by applying the modification factors A_{Nc}/A_{Nco} and $\psi_{ed,N}$ in Eq. (17.6.2.1a) and (17.6.2.1b).

Figure R17.6.2.1(a) shows A_{Nco} and the development of Eq. (17.6.2.1.4). A_{Nco} is the maximum projected area for a single anchor. Figure R17.6.2.1(b) shows examples of the projected areas for various single-anchor and multiple-anchor arrangements. Because A_{Nc} is the total projected area for an anchor group, and A_{Nco} is the area for a single anchor, there is no need to include n , the number of anchors, in Eq. (17.6.2.1b). If anchor groups are positioned in such a way that their projected areas overlap, the value of A_{Nc} is required to be reduced accordingly.

CODE




The critical edge distance for headed studs, headed bolts, expansion anchors, and undercut anchors is $1.5h_{ef}$



$$A_{Nco} = (2 \times 1.5h_{ef}) \times (2 \times 1.5h_{ef}) = 9h_{ef}^2$$

(a)

COMMENTARY



(b)

Fig. R17.6.2.1—(a) Calculation of A_{Nco} and (b) calculation of A_{Nc} for single anchors and anchor groups.

CODE

17.6.2.1.1 A_{Nc} is the projected concrete failure area of a single anchor or of an anchor group that is approximated as the base of the rectilinear geometrical shape that results from projecting the failure surface outward $1.5h_{ef}$ from the centerlines of the anchor, or in the case of an anchor group, from a line through a row of adjacent anchors. A_{Nc} shall not exceed nA_{Nco} , where n is the number of anchors in the group that resist tension.

17.6.2.1.2 If anchors are located less than $1.5h_{ef}$ from three or more edges, the value of h_{ef} used to calculate A_{Nc} in accordance with 17.6.2.1.1, as well as for the equations in 17.6.2.1 through 17.6.2.4, shall be the greater of (a) and (b):

- (a) $c_{a,max}/1.5$
- (b) $s/3$, where s is the maximum spacing between anchors within the group.

COMMENTARY

R17.6.2.1.2 For anchors located less than $1.5h_{ef}$ from three or more edges, the CCD Method (refer to R17.5.1.4), which is the basis for the equations in 17.6.2.1 through 17.6.2.4, gives overly conservative results for the tensile breakout strength (Lutz 1995). This occurs because the ordinary definitions of A_{Nc}/A_{Nco} do not correctly reflect the edge effects. This problem is corrected by limiting the value of h_{ef} used in the equations in 17.6.2.1 through 17.6.2.4 to $(c_{a,max})/1.5$, where $c_{a,max}$ is the greatest of the influencing edge distances that do not exceed the actual $1.5h_{ef}$. In no case should $(c_{a,max})/1.5$ be taken less than one-third of the maximum spacing between anchors within the group. The limit on h_{ef} of at least one-third of the maximum spacing between anchors within the group prevents the use of a calculated strength based on individual breakout volumes for an anchor group configuration. This approach is illustrated in Fig. R17.6.2.1.2. In this example, the proposed limit on the value of h_{ef} to be used in calculations where $h_{ef} = (c_{a,max})/1.5$, results in $h_{ef} = h'_{ef} = 4$ in. For this example, this would be the proper value to be used for h_{ef} in calculating the resistance even if the actual embedment depth is greater.

The requirement of 17.6.2.1.2 may be visualized by moving the actual concrete breakout surface, which originates at the actual h_{ef} , toward the surface of the concrete parallel to the applied tensile load. The value of h_{ef} used in 17.6.2.1 through 17.6.2.4 is determined when (a) the outer boundaries of the failure surface first intersect a free edge; or (b) the intersection of the breakout surface between anchors within the group first intersects the surface of the concrete. For the example shown in Fig. R17.6.2.1.2, point “A” shows the intersection of the assumed failure surface for limiting h_{ef} with the concrete surface.




Fig. R17.6.2.1.2—Example of tension where anchors are located in narrow members.

17.6.2.1.3 If an additional plate or washer is added at the head of the anchor, it shall be permitted to calculate the projected area of the failure surface by projecting the failure surface outward $1.5h_{ef}$ from the effective perimeter of the plate or washer. The effective perimeter shall not exceed the value at a section projected outward more than the thickness of the washer or plate from the outer edge of the head of the anchor

17.6.2.1.4 A_{Nco} is the projected concrete failure area of a single anchor with an edge distance of at least $1.5h_{ef}$ and shall be calculated by Eq. (17.6.2.1.4).

$$A_{Nco} = 9h_{ef}^2 \quad (17.6.2.1.4)$$

17.6.2.2 Basic single anchor breakout strength, N_b

17.6.2.2.1 Basic concrete breakout strength of a single anchor in tension in cracked concrete, N_b , shall be calculated by Eq. (17.6.2.2.1), except as permitted in 17.6.2.2.3

R17.6.2.2 Basic single anchor breakout strength, N_b

R17.6.2.2.1 The equation for the basic concrete breakout strength was derived assuming concrete breakout with an angle of approximately 35 degrees, considering fracture

CODE

$$N_b = k_c \lambda_a \sqrt{f'_c} h_{ef}^{1.5} \quad (17.6.2.2.1)$$

where $k_c = 24$ for cast-in anchors and 17 for post-installed anchors.

17.6.2.2.2 k_c for post-installed anchors shall be permitted to be increased based on **ACI CODE-355.2** or **ACI CODE-355.4** product-specific tests, but shall not exceed 24.

17.6.2.2.3 For single cast-in headed studs and headed bolts with $11 \text{ in.} \leq h_{ef} \leq 25 \text{ in.}$, N_b shall be calculated by:

$$N_b = 16 \lambda_a \sqrt{f'_c} h_{ef}^{5/3} \quad (17.6.2.2.3)$$

17.6.2.3 Breakout eccentricity factor, $\psi_{ec,N}$

17.6.2.3.1 Modification factor for anchor groups loaded eccentrically in tension, $\psi_{ec,N}$, shall be calculated by Eq. (17.6.2.3.1).

$$\psi_{ec,N} = \frac{1}{\left(1 + \frac{e'_N}{1.5h_{ef}}\right)} \leq 1.0 \quad (17.6.2.3.1)$$

COMMENTARY

mechanics concepts (Fuchs et al. 1995; Eligehausen and Balogh 1995; Eligehausen and Fuchs 1988; fib 2011).


The values of k_c in Eq. (17.6.2.2.1) were determined from a large database of test results in uncracked concrete at the 5% fractile (Fuchs et al. 1995). The values were adjusted to corresponding k_c values for cracked concrete (Eligehausen and Balogh 1995; Goto 1971). Tests have shown that the values of k_c applicable to adhesive anchors are approximately equal to those derived for expansion anchors (Eligehausen et al. 2006a; Zhang et al. 2001).

R17.6.2.2.3 For anchors with a deeper embedment ($h_{ef} > 11 \text{ in.}$), test evidence indicates the use of $h_{ef}^{1.5}$ can be overly conservative for some cases. An alternative expression (Eq. (17.6.2.2.3)) is provided using $h_{ef}^{5/3}$ for evaluation of cast-in headed studs and headed bolts with $11 \text{ in.} \leq h_{ef} \leq 25 \text{ in.}$ This expression can also be appropriate for some undercut post-installed anchors. However, for such anchors, the use of Eq. (17.6.2.2.3) should be justified by test results in accordance with 17.5.1.5. Experimental and numerical investigations indicate that Eq. (17.6.2.2.3) may be unconservative for $h_{ef} > 25 \text{ in.}$ if bearing pressure on the anchor head is at or near the limit permitted by Eq. (17.6.3.2.2a) (Ožbolt et al. 2007).

R17.6.2.3 Breakout eccentricity factor, $\psi_{ec,N}$


R17.6.2.3.1 Figure 17.6.2.3.1(a) shows an anchor group where all anchors are in tension but the resultant force is eccentric with respect to the centroid of the anchor group. Anchors can also be loaded in such a way that only some of the anchors are in tension (Fig. 17.6.2.3.1(b)). In this case, only the anchors in tension are to be considered for the calculation of e'_N . The eccentricity e'_N of the resultant tensile force is determined with respect to the center of gravity of the anchors in tension.

CODE



(a) Where all anchors in a group are in tension

COMMENTARY



(b) Where only some anchors are in tension

Fig. R17.6.2.3.1—Definition of e'_N for an anchor group.

17.6.2.3.2 If the loading on an anchor group is such that only some of the anchors in the group are in tension, only those anchors that are in tension shall be considered for determining eccentricity e'_N in Eq. (17.6.2.3.1) and for the calculation of N_{cbg} according to Eq. (17.6.2.1b).

17.6.2.3.3 If the loading is eccentric with respect to two orthogonal axes, $\psi_{ec,N}$ shall be calculated for each axis individually, and the product of these factors shall be used as $\psi_{ec,N}$ in Eq. (17.6.2.1b).

17.6.2.4 Breakout edge effect factor, $\psi_{ed,N}$

17.6.2.4.1 Modification factor for edge effects for single anchors or anchor groups loaded in tension, $\psi_{ed,N}$, shall be determined by (a) or (b).

(a) If $c_{a,min} \geq 1.5h_{ef}$, then

$$\psi_{ed,N} = 1.0 \quad (17.6.2.4.1a)$$

(b) If $c_{a,min} < 1.5h_{ef}$, then

$$\psi_{ed,N} = 0.7 + 0.3 \frac{c_{a,min}}{1.5h_{ef}} \quad (17.6.2.4.1b)$$

17.6.2.5 Breakout cracking factor, $\psi_{c,N}$

17.6.2.5.1 Modification factor for the influence of cracking in anchor regions at service load levels, $\psi_{c,N}$, shall be determined by (a) or (b):

R17.6.2.4 Breakout edge effect factor, $\psi_{ed,N}$

R17.6.2.4.1 If anchors are located close to an edge such that there is insufficient space for a complete breakout volume to develop, the strength of the anchor is further reduced beyond that reflected in A_{Nc}/A_{Nco} . If the smallest side cover distance is at least $1.5h_{ef}$, the design model assumes a complete breakout volume can form, and there is no reduction ($\psi_{ed,N} = 1$). If the side cover is less than $1.5h_{ef}$, the factor $\psi_{ed,N}$ is required to adjust for the edge effect (Fuchs et al. 1995).

R17.6.2.5 Breakout cracking factor, $\psi_{c,N}$

R17.6.2.5.1 Post-installed anchors that do not meet the requirements for use in cracked concrete according to ACI CODE-355.2 or ACI CODE-355.4 should be used only in regions that will remain uncracked. The analysis for the deter-

CODE

(a) For anchors located in a region of a concrete member where analysis indicates no cracking at service load levels, $\psi_{c,N}$ shall be permitted to be: $\psi_{c,N} = 1.25$ for cast-in anchors $\psi_{c,N} = 1.4$ for post-installed anchors, if the value of k_c used in Eq. (17.6.2.2.1) is 17. If the value of k_c used in Eq. (17.6.2.2.1) is taken from the **ACI CODE-355.2** or **ACI CODE-355.4** product evaluation report for post-installed anchors:

(i) $\psi_{c,N}$ shall be based on the ACI CODE-355.2 or ACI CODE-355.4 product evaluation report for anchors qualified for use in both cracked and uncracked concrete

(ii) $\psi_{c,N}$ shall be taken as 1.0 for anchors qualified for use in uncracked concrete.

(b) For anchors located in a region of a concrete member where analysis indicates cracking at service load levels, $\psi_{c,N}$ shall be taken as 1.0 for both cast-in anchors and post-installed anchors, and 17.6.2.6 shall be satisfied.

17.6.2.5.2 Post-installed anchors shall be qualified for use in cracked concrete in accordance with ACI CODE-355.2 or ACI CODE-355.4. Cracking in the concrete shall be controlled by flexural reinforcement distributed in accordance with **24.3.2**, or equivalent crack control shall be provided by confining reinforcement.

17.6.2.6 Breakout splitting factor, $\psi_{cp,N}$

17.6.2.6.1 Modification factor for post-installed anchors designed for uncracked concrete in accordance with 17.6.2.5 without supplementary reinforcement to control splitting, $\psi_{cp,N}$, shall be determined by (a) or (b) using the critical distance c_{ac} as defined in 17.9.5.

(a) If $c_{a,min} \geq c_{ac}$, then

$$\psi_{cp,N} = 1.0 \quad (17.6.2.6.1a)$$

(b) If $c_{a,min} < c_{ac}$, then

$$\psi_{cp,N} = \frac{c_{a,min}}{c_{ac}} \geq \frac{1.5h_{ef}}{c_{ac}} \quad (17.6.2.6.1b)$$

17.6.2.6.2 For all other cases, including cast-in anchors, $\psi_{cp,N}$ shall be taken as 1.0.

17.6.2.7 Breakout compression field factor, $\psi_{cm,N}$

17.6.2.7.1 Modification factor for breakout compression field effect, $\psi_{cm,N}$, to be applied to all tension-loaded anchors as part of a tension-compression couple where the tension-loaded anchors are located $1.5h_{ef}$ or farther from any free

COMMENTARY

mination of crack formation should include the effects of restrained shrinkage (refer to **24.4.2**). The anchor qualification tests of ACI CODE-355.2 or ACI CODE-355.4 require that anchors in cracked concrete zones perform well in a crack that is 0.012-in. wide. If wider cracks are expected, reinforcement to control the crack width to approximately 0.012 in. should be provided. Refer to **ACI PRC-224** for more information.

The concrete breakout strengths given by Eq. (17.6.2.2.1) and (17.6.2.2.3) assume cracked concrete ($\psi_{c,N} = 1.0$) with $\psi_{c,N}k_c = 24$ for cast-in anchors and 17 for post-installed anchors. If the uncracked concrete $\psi_{c,N}$ factors are applied (1.25 for cast-in and 1.4 for post-installed), $\psi_{c,N}k_c$ factors become 30 for cast-in anchors and 24 for post-installed anchors. This agrees with field observations and tests demonstrating cast-in anchor strength exceeds that of post-installed for both cracked and uncracked concrete.

R17.6.2.6 Breakout splitting factor, $\psi_{cp,N}$

R17.6.2.6.1 The design provisions in 17.6 are based on the assumption that the basic concrete breakout strength can be achieved if the minimum edge distance $c_{a,min}$ equals $1.5h_{ef}$. Test results (**Asmus 1999**), however, indicate that many torque-controlled and displacement-controlled expansion anchors and some undercut anchors require edge distances exceeding $1.5h_{ef}$ to achieve the basic concrete breakout strength if tested in uncracked concrete without supplementary reinforcement to control splitting. When a tensile load is applied, the resulting tensile stresses at the embedded end of the anchor are added to the tensile stresses induced due to anchor installation, and splitting failure may occur before reaching the concrete breakout strength given in 17.6.2.1. To account for this potential splitting mode of failure, the basic concrete breakout strength is reduced by a factor $\psi_{cp,N}$ if $c_{a,min}$ is less than the critical edge distance c_{ac} .

R17.6.2.6.2 If supplementary reinforcement to control splitting is present or if the anchors are located in a region where analysis indicates cracking of the concrete at service loads, the reduction factor $\psi_{cp,N}$ is taken as 1.0.

R17.6.2.7 Breakout compression field factor, $\psi_{cm,N}$

R17.6.2.7.1 For grouted baseplates or baseplates in direct contact with the concrete, where the internal lever arm, z , of the tension-compression couple resulting from a moment on an anchor plate is sufficiently small relative to the anchor embedment depth, the compression field developed in the

CODE

concrete edge and where the ratio of the resultant compression to tension forces is greater than 0.8 shall be calculated by:

$$\psi_{cm,N} = 2 - \frac{z}{1.5h_{ef}} \geq 1.0 \quad (17.6.2.7.1)$$

COMMENTARY

concrete inhibits formation of the tension breakout cone associated with the tension-loaded anchor(s) as shown in Fig. R17.6.2.7.1. This effect is accounted for with $\psi_{cm,N}$ (Eligehausen et al. 2006b). The effect of the compression field on the breakout strength of the tension-loaded anchors is neglected in cases where: a) the tension and compression resultants are separated by more than $1.5h_{ef}$; b) the ratio between the resultant compression and tension forces acting on the group is reduced, for example, by uplift on the connection; or c) the breakout strength is influenced by concrete edges. Determination of the compression resultant location and the value of z for a given combination of applied moments and axial force should correspond to a reasonable engineering model.




Fig. R17.6.2.7.1—Example of anchor group subjected to an overturning moment.

17.6.2.7.2 For all other cases, $\psi_{cm,N}$ shall be taken as 1.0.

R17.6.2.7.2 In all cases, it is conservative to take the value of $\psi_{cm,N} = 1.0$.

17.6.3 Pullout strength of a single cast-in anchor or a single post-installed expansion, screw, or undercut anchor in tension, N_{pn}

17.6.3.1 Nominal pullout strength of a single cast-in anchor or a single-post-installed expansion, screw, or undercut anchor in tension, N_{pn} , shall be calculated by:

$$N_{pn} = \psi_a \psi_{c,p} N_p \quad (17.6.3.1)$$

where $\psi_{c,p}$ is given in 17.6.3.3.

R17.6.3 Pullout strength of a single cast-in anchor or a single post-installed expansion, screw, or undercut anchor in tension, N_{pn}

R17.6.3.1 The design requirements for pullout are applicable to cast-in anchors and post-installed expansion, screw, and undercut anchors. They are not applicable to adhesive anchors, which are instead evaluated for bond failure in accordance with 17.6.5.

17.6.3.2 Basic single anchor pullout strength, N_p

17.6.3.2.1 For post-installed expansion, screw, and undercut anchors, the values of N_p shall be based on the 5 percent fractile of results of tests performed and evaluated according to ACI CODE-355.2. It is not permissible to calculate the pullout strength in tension for such anchors.

R17.6.3.2 Basic single anchor pullout strength, N_p

CODE

17.6.3.2.2 For single anchors, it shall be permitted to evaluate the pullout strength in tension, N_p , for use in Eq. (17.6.3.1) in accordance with (a) or (b). Alternatively, it shall be permitted to use values of N_p based on the 5% fractile of tests performed and evaluated in the same manner as the **ACI CODE-355.2** procedures but without the benefit of friction.

- (a) For cast-in headed studs and headed bolts, N_p shall be calculated by:

$$N_p = 8A_{brg}f'_c \quad (17.6.3.2.2a)$$

- (b) For J- or L-bolts, N_p shall be calculated by:

$$N_p = 0.9f'_c e_h d_a \quad (17.6.3.2.2b)$$

where $3d_a \leq e_h \leq 4.5d_a$.

COMMENTARY

R17.6.3.2.2 The pullout strength equations given in 17.6.3.2.2(a) and 17.6.3.2.2(b) are only applicable to cast-in headed and hooked anchors (**Kuhn and Shaikh 1996**; **fib 2011**); they are not applicable to post-installed expansion, screw, and undercut anchors that use various mechanisms for end anchorage unless the validity of the pullout strength equations is verified by tests.

The value calculated from Eq. (17.6.3.2.2a) corresponds to the force at which crushing of the concrete occurs due to bearing of the anchor head (**fib 2011**; **ACI CODE-349**). It is not the force required to pull the anchor completely out of the concrete; therefore, the equation does not contain a term relating to embedment depth. Local crushing of the concrete greatly reduces the stiffness of the connection, and generally will be the beginning of a pullout failure. The pullout strength in tension of headed studs or headed bolts can be increased by providing reinforcement, such as closely spaced spirals, throughout the head region. This increase can be demonstrated by tests, as required by the Licensed Design Professional for the specific application.

Equation (17.6.3.2.2b) for hooked bolts was developed by **Lutz (1995)** based on the results of **Kuhn and Shaikh (1996)**. Reliance is placed on the bearing component only, neglecting any frictional component, because crushing inside the hook will greatly reduce the stiffness of the connection and generally will be the beginning of a pullout failure. The limits on e_h are based on the range of variables used in the three test programs reported in **Kuhn and Shaikh (1996)**.

17.6.3.3 Pullout cracking factor, $\psi_{c,p}$

17.6.3.3.1 Modification factor to account for the influence of cracking in anchor regions at service load levels, $\psi_{c,p}$, shall be determined by (a) or (b):

- (a) For anchors located in a region of a concrete member where analysis indicates no cracking at service load levels, $\psi_{c,p}$ shall be permitted to be 1.4.
 (b) For anchors located in a region of a concrete member where analysis indicates cracking at service load levels, $\psi_{c,p}$ shall be taken as 1.0.

17.6.4 Concrete side-face blowout strength of headed anchors in tension, N_{sb}

17.6.4.1 For a single headed anchor with deep embedment close to an edge ($h_{ef} > 2.5c_{a1}$), the nominal side-face blowout strength, N_{sb} , shall be calculated by:

$$N_{sb} = \psi_a 160 c_{a1} \sqrt{A_{brg}} \lambda_a \sqrt{f'_c} \quad (17.6.4.1)$$

17.6.4.1.1 If c_{a2} for the single headed anchor is less than $3c_{a1}$, the value of N_{sb} shall be multiplied by the factor $(1 + c_{a2}/c_{a1})/4$, where $1.0 \leq c_{a2}/c_{a1} \leq 3.0$.

R17.6.4 Concrete side-face blowout strength of headed anchors in tension, N_{sb}

R17.6.4.1 The design requirements for side-face blowout are based on the recommendations of **Furche and Eligehausen (1991)** and are applicable to headed anchors that usually are cast-in. Splitting during installation rather than side-face blowout generally governs post-installed anchors and is evaluated by **ACI CODE-355.2** requirements.

CODE

17.6.4.2 For multiple headed anchors with deep embedment close to an edge ($h_{ef} > 2.5c_{a1}$) and anchor spacing less than $6c_{a1}$, the nominal strength of those anchors susceptible to a side-face blowout failure, N_{sb} , shall be calculated by:

$$N_{sb} = \left(1 + \frac{s}{6c_{a1}}\right) N_{sb} \quad (17.6.4.2)$$

where s is the distance between the outer anchors along the edge, and N_{sb} is obtained from Eq. (17.6.4.1) without modification for a perpendicular edge distance.

17.6.5 Bond strength of adhesive anchors in tension, N_a or N_{ag}

17.6.5.1 Nominal bond strength in tension, N_a of a single adhesive anchor or N_{ag} of an adhesive anchor group satisfying 17.5.1.4.1, shall be calculated by (a) or (b), respectively.

(a) For a single adhesive anchor:

$$N_a = \frac{A_{Na}}{A_{Nao}} \psi_a \psi_{ed,Na} \psi_{cp,Na} N_{ba} \quad (17.6.5.1a)$$

(b) For an adhesive anchor group:

$$N_{ag} = \frac{A_{Na}}{A_{Nao}} \psi_a \psi_{ec,Na} \psi_{ed,Na} \psi_{cp,Na} N_{ba} \quad (17.6.5.1b)$$

where ψ_a , $\psi_{ec,Na}$, $\psi_{ed,Na}$, and $\psi_{cp,Na}$ are given in 17.5.4.1, 17.6.5.3, 17.6.5.4, and 17.6.5.5, respectively.

COMMENTARY

R17.6.4.2 To calculate nominal side-face blowout strength for multiple headed anchors, only those anchors close to an edge ($c_{a1} < 0.4h_{ef}$) that are loaded in tension should be considered. Their strength is compared to the portion of the tensile load applied to those anchors.

R17.6.5 Bond strength of adhesive anchors in tension, N_a or N_{ag}

R17.6.5.1 Evaluation of bond strength applies only to adhesive anchors. Single anchors with small embedment loaded to failure in tension may exhibit concrete breakout failures, while deeper embedments produce bond failures. Adhesive anchors that exhibit bond failures when loaded individually may exhibit concrete failures in a group or in a near-edge condition. In all cases, the strength in tension of adhesive anchors is limited by concrete breakout strength as given by Eq. (17.6.2.1a) and (17.6.2.1b) (Eligehausen et al. 2006a).

The influence of anchor spacing and edge distance on both bond strength and concrete breakout strength must be evaluated for adhesive anchors. The influence of anchor spacing and edge distance on the nominal bond strength of adhesive anchors in tension are included in the modification factors A_{Na}/A_{Nao} and $\psi_{ed,Na}$ in Eq. (17.6.5.1a) and (17.6.5.1b).

The influence of nearby edges and adjacent loaded anchors on bond strength is dependent on the volume of concrete mobilized by a single adhesive anchor. In contrast to the projected concrete failure area concept used in Eq. (17.6.2.1a) and (17.6.2.1b) to calculate the breakout strength of an adhesive anchor, the influence area associated with the bond strength of an adhesive anchor used in Eq. (17.6.5.1a) and (17.6.5.1b) is not a function of the embedment depth, but rather a function of the anchor diameter and characteristic bond stress. The critical distance c_{Na} is assumed the same whether the concrete is cracked or uncracked. For simplicity, the relationship for c_{Na} in Eq. (17.6.5.1.2b) uses τ_{uncr} , the characteristic bond stress in uncracked concrete. This has been verified by experimental and numerical studies (Eligehausen et al. 2006a). Figure R17.6.5.1(a) shows A_{Nao} and the development of Eq. (17.6.5.1.2a). A_{Nao} is the projected influence area for the bond strength of a single adhesive anchor. Figure R17.6.5.1(b) shows an example of the projected influence area for an anchor group. Because, in this case, A_{Na} is the projected influence area for an anchor group, and A_{Nao} is the projected influence area for a single anchor, there is no need to include n , the number of anchors, in Eq. (17.6.5.1b). If individual anchors in a group (anchors loaded by a common base plate or attachment) are positioned in such a way that the projected influence areas of the individual anchors overlap, the value of A_{Na} is less than nA_{Nao} .

CODE

17.6.5.1.1 A_{Na} is the projected influence area of a single adhesive anchor or an adhesive anchor group that is approximated as a rectilinear area that projects outward a distance c_{Na} from the centerline of the adhesive anchor, or in the case of an adhesive anchor group, from a line through a row of adjacent adhesive anchors. A_{Na} shall not exceed nA_{Nao} , where n is the number of adhesive anchors in the group that resist tension.

17.6.5.1.2 A_{Nao} is the projected influence area of a single adhesive anchor with an edge distance of at least c_{Na} :

$$A_{Nao} = (2c_{Na})^2 \quad (17.6.5.1.2a)$$

where


$$c_{Na} = 10d_a \sqrt{\frac{\tau_{uncr}}{1100}} \quad (17.6.5.1.2b)$$

COMMENTARY

The tensile strength of closely spaced adhesive anchors with low bond strength may significantly exceed the value given by Eq. (17.6.5.1b). A correction factor is given in the literature ([Eligehausen et al. 2006a](#)) to address this issue, but for simplicity, this factor is not included in the Code.




CODE



Plan view

$$A_{Na0} = (2c_{Na})^2$$



COMMENTARY



Plan view

if c_{a1} and $c_{a2} < c_{Na}$ s_1 and $s_2 < 2c_{Na}$

$$A_{Na} = (c_{Na} + s_1 + c_{a1})(c_{Na} + s_2 + c_{a2})$$

Section through anchor
showing principal stress trajectories(a) Single adhesive anchor away
from edges and other anchorsSection through anchor group
showing principal stress trajectories(b) Group of four adhesive anchors
located near a cornerFig. R17.6.5.1—Calculation of influence areas A_{Na0} and A_{Na} .

CODE

17.6.5.2 Basic single anchor bond strength, N_{ba}

17.6.5.2.1 Basic bond strength of a single adhesive anchor in tension in cracked concrete, N_{ba} , shall be calculated by Eq. (17.6.5.2.1)

$$N_{ba} = \lambda_a \tau_{cr} \pi d_a h_{ef} \quad (17.6.5.2.1)$$

17.6.5.2.2 Characteristic bond stress, τ_{cr} , shall be taken as the 5 percent fractile of results of tests performed and evaluated in accordance with **ACI CODE-355.4**.

17.6.5.2.3 If analysis indicates cracking at service load levels, adhesive anchors shall be qualified for use in cracked concrete in accordance with ACI CODE-355.4.

17.6.5.2.4 For adhesive anchors located in a region of a concrete member where analysis indicates no cracking at service load levels, τ_{uncr} shall be permitted to be used in place of τ_{cr} in Eq. (17.6.5.2.1) and shall be taken as the 5 percent fractile of results of tests performed and evaluated according to ACI CODE-355.4.

17.6.5.2.5 It shall be permitted to use the minimum characteristic bond stress values in Table 17.6.5.2.5, provided (a) through (e) are satisfied:

- (a) Anchors shall meet the requirements of ACI CODE-355.4
- (b) Anchors shall be installed in holes drilled with a rotary impact drill or rock drill
- (c) Concrete compressive strength at time of anchor installation shall be at least 2500 psi
- (d) Concrete age at time of anchor installation shall be at least 21 days
- (e) Concrete temperature at time of anchor installation shall be at least 50°F

COMMENTARY

R17.6.5.2 Basic single anchor bond strength, N_{ba}

R17.6.5.2.1 The equation for basic bond strength of adhesive anchors as given in Eq. (17.6.5.2.1) represents a uniform bond stress model that has been shown to provide the best prediction of adhesive anchor bond strength based on numerical studies and comparisons of different models to an international database of experimental results (**Cook et al. 1998**). The basic bond strength is valid for bond failures that occur between the concrete and the adhesive as well as between the anchor and the adhesive.

R17.6.5.2.2 Characteristic bond stresses should be based on tests performed in accordance with ACI CODE-355.4 and should reflect the particular combination of installation and use conditions anticipated during construction and during anchor service life. If product-specific information is unavailable at the time of design, Table 17.6.5.2.5 provides lower-bound default values.

R17.6.5.2.5 The characteristic bond stresses in Table 17.6.5.2.5 are the minimum values permitted for adhesive anchor systems qualified in accordance with ACI CODE-355.4 for the tabulated installation and use conditions. Use of these values is restricted to the combinations of specific conditions listed; values for other combinations of installation and use conditions should not be inferred. If both sustained tension and earthquake-induced forces are required to be resisted by the anchors, the applicable factors given in the footnotes of Table 17.6.5.2.5 should be multiplied together. The table assumes a concrete age of at least 21 days and a concrete compressive strength of at least 2500 psi.

The terms “indoor” and “outdoor” as used in Table 17.6.5.2.5 refer to a specific set of installation and service environments. Indoor conditions represent anchors installed in dry concrete with a rotary impact drill or rock drill and subjected to limited concrete temperature variations over the service life of the anchor. Outdoor conditions are assumed to occur if, at the time of installation, the concrete is exposed to weather that might leave the concrete wet. Anchors installed in outdoor conditions are also assumed to be subject to greater concrete temperature variations such as might be associated with freezing and thawing or elevated temperatures resulting from direct sun exposure. While the indoor/

CODE

Table 17.6.5.2.5—Minimum characteristic bond stresses^{[1][2]}

Installation and service environment	Moisture content of concrete at time of anchor installation	Peak in-service temperature of concrete, °F	τ_{cr} , psi	τ_{uncr} , psi
Outdoor	Dry to fully saturated	175	200	650
Indoor	Dry	110	300	1000

^[1]If anchor design includes sustained tension, multiply values of τ_{cr} and τ_{uncr} by 0.4.

^[2]If anchor design includes earthquake-induced forces for structures assigned to SDC C, D, E, or F, multiply values of τ_{cr} by 0.8 and τ_{uncr} by 0.4.

COMMENTARY

outdoor characterization is useful for many applications, there may be situations in which a literal interpretation of the terms “indoor” and “outdoor” do not apply. For example, anchors installed before the building envelope is completed may involve drilling in saturated concrete. As such, the minimum characteristic bond stress associated with the outdoor condition in Table 17.6.5.2.5 applies, regardless of whether the service environment is “indoor” or “outdoor.”

Rotary impact drills and rock drills produce non-uniform hole geometries that are generally favorable for bond. Installation of adhesive anchors in core-drilled holes may result in substantially lower characteristic bond stresses. Because this effect is highly product dependent, design of anchors to be installed in core-drilled holes should adhere to the product-specific characteristic bond stresses established through testing in accordance with **ACI CODE-355.4**.

The characteristic bond stresses associated with specific adhesive anchor systems are dependent on a number of parameters. Consequently, care should be taken to include all parameters relevant to the value of characteristic bond stress used in the design. These parameters include but are not limited to:

- Type and duration of loading—bond strength is reduced for sustained tension
- Concrete cracking—bond strength is higher in uncracked concrete
- Anchor size—bond strength is generally inversely proportional to anchor diameter
- Drilling method—bond strength may be lower for anchors installed in core-drilled holes
- Degree of concrete saturation at time of hole drilling and anchor installation—bond strength may be reduced due to concrete saturation
- Concrete temperature at time of installation—installation of anchors in cold conditions may result in retarded adhesive cure and reduced bond strength
- Concrete age at time of installation—installation in early-age concrete may result in reduced bond strength (refer to R17.2.2)
- Peak concrete temperatures during anchor service life—under specific conditions (for example, anchors in thin concrete members exposed to direct sunlight), elevated concrete temperatures can result in reduced bond strength
- Chemical exposure—anchors used in industrial environments may be exposed to increased levels of contaminants that can reduce bond strength over time

Anchors tested and assessed under ACI CODE-355.4 may in some cases not be qualified for all of the installation and service environments represented in Table 17.6.5.2.5. Therefore, where the minimum values given in Table 17.6.5.2.5 are used for design, the relevant installation and service environments should be specified in accordance with **26.7.1(i), (j), (k), and (l)**, and only anchors that have been qualified under ACI CODE-355.4 for the installation and service environ-

CODE

COMMENTARY

17.6.5.3 Bond eccentricity factor, $\psi_{ec,Na}$

17.6.5.3.1 Modification factor for adhesive anchor groups loaded eccentrically in tension, $\psi_{ec,Na}$, shall be calculated by Eq. (17.6.5.3.1).

$$\psi_{ec,Na} = \frac{1}{\left(1 + \frac{e'_N}{c_{Na}}\right)} \leq 1.0 \quad (17.6.5.3.1)$$

17.6.5.3.2 If the loading on an adhesive anchor group is such that only some of the adhesive anchors are in tension, only those adhesive anchors that are in tension shall be considered for determining eccentricity e'_N in Eq. (17.6.5.3.1) and for the calculation of N_{ag} according to Eq. (17.6.5.1b).

17.6.5.3.3 If a load is eccentric about two orthogonal axes, $\psi_{ec,Na}$ shall be calculated for each axis individually, and the product of these factors shall be used as $\psi_{ec,Na}$ in Eq. (17.6.5.1b).

17.6.5.4 Bond edge effect factor, $\psi_{ed,Na}$

17.6.5.4.1 Modification factor for edge effects for single adhesive anchors or adhesive anchor groups in tension, $\psi_{ed,Na}$, shall be determined by (a) or (b) using the critical distance c_{Na} as defined in Eq. (17.6.5.1.2b).

(a) If $c_{a,min} \geq c_{Na}$, then

$$\psi_{ed,Na} = 1.0 \quad (17.6.5.4.1a)$$

(b) If $c_{a,min} < c_{Na}$, then

$$\psi_{ed,Na} = 0.7 + 0.3 \frac{c_{a,min}}{c_{Na}} \quad (17.6.5.4.1b)$$

17.6.5.5 Bond splitting factor, $\psi_{cp,Na}$

17.6.5.5.1 Modification factor for adhesive anchors designed for uncracked concrete in accordance with 17.6.5.1 without supplementary reinforcement to control splitting, $\psi_{cp,Na}$, shall be determined by (a) or (b) where c_{ac} is defined in 17.9.5

(a) If $c_{a,min} \geq c_{ac}$, then

ments corresponding to the characteristic bond stress taken from Table 17.6.5.2.5 should be specified.

Characteristic bond stresses associated with qualified adhesive anchor systems for a specific set of installation and use conditions may substantially exceed the minimum values provided in Table 17.6.5.2.5. For example, 1/2-in. to 3/4-in. diameter anchors installed in impact-drilled holes in dry concrete where use is limited to indoor conditions in uncracked concrete as described above may exhibit characteristic bond stresses τ_{uncr} in the range of 2000 to 2500 psi.

R17.6.5.3 Bond eccentricity factor, $\psi_{ec,Na}$

R17.6.5.3.1 Refer to R17.6.2.3.1.

R17.6.5.4 Bond edge effect factor, $\psi_{ed,Na}$

R17.6.5.4.1 If anchors are located close to an edge, their strength is further reduced beyond that reflected in A_{Na}/A_{Na0} . The factor $\psi_{ed,Na}$ accounts for the edge effect (Fuchs et al. 1995; Eligehausen et al. 2006a).

CODE

$$\psi_{cp,Na} = 1.0 \quad (17.6.5.5.1a)$$

(b) If $c_{a,min} < c_{ac}$, then

$$\psi_{ed,Na} = \frac{c_{a,min}}{c_{ac}} \geq \frac{c_{Na}}{c_{ac}} \quad (17.6.5.5.1b)$$

17.6.5.5.2 For all other cases, $\psi_{cp,Na}$ shall be taken as 1.0.

17.7—Shear strength**17.7.1 Steel strength of anchors in shear, V_{sa}**

17.7.1.1 Nominal steel strength of anchors in shear as governed by the steel, V_{sa} , shall be evaluated based on the properties of the anchor material and the physical dimensions of the anchors. If concrete breakout is a potential failure mode, the required steel shear strength shall be consistent with the assumed breakout surface.

17.7.1.2 Nominal strength of an anchor in shear, V_{sa} , shall not exceed (a) through (c):

(a) For cast-in headed stud anchor

$$V_{sa} = A_{se,V} f_{uta} \quad (17.7.1.2a)$$

where $A_{se,V}$ is the effective cross-sectional area of an anchor in shear, in.², and f_{uta} used for calculations shall not exceed either $1.9f_{ya}$ or 125,000 psi.

(b) For cast-in headed bolt and hooked bolt anchors and for post-installed adhesive anchors

$$V_{sa} = 0.6A_{se,V} f_{uta} \quad (17.7.1.2b)$$

where $A_{se,V}$ is the effective cross-sectional area of an anchor in shear, in.², and the value of f_{uta} shall not exceed either $1.9f_{ya}$ or 125,000 psi.

(c) For post-installed mechanical anchors, V_{sa} shall be based on the 5 percent fractile of results of tests performed and evaluated in accordance with **ACI CODE-355.2**. It is not permissible to calculate the steel strength in shear for such anchors.

17.7.1.2.1 If anchors are used with built-up grout pads, nominal strength V_{sa} calculated in accordance with 17.7.1.2 shall be multiplied by 0.80.

COMMENTARY**R17.7—Shear strength****R17.7.1 Steel strength of anchors in shear, V_{sa}**

R17.7.1.1 The shear applied to each anchor in an anchor group may vary depending on assumptions for the concrete breakout surface and load redistribution (refer to R17.7.2.1).

R17.7.1.2 The nominal shear strength of anchors is best represented as a function of f_{uta} rather than f_{ya} because the large majority of anchor materials do not exhibit a well-defined yield point. Welded studs develop a higher steel shear strength than headed anchors due to the fixity provided by the weld between the studs and the base plate. The use of Eq. (17.7.1.2a) and (17.7.1.2b) with the load factors of **5.3** and the ϕ -factors of 17.5.3 result in design strengths consistent with **ANSI/AISC 360**.

The limitation of $1.9f_{ya}$ on f_{uta} is to ensure that, under service load conditions, the anchor stress does not exceed f_{ya} . The limit on f_{uta} of $1.9f_{ya}$ was determined by converting the LRFD provisions to corresponding service-level conditions, as discussed in R17.6.1.2.

For post-installed adhesive anchors having a reduced cross-sectional area anywhere along the anchor length, the effective cross-sectional area of the anchor should be provided by the manufacturer. For threaded rods and headed bolts, **ASME B1.1** defines $A_{se,V}$ as

$$A_{se,V} = \frac{\pi}{4} \left(d_a - \frac{0.9743}{n_t} \right)^2$$

where n_t is the number of threads per inch.

CODE

17.7.2 Concrete breakout strength of anchors in shear, V_{cb}

17.7.2.1 Nominal concrete breakout strength in shear, V_{cb} of a single anchor or V_{cbg} of an anchor group satisfying 17.5.1.4.1, shall be calculated in accordance with (a) through (d):

(a) For shear perpendicular to the edge on a single anchor

$$V_{cb} = \frac{A_{Vc}}{A_{Vco}} \psi_a \psi_{ed,V} \psi_{c,V} \psi_{h,V} V_b \quad (17.7.2.1a)$$

(b) For shear perpendicular to the edge on an anchor group

$$V_{cbg} = \frac{A_{Vc}}{A_{Vco}} \psi_a \psi_{ec,V} \psi_{ed,V} \psi_{c,V} \psi_{h,V} V_b \quad (17.7.2.1b)$$

(c) For shear parallel to an edge, V_{cb} or V_{cbg} shall be permitted to be twice the value of the shear calculated by Eq. (17.7.2.1a) or (17.7.2.1b), respectively, with the shear assumed to act perpendicular to the edge and $\psi_{ed,V}$ taken equal to 1.0.

(d) For anchors located at a corner, the limiting nominal concrete breakout strength shall be calculated for each edge, and the lesser value shall be used.

where ψ_a , $\psi_{ec,V}$, $\psi_{ed,V}$, $\psi_{c,V}$, and $\psi_{h,V}$ are given in 17.5.4.1, 17.7.2.3, 17.7.2.4, 17.7.2.5, and 17.7.2.6, respectively.

COMMENTARY

R17.7.2 Concrete breakout strength of anchors in shear, V_{cb}

R17.7.2.1 The shear strength equations were developed from the CCD Method (refer to R17.5.1.4). They assume a breakout angle of approximately 35 degrees (refer to Fig. R17.5.1.4b) and consider fracture mechanics theory. The effects of multiple anchors, spacing of anchors, edge distance, and thickness of the concrete member on nominal concrete breakout strength in shear are included by applying the reduction factor of A_{Vc}/A_{Vco} in Eq. (17.7.2.1a) and (17.7.2.1b), and $\psi_{ec,V}$ in Eq. (17.7.2.1b). For anchors far from the edge, 17.7.2 usually will not govern. For these cases, 17.7.1 and 17.7.3 often govern.

Figure R17.7.2.1a shows A_{Vco} and the development of Eq. (17.7.2.1.3). A_{Vco} is the maximum projected area for a single anchor that approximates the surface area of the full breakout volume for an anchor unaffected by edge distance, spacing, or depth of member. Figure R17.7.2.1b shows examples of the projected areas for various single-anchor and multiple-anchor arrangements. A_{Vc} approximates the full surface area of the breakout for the particular arrangement of anchors. Because A_{Vc} is the total projected area for an anchor group, and A_{Vco} is the area for a single anchor, there is no need to include the number of anchors in the equation.

As shown in the examples in Fig. R17.7.2.1b of two-anchor groups loaded in shear, when using Eq. (17.7.2.1b) for cases where the anchor spacing s is greater than the edge distance to the near-edge anchor $c_{a1,1}$, both assumptions for load distribution illustrated in Cases 1 and 2 should be considered. This is because the anchors nearest to the free edge could fail first or the entire group could fail as a unit with the failure surface originating from the anchors farthest from the edge. For Case 1, the steel shear strength is provided by both anchors. For Case 2, the steel shear strength is provided entirely by the anchor farthest from the edge; no contribution of the anchor near the edge is considered. In addition, checking the near-edge anchor for concrete breakout under service loads is advisable to preclude undesirable cracking at service conditions. If the anchor spacing s is less than the edge distance to the near-edge anchor, the failure surfaces may merge (Eligehausen et al. 2006b) and Case 3 of Fig. R17.7.2.1b may be taken as a conservative approach.

If the anchors are welded to a common plate (regardless of anchor spacing s), when the anchor nearest the front edge begins to form a breakout failure, shear is transferred to the stiffer and stronger rear anchor. For this reason, only Case 2 need be considered, which is consistent with Section 6.5.5 of the *PCI Design Handbook* (PCI MNL 120). For determination of steel shear strength, it is conservative to consider only the anchor farthest from the edge. However, for anchors having a ratio of $s/c_{a1,1}$ less than 0.6, both the front and rear anchors may be assumed to resist the shear (Anderson and Meinheit 2007). For ratios of $s/c_{a1,1}$ greater than 1, it is advisable to check concrete breakout of the near-edge anchor to preclude undesirable cracking at service conditions.

CODE

COMMENTARY

Further discussion of design for multiple anchors is given in [Primavera et al. \(1997\)](#).

For anchors near a corner required to resist a shear force with components normal to each edge, a satisfactory solution is to check the connection independently for each component of the shear force. Other specialized cases, such as the shear resistance of anchor groups where all anchors do not have the same edge distance, are treated in [Eligehausen et al. \(2006a\)](#).

The detailed provisions of 17.7.2.1(a) apply to the case of shear directed toward an edge. If the shear is directed away from the edge, the strength will usually be governed by 17.7.1 or 17.7.3. The case of shear parallel to an edge is shown in Fig. R17.7.2.1c. The maximum shear that can be applied parallel to the edge, $V_{||}$, as governed by concrete breakout, is twice the maximum shear that can be applied perpendicular to the edge, $V_{\perp}$. For a single anchor required to resist shear near a corner (refer to Fig. R17.7.2.1d), the provisions for shear applied perpendicular to the edge should be checked in addition to the provisions for shear applied parallel to the edge.









Fig. R17.7.2.1a—Calculation of A_{Vco} .

CODE


COMMENTARY



Note: For $s \geq c_{a1,1}$, both Case 1 and Case 2 should be evaluated to determine which controls for design except as noted for anchors welded to a common plate



If $c_{a2} < 1.5c_{a1}$
 $A_{vc} = 1.5c_{a1}(1.5c_{a1} + c_{a2})$



Case 1: One assumption of the distribution of forces indicates that half of the shear force would be critical on the front anchor and the projected area. For the calculation of concrete breakout, c_{a1} is taken as $c_{a1,1}$.

Case 2: Another assumption of the distribution of forces indicates that the total shear force would be critical on the rear anchor and its projected area. Only this assumption needs to be considered when anchors are welded to a common plate independent of s . For the calculation of concrete breakout, c_{a1} is taken as $c_{a1,2}$.

Case 3: Where $s < c_{a1,1}$, apply the entire shear load V to the front anchor. This case does not apply for anchors welded to a common plate. For the calculation of concrete breakout, c_{a1} is taken as $c_{a1,1}$.

Fig. R17.7.2.1b—Calculation of A_{vc} for single anchors and anchor groups.

CODE

COMMENTARY




Fig. R17.7.2.1c—Shear force parallel to an edge.




Fig. R17.7.2.1d—Shear near a corner.

17.7.2.1.1 A_{Vc} is the projected area of the failure surface on the side of the concrete member at its edge for a single anchor or an anchor group. It shall be permitted to evaluate A_{Vc} as the base of a truncated half-pyramid projected on the side face of the member where the top of the half-pyramid is given by the axis of the anchor row selected as critical. The value of c_{a1} shall be taken as the distance from the edge to

CODE

this axis. A_{Vc} shall not exceed nA_{Vco} , where n is the number of anchors in the group.


17.7.2.1.2 If anchors are located in narrow sections of limited thickness such that both edge distances c_{a2} and thickness h_a are less than $1.5c_{a1}$, the value of c_{a1} used to calculate A_{Vc} in accordance with 17.7.2.1.1 as well as for the equations in 17.7.2.1 through 17.7.2.6 shall not exceed the greatest of (a) through (c).

- (a) $c_{a2}/1.5$, where c_{a2} is the greatest edge distance
- (b) $h_a/1.5$
- (c) $s/3$, where s is the maximum spacing perpendicular to direction of shear, between anchors within a group

COMMENTARY

R17.7.2.1.2 For anchors located in narrow sections of limited thickness where the edge distances perpendicular to the direction of load and the member thickness are less than $1.5c_{a1}$, the shear breakout strength calculated by the CCD Method (refer to R17.5.1.4) is overly conservative. These cases were studied for the Kappa Method (Eligehausen and Fuchs 1988), and the problem was pointed out by Lutz (1995). Similar to the approach used for concrete breakout strength in tension in 17.6.2.1.2, the concrete breakout strength in shear for this case is more accurately evaluated if the value of c_{a1} used in 17.7.2.1 through 17.7.2.6 and in the calculation of A_{Vc} is limited to the maximum of two-thirds of the greater of the two edge distances perpendicular to the direction of shear, two-thirds of the member thickness, and one-third of the maximum spacing between individual anchors within the group, measured perpendicular to the direction of shear. The limit on c_{a1} of at least one-third of the maximum spacing between anchors within the group prevents the use of a calculated strength based on individual breakout volumes for an anchor group configuration.

This approach is illustrated in Fig. R17.7.2.1.2. In this example, the limiting value of c_{a1} is denoted as c'_{a1} and is used to calculate A_{Vc} , A_{Vco} , $\psi_{ed,V}$, and $\psi_{h,V}$ as well as V_b (not shown). The requirement of 17.7.2.1.2 may be visualized by moving the actual concrete breakout surface originating at the actual c_{a1} toward the surface of the concrete in the direction of the applied shear. The value of c_{a1} used to calculate A_{Vc} and to be used in 17.7.2.1 through 17.7.2.6 is determined when (a) an outer boundary of the failure surface first intersects the concrete surface; or (b) the intersection of the breakout surface between individual anchors within the group first intersects the concrete surface. For the example shown in Fig. R17.7.2.1.2, point “A” shows the intersection of the assumed failure surface for limiting c_{a1} with the concrete surface.



1. The actual $c_{a1} = 12$ in.
2. The two edge distances c_{a2} as well as h_a are all less than $1.5c_{a1}$.
3. The limiting value of c_{a1} (shown as c'_{a1} in the figure) to be used to calculate A_{Vc} and to be used in 17.7.2.1 through 17.7.2.6 is the largest of the following:
 - $(c_{a2,max})/1.5 = (7)/1.5 = 4.67$ in.
 - $(h_a)/1.5 = (8)/1.5 = 5.33$ in. (controls)
 - $s/3 = 9/3 = 3$ in.
4. For this case, A_{Vc} , A_{Vco} , $\psi_{ed,v}$, and $\psi_{h,v}$ are:
 - $A_{Vc} = (5 + 9 + 7)(1.5 \times 5.33) = 168 \text{ in.}^2$
 - $A_{Vco} = 4.5(5.33)^2 = 128 \text{ in.}^2$
 - $\psi_{ed,v} = 0.7 + 0.3(5)/5.33 = 0.98$
 - $\psi_{h,v} = 1.0$ because $c_{a1} = (h_a)/1.5$. Point A shows the intersection of the assumed failure surface with the concrete surface that establishes the limiting value of c_{a1} .

Fig. R17.7.2.1.2—Example of shear where anchors are located in narrow members of limited thickness.

17.7.2.1.3 A_{Vco} is the projected area for a single anchor in a deep member with a distance from edges of at least $1.5c_{a1}$ in the direction perpendicular to the shear. It shall be permitted to calculate A_{Vco} by Eq. (17.7.2.1.3), which gives the area of the base of a half-pyramid with a side length parallel to the edge of $3c_{a1}$ and a depth of $1.5c_{a1}$.

$$A_{Vco} = 4.5(c_{a1})^2 \quad (17.7.2.1.3)$$

17.7.2.1.4 If anchors are located at varying distances from the edge and the anchors are welded to the attachment so as to distribute the force to all anchors, it shall be permitted to evaluate the strength based on the distance to the farthest row of anchors from the edge. In this case, it shall be permitted to base the value of c_{a1} on the distance from the edge to the axis of the farthest anchor row that is selected as critical, and all of the shear shall be assumed to be resisted by this critical anchor row alone.

CODE

17.7.2.2 Basic single anchor breakout strength, V_b

17.7.2.2.1 Basic concrete breakout strength of a single anchor in shear in cracked concrete, V_b , shall not exceed the lesser of (a) and (b):

$$(a) V_b = \left(7 \left(\frac{\ell_e}{d_a} \right)^2 \sqrt{d_a} \right) \lambda_a \sqrt{f'_c} (c_{a1})^{1.5} \quad (17.7.2.2.1a)$$

where ℓ_e is the load-bearing length of the anchor for shear: $\ell_e = h_{ef}$ for anchors with a constant stiffness over the full length of embedded section, such as headed studs and post-installed anchors with one tubular shell over full length of the embedment depth; $\ell_e = 2d_a$ for torque-controlled expansion anchors with a distance sleeve separated from expansion sleeve; $\ell_e \leq 8d_a$ in all cases.

$$(b) V_b = 9 \lambda_a \sqrt{f'_c} (c_{a1})^{1.5} \quad (17.7.2.2.1b)$$

17.7.2.2.2 For cast-in headed studs, headed bolts, or hooked bolts that are continuously welded to steel attachments, basic concrete breakout strength of a single anchor in shear in cracked concrete, V_b , shall be the lesser of Eq. (17.7.2.2.1b) and Eq. (17.7.2.2.2) provided that (a) through (d) are satisfied.

$$V_b = \left(8 \left(\frac{\ell_e}{d_a} \right)^{0.2} \sqrt{d_a} \right) \lambda_a \sqrt{f'_c} (c_{a1})^{1.5} \quad (17.7.2.2.2)$$

where ℓ_e is defined in 17.7.2.2.1.

- (a) Steel attachment thickness is the greater of $0.5d_a$ and 3/8 in.
- (b) Anchor spacing s is at least 2.5 in.
- (c) Reinforcement is provided at the corners if $c_{a2} \leq 1.5h_{ef}$
- (d) For anchor groups, the strength is calculated based on the strength of the row of anchors farthest from the edge.

17.7.2.3 Breakout eccentricity factor, $\psi_{ec,V}$

17.7.2.3.1 Modification factor for anchor groups loaded eccentrically in shear, $\psi_{ec,V}$, shall be calculated by Eq. (17.7.2.3.1).

$$\psi_{ec,V} = \frac{1}{\left(1 + \frac{e'_V}{1.5c_{a1}} \right)} \leq 1.0 \quad (17.7.2.3.1)$$

COMMENTARY

R17.7.2.2 Basic single anchor breakout strength, V_b

R17.7.2.2.1 Like the concrete breakout tensile strength, the concrete breakout shear strength does not increase with the failure surface, which is proportional to $(c_{a1})^2$. Instead, the strength increases proportionally to $(c_{a1})^{1.5}$ due to the size effect. The constant, 7, in the shear strength equation (17.7.2.2.1a) was determined from test data reported in [Fuchs et al. \(1995\)](#) at the 5% fractile adjusted for cracking.

The strength is also influenced by the anchor stiffness and the anchor diameter ([Fuchs et al. 1995](#); [Eligehausen and Balogh 1995](#); [Eligehausen et al. 1987, 2006b](#); [Eligehausen and Fuchs 1988](#)). The influence of anchor stiffness and diameter is not apparent in large-diameter anchors ([Lee et al. 2010](#)), resulting in a limitation on the shear breakout strength provided by Eq. (17.7.2.2.1b).


R17.7.2.2.2 For cast-in headed bolts continuously welded to an attachment, test data ([Shaikh and Yi 1985](#)) show that somewhat higher shear strength exists, possibly due to the stiff welded connection clamping the bolt more effectively than an attachment with an anchor gap. Because of this, the basic shear breakout strength for such anchors is increased, but the upper limit of Eq. (17.7.2.2.1b) is imposed because tests on large-diameter anchors welded to steel attachments are not available to justify a higher value than Eq. (17.7.2.2.1b). The design of supplementary reinforcement is discussed in [fib \(2011\)](#), [Eligehausen et al. \(1987, 2006b\)](#), and [Eligehausen and Fuchs \(1988\)](#).

R17.7.2.3 Breakout eccentricity factor, $\psi_{ec,V}$

R17.7.2.3.1 This section provides a modification factor for an eccentric shear toward an edge on an anchor group. If the shear originates above the plane of the concrete surface, the shear should first be resolved as a shear in the plane of the concrete surface, acting in combination with a moment that may or may not also cause tension in the anchors, depending on the normal force. Figure R17.7.2.3.1 defines the term e'_V for calculating the $\psi_{ec,V}$ modification factor that accounts for the fact that more shear is applied to one anchor than others, tending to split the concrete near an edge.

CODE

COMMENTARY

Fig. R17.7.2.3.1—Definition of e'_v for an anchor group.

17.7.2.3.2 If the loading on an anchor group is such that only some of the anchors in the group are in shear, only those anchors that are in shear in the same direction shall be considered for determining the eccentricity e'_v in Eq. (17.7.2.3.1) and for the calculation of V_{cbg} according to Eq. (17.7.2.1b).

17.7.2.4 Breakout edge effect factor, $\psi_{ed,V}$

17.7.2.4.1 Modification factor for edge effects for single anchors or anchor groups loaded in shear, $\psi_{ed,V}$, shall be determined by (a) or (b) using the lesser value of c_{a2} .

(a) If $c_{a2} \geq 1.5c_{a1}$, then

$$\psi_{ed,V} = 1.0 \quad (17.7.2.4.1a)$$

(b) If $c_{a2} < 1.5c_{a1}$, then

$$\psi_{ed,V} = 0.7 + 0.3 \frac{c_{a2}}{1.5c_{a1}} \quad (17.7.2.4.1b)$$

17.7.2.5 Breakout cracking factor, $\psi_{c,V}$

17.7.2.5.1 Modification factor for the influence of cracking in anchor regions at service load levels and presence or absence of supplementary reinforcement, $\psi_{c,V}$, shall be determined as follows:

- (a) For anchors located in a region of a concrete member where analysis indicates no cracking at service load levels, $\psi_{c,V}$ shall be permitted to be 1.4.
- (b) For anchors located in a region of a concrete member where analysis indicates cracking at service load levels, $\psi_{c,V}$ shall be in accordance with Table 17.7.2.5.1.

CODE

Table 17.7.2.5.1—Modification factor where analysis indicates cracking at service load levels,

Condition	$\psi_{c,v}$
Anchors without supplementary reinforcement or with edge reinforcement smaller than a No. 4 bar	1.0
Anchors with reinforcement of at least a No. 4 bar or greater between the anchor and the edge	1.2
Anchors with reinforcement of at least a No. 4 bar or greater between the anchor and the edge, and with the reinforcement enclosed within stirrups spaced at not more than 4 in.	1.4

17.7.2.6 Breakout thickness factor, $\psi_{h,v}$

17.7.2.6.1 Modification factor for anchors located in a concrete member where $h_a < 1.5c_{a1}$, $\psi_{h,v}$ shall be calculated by Eq. (17.7.2.6.1)

$$\psi_{h,v} = \sqrt{\frac{1.5c_{a1}}{h_a}} \geq 1.0 \quad (17.7.2.6.1)$$

17.7.3 Concrete pryout strength of anchors in shear, V_{cp} or V_{cpg}

17.7.3.1 Nominal pryout strength, V_{cp} of a single anchor or V_{cpg} of an anchor group satisfying 17.5.1.3.1, shall not exceed (a) or (b), respectively.

(a) For a single anchor

$$V_{cp} = k_{cp}N_{cp} \quad (17.7.3.1a)$$

(b) For an anchor group

$$V_{cpg} = k_{cp}N_{cpg} \quad (17.7.3.1b)$$

where

$$k_{cp} = 1.0 \text{ for } h_{ef} < 2.5 \text{ in.}$$

$$k_{cp} = 2.0 \text{ for } h_{ef} \geq 2.5 \text{ in.}$$

17.7.3.1.1 For cast-in anchors and post-installed expansion, screw, and undercut anchors, N_{cp} shall be taken as N_{cb} calculated by Eq. (17.6.2.1a), and for adhesive anchors, N_{cp} shall be the lesser of N_a calculated by Eq. (17.6.5.1a) and N_{cb} calculated by Eq. (17.6.2.1a).

17.7.3.1.2 For cast-in anchors and post-installed expansion, screw, and undercut anchors, N_{cpg} shall be taken as N_{cbg} calculated by Eq. (17.6.2.1b), and for adhesive anchors, N_{cpg} shall be the lesser of N_{ag} calculated by Eq. (17.6.5.1b) and N_{cbg} calculated by Eq. (17.6.2.1b).

COMMENTARY

R17.7.2.6 Breakout thickness factor, $\psi_{h,v}$

R17.7.2.6.1 For anchors located in a concrete member where $h_a < 1.5c_{a1}$, tests (fib 2011; Eligehausen et al. 2006b) have shown that the concrete breakout strength in shear is not directly proportional to the member thickness h_a . The factor $\psi_{h,v}$ accounts for this effect.

R17.7.3 Concrete pryout strength of anchors in shear, V_{cp} or V_{cpg}

R17.7.3.1 Fuchs et al. (1995) indicates that the pryout shear resistance can be approximated as one to two times the anchor tensile resistance with the lower value appropriate for h_{ef} less than 2.5 in. Because it is possible that the bond strength of adhesive anchors could be less than the concrete breakout strength, it is necessary to consider both 17.6.2.1 and 17.6.5.1 to calculate pryout strength.

CODE

17.8—Tension and shear interaction

17.8.1 Unless tension and shear interaction effects are considered in accordance with 17.5.2.3, a single anchor resisting both tension and shear shall satisfy 17.8.2 and 17.8.4, and anchor groups shall satisfy 17.8.3 and 17.8.4. The value of ϕ shall correspond to the governing failure mode in accordance with 17.5.3.

COMMENTARY

R17.8—Tension and shear interaction

R17.8.1 The tension-shear interaction expression has traditionally been expressed as

$$\left(\frac{N_{ua}}{N_n}\right)^{\zeta} + \left(\frac{V_{ua}}{V_n}\right)^{\zeta} \leq 1.0$$

where ζ varies from 1 to 2. The use of $\zeta = 5/3$ for concrete failure modes has been the basis of the Code for several editions. The use of $\zeta = 2$ for steel failure modes in bolts is in accordance with long-standing practice (Chesson et al. 1965). Interaction is checked for both concrete and steel failure modes independently as shown in Fig. R17.8.1. Previous versions of these provisions provided a trilinear expression for checking interaction, regardless of failure mode. This has been replaced by a less conservative approach.

Any other interaction expression that is verified by test data can be used to satisfy 17.5.2.3.




Fig. R17.8.1—Shear and tensile load interaction equation (single anchor case).

17.8.2 Single anchor concrete strength

For a single anchor satisfying the strength requirements of Table 17.5.2, interaction between tension and shear shall satisfy Eq. (17.8.2).

$$\left(\frac{N_{ua}}{\phi N_{n,c}}\right)^{\frac{5}{3}} + \left(\frac{V_{ua}}{\phi V_{n,c}}\right)^{\frac{5}{3}} \leq 1 \quad (17.8.2)$$

where $\phi N_{n,c}$ and $\phi V_{n,c}$ represent the minimum calculated strength in accordance with Table 17.5.2 as follows:

$\phi N_{n,c}$ = the least of ϕN_{cb} , ϕN_a , ϕN_{pn} , and ϕN_{sb} , lb

$\phi V_{n,c}$ = the lesser of ϕV_{cb} and ϕV_{cp} , lb

CODE

17.8.3 Anchor group concrete strength

For an anchor group satisfying the strength requirements of Table 17.5.2, interaction between tension and shear shall satisfy Eq. (17.8.3).

$$\left(\frac{N_{ua,g}}{\phi N_{n,cg}}\right)^{\frac{5}{3}} + \left(\frac{V_{ua,g}}{\phi V_{n,cg}}\right)^{\frac{5}{3}} \leq 1 \quad (17.8.3)$$

where $\phi N_{n,cg}$ and $\phi V_{n,cg}$ represent the minimum calculated strength in accordance with Table 17.5.2 as follows:

$\phi N_{n,cg}$ = the least of ϕN_{cbg} , ϕN_{ag} , and ϕN_{sbg} , lb

$\phi V_{n,cg}$ = the lesser of ϕV_{cbg} and ϕV_{cpg} , lb

17.8.4 Single anchor or anchor group steel strength

For a single anchor or an anchor group satisfying the strength requirements of Table 17.5.2, the most highly stressed anchor in tension and shear shall satisfy Eq. (17.8.4).

$$\left(\frac{N_{ua}}{\phi N_{sa}}\right)^2 + \left(\frac{V_{ua}}{\phi V_{sa}}\right)^2 \leq 1 \quad (17.8.4)$$

17.9—Edge distances, spacings, and thicknesses to preclude splitting failure

17.9.1 Minimum spacings and edge distances for anchors and minimum thicknesses of members shall conform to this section, unless supplementary reinforcement is provided to control splitting. Lesser values from product-specific tests performed in accordance with **ACI CODE-355.2** or **ACI CODE-355.4** shall be permitted.

17.9.2 Unless determined in accordance with 17.9.3, minimum spacing parameters shall conform to Table 17.9.2(a).

COMMENTARY

R17.8.4 Single anchor or anchor group steel strength

The interaction check for steel is intended for the shaft of the anchor (anchor bolt, cast-in headed stud, threaded rod, screw). It is not intended for shear lugs.

R17.9—Edge distances, spacings, and thicknesses to preclude splitting failure

R17.9.1 Minimum spacings, edge distances, and thicknesses are dependent on the anchor characteristics. Installation forces and torques in post-installed anchors can cause splitting of the surrounding concrete. Such splitting also can be produced in subsequent torquing during connection of attachments to anchors including cast-in anchors. The primary source of values for minimum spacings, edge distances, and thicknesses of post-installed anchors should be the product-specific tests of **ACI CODE-355.2** and **ACI CODE-355.4**. In some cases, however, specific products are not known in the design stage. Approximate values are provided for use in design.

R17.9.2 Edge cover for anchors with deep embedments can have a significant effect on the side face blowout strength provided in 17.6.4. It is therefore advantageous to increase edge cover beyond that required in **20.5.1.3** to increase side-face blowout strength.

Drilling holes for post-installed anchors can cause microcracking. The requirement for edge distance to be at least twice the nominal maximum aggregate size is to reduce effects of such microcracking.

CODE

COMMENTARY

Table 17.9.2(a)—Minimum spacing and edge distance requirements

Spacing parameter	Anchor type			
	Cast-in anchors		Post-installed	
	Not torqued	Torqued	Adhesive, expansion, and undercut anchors	Screw anchors
Minimum anchor spacing	$4d_a$	$6d_a$	$6d_a$	Greater of $0.6h_{ef}$ and $6d_a$
Minimum edge distance	Specified cover requirements for reinforcement according to 20.5.1.3	$6d_a$	Greatest of (a), (b), and (c): (a) Specified cover requirements for reinforcement according to 20.5.1.3 (b) Twice the nominal maximum aggregate size (c) Minimum edge distance requirements according to ACI CODE-355.2 or ACI CODE-355.4, or Table 17.9.2(b) when product information is absent	

Table 17.9.2(b)—Minimum edge distance in absence of product-specific ACI CODE-355.2 or ACI CODE-355.4 test information

Post-installed anchor type	Minimum edge distance
Torque-controlled	$8d_a$
Displacement-controlled	$10d_a$
Screw	$6d_a$
Undercut	$6d_a$
Adhesive	$6d_a$

17.9.3 For anchors where installation does not produce a splitting force and that will not be torqued, if the edge distance or spacing is less than those given in 17.9.2, calculations shall be performed by substituting for d_a a lesser value d_a' that meets the requirements of 17.9.2. Calculated forces applied to the anchor shall be limited to the values corresponding to an anchor having a diameter of d_a' .

17.9.4 Value of h_{ef} for a post-installed expansion, screw, or undercut post-installed anchor shall not exceed the greater of two-thirds of the member thickness, h_a , and the member thickness minus 4 in., unless determined from tests in accordance with **ACI CODE-355.2**.

R17.9.3 In some cases, it may be desirable to use a larger-diameter anchor than the requirements of 17.9.2 permit. In these cases, it is permissible to use a larger-diameter anchor, provided the design strength of the anchor is based on a smaller assumed anchor diameter d_a' .

R17.9.4 Splitting failures are caused by load transfer between the bolt and the concrete. The limitations on the value of h_{ef} do not apply to cast-in and adhesive anchors because the splitting forces associated with these anchor types are less than for expansion, screw, and undercut anchors.

For all post-installed anchors, the embedment depth for a given member thickness should be limited to avoid back-face blowout on the opposite side of the concrete member during hole drilling and anchor setting. This depth limit is dependent on many variables, including anchor type, drilling method, drilling technique, type and size of drilling equipment, presence of reinforcement, and strength and condition of the concrete.

CODE

17.9.5 Critical edge distance c_{ac} shall be in accordance with Table 17.9.5 unless determined from tension tests in accordance with **ACI CODE-355.2** or **ACI CODE-355.4**.

Table 17.9.5—Critical edge distance

Post-installed anchor type	Critical edge distance c_{ac}
Torque-controlled	$4h_{ef}$
Displacement-controlled	$4h_{ef}$
Screw	$4h_{ef}$
Undercut	$2.5h_{ef}$
Adhesive	$2h_{ef}$

17.10—Earthquake-resistant anchor design requirements

17.10.1 Anchors in structures assigned to Seismic Design Category (SDC) C, D, E, or F shall satisfy the additional requirements of this section.

COMMENTARY

R17.9.5 The critical edge distance c_{ac} is required for design of post-installed anchors for use in uncracked concrete where no supplemental reinforcement is available to restrain splitting cracks. To permit the design of these types of anchors if product-specific information is not available, conservative default values for c_{ac} are provided. Alternately, product-specific values of c_{ac} may be determined in accordance with ACI CODE-355.2 or ACI CODE-355.4. Corner-test requirements in the aforementioned qualification standards may not be satisfied with $c_{a,min} = 1.5h_{ef}$ for many expansion, screw, undercut, and adhesive anchors due to tensile and flexural stresses associated with anchor installation and loading, which may result in a premature splitting failure.

R17.10—Earthquake-resistant anchor design requirements

R17.10.1 Unless 17.10.5.1 or 17.10.6.1 apply, all anchors in structures assigned to Seismic Design Categories (SDC) C, D, E, or F are required to satisfy the additional requirements of 17.10.2 through 17.10.7, regardless of whether earthquake-induced forces are included in the controlling load combination for the anchor design. In addition, all post-installed anchors in structures assigned to SDC C, D, E, or F must meet the requirements of ACI CODE-355.2 or ACI CODE-355.4 for prequalification of anchors to resist earthquake-induced forces. Ideally, for tension, anchor strength should be governed by yielding of the ductile steel element of the anchor. If the anchor cannot meet the specified ductility requirements of 17.10.5.3(a), then the attachment should be designed to yield if it is structural or light gauge steel, or designed to crush if it is wood. If ductility requirements of 17.10.5.3(a) are satisfied, then any attachments to the anchor should be designed not to yield. In designing attachments using yield mechanisms to provide adequate ductility, as permitted by 17.10.5.3(b) and 17.10.6.3(a), the ratio of specified yield strength to expected strength for the material of the attachment should be considered in determining the design force. The value used for the expected strength should consider both material overstrength and strain hardening effects. For example, the material in a connection element could yield and, due to an increase in its strength with strain hardening, cause a secondary failure of a sub-element or place extra force or deformation demands on the anchors. For a structural steel attachment, if only the specified yield strength of the steel is known, the expected strength should be taken as approximately 1.5 times the specified yield strength. If the actual yield strength of the steel is known, the expected strength should be taken as approximately 1.25 times the actual yield strength.

Under earthquake conditions, the direction of shear may not be predictable. The full shear should be assumed in any direction for a safe design.

CODE

17.10.2 Provisions of this chapter shall not apply to the design of anchors in plastic hinge zones of concrete structures resisting earthquake-induced forces.

17.10.3 Post-installed anchors shall be qualified for earthquake-induced forces in accordance with **ACI CODE-355.2** or **ACI CODE-355.4**. The pullout strength, N_p , and steel strength in shear, V_{sa} , of post-installed expansion, screw, and undercut anchors shall be based on the results of the ACI CODE-355.2 Simulated Seismic Tests. For adhesive anchors, the steel strength in shear, V_{sa} , and the characteristic bond stresses, τ_{uncr} and τ_{cr} , shall be based on results of the ACI CODE-355.4 Simulated Seismic Tests.

17.10.4 Anchor reinforcement used in structures assigned to SDC C, D, E, or F shall be deformed reinforcement and shall be in accordance with the anchor reinforcement requirements of **20.2.2**.

17.10.5 Tensile loading design requirements

17.10.5.1 If the tensile component of the strength-level earthquake-induced force applied to a single anchor or anchor group does not exceed 20% of the total factored anchor tensile force associated with the same load combination, it shall be permitted to design a single anchor or anchor group in accordance with 17.6 and the tensile strength requirements of Table 17.5.2.

17.10.5.2 If the tensile component of the strength-level earthquake-induced force applied to anchors exceeds 20% of the total factored anchor tensile force associated with the same load combination, anchors and their attachments shall be designed in accordance with 17.10.5.3. The anchor design tensile strength shall be determined in accordance with 17.10.5.4.

COMMENTARY

R17.10.2 The possible higher levels of cracking and spalling in plastic hinge zones are beyond the conditions for which the nominal concrete-governed strength values in this chapter are applicable. Plastic hinge zones are considered to extend a distance equal to twice the member depth from any column or beam face, and also include any other sections in walls, frames, and slabs where yielding of reinforcement is likely to occur as a result of lateral displacements.

If anchors must be located in plastic hinge regions, they should be detailed so that the anchor forces are transferred directly to anchor reinforcement that is designed to transmit the anchor forces into the body of the member beyond the anchorage region. Configurations that rely on concrete tensile strength should not be used.

R17.10.3 Anchors that are not suitable for use in cracked concrete should not be used to resist earthquake-induced forces. Qualification of post-installed anchors for use in cracked concrete is an integral part of the qualification for resisting earthquake-induced forces in ACI CODE-355.2 and ACI CODE-355.4. The design values obtained from the Simulated Seismic Tests of ACI CODE-355.2 and ACI CODE-355.4 are expected to be less than those for static load applications.

R17.10.5 Tensile loading design requirements

R17.10.5.1 The requirements of 17.10.5.3 need not apply if the applied earthquake-induced tensile force is a small fraction of the total factored tensile force.

R17.10.5.2 If the ductile steel element is **ASTM A36** or **ASTM A307** steel, the f_{uta}/f_{ya} value is typically approximately 1.5, and the anchor can stretch considerably before rupturing at the threads. For other steels, calculations may need to be made to ensure that similar behavior can occur. Section R17.6.1.2 provides additional information on the steel properties of anchors. Use of upset threaded ends, whereby the threaded end of the anchor is enlarged to compensate for the area reduction associated with threading, can ensure that yielding occurs over the stretch length regardless of the tensile to yield strength ratio.

CODE

17.10.5.3 Anchors and their attachments shall satisfy (a), (b), (c), or (d).

(a) For single anchors, the concrete-governed strength shall be greater than the steel strength of the anchor. For anchor groups, the ratio of the tensile load on the most highly stressed anchor to the steel strength of that anchor shall be equal to or greater than the ratio of the tensile load on anchors loaded in tension to the concrete-governed strength of those anchors. In each case:

- (i) The steel strength shall be taken as 1.2 times the nominal steel strength of the anchor.
- (ii) The concrete-governed strength shall be taken as the nominal strength considering pullout, side-face blowout, concrete breakout, and bond strength as applicable. For consideration of pullout in groups, the ratio shall be calculated for the most highly stressed anchor.

In addition, the following shall be satisfied:

- (iii) Anchors shall transmit tensile loads via a ductile steel element with a stretch length of at least $8d_a$ unless otherwise determined by analysis.
- (iv) Anchors that resist load reversals shall be protected against buckling.
- (v) If connections are threaded and the ductile steel elements are not threaded over their entire length, the ratio of f_{ua}/f_{ya} shall be at least 1.3 unless the threaded portions are upset. The upset portions shall not be included in the stretch length.
- (vi) Deformed reinforcing bars used as ductile steel elements to resist earthquake-induced forces shall be in accordance with the anchor reinforcement requirements of 20.2.2.

(b) Anchor or anchor groups shall be designed for the maximum tension that can be transmitted to the anchor or group of anchors based on the development of a ductile yield mechanism in the attachment in tension, flexure, shear, or bearing, or a combination of those conditions, considering both material overstrength and strain-hardening effects for the attachment. The anchor design tensile strength shall be calculated in accordance with 17.10.5.4.

(c) Anchor or anchor groups shall be designed for the maximum tension that can be transmitted to the anchors by a non-yielding attachment. The anchor design tensile strength shall be calculated in accordance with 17.10.5.4.

(d) Anchor or anchor groups shall be designed for the maximum tension obtained from factored load combinations that include E , with E_h increased by Ω_o . The anchor design tensile strength shall be calculated in accordance with 17.10.5.4.

COMMENTARY

R17.10.5.3 Four options are provided for determining the required anchor or attachment strength to protect against nonductile tensile failure:

In option (a), anchor ductility requirements are imposed, and the required anchor strength is that determined using strength-level earthquake-induced forces acting on the structure. Research (Hoehler and Eligehausen 2008; Vintzileou and Eligehausen 1992) has shown that if the steel of the anchor yields before the concrete anchorage fails, no reduction in the anchor tensile strength is needed for earthquake-induced forces. Ductile steel anchors should satisfy the definition for steel element, ductile in Chapter 2. To facilitate comparison between steel strength, which is based on the most highly-stressed anchor, and concrete strength based on group behavior, the design is performed on the basis of the ratio of applied load to strength for the steel and concrete, respectively.

For some structures, anchors provide the best locations for energy dissipation in the nonlinear range of response. The stretch length of the anchor, shown in Fig. R17.10.5.3, affects the lateral displacement capacity of the structure; therefore, that length needs to be sufficient such that the displacement associated with the design-basis earthquake can be achieved (FEMA P-750). Observations from earthquakes indicate that the provision of a stretch length of $8d_a$ results in good structural performance. If the required stretch length is calculated, the relative stiffness of the connected elements needs to be considered. When an anchor is subject to load reversals, and its yielding length outside the concrete exceeds $6d_a$, buckling of the anchor in compression is likely. Buckling can be restrained by placing the anchor in a tube. However, care must be taken that the tube does not share in resisting the tensile load assumed to act on the anchor. For anchor bolts that are not threaded over their length, it is important to ensure that yielding occurs over the unthreaded portion of the bolt within the stretch length before failure in the threads. This is accomplished by maintaining sufficient margin between the specified yield and tensile strengths of the bolt. It should be noted that the available stretch length may be adversely influenced by construction techniques (for example, the addition of leveling nuts to the examples illustrated in Fig. R17.10.5.3).

In option (b), the anchor is designed for the tensile force associated with the expected strength of the attachment. Care must be taken in design to consider the consequences of potential differences between the specified yield strength and the expected strength of the attachment. An example is the design of connections of intermediate precast walls where a connection not designed to yield should develop at least $1.5S_y$, where S_y is the nominal strength of the yielding element based on its specified yield strength (refer to 18.5.2.2). Similarly, steel design manuals require structural steel connections that are designated nonyielding and part of the seismic load path to have design strengths that exceed a multiple of the nominal strength. That multiple depends on a factor relating the likely actual to specified yield strength

CODE

COMMENTARY

of the material and an additional factor exceeding unity to account for material strain hardening. For attachments of cold-formed steel or wood, similar principles should be used to determine the expected strength of the attachment in order to determine the required strength of the anchors.

Additional guidance on the use of options (a) through (d) is provided in the 2009 edition of the NEHRP Recommended Seismic Provisions for New Buildings and Other Structures (**FEMA P-750**). The design of anchors in accordance with option (a) should be used only if the anchor yield behavior is well defined and if the interaction of the yielding anchor with other elements in the load path has been adequately addressed. For the design of anchors in accordance with option (b), the force associated with yield of a steel attachment, such as an angle, baseplate, or web tab, should be the expected strength rather than the specified yield strength of the steel. Option (c) may apply to cases, such as the design of sill bolts where crushing of the wood limits the force that can be transferred to the bolt, or where the provisions of the American National Standards Institute/American Institute of Steel Construction (AISC) Code Seismic Provisions for Structural Steel Buildings (**ANSI/AISC 341**) specify design loads based on member strengths.




Fig. R17.10.5.3—Illustrations of stretch length.

17.10.5.4 The anchor design tensile strength shall be calculated from (a) through (e) for the failure modes given in Table 17.5.2 assuming the concrete is cracked unless it can be demonstrated that the concrete remains uncracked.

- (a) ϕN_{sa} for a single anchor, or for the most highly stressed individual anchor in an anchor group
- (b) $0.75\phi N_{cb}$ or $0.75\phi N_{cbg}$, except that N_{cb} or N_{cbg} need not be calculated if anchor reinforcement satisfying 17.5.2.1(a) is provided
- (c) $0.75\phi N_{pn}$ for a single anchor or for the most highly stressed individual anchor in an anchor group
- (d) $0.75\phi N_{sb}$ or $0.75\phi N_{sbg}$

R17.10.5.4 The reduced anchor nominal tensile strengths associated with concrete failure modes is to account for increased cracking and spalling in the concrete resulting from earthquake effects. Because earthquake-resistant design generally assumes that all or portions of the structure are loaded beyond yield, it is likely that the concrete is cracked throughout for the purpose of calculating anchor strength. In locations where it can be demonstrated that the concrete does not crack, uncracked concrete may be assumed in calculating anchor strength as governed by concrete failure modes.

CODE

(e) $0.75\phi N_a$ or $0.75\phi N_{ag}$
 where ϕ is in accordance with 17.5.3.

17.10.5.5 If anchor reinforcement is provided in accordance with 17.5.2.1(a), no reduction in design tensile strength beyond that given in Table 21.2.1 for anchor reinforcement shall be required.

17.10.6 Shear design requirements

17.10.6.1 If the shear component of the strength-level earthquake-induced force applied to a single anchor or anchor group does not exceed 20 percent of the total factored anchor shear associated with the same load combination, it shall be permitted to design a single anchor or anchor group in accordance with 17.7 and the shear strength requirements of 17.5.2.

17.10.6.2 If the shear component of the strength-level earthquake-induced force applied to anchors exceeds 20% of the total factored anchor shear associated with the same load combination, anchors and their attachments shall be designed in accordance with 17.10.6.3. The anchor design shear strength for resisting earthquake-induced forces shall be determined in accordance with 17.7.

17.10.6.3 Anchors and their attachments shall satisfy (a), (b) or (c).

- (a) Anchor or anchor groups shall be designed for the maximum shear that can be transmitted to the anchor or anchor groups based on the development of a ductile yield mechanism in the attachment in tension, flexure, shear, or bearing, or a combination of those conditions, and considering both material overstrength and strain-hardening effects in the attachment.
- (b) Anchor or anchor groups shall be designed for the maximum shear that can be transmitted to the anchors by a non-yielding attachment.
- (c) Anchor or anchor groups shall be designed for the maximum shear obtained from factored load combinations that include E , with E_n increased by Ω_o .

COMMENTARY

R17.10.5.5 If anchor reinforcement conforming to 17.5.2.1(a) is provided, the strength of the connection is assumed to be controlled by yielding of the anchor reinforcement and not concrete breakout, and the factor ϕ applied to this case is given in Table 21.2.1.

R17.10.6 Shear design requirements

R17.10.6.1 The requirements of 17.10.6.3 need not apply if the applied earthquake-induced shear is a small fraction of the total factored shear.

R17.10.6.2 If the shear component of the earthquake-induced force applied to the anchor exceeds 20% of the total anchor shear force, three options are recognized to determine the required shear strength to protect the anchor or anchor group against premature shear failure.

R17.10.6.3 Option (a) of 17.10.5.3 is not permitted for shear because the cross section of the steel element of the anchor cannot be configured so that steel failure in shear provides any meaningful degree of ductility.

Design of the anchor or anchor group for the strength associated with force-limiting mechanisms under option (b), such as the bearing strength at holes in a steel attachment or the combined crushing and bearing strength for wood members, may be particularly relevant. Tests on typical anchor bolt connections for wood-framed structural walls (Fennel et al. 2009) demonstrated that wood components attached to concrete with minimum edge distances exhibited ductile behavior. Wood “yield” (crushing) was the first limiting state and resulted in nail slippage in shear. Nail slippage combined with bolt bending provided the required ductility and toughness for the structural walls and limited the loads acting on the bolts. Procedures for defining bearing and shear limit states for connections to cold-formed steel are described in [AISI S100](#), and examples of strength calculations are provided in the AISI manual ([AISI D100](#)). In such cases, exceeding the bearing strength may lead to tearing and an unacceptable loss of connectivity. If anchors are located far from edges, it may not be possible to design such that anchor reinforcement controls the anchor strength. In such cases, anchors should be designed for overstrength in accordance with option (c).

CODE**17.10.7 Tension and shear interaction**

17.10.7.1 Single anchors or anchor groups that resist both tensile and shear forces shall be designed in accordance with 17.8, and the anchor design tensile strength calculated in accordance with 17.10.5.4.

17.11—Attachments with shear lugs**17.11.1 General**

17.11.1.1 It is permitted to design attachments with shear lugs in accordance with 17.11.1.1.1 through 17.11.1.1.9. Alternatively, it is permitted to design using alternative methods if adequate strength and load transfer can be demonstrated by analysis or tests.

COMMENTARY**R17.11—Attachments with shear lugs****R17.11.1 General**

R17.11.1.1 The provisions of 17.11 cover concrete failure modes of attachments with shear lugs. These provisions do not cover the steel or welding design of the attachment base plate or shear lugs.

Attachments with shear lugs may be embedded in cast-in-place or precast concrete, or post-installed by using a blockout in the concrete that receives the shear lug and is then filled with a fluid, non-shrink grout as shown in Fig. R17.11.1.1a. Base plates with anchors provide moment resistance, which prevents pryout action on the shear lugs. Attachments with embedded shapes and without base plates and anchors, which must resist moment by pryout action on the embedment, are not covered in this section.

Bearing strength in shear refers to the strength prior to concrete fracture in front of the shear lug. Bearing failure occurs at small displacements (Cook and Michler 2017). Following bearing failure, there is a significant decrease in strength and increase in lateral displacement leading eventually to steel failure of the anchors (Fig. R17.11.1.1b) at lateral displacements at least an order of magnitude greater than that corresponding to bearing failure.

Types of attachments with shear lugs that satisfy 17.11.1.1.1 through 17.11.1.1.9 are shown in Fig. R17.11.1.1a. Shear lugs that are different than those covered in 17.11.1.1.1 through 17.11.1.1.9, such as shear lugs composed of steel pipe or attachments with shear lugs where the top of plate is located below the concrete surface, can be used provided adequate strength and load transfer can be demonstrated by analysis or tests.

CODE

COMMENTARY





Fig. R17.11.1.1a—Examples of attachments with shear lugs.



(a) Just prior to bearing failure




Fig. R17.11.1.1b—Bearing failure and subsequent anchor steel failure for embedded plate with shear lug (if concrete breakout is not applicable).

CODE

COMMENTARY

17.11.1.1.1 Shear lugs shall be constructed of rectangular plates, or steel shapes composed of plate-like elements, welded to an attachment base plate.

17.11.1.1.2 A minimum of four anchors shall be provided that satisfy the requirements of Chapter 17 with the exception of the requirements of 17.5.1.3(f), (g), and (h) and the corresponding requirements of Table 17.5.2 for steel strength of anchors in shear, concrete breakout strength of anchors in shear, and concrete pryout strength of anchors in shear.

17.11.1.1.3 For anchors welded to the attachment base plate, tension and shear interaction requirements of 17.8 shall include a portion of the total shear on the anchor.

R17.11.1.1.3 Although neglected in the bearing strength evaluation in 17.11.2, welded anchors resist a portion of the shear load because they displace the same as the shear lug. The portion of the applied shear, V_u , that each anchor carries, $V_{ua,i}$, is given by

$$V_{ua,i} = V_u \left(\frac{2d_a^2}{A_{ef,sl} + n2d_a^2} \right)$$

The effective bearing area of an anchor is assumed to be the diameter of the anchor multiplied by an effective bearing depth of twice its diameter (Cook and Michler 2017). The bearing reaction on the anchor is not large enough to fail the anchor in shear alone but does need to be considered in tension and shear interaction for steel failure (refer to 17.8).

17.11.1.1.4 Bearing strength in shear shall satisfy $\phi V_{brg,sl} \geq V_u$ with $\phi = 0.65$.

17.11.1.1.5 Nominal bearing strength in shear, $V_{brg,sl}$, shall be determined by 17.11.2.

17.11.1.1.6 Concrete breakout strength of the shear lug shall satisfy $\phi V_{cb,sl} \geq V_u$ with $\phi = 0.65$.

17.11.1.1.7 Nominal concrete breakout strength, $V_{cb,sl}$, shall be determined by 17.11.3.

17.11.1.1.8 For attachments with anchors in tension, both (a) and (b) shall be satisfied:

- (a) $h_{ef}/h_{sl} \geq 2.5$
- (b) $h_{ef}/c_{sl} \geq 2.5$

17.11.1.1.9 The moment from the couple developed by the bearing reaction on the shear lug and the shear shall be considered in the design of the anchors for tension.

R17.11.1.1.8 The lower bound limitations on the ratios of anchor embedment depth to shear lug embedment depth and anchor embedment depth to the distance between the centerline of the anchors in tension and the centerline of the shear lug in the direction of shear are based on available test data. The required lower limits reduce potential interaction between concrete breakout of the anchors in tension and bearing failure in shear of the shear lug.

R17.11.1.1.9 The bearing reaction on shear lugs occurs further below the surface of the concrete than the bearing reaction on anchors and embedded plates. As a result, the couple caused by the bearing reaction and the shear load needs to be considered when determining anchor tension.

CODE

17.11.1.2 Horizontally installed steel base plates with shear lugs shall have a minimum 1 in. diameter hole along each of the long sides of the shear lug.

17.11.2 Bearing strength in shear of attachments with shear lugs, $V_{brg,sl}$

17.11.2.1 Nominal bearing strength in shear of a shear lug, $V_{brg,sl}$ shall be calculated as:

$$V_{brg,sl} = 1.7f_c' A_{ef,sl} \psi_{brg,sl} \quad (17.11.2.1)$$

where $\psi_{brg,sl}$ is given in 17.11.2.2.

17.11.2.1.1 The effective bearing area, $A_{ef,sl}$ shall be below the surface of the concrete, perpendicular to the applied shear, and composed of areas according to (a) through (d):

- (a) Bearing area of shear lugs located within $2t_{sl}$ of the bottom surface of the base plate if the top or bottom surface of the base plate is flush with the surface of the concrete
- (b) Bearing area of shear lugs located within $2t_{sl}$ of the surface of the concrete if the base plate is above the surface of the concrete
- (c) Bearing area of shear lugs located within $2t_{sl}$ of the interface with stiffeners
- (d) Bearing area on the leading edge of stiffeners below the surface of the concrete

COMMENTARY


R17.11.1.2 Base plate holes are necessary to verify proper concrete or grout consolidation around the shear lug and to avoid trapping air immediately below a horizontal plate. Holes in the base plate should be placed close to each face of the shear lug. For a single shear lug, place at least one inspection hole near the center of each long side of the shear lug. For a cruciform-shaped shear lug, four inspection holes are recommended, one per quadrant. For other configurations or long shear lug lengths, the licensed design professional should specify inspection hole locations that will permit adequate observation and allow trapped air to escape.

R17.11.2 Bearing strength in shear of attachments with shear lugs, $V_{brg,sl}$


R17.11.2.1 The nominal bearing strength in shear of a shear lug, $V_{brg,sl}$ given by Eq. (17.11.2.1) is based on a uniform bearing stress of $1.7f_c'$ acting over the effective area of the shear lug as discussed in **Cook and Michler (2017)**. Although the bearing strength in shear of attachments with shear lugs is a function of bearing on the shear lug, embedded plate (if present), and welded anchors (if present), the method presented in 17.11.2 only includes the contribution of shear lugs. Cook and Michler (2017) discuss development of the method and a less conservative procedure to include bearing on the embedded plate and welded anchors.

R17.11.2.1.1 Figure R17.11.2.1.1 shows examples of effective bearing areas. The effective bearing area for stiffened shear lugs is applicable to both welded plates and steel shapes composed of plate-like elements in which case the web would be the stiffening element. The limit of a distance of $2t_{sl}$ in determining the effective bearing area is described in Cook and Michler (2017).

CODE



COMMENTARY



Note: Anchors and inspection holes not shown.

Fig. R17.11.2.1.1—Examples of effective bearing areas for attachments with shear lugs.

17.11.2.2 Bearing factor, $\psi_{brg,sl}$

17.11.2.2.1 Modification factor, $\psi_{brg,sl}$, for the effects of axial load, P_u , on bearing strength in shear, shall be determined by (a), (b), or (c):

(a) For applied axial tension:

$$\psi_{brg,sl} = 1 + \frac{P_u}{nN_{sa}} \leq 1.0 \quad (17.11.2.2.1a)$$

where P_u is negative for tension and n is the number of anchors in tension.

(b) For no applied axial load:

$$\psi_{brg,sl} = 1 \quad (17.11.2.2.1b)$$

(c) For applied axial compression:

$$\psi_{brg,sl} = 1 + 4 \frac{P_u}{A_{bp}f'_c} \leq 2.0 \quad (17.11.2.2.1c)$$

where P_u is positive for compression.

CODE

17.11.2.3 If used, the length of shear lug stiffeners in the direction of the shear load shall not be less than $0.5h_{sl}$.

17.11.2.4 For attachments with multiple shear lugs arranged perpendicular to the direction of applied shear, the bearing strength of the individual shear lugs may be considered to be additive provided the shear stress on a shear plane in the concrete at the bottom of the shear lugs, and extending between the shear lugs, does not exceed $0.2f'_c$. The nominal bearing strength of each individual lug shall be determined by Eq. (17.11.2.1) using the effective area of the lug.

17.11.3 Concrete breakout strength of shear lug, $V_{cb,sl}$

17.11.3.1 Nominal concrete breakout strength of a shear lug for shear perpendicular to the edge, $V_{cb,sl}$, shall be determined from 17.7.2 using Eq. (17.7.2.1a), where V_b is calculated using Eq. (17.7.2.2.1b) with c_{a1} taken as the distance from the bearing surface of the shear lug to the free edge and where A_{Vc} is the projected area of the failure surface on the side of the concrete member.

COMMENTARY

R17.11.2.4 The limitation for considering multiple shear lugs to be effective is based on the maximum limits for shear friction in Table 22.9.4.4 and two tests reported in **Rotz and Reifschneider (1984)**. The area of the shear plane is the clear distance between adjacent shear lugs measured in the direction of the applied shear multiplied by the width of the shear lugs perpendicular to the applied shear.

R17.11.3 Concrete breakout strength of shear lug, $V_{cb,sl}$

R17.11.3.1 The method for evaluating concrete breakout strength where shear is perpendicular to an edge is similar to that used in 17.7.2 for anchors. The difference is in the determination of A_{Vc} , which is illustrated in Fig. R17.11.3.1. The method has been confirmed by tests where the shear lug is concentrically loaded in shear (**Gomez et al. 2009; Cook and Michler 2017**). With shear transferred by the shear lug, embedded plate (if present), and welded anchors (if present), the bearing surfaces all displace the same amount with any incremental change in applied shear. This behavior is similar to connections with anchors welded to steel attachments where concrete edge failure originates from the row of anchors farthest from the edge. In anchorages with shear lugs, the effective contributions to concrete breakout strength from the bearing areas of the shear lug and embedded plate (if present) dominate over the contribution from the effective bearing area of anchors farther from the edge than the shear lug. As a result, concrete breakout strength for the anchorage should be determined based on the concrete breakout surface originating at the shear lug (Fig. R17.11.3.1).

The nominal concrete breakout strength of a shear lug is based on Eq. (17.7.2.2.1b) for V_b that applies to concrete edge failure in shear for large diameter anchors.




Fig. R17.11.3.1—Example of A_{Vc} for a shear lug near an edge.

CODE**COMMENTARY**

17.11.3.1.1 A_{Vc} is the projected concrete failure area on the side face of the concrete that is approximated as the rectangular shape resulting from projecting horizontally $1.5c_{a1}$ from the edge of the shear lug and projecting vertically $1.5c_{a1}$ from the edge of the effective depth of the shear lug, $h_{ef,sl}$. The effective area of the shear lug, $A_{ef,sl}$, shall not be included. The effective embedment depth of the shear lug, h_{ef} , shall be taken as the distance from the concrete surface to the bottom of the effective bearing area, $A_{ef,sl}$.

17.11.3.2 Nominal concrete breakout strength of a shear lug for shear parallel to the edge shall be permitted to be determined in accordance with 17.7.2.1(c) using Eq. (17.7.2.1(a)) with c_{a1} taken as the distance from the edge to the center of the shear lug and with $\psi_{ec,V}$ taken as 1.0.

17.11.3.3 For shear lugs located at a corner, the limiting concrete breakout strength shall be determined for each edge, and the minimum value shall be used.

17.11.3.4 For cases with multiple shear lugs, the concrete breakout strength shall be determined for each potential breakout surface.

R17.11.3.2 The concrete breakout strength for shear lugs loaded parallel to the edge is based on 17.7.2.1(c) for concrete failure with load applied parallel to the free edge, assuming shear lug breakout behavior is similar to that of a single anchor.

R17.11.3.3 The concrete breakout strength for shear lugs located near a corner is based on 17.7.2.1(d) for anchors.

R17.11.3.4 The concrete breakout strength for multiple shear lugs is based on R17.7.2.1 and shown in Fig. R17.7.2.1b Case 1 and Case 2.

CHAPTER 18—EARTHQUAKE-RESISTANT STRUCTURES

CODE	COMMENTARY
------	------------

18.1—Scope

R18.1—Scope

Chapter 18 does not apply to structures assigned to Seismic Design Category (SDC) A. For structures assigned to SDC B and C, Chapter 18 applies to structural systems designated as part of the seismic-force-resisting system. For structures assigned to SDC D through F, Chapter 18 applies to both structural systems designated as part of the seismic-force-resisting system and structural systems not designated as part of the seismic-force-resisting system.

Chapter 18 contains provisions considered to be the minimum requirements for a cast-in-place or precast concrete structure capable of sustaining a series of oscillations into the inelastic range of response without critical deterioration in strength. The integrity of the structure in the inelastic range of response should be maintained because the design earthquake forces defined in documents such as *ASCE/SEI 7*, the *2021 IBC*, the *UBC (ICBO 1997)*, and the *NEHRP (FEMA P-749)* provisions are considered less than those corresponding to linear response at the anticipated earthquake intensity (*FEMA P-749*; *Blume et al. 1961*; *Clough 1960*; *Gulkan and Sozen 1974*).

The design philosophy in Chapter 18 is for cast-in-place concrete structures to respond in the nonlinear range when subjected to design-level ground motions, with decreased stiffness and increased energy dissipation but without critical strength decay. Precast concrete structures designed in accordance with Chapter 18 are intended to emulate cast-in-place construction, except 18.5, 18.9.2.3, and 18.11.2.2, which permit precast construction with alternative yielding mechanisms. The combination of reduced stiffness and increased energy dissipation tends to reduce the response accelerations and lateral inertia forces relative to values that would occur were the structure to remain linearly elastic and lightly damped (*Gulkan and Sozen 1974*). Thus, the use of design forces representing earthquake effects such as those in *ASCE/SEI 7* requires that the seismic-force-resisting system retain a substantial portion of its strength into the inelastic range under displacement reversals.

The provisions of Chapter 18 relate detailing requirements to type of structural framing and SDC. Seismic design categories are adopted directly from *ASCE/SEI 7*, and relate to considerations of seismic hazard level, soil type, occupancy, and use. Before the 2008 Code, low, intermediate, and high seismic risk designations were used to delineate detailing requirements. For a qualitative comparison of seismic design categories and seismic risk designations, refer to Table R5.2.2. The assignment of a structure to a SDC is regulated by the general building code (refer to *4.4.6.1*).

18.1.1 This chapter shall apply to the design of nonprestressed and prestressed concrete structures assigned to Seismic Design Categories (SDC) B through F, including, where applicable:

- (a) Structural systems designated as part of the seismic-force-resisting system, including diaphragms, moment frames, structural walls, and foundations

CODE

(b) Members not designated as part of the seismic-force-resisting system but required to support other loads while undergoing deformations associated with earthquake effects

18.1.2 Structures designed according to the provisions of this chapter are intended to resist earthquake motions through ductile inelastic response of selected members.

18.2—General

COMMENTARY

R18.2—General

Structures assigned to SDC A need not satisfy requirements of Chapter 18 but must satisfy all other applicable requirements of the Code. Structures assigned to Seismic Design Categories B through F must satisfy requirements of Chapter 18 in addition to all other applicable requirements of the Code.

Sections 18.2.1.3 through 18.2.1.5 identify those parts of Chapter 18 that apply to the building based on its assigned SDC, regardless of the vertical elements of the seismic-force-resisting system. **ASCE/SEI 7** defines the permissible vertical elements of the seismic-force-resisting system and applies where adopted. The remaining commentary of R18.2 summarizes the intent of ACI CODE-318 regarding which vertical elements should be permissible in a building considering its SDC. Section 18.2.1.6 defines the requirements for the vertical elements of the seismic-force-resisting system.

The design and detailing requirements should be compatible with the level of inelastic response assumed in the calculation of the design earthquake forces. The terms “ordinary,” “intermediate,” and “special” are used to facilitate this compatibility. For any given structural element or system, the terms “ordinary,” “intermediate,” and “special,” refer to increasing requirements for detailing and proportioning, with expectations of increased deformation capacity. Structures assigned to SDC B are not expected to be subjected to strong ground motion, but instead are expected to experience low levels of ground motion at long time intervals. The Code provides some requirements for beam-column ordinary moment frames to improve deformation capacity.

Structures assigned to SDC C may be subjected to moderately strong ground motion. The designated seismic-force-resisting system typically comprises some combination of ordinary cast-in-place structural walls, intermediate precast structural walls, and intermediate moment frames. The general building code also may contain provisions for use of other seismic-force-resisting systems in SDC C. Provision 18.2.1.6 defines requirements for whatever system is selected.

Structures assigned to SDC D, E, or F may be subjected to strong ground motion. It is the intent of ACI Committee 318 that the seismic-force-resisting system of structural concrete buildings assigned to SDC D, E, or F be provided by special moment frames, special structural walls, and, in limited conditions, intermediate precast walls. In addition to 18.2.2 through 18.2.8, these structures also are required to satisfy applicable requirements for continuous inspection (**26.13.1.3**), diaphragms and trusses (18.12), foundations (18.13), gravity-

CODE**COMMENTARY**

load-resisting elements that are not designated as part of the seismic-force-resisting system (18.14), and regions of the seismic-force-resisting system designed with the strut-and-tie method (23.11). These provisions have been developed to provide the structure with adequate deformation capacity for the high demands expected for these seismic design categories.

The general building code may also permit the use of intermediate moment frames as part of dual systems for some buildings assigned to SDC D, E, or F. It is not the intent of ACI Committee 318 to recommend the use of intermediate moment frames as part of moment-resisting frame or dual systems in SDC D, E, or F. The general building code may also permit substantiated alternative or nonprescriptive designs or, with various supplementary provisions, the use of ordinary or intermediate systems for nonbuilding structures in the higher seismic design categories. These are not the typical applications that were considered in the writing of this chapter, but wherever the term “ordinary or intermediate moment frame” is used in reference to reinforced concrete, 18.3 or 18.4 apply.

Table R18.2 summarizes the applicability of the provisions of Chapter 18 as they are typically applied when using the minimum requirements in the various seismic design categories. Where special systems are used for structures in SDC B or C, it is not required to satisfy the requirements of 18.14, although it should be verified that members not designated as part of the seismic-force-resisting system will be stable under design displacements.

CODE

COMMENTARY

Table R18.2—Sections of Chapter 18 to be satisfied in typical applications^[1]

Component resisting earthquake effect, unless otherwise noted	SDC			
	A (None)	B (18.2.1.3)	C (18.2.1.4)	D, E, F (18.2.1.5)
Analysis and design requirements	None	18.2.2	18.2.2	18.2.2, 18.2.4
Materials		None	None	18.2.5 through 18.2.8
Frame members		18.3	18.4	18.6 through 18.9
Structural walls and coupling beams		None	None	18.10
Precast structural walls		None	18.5	18.5 ^[2] , 18.11
Diaphragms and trusses		None	18.12.1.2	18.12
Foundations		None	18.13	18.13
Frame members not designated as part of the seismic-force-resisting system		None	None	18.14
Anchors		None	18.2.3	18.2.3

^[1]In addition to requirements of Chapters 1 through 17, 19 through 26, and ACI CODE-318.2, except as modified by Chapter 18. Section 14.1.3 also applies in SDC D, E, and F.

^[2]As permitted by the general building code.

The proportioning and detailing requirements in Chapter 18 are based predominantly on field and laboratory experience with monolithic reinforced concrete building structures and precast concrete building structures designed and detailed to behave like monolithic building structures. Extrapolation of these requirements to other types of cast-in-place or precast concrete structures should be based on evidence provided by field experience, tests, or analysis. The acceptance criteria for moment frames given in **ACI CODE-374.1** can be used in conjunction with Chapter 18 to demonstrate that the strength, energy dissipation capacity, and deformation capacity of a proposed frame system equals or exceeds that provided by a comparable monolithic concrete system. **ACI CODE-550.6** provides similar information for precast wall systems.

The toughness requirement in 18.2.1.7 refers to the requirement to maintain structural integrity of the entire seismic-force-resisting system at lateral displacements anticipated for the maximum considered earthquake motion. Depending on the energy-dissipation characteristics of the structural system used, such displacements may be larger than for a monolithic reinforced concrete structure satisfying the prescriptive provisions of other parts of the Code.

CODE

COMMENTARY

18.2.1 Structural systems

18.2.1.1 All structures shall be assigned to a SDC in accordance with 4.4.6.1.

18.2.1.2 All members shall satisfy Chapters 1 to 17 and 19 to 26. Structures assigned to SDC B, C, D, E, or F also shall satisfy 18.2.1.3 through 18.2.1.7, as applicable. Where Chapter 18 conflicts with other chapters of this Code, Chapter 18 shall govern.

18.2.1.3 Structures assigned to SDC B shall satisfy 18.2.2.

18.2.1.4 Structures assigned to SDC C shall satisfy 18.2.2, 18.2.3, 18.12.1.2, and 18.13.

18.2.1.5 Structures assigned to SDC D, E, or F shall satisfy 18.2.2 through 18.2.8, 18.12 through 18.14, and 23.11.

18.2.1.6 Structural systems designated as part of the seismic-force-resisting system shall be restricted to those designated by the general building code, or determined by other authority having jurisdiction in areas without a legally adopted building code. Except for SDC A, for which Chapter 18 does not apply, (a) through (h) shall be satisfied for each structural system designated as part of the seismic-force-resisting system, in addition to 18.2.1.3 through 18.2.1.5:

- (a) Ordinary moment frames shall satisfy 18.3
- (b) Ordinary reinforced concrete structural walls need not satisfy any detailing provisions in Chapter 18, unless required by 18.2.1.3 or 18.2.1.4
- (c) Intermediate moment frames shall satisfy 18.4
- (d) Intermediate precast walls shall satisfy 18.5
- (e) Special moment frames shall satisfy 18.2.3 through 18.2.8 and 18.6 through 18.8
- (f) Special moment frames constructed using precast concrete shall satisfy 18.2.3 through 18.2.8 and 18.9
- (g) Special structural walls shall satisfy 18.2.3 through 18.2.8 and 18.10
- (h) Special structural walls constructed using precast concrete shall satisfy 18.2.3 through 18.2.8 and 18.11

18.2.1.7 A reinforced concrete structural system not satisfying this chapter shall be permitted if it is demonstrated by experimental evidence and analysis that the proposed system will have strength and toughness equal to or exceeding those provided by a comparable reinforced concrete structure satisfying this chapter.

18.2.2 Analysis and proportioning of structural members**R18.2.2 Analysis and proportioning of structural members**

It is assumed that the distribution of required strength to the various components of a seismic-force-resisting system will be determined from the analysis of a linearly elastic model of the system acted upon by the factored forces, as

CODE

COMMENTARY

required by the general building code. If nonlinear response history analyses are to be used, base motions should be selected after a detailed study of the site conditions and local seismic history.

Because the basis for earthquake-resistant design admits nonlinear response, it is necessary to investigate the stability of the seismic-force-resisting system, as well as its interaction with other structural and nonstructural members, under expected lateral displacements corresponding to maximum considered earthquake ground motion. For lateral displacement calculations, assuming all the structural members to be fully cracked is likely to lead to better estimates of the possible drift than using uncracked stiffness for all members. The analysis assumptions described in 6.6.3.1.2 may be used to estimate lateral deflections of reinforced concrete building systems.

The main objective of Chapter 18 is the safety of the structure. The intent of 18.2.2.1 and 18.2.2.2 is to draw attention to the influence of nonstructural members on structural response and to hazards from falling objects.

Section 18.2.2.3 serves as an alert that the base of structure as defined in analysis may not necessarily correspond to the foundation or ground level. Details of columns and walls extending below the base of structure to the foundation are required to be consistent with those above the base of structure.

In selecting member sizes for earthquake-resistant structures, it is important to consider constructibility problems related to congestion of reinforcement. The design should be such that all reinforcement can be assembled and placed in the proper location and that concrete can be cast and consolidated properly. Using the upper limits of permitted reinforcement ratios may lead to construction problems.

18.2.2.1 The interaction of all structural and nonstructural members that affect the linear and nonlinear response of the structure to earthquake motions shall be considered in the analysis.

18.2.2.2 Rigid members assumed not to be a part of the seismic-force-resisting system shall be permitted provided their effect on the response of the system is considered in the structural design. Consequences of failure of structural and nonstructural members that are not a part of the seismic-force-resisting system shall be considered.

18.2.2.3 Structural members extending below the base of structure that are required to transmit forces resulting from earthquake effects to the foundation shall comply with the requirements of Chapter 18 that are consistent with the seismic-force-resisting system above the base of structure.

CODE

18.2.3 Anchoring to concrete

18.2.3.1 Anchors resisting earthquake-induced forces in structures assigned to SDC C, D, E, or F shall be in accordance with **17.10**.

18.2.4 Strength reduction factors

18.2.4.1 Strength reduction factors shall be in accordance with **Chapter 21**.

18.2.5 Concrete in special moment frames and special structural walls

18.2.5.1 Specified compressive strength of concrete in special moment frames and special structural walls shall be in accordance with the special seismic systems requirements of **19.2.1**.

18.2.6 Reinforcement in special moment frames and special structural walls

18.2.6.1 Reinforcement in special moment frames and special structural walls shall be in accordance with the special seismic systems requirements of **20.2.2**.

COMMENTARY

R18.2.4 Strength reduction factors

R18.2.4.1 Chapter 21 contains strength reduction factors for all members, joints, and connections of earthquake-resistant structures, including specific provisions in **21.2.4** for buildings that use special moment frames, special structural walls, and intermediate precast walls.

R18.2.5 Concrete in special moment frames and special structural walls

Requirements of this section refer to concrete quality in frames and walls that resist earthquake-induced forces. The maximum specified compressive strength of lightweight concrete to be used in structural design calculations is limited to 5000 psi, primarily because of paucity of experimental and field data on the behavior of members made with lightweight concrete subjected to displacement reversals in the nonlinear range. If convincing evidence is developed for a specific application, the limit on maximum specified compressive strength of lightweight concrete may be increased to a level justified by the evidence.

R18.2.6 Reinforcement in special moment frames and special structural walls

R18.2.6.1 Nonprestressed reinforcement for seismic systems is required to meet **20.2.2.4** and **20.2.2.5**. **ASTM A706** Grades 60, 80 and 100 reinforcement is permitted to resist moments, axial, and shear forces in special structural walls and all components of special structural walls, including coupling beams and wall piers. **ASTM A706** Grades 60 and 80 reinforcement is permitted in special moment frames. Results of tests and analytical studies presented in **NIST (2014)** and **Sokoli and Ghannoum (2016)** indicate that properly detailed beams and columns of special moment frames with **ASTM A706** Grade 80 reinforcement exhibit strength and deformation capacities similar to those of members reinforced with Grade 60 reinforcement. The use of Grade 100 reinforcement is not allowed in special moment frames because there is insufficient data to demonstrate satisfactory seismic performance.

To allow the use of **ASTM A706** Grade 80 and 100 reinforcement, the **2019 Code** includes limits for spacing of transverse reinforcement to provide adequate longitudinal bar support to control longitudinal bar buckling. In special

CODE

COMMENTARY

moment frames, the use of Grade 80 reinforcement requires increased joint depths to prevent excessive slip of beam bars passing through beam-column joints (18.8.2.3).

The requirement in 20.2.1.3(b) for a tensile strength greater than the yield strength of the reinforcement is based on laboratory tests demonstrating adequate deformation capacities in structural components with reinforcement satisfying this requirement.

The restrictions on the value of f_{yt} apply to all types of transverse reinforcement, including spirals, circular hoops, rectilinear hoops, and crossties. Research results (Budek et al. 2002; Muguruma and Watanabe 1990; Sugano et al. 1990) indicate that higher yield strengths can be used effectively as confinement reinforcement as specified in 18.7.5.4. The increases to 80,000 psi and 100,000 psi for shear design of some special seismic system members is based on research indicating the design shear strength can be developed (Wallace 1998; Aoyama 2001; Budek et al. 2002; Sokoli and Ghannoum 2016; Cheng et al. 2016; Huq et al. 2018; Weber-Kamin et al. 2020). The 60,000 psi restriction on the value of f_{yt} for deformed bar in 20.2.2.4 for calculating nominal shear strength is intended to limit the width of shear cracks at service-level loads. Service-level cracking is not a concern in members of the seismic-force-resisting system subjected to design-level earthquake forces.

18.2.7 Mechanical splices in special moment frames and special structural walls

18.2.7.1 Mechanical splices shall conform to 25.5.7 and the requirements of this section.

R18.2.7 Mechanical splices in special moment frames and special structural walls

R18.2.7.1 The 2025 Code consolidated the requirements for all classes of mechanical splices into 25.5.7, with mechanical splice classifications designated as Class L, Class G, and Class S replacing the classifications and requirements used in prior Code editions. The requirements for each class of mechanical splice are described in R25.5.7.2. In a structure undergoing inelastic deformations during an earthquake, tensile strains in reinforcing bars may approach the specified minimum uniform elongation. The requirements specified in Table 25.5.7.2 for Class S mechanical splices are intended to avoid premature failure under inelastic cyclic effects on the mechanical splicing device and the bars being mechanically spliced.

18.2.7.2 Mechanical splices shall satisfy (a) through (d):
 (a) Mechanical splices shall be Class G or Class S.
 (b) Class S mechanical splices shall be permitted at any location, except as noted in 18.9.2.1(c)
 (c) Class G mechanical splices in special moment frames are prohibited within joints, within a distance equal to twice the member depth from the column or beam face for special moment frames, and within a distance equal to twice the member depth from critical sections where yielding of the reinforcement is likely to occur as a result of lateral displacements beyond the linear range of behavior.

R18.2.7.2 Class L and Class G mechanical splices are not required to be capable of resisting the considerable strain levels that may occur in yielding regions due to earthquake loading, nor are these particular classes of mechanical splices required to resist inelastic cyclic loading. As a result, in special seismic systems, Class L mechanical splices are not permitted and locations where Class G mechanical splices may be used are restricted. These restrictions apply to all reinforcement resisting earthquake effects, including transverse reinforcement.

Regarding the use of Class L mechanical splices in ordinary and intermediate moment frames and structural walls,

CODE

(d) Class G mechanical splices in special structural walls are prohibited where lap splices of longitudinal reinforcement in boundary regions are prohibited by 18.10.2.3(c), within coupling beams, and within a distance equal to twice the member depth from critical sections where yielding of the reinforcement is likely to occur as a result of lateral displacements beyond the linear range of behavior.

18.2.8 *Welded splices in special moment frames and special structural walls*

18.2.8.1 Welded splices are not permitted in special moment frames or in special structural walls, including coupling beams.

18.2.8.2 Welding of stirrups, ties, inserts, or other similar elements to longitudinal reinforcement required by design shall not be permitted.

18.3—Ordinary moment frames

COMMENTARY

including coupling beams, the requirements of 25.5.7.2(a) preclude the use of Class L mechanical splices in yielding regions of these systems, resulting in location restrictions similar to those of 18.2.7.2(c) and (d).

Recommended detailing practice precludes use of mechanical or lapped bar splices in regions of potential yielding in members resisting earthquake effects. If use of mechanical splices in regions of potential yielding cannot be avoided, Class S mechanical splices are required. Documentation required by 26.6.1.2(b) should be provided to confirm the mechanical splice used in construction meets the Class S requirements as specified in 25.5.7.2.

For staggering of mechanical splices, refer to R25.5.7.4.

R18.2.8 *Welded splices in special moment frames and special structural walls*

R18.2.8.1 Welded splices are similar to Class L mechanical splices. Therefore, welded splices are not permitted in special seismic systems because reinforcement tension strains and stresses in yielding regions can exceed the requirements of 25.5.7.3(a), which does not establish minimum tensile strain or inelastic cyclic endurance requirements for welded splices. The restriction on welded splices applies to all reinforcement resisting earthquake effects, including transverse reinforcement.

Regarding the use of welded splices in ordinary and intermediate moment frames and structural walls, including coupling beams, the requirement of 25.5.7.3(c) precludes the use of welded splices in yielding regions of these systems, resulting in location restrictions similar to those of Class G mechanical splices in 18.2.7.2(c) and 18.2.7.2(d).

R18.2.8.2 Welding of crossing reinforcing bars can lead to local embrittlement of the steel. If welding of crossing bars is used to facilitate fabrication or placement of reinforcement, it should be done only on bars added for such purposes. The prohibition of welding crossing reinforcing bars does not apply to bars that are welded with automated welding operations under continuous, competent control, as in the manufacture of welded-wire reinforcement.

R18.3—Ordinary moment frames

This section applies only to ordinary moment frames assigned to SDC B. The provisions for beam reinforcement are intended to improve continuity in the framing members and thereby improve lateral force resistance and structural integrity; these provisions do not apply to slab-column moment frames. The provisions for columns are intended to provide additional capacity to resist shear for columns with proportions that would otherwise make them more susceptible to shear failure under earthquake loading.

CODE

COMMENTARY

18.3.1 Scope

18.3.1.1 This section shall apply to ordinary moment frames forming part of the seismic-force-resisting system.

18.3.2 Beams shall have at least two continuous bars at both top and bottom faces. Continuous bottom bars shall have area not less than one-fourth the maximum area of bottom bars along the span. These bars shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at the face of support.

18.3.3 Columns having unsupported length $\ell_u \leq 5c_1$ shall have ϕV_n at least the lesser of (a) and (b):

- (a) The shear associated with development of nominal moment strengths of the column at each restrained end of the unsupported length due to reverse curvature bending. Column flexural strength shall be calculated for the factored axial force, consistent with the direction of the lateral forces considered, resulting in the highest flexural strength.
- (b) The maximum shear obtained from design load combinations that include E , with $\Omega_o E$ substituted for E .

18.3.4 Beam-column joints shall satisfy Chapter 15 with joint shear V_u calculated on a plane at mid-height of the joint using tensile and compressive beam forces and column shear consistent with beam nominal moment strengths M_n .

18.4—Intermediate moment frames**R18.4—Intermediate moment frames**

The objective of the requirements in 18.4.2.3 and 18.4.3.1 is to reduce the risk of failure in shear in beams and columns during an earthquake. Two options are provided to determine the factored shear force.

18.4.1 Scope

18.4.1.1 This section shall apply to intermediate moment frames including two-way slabs without beams forming part of the seismic-force-resisting system.

18.4.2 Beams**R18.4.2 Beams**

According to 18.4.2.3(a), the factored shear force is determined from a free-body diagram obtained by cutting through the beam ends, with end moments assumed equal to the nominal moment strengths acting in reverse curvature bending, both clockwise and counterclockwise. Figure R18.4.2 demonstrates only one of the two options that are to be considered for every beam. To determine the maximum beam shear, it is assumed that its nominal moment strengths ($\phi = 1.0$ for moment) are developed simultaneously at both ends of its clear span. As indicated in Fig. R18.4.2, the shear associated with this condition $[(M_{nl} + M_{nr})/\ell_n]$ is added algebraically to the shear due to the factored gravity loads and vertical earthquake effects to obtain the design shear for the

CODE

COMMENTARY

beam. For the example shown, dead load, live load, and snow load have been assumed to be uniformly distributed. The figure also shows that vertical earthquake effects are to be included, as is typically required by the general building code. For example, **ASCE/SEI 7** requires vertical earthquake effects, $0.2S_{DS}$, to be included.

Provision 18.4.2.3(b) bases V_u on the load combination including the earthquake effect E , which should be doubled. For example, the load combination defined by Eq. (5.3.1.e) would be

$$U = 1.2D + 2.0E + 1.0L + 0.2S$$

where E is the value specified by the general building code. The factor of 1.0 applied to L is allowed to be reduced to 0.5 in accordance with **5.3.3**.

Transverse reinforcement at the ends of the beam is required to be hoops. In most cases, transverse reinforcement required by 18.4.2.3 for the design shear force will be more than those required by 18.4.2.4.

Beams may be subjected to axial compressive force due to prestressing or applied loads. The additional requirements in 18.4.2.6 are intended to provide lateral support for beam longitudinal reinforcement.

CODE

COMMENTARY




Fig. R18.4.2—Design shears for intermediate moment frames.

18.4.2.1 Beams shall have at least two continuous bars at both top and bottom faces. Continuous bottom bars shall have area not less than one-fourth the maximum area of bottom bars along the span. These bars shall be developed in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y at the face of support.

CODE

COMMENTARY

18.4.2.2 The positive moment strength at the face of the joint shall be at least one-third the negative moment strength provided at that face of the joint. Neither the negative nor the positive moment strength at any section along the length of the beam shall be less than one-fifth the maximum moment strength provided at the face of either joint.

18.4.2.3 ϕV_n shall be at least the lesser of (a) and (b):

- (a) The sum of the shear associated with development of nominal moment strengths of the beam at each restrained end of the clear span due to reverse curvature bending and the shear calculated for factored gravity and vertical earthquake loads
- (b) The maximum shear obtained from design load combinations that include E , with E taken as twice that prescribed by the general building code

18.4.2.4 At both ends of the beam, hoops or closed stirrups in accordance with 18.6.4.3 shall be provided over a length of at least twice the beam depth measured from the face of the supporting member toward midspan. The first hoop or closed stirrup shall be located not more than 2 in. from the face of the supporting member. Spacing of hoops or closed stirrups shall not exceed the smallest of (a) through (d):

- (a) $d/4$
- (b) Eight times the diameter of the smallest longitudinal bar enclosed
- (c) 24 times the diameter of the transverse reinforcing bar
- (d) 12 in.

18.4.2.5 Transverse reinforcement spacing shall not exceed $d/2$ throughout the length of the beam.

18.4.2.6 In beams having factored axial compressive force exceeding $A_g f_c'/10$, transverse reinforcement required by 18.4.2.5 shall conform to 25.7.2.2 and either 25.7.2.3 or 25.7.2.4.

18.4.3 Columns**R18.4.3 Columns**

According to 18.4.3.1(a), the factored shear force is determined from a free-body diagram obtained by cutting through the column ends, with end moments assumed equal to the nominal moment strengths acting in reverse curvature bending, both clockwise and counterclockwise. Figure R18.4.2 demonstrates only one of the two options that are to be considered for every column. The factored axial force P_u should be chosen to develop the largest moment strength of the column within the range of design axial forces. Provision 18.4.3.1(b) for columns is similar to 18.4.2.3(b) for beams except it bases V_u on load combinations including the earthquake effect E , with E increased by the overstrength factor Ω_o rather than the factor 2.0. In ASCE/SEI 7, $\Omega_o = 3.0$ for intermediate moment frames. The higher factor for columns relative to beams is because of greater concerns about shear failures in columns.

CODE

COMMENTARY

Transverse reinforcement at the ends of columns is required to be spirals or hoops. The amount of transverse reinforcement at the ends must satisfy both 18.4.3.1 and 18.4.3.2. Note that hoops require seismic hooks at both ends. The maximum spacing allowed for hoops is intended to inhibit or delay buckling of longitudinal reinforcement.

Discontinuous structural walls and other stiff members can impose large axial forces on supporting columns during earthquakes. The required transverse reinforcement in 18.4.3.6 is to improve column toughness under anticipated demands. The factored axial compressive force related to earthquake effect should include the factor Ω_o if required by the general building code.

18.4.3.1 ϕV_n shall be at least the lesser of (a) and (b):

- (a) The shear associated with development of nominal moment strengths of the column at each restrained end of the unsupported length due to reverse curvature bending. Column flexural strength shall be calculated for the factored axial force, consistent with the direction of the lateral forces considered, resulting in the highest flexural strength
- (b) The maximum shear obtained from factored load combinations that include E , with $\Omega_o E$ substituted for E

18.4.3.2 Columns shall be spirally reinforced in accordance with **Chapter 10** or shall be in accordance with 18.4.3.3 through 18.4.3.5. Provision 18.4.3.6 shall apply to all columns supporting discontinuous stiff members.

18.4.3.3 At both ends of the column, hoops shall be provided at spacings s_o over a length ℓ_o measured from the joint face. Spacing s_o shall not exceed the least of (a) through (c):

- (a) For Grade 60, the smaller of $8d_b$ of the smallest longitudinal bar enclosed and 8 in.
- (b) For Grade 80, the smaller of $6d_b$ of the smallest longitudinal bar enclosed and 6 in.
- (c) One-half of the smallest cross-sectional dimension of the column

Length ℓ_o shall not be less than the longest of (d), (e), and (f):

- (d) One-sixth of the clear span of the column
- (e) Maximum cross-sectional dimension of the column
- (f) 18 in.

18.4.3.4 The first hoop shall be located not more than $s_o/2$ from the joint face.

18.4.3.5 Outside of length ℓ_o , spacing of transverse reinforcement shall be in accordance with **10.7.6.5.2**.

18.4.3.6 Columns supporting reactions from discontinuous stiff members, such as walls, shall be provided with transverse reinforcement at the spacing s_o in accordance with 18.4.3.3 over the full height beneath the level at which the discontinuity occurs if the portion of factored axial compressive force in these members related to earthquake effects exceeds $A_g f'_c/10$. If design forces have been magnified to

CODE

account for the overstrength of the vertical elements of the seismic-force-resisting system, the limit of $A_g f'_c / 10$ shall be increased to $A_g f'_c / 4$. Transverse reinforcement shall extend above and below the column in accordance with 18.7.5.6(b).

18.4.4 Joints

18.4.4.1 Beam-column joints shall satisfy the detailing requirements of 15.7.1.2, 15.7.1.3, and 18.4.4.2 through 18.4.4.5.

18.4.4.2 If a beam framing into the joint and generating joint shear has depth exceeding twice the column depth, analysis and design of the joint shall be based on the strut-and-tie method in accordance with Chapter 23 and (a) and (b) shall be satisfied:

- (a) Design joint shear strength determined in accordance with Chapter 23 shall not exceed ϕV_n calculated in accordance with 15.5.
- (b) Detailing requirements of 18.4.4.3 through 18.4.4.5 shall be satisfied.

18.4.4.3 Longitudinal reinforcement terminated in a joint shall extend to the far face of the joint core and shall be developed in tension in accordance with 18.8.5.

18.4.4.4 Spacing of joint transverse reinforcement s shall not exceed the lesser of 18.4.3.3(a) through (c) within the height of the deepest beam framing into the joint.

18.4.4.5 Where the top beam longitudinal reinforcement consists of headed deformed bars that terminate in the joint, the column shall extend above the top of the joint a distance at least the depth h of the joint. Alternatively, the beam reinforcement shall be enclosed by additional vertical joint reinforcement providing equivalent confinement to the top face of the joint.

18.4.4.6 Slab-column joints shall satisfy transverse reinforcement requirements of 15.7.2. Where slab-column joint transverse reinforcement is required, at least one layer of joint transverse reinforcement shall be placed between the top and bottom slab reinforcement.

18.4.4.7 Shear strength requirements for beam-column joints

18.4.4.7.1 Design shear strength of cast-in-place beam-column joints shall satisfy:

$$\phi V_n \geq V_u$$

COMMENTARY

R18.4.4 Joints

R18.4.4.2 For joints in which the beam depth is significantly greater than the column depth, a diagonal strut between the joint corners may not be effective. Therefore, the Code requires that joints in which the beam depth exceeds twice the column depth be designed using the strut-and-tie method of Chapter 23.

R18.4.4.3 Refer to R18.8.2.2.

R18.4.4.4 The maximum spacing of transverse reinforcement within a joint is consistent with the spacing limits for reinforcement in columns of intermediate moment frames.

R18.4.4.5 Refer to R25.4.4.6.

R18.4.4.7 Shear strength requirements for beam-column joints

CODE

18.4.4.7.2 V_u of the joint shall be determined in accordance with 18.3.4.

18.4.4.7.3 ϕ shall be in accordance with 21.2.1 for shear.

18.4.4.7.4 V_n of the joint shall be in accordance with 18.8.4.3.

18.4.5 Two-way slabs without beams

18.4.5.1 Factored slab moment at the support including earthquake effects, E , shall be calculated for load combinations given in Eq. (5.3.1e) and (5.3.1g). Reinforcement to resist M_{sc} shall be placed within the column strip defined in 8.4.1.5.

COMMENTARY

R18.4.4.7.2 Factored joint shear force is determined assuming that beams framing into the joint develop end moments equal to their nominal moment strengths. Consequently, joint shear force generated by the flexural reinforcement is calculated for a stress of f_y in the reinforcement. This is consistent with 18.4.2 and 18.4.3 for determination of minimum design shear strength in beams and columns of intermediate moment frames.

R18.4.5 Two-way slabs without beams

Section 18.4.5 applies to two-way slabs without beams, such as flat plates.

Using load combinations of Eq. (5.3.1e) and (5.3.1g) may result in moments requiring top and bottom reinforcement at the supports.


The moment M_{sc} refers, for a given design load combination with E acting in one horizontal direction, to that portion of the factored slab moment that is balanced by the supporting members at a joint. It is not necessarily equal to the total design moment at the support for a load combination including earthquake effect. In accordance with 8.4.2.2.3, only a fraction of the moment M_{sc} is assigned to the slab effective width. For edge and corner connections, flexural reinforcement perpendicular to the edge is not considered fully effective unless it is placed within the effective slab width (ACI PRC-352.1; Pan and Moehle 1989). Refer to Fig. R18.4.5.1.

Application of the provisions of 18.4.5 is illustrated in Fig. R18.4.5.2 and R18.4.5.3.


R18.4.5.1

CODE

COMMENTARY



(a) Edge connection



(b) Corner connection


Fig. R18.4.5.1—Effective width for reinforcement placement in edge and corner connections.

18.4.5.2 Reinforcement placed within the effective width given in 8.4.2.2.3 shall be designed to resist $\gamma_f M_{sc}$. Effective slab width for exterior and corner connections shall not extend beyond the column face a distance greater than c_t measured perpendicular to the slab span.

R18.4.5.2

CODE

18.4.5.3 At least one-half of the reinforcement in the column strip at the support shall be placed within the effective slab width given in 8.4.2.2.3.

COMMENTARY

Note: Applies to both top and bottom reinforcement

Fig. R18.4.5.2—Location of reinforcement in slabs.


R18.4.5.3

Fig. R18.4.5.3—Arrangement of reinforcement in slabs.

18.4.5.4 At least one-fourth of the top reinforcement at the support in the column strip shall be continuous throughout the span.

18.4.5.5 Continuous bottom reinforcement in the column strip shall be at least one-third of the top reinforcement at the support in the column strip.

18.4.5.6 At least one-half of all bottom middle strip reinforcement and all bottom column strip reinforcement at midspan shall be continuous and shall develop f_y at the face of columns, capitals, brackets, or walls.

CODE

18.4.5.7 At discontinuous edges of the slab, all top and bottom reinforcement at the support shall be developed at the face of columns, capitals, brackets, or walls.

18.4.5.8 At the critical sections for columns defined in **22.6.4.1**, two-way shear stress caused by factored gravity loads without moment transfer shall not exceed $0.4\phi v_c$ for nonprestressed slab-column connections and $0.5\phi v_c$ for unbonded post-tensioned slab-column connections with f_{pc} in each direction meeting the requirements of **8.6.2.1**, where v_c shall be calculated in accordance with **22.6.5**. This requirement need not be satisfied if the slab-column connection satisfies **18.14.5**.

18.5—Intermediate precast structural walls**18.5.1 Scope**

18.5.1.1 This section shall apply to intermediate precast structural walls forming part of the seismic-force-resisting system.

18.5.2 General

18.5.2.1 In connections between wall panels, or between wall panels and the foundation, yielding shall be restricted to steel elements or reinforcement. Mechanical splices used as components of the connection shall be Class S.

18.5.2.2 For elements of the connection that are not designed to yield, the required strength shall be based on $1.5S_y$ of the yielding portion of the connection, but need not exceed the strength required from applying factored load combinations that include E_{mh} .

18.5.2.3 In structures assigned to SDC D, E, or F, wall piers shall be designed in accordance with **18.10.8** or **18.14**.

18.6—Beams of special moment frames**18.6.1 Scope**

COMMENTARY

R18.4.5.8 The requirements apply to two-way slabs that are designated part of the seismic-force-resisting system. Nonprestressed slab-column connections in laboratory tests (**Pan and Moehle 1989**) exhibited reduced lateral displacement ductility when the shear stress at the column connection exceeded the recommended limit of $0.4\phi v_c$. Based on laboratory test data (**Kang and Wallace 2006**; **Kang et al. 2007**), a higher maximum factored gravity shear stress of $0.5\phi v_c$ is allowed for unbonded post-tensioned slab-column connections with f_{pc} in each direction meeting the requirements of **8.6.2.1**. Post-tensioned slab-column connections with f_{pc} in each direction not meeting the requirements of **8.6.2.1** can be designed as nonprestressed slab-column connections in accordance with **8.2.3**. Slab-column connections also must satisfy shear and moment strength requirements of **Chapter 8** under load combinations including earthquake effect.

R18.5—Intermediate precast structural walls

Connections between precast wall panels or between wall panels and the foundation are required to resist forces induced by earthquake motions and to provide for yielding in the vicinity of connections.

R18.5.2.2 Connection design forces need not exceed the maximum forces that the structural system can deliver to the connection.

R18.6—Beams of special moment frames**R18.6.1 Scope**

CODE

COMMENTARY

This section applies to beams of special moment frames resisting lateral loads induced by earthquake motions. In previous Codes, any frame member subjected to a factored axial compressive force exceeding $(A_g f'_c/10)$ under any load combination was to be proportioned and detailed as described in 18.7. In the 2014 Code, all requirements for beams are contained in 18.6 regardless of the magnitude of axial compressive force.

The Code is written with the assumption that special moment frames comprise horizontal beams and vertical columns interconnected by beam-column joints. It is acceptable for beams and columns to be inclined provided the resulting system behaves as a frame—that is, lateral resistance is provided primarily by moment transfer between beams and columns rather than by strut or brace action. In special moment frames, it is acceptable to design beams to resist combined moment and axial force as occurs in beams that act both as moment frame members and as chords or collectors of a diaphragm. It is acceptable for beams of special moment frames to cantilever beyond columns, but such cantilevers are not part of the special moment frame that forms part of the seismic-force-resisting system. It is acceptable for beams of a special moment frame to connect into a wall boundary if the boundary is reinforced as a special moment frame column in accordance with 18.7. A concrete braced frame, in which lateral resistance is provided primarily by axial forces in beams and columns, is not a recognized seismic-force-resisting system.

18.6.1.1 This section shall apply to beams of special moment frames that form part of the seismic-force-resisting system and are proportioned primarily to resist flexure and shear.

18.6.1.2 Beams of special moment frames shall frame into columns of special moment frames satisfying 18.7.

18.6.2 Dimensional limits

R18.6.2 Dimensional limits

Experimental evidence (Hirosawa 1977) indicates that, under reversals of displacement into the nonlinear range, behavior of continuous members having length-to-depth ratios of less than 4 is significantly different from the behavior of relatively slender members. Design rules derived from experience with relatively slender members do not apply directly to members with length-to-depth ratios less than 4, especially with respect to shear strength.

Geometric constraints indicated in 18.6.2.1(b) and (c) were derived from practice and research (ACI PRC-352) on reinforced concrete frames resisting earthquake-induced forces. The limits in 18.6.2.1(c) define the maximum beam width that can effectively transfer forces into the beam-column joint. An example of maximum effective beam width is shown in Fig. R18.6.2.

CODE

COMMENTARY




Fig. R18.6.2—Maximum effective width of wide beam and required transverse reinforcement.

18.6.2.1 Beams shall satisfy (a) through (c):

- (a) Clear span ℓ_n shall be at least $4d$
- (b) Width b_w shall be at least the larger of $0.3h$ and 10 in.
- (c) Projection of the beam width beyond the width of the supporting column on each side shall not exceed the smaller of c_2 and $0.7c_1$.

R18.6.2.1 Experimental evidence (Hirosawa 1977) indicates that, under reversals of displacement into the nonlinear range, behavior of continuous members having length-to-depth ratios less than 4 is significantly different from the behavior of relatively slender members. Design rules derived from experience with relatively slender members do not apply directly to members with length-to-depth ratios less than 4, especially with respect to shear strength.

Geometric constraints indicated in 18.6.2.1(b) and (c) were derived from practice and research (ACI PRC-352) on reinforced concrete frames resisting earthquake-induced forces. The limits in 18.6.2.1(c) define the maximum beam width that can effectively transfer forces into the beam-column joint. An example of maximum effective beam width is shown in Fig. R18.6.2.

CODE

18.6.3 Longitudinal reinforcement

18.6.3.1 Beams shall have at least two continuous bars at both top and bottom faces. At any section, for top as well as for bottom reinforcement, the amount of reinforcement shall be at least that required by 9.6.1.2, and the reinforcement ratio ρ shall not exceed 0.025 for Grade 60 reinforcement and 0.02 for Grade 80 reinforcement.

18.6.3.2 Positive moment strength at joint face shall be at least one-half the negative moment strength provided at that face of the joint. Both the negative and the positive moment strength at any section along member length shall be at least one-fourth the maximum moment strength provided at face of either joint.

18.6.3.3 Lap splices of deformed longitudinal reinforcement shall be permitted if hoop or spiral reinforcement is provided over the lap length. Spacing of the transverse reinforcement enclosing the lap-spliced bars shall not exceed the lesser of $d/4$ and 4 in. Lap splices shall not be used in locations (a) through (c):

- (a) Within the joints
- (b) Within a distance of twice the beam depth from the face of the joint
- (c) Within a distance of twice the beam depth from critical sections where flexural yielding is likely to occur as a result of lateral displacements beyond the elastic range of behavior

18.6.3.4 Mechanical splices shall conform to 18.2.7 and welded splices shall conform to 18.2.8.

18.6.3.5 Unless used in a special moment frame as permitted by 18.9.2.3, prestressing shall satisfy (a) through (d):

- (a) The average prestress f_{pc} calculated for an area equal to the least cross-sectional dimension of the beam multiplied by the perpendicular cross-sectional dimension shall not exceed the lesser of 500 psi and $f_c'/10$.
- (b) Prestressed reinforcement shall be unbonded in potential plastic hinge regions, and the calculated strains in prestressed reinforcement under the design displacement shall be less than 0.01.
- (c) Prestressed reinforcement shall not contribute more than one-fourth of the positive or negative flexural strength at the critical section in a plastic hinge region and shall be anchored at or beyond the exterior face of the joint.
- (d) Anchorages of post-tensioning tendons resisting earthquake-induced forces shall be capable of allowing tendons to withstand 50 cycles of loading, with prestressed reinforcement forces bounded by 40 and 85% of the specified tensile strength of the prestressing reinforcement.

COMMENTARY

R18.6.3 Longitudinal reinforcement

R18.6.3.1 The limiting reinforcement ratios of 0.025 and 0.02 are based primarily on considerations of providing adequate deformation capacity, avoiding reinforcement congestion, and, indirectly, on limiting shear stresses in beams of typical proportions.

R18.6.3.3 Lap splices of reinforcement are prohibited along lengths where flexural yielding is anticipated because such splices are not reliable under conditions of cyclic loading into the inelastic range. Transverse reinforcement for lap splices at any location is mandatory because of the potential of concrete cover spalling and the need to confine the splice.

R18.6.3.5 These provisions were developed, in part, based on observations of building performance in earthquakes (ACI PRC-423.3). For calculating the average prestress, the least cross-sectional dimension in a beam normally is the web dimension, and is not intended to refer to the flange thickness. In a potential plastic hinge region, the limitation on strain and the requirement for unbonded tendons are intended to prevent fracture of tendons under inelastic earthquake deformation. Calculation of strain in the prestressed reinforcement is required considering the anticipated inelastic mechanism of the structure. For prestressed reinforcement unbonded along the full beam span, strains generally will be well below the specified limit. For prestressed reinforcement with short unbonded length through or adjacent to the joint, the additional strain due to earthquake deformation is calculated as the product of the depth to the neutral axis and the sum of plastic hinge rotations at the joint, divided by the unbonded length.

The restrictions on the flexural strength provided by the tendons are based on the results of analytical and experimental studies (Ishizuka and Hawkins 1987; Park and Thompson 1977). Although satisfactory seismic perfor-

CODE

COMMENTARY

mance can be obtained with greater amounts of prestressed reinforcement, this restriction is needed to allow the use of the same response modification and deflection amplification factors as those specified in model codes for special moment frames without prestressed reinforcement. Prestressed special moment frames will generally contain continuous prestressed reinforcement that is anchored with adequate cover at or beyond the exterior face of each beam-column connection located at the ends of the moment frame.

Fatigue testing for 50 cycles of loading between 40 and 80% of the specified tensile strength of the prestressed reinforcement has been a long-standing industry practice (ACI PRC-423.3; ACI SPEC-423.7). The 80% limit was increased to 85% to correspond to the 1% limit on the strain in prestressed reinforcement. Testing over this range of stress is intended to conservatively simulate the effect of a severe earthquake. Additional details on testing procedures are provided in ACI SPEC-423.7.

18.6.4 Transverse reinforcement

R18.6.4 Transverse reinforcement

Transverse reinforcement is required primarily to confine the concrete and provide lateral support for the reinforcing bars in regions where yielding is expected. Examples of transverse reinforcement suitable for beams are shown in Fig. R18.6.4.

In earlier Code editions, the upper limit on hoop spacing was the least of $d/4$, eight longitudinal bar diameters, 24 tie bar diameters, and 12 in. The upper limits were changed in the 2011 edition because of concerns about adequacy of longitudinal bar buckling restraint and confinement in large beams.

In the case of members with varying strength along the span or members for which the permanent load represents a large proportion of the total design load, concentrations of inelastic rotation may occur within the span. If such a condition is anticipated, transverse reinforcement is also required in regions where yielding is expected. Because spalling of the concrete shell might occur, especially at and near regions of flexural yielding, all web reinforcement is required to be provided in the form of closed hoops.

CODE

COMMENTARY




Fig. R18.6.4—Examples of beam transverse reinforcement and illustration of limit on maximum horizontal spacing of supported longitudinal bars.

18.6.4.1 Hoops or closed stirrups in accordance with 18.6.4.3 shall be provided in the following regions of a beam:

- (a) Over a length equal to twice the beam depth measured from the face of the supporting column toward midspan, at both ends of the beam
- (b) Over lengths equal to twice the beam depth on both sides of a section where flexural yielding is likely to occur as a result of lateral displacements beyond the elastic range of behavior.

18.6.4.2 In regions of the beam defined in 18.6.4.1, primary longitudinal reinforcing bars closest to the tension and compression faces shall have lateral support in accor-

CODE

dance with 25.7.2.3 and 25.7.2.4. The transverse spacing of supported flexural reinforcing bars shall not exceed 14 in. Skin reinforcement required by 9.7.2.3 need not be laterally supported.

18.6.4.3 Closed stirrups in beams shall be permitted to be made up of one or more U-stirrups having seismic hooks at both ends, closed by a crosstie. Consecutive crossties engaging the same longitudinal bar shall have their 90-degree hooks at opposite sides of the flexural member. If the longitudinal reinforcing bars secured by the crossties are confined by a slab on only one side of the beam, the 90-degree hooks of the crossties shall be placed on that side.

18.6.4.4 The first hoop or closed stirrup shall be located not more than 2 in. from the face of a supporting column. Spacing of the hoops or closed stirrups shall not exceed the least of (a) through (d):

- (a) $d/4$
- (b) 6 in.
- (c) For Grade 60, $6d_b$ of the smallest primary flexural reinforcing bar excluding longitudinal skin reinforcement required by 9.7.2.3
- (d) For Grade 80, $5d_b$ of the smallest primary flexural reinforcing bar excluding longitudinal skin reinforcement required by 9.7.2.3

18.6.4.5 Where hoops are not required, stirrups with seismic hooks at both ends shall be spaced at a distance not more than $d/2$ throughout the length of the beam.

18.6.4.6 In beams having factored axial compressive force exceeding $A_g f_c'/10$, hoops satisfying 18.7.5.2 through 18.7.5.4 shall be provided along lengths given in 18.6.4.1. Along the remaining length, hoops satisfying 18.7.5.2 shall have spacing s not exceeding the least of 6 in., $6d_b$ of the smallest Grade 60 enclosed longitudinal beam bar, and $5d_b$ of the smallest Grade 80 enclosed longitudinal beam bar. Where concrete cover over transverse reinforcement exceeds 4 in., additional transverse reinforcement having cover not exceeding 4 in. and spacing not exceeding 12 in. shall be provided.

18.6.5 Shear strength

COMMENTARY

R18.6.5 Shear strength

Unless a beam possesses a moment strength that is on the order of 3 or 4 times the design moment, it should be assumed that it will yield in flexure in the event of a major earthquake. The design shear force should be selected so as to be a good approximation of the maximum shear that may develop in a member. Therefore, required shear strength for frame members is related to flexural strengths of the designed member rather than to factored shear forces indicated by lateral load analysis. The conditions described by 18.6.5.1 are illustrated in Fig. R18.6.5. The figure also shows that vertical earthquake effects are to be included, as is typi-

CODE

COMMENTARY

cally required by the general building code. For example, **ASCE/SEI 7** requires vertical earthquake effects, $0.2S_{DS}$, to be included.

Because the actual yield strength of the longitudinal reinforcement may exceed the specified yield strength and because strain hardening of the reinforcement is likely to take place at a joint subjected to large rotations, required shear strengths are determined using a stress of at least $1.25f_y$ in the longitudinal reinforcement.

Experimental studies (**Popov et al. 1972**) of reinforced concrete members subjected to cyclic loading have demonstrated that more shear reinforcement is required to ensure a flexural failure if the member is subjected to alternating nonlinear displacements than if the member is loaded in only one direction: the necessary increase of shear reinforcement being higher in the case of no axial load. This observation is reflected in the Code (refer to 18.6.5.2) by eliminating the term representing the contribution of concrete to shear strength. The added conservatism on shear is deemed necessary in locations where potential flexural hinging may occur. However, this stratagem, chosen for its relative simplicity, should not be interpreted to mean that no concrete is required to resist shear. On the contrary, it may be argued that the concrete core resists all the shear with the shear (transverse) reinforcement confining and strengthening the concrete. The confined concrete core plays an important role in the behavior of the beam and should not be reduced to a minimum just because the design expression does not explicitly recognize it.




Fig. R18.6.5—Design shears for beams and columns.

18.6.5.1 Design forces

The design shear force V_e shall be calculated from consideration of the forces on the portion of the beam between faces of the joints. It shall be assumed that moments of opposite sign corresponding to probable flexural strength, M_{pr} , act at the joint faces and that the beam is loaded with the factored gravity and vertical earthquake loads along its span.

18.6.5.2 Transverse reinforcement

Transverse reinforcement over the lengths identified in 18.6.4.1 shall be designed to resist shear assuming $V_c = 0$ when both (a) and (b) occur:

- The earthquake-induced shear force calculated in accordance with 18.6.5.1 represents at least one-half of the maximum required shear strength within those lengths.
- The factored axial compressive force P_u including earthquake effects is less than $A_g f'_c / 20$.

CODE

18.7—Columns of special moment frames**18.7.1** *Scope*

18.7.1.1 This section shall apply to columns of special moment frames that form part of the seismic-force-resisting system and are proportioned primarily to resist flexure, shear, and axial forces.

18.7.2 *Dimensional limits*

18.7.2.1 Columns shall satisfy (a) and (b):

- (a) The shortest cross-sectional dimension, measured on a straight line passing through the geometric centroid, shall be at least 12 in.
- (b) The ratio of the shortest cross-sectional dimension to the perpendicular dimension shall be at least 0.4.

18.7.3 *Minimum flexural strength of columns*

COMMENTARY

R18.7—Columns of special moment frames**R18.7.1** *Scope*

This section applies to columns of special moment frames regardless of the magnitude of axial force. Before 2014, the Code permitted columns with low levels of axial stress to be detailed as beams.

R18.7.2 *Dimensional limits*

The geometric constraints in this provision follow from previous practice ([Seismology Committee of SEAOC \[1996\]](#)).

R18.7.3 *Minimum flexural strength of columns*

The intent of 18.7.3.2 is to reduce the likelihood of yielding in columns that are considered as part of the seismic-force-resisting system. If columns are not stronger than beams framing into a joint, there is increased likelihood of inelastic action. In the worst case of weak columns, flexural yielding can occur at both ends of all columns in a given story, resulting in a column failure mechanism that can lead to collapse. Connections with discontinuous columns above the connection, such as roof-level connections, are exempted if the column axial load is low, because special moment frame columns with low axial stress are inherently ductile and column yielding at such levels is unlikely to create a column failure mechanism that can lead to collapse.

In 18.7.3.2, the nominal strengths of the beams and columns are calculated at the joint faces, and those strengths are compared directly using Eq. (18.7.3.2). The 1995 and earlier Codes required design strengths to be compared at the center of the joint, which typically produced similar results but with added calculation effort.

In determining the nominal moment strength of a beam section in negative bending (top in tension), longitudinal reinforcement contained within an effective flange width of a top slab that acts monolithically with the beam increases the beam strength. [French and Moehle \(1991\)](#), on beam-column subassemblies under lateral loading, indicates that using the effective flange widths defined in 6.3.2 gives reasonable estimates of beam negative moment strengths of interior connections at story displacements approaching 2 percent of

CODE

COMMENTARY

18.7.3.1 Columns shall satisfy 18.7.3.2 or 18.7.3.3, except at connections where the column is discontinuous above the connection and the column factored axial compressive force P_u under load combinations including earthquake effect, E , are less than $A_g f'_c / 10$.

18.7.3.2 The flexural strengths of the columns shall satisfy

$$\sum M_{nc} \geq (6/5) \sum M_{nb} \quad (18.7.3.2)$$

where

$\sum M_{nc}$ is sum of nominal flexural strengths of columns framing into the joint, evaluated at the faces of the joint. Column flexural strength shall be calculated for the factored axial force, consistent with the direction of the lateral forces considered, resulting in the lowest flexural strength.

$\sum M_{nb}$ is sum of nominal flexural strengths of the beams framing into the joint, evaluated at the faces of the joint. In T-beam construction, where the slab is in tension under moments at the face of the joint, slab reinforcement within an effective slab width defined in accordance with 6.3.2 shall be assumed to contribute to M_{nb} if the slab reinforcement is developed at the critical section for flexure.

Flexural strengths shall be summed such that the column moments oppose the beam moments. Equation (18.7.3.2) shall be satisfied for beam moments acting in both directions in the vertical plane of the frame considered.

18.7.3.3 If 18.7.3.2 is not satisfied at a joint, the lateral strength and stiffness of the columns framing into that joint shall be ignored when calculating strength and stiffness of the structure. These columns shall conform to 18.14.

18.7.4 Longitudinal reinforcement

story height. This effective width is conservative where the slab terminates in a weak spandrel.

If 18.7.3.2 cannot be satisfied at a joint, 18.7.3.3 requires that any positive contribution of the column or columns involved to the lateral strength and stiffness of the structure is to be ignored. Negative contributions of the column or columns should not be ignored. For example, ignoring the stiffness of the columns ought not to be used as a justification for reducing the design base shear. If inclusion of those columns in the analytical model of the building results in an increase in torsional effects, the increase should be considered as required by the general building code. Furthermore, the column must be provided with transverse reinforcement to increase its resistance to shear and axial forces.

R18.7.4 Longitudinal reinforcement

The lower limit of the area of longitudinal reinforcement is to control time-dependent deformations and to have the yield moment exceed the cracking moment. The upper limit of the area reflects concern for reinforcement congestion, load

CODE

COMMENTARY

18.7.4.1 Area of longitudinal reinforcement, A_{st} , shall be at least $0.01A_g$ and shall not exceed $0.06A_g$.

18.7.4.2 In columns with circular hoops, there shall be at least six longitudinal bars.

18.7.4.3 Over column clear height, either (a) or (b) shall be satisfied:

(a) Longitudinal reinforcement shall be selected such that $1.25\ell_d \leq \ell_u/2$.

(b) Transverse reinforcement shall be selected such that $K_{tr} \geq 1.2d_b$.

18.7.4.4 Mechanical splices shall conform to 18.2.7 and welded splices shall conform to 18.2.8. Lap splices shall be permitted only within the center half of the member length, shall be designed as tension lap splices, and shall be enclosed within transverse reinforcement in accordance with 18.7.5.2 and 18.7.5.3.

18.7.5 Transverse reinforcement

18.7.5.1 Transverse reinforcement required in 18.7.5.2 through 18.7.5.4 shall be provided over a length ℓ_o from each joint face and on both sides of any section where flexural yielding is likely to occur as a result of lateral displacements beyond the elastic range of behavior. Length ℓ_o shall be at least the greatest of (a) through (c):

- (a) The depth of the column at the joint face or at the section where flexural yielding is likely to occur
- (b) One-sixth of the clear span of the column
- (c) 18 in.

18.7.5.2 Transverse reinforcement shall be in accordance with (a) through (f):

transfer from floor elements to column (especially in low-rise construction) and the development of high shear stresses.

Spalling of the shell concrete, which is likely to occur near the ends of the column in frames of typical configuration, makes lap splices in these locations vulnerable. If lap splices are to be used at all, they should be located near the midheight where stress reversal is likely to be limited to a smaller stress range than at locations near the joints. Transverse reinforcement is required along the lap-splice length because of the uncertainty in moment distributions along the height and the need for confinement of lap splices subjected to stress reversals (Sivakumar et al. 1983).

R18.7.4.3 Bond splitting failure along longitudinal bars within the clear column height may occur under earthquake demands (Ichinose 1995; Sokoli and Ghannoum 2016).

Splitting can be controlled by restricting longitudinal bar size, increasing the amount of transverse reinforcement, or increasing concrete strength, all of which reduce the development length of longitudinal bars (ℓ_d) over column clear height (ℓ_u).

R18.7.5 Transverse reinforcement

This section is concerned with confining the concrete and providing lateral support to the longitudinal reinforcement.

R18.7.5.1 This section stipulates a minimum length over which to provide closely-spaced transverse reinforcement at the column ends, where flexural yielding normally occurs. Research results indicate that the length should be increased by 50% or more in locations, such as the base of a building, where axial loads and flexural demands may be especially high (Watson et al. 1994)

R18.7.5.2 Sections 18.7.5.2 and 18.7.5.3 provide requirements for configuration of transverse reinforcement for columns and joints of special moment frames. Figure R18.7.5.2 shows an example of transverse reinforcement


CODE

- (a) Transverse reinforcement shall comprise either single or overlapping spirals, circular hoops, or single or overlapping rectilinear hoops with or without cross-ties.
- (b) Bends of rectilinear hoops and cross-ties shall engage peripheral longitudinal reinforcing bars.
- (c) Cross-ties of the same or smaller bar size as the hoops shall be permitted, subject to the limitation of 25.7.2.2. Consecutive cross-ties shall be alternated end for end along the longitudinal reinforcement and around the perimeter of the cross section.
- (d) Where rectilinear hoops or cross-ties are used, they shall provide lateral support to longitudinal reinforcement in accordance with 25.7.2.2 and 25.7.2.3.
- (e) Reinforcement shall be arranged such that the spacing h_x of longitudinal bars laterally supported by the corner of a cross-tie or hoop leg shall not exceed 14 in. around the perimeter of the column.
- (f) Where $P_u > 0.3A_gf'_c$ or $f'_c > 10,000$ psi in columns with rectilinear hoops, every longitudinal bar or bundle of bars around the perimeter of the column core shall have lateral support provided by the corner of a hoop or by a seismic hook, and the value of h_x shall not exceed 8 in. P_u shall be the largest value in compression consistent with factored load combinations including E .

COMMENTARY

provided by one hoop and three cross-ties. Cross-ties with a 90-degree hook are not as effective as either cross-ties with 135-degree hooks or hoops in providing confinement. For lower values of $P_u/A_gf'_c$ and lower concrete compressive strengths, cross-ties with 90-degree hooks are adequate if the ends are alternated along the length and around the perimeter of the column. For higher values of $P_u/A_gf'_c$, for which compression-controlled behavior is expected, and for higher compressive strengths, for which behavior tends to be more brittle, the improved confinement provided by having corners of hoops or seismic hooks supporting all longitudinal bars is important to achieving intended performance. Where these conditions apply, cross-ties with seismic hooks at both ends are required. The 8 in. limit on h_x is also intended to improve performance under these critical conditions. For bundled bars, bends or hooks of hoops and cross-ties need to enclose the bundle, and longer extensions on hooks should be considered. Column axial load P_u should reflect factored compressive demands from both earthquake and gravity loads.

In past editions of the Code, the requirements for transverse reinforcement in columns, walls, beam-column joints, and diagonally reinforced coupling beams referred to the same equations. In the 2014 edition of the Code, the equations and detailing requirements differ among the member types based on consideration of their loadings, deformations, and performance requirements. Additionally, h_x previously referred to the distance between legs of hoops or cross-ties. In the 2014 edition of the Code, h_x refers to the distance between longitudinal bars supported by those hoops or cross-ties.



The dimension x_j from centerline to centerline of laterally supported longitudinal bars is not to exceed 14 inches. The term h_x used in Eq. (18.7.5.3) is taken as the largest value of x_j .

Fig. R18.7.5.2—Example of transverse reinforcement in columns.

CODE

18.7.5.3 Spacing of transverse reinforcement shall not exceed the least of (a) through (d):

- (a) One-fourth of the minimum column dimension
- (b) For Grade 60, $6d_b$ of the smallest longitudinal bar
- (c) For Grade 80, $5d_b$ of the smallest longitudinal bar
- (d) s_o , as calculated by:

$$s_o = 4 + \left(\frac{14 - h_x}{3} \right) \quad (18.7.5.3)$$

The value of s_o from Eq. (18.7.5.3) shall not exceed 6 in. and need not be taken less than 4 in.

18.7.5.4 Amount of transverse reinforcement shall be in accordance with Table 18.7.5.4.

The concrete strength factor k_f and confinement effectiveness factor k_n are calculated according to Eq. (18.7.5.4a) and (18.7.5.4b).

$$(a) \quad k_f = \frac{f'_c}{25,000} + 0.6 \geq 1.0 \quad (18.7.5.4a)$$

$$(b) \quad k_n = \frac{n_l}{n_l - 2} \quad (18.7.5.4b)$$

where n_l is the number of longitudinal bars or bar bundles around the perimeter of a column core with rectilinear hoops that are laterally supported by the corner of hoops or by seismic hooks.

Table 18.7.5.4—Transverse reinforcement for columns of special moment frames

Transverse reinforcement	Conditions	Applicable expressions	
A_{sh}/sb_c for rectilinear hoop	$P_u \leq 0.3A_g f'_c$ and $f'_c \leq 10,000$ psi	Greater of (a) and (b)	$0.3 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$ (a)
	$P_u > 0.3A_g f'_c$ or $f'_c > 10,000$ psi	Greatest of (a), (b), and (c)	$0.09 \frac{f'_c}{f_{yt}}$ (b) $0.2 k_f k_n \frac{P_u}{f_{yt} A_{ch}}$ (c)
ρ_s for spiral or circular hoop	$P_u \leq 0.3A_g f'_c$ and $f'_c \leq 10,000$ psi	Greater of (d) and (e)	$0.45 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$ (d)
	$P_u > 0.3A_g f'_c$ or $f'_c > 10,000$ psi	Greatest of (d), (e), and (f)	$0.12 \frac{f'_c}{f_{yt}}$ (e) $0.35 k_f \frac{P_u}{f_{yt} A_{ch}}$ (f)

COMMENTARY

R18.7.5.3 The requirement that spacing not exceed one-fourth of the minimum member dimension or 6 in. is for concrete confinement. If the maximum spacing of crossties or legs of overlapping hoops within the section is less than 14 in., then the 4 in. limit can be increased as permitted by Eq. (18.7.5.3). The spacing limit as a function of the longitudinal bar diameter is intended to provide adequate longitudinal bar restraint to control buckling after spalling.

R18.7.5.4 The effect of helical (spiral) reinforcement and adequately configured rectilinear hoop reinforcement on deformation capacity of columns is well established (Sakai and Sheikh 1989). Expressions (a), (b), (d), and (e) in Table 18.7.5.4 have historically been used in ACI 318 to calculate the required confinement reinforcement to ensure that spalling of shell concrete does not result in a loss of column axial load strength. Expressions (c) and (f) were developed from a review of column test data (Elwood et al. 2009) and are intended to result in columns capable of sustaining a drift ratio of 0.03 with limited strength degradation. Expressions (c) and (f) are triggered for axial load greater than $0.3A_g f'_c$, which corresponds approximately to the onset of compression-controlled behavior for symmetrically reinforced columns. The k_n term (Paultre and Légeron 2008) decreases the required confinement for columns with closely spaced, laterally supported longitudinal reinforcement because such columns are more effectively confined than columns with more widely spaced longitudinal reinforcement. The k_f term increases the required confinement for columns with $f'_c > 10,000$ psi because such columns can experience brittle failure if not well confined. Concrete strengths greater than 15,000 psi should be used with caution given the limited test data for such columns. The concrete strength used to determine the confinement reinforcement is required to be the same as that specified in the construction documents.

Expressions (a), (b), and (c) in Table 18.7.5.4 are to be satisfied in both cross-sectional directions of the rectangular core. For each direction, b_c is the core dimension perpendicular to the tie legs that constitute A_{sh} , as shown in Fig. R18.7.5.2.

Research results indicate that high strength reinforcement can be used effectively as confinement reinforcement. Section 20.2.2.4 permits a value of f_{yt} as high as 100,000 psi to be used in Table 18.7.5.4.

CODE

18.7.5.5 Beyond the length ℓ_o given in 18.7.5.1, the column shall contain spiral reinforcement satisfying 25.7.3 or hoop and crosstie reinforcement satisfying 25.7.2 and 25.7.4 with spacing s not exceeding the least of 6 in., $6d_b$ of the smallest Grade 60 longitudinal column bar, and $5d_b$ of the smallest Grade 80 longitudinal column bar, unless a greater amount of transverse reinforcement is required by 18.7.4.4 or 18.7.6.

18.7.5.6 Columns supporting reactions from discontinued stiff members, such as walls, shall satisfy (a) and (b):

(a) Transverse reinforcement required by 18.7.5.2 through 18.7.5.4 shall be provided over the full height at all levels beneath the discontinuity if the factored axial compressive force in these columns, related to earthquake effect, exceeds $A_g f_c' / 10$. Where design forces have been magnified to account for the overstrength of the vertical elements of the seismic-force-resisting system, the limit of $A_g f_c' / 10$ shall be increased to $A_g f_c' / 4$.

(b) Transverse reinforcement shall extend into the discontinued member at least ℓ_d of the largest longitudinal column bar, where ℓ_d is in accordance with 18.8.5. Where the lower end of the column terminates on a wall, the required transverse reinforcement shall extend into the wall at least ℓ_d of the largest longitudinal column bar at the point of termination. Where the column terminates on a footing or mat, the required transverse reinforcement shall extend at least 12 in. into the footing or mat.

18.7.5.7 If the concrete cover outside the confining transverse reinforcement required by 18.7.5.1, 18.7.5.5, and 18.7.5.6 exceeds 4 in., additional transverse reinforcement having cover not exceeding 4 in. and spacing not exceeding 12 in. shall be provided.

18.7.6 Shear strength**18.7.6.1 Design forces**

18.7.6.1.1 The design shear force V_e shall be calculated from considering the maximum forces that can be generated at the faces of the joints at each end of the column. These joint forces shall be calculated using the maximum probable flexural strengths, M_{pr} , at each end of the column associated with the range of factored axial forces, P_u , acting on the column. The column shears need not exceed those calculated from joint strengths based on M_{pr} of the beams framing into the joint. In no case shall V_e be less than the factored shear calculated by analysis of the structure.

COMMENTARY

R18.7.5.5 This provision is intended to provide reasonable protection to the midheight of columns outside the length ℓ_o . Observations after earthquakes have shown significant damage to columns in this region, and the minimum hoops or spirals required should provide more uniform strength of the column along its length.

R18.7.5.6 Columns supporting discontinued stiff members, such as walls or trusses, may develop considerable inelastic response. Therefore, it is required that these columns have the specified reinforcement throughout their length. This covers all columns beneath the level at which the stiff member has been discontinued, unless the factored forces corresponding to earthquake effect are low. Refer to R18.12.7.6 for discussion of the overstrength factor Ω_o .

R18.7.5.7 The unreinforced shell may spall as the column deforms to resist earthquake effects. Separation of portions of the shell from the core caused by local spalling creates a falling hazard. The additional reinforcement is required to reduce the risk of portions of the shell falling away from the column.

R18.7.6 Shear strength**R18.7.6.1 Design forces**

R18.7.6.1.1 The procedures of 18.6.5.1 also apply to columns. Above the ground floor, the moment at a joint may be limited by the flexural strength of the beams framing into the joint. Where beams frame into opposite sides of a joint, the combined strength is the sum of the negative moment strength of the beam on one side of the joint and the positive moment strength of the beam on the other side of the joint. Moment strengths are to be determined using a strength reduction factor of 1.0 and reinforcement with an effective yield stress equal to at least $1.25f_y$. Distribution of the combined moment strength of the beams to the columns above and below the joint should be based on analysis.

CODE

COMMENTARY

18.7.6.2 *Transverse reinforcement*

18.7.6.2.1 Transverse reinforcement over the lengths ℓ_o , given in 18.7.5.1, shall be designed to resist shear assuming $V_c = 0$ when both (a) and (b) occur:

- (a) The earthquake-induced shear force, calculated in accordance with 18.7.6.1, is at least one-half of the maximum required shear strength within ℓ_o .
- (b) The factored axial compressive force P_u including earthquake effects is less than $A_g f_c' / 20$.

18.8—Joints of special moment frames**18.8.1** *Scope*

18.8.1.1 This section shall apply to beam-column joints of special moment frames forming part of the seismic-force-resisting system.

18.8.2 *General*

18.8.2.1 Forces in longitudinal beam reinforcement at the joint face shall be calculated assuming that the stress in the flexural tensile reinforcement is $1.25f_y$.

18.8.2.2 Longitudinal reinforcement terminated in a joint shall extend to the far face of the joint core and shall be developed in tension in accordance with 18.8.5.

18.8.2.3 Where longitudinal beam reinforcement extends through a beam-column joint, the depth h of the joint parallel to the beam longitudinal reinforcement shall be at least the greatest of (a) through (c):

- (a) $(20/\lambda)d_b$ of the largest Grade 60 longitudinal bar, where $\lambda = 0.75$ for lightweight concrete and 1.0 for all other cases
- (b) $26d_b$ of the largest Grade 80 longitudinal bar
- (c) $h/2$ of any beam framing into the joint and generating joint shear as part of the seismic-force-resisting system in the direction under consideration

R18.8—Joints of special moment frames**R18.8.2** *General*

Development of inelastic rotations at the faces of joints of reinforced concrete frames is associated with strains in the flexural reinforcement well in excess of the yield strain. Consequently, joint shear force generated by the flexural reinforcement is calculated for a stress of $1.2f_y$ in the reinforcement (refer to 18.8.2.1). A detailed explanation of the reasons for the possible development of stresses in excess of the yield strength in beam tensile reinforcement is provided in [ACI PRC-352](#).

R18.8.2.2 The design provisions for hooked bars in special moment frames are based mainly on research and experience for joints with standard 90-degree hooks. Therefore, standard 90-degree hooks generally are preferred to standard 180-degree hooks unless unusual considerations dictate use of 180-degree hooks. Prior to the 2025 edition of the Code, it was required to check compression development length of longitudinal reinforcement. Assessment of experimental data indicates this check is unnecessary to achieve satisfactory joint behavior ([Uzumeri and Seckin 1974](#); [Kang et al. 2009](#)).

R18.8.2.3 Depth h of the joint is defined in Fig. R15.5.2.2. The column dimension parallel to the beam reinforcement in joints with circular columns may be taken as that of a square section of equivalent area. Research ([Meinheit and Jirsa 1977](#); [Briss et al. 1978](#); [Ehsani 1982](#); [Durrani and Wight 1982](#); [Leon 1989](#); [Aoyama 2001](#); [Lin et al. 2000](#)) has shown that straight longitudinal beam bars may slip within the beam-column joint during a series of large moment reversals. The bond stresses on these straight bars may be very large. To reduce slip substantially during the formation of

CODE

18.8.2.3.1 Concrete used in joints with Grade 80 longitudinal reinforcement shall be normalweight concrete.

18.8.3 Transverse reinforcement

18.8.3.1 Joint transverse reinforcement shall satisfy 18.7.5.2, 18.7.5.3, 18.7.5.4, and 18.7.5.7, except as permitted in 18.8.3.2.

18.8.3.2 Where beams frame into all four sides of the joint and where each beam width is at least three-fourths the column width, the amount of reinforcement required by 18.7.5.4 shall be permitted to be reduced by one-half, and the spacing required by 18.7.5.3 shall be permitted to be increased to 6 in. within the overall depth h of the shallowest framing beam.

18.8.3.3 Longitudinal beam reinforcement outside the column core shall be confined by transverse reinforcement passing through the column that satisfies spacing requirements of 18.6.4.4, and requirements of 18.6.4.2, and 18.6.4.3, if such confinement is not provided by a beam framing into the joint.

COMMENTARY

adjacent beam hinging, it would be necessary to have a ratio of column dimension to bar diameter of approximately 32 for Grade 60 bars, which would result in very large joints. Tests demonstrate adequate behavior if the ratio of joint depth to maximum beam longitudinal bar diameter for Grade 60 reinforcement is at least 20 for normalweight concrete and 26 for lightweight concrete. A joint depth of $26d_b$ for Grade 80 reinforcement is intended to achieve similar performance to that of a joint depth of $20d_b$ for Grade 60 reinforcement and normalweight concrete. The limits on joint depth provide reasonable control on the amount of slip of the beam bars in a beam-column joint, considering the number of anticipated inelastic excursions of the building frame during a major earthquake. A thorough treatment of this topic is given in [Zhu and Jirsa \(1983\)](#).

Requirement (c) on joint aspect ratio applies only to beams that are designated as part of the seismic-force-resisting system. Joints having depth less than half the beam depth require a steep diagonal compression strut across the joint, which may be less effective in resisting joint shear. Tests to demonstrate performance of such joints have not been reported in the literature.

R18.8.2.3.1 Test data justifying the combination of lightweight concrete and Grade 80 longitudinal reinforcement in joints are not available.

R18.8.3 Transverse reinforcement

The Code requires transverse reinforcement in a joint regardless of the magnitude of the calculated shear force.

R18.8.3.2 The amount of confining reinforcement may be reduced and the spacing may be increased if beams of adequate dimensions frame into all four sides of the joint.

R18.8.3.3 The required transverse reinforcement, or transverse beam if present, is intended to confine the beam longitudinal reinforcement and improve force transfer to the beam-column joint.

An example of transverse reinforcement through the column provided to confine the beam reinforcement passing outside the column core is shown in Fig. R18.6.2. Additional detailing guidance and design recommendations for both interior and exterior wide-beam connections with beam reinforcement passing outside the column core may be found in [ACI PRC-352](#).

CODE

18.8.4 Shear strength

COMMENTARY

R18.8.4 Shear strength

The shear strength values given in 18.8.4.3 are based on the recommendation in **ACI PRC-352** for joints with members that are expected to undergo reversals of deformation into the inelastic range, although the ACI PRC-352 definition of effective cross-sectional joint area is sometimes different. The given nominal joint shear strengths do not explicitly consider transverse reinforcement in the joint because tests of joints (**Meinheit and Jirsa 1977**) and deep beams (**Hiro-sawa 1977**) have indicated that joint shear strength is not sensitive to transverse reinforcement if at least the required minimum amount is provided in the joint.

Cyclic loading tests of joints with extensions of beams with lengths at least equal to their depths have indicated similar joint shear strengths to those of joints with continuous beams. These findings suggest that extensions of beams and columns, when properly dimensioned and reinforced with longitudinal and transverse bars, provide effective confinement to the joint faces, thus delaying joint strength deterioration at large deformations (**Meinheit and Jirsa 1981**).

18.8.4.1 Joint shear force V_u shall be calculated on a plane at mid-height of the joint from calculated forces at the joint faces using tensile and compressive beam forces determined in accordance with 18.8.2.1 and column shear consistent with beam probable flexural strengths M_{pr} .

18.8.4.2 ϕ shall be in accordance with **21.2.4.4**.

18.8.4.3 V_n of the joint shall be in accordance with Table 18.8.4.3.

Table 18.8.4.3—Nominal joint shear strength V_n

Column	Beam in direction of V_u	Confinement by transverse beams according to 15.5.2.5	V_n , lb ^[1]
Continuous or meets 15.5.2.3	Continuous or meets 15.5.2.4	Confined	$20\lambda\sqrt{f'_c}A_j$
		Not confined	$15\lambda\sqrt{f'_c}A_j$
	Other	Confined	$15\lambda\sqrt{f'_c}A_j$
		Not confined	$12\lambda\sqrt{f'_c}A_j$
Other	Continuous or meets 15.5.2.4	Confined	$15\lambda\sqrt{f'_c}A_j$
		Not confined	$12\lambda\sqrt{f'_c}A_j$
	Other	Confined	$12\lambda\sqrt{f'_c}A_j$
		Not confined	$8\lambda\sqrt{f'_c}A_j$

^[1] λ shall be 0.75 for lightweight concrete and 1.0 for normalweight concrete. A_j shall be calculated in accordance with 15.5.2.2.

18.8.5 Development length of bars in tension

18.8.5.1 For bar sizes No. 3 through No. 11 terminating in a standard hook, ℓ_{dh} shall be calculated by Eq. (18.8.5.1), but ℓ_{dh} shall be at least the greater of $8d_b$ and 6 in. for normal-

R18.8.5 Development length of bars in tension

R18.8.5.1 Minimum embedment length in tension for deformed bars with standard hooks is determined using Eq. (18.8.5.1), which is based on the requirements of 25.4.3 of **ACI 318-14**. The embedment length of a bar with a stan-

CODE

weight concrete and at least the greater of $10d_b$ and 7-1/2 in. for lightweight concrete.

$$\ell_{dh} = f_y d_b / (65 \lambda \sqrt{f'_c}) \quad (18.8.5.1)$$

The value of λ shall be 0.75 for concrete containing lightweight aggregate and 1.0 otherwise.

The hook shall be located within the confined core of a column or of a boundary element, with the hook bent into the joint.

18.8.5.2 Headed deformed bars satisfying 20.2.1.6 shall develop $1.25f_y$ in tension in accordance with 25.4.4 by substituting a bar stress of $1.25f_y$ for f_y .

18.8.5.3 For bar sizes No. 3 through No. 11, ℓ_d , the development length in tension for a straight bar, shall be at least the greater of (a) and (b):

- (a) 2.5 times the length in accordance with 18.8.5.1 if the depth of the concrete cast in one lift beneath the bar does not exceed 12 in.
- (b) 3.25 times the length in accordance with 18.8.5.1 if the depth of the concrete cast in one lift beneath the bar exceeds 12 in.

18.8.5.4 Straight bars terminated at a joint shall pass through the confined core of a column or a boundary element. Any portion of ℓ_d not within the confined core shall be increased by a factor of 1.6.

COMMENTARY

Standard hook is the distance, parallel to the bar, from the critical section (where the bar is to be developed) to a tangent drawn to the outside edge of the hook. The tangent is to be drawn perpendicular to the axis of the bar (refer to Table 25.3.1).

Equation (18.8.5.1) was derived from the equation for development length ℓ_{dh} in 25.4.3 of ACI 318-14 using coefficients of 1.0 (no epoxy coating), 0.7 (cover) and 0.8 (confinement reinforcement) because Chapter 18 stipulates that the hook is to be embedded in confined concrete. The development length that would be derived directly from 25.4.3 in ACI 318-14 was increased to reflect the effect of load reversals. Factors such as the actual stress in the reinforcement being more than the yield strength and the effective development length not necessarily starting at the face of the joint were implicitly considered in the formulation of the expression for basic development length that has been used as the basis for Eq. (18.8.5.1).

The requirement for the hook to project into the joint is to improve development of a diagonal compression strut across the joint. The requirement applies to beam and column bars terminated at a joint with a standard hook, preferably a standard 90-degree hook.

R18.8.5.2 The factor 1.25 is intended to represent the potential increase in stresses due to inelastic response, including strain hardening that may occur in beams of special moment frames.

R18.8.5.3 Minimum development length in tension for straight bars is a multiple of the length indicated by 18.8.5.1. Section 18.8.5.3(b) refers to top bars. Lack of reference to No. 14 and No. 18 bars in 18.8.5 is due to the paucity of information on anchorage of such bars subjected to load reversals simulating earthquake effects.

R18.8.5.4 If the required straight embedment length of a reinforcing bar extends beyond the confined volume of concrete (as defined in 18.6.4, 18.7.5, or 18.8.3), the required development length is increased on the premise that the limiting bond stress outside the confined region is less than that inside.

$$\ell = 1.6(\ell_d - \ell_{dc}) + \ell_{dc}$$

or

$$\ell_{dm} = 1.6\ell_d - 0.6\ell_{dc}$$

where ℓ_{dm} is the required development length if bar is not entirely embedded in confined concrete; ℓ_d is the required development length in tension for straight bar as defined in 18.8.5.3; and ℓ_{dc} is the length of bar embedded in confined concrete.

CODE

18.8.5.5 If epoxy-coated reinforcement is used, the development lengths in 18.8.5.1, 18.8.5.3, and 18.8.5.4 shall be multiplied by applicable factors in 25.4.2.5 or 25.4.3.2.

18.9—Special moment frames constructed using precast concrete

COMMENTARY

R18.9—Special moment frames constructed using precast concrete

The detailing provisions in 18.9.2.1 and 18.9.2.2 are intended to produce frames that respond to design displacements essentially like monolithic special moment frames.

Precast frame systems composed of concrete elements with ductile connections are expected to experience flexural yielding in connection regions (Yoshioka and Sekine 1991; Kurose et al. 1991; Restrepo et al. 1995a,b). The restriction on location of mechanical splices is intended to avoid strain concentrations over a short length of reinforcement adjacent to a splice device. Additional requirements for shear strength are provided in 18.9.2.1 to prevent sliding on connection faces. Precast frames composed of elements with ductile connections may be designed to promote yielding at locations not adjacent to the joints. Therefore, design shear V_e , as calculated according to 18.6.5.1 or 18.7.6.1, may not be conservative.

Precast concrete frame systems composed of elements joined using strong connections are intended to experience flexural yielding outside the connections. Strong connections include the length of the mechanical splice hardware as shown in Fig. R18.9.2.2. Capacity-design techniques are used in 18.9.2.2(c) to ensure the strong connection remains elastic following formation of plastic hinges. Additional column requirements are provided to avoid hinging and strength deterioration of column-to-column connections.

Strain concentrations have been observed to cause brittle fracture of reinforcing bars at the face of mechanical splices in laboratory tests of precast beam-column connections (Palmieri et al. 1996). Locations of strong connections should be selected carefully or other measures should be taken, such as debonding of reinforcing bars in highly stressed regions, to avoid strain concentrations that can result in premature fracture of reinforcement.

18.9.1 Scope

18.9.1.1 This section shall apply to special moment frames constructed using precast concrete forming part of the seismic-force-resisting system.

18.9.2 General

18.9.2.1 Special moment frames with ductile connections constructed using precast concrete shall satisfy (a) through (c):

- (a) Requirements of 18.6 through 18.8 for special moment frames constructed with cast-in-place concrete
- (b) V_n for connections calculated according to 22.9 shall be at least $2V_e$, where V_e is in accordance with 18.6.5.1 or 18.7.6.1


R18.9.2 General

CODE


(c) Mechanical splices of beam reinforcement shall be located not closer than $h/2$ from the joint face and shall be Class S.

18.9.2.2 Special moment frames with strong connections constructed using precast concrete shall satisfy (a) through (e):


- (a) Requirements of 18.6 through 18.8 for special moment frames constructed with cast-in-place concrete
- (b) Provision 18.6.2.1(a) shall apply to segments between locations where flexural yielding is intended to occur due to design displacements
- (c) Design strength of the strong connection, ϕS_n , shall be at least S_e
- (d) Primary longitudinal reinforcement shall be made continuous across connections and shall be developed outside both the strong connection and the plastic hinge region
- (e) For column-to-column connections, ϕS_n shall be at least $1.4S_e$, ϕM_n shall be at least $0.4M_{pr}$ for the column within the story height, and ϕV_n shall be at least V_e in accordance with 18.7.6.1

COMMENTARY


(a) Beam-to-beam connection



(b) Beam-to-column connection



(c) Beam-to-column connection



(d) Column-to-footing connection

Fig. R18.9.2.2—Strong connection examples.

18.9.2.3 Special moment frames constructed using precast concrete and not satisfying 18.9.2.1 or 18.9.2.2 shall satisfy (a) through (c):

- (a) **ACI CODE-374.1**

R18.9.2.3 Precast frame systems not satisfying the prescriptive requirements of Chapter 18 have been demonstrated in experimental studies to provide satisfactory seismic performance characteristics (Stone et al. 1995; Nakaki et al. 1999). ACI CODE-374.1 defines a protocol for establishing

CODE

(b) Details and materials used in the test specimens shall be representative of those used in the structure

(c) The design procedure used to proportion the test specimens shall define the mechanism by which the frame resists gravity and earthquake effects, and shall establish acceptance values for sustaining that mechanism. Portions of the mechanism that deviate from Code requirements shall be contained in the test specimens and shall be tested to determine upper bounds for acceptance values.

COMMENTARY

a design procedure, validated by analysis and laboratory tests, for such frames. The design procedure should identify the load path or mechanism by which the frame resists gravity and earthquake effects. The tests should be configured to investigate critical behaviors, and the measured quantities should establish upper-bound acceptance values for components of the load path, which may be in terms of limiting stresses, forces, strains, or other quantities. The design procedure used for the structure should not deviate from that used to design the test specimens, and acceptance values should not exceed values that were demonstrated by the tests to be acceptable. Materials and components used in the structure should be similar to those used in the tests. Deviations may be acceptable if the licensed design professional can demonstrate that those deviations do not adversely affect the behavior of the framing system.

ACI CODE-550.3 defines design requirements for one type of special precast concrete moment frame for use in accordance with 18.9.2.3.

18.10—Special structural walls**18.10.1 Scope****R18.10—Special structural walls****R18.10.1 Scope**

This section contains requirements for the dimensions and details of special structural walls and all components including coupling beams and wall piers. Wall piers are defined in **Chapter 2**. Design provisions for vertical wall segments depend on the aspect ratio of the wall segment in the plane of the wall (h_w/ℓ_w), and the aspect ratio of the horizontal cross section (ℓ_w/b_w), and generally follow the descriptions in Table R18.10.1. The limiting aspect ratios for wall piers are based on engineering judgment. It is intended that flexural yielding of the vertical reinforcement in the pier should limit shear demand on the pier.

Bearing wall systems utilizing special structural walls with $h_{wcs}/\ell_w \geq 2.0$ that are designed and detailed according to these provisions are expected to meet the seismic performance objectives of Building Frame Systems: Special reinforced concrete shear walls as defined by **ASCE/SEI 7**.

Table R18.10.1—Governing design provisions for vertical wall segments^[1]

Clear height of vertical wall segment/length of vertical wall segment (h_w/ℓ_w)	Length of vertical wall segment/wall thickness (ℓ_w/b_w)		
	$(\ell_w/b_w) \leq 2.5$	$2.5 < (\ell_w/b_w) \leq 6.0$	$(\ell_w/b_w) > 6.0$
$h_w/\ell_w < 2.0$	Wall	Wall	Wall
$h_w/\ell_w \geq 2.0$	Wall pier required to satisfy specified column design requirements; refer to 18.10.8.1	Wall pier required to satisfy specified column design requirements or alternative requirements; refer to 18.10.8.1	Wall

^[1] h_w is the clear height, ℓ_w is the horizontal length, and b_w is the width of the web of the wall segment.

CODE

18.10.1.1 This section shall apply to special structural walls, including ductile coupled walls, and all components of special structural walls including coupling beams and wall piers forming part of the seismic-force-resisting system.

18.10.1.2 Special structural walls constructed using precast concrete shall be in accordance with 18.11 in addition to 18.10.

18.10.2 Reinforcement

18.10.2.1 The distributed web reinforcement ratios, ρ_t and ρ_v , for structural walls shall be at least 0.0025, except that if V_u does not exceed $\lambda\sqrt{f'_c}A_{cv}$, ρ_t shall be permitted to be reduced to the values in 11.6. Reinforcement spacing each way in structural walls shall not exceed 18 in. Reinforcement contributing to V_n shall be continuous and shall be distributed across the shear plane.

18.10.2.2 At least two curtains of reinforcement shall be used in a wall if $V_u > 2\lambda\sqrt{f'_c}A_{cv}$ or $h_w/\ell_w \geq 2.0$, in which h_w and ℓ_w refer to height and length of entire wall, respectively.

18.10.2.3 Reinforcement in structural walls shall be developed or spliced for f_y in tension in accordance with 25.4, 25.5, and (a) through (d):

- (a) Except at the top of a wall, longitudinal reinforcement shall extend at least 12 ft above the point at which it is no longer required to resist flexure but need not extend more than ℓ_d above the next floor level.
- (b) At locations where yielding of longitudinal reinforcement is likely to occur as a result of lateral displacements, longitudinal reinforcement shall develop $1.25f_y$ in tension in accordance with 25.4 by substituting a bar stress of $1.25f_y$ for f_y .
- (c) Lap splices of longitudinal reinforcement within boundary regions shall not be permitted over a height equal to h_{sx} above, and ℓ_d below, critical sections where yielding of longitudinal reinforcement is likely to occur

COMMENTARY

R18.10.2 Reinforcement

Minimum reinforcement requirements in 18.10.2.1 follow from preceding Codes. The requirement for distributed shear reinforcement is related to the intent to control the width of inclined cracks. The requirement for two layers of reinforcement in walls resisting substantial design shears in 18.10.2.2 is based on the observation that, under ordinary construction conditions, the probability of maintaining a single layer of reinforcement near the middle of the wall section is quite low. Furthermore, presence of reinforcement close to the surface tends to inhibit fragmentation of the concrete in the event of severe cracking during an earthquake. The requirement for two layers of vertical reinforcement in more slender walls is to improve lateral stability of the compression zone under cyclic loads following yielding of vertical reinforcement in tension.

R18.10.2.3 Requirements are based on provisions in Chapter 25, with modifications to address issues specific to structural walls, as well as to the use of high-strength reinforcement. Because actual forces in longitudinal reinforcement of structural walls may exceed calculated forces, reinforcement should be developed or spliced to reach the yield strength of the bar in tension. Termination of longitudinal (vertical) reinforcement in structural walls should be specified so that bars extend above elevations where they are no longer required to resist design flexure and axial force; extending bars ℓ_d above the next floor level is a practical approach to achieving this requirement. A limit of 12 ft is included for cases with large story heights. Bar terminations should be accomplished gradually over a wall height and should not be located close to critical sections where yielding of longitudinal reinforcement is expected,

CODE

as a result of lateral displacements. The value of h_{sx} need not exceed 20 ft. Boundary regions include those within lengths specified in 18.10.6.4(a) and within a length equal to the wall thickness measured beyond the intersecting region(s) of connected walls.


(d) Mechanical splices of reinforcement shall conform to 18.2.7 and welded splices of reinforcement shall conform to 18.2.8.

COMMENTARY

which typically occurs at the base of a wall with a uniform, or nearly uniform, cross section over the building height. Strain hardening of reinforcement results in spread of plasticity away from critical sections as lateral deformations increase. Research (Aaleti et al. 2013; Hardisty et al. 2015) shows that lap splices should be avoided in walls where flexural yielding is anticipated, for example at the base of walls, because they may lead to large localized strains and bar fractures. Figure R18.10.2.3 illustrates boundary regions where lap splices are not permitted.


At locations where yielding of longitudinal reinforcement is expected, the reinforcement is developed for $1.25f_y$ to account for the likelihood that the actual yield strength exceeds the specified yield strength of the bar, as well as the influence of strain hardening and cyclic load reversals. Where transverse reinforcement is used, development lengths for straight and hooked bars may be reduced as permitted in 25.4.2 and 25.4.3, respectively, because closely spaced transverse reinforcement improves the performance of splices and hooks subjected to repeated inelastic demands (ACI PRC-408.2).





Note: For clarity, only the required reinforcement is shown

(a) Elevation



(b) Section A-A

Fig. R18.10.2.3—Wall boundary regions within heights where lap splices are not permitted.

18.10.2.4 Walls or wall piers with $h_w/\ell_w \geq 2.0$ that are effectively continuous from the base of structure to top of wall and are designed to have a single critical section for

R18.10.2.4 This provision is based on the assumption that inelastic response of the wall is dominated by flexural action at a critical, yielding section. The wall should be propor-

CODE

flexure and axial loads shall have longitudinal reinforcement at the ends of a vertical wall segment that satisfies (a) through (c).

- (a) Longitudinal reinforcement ratio within $0.15\ell_w$ from the end of a vertical wall segment, and over a width equal to the wall thickness, shall be at least $6\sqrt{f'_c}/f_y$.
- (b) The longitudinal reinforcement required by 18.10.2.4(a) shall extend vertically above and below the critical section at least the greater of ℓ_w and $M_u/3V_u$.
- (c) No more than 50% of the reinforcement required by 18.10.2.4(a) shall be terminated at any one section.

COMMENTARY

tioned so that the critical section occurs where intended. If there is potential for more than one critical section, it is prudent to provide the minimum boundary reinforcement at all such sections.

The requirement for minimum longitudinal reinforcement in the ends of the wall is to promote the formation of well-distributed secondary flexural cracks in the wall plastic hinge region to achieve the required deformation capacity during earthquakes (Lu et al. 2017; Sritharan et al. 2014). Furthermore, significantly higher in-place concrete strengths than used in design calculations may be detrimental to the distribution of cracking. 18.10.2.4(a) specifies the required reinforcement ratio in the end tension zones, as shown for different wall sections in Fig. R18.10.2.4.

The longitudinal reinforcement required by 18.10.2.4(a) should be located at a critical section where concentrated yielding of longitudinal reinforcement is expected (typically the base of a cantilever wall) and must continue to a sufficient elevation of the wall to avoid a weak section adjacent to the intended plastic hinge region. A height above or below the critical section of $M_u/3V_u$ is used to identify the length over which yielding is expected.




Fig. R18.10.2.4—Locations of longitudinal reinforcement required by 18.10.2.4(a) in different configurations of wall sections.

- 18.10.2.5** Reinforcement in coupling beams shall develop f_y in tension in accordance with 25.4, 25.5, and (a) and (b):
- (a) If coupling beams are reinforced according to 18.6.3.1, longitudinal reinforcement shall develop $1.25f_y$ in tension in accordance with 25.4.
 - (b) If coupling beams are reinforced according to 18.10.7.4, diagonal reinforcement shall develop $1.25f_y$ in tension in accordance with 25.4.

CODE

18.10.3 *Design forces*

COMMENTARY

R18.10.3 *Design forces*

Numerous studies (Priestley et al. 2007; Pugh et al. 2017; Rodriguez et al. 2002) have shown that the actual shear experienced by a structural wall subjected to a design-basis earthquake may be greater than the shear obtained from linear analysis of the structure under code-prescribed earthquake-induced forces. The procedures of 18.10.3 may amplify wall shear for some walls designed by linear analysis methods. The amplification factors do not apply to wall piers (refer to 2.3 and Table R18.10.1) or horizontal wall segments including coupling beams because alternative approaches to determine design shears for those components are specified in 18.10.7, 18.10.8, and 21.2.4.1. Design shears determined by linear analysis procedures of the general building code are increased to account for (i) flexural overstrength at critical sections where yielding of longitudinal reinforcement is anticipated, as represented by the factor Ω_v , and (ii) dynamic amplification due to higher-mode effects, as represented by the factor ω_v (refer to Fig. R18.10.3.3). The factors apply only to the portion of wall shear V_{uEh} due to the horizontal seismic load effect E_h specified in the general building code. Design shear generally will be controlled by load combinations 5.3.1(e) or 5.3.1(g) in Table 5.3.1, whichever produces the greater value of design shear V_e .

18.10.3.1 Design shear forces for horizontal wall segments, including coupling beams, shall be in accordance with 18.10.7.

18.10.3.2 Design shear forces for wall piers shall be in accordance with 18.10.8.

18.10.3.3 Design shear forces for parts of walls not covered by 18.10.3.1 or 18.10.3.2 shall be in accordance with the requirements of 18.10.3.3.1 through 18.10.3.3.5.

CODE

COMMENTARY




Fig. R18.10.3.3—Determination of shear demand for walls with $h_w/\ell_w \geq 2.0$ (Moehle et al. 2011).

18.10.3.3.1 If the wall design actions are determined in accordance with nonlinear dynamic analysis procedures satisfying **Appendix A**, design shear forces shall be as determined in **Appendix A**.

18.10.3.3.2 If V_{uEh} is determined by linear analysis procedures of the general building code, it shall be amplified by the product $\Omega_v \omega_v$, where Ω_v and ω_v are defined in 18.10.3.3.3 through 18.10.3.3.5.

18.10.3.3.3 Ω_v and ω_v shall be in accordance with **Table 18.10.3.3.3**. Alternatively, it shall be permitted to calculate $\Omega_v = M_{pr}/M_u$ at the critical section for flexure, where M_{pr} is calculated for axial force that includes the effects of E and the expected gravity loads, with expected gravity loads in accordance with **ASCE/SEI 7** Section 16.3.2.

Table 18.10.3.3.3—Factors Ω_v and ω_v

Condition	Ω_v	ω_v
$h_{wcs}/\ell_w \leq 1.0$	1.0	1.0
$1.0 < h_{wcs}/\ell_w < 2.0$	Linear interpolation permitted between 1.0 and 1.5	
$h_{wcs}/\ell_w \geq 2.0$	1.5	$0.8 + 0.09 h_n^{1/3} \geq 1.0$

R18.10.3.3.3 The factor Ω_v is intended to approximate the flexural overstrength ratio M_{pr}/M_u of the wall critical section, with M_{pr} based on axial forces due to E and expected gravity loads as specified in **ASCE/SEI 7**. While it is permitted to calculate this ratio directly from analysis of the wall critical section, **Table 18.10.3.3.3** provides a simpler alternative. For walls with $h_{wcs}/\ell_w \leq 1.0$, a value of $\Omega_v = 1$ is permitted because low-aspect-ratio walls are unlikely to develop extensive flexural yielding. For walls with $h_{wcs}/\ell_w \geq 2.0$, yielding of the wall critical section is likely to produce flexural overstrength. The value of $\Omega_v = 1.5$ assumes that the wall is proportioned for moment strength using a strength reduction factor $\phi = 0.9$, that the provided moment strength ϕM_n closely matches the required moment strength M_u , and that longitudinal reinforcement reaches a tensile stress of $1.25f_y$ under earthquake shaking.

The dynamic amplification factor ω_v is derived from the similar factor in **New Zealand Standard 3101 (2006)**. Dynamic amplification is not significant in walls with $h_{wcs}/\ell_w < 2$.

Design shear forces are amplified over the entire wall height, including portions of the wall below the critical section.

CODE

18.10.3.3.4 If the general building code includes provisions to account for overstrength of the seismic-force-resisting system, it shall be permitted to take $\Omega_v\omega_v$ equal to Ω_o .

18.10.3.3.5 If $\Omega_v\omega_v = \Omega_o$, it shall be permitted to take the redundancy factor contained in the general building code equal to 1.0 for determination of V_{uEh} .

18.10.4 Shear strength

COMMENTARY

R18.10.3.3.5 Consistent with **ASCE/SEI 7**, it is permitted to take the redundancy factor as 1.0 where member design is for seismic load effects including the overstrength factor Ω_o .

R18.10.4 Shear strength

Equation (18.10.4.1) recognizes the higher shear strength of walls with lower moment-to-shear ratios (**Hirosawa 1977**; **Joint ACI-ASCE Committee 326 [1962]**; **Barda et al. 1977**; **Rojas-Leon et al. 2024**). The nominal shear strength is given in terms of the gross area of the section resisting shear, A_{cv} . For a rectangular section without openings, the term A_{cv} refers to the gross area of the cross section rather than to the product of the width and the effective depth.

In **ACI CODE-318-19** Section 18.10.4, no limit was specified on the value of $\sqrt{f'_c}$. The limit on f'_c of 12,000 psi is based on review of test data for walls subjected to cyclic loading by **Rojas-Leon et al. (2024)**.

A vertical wall segment refers to a part of a wall bounded horizontally by openings or by an opening and an edge. For an isolated wall or a vertical wall segment, ρ_t refers to horizontal reinforcement and ρ_ℓ refers to vertical reinforcement.

The ratio h_w/ℓ_w may refer to overall dimensions of a wall, or of a segment of the wall bounded by two openings, or an opening and an edge. The intent of 18.10.4.2 is to make certain that any segment of a wall is not assigned a unit strength greater than that for the entire wall. However, a wall segment with a ratio of h_w/ℓ_w higher than that of the entire wall should be proportioned for the unit strength associated with the ratio h_w/ℓ_w based on the dimensions for that segment.

To restrain the inclined cracks effectively, reinforcement included in ρ_t and ρ_ℓ should be appropriately distributed along the length and height of the wall (refer to 18.10.4.3). Chord reinforcement provided near wall edges in concentrated amounts for resisting bending moment is not to be included in determining ρ_t and ρ_ℓ . Within practical limits, shear reinforcement distribution should be uniform and at a small spacing.

If the factored shear force at a given level in a structure is resisted by several walls or several vertical wall segments of a perforated wall, the average unit shear strength assumed for the total available cross-sectional area is limited to the sum of $\alpha_{sh}8\sqrt{f'_c}$ for those walls or wall segments with the additional requirement that the unit shear strength assigned to any single wall or vertical wall segment does not exceed $\alpha_{sh}10\sqrt{f'_c}$ (refer to 18.10.4.4). The upper limit of strength to be assigned to any one member is imposed to limit the degree of redistribution of shear force. The term α_{sh} accounts for the higher unit shear stress that develops prior to diagonal compression failure in a wall with a compression flange

CODE

COMMENTARY

18.10.4.1 V_n shall be calculated by:

$$V_n = (\alpha_c \lambda \sqrt{f'_c} + \rho_f f_{yt}) A_{cv} \quad (18.10.4.1)$$

where

$$\alpha_c = 3 \text{ for } h_w/\ell_w \leq 1.5$$

$$\alpha_c = 2 \text{ for } h_w/\ell_w \geq 2.0$$

It shall be permitted to linearly interpolate the value of α_c between 3 and 2 for $1.5 < h_w/\ell_w < 2.0$. The value of f'_c used in Eq. (18.10.4.1) and in 18.10.4.4 and 18.10.4.5 shall not exceed 12,000 psi.

18.10.4.2 In 18.10.4.1, the value of ratio h_w/ℓ_w used to calculate V_n for segments of a wall shall be the greater of the ratios for the entire wall and the segment of wall considered.

18.10.4.3 Walls shall have distributed shear reinforcement in two orthogonal directions in the plane of the wall. If h_w/ℓ_w does not exceed 2.0, reinforcement ratio ρ_ℓ shall be at least the reinforcement ratio ρ_t .

18.10.4.4 V_n shall not be taken greater than the sum of $\alpha_{sh} 8 \sqrt{f'_c} A_{cv}$ for all vertical wall segments sharing a common lateral force. For any one of the individual vertical wall segments, V_n shall not be taken greater than $\alpha_{sh} 10 \sqrt{f'_c} A_{cw}$, where A_{cw} is the area of concrete section of the individual vertical wall segment considered. The term α_{sh} is determined as

$$0.7 \left(1 + \frac{(b_w + b_{cf}) t_{cf}}{A_{cs}} \right)^2 \leq 1.2 \quad (18.10.4.4)$$

where b_{cf} is determined according to 18.10.5.2 and A_{cs} shall be taken as A_{cv} or A_{cw} , as applicable. The value of α_{sh} need not be taken less than 1.0. It shall be permitted to take $\alpha_{sh} = 1.0$.

(Rojas-Leon et al. 2024). If the term $b_{cf} t_{cf}$ is different at each edge (boundary) of a wall or if a flange does not exist at one end (for example, a T-shaped wall cross section), then the wall shear stress limit is evaluated independently for each load combination depending on the direction of the shear demand or the wall shear stress limit may be based on the smaller value of $b_{cf} t_{cf}$. For a barbell-shaped wall cross section, b_{cf} is the width of the boundary column minus the web width b_w and t_{cf} is the depth of the boundary column.

Horizontal wall segments in 18.10.4.5 refer to wall sections between two vertically aligned openings (refer to Fig. R18.10.4.5). It is, in effect, a vertical wall segment rotated through 90 degrees. A horizontal wall segment is also referred to as a coupling beam when the openings are aligned vertically over the building height. When designing a horizontal wall segment or coupling beam, ρ_t refers to vertical reinforcement and ρ_ℓ refers to horizontal reinforcement.

CODE

18.10.4.5 For horizontal wall segments and coupling beams, V_n shall not be taken greater than $10\sqrt{f'_c}A_{cw}$, where A_{cw} is the area of concrete section of a horizontal wall segment or coupling beam.

COMMENTARY




Fig. R18.10.4.5—Wall with openings.

18.10.5 Design for flexure and axial force

18.10.5.1 Structural walls and portions of such walls subject to combined flexure and axial loads shall be designed in accordance with 22.4. Concrete and developed longitudinal reinforcement within effective flange widths, boundary elements, and the wall web shall be considered effective. The effects of openings shall be considered.

18.10.5.2 Unless a more detailed analysis is performed, effective flange widths of flanged sections shall extend from the face of the web a distance equal to the lesser of one-half the distance to an adjacent wall web and 25% of the total wall height above the section under consideration.

18.10.6 Boundary elements of special structural walls

18.10.6.1 The need for special boundary elements at the edges of structural walls shall be evaluated in accordance with 18.10.6.2 or 18.10.6.3. The requirements of 18.10.6.4 and 18.10.6.5 shall also be satisfied.

18.10.5 Design for flexure and axial force

R18.10.5.1 Flexural strength of a wall or wall segment is determined according to procedures commonly used for columns. Strength should be determined considering the applied axial and lateral forces. Reinforcement concentrated in boundary elements and distributed in flanges and webs should be included in the strength calculations based on a strain compatibility analysis. The foundation supporting the wall should be designed to resist the wall boundary and web forces. For walls with openings, the influence of the opening or openings on flexural and shear strengths is to be considered and a load path around the opening or openings should be verified. Capacity-design concepts and the strut-and-tie method may be useful for this purpose (Taylor et al. 1998).

R18.10.5.2 Where wall sections intersect to form L-, T-, C-, or other cross-sectional shapes, the influence of the flange on the behavior of the wall should be considered by selecting appropriate flange widths. Tests (Wallace 1996) show that effective flange width increases with increasing drift level and the effectiveness of a flange in compression differs from that for a flange in tension. The value used for the effective compression flange width has little effect on the strength and deformation capacity of the wall; therefore, to simplify design, a single value of effective flange width based on an estimate of the effective tension flange width is used in both tension and compression.

18.10.6 Boundary elements of special structural walls

R18.10.6.1 Two design approaches for evaluating detailing requirements at wall boundaries are included in 18.10.6.1. Provision 18.10.6.2 allows the use of displacement-based design of walls, in which the structural details are determined directly on the basis of the expected lateral

CODE

18.10.6.2 Walls or wall piers with $h_{wcs}/\ell_w \geq 2.0$ that are effectively continuous from the base of structure to top of wall and are designed to have a single critical section for flexure and axial loads shall satisfy (a) and (b):

(a) Compression zones shall be reinforced with special boundary elements where

$$\frac{1.5\delta_u}{h_{wcs}} \geq \frac{\ell_w}{600c} \quad (18.10.6.2a)$$

and c corresponds to the largest neutral axis depth calculated for the factored axial force and nominal moment strength consistent with the direction of the design displacement δ_u . Ratio δ_u/h_{wcs} shall not be taken less than 0.005.

(b) If special boundary elements are required by (a), then (i) and either (ii) or (iii) shall be satisfied.

(i) Special boundary element transverse reinforcement shall extend vertically above and below the critical section at least the greater of ℓ_w and $M_u/4V_u$, except as permitted in 18.10.6.4(j).

(ii) $b \geq \sqrt{c\ell_w/40}$

(iii) $\delta_c/h_{wcs} \geq 1.5\delta_u/h_{wcs}$, where:

$$\frac{\delta}{h_{wcs}} = \frac{1}{100} \left(4 - \frac{1}{50} - \left(\frac{\ell_w}{b} \right) \left(\frac{c}{b} \right) - \frac{V_e}{8\sqrt{f'_c A_{cv}}} \right) \quad (18.10.6.2b)$$

The value of δ_c/h_{wcs} in Eq. (18.10.6.2b) need not be taken less than 0.015.

COMMENTARY

displacements of the wall. The provisions of 18.10.6.3 are similar to those of the 1995 Code, and have been retained because they are conservative for assessing required transverse reinforcement at wall boundaries for many walls. Provisions 18.10.6.4 and 18.10.6.5 apply to structural walls designed by either 18.10.6.2 or 18.10.6.3.

R18.10.6.2 This section is based on the assumption that inelastic response of the wall is dominated by flexural action at a critical, yielding section. The wall should be proportioned and reinforced so that the critical section occurs where intended.

Equation (18.10.6.2a) follows from a displacement-based approach (Moehle 1992; Wallace and Orakcal 2002). The approach assumes that special boundary elements are required to confine the concrete where the strain at the extreme compression fiber of the wall exceeds a critical value when the wall is displaced to 1.5 times the design displacement. Consistent with a displacement-based design approach, the design displacement in Eq. (18.10.6.2a) is taken at the top of the wall, and the wall height is taken as the height above the critical section. The multiplier of 1.5 on design displacement was added to Eq. (18.10.6.2) in the 2014 Code to produce detailing requirements more consistent with the building code performance intent of a low probability of collapse in Maximum Considered Earthquake level shaking. The lower limit of 0.005 on the quantity δ_u/h_{wcs} requires special boundary elements if wall boundary longitudinal reinforcement tensile strain does not reach approximately twice the limit used to define tension-controlled beam sections according to 21.2.2. The lower limit of 0.005 on the quantity δ_u/h_{wcs} requires moderate wall deformation capacity for stiff buildings.

The neutral axis depth c in Eq. (18.10.6.2) is the depth calculated according to 22.2 corresponding to development of nominal flexural strength of the wall when displaced in the same direction as δ_u . The axial load is the factored axial load that is consistent with the design load combination that produces the design displacement δ_u .

The height of the special boundary element is based on estimates of plastic hinge length and extends beyond the zone over which yielding of tension reinforcement and spalling of concrete are likely to occur.

Equation (18.10.6.2b) is based on the mean top-of-wall drift capacity at 20% loss of lateral strength proposed by Abdullah and Wallace (2019). The requirement that drift capacity exceed 1.5 times the drift demand results in a low probability of strength loss for the design earthquake. The expression for b in (ii) is derived from Eq. (18.10.6.2b), assuming values of $V_u/(8A_{cv}\sqrt{f'_c})$ and δ_u/h_{wcs} of approximately 1.0 and 0.015, respectively. If b varies over c , an average or representative value of b should be used. For example, at the flanged end of a wall, b should be taken equal to the effective flange width defined in 18.10.5.2, unless c extends into the web, then a weighted average should be used for b . At the

CODE

18.10.6.3 Structural walls not designed in accordance with 18.10.6.2 shall have special boundary elements at boundaries and edges around openings of structural walls where the maximum extreme fiber compressive stress, corresponding to load combinations including earthquake effects E , exceeds $0.2f'_c$. The special boundary element shall be permitted to be discontinued where the calculated compressive stress is less than $0.15f'_c$. Stresses shall be calculated for the factored loads using a linearly elastic model and gross section properties. For walls with flanges, an effective flange width as given in 18.10.5.2 shall be used.

18.10.6.4 If special boundary elements are required by 18.10.6.2 or 18.10.6.3, (a) through (k) shall be satisfied:

- (a) The boundary element shall extend horizontally from the extreme compression fiber a distance at least the greater of $c - 0.1\ell_w$ and $c/2$, where c is the largest neutral axis depth calculated for the factored axial force and nominal moment strength consistent with δ_u .
- (b) Width of the flexural compression zone, b , over the horizontal distance calculated by 18.10.6.4(a), including flange if present, shall be at least $h_u/16$.
- (c) For walls or wall piers with $h_w/\ell_w \geq 2.0$ that are effectively continuous from the base of structure to top of wall, designed to have a single critical section for flexure and axial loads, and with $c/\ell_w \geq 3/8$, width of the flexural compression zone b over the length calculated in 18.10.6.4(a) shall be greater than or equal to 12 in.
- (d) In flanged sections, the boundary element shall include the effective flange width in compression and shall extend at least 12 in. into the web.
- (e) The boundary element transverse reinforcement shall satisfy 18.7.5.2(a) through (d) and 18.7.5.3, except the transverse reinforcement spacing limit of 18.7.5.3(a) shall be one-third of the least dimension of the boundary element. The maximum vertical spacing of transverse reinforcement in the boundary element shall also not exceed that in Table 18.10.6.5(b).
- (f) Spacing h_x between laterally supported longitudinal bars around the perimeter of the boundary element shall not exceed the lesser of 14 in. and $(2/3)b$. Lateral support shall be provided by a seismic hook of a crosstie or corner of a hoop. Unless (i) or (ii) is satisfied, the length of the

COMMENTARY

end of a wall without a flange, b should be taken equal to the wall thickness. If the drift capacity does not exceed the drift demand for a trial design, then changes to the design are required to increase wall drift capacity, reduces wall drift demand, or both, such that drift capacity exceeds drift demand for each wall in a given building.

R18.10.6.3 By this procedure, the wall is considered to be acted on by gravity loads and the maximum shear and moment induced by earthquake in a given direction. Under this loading, the compressed boundary at the critical section resists the tributary gravity load plus the compressive resultant associated with the bending moment.

Recognizing that this loading condition may be repeated many times during the strong motion, the concrete is to be confined where the calculated compressive stresses exceed a nominal critical value equal to $0.2f'_c$. The stress is to be calculated for the factored forces on the section assuming linear response of the gross concrete section. The compressive stress of $0.2f'_c$ is used as an index value and does not necessarily describe the actual state of stress that may develop at the critical section under the influence of the actual inertia forces for the anticipated earthquake intensity.

R18.10.6.4 The horizontal dimension of the special boundary element is intended to extend at least over the length where the concrete compressive strain exceeds the critical value. For flanged wall sections, including box shapes, L-shapes, and C-shapes, the calculation to determine the need for special boundary elements should include a direction of lateral load consistent with the orthogonal combinations defined in [ASCE/SEI 7](#). The value of $c/2$ in 18.10.6.4(a) is to provide a minimum length of the special boundary element. Good detailing practice is to arrange the longitudinal reinforcement and the confinement reinforcement such that all primary longitudinal reinforcement at the wall boundary is supported by transverse reinforcement.

A slenderness limit is introduced into the [2014 edition of the Code](#) based on lateral instability failures of slender wall boundaries observed in recent earthquakes and tests ([Wallace 2012](#); [Wallace et al. 2012](#)). For walls with large cover, where spalling of cover concrete would lead to a significantly reduced section, increased boundary element thickness should be considered.

A value of $c/\ell_w \geq 3/8$ is used to define a wall critical section that is not tension-controlled according to [21.2.2](#). A minimum wall thickness of 12 in. is imposed to reduce the likelihood of lateral instability of the compression zone after spalling of cover concrete.

Where flanges are highly stressed in compression, the web-to-flange interface is likely to be highly stressed and may sustain local crushing failure unless special boundary element transverse reinforcement extends into the web (Fig. R18.10.6.4.4b).

CODE

hoop legs shall not exceed $2b_c$, and adjacent hoops shall overlap at least the lesser of 6 in. and $(2/3)b$:

(i) $b \geq \sqrt{\ell_w c / 40}$ and $\delta_u / h_{wcs} < 0.012$

(ii) A flange is provided within depth c with a total width at least $2b_w$ and a thickness t_f at least $b_w/2$

(g) The amount of transverse reinforcement shall be in accordance with Table 18.10.6.4(g).

Table 18.10.6.4(g)—Transverse reinforcement for special boundary elements

Transverse reinforcement	Applicable expressions		
A_{sh}/sb_c for rectilinear hoop	Greater of	$0.3 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$	(a)
		$0.09 \frac{f'_c}{f_{yt}}$	(b)
ρ_s for spiral or circular hoop	Greater of	$0.45 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$	(c)
		$0.12 \frac{f'_c}{f_{yt}}$	(d)

(h) Concrete within the thickness of the floor system at the special boundary element location shall have specified compressive strength at least 0.7 times f'_c of the wall.

(i) For a distance above and below the critical section specified in 18.10.6.2(b), web vertical reinforcement shall have lateral support provided by the corner of a hoop or by a crosstie with seismic hooks at each end. Hoops and crossties shall have a vertical spacing not to exceed 12 in. and diameter satisfying 25.7.2.2. Alternatively, it shall be permitted to use crossties with a 90-degree hook at one end and a seismic hook at the other end, with the crossties alternated end for end along the length and the height of the web if vertical spacing of crossties does not exceed 9 in.

(j) Where the critical section occurs at the wall base, the boundary element transverse reinforcement at the wall base shall extend into the support at least ℓ_d , in accordance with 18.10.2.3, of the largest longitudinal reinforcement in the special boundary element. Where the special boundary element terminates on a footing, mat, or pile cap, special boundary element transverse reinforcement shall extend at least 12 in. into the footing, mat, or pile cap, unless a greater extension is required by 18.13.2.4.

(k) Horizontal reinforcement in the wall web shall extend to within 6 in. of the end of the wall. Reinforcement shall develop f_y in tension at the face of the confined core of the boundary element using standard hooks or heads. Where the confined boundary element has sufficient length to develop the horizontal web reinforcement, and A_{sh}/s of the horizontal web reinforcement does not exceed A_{sh}/s of the boundary element transverse reinforcement parallel to the horizontal web reinforcement, it shall be permitted to terminate the horizontal web reinforcement without a standard hook or head.

COMMENTARY

Required transverse reinforcement at wall boundaries is based on column provisions. Expression (a) of Table 18.10.6.4(g) was applied to wall special boundary elements prior to the 1999 edition of the Code. It is reinstated in the 2014 edition of the Code due to concerns that expression (b) of Table 18.10.6.4(g) by itself does not provide adequate transverse reinforcement for thin walls where concrete cover accounts for a significant portion of the wall thickness. For wall special boundary elements having rectangular cross section, A_g and A_{ch} in expressions (a) and (c) in Table 18.10.6.4(g) are defined as $A_g = \ell_{be}b$ and $A_{ch} = b_{c1}b_{c2}$, where dimensions are shown in Fig. R18.10.6.4a. This considers that concrete spalling is likely to occur only on the exposed faces of the confined boundary element. Tests (Thomsen and Wallace 2004) show that adequate performance can be achieved using vertical spacing greater than that permitted by 18.7.5.3(a). The limits on spacing between laterally supported longitudinal bars are intended to provide more uniform spacing of hoops and crossties for thin walls.

Configuration requirements for boundary element transverse reinforcement and crossties for web longitudinal reinforcement are summarized in Fig. R18.10.6.4a. Multiple overlapping hoops at elongated boundary elements are more effective in restraining bar buckling and confining the concrete than a single, elongated hoop with multiple crossties that have alternating 90- and 135-degree hooks (Segura and Wallace 2018; Welt et al. 2017; Arteta 2015). Overlapping hoops are not required if the drift demand for anticipated design-level earthquake shaking is low relative to the drift capacity, δ_c . Out-of-plane, lateral instability failure is more likely to occur at the boundaries of planar walls with relatively slender, deep compression zones—for example, where $(c/b)(\ell_w/b)$ is greater than approximately 40, or at the web boundary opposite a flanged boundary for a wall with a T-, C-, or L-shaped cross section (Abdullah and Wallace 2020). At a wall boundary where a web and flange intersect, use of overlapping hoops is not required in either the flange or web (Fig. R18.10.6.4b) because the flange provides lateral support to the wall web. A web hoop, however, may overlap with a flange hoop at the web-flange intersection. The geometric limits in 18.10.6.4f(ii) are based on judgment from observed damage of wall boundaries.

These tests also show that loss of axial load-carrying capacity of a wall can occur immediately following damage to the wall boundary elements if web vertical reinforcement within the plastic hinge region is not restrained. Use of web crossties outside of boundary elements also results in a less abrupt transition in transverse reinforcement used to provide concrete confinement and restrain buckling of longitudinal reinforcement, which addresses potential increases in the neutral axis depth due to shear (diagonal compression) and uncertainties in axial load.

Requirements for vertical extensions of boundary elements are summarized in Fig. R18.10.6.4d (Moehle et al. 2011).




Fig. R18.10.6.4a—Configurations of boundary transverse reinforcement and web crossties.

The horizontal reinforcement in a structural wall with low shear-to-moment ratio resists shear through truss action, with the horizontal bars acting like the stirrups in a beam. Thus, the horizontal bars provided for shear reinforcement must be developed within the confined core of the boundary element and extended as close to the end of the wall as cover requirements and proximity of other reinforcement permit. The requirement that the horizontal web reinforcement be anchored within the confined core of the boundary element and extended to within 6 in. from the end of the wall applies to all horizontal bars whether straight, hooked, or headed, as illustrated in Fig. R18.10.6.4c.

The requirements in 18.10.2.4 apply to the minimum longitudinal reinforcement in the ends of walls, including those with special boundary elements.

CODE

COMMENTARY






Fig. R18.10.6.4b—Example configuration for a case if a special boundary element is required for a flanged wall

CODE

COMMENTARY



(a) Wall with $h_w/l_w \geq 2.0$ and a single critical section controlled by flexure and axial load designed using 18.10.6.2, 18.10.6.4, and 18.10.6.5




Notes: Requirement for special boundary element is triggered if maximum extreme fiber compressive stress $\sigma \geq 0.2f'_c$. Once triggered, the special boundary element extends until $\sigma < 0.15f'_c$. Since $h_w/l_w \leq 2.0$, 18.10.6.4(c) does not apply.

(b) Wall and wall pier designed using 18.10.6.3, 18.10.6.4, and 18.10.6.5.

Fig. R18.10.6.4c—Summary of boundary element requirements for special walls.


CODE

COMMENTARY



(a)

Option with standard hooks or headed reinforcement



(b)

Option with straight developed reinforcement

Fig. R18.10.6.4d—Development of wall horizontal reinforcement in confined boundary element.

CODE

18.10.6.5 Where special boundary elements are not required by 18.10.6.2 or 18.10.6.3, (a) and (b) shall be satisfied:

(a) Except where $\omega_v \Omega_v V_u$ in the plane of the wall is less than $\lambda \sqrt{f'_c} A_{cv}$, horizontal reinforcement terminating at the edges of structural walls without boundary elements shall have a standard hook engaging the edge reinforcement or the edge reinforcement shall be enclosed in U-stirrups having the same size and spacing as, and spliced to, the horizontal reinforcement.

(b) If the maximum longitudinal reinforcement ratio at the wall boundary exceeds $400/f_y$, boundary transverse reinforcement shall satisfy 18.7.5.2(a) through (e) over the length calculated in accordance with 18.10.6.4(a). At corners where a wall web and flange intersect, boundary transverse reinforcement shall extend into the web and the flange at least 12 in. The vertical spacing of transverse reinforcement at the wall boundary shall be in accordance with Table 18.10.6.5(b).

Table 18.10.6.5(b)—Maximum vertical spacing of transverse reinforcement at wall boundary

Grade of primary flexural reinforcement	Transverse reinforcement required	Maximum vertical spacing of transverse reinforcement ^[1]
60	Within the greater of ℓ_w and $M_u/4V_u$ above and below critical sections ^[2]	Lesser of: $6d_b$ 6 in.
	Other locations	Lesser of: $8d_b$ 8 in.
80	Within the greater of ℓ_w and $M_u/4V_u$ above and below critical sections ^[2]	Lesser of: $5d_b$ 6 in.
	Other locations	Lesser of: $6d_b$ 6 in.
100	Within the greater of ℓ_w and $M_u/4V_u$ above and below critical sections ^[2]	Lesser of: $4d_b$ 6 in.
	Other locations	Lesser of: $6d_b$ 6 in.

^[1]In this table, d_b is the diameter of the smallest primary flexural reinforcing bar.

^[2]Critical sections are defined as locations where yielding of longitudinal reinforcement is likely to occur as a result of lateral displacements.

COMMENTARY

R18.10.6.5 Cyclic load reversals may lead to buckling of boundary longitudinal reinforcement even in cases where the demands on the boundary of the wall do not require special boundary elements. For walls with moderate amounts of boundary longitudinal reinforcement, ties are required to inhibit buckling. The longitudinal reinforcement ratio is intended to include only the reinforcement at the wall boundary, as indicated in Fig. R18.10.6.5a. A greater spacing of ties relative to 18.10.6.4(e) is allowed due to the lower deformation demands on the walls. Requirements of 18.10.6.5 apply over the entire wall height and are summarized in Fig. R18.10.6.4c for cases where special boundary elements are required (Moehle et al. 2011).

The addition of hooks or U-stirrups at the ends of horizontal wall reinforcement provides anchorage so that the reinforcement will be effective in resisting shear forces. It will also tend to inhibit the buckling of the vertical edge reinforcement. In walls with low in-plane shear, the development of horizontal reinforcement is not necessary.

Limits on spacing of transverse reinforcement are intended to prevent bar buckling until reversed cyclic strains extend well into the inelastic range. To achieve similar performance capability, smaller spacing is required for higher-strength longitudinal reinforcement.

To address potential significant tensile or compressive strain demands under biaxial loading, transverse reinforcement is required at corners where a wall web and flange intersect, as shown in Fig. R18.10.6.5b.




Fig. R18.10.6.5a—Longitudinal reinforcement ratios for typical wall boundary conditions.

CODE

COMMENTARY




Fig. R18.10.6.5b—Transverse reinforcement at the intersection of a wall web and flange.

18.10.7 Coupling beams

R18.10.7 Coupling beams

Coupling beams connecting structural walls can provide stiffness and energy dissipation. In many cases, geometric limits result in coupling beams that are deep in relation to their clear span. Deep coupling beams may be controlled by shear and may be susceptible to strength and stiffness deterioration under earthquake loading. Test results (Paulay and Binney 1974; Barney et al. 1980) have shown that confined diagonal reinforcement provides adequate resistance in deep coupling beams.

Experiments show that diagonally oriented reinforcement is effective only if the bars are placed with a large inclination. Therefore, diagonally reinforced coupling beams are restricted to beams having aspect ratio $\ell_n/h < 4$. The 2008 edition of the Code was changed to clarify that coupling beams of intermediate aspect ratio can be reinforced according to 18.6.3 through 18.6.5.

Diagonal bars should be placed approximately symmetrically in the beam cross section, in two or more layers. The diagonally placed bars are intended to provide the entire shear and corresponding moment strength of the beam. Designs deriving their moment strength from combinations of diagonal and longitudinal bars are not covered by these provisions.

Two confinement options are described. According to 18.10.7.4(c), each diagonal element consists of a cage of longitudinal and transverse reinforcement, as shown in Fig. R18.10.7a. Each cage contains at least four diagonal

CODE

COMMENTARY

bars and confines a concrete core. The requirement on side dimensions of the cage and its core is to provide adequate stability to the cross section when the bars are loaded beyond yielding. The minimum dimensions and required reinforcement clearances may control the wall width. Revisions were made in the 2008 Code to relax spacing of transverse reinforcement confining the diagonal bars, to clarify that confinement is required at the intersection of the diagonals, and to simplify design of the longitudinal and transverse reinforcement around the beam perimeter; beams with these new details are expected to perform acceptably. The expressions for transverse reinforcement A_{sh} are based on ensuring compression capacity of an equivalent column section is maintained after spalling of cover concrete.

Limits on transverse reinforcement spacing in Table 18.10.7.4 are intended to provide adequate support of diagonal and primary flexural reinforcement to control bar buckling.

Section 18.10.7.4(d) describes a second option for confinement of the diagonals introduced in the 2008 Code (refer to Fig. R18.10.7b). This second option is to confine the entire beam cross section instead of confining the individual diagonals. This option can considerably simplify field placement of hoops, which can otherwise be especially challenging where diagonal bars intersect each other or enter the wall boundary.

For coupling beams not used as part of the lateral-force-resisting system, the requirements for diagonal reinforcement may be waived.

Test results (Barney et al. 1980) demonstrate that beams reinforced as described in 18.10.7 have adequate ductility at shear forces exceeding $10\sqrt{f'_c}b_wd$. Consequently, the use of a limit of $10\sqrt{f'_c}A_{cw}$ provides an acceptable upper limit.




Fig. R18.10.7b—Full confinement of diagonally reinforced concrete beam section in coupling beams with diagonally oriented reinforcement. Wall boundary reinforcement shown on one side only for clarity.

18.10.7.1 Coupling beams with $(\ell_n/h) \geq 4$ shall satisfy the requirements of 18.6, with the wall boundary interpreted as being a column. The provisions of 18.6.2.1(b) and (c) need not be satisfied if it can be shown by analysis that the beam has adequate lateral stability.

18.10.7.2 Coupling beams with $(\ell_n/h) < 2$ and with $V_u \geq 4\lambda\sqrt{f'_c}A_{cw}$ shall be reinforced with two intersecting groups of diagonally placed bars symmetrical about the midspan, unless it can be shown that loss of stiffness and strength of the coupling beams will not impair the vertical load-carrying ability of the structure, the egress from the structure, or the

CODE

COMMENTARY

integrity of nonstructural components and their connections to the structure.

18.10.7.3 Coupling beams not governed by 18.10.7.1 or 18.10.7.2 shall be reinforced in accordance with (a) or (b):

- (a) Two intersecting groups of diagonally placed bars symmetrical about the midspan
- (b) Longitudinal and transverse reinforcement satisfying (i) through (iii):
 - (i) 18.6.3 and 18.6.4, with the wall boundary interpreted as being a column.
 - (ii) Transverse reinforcement proportioned to satisfy the shear strength requirements of 18.6.5.
 - (iii) Spacing of transverse reinforcement not exceeding the limits in Table 18.10.7.4.

18.10.7.4 Coupling beams reinforced with two intersecting groups of diagonally placed bars symmetrical about the midspan shall satisfy (a), (b), and either (c) or (d), and the requirements of 9.9 need not be satisfied:

- (a) V_n shall be calculated by

$$V_n = 2A_{vd}f_y \sin \alpha \leq 10\sqrt{f'_c}A_{cw} \quad (18.10.7.4)$$

where α is the angle between the diagonal bars and the longitudinal axis of the coupling beam.

- (b) Each group of diagonal bars shall consist of a minimum of four bars provided in two or more layers.
- (c) Each group of diagonal bars shall be enclosed by rectangular transverse reinforcement having out-to-out dimensions of at least $b_w/2$ in the direction parallel to b_w and $b_w/5$ along the other sides, where b_w is the web width of the coupling beam. The transverse reinforcement shall be in accordance with 18.7.5.2(a) through (c) and shall provide lateral support to the diagonal reinforcement in accordance with 25.7.2.2 and 25.7.2.3. Reinforcement shall be arranged such that spacing of diagonal bars laterally supported by the corner of a crosstie or a hoop leg shall not exceed 14 in. around the perimeter of each group of diagonal bars, with A_{sh} not less than the greater of (i) and (ii):

$$(i) 0.09sb_c \frac{f'_c}{f_{yt}}$$

$$(ii) 0.3sb_c \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$$

In calculating A_g for each group of diagonal bars, the concrete cover in 20.5.1 shall be assumed on all four sides of each group of diagonal bars. The transverse reinforcement shall have spacing measured parallel to the diagonal bars satisfying 18.7.5.3(d) and not exceeding the limits in Table 18.10.7.4, and shall have spacing of crossties or legs of hoops measured perpendicular to the diagonal bars not exceeding 14 in. The transverse reinforcement shall continue through the intersection of the diagonal bars. At the intersec-

CODE

tion, it is permitted to modify the arrangement of the transverse reinforcement provided the spacing and volume ratio requirements are satisfied. Additional longitudinal and transverse reinforcement shall be distributed around the beam perimeter with total area in each direction of at least $0.002b_w s$ and spacing not exceeding 12 in.

(d) Transverse reinforcement shall be provided for the entire beam cross section in accordance with 18.7.5.2(a) through (e) with A_{sh} not less than the greater of (i) and (ii):

$$(i) 0.09sb_c \frac{f'_c}{f_{yt}}$$

$$(ii) 0.3sb_c \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$$

Longitudinal spacing of transverse reinforcement shall not exceed the limits in Table 18.10.7.4. Spacing of crossties or legs of hoops both vertically and horizontally in the plane of the beam cross section shall not exceed 8 in. Each crosstie and each hoop leg shall engage a longitudinal bar of equal or greater diameter. It shall be permitted to configure hoops as specified in 18.6.4.3.

Table 18.10.7.4—Maximum spacing of transverse reinforcement in coupling beams

Grade of diagonal or primary flexural reinforcement	Maximum spacing of transverse reinforcement ^[1]
60	Lesser of:
	$6d_b$ 6 in.
80	Lesser of:
	$5d_b$ 6 in.
100	Lesser of:
	$4d_b$ 6 in.

^[1] d_b is the diameter of the smallest diagonal bar or primary flexural reinforcing bar.

18.10.7.5 Design shear force V_e of coupling beams shall be permitted to be redistributed to coupling beams at adjacent floor levels provided (a) through (d) are satisfied:

- (a) Coupling beams sharing redistributed forces shall be vertically aligned within a special structural wall.
- (b) Coupling beams sharing redistributed forces shall have $\ell_n/h \geq 2$.
- (c) The maximum redistribution of V_e from any beam shall not exceed 20% of the value determined from analysis.
- (d) The sum of ϕV_n of coupling beams sharing redistributed demands shall be equal to or greater than the sum of V_e in those beams.

COMMENTARY

R18.10.7.5 Redistribution of coupling beam shear demands determined from linear analysis is permitted because coupling beams designed in accordance with 18.10.7 have significant plastic rotational capacity and are expected to be a primary yielding mechanism. For coupling beams designed in accordance with 18.6 as allowed by 18.10.7.1 and 18.10.7.3, the redistribution of earthquake beam moments in proportion to the redistributed shears is necessary to maintain internal equilibrium.

Redistributing demands in vertically aligned coupling beams generally creates more economical and constructible design details. Although precise vertical alignment of coupling beams sharing coupling demands is not necessary, coupling beams with similar stiffnesses more predictably and evenly share redistributed demands. The presence of one or more coupling beams or horizontal wall segments significantly deeper than coupling beams aligned above or below inhibits redistribution and should be avoided.

CODE

COMMENTARY

18.10.7.6 Penetrations in a coupling beam designed according to 18.10.7.4 shall satisfy (a) through (d):

- (a) The number of penetrations shall not exceed two.
- (b) Each penetration shall comprise a cast-in horizontal cylindrical void oriented transverse to the plane of the coupling beam, with diameter not exceeding the larger of $h/6$ and 6 in.
- (c) Penetrations shall be located at least 2 in. clear from diagonally placed bars, at least $h/4$ clear from the ends of the coupling beam, at least 4 in. clear from the top and bottom of the coupling beam, and at least a dimension equal to the larger penetration diameter from an adjacent penetration.
- (d) Penetrations shall not cause transverse reinforcement to violate requirements of 18.10.7.4(d).

Redistribution of coupling beam demands relies upon beam end rotations beyond the elastic range. Vertically aligned coupling beams with close proximity are more likely to experience similar end rotations, and thus more reliably share redistributed forces. Consideration should be given to redistribute demands to coupling beams within reasonable proximity.

R18.10.7.6 Penetrations through diagonally reinforced coupling beams are at times unavoidable due to the routing of plumbing, electrical, and other building services. Penetrations should be avoided where possible or otherwise minimized. Penetrations with excessive size or located in critical regions of a beam have the potential to compromise the ductility capacity of the beam.

Test results (Abdullah et al. 2023) have shown that the shear resistance and rotational capacity of diagonally reinforced coupling beams are not appreciably affected by penetrations meeting the limitations of 18.10.7.6. Tests cited were conducted with circular openings; rectangular openings are to be avoided because corners can cause stress concentrations under dynamic loads that have not been evaluated experimentally. Figure R18.10.7.6 illustrates these limitations for a coupling beam with a typical ℓ_n/h aspect ratio.




Fig. R18.10.7.6—Coupling beam elevation showing prohibited penetration regions shaded. Note that four potential locations for penetrations are shown although only two are permitted in any one beam.

CODE

18.10.8 *Wall piers*

COMMENTARY

R18.10.8 *Wall piers*

Door and window placements in structural walls sometimes lead to narrow vertical wall segments that are considered to be wall piers. The dimensions defining wall piers are given in [Chapter 2](#). Shear failures of wall piers have been observed in previous earthquakes. The intent of this section is to provide sufficient shear strength to wall piers such that inelastic response, if it occurs, will be primarily in flexure. The provisions apply to wall piers designated as part of the seismic-force-resisting system. Provisions for wall piers not designated as part of the seismic-force-resisting system are given in 18.14. The effect of all vertical wall segments on the response of the structural system, whether designated as part of the seismic-force-resisting system or not, should be considered as required by 18.2.2. Wall piers having $(\ell_w/b_w) \leq 2.5$ behave essentially as columns. Provision 18.10.8.1 requires that such members satisfy reinforcement and shear strength requirements of 18.7.4 through 18.7.6. Alternative provisions are provided for wall piers having $(\ell_w/b_w) > 2.5$.

The design shear force determined according to 18.7.6.1 may be unrealistically large in some cases. As an alternative, 18.10.8.1(a) permits the design shear force to be determined using factored load combinations in which the earthquake effect has been amplified to account for system overstrength. Documents such as the NEHRP provisions ([FEMA P-749](#)), [ASCE/SEI 7](#), and the [2021 IBC](#) represent the amplified earthquake effect using the factor Ω_o .

Section 18.10.8.2 addresses wall piers at the edge of a wall. Under in-plane shear, inclined cracks can propagate into segments of the wall directly above and below the wall pier. Unless there is sufficient reinforcement in the adjacent wall segments, shear failure within the adjacent wall segments can occur. The length of embedment of the provided reinforcement into the adjacent wall segments should be determined considering both development length requirements and shear strength of the wall segments (refer to Fig. R18.10.8).

CODE

COMMENTARY




Fig. R18.10.8—Required horizontal reinforcement in wall segments above and below wall piers at the edge of a wall.

CODE

COMMENTARY

18.10.8.1 Wall piers shall satisfy the special moment frame requirements for columns of 18.7.4, 18.7.5, and 18.7.6, with joint faces taken as the top and bottom of the clear height of the wall pier. Alternatively, wall piers with $(\ell_w/b_w) > 2.5$ shall satisfy (a) through (f):

- (a) Design shear force shall be calculated in accordance with 18.7.6.1 with joint faces taken as the top and bottom of the clear height of the wall pier. If the general building code includes provisions to account for overstrength of the seismic-force-resisting system, the design shear force need not exceed Ω_o times the factored shear calculated by analysis of the structure for earthquake load effects.
- (b) V_n and distributed shear reinforcement shall satisfy 18.10.4.
- (c) Transverse reinforcement shall be hoops except it shall be permitted to use single-leg horizontal reinforcement parallel to ℓ_w where only one curtain of distributed shear reinforcement is provided. Single-leg horizontal reinforcement shall have 180-degree bends at each end that engage wall pier boundary longitudinal reinforcement.
- (d) Vertical spacing of transverse reinforcement shall not exceed 6 in.
- (e) Transverse reinforcement shall extend at least 12 in. above and below the clear height of the wall pier.
- (f) Special boundary elements shall be provided if required by 18.10.6.3.

18.10.8.2 For wall piers at the edge of a wall, horizontal reinforcement shall be provided in adjacent wall segments above and below the wall pier and be designed to transfer the design shear force from the wall pier into the adjacent wall segments.

18.10.9 Ductile coupled walls

18.10.9.1 Ductile coupled walls shall satisfy the requirements of this section.

18.10.9.2 Individual walls shall satisfy $h_{wcs}/\ell_w \geq 2$ and the applicable provisions of 18.10 for special structural walls.

18.10.9.3 Coupling beams shall satisfy 18.10.7 and (a) through (c) in the direction considered.

- (a) Coupling beams shall have $\ell_n/h \geq 2$ at all levels of the building.
- (b) All coupling beams at a floor level shall have $\ell_n/h \leq 5$ in at least 90% of the levels of the building.

R18.10.9 Ductile coupled walls

The aspect ratio limits and development length requirements for ductile coupled walls are intended to induce an energy dissipation mechanism associated with inelastic deformation reversal of coupling beams. Wall stiffness and strength at each end of coupling beams should be sufficient to develop this intended behavior.

CODE

(c) The requirements of 18.10.2.5 shall be satisfied at both ends of all coupling beams.

18.10.10 Construction joints

18.10.10.1 Construction joints in structural walls shall be specified according to 26.5.6, and contact surfaces shall be roughened consistent with condition (b) of Table 22.9.4.2.

18.10.11 Discontinuous walls

18.10.11.1 Columns supporting discontinuous structural walls shall be reinforced in accordance with 18.7.5.6.

18.11—Special structural walls constructed using precast concrete**18.11.1 Scope**

18.11.1.1 This section shall apply to special structural walls constructed using precast concrete forming part of the seismic-force-resisting system.

18.11.2 General

18.11.2.1 Special structural walls constructed using precast concrete shall satisfy 18.10 and 18.5.2, except 18.10.2.4 shall not apply for precast walls where deformation demands are concentrated at the panel joints.

18.11.2.2 Special structural walls constructed using precast concrete and unbonded post-tensioning tendons and not satisfying the requirements of 18.11.2.1 are permitted provided they satisfy the requirements of ACI CODE-550.6.

18.12—Diaphragms and trusses**18.12.1 Scope****COMMENTARY****R18.11—Special structural walls constructed using precast concrete****R18.11.2 General**

R18.11.2.2 Experimental and analytical studies (Priestley et al. 1999; Perez et al. 2003; Restrepo 2002) have demonstrated that some types of precast structural walls post-tensioned with unbonded tendons, and not satisfying the prescriptive requirements of Chapter 18, provide satisfactory seismic performance characteristics. ACI CODE-550.6 defines a protocol for establishing a design procedure, validated by analysis and laboratory tests, for such walls, with or without coupling beams.

ACI CODE-550.7 defines design requirements for one type of special structural wall constructed using precast concrete and unbonded post-tensioning tendons, and validated for use in accordance with 18.11.2.2.

R18.12—Diaphragms and trusses**R18.12.1 Scope**

Diaphragms as used in building construction are structural elements (such as a floor or roof) that provide some or all of the following functions:

- (a) Support for building elements (such as walls, partitions, and cladding) resisting horizontal forces but not acting as part of the seismic-force-resisting system
- (b) Transfer of lateral forces from the point of application to the vertical elements of the seismic-force-resisting system

CODE

18.12.1.1 This section shall apply to diaphragms and collectors forming part of the seismic-force-resisting system in structures assigned to SDC D, E, or F and to SDC C if 18.12.1.2 applies.

18.12.1.2 Section 18.12.11 shall apply to diaphragms constructed using precast concrete members and forming part of the seismic-force-resisting system for structures assigned to SDC C, D, E, or F.

18.12.1.3 Section 18.12.12 shall apply to structural trusses forming part of the seismic-force-resisting system in structures assigned to SDC D, E, or F.

18.12.2 *Design forces*

18.12.2.1 The earthquake design forces for diaphragms shall be obtained from the general building code using the applicable provisions and load combinations.

COMMENTARY

(c) Connection of various components of the vertical seismic-force-resisting system with appropriate strength, stiffness, and ductility so the building responds as intended in the design (Wyllie 1987).

R18.12.2 *Design forces*

R18.12.2.1 In the general building code, earthquake design forces for floor and roof diaphragms typically are not calculated directly during the lateral-force analysis that provides story forces and story shears. Instead, diaphragm design forces at each level are calculated by a formula that amplifies the story forces recognizing dynamic effects and includes minimum and maximum limits. These forces are used with the governing load combinations to design diaphragms for shear and moment.

For collector elements, the general building code in the United States specifies load combinations that amplify earthquake forces by a factor Ω_o . The forces amplified by Ω_o are also used for the local diaphragm shear forces resulting from the transfer of collector forces, and for local diaphragm flexural moments resulting from any eccentricity of collector forces. The specific requirements for earthquake design forces for diaphragms and collectors depend on which edition of the general building code is used. The requirements may also vary according to the SDC.

For most concrete buildings subjected to inelastic earthquake demands, it is desirable to limit inelastic behavior of floor and roof diaphragms under the imposed earthquake forces and deformations. It is preferable for inelastic behavior to occur only in the intended locations of the vertical seismic-force-resisting system that are detailed for ductile response, such as in beam plastic hinges of special moment frames, or in flexural plastic hinges at the base of structural walls or in coupling beams. For buildings without long diaphragm spans between lateral-force-resisting elements, elastic diaphragm behavior is typically not difficult to achieve. For buildings where diaphragms could reach their flexural or shear strength before yielding occurs in the vertical seismic-force-resisting system, the licensed

CODE

COMMENTARY

design professional should consider providing increased diaphragm strength.

For reinforced concrete diaphragms, **ASCE/SEI 7** Sections 12.10.1 and 12.10.2 provide requirements to determine design forces for reinforced concrete diaphragms. For precast concrete diaphragms in buildings assigned to SDC C, D, E, or F, the provisions of ASCE/SEI 7 Section 12.10.3 apply.

18.12.3 Seismic load path

18.12.3.1 All diaphragms and their connections shall be designed and detailed to provide for transfer of forces to collector elements and to the vertical elements of the seismic-force-resisting system.

18.12.3.2 Elements of a structural diaphragm system that are subjected primarily to axial forces and used to transfer diaphragm shear or flexural forces around openings or other discontinuities shall satisfy the requirements for collectors in 18.12.7.6 and 18.12.7.7.

R18.12.3 Seismic load path

R18.12.3.2 This provision applies to strut-like elements that occur around openings, diaphragm edges, or other discontinuities in diaphragms. Figure R18.12.3.2 shows an example. Such elements can be subjected to earthquake axial forces in combination with bending and shear from earthquake or gravity loads.




Fig. R18.12.3.2—Example of diaphragm subject to the requirements of 18.12.3.2 and showing an element having confinement as required by 18.12.7.6.

CODE

18.12.4 *Cast-in-place composite topping slab diaphragms*

18.12.4.1 A cast-in-place composite topping slab on a precast floor or roof shall be permitted as a structural diaphragm, provided the cast-in-place topping slab is reinforced and the surface of the previously hardened concrete on which the topping slab is placed is clean, free of laitance, and intentionally roughened.

18.12.5 *Cast-in-place noncomposite topping slab diaphragms*

18.12.5.1 A cast-in-place noncomposite topping on a precast floor or roof shall be permitted as a structural diaphragm, provided the cast-in-place topping slab acting alone is designed and detailed to resist the design earthquake forces.

18.12.6 *Minimum thickness of diaphragms*

18.12.6.1 Concrete slabs and composite topping slabs serving as diaphragms used to transmit earthquake forces shall be at least 2 in. thick. Topping slabs placed over precast floor or roof elements, acting as diaphragms and not relying on composite action with the precast elements to resist the design earthquake forces, shall be at least 2-1/2 in. thick.

18.12.7 *Reinforcement*

18.12.7.1 Minimum reinforcement for diaphragms shall be in conformance with 12.6. Except for post-tensioned slabs, reinforcement spacing each way in floor or roof systems shall not exceed 18 in. Where welded wire reinforcement is used as the distributed reinforcement to resist shear in topping slabs placed over precast floor and roof elements, the wires parallel to the joints between the precast elements shall be spaced not less than 10 in. on center. Reinforcement provided for shear strength shall be continuous and shall be distributed uniformly across the shear plane.

18.12.7.2 Bonded tendons used as reinforcement to resist collector forces, diaphragm shear, or flexural tension shall be designed such that the stress due to design earthquake forces does not exceed 60,000 psi. Precompression from unbonded tendons shall be permitted to resist diaphragm design forces if a seismic load path is provided.

COMMENTARY

R18.12.4 *Cast-in-place composite topping slab diaphragms*

R18.12.4.1 A bonded topping slab is required so that the floor or roof system can provide restraint against slab buckling. Reinforcement is required to ensure the continuity of the shear transfer across precast joints. The connection requirements are introduced to promote a complete system with necessary shear transfers.

R18.12.5 *Cast-in-place noncomposite topping slab diaphragms*

R18.12.5.1 Composite action between the topping slab and the precast floor elements is not required, provided that the topping slab is designed to resist the design earthquake forces.

R18.12.6 *Minimum thickness of diaphragms*

R18.12.6.1 The minimum thickness of concrete diaphragms reflects current practice in joist and waffle systems and composite topping slabs on precast floor and roof systems. Thicker slabs are required if the topping slab is not designed to act compositely with the precast system to resist the design earthquake forces.

R18.12.7 *Reinforcement*

R18.12.7.1 The maximum spacing for reinforcement is intended to control the width of inclined cracks. Minimum average prestress requirements (refer to 24.4.4.1) are considered to be adequate to limit the crack widths in post-tensioned floor systems; therefore, the maximum spacing requirements do not apply to these systems.

The minimum spacing requirement for welded wire reinforcement in topping slabs on precast floor systems is to avoid fracture of the distributed reinforcement during an earthquake. Cracks in the topping slab open immediately above the boundary between the flanges of adjacent precast members, and the wires crossing those cracks are restrained by the transverse wires (Wood et al. 2000). Therefore, all the deformation associated with cracking should be accommodated in a distance not greater than the spacing of the transverse wires. A minimum spacing of 10 in. for the transverse wires is required to reduce the likelihood of fracture of the wires crossing the critical cracks during a design earthquake. The minimum spacing requirements do not apply to diaphragms reinforced with individual bars, because strains are distributed over a longer length.

CODE

18.12.7.3 All reinforcement used to resist collector forces, diaphragm shear, or flexural tension shall be developed or spliced for f_y in tension.

18.12.7.4 Class G or Class S mechanical splices are required where mechanical splices are used in the region of the connection between the diaphragm and the vertical elements of the seismic-force-resisting system.

18.12.7.5 Longitudinal reinforcement for collectors shall be proportioned such that the average tensile stress over length (a) or (b) does not exceed ϕf_y , where the value of f_y is limited to 60,000 psi.

- (a) Length between the end of a collector and location at which transfer of load to a vertical element begins
- (b) Length between two vertical elements

18.12.7.6 Collector elements with compressive stresses exceeding $0.2f_c'$ at any section shall have transverse reinforcement satisfying 18.7.5.2(a) through (e) and 18.7.5.3, except the spacing limit of 18.7.5.3(a) shall be one-third of the least dimension of the collector. The amount of transverse reinforcement shall be in accordance with Table 18.12.7.6. The specified transverse reinforcement is permitted to be discontinued at a section where the calculated compressive stress is less than $0.15f_c'$.

If design forces have been amplified to account for the overstrength of the vertical elements of the seismic-force-resisting system, the limit of $0.2f_c'$ shall be increased to $0.5f_c'$, and the limit of $0.15f_c'$ shall be increased to $0.4f_c'$.

Table 18.12.7.6—Transverse reinforcement for collector elements

Transverse reinforcement	Applicable expressions	
A_{sh}/sb_c for rectilinear hoop	$0.9 \frac{f_c'}{f_{yt}}$	(a)
ρ_s for spiral or circular hoop	Greater of:	$0.45 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f_c'}{f_{yt}}$ (b)
		$0.12 \frac{f_c'}{f_{yt}}$ (c)

18.12.7.7 Longitudinal reinforcement detailing for collector elements at splices and anchorage zones shall satisfy (a) or (b):

COMMENTARY

R18.12.7.3 Bar development and lap splices are designed according to requirements of [Chapter 25](#) for reinforcement in tension. Reductions in development or splice length for calculated stresses less than f_y are not permitted, as indicated in [25.4.10.2](#).

R18.12.7.4 Although the Ω_o factor is to be applied to the design forces transferred by the connection between the diaphragm and the vertical elements of the seismic-force-resisting system, significant yielding of reinforcement at the connection may occur due to inelastic displacements, including but not limited to displacements caused by rocking structural walls and displacements arising from flexural elongation of wall boundaries occurring over several stories. The application of the Ω_o factor does not limit this kind of yielding, and a Class S splice should be considered.

R18.12.7.5 Table 20.2.2.4(a) permits the maximum design yield strength to be 80,000 psi for portions of a collector, for example, at and near critical sections. The average stress in the collector is limited to control diaphragm cracking over the length of the collector. The calculation of average stress along the length is not necessary if the collector is designed for f_y of 60,000 psi even if Grade 80 reinforcement is specified.

R18.12.7.6 In documents such as the NEHRP Provisions ([FEMA P-750](#)), [ASCE/SEI 7](#), the [2024 IBC](#), and the Uniform Building Code ([ICBO 1997](#)), collector elements of diaphragms are designed for forces amplified by a factor Ω_o to account for the overstrength in the vertical elements of the seismic-force-resisting systems. The amplification factor Ω_o ranges between 2 and 3 for most concrete structures, depending on the document selected and on the type of seismic-force-resisting system. In some documents, the factor can be calculated based on the maximum forces that can be developed by the elements of the vertical seismic-force-resisting system.

Compressive stress calculated for the factored forces on a linearly elastic model based on gross section of the structural diaphragm is used as an index value to determine whether confining reinforcement is required. A calculated compressive stress of $0.2f_c'$, or $0.5f_c'$ for forces amplified by Ω_o , is assumed to indicate that integrity of the entire structure depends on the ability of that member to resist substantial compressive force under severe cyclic loading. Transverse reinforcement is required at such locations to provide confinement for the concrete and the reinforcement.

R18.12.7.7 This section is intended to reduce the possibility of bar buckling and provide adequate bar development conditions in the vicinity of splices and anchorage zones.

CODE

(a) Center-to-center spacing of at least three longitudinal bar diameters, but not less than 1-1/2 in., and concrete clear cover of at least two and one-half longitudinal bar diameters, but not less than 2 in.

(b) Area of transverse reinforcement, providing A_v at least the greater of $0.75\sqrt{f'_c}(b_ws/f_{yt})$ and $50b_ws/f_{yt}$, except as required in 18.12.7.6

18.12.8 Combined moment and axial strength

18.12.8.1 Diaphragms and portions of diaphragms shall be designed for flexure in accordance with **Chapter 12**. The effects of openings shall be considered.

18.12.9 Shear strength**COMMENTARY****R18.12.8 Combined moment and axial strength**

R18.12.8.1 Flexural strength of diaphragms is calculated using the same assumptions as for walls, columns, or beams. The design of diaphragms for moment and other actions uses the applicable load combinations of **5.3.1** to consider earthquake forces acting concurrently with gravity or other loads.

The influence of slab openings on moment and shear strength is to be considered, including evaluating the potential critical sections created by the openings. The strut-and-tie method is potentially useful for designing diaphragms with openings.

In the 1999 through 2005 editions of the Code, it was assumed that design moments for diaphragms were resisted entirely by chord forces acting at opposite edges of the diaphragm consistent with a beam idealization of the diaphragm. While this approach is still used, it is also acceptable to resist design moments using distributed reinforcement or precompression with proper consideration of applicable load combinations and analysis including compatibility of stresses and strains.

R18.12.9 Shear strength

The shear strength requirements for diaphragms are similar to those for slender structural walls and are based on the shear provisions for beams. The term A_{cv} refers to the gross area of the diaphragm, but may not exceed the thickness times the width of the diaphragm. This corresponds to the gross area of the effective deep beam that forms the diaphragm. Distributed slab reinforcement ρ_t used to calculate shear strength of a diaphragm in Eq. (18.12.9.1) is positioned perpendicular to the diaphragm flexural reinforcement. Provision 18.12.9.2 limits the maximum shear strength of the diaphragm.

In addition to satisfying 18.12.9.1 and 18.12.9.2, cast-in-place topping slab diaphragms must also satisfy 18.12.9.3 and 18.12.9.4. Cast-in-place topping slabs on a precast floor or roof system tend to have shrinkage cracks that are aligned with the joints between adjacent precast members. Therefore, the additional shear strength requirements for topping slab diaphragms in 18.12.9.3 are based on a shear friction model (Wood et al. 2000), and the assumed crack plane corresponds to joints in the precast system along the direction of the applied shear, as shown in Fig. R22.9.4.3a. The coefficient of friction, μ , in the shear friction model is taken

CODE

COMMENTARY

equal to 1.0 for normalweight concrete due to the presence of these shrinkage cracks.

Both distributed and boundary reinforcement in the topping slab may be considered as shear friction reinforcement A_{vf} . Boundary reinforcement within the diaphragm was called chord reinforcement in ACI 318 before 2008. Although the boundary reinforcement also resists forces due to moment and axial force in the diaphragm, the reduction in the shear friction resistance in the tension zone is offset by the increase in shear friction resistance in the compression zone. Therefore, the area of boundary reinforcement used to resist shear friction need not be added to the area of boundary reinforcement used to resist moment and axial force. The distributed topping slab reinforcement must contribute at least one-half of the nominal shear strength. It is assumed that connections between the precast elements do not contribute to the shear strength of the topping slab diaphragm.

Provision 18.12.9.4 limits the maximum shear that may be transmitted by shear friction within a topping slab diaphragm.

18.12.9.1 V_n of diaphragms shall not exceed:

$$V_n = A_{cv}(2\lambda\sqrt{f'_c} + \rho f_y) \quad (18.12.9.1)$$

For cast-in-place topping slab diaphragms on precast floor or roof members, A_{cv} shall be calculated using only the thickness of topping slab for noncomposite topping slab diaphragms and the combined thickness of cast-in-place and precast elements for composite topping slab diaphragms. For composite topping slab diaphragms, the value of f'_c used to calculate V_n shall not exceed the lesser of f'_c for the precast members and f'_c for the topping slab.

18.12.9.2 V_n of diaphragms shall not exceed $8\sqrt{f'_c} A_{cv}$.

18.12.9.3 Above joints between precast elements in noncomposite and composite cast-in-place topping slab diaphragms, V_n shall not exceed:

$$V_n = A_{vf}f_y\mu \quad (18.12.9.3)$$

where A_{vf} is the total area of shear friction reinforcement within the topping slab, including both distributed and boundary reinforcement, that is oriented perpendicular to joints in the precast system and coefficient of friction, μ , is 1.0λ , where λ is given in 19.2.4. At least one-half of A_{vf} shall be uniformly distributed along the length of the potential shear plane. The area of distributed reinforcement in the topping slab shall satisfy 24.4.3.2 in each direction.

18.12.9.4 Above joints between precast elements in noncomposite and composite cast-in-place topping slab diaphragms, V_n shall not exceed the limits in 22.9.4.4, where A_c is calculated using only the thickness of the topping slab.

CODE

COMMENTARY

18.12.10 Construction joints

18.12.10.1 Construction joints in diaphragms shall be specified according to **26.5.6**, and contact surfaces shall be roughened consistent with condition (b) of Table 22.9.4.2.

18.12.11 Precast concrete diaphragms

18.12.11.1 Diaphragms and collectors constructed using precast concrete members with composite topping slab and not satisfying 18.12.4, and untopped precast concrete diaphragms, are permitted provided they satisfy the requirements of **ACI CODE-550.5**. Cast-in-place noncomposite topping slab diaphragms shall satisfy 18.12.5 and 18.12.6.

18.12.11.2 Connections and reinforcement at joints used in the construction of precast concrete diaphragms satisfying 18.12.11.1 shall have been tested in accordance with ACI CODE-550.4.

18.12.11.3 Extrapolation of data on connections and reinforcement at joints to project details that result in larger construction tolerances than those used to qualify connections in accordance with ACI CODE-550.4 shall not be permitted.

18.12.12 Structural trusses

18.12.12.1 Structural truss elements with compressive stresses exceeding $0.2f_c'$ at any section shall have transverse reinforcement, in accordance with 18.7.5.2, 18.7.5.3, 18.7.5.7, and Table 18.12.12.1, over the length of the element.

R18.12.11 Precast concrete diaphragms

R18.12.11.1 ACI CODE-550.5 provides requirements for the design of precast concrete diaphragms with connections whose performance has been validated by **ACI CODE-550.4** testing. ACI CODE-550.5 permits a maximum tolerance for positioning and completion of connections of 1/2 in., which can be difficult to achieve with normal construction practices. **Section 26.13.1.3** requires continuous inspection of precast concrete diaphragm connections to verify that construction is performed properly and tolerances not greater than 1/2 in. for all connections are achieved. Results from ACI CODE-550.4 testing are not to be extrapolated to allow greater tolerances.

Topped precast concrete floors designed in accordance with Chapter 18 need careful consideration of support conditions to verify precast concrete members have sufficient seating for anticipated displacements and ability to accommodate relative rotations between beam supports and the member (**Henry et al. 2017**).

R18.12.12 Structural trusses

R18.12.12.1 The expressions for transverse reinforcement A_{sh} are based on ensuring compression capacity of an equivalent column section is maintained after spalling of cover concrete.

CODE

COMMENTARY

Table 18.12.12.1—Transverse reinforcement for structural trusses

Transverse reinforcement	Applicable expressions		
$A_{sh}/s_b c$ for rectilinear hoop	Greater of:	$0.3 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f_c'}{f_{yt}}$	(a)
		$0.09 \frac{f_c'}{f_{yt}}$	(b)
ρ_s for spiral or circular hoop	Greater of:	$0.45 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f_c'}{f_{yt}}$	(c)
		$0.12 \frac{f_c'}{f_{yt}}$	(d)

18.12.12.2 All continuous reinforcement in structural truss elements shall be developed or spliced for f_y in tension.

18.13—Foundations**18.13.1 Scope**

18.13.1.1 This section shall apply to foundations resisting earthquake-induced forces or transferring earthquake-induced forces between structure and ground.

18.13.1.2 The provisions in this section for piles, drilled piers, caissons, and slabs-on-ground shall supplement other applicable Code design and construction criteria, including 1.4.7 and 1.4.8.

18.13.2 Footings, foundation mats, and pile caps

18.13.2.1 The provisions of this section shall apply to structures assigned to SDC D, E, or F.

18.13.2.2 Longitudinal reinforcement of columns and structural walls resisting forces induced by earthquake effects shall extend into the footing, mat, or pile cap, and shall develop f_y in tension at the interface.

18.13.2.3 Columns designed assuming fixed-end conditions at the foundation shall comply with 18.13.2.2 and, if hooks are required, longitudinal reinforcement resisting flexure shall have 90-degree hooks near the bottom of the

R18.13—Foundations**R18.13.1 Scope**

Requirements for foundations supporting buildings assigned to SDC C, D, E, or F represent a consensus of a minimum level of good practice in designing and detailing concrete foundations. However, because repairs to foundations can be extremely difficult and expensive, it may be desirable that the elements of the foundation remain essentially elastic during strong ground motions. Methods to achieve this goal include designing the foundation to include an overstrength factor or an increased seismic demand level when compared to the superstructure, or comparing strengths to demands predicted by nonlinear response history analyses with appropriate consideration of uncertainty in demands (Klemencic et al. 2012).

R18.13.2 Footings, foundation mats, and pile caps

R18.13.2.3 Tests (Nilsson and Losberg 1976) have demonstrated that flexural members terminating in a footing, slab, or beam (a T-joint or L-joint) should have their hooks turned inward toward the axis of the member for the joint to

CODE

foundation with the free end of the bars oriented toward the center of the column.

18.13.2.4 Columns or boundary elements of special structural walls that have an edge within one-half the footing depth from an edge of the footing shall have transverse reinforcement in accordance with 18.7.5.2 through 18.7.5.4 provided below the top of the footing. This reinforcement shall extend into the footing, mat, or pile cap a length equal to the development length, calculated for f_y in tension, of the column or boundary element longitudinal reinforcement.

18.13.2.5 Where earthquake effects create uplift forces in boundary elements of special structural walls or columns, flexural reinforcement shall be provided in the top of the footing, mat, or pile cap to resist actions resulting from the factored load combinations, and shall be at least that required by 7.6.1 or 9.6.1.

18.13.2.6 Structural plain concrete in footings and basement walls shall be in accordance with 14.1.3.

18.13.2.7 Pile caps incorporating batter piles shall be designed to resist the full compressive strength of the batter piles acting as short columns. The slenderness effects of batter piles shall be considered for the portion of the piles in soil that is not capable of providing lateral support, or in air or water.

18.13.3 *Grade beams and slabs-on-ground*

18.13.3.1 For structures assigned to SDC D, E, or F, grade beams and beams that are part of a mat foundation subjected to flexure from columns that are part of the seismic-force-resisting system shall be in accordance with 18.6.

18.13.3.2 For structures assigned to SDC C, D, E, or F, slabs-on-ground that resist in-plane earthquake forces from walls or columns that are part of the seismic-force-resisting system shall be designed as diaphragms in accordance with 18.12. The construction documents shall clearly indicate that the slab-on-ground is a structural diaphragm and part of the seismic-force-resisting system.

18.13.4 *Foundation seismic ties*

18.13.4.1 For structures assigned to SDC C, D, E, or F, individual pile caps, piers, or caissons shall be interconnected by foundation seismic ties in orthogonal directions,

COMMENTARY

be able to resist the flexure in the member forming the stem of the T or L.

R18.13.2.4 Columns or boundary members supported close to the edge of the foundation, as often occurs near property lines, should be detailed to prevent an edge failure of the footing, pile cap, or mat.

R18.13.2.5 The purpose of this section is to emphasize that top reinforcement in footings, mats, and pile caps may be required, in addition to other required reinforcement.

R18.13.2.6 Foundation and basement walls should be reinforced in buildings assigned to SDC D, E, or F.

R18.13.2.7 Batter piles typically attract higher lateral forces during earthquakes than vertical piles. Extensive structural damage has been observed at the junction of batter piles and building foundations. The pile cap and surrounding structure should be designed for the potentially large forces that can be developed in batter piles.

R18.13.3 *Grade beams and slabs-on-ground*

For earthquake conditions, slabs-on-ground (soil-supported slabs) are often part of the lateral-force-resisting system and should be designed in accordance with this Code as well as other appropriate standards or guidelines (refer to 1.4.8).

R18.13.3.1 Grade beams resisting flexural stresses from column moments should have reinforcement details similar to the beams of the frame above the foundation.

R18.13.3.2 Slabs-on-ground often act as a diaphragm to tie the building together at the ground level and minimize the effects of out-of-phase ground motion that may occur over the footprint of the building. The construction documents should clearly state that these slabs-on-ground are structural members so as to prohibit saw cutting of the slab.

R18.13.4 *Foundation seismic ties*

R18.13.4.1 The foundation seismic ties should sufficiently interconnect foundations to act as a unit and be designed to minimize the relative movement of an individual column or tie relative to the foundation. This is essential where surface

CODE

unless it can be demonstrated that equivalent restraint is provided by other means.

18.13.4.2 For structures assigned to SDC D, E, or F, individual spread footings founded on soil defined in ASCE/SEI 7 as Site Class E or F shall be interconnected by foundation seismic ties.

18.13.4.3 Where required, foundation seismic ties shall have a design strength in tension and compression at least equal to $0.1S_{DS}$ times the greater of the pile cap or column factored dead load plus factored live load unless it is demonstrated that equivalent restraint will be provided by (a), (b), (c), or (d):

- (a) Reinforced concrete beams within the slab-on-ground
- (b) Reinforced concrete slabs-on-ground
- (c) Confinement by competent rock, hard cohesive soils, or very dense granular soils
- (d) Other means approved by the building official

18.13.4.4 For structures assigned to SDC D, E, or F, grade beams designed to act as horizontal foundation seismic ties between pile caps or footings shall have continuous longitudinal reinforcement that shall be developed within or beyond the supported column or anchored within the pile cap or footing at all discontinuities and shall satisfy (a) and (b):

- (a) The smallest cross-sectional dimension of the grade beam shall be at least equal to the clear spacing between connected columns divided by 20, but need not exceed 18 in.
- (b) Closed tie transverse reinforcement shall be provided at a spacing not to exceed the lesser of 0.5 times the smallest orthogonal cross-sectional dimension and 12 in.

18.13.5 *Deep foundations*

18.13.5.1 This section shall apply to the following types of deep foundations

- (a) Uncased cast-in-place concrete drilled or augered piles
- (b) Metal cased concrete piles
- (c) Concrete filled pipe piles
- (d) Precast concrete piles

18.13.5.2 For structures assigned to SDC C, D, E, or F, piles, piers, or caissons resisting tension loads shall have continuous longitudinal reinforcement over their length to resist design tension forces.

18.13.5.3 For structures assigned to SDC C, D, E, or F, the minimum longitudinal and transverse reinforcement required by 18.13.5.7 through 18.13.5.10 shall be extended

COMMENTARY

soils are soft enough to require deep foundations or where the site soils are susceptible to liquefaction.

R18.13.4.2 The ties between footings should have the same characteristics as the ties between pile caps in R18.13.4.1.

R18.13.4.3 The minimum foundation seismic tie design strength requirement based on a percentage of the factored dead plus live load provides a minimum connection between foundation elements. Other types of restraint can be used if substantiated as equivalent to the minimum tie design strength. The required design strength for the tie beam must be at least equal to $0.1S_{DS}$ times the larger force on either end of the tie beam, and that force is from the column or pile cap, whichever applies.

R18.13.5 *Deep foundations*

Adequate performance of piles and caissons for earthquake effects requires that these provisions be met in addition to other applicable standards or guidelines (refer to [R1.4.7](#)).

R18.13.5.3 Minimum reinforcement lengths for both longitudinal and transverse reinforcement are based on the assumption that soil is capable of providing lateral

CODE

over the entire unsupported length for the portion of deep foundation member in air or water, or in soil that is not capable of providing adequate lateral restraint to prevent buckling throughout this length.

18.13.5.4 For structures assigned to SDC C, D, E, or F, hoops, spirals, and ties in deep foundation members shall be terminated with seismic hooks.

18.13.5.5 For structures assigned to SDC D, E, or F or located in Site Class E or F, concrete deep foundation members shall have transverse reinforcement in accordance with 18.7.5.2, 18.7.5.3, and Table 18.7.5.4 Item (e) within seven member diameters above and below the interfaces between strata that are hard or stiff and strata that are liquefiable or soft.

18.13.5.6 For structures assigned to SDC D, E, or F, in foundations supporting one- and two-story stud bearing wall construction, concrete piles, piers or caissons, and foundation ties are exempt from the transverse reinforcement requirements of 18.13.5.3 through 18.13.5.5.

18.13.5.7 *Uncased cast-in-place drilled or augered concrete piles or piers*

18.13.5.7.1 For structures assigned to SDC C, D, E, or F, reinforcement shall be provided in uncased cast-in-place drilled or augered concrete piles where required by analysis and in accordance with the requirements in Table 18.13.5.7.1.

COMMENTARY

support. For portions of the pile above ground, typically in air or water, or where soil is not capable of providing this lateral restraint, the minimum reinforced lengths should be increased, and the member should be designed as a column.

R18.13.5.5 During earthquakes, piles can be subjected to high flexural and shear demands at points of discontinuity, such as at interfaces between stiff and soft soil strata. **ASCE/SEI 7** defines limits for soil strata. Transverse reinforcement is required in these regions to provide ductile behavior. In determining the portions of a pile with increased transverse reinforcement, accommodations are often made to the length of the reinforced zone for transverse reinforcement to account for variations in the driven pile tip elevations and variations in the interface elevations between stiff and soft soil strata.

R18.13.5.7 *Uncased cast-in-place drilled or augered concrete piles or piers*

R18.13.5.7.1 Longitudinal and transverse reinforcement requirements prescribed by this section result in ductility consistent with the applicable Seismic Design Category (SDC) to withstand ground deformation that occurs during earthquakes.

Where piles are subjected to significant uplift forces, the longitudinal reinforcement length required by analysis may exceed the minimum reinforcement length requirements.

Transverse reinforcement is required at the top of the pile to provide ductile performance where flexural yielding can potentially occur. For SDC D, E, and F and Site Classes A, B, C, and D, one-half of the transverse reinforcement for special moment frame columns is acceptable because some level of confinement is attributed to competent soils. For Site Class E and F, full column confinement is required because the soils are either liquefiable or not considered competent enough to provide confinement.

CODE

COMMENTARY

Table 18.13.5.7.1—Minimum reinforcement for uncased cast-in-place or augered concrete piles or piers

Minimum reinforcement		SDC C – All Site Classes	SDC D, E, and F – Site Class A, B, C, and D	SDC D, E, and F – Site Class E and F
Minimum longitudinal reinforcement ratio (minimum number of bars)		0.0025 (minimum number of bars in accordance with 10.7.3.1)	0.005 (minimum number of bars in accordance with 10.7.3.1)	0.005 (minimum number of bars in accordance with 10.7.3.1)
Minimum reinforced pile length		Longest of (a) through (d): (a) 1/3 pile length (b) 10 ft (c) 3 times the pile diameter (d) Flexural length of pile - distance from bottom of pile cap to where $0.4M_{cr}$ exceeds M_u	Longest of (a) through (d): (a) 1/2 pile length (b) 10 ft (c) 3 times the pile diameter (d) Flexural length of pile - distance from bottom of pile cap to where $0.4M_{cr}$ exceeds M_u	Full length of pile except in accordance with [1] or [2].
Transverse confinement reinforcement zone	Length of reinforcement zone	3 times the pile diameter from the bottom of the pile cap	3 times the pile diameter from the bottom of the pile cap	7 times the pile diameter from the bottom of the pile cap
	Type of transverse reinforcement	Closed ties or spirals with a minimum 3/8 in. diameter	Minimum of No. 3 closed tie or 3/8 in. diameter spiral for piles ≤ 20 in. diameter Minimum No. 4 closed tie or 1/2 in. diameter spiral for piles > 20 in. diameter	
	Spacing and amount of transverse reinforcement	Spacing shall not exceed lesser of 6 in. or 8 longitudinal bar diameters	In accordance with 18.7.5.3 and not less than one-half the requirement of Table 18.7.5.4 Item (e)	In accordance with 18.7.5.3 and not less than the requirement of Table 18.7.5.4 Item (e).
Transverse reinforcement in remainder of reinforced pile length	Type of transverse reinforcement	Closed ties or spirals with minimum 3/8 in. diameter	Minimum of No. 3 closed tie or 3/8 in. diameter spiral for piles ≤ 20 in. diameter Minimum of No. 4 closed tie or 1/2 in. diameter spiral for piles > 20 in. diameter	
	Spacing and amount of transverse reinforcement	Maximum spacing of 16 longitudinal bar diameters	In accordance with 18.7.5.2 Spacing shall not exceed the least of (a) through (c): (a) 12 longitudinal bar diameters (b) 1/2 the pile diameter (c) 12 in.	

[1] For piles sufficiently embedded in firm soil or rock, reinforcement shall be permitted to be terminated a length above the tip equal to the lesser of 5 percent of the pile length and 33 percent of the length of the pile within rock or firm soil.

[2] In lieu of providing full length minimum flexural reinforcement, the deep foundation element shall be designed to withstand maximum imposed curvatures from the earthquake ground motions and structural response. Curvatures shall include free-field soil strains modified for soil-foundation-structure interaction coupled with foundation element deformations associated with earthquake loads imparted to the foundation by the structure. Minimum reinforced length shall not be less than the requirement for SDC D, E, or F; Site Class D.

18.13.5.7.2 Minimum longitudinal and transverse reinforcement shall be provided along minimum reinforced lengths measured from the top of the pile in accordance with Table 18.13.5.7.1.

18.13.5.7.3 Longitudinal reinforcement shall extend at least the development length, calculated for f_y in tension, beyond the flexural length of the pile, which is defined in Table 18.13.5.7.1 as the distance from the bottom of the pile cap to where $0.4M_{cr} > M_u$.

R18.13.5.7.3 Reinforcement should extend ℓ_d beyond the point where plain concrete is no longer adequate to resist the factored moment.

18.13.5.8 Metal-cased concrete piles

18.13.5.8.1 For structures assigned to SDC C, D, E, or F, longitudinal reinforcement requirements and minimum reinforced lengths for metal-cased concrete piles shall be the same as for uncased concrete piles in 18.13.5.7.

18.13.5.8.2 Metal-cased concrete piles shall have a spiral-welded metal casing of a thickness not less than 0.0747 in.

R18.13.5.8 Metal-cased concrete piles

CODE

(No. 14 gauge) that is adequately protected from possible deleterious action due to soil constituents, changing water levels, or other factors indicated by boring records of site conditions.

18.13.5.9 Concrete-filled pipe piles

18.13.5.9.1 For structures assigned to SDC C, D, E or F, concrete-filled pipe piles shall have longitudinal reinforcement in the top of the pile with a total area of at least $0.01A_g$ and with a minimum length within the pile equal to two times the required embedment length into the pile cap, but not less than the development length, calculated for f_y in tension, of the reinforcement.

18.13.5.10 Precast concrete piles

18.13.5.10.1 For precast concrete driven piles, the length of transverse reinforcement provided shall be sufficient to account for potential variations in the elevation of pile tips.

18.13.5.10.2 Precast nonprestressed concrete piles for structures assigned to SDC C shall satisfy (a) through (d):

- (a) Minimum longitudinal steel reinforcement ratio shall be 0.01.
- (b) Longitudinal reinforcement shall be enclosed within a minimum of No. 3 closed ties or 3/8 in. diameter spirals, for up to 20 in. diameter piles, and No. 4 closed ties or 1/2 in. diameter spirals, for larger diameter piles.
- (c) Spacing of transverse reinforcement within a distance of 3 times the least cross-sectional dimension of the pile from the bottom of the pile cap shall not exceed the lesser of 8 times the diameter of the smallest longitudinal bar and 6 in.
- (d) Transverse reinforcement shall be provided throughout the length of the pile at a spacing not exceeding 6 in.

18.13.5.10.3 For structures assigned to SDC D, E, or F, precast nonprestressed concrete piles shall satisfy the requirements of 18.13.5.10.2 and the requirements for uncased cast-in-place or augered concrete piles in SDC D, E, or F in Table 18.13.5.7.1.

18.13.5.10.4 For structures assigned to SDC C, precast-prestressed concrete piles shall satisfy (a) and (b):

- (a) If the transverse reinforcement consists of spirals or circular hoops, the volumetric ratio of transverse reinforcement, ρ_s , in the upper 20 ft shall not be less than that

COMMENTARY

R18.13.5.8.2 Spiral-welded metal casing with the specified wall thickness provides confinement equivalent to closed ties or spirals required in an uncased concrete pile and eliminates the need for confinement ties.

R18.13.5.9 Concrete-filled pipe piles

R18.13.5.9.1 For resistance to uplift forces, concrete bond to the steel pipe is to be ignored in determining anchorage of the pile. Concrete shrinkage can be detrimental to bond, therefore shrinkage should be controlled, or force transfer via other methods such as headed studs or surface irregularities on the pipe should be considered. Reinforcement at the top of the pile is extended into the pile cap to tie the elements together and assist transfer of force to the pile cap.

R18.13.5.10 Precast concrete piles

R18.13.5.10.1 The potential for driving precast piles to a tip elevation different than that specified in the construction documents should be considered when detailing the pile. If the pile reaches refusal at a shallower depth, a longer length of pile will need to be cut off. If this possibility is not foreseen, the length of transverse reinforcement required by these provisions may not be provided after the excess pile length is cut off.

R18.13.5.10.4

(a) In a study of minimum confinement reinforcement for prestressed concrete piles (Sritharan et al. 2016), the relationship between curvature ductility demand on prestressed piles and overall system ductility demand was considered in the context of all soil profiles identified in ASCE/SEI 7. It was concluded that Eq. (18.13.5.10.4b)

CODE

calculated by Eq. (18.13.5.10.4a) or calculated from a more detailed analysis by Eq. (18.13.5.10.4b):

$$0.15 \left(\frac{f'_c}{f_{yt}} \right) \quad (18.13.5.10.4a)$$

$$0.04 \left(\frac{f'_c}{f_{yt}} \right) \left(2.8 + \frac{2.3P_u}{f'_c A_g} \right) \quad (18.13.5.10.4b)$$

and f_{yt} shall not be taken greater than 100,000 psi.

(b) A minimum of one-half of the volumetric ratio of spiral reinforcement required by Eq. (18.13.5.10.4a) or Eq. (18.13.5.10.4b) shall be provided for the remaining length of the pile.

18.13.5.10.5 For structures assigned to SDC D, E, or F, precast-prestressed concrete piles shall satisfy (a) through (e) and the ductile pile region shall be defined as the length of pile measured from the bottom of the pile cap to the point of zero curvature plus 3 times the least pile dimension, but not less than 35 ft. If the total pile length in the soil is 35 ft or less, the ductile pile region shall be taken as the entire length of the pile:

(a) In the ductile pile region, the center-to-center spacing of spirals or hoop reinforcement shall not exceed the least of 0.2 times the least pile dimension, 6 times the diameter of the longitudinal strand, and 6 in.

(b) Spiral reinforcement shall be spliced by lapping one full turn, by welding, or by the use of a mechanical splice. If spiral reinforcement is lap spliced, the ends of the spiral shall terminate in a seismic hook. Mechanical and welded splices of deformed bars shall comply with 25.5.7.

(c) If the transverse reinforcement consists of spirals, or circular hoops, the volumetric ratio of transverse reinforcement, ρ_s , in the ductile pile region shall not be less than that calculated by Eq. (18.13.5.10.5a) or calculated from a more detailed analysis by Eq. (18.13.5.10.5b), and the required volumetric ratio shall be permitted to be obtained by providing an inner and outer spiral.

$$0.2 \left(\frac{f'_c}{f_{yt}} \right) \quad (18.13.5.10.5a)$$

$$0.06 \left(\frac{f'_c}{f_{yt}} \right) \left(2.8 + \frac{2.3P_u}{f'_c A_g} \right) \quad (18.13.5.10.5b)$$

and f_{yt} shall not be taken as greater than 100,000 psi.

(d) Outside of the ductile pile region, spiral or hoop reinforcement shall be provided with a volumetric ratio not less than one-half of that required within the ductile pile region, and the maximum spacing shall be in accordance with Table 13.4.5.6(b).

(e) If transverse reinforcement consists of rectangular hoops and crossties, the total cross-sectional area of lateral transverse reinforcement in the ductile region shall be the greater of Eq. (18.13.5.10.5c) and Eq. (18.13.5.10.5d). The hoops and crossties shall be equivalent to deformed

COMMENTARY

results in adequate deformation capacity for structures assigned to SDC C. The factored axial force on a pile should be determined from Eq. (5.3.1c) and Eq. (5.3.1g) with 5.3.7 and 5.3.8 as applicable.

R18.13.5.10.5 Observed damage from earthquakes and concerns about the accuracy of calculated pile demands have led to prescriptive requirements for confinement of potential yielding regions of piles. The required confinement is intended to provide adequate ductility capacity for structures assigned to SDC D, E, and F (Sriharan et al. 2016).

CODE

bars not less than No. 3 in size, and rectangular hoop ends shall terminate at a corner with seismic hooks.

$$A_{sh} = 0.3s b_c \left(\frac{f'_c}{f_{yt}} \right) \left(\frac{A_g}{A_{ch}} - 1.0 \right) \left(0.5 + \frac{1.4P_u}{f'_c A_g} \right) \quad (18.13.5.10.5c)$$

$$A_{sh} = 0.12s b_c \left(\frac{f'_c}{f_{yt}} \right) \left(0.5 + \frac{1.4P_u}{f'_c A_g} \right) \quad (18.13.5.10.5d)$$

and f_{yt} shall not be taken as greater than 100,000 psi.

18.13.5.10.6 For structures assigned to SDC C, D, E, or F, the maximum factored axial load that can be applied to precast, prestressed piles subjected to a combination of earthquake lateral force and axial load shall not exceed the following values:

- (a) $0.2f'_c A_g$ for square piles with side dimension of 14 in. or less
- (b) $0.25f'_c A_g$ for square piles with side dimension greater than 14 in.
- (c) $0.4f'_c A_g$ for circular or octagonal piles less than or equal to 24 in. in diameter
- (d) $0.45f'_c A_g$ for circular or octagonal piles greater than 24 in. in diameter

18.13.6 Anchorage of piles, piers, and caissons

18.13.6.1 For structures assigned to SDC C, D, E, or F, the longitudinal reinforcement in piles, piers, or caissons resisting tension loads shall be detailed to transfer tension forces within the pile cap to supported structural members.

18.13.6.2 For structures assigned to SDC C, D, E, or F, concrete piles and concrete filled pipe piles shall be connected to the pile cap by embedding the pile reinforcement in the pile cap a distance equal to the development length or by the use of field-placed dowels anchored in the concrete pile. For deformed bars, the compression development length is used if the pile is in compression. In the case of uplift, the tension development length is used without reduction in length for excess reinforcement.

18.13.6.3 For structures assigned to SDC D, E, or F, if tension forces induced by earthquake effects are transferred between pile cap or mat foundation and precast pile by reinforcing bars grouted or post-installed in the top of the pile, the grouting system shall have been demonstrated by testing to develop at least $1.25f_y$ of the bar.

COMMENTARY

R18.13.5.10.6 The axial load in precast prestressed piles is limited to preclude spalling of the concrete cover prior to the pile section experiencing flexural cracking, as this will result in a significant loss in pile resistance (Sriharan et al. 2016).

Research (Ryan and Mays 2021) indicates an increase in axial load may be permitted for precast prestressed concrete piles with larger cross-sections; hence, the distinction in the axial load limit as a function of pile size.

R18.13.6 Anchorage of piles, piers, and caissons

R18.13.6.1 A load path is necessary at pile caps to transfer tension forces from the reinforcing bars in the column or boundary element through the pile cap to the reinforcement of the pile or caisson. Examples of different types of pile connections to pile caps are available in ASCE/COPRI Standard for the Seismic Design of Piers and Wharves (61-14).

R18.13.6.2 Development length is determined according to requirements of Chapter 25. Embedment lengths less than the development length for calculated stresses less than f_y are not permitted, as indicated in 25.4.10.2. Development of the pile longitudinal reinforcement into the pile cap is intended to enable the capacity of the pile to pile cap connection to meet or exceed the pile section strength.

R18.13.6.3 Grouted dowels in a blockout in the top of a precast concrete pile need to be developed, and testing is a practical means of demonstrating strength. Alternatively, reinforcing bars can be cast in the upper portion of the pile, exposed by chipping of concrete and mechanically spliced or welded to an extension.

CODE

18.14—Members not designated as part of the seismic-force-resisting system**18.14.1 Scope**

18.14.1.1 This section shall apply to members not designated as part of the seismic-force-resisting system in structures assigned to SDC D, E, and F.

18.14.2 Design actions

18.14.2.1 Members not designated as part of the seismic-force-resisting system shall be evaluated for gravity load combinations of 5.3 including the effect of vertical ground motion acting simultaneously with the design displacement δ_u .

18.14.3 Cast-in-place beams, columns, and joints

18.14.3.1 Cast-in-place beams, columns, and joints shall be detailed in accordance with 18.14.3.2 or 18.14.3.3 depending on the magnitude of moments and shears induced in those members when subjected to the design displacement δ_u . If effects of δ_u are not explicitly checked, the provisions of 18.14.3.3 shall be satisfied.

18.14.3.2 Where the induced moments and shears do not exceed the design moment and shear strength of the frame member, (a) through (d) shall be satisfied:

- (a) Beams shall satisfy 18.6.3.1. Transverse reinforcement satisfying 25.7 shall be provided throughout the length of the beam at spacing not to exceed $d/2$. Where factored axial force exceeds $A_g f_c'/10$, transverse reinforcement shall be hoops satisfying 18.7.5.2 at a spacing not to exceed the lesser of $6d_b$ of the smallest enclosed longitudinal bar and 6 in.

COMMENTARY

R18.14—Members not designated as part of the seismic-force-resisting system

This section applies only to structures assigned to SDC D, E, or F. For those SDCs, all structural members not designated as a part of the seismic-force-resisting system are required to be designed to support gravity loads and the load effects of vertical ground motion, while subjected to the design displacement. For concrete structures, the provisions of this section satisfy this requirement for columns, beams, slabs, and wall piers of the gravity system.

Design displacement is defined in Chapter 2. Models used to determine design displacement of buildings should be chosen to produce results that conservatively bound the values expected during the design earthquake and should include, as appropriate, effects of concrete cracking, foundation flexibility, and deformation of floor and roof diaphragms.

The provisions of 18.14 are intended to enable ductile flexural yielding of columns, beams, slabs, and wall piers under the design displacement, by providing sufficient confinement and shear strength in elements that yield.

R18.14.3 Cast-in-place beams, columns, and joints

R18.14.3.1 Cast-in-place columns and beams are assumed to yield if the combined effects of factored gravity loads and design displacements exceed the strengths specified, or if the effects of design displacements are not calculated. Requirements for transverse reinforcement and shear strength vary with member type and whether the member yields under the design displacement.

CODE

(b) Columns shall satisfy 18.7.4.1 and 18.7.6. Spiral reinforcement satisfying 25.7.3 or hoop reinforcement satisfying 25.7.4 shall be provided over the full length of the column with spacing not to exceed the lesser of $6d_b$ of the smallest enclosed longitudinal bar and 6 in. Transverse reinforcement satisfying 18.7.5.2(a) through (e) shall be provided over a length ℓ_o , as defined in 18.7.5.1, from each joint face.

(c) Columns with factored gravity axial forces exceeding $0.35P_o$ shall satisfy 18.14.3.2(b) and 18.7.5.7. The minimum amount of transverse reinforcement provided shall be, for rectilinear hoops, one-half the greater of Table 18.7.5.4 parts (a) and (b) and, for spiral or circular hoops, one-half the greater of Table 18.7.5.4 parts (d) and (e). This transverse reinforcement shall be provided over a length ℓ_o , as defined in 18.7.5.1, from each joint face.

(d) Joints shall satisfy Chapter 15.

18.14.3.3 Where the induced moments or shears exceed ϕM_n or ϕV_n of the frame member, or if induced moments or shears are not calculated, (a) through (d) shall be satisfied:

- (a) Materials, mechanical splices, and welded splices shall satisfy the requirements for special moment frames in 18.2.5 through 18.2.8.
- (b) Beams shall satisfy 18.14.3.2(a) and 18.6.5.
- (c) Columns shall satisfy 18.7.4, 18.7.5, and 18.7.6, except 18.7.4.3 need not be satisfied.
- (d) Joints shall satisfy 18.4.4.1.

18.14.4 *Precast beams and columns*

18.14.4.1 Precast concrete frame members assumed not to contribute to lateral resistance, including their connections, shall satisfy (a) through (d):

- (a) Requirements of 18.14.3
- (b) Ties specified in 18.14.3.2(b) over the entire column height, including the depth of the beams
- (c) Structural integrity reinforcement, in accordance with 4.10
- (d) Bearing length at the support of a beam shall be at least 2 in. longer than determined from 16.2.6

18.14.5 *Slab-column connections*

18.14.5.1 For slab-column connections of two-way slabs without beams, slab shear reinforcement satisfying the requirements of 18.14.5.3 and either 8.7.6 or 8.7.7 shall be provided at any slab critical section defined in 22.6.4.1 for the following conditions:

COMMENTARY

R18.14.4 *Precast beams and columns*

R18.14.4.1 Damage to some buildings with precast concrete gravity systems during the 1994 Northridge earthquake was attributed to several factors addressed in this section. Columns should contain ties over their entire height, frame members not proportioned to resist earthquake forces should be tied together, and longer bearing lengths should be used to maintain integrity of the gravity system during ground motion. The 2 in. increase in bearing length is based on an assumed 4 percent story drift ratio and 50 in. beam depth, and is considered to be conservative for the ground motions expected for structures assigned to SDC D, E, or F. In addition to this provision, precast frame members assumed not to contribute to lateral resistance should also satisfy the requirements for cast-in-place construction addressed in 18.14.3, as applicable.

R18.14.5 *Slab-column connections*

R18.14.5.1 Provisions for shear reinforcement at slab-column connections are intended to reduce the likelihood of slab punching shear failure if the design story drift ratio exceeds the value specified.

No calculation of induced moments is required, based on research (Megally and Ghali 2002; Moehle 1996; Kang and

CODE

- (a) Nonprestressed slabs where $\Delta_x/h_{sx} \geq 0.035 - (1/20)(v_{uv}/\phi v_c)$
- (b) Unbonded post-tensioned slabs with f_{pc} in each direction meeting the requirements of 8.6.2.1, where $\Delta_x/h_{sx} \geq 0.040 - (1/20)(v_{uv}/\phi v_c)$

The load combinations to be evaluated for v_{uv} shall only include those with E . The value of (Δ_x/h_{sx}) shall be taken as the greater of the values of the adjacent stories above and below the slab-column connection, v_c shall be calculated in accordance with 22.6.5; and, for unbonded post-tensioned slabs, the value of V_p shall be taken as zero when calculating v_c .

COMMENTARY

Wallace 2006; Kang et al. 2007) that identifies the likelihood of punching shear failure considering the story drift ratio and shear stress v_{uv} due to gravity loads and the vertical component of earthquake loads, without moment transfer, about the slab critical section. Figure R18.14.5.1 illustrates the requirement for nonprestressed and unbonded post-tensioned slab-column connections. The requirement can be satisfied by adding slab shear reinforcement, increasing slab thickness, changing the design to reduce the design story drift ratio, or a combination of these.

If column capitals, drop panels, shear caps, or other changes in slab thickness are used, the requirements of 18.14.5 are evaluated at all potential critical sections, as required by 22.6.5.1.

Post-tensioned slab-column connections with f_{pc} in each direction not meeting the requirements of 8.6.2.1 can be designed as nonprestressed slab-column connections in accordance with 8.2.3.




Fig. R18.14.5.1—Illustration of the criteria of 18.14.5.1.

18.14.5.2 The shear reinforcement requirements of 18.14.5.1 need not be satisfied if (a) or (b) is met:

- (a) $\Delta_x/h_{sx} \leq 0.005$ for nonprestressed slabs
- (b) $\Delta_x/h_{sx} \leq 0.01$ for unbonded post-tensioned slabs with f_{pc} in each direction meeting the requirements of 8.6.2.1

18.14.5.3 Required slab shear reinforcement shall provide $v_s \geq 3.5\sqrt{f'_c}$ at the slab critical section and shall extend at least four times the slab thickness from the face of the support adjacent to the slab critical section.

18.14.6 Wall piers

18.14.6.1 Wall piers not designated as part of the seismic-force-resisting system shall satisfy the requirements of 18.10.8. Where the general building code includes provisions to account for overstrength of the seismic-force-resisting system, it shall be permitted to calculate the design shear force as Ω_o times the shear induced under design displacements, δ_u .

R18.14.6 Wall piers

R18.14.6.1 Section 18.10.8 requires that the design shear force be determined according to 18.7.6.1, which in some cases may result in unrealistically large forces. As an alternative, the design shear force can be determined as the product of an overstrength factor and the shear induced when the wall pier is displaced by δ_u . The overstrength factor Ω_o included in FEMA P-749, ASCE/SEI 7, and the 2021 IBC can be used for this purpose.

CHAPTER 19—CONCRETE: DESIGN AND DURABILITY REQUIREMENTS

CODE

COMMENTARY

19.1—Scope

19.1.1 This chapter shall apply to concrete, including:

- (a) Properties to be used for design
- (b) Durability requirements

19.1.2 This chapter shall apply to durability requirements for grout used for bonded tendons in accordance with 19.4.

19.2—Concrete design properties

19.2.1 Specified compressive strength

19.2.1.1 The value of f_c' shall be in accordance with (a) through (d):

- (a) Limits for f_c' in Table 19.2.1.1. Limits apply to both normalweight and lightweight concrete.
- (b) Durability requirements in Table 19.3.2.1
- (c) Structural strength requirements
- (d) f_c' for lightweight concrete in special moment frames and special structural walls, and their foundations, shall not exceed 5000 psi, unless demonstrated by experimental evidence that members made with lightweight concrete provide strength and toughness equal to or exceeding those of comparable members made with normalweight concrete of the same strength.

Table 19.2.1.1—Limits for f_c'

Application	Minimum f_c' , psi
General	2500
Foundations for structures assigned to SDC A, B, or C	2500
Foundations for Residential and Utility use and occupancy classification with stud bearing wall construction two stories or less assigned to SDC D, E, or F	2500
Foundations for structures assigned to SDC D, E, or F other than Residential and Utility use and occupancy classification with stud bearing wall construction two stories or less	3000
Special moment frames	3000
Special structural walls with Grade 60 or 80 reinforcement	3000
Special structural walls with Grade 100 reinforcement	5000
Precast-nonprestressed driven piles	4000
Drilled shafts	4000
Precast-prestressed driven piles	5000

19.2.1.2 The specified compressive strength shall be used for proportioning of concrete mixtures in 26.4.3 and for testing and acceptance of concrete in 26.12.3.

19.2.1.3 Unless otherwise specified, f_c' shall be based on 28-day tests. If other than 28 days, test age for f_c' shall be indicated in the construction documents.

R19.1—Scope

R19.2—Concrete design properties

R19.2.1 Specified compressive strength

Requirements for concrete mixtures are based on the philosophy that concrete should provide both adequate strength and durability. The Code defines a minimum value of f_c' for structural concrete. There is no limit on the maximum value of f_c' except as required by specific Code provisions.

Concrete mixtures proportioned in accordance with 26.4.3 should achieve an average compressive strength that exceeds the value of f_c' used in the structural design calculations. The amount by which the average strength of concrete exceeds f_c' is based on statistical concepts. When concrete is designed to achieve a strength level greater than f_c' , it ensures that the concrete strength tests will have a high probability of meeting the strength acceptance criteria in 26.12.3. The durability requirements prescribed in Table 19.3.2.1 are to be satisfied in addition to meeting the minimum f_c' of 19.2.1. Under some circumstances, durability requirements may dictate a higher f_c' than that required for structural purposes.

Available test data do not include lower strength concrete with Grade 100 reinforcement in special structural walls (refer to R18.2.6).

For design of special moment frames and special structural walls used to resist earthquake forces, the Code limits the maximum f_c' of lightweight concrete to 5000 psi. This limit is imposed primarily because of a paucity of experimental and field data on the behavior of members made with lightweight concrete subjected to displacement reversals in the nonlinear range.

Minimum concrete strengths are increased for special seismic systems with $f_y > 80,000$ psi to enhance bar anchorage and reduce the neutral axis depth for improved performance.

The Code also limits f_c' for design of anchors to concrete. The requirements are in 17.3.1.

CODE

COMMENTARY

19.2.1.4 For pretensioned members, f'_{ci} shall be at least 3000 psi.

19.2.2 Modulus of elasticity

19.2.2.1 It shall be permitted to calculate E_c in accordance with (a) or (b):

(a) For values of w_c between 90 and 160 lb/ft³

$$E_c = w_c^{1.5} 33 \sqrt{f'_c} \text{ (in psi)} \quad (19.2.2.1.a)$$

(b) For normalweight concrete

$$E_c = 57,000 \sqrt{f'_c} \text{ (in psi)} \quad (19.2.2.1.b)$$

19.2.2.2 It shall be permitted to specify E_c based upon testing of concrete mixtures to be used in the Work in accordance with (a) through (c):

(a) Specified E_c shall be used for proportioning concrete mixtures in accordance with **26.4.3**.

(b) Testing to verify that the specified E_c has been achieved shall be conducted, and results shall be provided with the mixture submittal.

(c) Test age of measurement of E_c shall be 28 days or as indicated in the construction documents.

R19.2.2 Modulus of elasticity

R19.2.2.1 Equations in 19.2.2.1 provide an estimate of E_c for general design use. Studies leading to the expression for E_c of concrete are summarized in **Pauw (1960)**, where E_c is defined as the slope of the line drawn from a stress of zero to 45 percent of the compressive strength using the stress-strain curve of the concrete. This definition is slightly different than the definition in **ASTM C469**. ASTM C469 defines E_c using 40% of the compressive strength.

The modulus of elasticity is sensitive to a number of variables including aggregate type, concrete constituents, mixture proportions, bond between paste and aggregate, and the age of the concrete. This sensitivity, coupled with the inherent variability in the properties of the constituent materials and quality control exercised during construction, can result in differences between measured and calculated values for deflection, drift, periods of vibration, and other quantities that depend on E_c . Refer to **ACI PRC-435** for more information on the use of E_c , especially when used in deflection calculations.

Modulus of elasticity determined by calculation using the Code equations has been shown to be appropriate for most applications based on many years of use. For some applications, however, these equations may not provide sufficiently accurate estimates of actual values. Larger differences between measured and calculated values of E_c have been observed for high-strength concrete ($f'_c > 8000$ psi), lightweight concrete, and for mixtures with low coarse aggregate volume, as can occur with self-consolidating concrete. Refer to **ACI PRC-363**, **ACI PRC-213**, and **ACI PRC-237** for more information.

R19.2.2.2 For any project, E_c used for design may be specified and verified by testing. Design conditions that are sensitive to the value of E_c may warrant testing. Examples include applications where deflections are critical, tall buildings or similar structures for which axial deformation or lateral stiffness impact performance, and where estimation of E_c is important to acceptable vibration or seismic performance.

In cases where an unintended change of stiffness may have an adverse effect on the design, such as for some seismic applications, the licensed design professional may choose to specify a range of acceptable values of E_c at a specified test age. If a range of values of E_c is specified, details of a testing program and acceptance criteria should be provided in the construction documents.

The licensed design professional may choose to specify laboratory testing of E_c at multiple ages. It should be recognized that the development of E_c over time cannot be controlled with precision.

CODE

COMMENTARY

19.2.3 Modulus of rupture

19.2.3.1 Modulus of rupture, f_r , for concrete shall be calculated by:

$$f_r = 7.5\lambda\sqrt{f'_c} \quad (19.2.3.1)$$

where the value of λ is in accordance with 19.2.4.

19.2.4 Lightweight concrete

19.2.4.1 Except as required in Table 25.4.2.5, the value of λ shall be determined using Table 19.2.4.1(a) based on the equilibrium density, w_c , of the concrete mixture used in design, or Table 19.2.4.1(b) based on the composition of the aggregate in the concrete mixture assumed in the design.

Table 19.2.4.1(a)—Values of λ for lightweight concrete based on equilibrium density

w_c , lb/ft ³	λ	
≤ 100	0.75	(a)
$100 < w_c \leq 135$	$0.0075w_c \leq 1.0$	(b)
> 135	1.0	(c)

Table 19.2.4.1(b)—Values of λ for lightweight concrete based on composition of aggregates

Concrete	Composition of aggregates	λ
All-lightweight	Fine: ASTM C330 Coarse: ASTM C330	0.75
Lightweight, fine blend	Fine: Combination of ASTM C330 and C33 Coarse: ASTM C330	0.75 to 0.85 ^[1]
Sand-lightweight	Fine: ASTM C33 Coarse: ASTM C330	0.85
Sand-lightweight, coarse blend	Fine: ASTM C33 Coarse: Combination of ASTM C330 and C33	0.85 to 1 ^[2]

^[1]Linear interpolation from 0.75 to 0.85 is permitted based on the absolute volume of normalweight fine aggregate as a fraction of the total absolute volume of fine aggregate.

^[2]Linear interpolation from 0.85 to 1 is permitted based on the absolute volume of normalweight coarse aggregate as a fraction of the total absolute volume of aggregate.

19.2.4.2 It shall be permitted to take λ as 0.75 for lightweight concrete.

19.2.4.3 The value of λ shall be taken as 1.0 for normalweight concrete.

R19.2.4 Lightweight concrete

The modification factor λ is used to account for the reduced mechanical properties of lightweight concrete compared with normalweight concrete of the same compressive strength. For design using lightweight concrete, shear strength, friction properties, splitting resistance, bond between concrete and reinforcement, and development length requirements are not taken as equivalent to normalweight concrete of the same compressive strength. The methodology for determining λ was changed in the 2019 Code to include a new method that is based on the equilibrium density of the lightweight concrete. The new method allows the designer to select a value for λ based on the equilibrium density of the lightweight concrete that is used in design. Laboratory testing on the specific mixture to be used in the structure can be accomplished if the designer desires to determine a more accurate value of λ (Ivey and Buth 1967; Hanson 1961). Table 19.2.4.1 is based on data from tests (Graybeal 2014; Greene and Graybeal 2013, 2015) of concrete made with many types of structural lightweight aggregate and having a wide range of mixture proportions that resulted in equilibrium densities over a range of 90 to 135 lb/ft³.

The second method for determining λ , which is retained from the previous code, is based on the composition of aggregates. In most cases, local concrete and aggregate suppliers have standard lightweight concrete mixtures and can provide the volumetric fractions to determine the value of λ . In the absence of such data, it is permissible to use the lower-bound value of λ for the type of lightweight concrete specified. This method is based on the assumption that, for equivalent compressive strength levels, the tensile strength of lightweight concrete is a fixed fraction of the tensile strength of normalweight concrete (Ivey and Buth 1967). The multipliers used for λ are based on data from tests on concrete made with many types of structural lightweight aggregate.

A previously included method to calculate λ based on splitting tensile strength and the corresponding value of measured compressive strength was removed from the Code in 2019.

In editions of the Code prior to 2019, the upper limit on the equilibrium density for lightweight concrete was 115 lb/ft³. With the lower limit for normalweight concrete established at 135 lb/ft³, a 20 lb/ft³ range remained that was undefined. In practice, to achieve an equilibrium density in the range of 115 to 135 lb/ft³, the use of some amount of light-

CODE

19.3—Concrete durability requirements

19.3.1 *Exposure categories and classes*

COMMENTARY

weight aggregate is required. The 2019 Code removes this undefined range by defining lightweight concrete as having an equilibrium density from 90 to 135 lb/ft³.

R19.3—Concrete durability requirements

The Code addresses concrete durability on the basis of exposure categories and exposure classes as defined in Table 19.3.1.1. The licensed design professional assigns members in the structure to the appropriate exposure category and class. The assigned exposure classes, which are based on the severity of exposure, are used to establish the appropriate concrete properties from Table 19.3.2.1 to include in the construction documents.

The Code does not include provisions for especially severe exposures, such as acids or high temperatures.

R19.3.1 *Exposure categories and classes*

The Code addresses four exposure categories that affect the requirements for concrete to ensure adequate durability:

Exposure Category F applies to concrete exposed to moisture and cycles of freezing and thawing.

Exposure Category S applies to concrete in contact with soil or water containing deleterious amounts of water-soluble sulfate ions.

Exposure Category W applies to concrete in contact with water.

Exposure Category C applies to concrete exposed to conditions that require additional protection against corrosion of reinforcement because of exposure to moisture, with or without exposure to external sources of chlorides.

Severity of exposure within each category is defined by classes with increasing numerical values representing increasingly severe exposure conditions. A classification of 0 is assigned if the exposure severity has negligible effect (is benign) or the exposure category does not apply to the member.

The following discussion provides assistance for selecting the appropriate exposure class for each of the exposure categories. Members are required to be assigned to four exposure classes, one for each exposure category, and are also required to meet the most restrictive requirements of all of these exposures. For example, an exterior elevated slab subject to deicing salt application in a cold climate might be assigned to Exposure Classes F2, S0, W2, and C2.

Exposure Category F: Whether concrete is damaged by cycles of freezing and thawing depends on the amount of water in the pores of the concrete at the time of freezing (Powers 1975). The amount of water present may be described in terms of the degree of saturation of the concrete. If the degree of saturation is high enough, there will be sufficient water in the concrete pores to produce internal tensile stresses large enough to cause cracking when the water freezes and expands. The entire member need not be

CODE

COMMENTARY

saturated to be susceptible to damage. For example, if the top 3/8 in. of a slab or outer 1/4 in. of a wall is saturated, those portions are vulnerable to damage from freezing and thawing, regardless of how dry the interior may be.

For any portion of a member to be resistant to freezing and thawing, that portion of the concrete needs to have sufficient entrained air and adequate strength. Adequate strength is obtained by requiring a low w/cm , which also reduces the pore volume and increases resistance to water penetration. Entrained air makes it more difficult for the concrete to become saturated and allows for expansion of the water when it freezes.

Exposure class varies with degree of exposure to water, as this will influence the likelihood that any portion of the concrete will be saturated when exposed to cyclic freezing and thawing. Conditions that increase the potential for saturation include longer-duration or more-frequent contact with water without intervening drainage or drying periods. The likelihood that concrete in a member will be saturated depends on project location, member location and orientation in the structure, and climate. Records of performance of similar members in existing structures in the same general location can also provide guidance in assigning exposure classes. Various deicing chemicals can increase water absorption and retention ([Spragg et al. 2011](#)), which would enable the concrete to become saturated more readily, increasing the risk of freezing and thawing damage and scaling.

Plain concrete with minimal reinforcement and metallic embedments subjected to deicing chemical application assigned to Exposure Class F2 should also be assigned to Exposure Class C2.

Exposure Category F is subdivided into three exposure classes:

- (a) Exposure Class F0 is assigned to concrete that will not be exposed to cycles of freezing and thawing.
- (b) Exposure Class F1 is assigned to concrete that will be exposed to cycles of freezing and thawing and that will have limited exposure to water. Limited exposure to water implies some contact with water and water absorption; however, it is not anticipated that the concrete will absorb sufficient water to become saturated. The licensed design professional should review the exposure conditions carefully to support the decision that the concrete is not anticipated to become saturated before freezing. Even though concrete in this exposure class is not expected to become saturated, a minimum entrained air content of 3.5 to 6% is required to reduce the potential for damage in case portions of the concrete member become saturated.
- (c) Exposure Class F2 is assigned to concrete that will be exposed to cycles of freezing and thawing and that will have frequent exposure to water. Frequent exposure to water implies that some portions of the concrete will absorb sufficient water such that over time they will have the potential to be saturated before freezing. If there is doubt about whether to assign Exposure Classes F1 or F2

CODE**COMMENTARY**

to a member, the more conservative choice, F2, should be selected. If scaling is a concern, Exposure Class F2 is appropriate. Exposure Class F3 has been deleted in the 2025 edition of the Code as redundant because it is equivalent to a combination of Exposure Classes F2 and C2. Furthermore, Exposure Class F3 incorrectly implied that scaling is only possible in the presence of deicing chemicals.

Table R19.3.1 provides examples of concrete members for each of these exposure classes.

Table R19.3.1—Examples of structural members in Exposure Category F

Exposure class	Examples
F0	• Members in climates where freezing temperatures will not be encountered • Members inside structures and not exposed to freezing • Foundations not exposed to freezing • Members buried in soil below the design frost depth
F1	• Members not subject to ponding of water or snow and ice accumulation, such as exterior walls, beams, girders, and slabs not in direct contact with soil • Foundation walls likely to be saturated
F2	• Members subject to ponding of water or snow and ice accumulation, such as exterior elevated slabs • Foundation or basement walls extending above grade that have snow and ice buildup against them • Horizontal and vertical members in contact with soil above the design frost depth

Exposure Category S is subdivided into four exposure classes:

- Exposure Class S0 is assigned for conditions where the water-soluble sulfate concentration in contact with concrete is low and injurious sulfate attack is not a concern.
- Exposure Classes S1, S2, and S3 are assigned for structural concrete members in direct contact with soluble sulfates in soil or water. The severity of exposure increases from Exposure Class S1 to S3 based on the more critical value of measured water-soluble sulfate concentration in soil or the concentration of dissolved sulfate in water. Seawater exposure is classified as Exposure Class S1.

Exposure Category W is subdivided into three exposure classes:

- Members are assigned to Exposure Class W0 if they are dry in service.
- Members are assigned to Exposure Class W1 if they may be exposed to continuous contact with water, to intermittent sources of water, or can absorb water from surrounding soil. Members assigned to W1 do not require concrete with low permeability.
- Members are assigned to Exposure Class W2 if they may be exposed to continuous contact with water, to intermittent sources of water, or can absorb water from surrounding soil,

CODE

COMMENTARY

and if the penetration of water through the concrete might reduce durability or serviceability. Members assigned to W2 require concrete with low permeability.

Exposure Category C is subdivided into three exposure classes:

- (a) Exposure Class C0 is assigned to concrete members not exposed to moisture in service.
- (b) Exposure Class C1 is assigned to concrete members requiring protection against reinforcement corrosion due to exposure to moisture, but not to external sources of chlorides in service. Because of the potential exposure to moisture, the limits on water-soluble chloride ions in the concrete materials are more stringent for this exposure class than for Exposure Class C0.
- (c) Exposure Class C2 is assigned to concrete members requiring additional protection against reinforcement corrosion or concrete degradation due to exposure to moisture and external sources of chlorides in service. Examples of exposure to external sources of chlorides include concrete in direct contact with deicing chemicals, salt, industrial chloride solutions, salt water, brackish water, seawater, spray from these sources, and airborne chlorides. Depending on prevailing winds, humidity, and geography, it is possible for airborne chlorides to reach inland up to 1 mile from the source, and sometimes farther. In cases of intracoastal or intercoastal waterways, salt lakes, and other chloride-containing bodies of water, there may not be significant quantities of airborne chlorides that would require Exposure Class C2. In cases such as islands surrounded by salt water or low-lying coastal regions with strong onshore winds, chloride exposure at greater distances may need to be addressed. **ACI PRC-362.1** provides guidance for the consideration of exposure to external chlorides that extend up to 3 miles from the source. The licensed design professional should consider local conditions and the long-term chloride penetration and corrosion performance of existing structures to at least 1 mile from the source, and sometimes farther when establishing the corrosion exposure class.

19.3.1.1 The licensed design professional shall assign exposure classes in accordance with (a) and (b) and the severity of the anticipated exposure of members for each category in Table 19.3.1.1.

- (a) Plain concrete exposed to freezing and thawing shall be assigned to Exposure Class F2 or Exposure Classes F2 and C2 depending on potential exposure to chlorides and the presence of reinforcement, embedments, or both.
- (b) Concrete potentially susceptible to freezing and thawing scaling shall be assigned to Exposure Class F2 or Exposure Classes F2 and C2 depending on potential exposure to chlorides.

R19.3.1.1

- (b) Scaling is local flaking or peeling away of the near-surface portion of hardened concrete or mortar. Horizontal concrete members that are subject to wetting are most susceptible to scaling. If exposed to an external source of chlorides from deicing or other chemicals, salts, brackish water, seawater, spray, or airborne chlorides from these sources, scaling will be exacerbated. Resistance to freezing

CODE

Table 19.3.1.1—Exposure categories and classes

Category	Class	Condition	
Freezing and thawing (F)	F0	Concrete not exposed to freezing-and-thawing cycles	
	F1	Concrete exposed to freezing-and-thawing cycles with limited exposure to water	
	F2	Concrete exposed to freezing-and-thawing cycles with frequent exposure to water	
Sulfate (S)		Water-soluble sulfate (SO_4^{2-}) in soil, percent by mass ^[1]	Dissolved sulfate (SO_4^{2-}) in water, ppm ^[2]
	S0	$\text{SO}_4^{2-} < 0.10$	$\text{SO}_4^{2-} < 150$
	S1	$0.10 \leq \text{SO}_4^{2-} < 0.20$	$150 \leq \text{SO}_4^{2-} < 1500$ or seawater
	S2	$0.20 \leq \text{SO}_4^{2-} \leq 2.00$	$1500 \leq \text{SO}_4^{2-} \leq 10,000$
	S3	$\text{SO}_4^{2-} > 2.00$	$\text{SO}_4^{2-} > 10,000$
In contact with water (W)	W0	Concrete dry in service	
	W1	Concrete in contact with water where low permeability is not required	
	W2	Concrete in contact with water where low permeability is required	
Corrosion protection of reinforcement (C)	C0	Concrete dry or protected from moisture	
	C1	Concrete exposed to moisture but not to an external source of chlorides	
	C2	Concrete exposed to moisture and an external source of chlorides from deicing or other chemicals, salt, brackish water, seawater, spray, or airborne chlorides from these sources.	

^[1]Percent sulfate by mass in soil shall be determined by ASTM C1580.

^[2]Concentration of dissolved sulfates in water, in ppm, shall be determined by ASTM D516.

COMMENTARY

and thawing scaling requires appropriate selection of materials, proper finishing, and proper curing. Causes and prevention of scaling are discussed in [ACI PRC-302.1](#) and [ACI PRC-201.2](#).

19.3.2 Requirements for concrete mixtures

R19.3.2 Requirements for concrete mixtures

For the Exposure Classes addressed by the Code, durability is impacted by the resistance of the concrete to fluid or ion (chloride or sulfate) penetration. This resistance is primarily affected by the w/cm and the types of cementitious and supplementary cementitious materials used in the concrete. The Code provides limits on w/cm in Table 19.3.2.1 to achieve the intended durability. Combinations of the materials listed in Table 26.4.1.1(a) are also commonly used to improve durability. Refer to [ACI PRC-201.2](#) for guidance on appropriate concrete mixtures for specific exposure conditions.

Because w/cm of concrete cannot be accurately verified in the field using standard test methods, strength tests are used as a surrogate. Representative values for minimum f'_c have been assigned to each w/cm limit in Table 19.3.2.1. The acceptance criteria for strength tests in [26.12](#) establish a basis to indicate that the maximum w/cm has not been exceeded. For this approach to be reliable, the values of f'_c specified in construction documents should be consistent with the maximum w/cm . Considering the wide range of

CODE

COMMENTARY

materials and concrete mixtures possible, including regional variations, the minimum f_c' limit in Table 19.3.2.1 associated with the maximum w/cm should not be considered absolute. The average strength of concrete mixtures for a given w/cm can in some cases be considerably higher than the average strength expected for the representative value of f_c' . For a given exposure class, the licensed design professional may choose to specify a higher value of f_c' than listed in the table to obtain better consistency between the maximum w/cm and f_c' . This improves the confidence that concrete complies with the w/cm limit if the strength acceptance criteria are satisfied.

As stated in the footnote to Table 19.3.2.1, maximum w/cm limits are not specified for lightweight concrete because the amount of mixing water that is absorbed by the lightweight aggregates makes calculation of w/cm uncertain. Therefore, only a minimum f_c' is specified to achieve the required durability.

Table 19.3.2.1 provides the requirements for concrete on the basis of the assigned exposure classes. The most restrictive requirements are applicable. For example, a member assigned to Exposure Class W1 and Exposure Class S2 would require concrete to comply with a maximum w/cm of 0.45 and a minimum f_c' of 4500 psi because the requirement for Exposure Class S2 is more restrictive than the requirement for Exposure Class W1.

Exposure Classes F1 and F2: In addition to complying with a maximum w/cm limit and a minimum f_c' , strength for durability, concrete for members subject to freezing-and-thawing exposures is required to be air entrained in accordance with 19.3.3.1.

Exposure Classes S1, S2, and S3: Table 19.3.2.1 lists the appropriate types of cement and the maximum w/cm and minimum f_c' for various sulfate exposure conditions. In selecting cement for sulfate resistance, the principal consideration is its tricalcium aluminate (C_3A) content.

The use of fly ash (ASTM C618, Class F), natural pozzolans (ASTM C618, Class N), silica fume (ASTM C1240), or slag cement (ASTM C989) has been shown to improve the sulfate resistance of concrete (Li and Roy 1986; ACI PRC-233; ACI PRC-234). Therefore, Footnote [7] to Table 19.3.2.1 provides a performance option to determine the appropriate amounts of these materials to use in combination with the specific cement types listed. ASTM C1012 is permitted to be used to evaluate the sulfate resistance of mixtures using combinations of cementitious materials in accordance with 26.4.2.2(c).

Some ASTM C595 and ASTM C1157 blended cements can meet the testing requirements of 26.4.2.2(c) without addition of pozzolans or slag cement to the blended cement as manufactured.

Note that sulfate-resisting cement will not increase resistance of concrete to some chemically aggressive solutions—for example, sulfuric acid. The construction documents should explicitly cover such cases.

CODE

COMMENTARY

In addition to the proper selection of cementitious materials, other requirements for durable concrete exposed to water-soluble sulfates are essential, such as w/cm , strength, consolidation, uniformity, cover of reinforcement, and moist curing to develop the potential properties of the concrete.

Exposure Class S1: **ASTM C150** Type II cement is limited to a maximum C_3A content of 8 percent and is acceptable for use in Exposure Class S1. Blended cements under **ASTM C595** with the MS designation, which indicates the cement meets requirements for moderate sulfate resistance, are also appropriate for use. Under **ASTM C1157**, the appropriate designation for moderate sulfate exposure is Type MS.

Seawater is listed under Exposure Class S1 (moderate exposure) in Table 19.3.1.1, even though it generally contains more than 1500 ppm SO_4^{2-} . Less expansion is produced by a given cement in seawater compared with freshwater with the same sulfate content (**ACI 201.2R**). Therefore, seawater is included in the same exposure class as solutions with lower sulfate concentrations. Portland cement with C_3A up to 10 percent is allowed in concrete mixtures exposed to seawater if the maximum w/cm is limited to 0.40 (refer to the footnote to Table 19.3.2.1).

Exposure Class S2: **ASTM C150** Type V cement is limited to a maximum C_3A content of 5 percent and is acceptable for use in Exposure Class S2. The appropriate binary and ternary blended cements under **ASTM C595** include the suffix (HS) as part of their designation, which indicates the cement conforms to requirements for high sulfate resistance. Under **ASTM C1157**, the appropriate designation for severe sulfate exposure is Type HS.

Exposure Class S3 (Option 1): The benefit of the addition of pozzolan or slag cement allows for a greater w/cm than required for Option 2. The amounts of supplementary cementitious materials are based on records of successful service or testing in accordance with **26.4.2.2(c)**.

Exposure Class S3 (Option 2): This option allows the use of **ASTM C150** Type V portland cement meeting the optional limit of 0.040 percent maximum expansion, **ASTM C595** binary and ternary blended cements with the (HS) suffix in their designation, and **ASTM C1157** Type HS cements without the use of additional pozzolan or slag cement, but it instead requires a lower w/cm than that required for Option 1. This lower w/cm reduces the permeability of the concrete and thus increases sulfate resistance (**Lenz 1992**). Use of this lower w/cm permits a shorter testing period to qualify the sulfate resistance of a cementitious system in accordance with **26.4.2.2(c)**.

In addition to the proper selection of cementitious materials, other requirements for durable concrete exposed to water-soluble sulfates are essential, such as low w/cm , strength, adequate consolidation, uniformity, adequate cover of reinforcement, and sufficient moist curing to develop the potential properties of the concrete.

Exposure Class W1: This exposure class does not have specific requirements for low permeability. However,

CODE

COMMENTARY

because of the exposure to water, the Code (26.4.2.2(d)) has a requirement to demonstrate that aggregates used in concrete are not alkali reactive according to ASTM C1778. If the aggregates are alkali-silica reactive, the Code (26.4.2.2(d)) also requires submission of proposed mitigation measures. The Code (26.4.2.2(d)) prohibits the use of aggregates that are alkali-carbonate reactive.

Exposure Class W2: This exposure class requires low concrete permeability. The primary means to obtain a concrete with low permeability is to reduce w/cm . For a given w/cm , permeability can be reduced by optimizing the cementitious materials used in the concrete mixture. In addition, because of the exposure to water, the Code (26.4.2.2(d)) has a requirement to demonstrate that aggregates used in concrete are not alkali reactive according to ASTM C1778. If the aggregates are alkali-silica reactive, the Code (26.4.2.2(d)) also requires submission of proposed mitigation measures. The Code (26.4.2.2(d)) prohibits the use of aggregates that are alkali-carbonate reactive.

Exposure Class C2: For concrete in Exposure Class C2, the maximum w/cm , minimum specified compressive strength, and minimum cover are the basic requirements to be considered. Conditions should be evaluated for structures exposed to chlorides, such as in parking structures where chlorides may be tracked in by vehicles, or in structures near seawater. Coated reinforcement, corrosion-resistant steel reinforcement, corrosion-inhibiting admixtures, sealers, membranes, and cover greater than the minimum required in 20.5 can provide additional protection under such conditions. Use of slag cement meeting ASTM C989 or fly ash meeting ASTM C618 and higher values of specified compressive strength provide increased protection. Use of silica fume meeting ASTM C1240 with an appropriate high-range water reducing admixture conforming to ASTM C494, Types F and G, can also provide additional protection (Ozyildirim and Halstead 1988). The use of ASTM C1202 to test concrete mixtures proposed for use will provide additional information on their resistance to chloride ion penetration.

Chloride limits for Exposure Category C: For Exposure Classes C0, C1, and C2, the chloride ion limits apply to the chlorides contributed from the concrete materials, not from the environment surrounding the concrete. Even for Exposure Class C0, water-soluble chlorides introduced from the concrete materials can potentially induce corrosion of the reinforcement and must be limited for both nonprestressed and prestressed concrete, regardless of external exposure. For nonprestressed concrete, the permitted maximum amount of water-soluble chloride ions incorporated into the concrete, depends on the degree of exposure to an anticipated external source of moisture and chlorides. For prestressed concrete, the same limit of 0.06% chloride ion by mass of cementitious material applies regardless of exposure. The limits on chloride ion content for prestressed concrete are reduced from those for nonprestressed concrete because corrosion of prestressed reinforcement generally has more severe conse-

CODE

COMMENTARY

quences than corrosion of nonprestressed reinforcement. Corrosion-induced reduction in the cross-sectional area of the prestressed reinforcement may result in fracture of the steel ([ACI PRC-222](#)).

Some admixtures contain intentionally added chlorides, and many admixtures contain trace or background amounts of chlorides as an impurity in the ingredients. The Code does not impose limits on chloride ion content for admixtures. The total chloride ion content of admixtures measured by the supplier should be used when calculating the chloride ion content of concrete to meet the requirements of Table 19.3.2.1.

The presence of chloride ions may increase the corrosion rate of embedded aluminum such as conduits, especially if the aluminum is in contact with embedded steel and the concrete is in a humid environment ([Woods 1966](#)). Requirements for protecting aluminum embedments from corrosion are given in [20.6.3](#) and [26.8.2](#).

Allowable chloride limits are based on the mass of total cementitious materials rather than portland cement alone. This change was made in [ACI CODE-318-19](#) to reflect findings that demonstrate the beneficial effects of supplementary cementitious materials (SCMs) in reducing permeability and binding chlorides, thus helping to inhibit corrosion ([Wilson and Tennis 2021](#)). Because there are diminishing chloride binding effects with increasing amounts of SCMs, the Code ([26.4.2.2\(d\)](#)) limits the mass of SCMs that can be used to calculate the allowable amount of chloride ions in concrete ([Tepke et al. 2016](#)).

Additional information on the effects of chlorides on the corrosion of steel reinforcement is given in [ACI PRC-201.2](#), which provides guidance on concrete durability, and [ACI PRC-222](#), which provides guidance on factors that impact corrosion of metals in concrete. Requirements for the evaluation of chloride ion content are provided in [26.4.2.2](#).

19.3.2.1 Based on the exposure classes assigned from 19.3.1, concrete mixtures shall conform to the requirements given in Table 19.3.2.1, and as indicated in (a) through (c):

- (a) Specified compressive strength, f_c' , shall be the greater of that required for structural design of the member and the greatest minimum f_c' in Table 19.3.2.1 assigned for durability considering all Exposure Categories.
- (b) The chloride ion content of concrete mixtures shall meet the requirements of Table 19.3.2.1 as determined in accordance with [26.4.2.2\(d\)](#).
- (c) For plain concrete assigned to Exposure Class C2, the licensed design professional shall assign concrete requirements according to (i) through (iii) depending on potential exposure to chlorides and the presence of reinforcement, embedments, or both.
 - (i) Limit on water-soluble chloride ion content in concrete from those in Table 19.3.2.1
 - (ii) Maximum w/cm of 0.45
 - (iii) Minimum f_c' of 4500 psi

R19.3.2.1

- (c) The requirements for plain concrete members in Exposure Class C2 may be relaxed because of the reduced likelihood of problems caused by reinforcement or embedment corrosion. The licensed design professional should consider the details of the minimal reinforcement and embedments to be included in plain concrete members to ensure that the less restrictive requirements are appropriate for the specific project.

CODE

COMMENTARY

Table 19.3.2.1—Requirements for concrete by exposure class

Exposure class		Maximum w/cm ^[1,2]	Minimum f_c' , psi	Additional requirements			
				Air content			
F0		N/A	2500	N/A			
F1		0.55	3500	Table 19.3.3.1 for concrete or Table 19.3.3.3 for shotcrete			
F2		0.45	4500	Table 19.3.3.1 for concrete or Table 19.3.3.3 for shotcrete			
			Cementitious materials ^[3] — Types			Calcium chloride admixture	
			ASTM C150	ASTM C595	ASTM C1157		
S0		N/A	2500	No type restriction	No type restriction	No type restriction	No restriction
S1		0.50	4000	II ^{[4][5]}	Types with (MS) designation	MS	No restriction
S2		0.45	4500	V ^[5]	Types with (HS) designation	HS	Not permitted
S3	Option 1	0.45	4500	V plus pozzolan or slag cement ^[6]	Types with (HS) designation plus pozzolan or slag cement ^[6]	HS plus pozzolan or slag cement ^[6]	Not permitted
	Option 2	0.40	5000	V ^[7]	Types with (HS) designation	HS	Not permitted
W0		N/A	2500	None [®]			
W1		N/A	2500	26.4.2.2(d)			
W2		0.50	4000	26.4.2.2(d)			
				Maximum water-soluble chloride ion (Cl ⁻) content in concrete, percent by mass of cementitious materials			
				Nonprestressed concrete	Prestressed concrete		
C0		N/A	2500	1.00	0.06		
C1		N/A	2500	0.30	0.06		
C2 ^[8]		0.40	5000	0.15	0.06		

^[1]The w/cm is calculated on all cementitious and supplementary cementitious materials in the concrete mixture.

^[2]The maximum w/cm limits do not apply to lightweight concrete.

^[3]Alternative combinations of cementitious materials to those listed are permitted for all sulfate exposure classes when tested for sulfate resistance and meeting the criteria in 26.4.2.2(b).

^[4]For seawater exposure, other types of portland cements with tricalcium aluminate (C_3A) contents up to 10 percent are permitted if the w/cm does not exceed 0.40.

^[5]Other available types of cement such as Type I or Type III are permitted in Exposure Classes S1 or S2 if the C_3A contents are less than 8 percent for Exposure Class S1 or less than 5 percent for Exposure Class S2.

^[6]The amount of the specific source of the pozzolan or slag cement to be used shall be at least the amount that has been determined by service record to improve sulfate resistance when used in concrete containing Type V cement. Alternatively, the amount of the specific source of the pozzolan or slag cement to be used shall be at least the amount tested in accordance with ASTM C1012 and meeting the criteria in 26.4.2.2(b).

^[7]If Type V cement is used as the sole cementitious material, the optional sulfate resistance requirement of 0.040 percent maximum expansion in ASTM C150 shall be specified.

^[8]Concrete cover shall be in accordance with 20.5.1.4.

19.3.3 Additional requirements for freezing-and-thawing exposure

19.3.3.1 Concrete assigned to freezing-and-thawing Exposure Classes F1 and F2 shall be air entrained. Except as permitted in 19.3.3.6, air content shall conform to Table 19.3.3.1.

R19.3.3 Additional requirements for freezing-and-thawing exposure

R19.3.3.1 A table of required air contents for concrete to resist damage from cycles of freezing and thawing is included in the Code, based on guidance provided for proportioning concrete mixtures in **ACI PRC-211.1**. Entrained air will not protect concrete containing coarse aggregates that undergo disruptive volume changes when frozen in a saturated condition.

CODE

COMMENTARY

Table 19.3.3.1—Total air content for concrete exposed to cycles of freezing and thawing

Nominal maximum aggregate size, in.	Target air content, %	
	F1	F2
3/8	6.0	7.5
1/2	5.5	7.0
3/4	5.0	6.0
1	4.5	6.0
1-1/2	4.5	5.5
2	4.0	5.0
3	3.5	4.5

19.3.3.2 Concrete shall be sampled in accordance with **ASTM C172**, and air content shall be measured in accordance with **ASTM C231** or **ASTM C173**.

R19.3.3.2 The sampling of fresh concrete for acceptance based on air content is usually performed as the concrete is discharged from a mixer or a transportation unit (for example, a ready mixed concrete truck) to the conveying equipment used to transfer the concrete to the forms. ASTM C172 primarily covers sampling of concrete as it is discharged from a mixer or a transportation unit, but recognizes that specifications may require sampling at other points such as discharge from a pump. Table 19.3.3.1 was developed for testing as-delivered concrete. ASTM C231 is applicable to normalweight concrete and ASTM C173 is applicable to normalweight or lightweight concrete.

If the licensed design professional requires measurement of air content of fresh concrete at additional sampling locations, such requirements should be stated in the construction documents, including the sampling protocol, test methods to be used, and the criteria for acceptance.

19.3.3.3 Wet-mix shotcrete assigned to freezing-and-thawing Exposure Classes F1 or F2 shall be air entrained. Dry-mix shotcrete assigned to freezing-and-thawing Exposure Class F2 and corrosion protection Exposure Class C2 shall be air entrained. Except as permitted in 19.3.3.6, air content shall conform to Table 19.3.3.3.

Table 19.3.3.3—Total air content for shotcrete exposed to cycles of freezing and thawing

Mixture type	Sampling location	Target air content, %		
		F1	F2	F2 and C2
Wet-mix shotcrete	Before placement	5.0	6.0	6.0
Dry-mix shotcrete	In-place	N/A ^[1]	N/A ^[1]	4.5

^[1]Entrained air is not required in dry-mix shotcrete for these exposure classes.

R19.3.3.3 Adding air-entraining admixtures improves freezing-and-thawing resistance of wet-mix shotcrete (**ACI PRC-506**). Having air contents before placement as specified in Table 19.3.3.3 will provide required performance in freezing and thawing. Air contents greater than those specified will not improve shotcrete performance because once adequate air content for durability is achieved, there is no further benefit. As in all concrete, too much in-place air will reduce strength.

Dry-mix shotcrete without air entrainment has performed well in freezing-and-thawing environments with no exposure to saltwater or deicing salts (**ACI PRC-506**; **Seegebrecht et al. 1989**). For exposure to saltwater or deicing salts, air-entraining admixtures, in either a wet or dry form, can be added to dry-mix shotcrete to provide the required air content for durability in these exposures (**Bertrand and Vezina 1994**). The higher air content of wet-mix shotcrete sampled at the point of delivery accounts for expected air losses during shooting.

CODE

19.3.3.4 Wet-mix shotcrete shall be sampled in accordance with **ASTM C172**, and air content shall be measured in accordance with **ASTM C231** or **ASTM C173**.

19.3.3.5 Dry-mix shotcrete shall be sampled and air content shall be measured as directed by the licensed design professional.

19.3.3.6 For $f'_c \geq 5000$ psi, reduction of air content indicated in Table 19.3.3.1 and 19.3.3.3 by 1.0 percentage point is permitted.

19.3.4 Additional requirements for chloride ion content

19.3.4.1 Nonprestressed concrete that will be cast against stay-in-place galvanized steel forms shall comply with the chloride ion limits for Exposure Class C1 unless a more stringent limit is required by other project conditions.

COMMENTARY

R19.3.3.5 If the licensed design professional requires measurement of air content of fresh dry-mix shotcrete, such requirements are to be stated in the construction documents, including the sampling frequency, sampling protocol, test methods to be used, and the criteria for acceptance.

The air content required for dry-mix shotcrete is for sampling of in-place shotcrete. This air content can be verified by taking cores from shotcrete test panels for analysis in accordance with **ASTM C457**. During the mixture development process, shotcrete test panels may be prepared with different amounts of air-entraining admixture and cored to determine a dosage that will provide the required amount of air after placement.

The use of ASTM C457 for quality control during construction is not practical. Although there are no standard tests for air content of dry-mix shotcrete during construction, there are industry accepted methods for testing. These methods involve obtaining samples of dry-mix shotcrete and performing standard tests such as ASTM C231 to determine air content.

Field measurements of air content of dry-mix shotcrete have been obtained by shooting the material directly into a bowl of an air meter (**Betrand and Vezina 1994**). Samples for air content testing can also be taken from material shot into test panels, into a wheelbarrow, or onto the ground. These samples can then be used for testing in accordance with ASTM C231 (**Zhang 2015**).

R19.3.3.6 This section permits a 1.0 percentage point lower air content for concrete with f'_c equal to or greater than 5000 psi. Such higher-strength concretes, which have a lower w/cm and porosity, have greater resistance to cycles of freezing and thawing.

R19.3.4 Additional requirements for chloride ion content

R19.3.4.1 Corrosion of galvanized steel sheet or stay-in-place galvanized steel forms may occur, especially in humid environments or where drying is inhibited by the thickness of the concrete, coatings, or impermeable coverings. If stay-in-place galvanized steel forms are used, the maximum chloride limit of 0.30% is required. For more severe environments, such as for concrete in Exposure Class C2, a more stringent limit of 0.15% would be required.

At the time of design, the licensed design professional may not know if aluminum embedments or stay-in-place galvanized steel forms will be used. Use of aluminum embedments is covered in **26.8.2**. Use of stay-in-place galvanized steel forms is covered in **26.4.2.2**.

CODE**19.4—Grout durability requirements**

19.4.1 Water-soluble chloride ion content of grout for bonded tendons shall not exceed 0.06% when tested in accordance with **ASTM C1218**, measured by mass of chloride ion to mass of cementitious materials.

COMMENTARY**R19.4—Grout durability requirements**

CHAPTER 20—STEEL REINFORCEMENT PROPERTIES, DURABILITY, AND EMBEDMENTS

CODE

COMMENTARY

20.1—Scope

20.1.1 This chapter shall apply to steel reinforcement and shall govern for (a) through (c):

- (a) Material properties
- (b) Properties to be used for design
- (c) Durability requirements, including minimum specified cover requirements

20.1.2 Provisions of 20.6 shall apply to embedments.

20.2—Nonprestressed bars and wires

20.2.1 *Material properties*

20.2.1.1 Nonprestressed bars and wires shall be deformed, except plain bars or wires are permitted for use in spirals.

20.2.1.2 Yield strength of nonprestressed bars and wires shall be determined by either (a) or (b):

- (a) The offset method, using an offset of 0.2% in accordance with **ASTM A370**
- (b) The yield point by the halt-of-force method, provided the nonprestressed bar or wire has a sharp-knead or well-defined yield point

20.2.1.3 Deformed bars shall conform to (a), (b), (c), (d), or (e), except bar sizes larger than No. 18 shall not be permitted:

- (a) **ASTM A615** – carbon steel
- (b) **ASTM A706** including Supplementary Requirements S1 – low-alloy steel
- (c) **ASTM A996** – axle steel and rail steel; bars from rail steel shall be Type R
- (d) **ASTM A955** – stainless steel
- (e) **ASTM A1035** – low-carbon chromium steel

R20.1—Scope

R20.1.1 Materials permitted for use as reinforcement are specified. Other metal elements, such as inserts, anchor bolts, or plain bars for dowels at isolation or contraction joints, are not normally considered reinforcement under the provisions of this Code. Fiber-reinforced polymer (FRP) reinforcement is not addressed in the Code. ACI Committee 440 has developed guidelines for the use of FRP reinforcement (**ACI PRC-440.1** and **ACI PRC-440.2**) and a code for design of members reinforced with glass fiber-reinforced polymer (GFRP) bars (**ACI CODE-440.11**).

R20.2—Nonprestressed bars and wires

R20.2.1 *Material properties*

R20.2.1.2 The majority of nonprestressed steel bar reinforcement exhibits actual stress-strain behavior that is sharply yielding or sharp-knead (elasto-plastic stress-strain behavior). However, bars of higher strength grade, steel wire, coiled steel bar, and stainless steel bars and wire generally do not exhibit sharply-yielding stress-strain behavior, but instead are gradually-yielding. The method used to measure yield strength of reinforcement needs to provide for both types of reinforcement stress-strain relationships.

Paulson et al. (2013) considered reinforcement manufactured during 2008 through 2012, and found that the offset method (0.2% offset), provides for a reasonable estimate of the strength of reinforced concrete structures.

The yield strength is determined by the manufacturer during tensile tests performed at the mill on samples of reinforcement. Test methods for determining yield strength of steel, including the offset method and yield point by halt-of-force method, are referenced either in the ASTM standards for nonprestressed bars and wire or in ASTM A370 Test Methods and Definitions.

R20.2.1.3 ASTM A615-24, Table 2 includes the minimum ratio of actual tensile strength to actual yield strength.

ASTM A706, Supplementary Requirements S1 are necessary to be specified in the project specifications and general notes. ASTM requires the bar purchaser to specify the Supplementary Requirements S1. Refer to **R26.6.1.1**.

Low-alloy steel deformed bars conforming to ASTM A706 are intended for applications where controlled tensile properties are required. ASTM A706 also includes restrictions on chemical composition to enhance weldability for Grades

CODE

COMMENTARY

20.2.1.4 Plain bars for spiral reinforcement shall conform to ASTM A615, A706, A955, or A1035.

20.2.1.5 Welded deformed bar mats shall conform to ASTM A184. Deformed bars used in welded deformed bar mats shall conform to ASTM A615 or A706.

20.2.1.6 Headed deformed bars shall conform to ASTM A970, including Annex A1 requirements for Class HA head dimensions.

20.2.1.7 Deformed wire, plain wire, welded deformed wire reinforcement, and welded plain wire reinforcement shall conform to (a) or (b), except that yield strength shall be determined in accordance with 20.2.1.2:

- (a) ASTM A1064 – carbon steel
- (b) ASTM A1022 – stainless steel

60, 80 and 100 . Use of ASTM A706 reinforcement requires specifying the Supplementary Requirements S1 of this standard, “Additional Requirements for Bars Used in Earthquake Resistant Structures.” This supplement includes the deformation radius requirements, and uniform elongation requirements in Table S1.1 of the supplement.

Rail-steel deformed bars used with the Code are required to conform to ASTM A996, including the provisions for Type R bars. Type R bars are required to meet more restrictive provisions for bend tests than other types of rail steel.

Stainless steel deformed bars are used in applications where high corrosion resistance or controlled magnetic permeability are required.

Low-carbon chromium steel is a high-strength material that is permitted for use as transverse reinforcement for confinement in special earthquake-resistant structural systems and spirals in columns. Refer to Tables 20.2.2.4(a) and (b). ASTM A1035 provides requirements for bars of two minimum yield strength levels—100,000 psi and 120,000 psi—designated as Grade 100 and Grade 120, respectively, but the maximum f_y permitted for design calculations in the Code is limited in accordance with 20.2.2.3.

In 2015, ASTM A615 included bar sizes larger than No. 18, and in 2016, ASTM A1035 also included bar sizes larger than No. 18. Bar sizes larger than No. 18 are not permitted by the Code due to the lack of information on their performance including bar bends and development lengths.

R20.2.1.4 Plain bars are permitted only for spiral reinforcement used as transverse reinforcement for columns, transverse reinforcement for shear and torsion, or confining reinforcement for splices.

R20.2.1.6 The limitation to Class HA head dimensions from Annex A1 of ASTM A970 is due to a lack of test data for headed deformed bars that do not meet Class HA dimensional requirements. Heads not conforming to Class HA limits on bar deformation obstructions and bearing face features have been shown to provide lower anchorage strength than the heads used in the tests that serve as the basis for 25.4.4 (Shao et al. 2016).

R20.2.1.7 Plain wire is permitted only for spiral reinforcement and in welded plain wire reinforcement, the latter of which is considered deformed. Stainless steel wire and stainless steel welded wire reinforcement are used in applications where high corrosion resistance or controlled magnetic permeability is required. The physical and mechanical property requirements for deformed stainless steel wire and deformed and plain welded wire reinforcement under

CODE

20.2.1.7.1 Deformed wire sizes D4 through D31 shall be permitted.

20.2.1.7.2 Deformed wire sizes larger than D31 shall be permitted in welded wire reinforcement if treated as plain wire for calculation of development and splice lengths in accordance with 25.4.7 and 25.5.4, respectively.

20.2.1.7.3 Except as permitted for welded wire reinforcement used as stirrups in accordance with 25.7.1, spacing of welded intersections in welded wire reinforcement in the direction of calculated stress shall not exceed (a) or (b):

- (a) 16 in. for welded deformed wire reinforcement
- (b) 12 in. for welded plain wire reinforcement

20.2.2 Design properties

20.2.2.1 For nonprestressed bars and wires, the stress below f_y shall be E_s times steel strain. For strains greater than that corresponding to f_y , stress shall be considered independent of strain and equal to f_y .

20.2.2.2 Modulus of elasticity, E_s , for nonprestressed bars and wires shall be permitted to be taken as 29,000,000 psi.

20.2.2.3 Yield strength for nonprestressed bars and wires shall be based on the specified grade of reinforcement and shall not exceed the values given in 20.2.2.4 for the associated applications.

20.2.2.4 Types of nonprestressed bars and wires to be specified for particular structural applications shall be in accordance with Table 20.2.2.4(a) for deformed reinforcement and Table 20.2.2.4(b) for plain reinforcement.

COMMENTARY

ASTM A1022 are the same as those for deformed wire, deformed welded wire reinforcement, and plain welded wire reinforcement under **ASTM A1064**.

R20.2.1.7.1 An upper limit is placed on the size of deformed wire because test results **Rutledge and Devries (2002)** have shown that D45 wire will achieve only approximately 60% of the bond strength in tension given by Eq. (25.4.2.4a).

R20.2.2 Design properties

R20.2.2.1 For deformed reinforcement, it is reasonably accurate to assume that the stress in reinforcement is proportional to strain below the specified yield strength f_y . The increase in strength due to strain hardening of the reinforcement is neglected for nominal strength calculations. In nominal strength calculations, the force developed in tension or compression reinforcement is calculated as:

if $\epsilon_s < \epsilon_y$ (yield strain)

$$A_s f_s = A_s E_s \epsilon_s$$

if $\epsilon_s \geq \epsilon_y$

$$A_s f_s = A_s f_y$$

where ϵ_s is the value from the strain diagram at the location of the reinforcement.

R20.2.2.4 Tables 20.2.2.4(a) and 20.2.2.4(b) limit the maximum values of yield strength to be used in design calculations for nonprestressed deformed reinforcement and nonprestressed plain spiral reinforcement, respectively.

CODE

COMMENTARY

Grade 100 reinforcement is now permitted to resist tension and compression in some applications. For reinforcement resisting compression, strain compatibility calculations indicate that stresses are not likely to exceed 80,000 psi before strain in unconfined concrete reaches the strain limit of 0.003 unless special confinement reinforcement is provided to increase the limiting concrete compressive strain. For beams, the deflection provisions of 24.2 and the limitations on distribution of flexural reinforcement of 24.3 become increasingly critical as f_y increases.

In Table 20.2.2.4(a), for deformed reinforcement in special moment frames and special structural walls, the use of longitudinal reinforcement with strength substantially higher than that assumed in design will lead to higher shear and bond stresses at the time of development of yield moments. These conditions may lead to brittle failures in shear or bond and should be avoided even if such failures may occur at higher loads than those anticipated in design. Therefore, ASTM A706 specifies both a lower and an upper limit on the actual yield strength of the steel and requires a minimum tensile-to-yield strength ratio. ASTM A615 reinforcement is not permitted as longitudinal reinforcement in special seismic systems (refer to R20.2.2.5). For reinforcement resisting compression, strain compatibility calculations indicate that stresses are not likely to exceed 80,000 psi before strain in unconfined concrete reaches the strain limit of 0.003 unless special confinement reinforcement is provided to increase the limiting concrete compressive strain.

The maximum value of yield strength for calculation purposes is limited to 100,000 psi for both nonprestressed deformed reinforcement and plain spiral reinforcement in Tables 20.2.2.4(a) and (b), respectively, when used for lateral support of longitudinal bars or for concrete confinement. The research that supports this limit for confinement is given in Saatcioglu and Razvi (2002), Pessiki et al. (2001), and Richart et al. (1929). For reinforcement in special moment frames and special structural walls, the research that indicated that higher yield strengths can be used effectively for confinement reinforcement is given in Budek et al. (2002), Muguruma and Watanabe (1990), and Sugano et al. (1990).

The limit of 60,000 psi on the values of f_y and f_{yt} used in design for most shear and torsional reinforcement is intended to control the width of inclined cracks under service-level gravity loads. The higher yield strength of 80,000 psi permitted in shear design for welded deformed wire reinforcement is also intended to control width of inclined cracks and is based on Guimaraes et al. (1992), Griezic et al. (1994), and Furlong et al. (1991). In particular, full-scale beam tests described in Griezic et al. (1994) indicated that the widths of inclined shear cracks at service load levels were less for beams reinforced with smaller diameter welded deformed wire reinforcement cages designed on the basis of a yield strength of 75,000 psi than beams reinforced with deformed Grade 60 stirrups.

CODE

COMMENTARY

For strength-level earthquake load effects, tests of members using higher strength reinforcement have shown acceptable behavior (Wallace 1998; Aoyama 2001; Budek et al. 2002; Sokoli and Ghannoum 2016; Cheng et al. 2016; Huq et al. 2018; Weber-Kamin et al. 2020), leading to the allowance of ASTM A706 Grade 80 reinforcement for special seismic systems and ASTM A706 Grade 100 for special structural walls in the 2019 Code, as indicated in Table 20.2.2.4(a).

Footnote [6] of Table 20.2.2.4(a) is provided because ASTM A1064 and A1022 only require the welds to develop 35,000 psi in the interconnected wires. Hoops, stirrups, and other elements used in special seismic systems should have anchorages that are capable of developing $1.25f_y$ or $1.25f_{yt}$, as applicable, or tensile strength of the bar or wire, whichever is less, so that moderate ductility capacity can be achieved. A welded product that is capable of developing these stress limits could be approved for use through Code Section 1.10.

Footnote [3] of Table 20.2.2.4(a) limiting slab and beam bars passing through or extending from special structural walls to reinforcement meeting 20.2.2.5 provides for greater ductility of these members that are not designated as part of the seismic-force-resisting system but are likely to undergo large nonlinear rotational demands.

The 80,000 psi limit on f_y for ties of members or regions of members designed using the strut-and-tie method is imposed because of scarcity of test data justifying a higher limit. The yield strength f_y of “other” ties is limited to 60,000 psi for consistency with the usage “shear.”

CODE

COMMENTARY

Table 20.2.2.4(a)—Nonprestressed deformed reinforcement

Usage	Application		Maximum value of f_y or f_{yr} permitted for design calculations, psi	Applicable ASTM specification			
				Deformed bars	Deformed wires	Welded wire reinforcement	Welded deformed bar mats
Flexure; axial force; and shrinkage and temperature	Special seismic systems	Special moment frames	80,000	A706 ^[2]	Not permitted	Not permitted	Not permitted
		Special structural walls ^[1]	100,000				
	Other		100,000 ^[3] [4]	A615, A706, A955, A996, A1035	A1064, A1022	A1064, A1022	A184 ^[5]
Lateral support of longitudinal bars; or concrete confinement	Special seismic systems		100,000	A615, A706, A955, A996, A1035	A1064, A1022	A1064 ^[6] , A1022 ^[6]	Not permitted
	Spirals		100,000	A615, A706, A955, A996, A1035	A1064, A1022	Not permitted	Not permitted
	Other		80,000	A615, A706, A955, A996	A1064, A1022	A1064, A1022	Not permitted
Shear ^[7]	Special seismic systems ^[8]	Special moment frames ^[9]	80,000	A615, A706, A955, A996	A1064, A1022	A1064 ^[6] , A1022 ^[6]	Not permitted
		Special structural walls ^[10]	100,000				
	Spirals		60,000	A615, A706, A955, A996	A1064, A1022	Not permitted	Not permitted
	Shear friction		60,000	A615, A706, A955, A996	A1064, A1022	A1064, A1022	Not permitted
	Stirrups, ties, hoops		60,000	A615, A706, A955, A996, A1035	A1064, A1022	A1064 and A1022 welded plain wire	Not permitted
			80,000	Not permitted	Not permitted	A1064 and A1022 welded deformed wire	Not permitted
Torsion	Longitudinal and transverse		60,000	A615, A706, A955, A996	A1064, A1022	A1064, A1022	Not permitted
Anchor reinforcement	Seismic Design Category (SDC) C, D, E, or F		80,000	A706 ^[11]	Not permitted	Not permitted	Not permitted
	Other		80,000	A615, A706, A955, A996	A1064, A1022	A1064, A1022	A184 ^[5]
Regions designed using strut-and-tie method	Longitudinal ties		80,000	A615, A706, A955, A996	A1064, A1022	A1064, A1022	Not permitted
	Other		60,000				

^[1]All components of special structural walls, including coupling beams and wall piers.

^[2]Reinforcement shall comply with 20.2.2.5.

^[3]In slabs and beams not part of a special seismic system, bars that pass through or extend from special structural walls shall comply with 20.2.2.5.

^[4]Longitudinal reinforcement with $f_y > 80,000$ psi is not permitted for intermediate moment frames and ordinary moment frames resisting earthquake demands E .

^[5]Welded deformed bar mats shall be permitted to be assembled using only ASTM A615 or A706 deformed bars of Grade 60 or Grade 80.

^[6]ASTM A1064 and A1022 are not permitted in special seismic systems if the weld is required to resist stresses in response to confinement, lateral support of longitudinal bars, shear, or other actions.

^[7]Steel fiber reinforcement for shear shall conform to ASTM A820 in accordance with 26.4.1.6.1.

^[8]This application also includes shear reinforcement with a maximum value of 80,000 psi f_y or f_{yr} permitted for design calculations for diaphragms and foundations for load combinations including earthquake forces if part of a building with a special seismic system.

^[9]Shear reinforcement in this application includes stirrups, ties, hoops, and spirals in special moment frames.

^[10]Shear reinforcement in this application includes all transverse reinforcement in special structural walls, coupling beams, and wall piers. Diagonal bars in coupling beams shall comply with 20.2.2.5.

^[11]Anchor reinforcement shall comply with 20.2.2.6.

CODE

COMMENTARY

Table 20.2.2.4(b)—Nonprestressed plain spiral reinforcement

Usage	Application	Maximum value of f_y or f_{yt} permitted for design calculations, psi	Applicable ASTM specification	
			Plain bars	Plain wires
Lateral support of longitudinal bars; or concrete confinement	Spirals in special seismic systems	100,000	A615, A706, A955, A1035	A1064, A1022
	Spirals	100,000	A615, A706, A955, A1035	A1064, A1022
Shear	Spirals	60,000	A615, A706, A955, A1035	A1064, A1022
Torsion in nonprestressed beams	Spirals	60,000	A615, A706, A955, A1035	A1064, A1022

20.2.2.5 Deformed nonprestressed longitudinal reinforcement resisting earthquake-induced moment, axial force, or both, in special seismic systems shall comply with **ASTM A706**, Grade 60, 80, or 100 for special structural walls and **ASTM A706** Grade 60 or 80 for special moment frames.

R20.2.2.5 Additional requirements for ASTM A706 reinforcement are provided in 20.2.1.3(b). Refer to **R18.2.6** for commentary regarding the requirements in 20.2.1.3(b) for a tensile strength greater than the yield strength of the reinforcement.

ASTM A706 reinforcement is required because of its inelastic fatigue performance and its controlled mechanical properties and chemical composition. **ASTM A615** reinforcement is not permitted as longitudinal reinforcement to resist moments and axial forces in special seismic systems because of concern associated with low-cycle fatigue behavior (**Slavin and Ghannoum 2015**) and because the mechanical properties and chemical composition of ASTM A615 reinforcement are less restricted.

20.2.2.6 Anchor reinforcement in Seismic Design Category (SDC) C, D, E, or F shall comply with **ASTM A706** Grade 60 or 80.

20.3—Prestressing strands, wires, and bars

20.3.1 Material properties

20.3.1.1 Except as required in 20.3.1.3 for special moment frames and special structural walls, prestressing reinforcement shall conform to (a), (b), (c), or (d):

- (a) **ASTM A416** – strand
- (b) **ASTM A421** – wire
- (c) **ASTM A421** – low-relaxation wire including Supplementary Requirement S1, “Low-Relaxation Wire and Relaxation Testing”
- (d) **ASTM A722** – high-strength bar

20.3.1.2 Prestressing strands, wires, and bars not listed in **ASTM A416**, **A421**, or **A722** are permitted provided they conform to minimum requirements of these specifications and are shown by test or analysis not to impair the performance of the member.

20.3.1.3 Prestressing reinforcement resisting earthquake-induced moment, axial force, or both, in special moment frames, special structural walls, and all components of special structural walls including coupling beams and wall piers, cast using precast concrete shall comply with **ASTM A416** or **ASTM A722**.

R20.3—Prestressing strands, wires, and bars

R20.3.1 Material properties

R20.3.1.1 Because low-relaxation prestressing reinforcement is addressed in a supplementary requirement to **ASTM A421**, which applies only if low-relaxation material is specified, the appropriate ASTM reference is listed as a separate entity.

CODE

20.3.2 Design properties

20.3.2.1 Modulus of elasticity, E_p , for prestressing reinforcement shall be determined from tests or as reported by the manufacturer.

20.3.2.2 Tensile strength, f_{pu} , shall be based on the specified grade or type of prestressing reinforcement and shall not exceed the values given in Table 20.3.2.2.

Table 20.3.2.2—Prestressing strands, wires, and bars

Type	Maximum value of f_{pu} permitted for design calculations, psi	Applicable ASTM Specification
Strand (stress-relieved and low-relaxation)	270,000	A416
Wire (stress-relieved and low-relaxation)	250,000	A421
		A421, including Supplementary Requirement S1 “Low-Relaxation Wire and Relaxation Testing”
High-strength bar	150,000	A722

20.3.2.3 Stress in bonded prestressed reinforcement at nominal flexural strength, f_{ps}

20.3.2.3.1 As an alternative to a more accurate calculation of f_{ps} based on strain compatibility, values of f_{ps} calculated in accordance with Eq. (20.3.2.3.1) shall be permitted for members with bonded prestressed reinforcement if all prestressed reinforcement is in the tension zone and $f_{se} \geq 0.5f_{pu}$.

$$f_{ps} = f_{pu} \left\{ 1 - \frac{\gamma_p}{\beta_1} \left[\rho_p \frac{f_{pu}}{f_c'} + \frac{d}{d_p} \frac{f_y}{f_c'} (\rho - \rho') \right] \right\} \quad (20.3.2.3.1)$$

where γ_p is in accordance with Table 20.3.2.3.1.

If compression reinforcement is considered for the calculation of f_{ps} by Eq. (20.3.2.3.1), (a) and (b) shall be satisfied.

(a) If d' exceeds $0.15d_p$, the compression reinforcement shall be neglected in Eq. (20.3.2.3.1).

COMMENTARY

R20.3.2 Design properties

R20.3.2.1 Default values of E_p between 28,500,000 and 29,000,000 psi are commonly used for design purposes. More accurate values based on tests or the manufacturer's reports may be needed for elongation checks during stressing.

R20.3.2.2 **ASTM A416** specifies two grades of strand tensile strength: 250,000 and 270,000 psi.

ASTM A421 specifies tensile strengths of 235,000, 240,000, and 250,000 psi, depending on the diameter and type of wire. For the most common diameter, 0.25 in., ASTM A421 specifies a tensile strength of 240,000 psi.

R20.3.2.3 Stress in bonded prestressed reinforcement at nominal flexural strength, f_{ps}

R20.3.2.3.1 Use of Eq. (20.3.2.3.1) may underestimate the strength of beams with high percentages of reinforcement and, for more accurate evaluations of their strength, the strain compatibility and equilibrium method should be used. If part of the prestressed reinforcement is in the compression zone, a strain compatibility and equilibrium method should be used.

The γ_p term in Eq. (20.3.2.3.1) and Table 20.3.2.3.1 reflects the influence of different types of prestressing reinforcement on the value of f_{ps} . Table R20.3.2.3.1 shows prestressing reinforcement type and the associated ratio f_{py}/f_{pu} .

Table R20.3.2.3.1—Ratio of f_{py}/f_{pu} associated with reinforcement type

Prestressing reinforcement type		f_{py}/f_{pu}
High-strength prestressing bars	ASTM A722 Type I (Plain)	≥ 0.85
	ASTM A722 Type II (Deformed)	≥ 0.80
Stress-relieved strand and wire	ASTM A416 ASTM A421	≥ 0.85
Low-relaxation strand and wire	ASTM A416 ASTM A421	≥ 0.90

CODE

(b) If compression reinforcement is included in Eq. (20.3.2.3.1), the term

$$\left[\rho_p \frac{f_{pu}}{f_c'} + \frac{d}{d_p} \frac{f_y}{f_c'} (\rho - \rho') \right]$$

shall not be taken less than 0.17.

Table 20.3.2.3.1—Values of γ_p for use in Eq. (20.3.2.3.1)

f_{py}/f_{pu}	γ_p
≥ 0.80	0.55
≥ 0.85	0.40
≥ 0.90	0.28

20.3.2.3.2 For pretensioned strands, the strand design stress at sections of members located within ℓ_d from the free end of strand shall not exceed that calculated in accordance with 25.4.8.3.

20.3.2.4 Stress in unbonded prestressed reinforcement at nominal flexural strength, f_{ps}

20.3.2.4.1 As an alternative to a more accurate calculation of f_{ps} , values of f_{ps} calculated in accordance with Table 20.3.2.4.1 shall be permitted for members prestressed with unbonded tendons if $f_{se} \geq 0.5f_{pu}$.

Table 20.3.2.4.1—Approximate values of f_{ps} at nominal flexural strength for unbonded tendons

ℓ_n/h	f_{ps}	
≤ 35	The least of:	$f_{se} + 10,000 + f_c'/(100\rho_p)$
		$f_{se} + 60,000$
		f_{py}
> 35	The least of:	$f_{se} + 10,000 + f_c'/(300\rho_p)$
		$f_{se} + 30,000$
		f_{py}

20.3.2.5 Permissible tensile stresses in prestressed reinforcement

20.3.2.5.1 The tensile stress in prestressed reinforcement shall not exceed the limits in Table 20.3.2.5.1.

COMMENTARY

R20.3.2.3.1(a) If d' is large, the strain in compression reinforcement can be considerably less than its yield strain. In such a case, the compression reinforcement does not influence f_{ps} as favorably as implied by Eq. (20.3.2.3.1). For this reason, if d' exceeds $0.15d_p$, Eq. (20.3.2.3.1) is applicable only if the compression reinforcement is neglected.

R20.3.2.3.1(b) The ρ' term in Eq. (20.3.2.3.1) reflects the increased value of f_{ps} obtained when compression reinforcement is provided in a beam with a large reinforcement index. If the term $[\rho_p(f_{pu}/f_c') + (d/d_p)(f_y/f_c')(\rho - \rho')]$ is small, the neutral axis depth is small, the compressive reinforcement does not develop its yield strength, and Eq. (20.3.2.3.1) becomes unconservative. For this reason, the term $[\rho_p(f_{pu}/f_c') + (d/d_p)(f_y/f_c')(\rho - \rho')]$ may not be taken less than 0.17 if compression reinforcement is taken into account when calculating f_{ps} . The compression reinforcement may be conservatively neglected when using Eq. (20.3.2.3.1) by taking ρ' as zero, in which case the term $[\rho_p(f_{pu}/f_c') + (d/d_p)(f_y/f_c')(\rho)]$ may be less than 0.17 and an acceptable value of f_{ps} is obtained.

R20.3.2.4 Stress in unbonded prestressed reinforcement at nominal flexural strength, f_{ps}

R20.3.2.4.1 The term $[f_{se} + 10,000 + f_c'/(300\rho_p)]$ reflects results of tests on members with unbonded tendons and span-to-depth ratios greater than 35 (one-way slabs, flat plates, and flat slabs) (Mojtahedi and Gamble 1978). These tests also indicate that the term $[f_{se} + 10,000 + f_c'/(100\rho_p)]$, formerly used for all span-depth ratios, overestimates the amount of stress increase in such members. Although these same tests indicate that the moment strength of those shallow members designed using $[f_{se} + 10,000 + f_c'/(100\rho_p)]$ meets the factored load strength requirements, this reflects the effect of the Code requirements for minimum bonded reinforcement as well as the limitation on concrete tensile stress that often control the amount of prestressing force provided.

R20.3.2.5 Permissible tensile stresses in prestressed reinforcement

R20.3.2.5.1 Because of the high yield strength of low-relaxation strand and wire meeting the requirements of ASTM A416 and ASTM A421 including Supplementary Requirement S1 “Low-Relaxation Wire and Relaxation Testing,” it is appropriate to specify permissible stresses

CODE

Table 20.3.2.5.1—Maximum permissible tensile stresses in prestressed reinforcement

Stage	Location	Maximum tensile stress	
During stressing	At jacking end	Least of:	$0.94f_{py}$
			$0.80f_{pu}$
			Maximum jacking force recommended by the supplier of anchorage device
Immediately prior to force transfer	At jacking end of pretensioned strands	$0.75f_{pu}$	
Immediately after force transfer	At post-tensioning anchorage devices and couplers	$0.70f_{pu}$	

20.3.2.6 Prestress losses

20.3.2.6.1 Prestress losses shall be considered in the calculation of the effective tensile stress in the prestressed reinforcement, f_{se} , and shall include (a) through (f):

- (a) Prestressed reinforcement seating at transfer
- (b) Elastic shortening of concrete
- (c) Creep of concrete
- (d) Shrinkage of concrete
- (e) Relaxation of prestressed reinforcement
- (f) Friction loss due to intended or unintended curvature in post-tensioning tendons

20.3.2.6.2 Calculated friction loss in post-tensioning tendons shall be based on experimentally determined wobble and curvature friction coefficients.

20.3.2.6.3 Where loss of prestress in a member is anticipated due to connection of the member to adjoining construction, such loss of prestress shall be included in design calculations.

COMMENTARY

in terms of specified minimum ASTM yield strength along with the specified minimum ASTM tensile strength. Because of the higher allowable initial prestressed reinforcement stresses permitted since the 1983 Code, final stresses can be greater. For structures subject to corrosive conditions or repeated loadings, consideration should be given to limiting the final stress.

The margin between the maximum stress during stressing and the maximum stress immediately prior to force transfer for pretensioned strands allows the manufacturer to stress the strands to compensate for prestress losses accrued between stressing and force transfer.

R20.3.2.6 Prestress losses

R20.3.2.6.1 **ACI PRC-423.10** provides a comprehensive treatment of the estimation of prestress losses.

Actual losses, greater or smaller than the calculated values, have little effect on the design strength of the member, but affect service load behavior (deflections, camber, cracking load) and connections. At service loads, overestimation of prestress losses can be almost as detrimental as underestimation because the former can result in excessive camber and horizontal movement.

R20.3.2.6.2 Estimation of friction losses in post-tensioned tendons is addressed in the *Post-Tensioning Manual* (**TAB.1**). Values of the wobble and curvature friction coefficients to be used for the particular types of prestressing reinforcement and particular types of ducts should be obtained from the manufacturers of the tendons. An unrealistically low estimate of the friction loss can lead to improper camber, or potential deflection, of the member and inadequate prestress. Overestimation of the friction may result in extra prestressing force. This could lead to excessive camber and excessive shortening of a member. If the friction factors are determined to be less than those assumed in the design, the tendon stressing should be adjusted to provide only that prestressing force in the critical portions of the structure required by the design.

When safety or serviceability of the structure may be involved, the acceptable range of prestressing reinforcement jacking forces or other limiting requirements should either be given or approved by the licensed design professional in conformance with the permissible stresses of 20.3.2.5 and **24.5**.

CODE

COMMENTARY

20.4—Headed shear stud reinforcement

20.4.1 Headed shear stud reinforcement and stud assemblies shall conform to **ASTM A1044**.

R20.4—Headed shear stud reinforcement

R20.4.1 The configuration of the studs for headed shear stud reinforcement differs from the configuration of the headed-type shear studs prescribed in Section 7 of **AWS D1.1 (2015)** and referenced for use in **Chapter 17** of this Code (Fig. R20.4.1). Ratios of the head to shank cross-sectional areas of the AWS D1.1 studs range from approximately 2.5 to 4. In contrast, **ASTM A1044** requires the area of the head of headed shear stud reinforcement to be at least 10 times the area of the shank. Thus, the AWS D1.1 headed studs are not suitable for use as headed shear stud reinforcement. The base rail, where provided, anchors one end of the studs; ASTM A1044 specifies material width and thickness of the base rail that are sufficient to provide the required anchorage without yielding for stud shank diameters of 0.375, 0.500, 0.625, and 0.750 in. In ASTM A1044, the minimum specified yield strength of headed shear studs is 51,000 psi.

Headed shear studs also differ from headed deformed bars, which are required to conform to 20.2.1.6 and may be used as an alternative to hooks for anchoring transverse reinforcement as permitted in **25.7.1.8**.




Fig. R20.4.1—Example stud head configurations.

20.5—Provisions for durability of steel reinforcement**20.5.1 Specified concrete cover****R20.5—Provisions for durability of steel reinforcement****R20.5.1 Specified concrete cover**

This section addresses concrete cover over reinforcement and does not include requirements for concrete cover over embedments such as pipes, conduits, and fittings, which are addressed in 20.6.5.

CODE

20.5.1.1 Unless the general building code requires a greater concrete cover for fire protection, the minimum specified concrete cover shall be in accordance with 20.5.1.2 through 20.5.1.4.

20.5.1.2 It shall be permitted to consider concrete floor finishes as part of required cover for nonstructural purposes.

20.5.1.3 *Specified concrete cover requirements*

20.5.1.3.1 Nonprestressed cast-in-place concrete members shall have specified concrete cover for reinforcement at least that given in Table 20.5.1.3.1.

COMMENTARY

R20.5.1.1 Concrete cover as protection of reinforcement from weather and other effects is measured from the concrete surface to the outermost surface of the reinforcement to which the cover requirement applies. Where concrete cover is prescribed for a class of structural members, it is measured to the outer edge of stirrups, ties, or spirals if transverse reinforcement encloses main bars; to the outermost layer of bars if more than one layer is used without stirrups or ties; to the metal end fitting or duct of post-tensioning tendons; or to the outermost part of the head on headed bars.

The condition “exposed to weather or in contact with ground” refers to direct exposure to moisture changes and not just to temperature changes. The term “exposed to weather” also includes exposure to moisture and airborne chlorides as described in **R19.3.1**. Slab soffits are not usually considered directly exposed unless subject to road spray from deicing chemicals or airborne chlorides, or alternate wetting and drying, (including that due to condensation conditions or direct leakage from exposed top surface, run off, or similar effects), or both.

Alternative methods of protecting the reinforcement from weather may be provided if they are equivalent to the additional concrete cover required by the Code. When approved by the building official under the provisions of **1.10**, reinforcement with alternative protection from weather may not have concrete cover less than the cover required for reinforcement not exposed to weather.

Development length provisions given in **Chapter 25** are a function of cover over the reinforcement. To meet requirements for development length, it may be necessary to use cover greater than the minimums specified in 20.5.1.

R20.5.1.2 Concrete floor finishes may be considered for nonstructural purposes such as cover for reinforcement and fire protection. Provisions should be made, however, to ensure that the concrete finish will not spall off, thus resulting in decreased cover. Furthermore, considerations for development of reinforcement require minimum monolithic concrete cover in accordance with 20.5.1.3.

R20.5.1.3 *Specified concrete cover requirements*

CODE

COMMENTARY

Table 20.5.1.3.1—Specified concrete cover for cast-in-place nonprestressed concrete members

Concrete exposure	Member	Reinforcement	Specified cover, in.
Cast against and permanently incontact with ground	All	All	3
Exposed to weather or in contact with ground	All	No. 6 through No. 18 bars	2
		No. 5 bar, W31 or D31 wire, and smaller	1-1/2
Not exposed to weather or in contact with ground	Slabs, joists, and walls	No. 14 and No. 18 bars	1-1/2
		No. 11 bar and smaller	3/4
	Beams, columns, pedestals, and tension ties	Primary reinforcement, stirrups, ties, spirals, and hoops	1-1/2

20.5.1.3.2 Cast-in-place prestressed concrete members shall have specified concrete cover for reinforcement, ducts, and end fittings at least that given in Table 20.5.1.3.2.

Table 20.5.1.3.2—Specified concrete cover for cast-in-place prestressed concrete members

Concrete exposure	Member	Reinforcement	Specified cover, in.
Cast against and permanently in contact with ground	All	All	3
Exposed to weather or in contact with ground	Slabs, joists, and walls	All	1
	All other	All	1-1/2
Not exposed to weather or in contact with ground	Slabs, joists, and walls	All	3/4
	Beams, columns, and tension ties	Primary reinforcement	1-1/2
		Stirrups, ties, spirals, and hoops	1

20.5.1.3.3 Precast nonprestressed or prestressed concrete members manufactured under plant conditions shall have specified concrete cover for reinforcement, ducts, and end fittings at least that given in Table 20.5.1.3.3.

R20.5.1.3.3 The lesser cover thicknesses for precast construction reflect the greater control for proportioning, placing, and curing inherent in precasting. Manufactured under plant conditions does not imply that precast members should be manufactured in a plant. Structural elements precast at the job site will also qualify under this section if the control of form dimensions, placing of reinforcement, quality control of concrete, and curing procedures are equal to that normally expected in a plant.

Concrete cover to pretensioned strand as described in this section is intended to provide minimum protection from weather and other effects. Such cover may not be sufficient to transfer or develop the stress in the strand, and it may be necessary to increase the cover accordingly.

CODE

COMMENTARY

Table 20.5.1.3.3—Specified concrete cover for precast-nonprestressed or prestressed concrete members manufactured under plant conditions

Concrete exposure	Member	Reinforcement	Specified cover, in.
Exposed to weather or in contact with ground	Walls	No. 14 and No. 18 bars; tendons larger than 1-1/2 in. diameter	1-1/2
		No. 11 bars and smaller; W31 and D31 wire and smaller; tendons and strands 1-1/2 in. diameter and smaller	3/4
	All other	No. 14 and No. 18 bars; tendons larger than 1-1/2 in. diameter	2
		No. 6 through No. 11 bars; tendons and strands larger than 5/8 in. diameter through 1-1/2 in. diameter	1-1/2
		No. 5 bar, W31 or D31 wire, and smaller; tendons and strands 5/8 in. diameter and smaller	1-1/4
Not exposed to weather or in contact with ground	Slabs, joists, and walls	No. 14 and No. 18 bars; tendons larger than 1-1/2 in. diameter	1-1/4
		Tendons and strands 1-1/2 in. diameter and smaller	3/4
		No. 11 bar, W31 or D31 wire, and smaller	5/8
	Beams, columns, pedestals, and tension ties	Primary reinforcement	Greater of d_b and 5/8 and need not exceed 1-1/2
		Stirrups, ties, spirals, and hoops	3/8

20.5.1.3.4 Deep foundation members shall have specified concrete cover for reinforcement at least that given in Table 20.5.1.3.4.

CODE

COMMENTARY

Table 20.5.1.3.4—Specified concrete cover for deep foundation members

Concrete exposure	Deep foundation member type	Reinforcement	Specified cover, in.
Cast against and permanently in contact with ground, not enclosed by steel pipe, tube permanent casing, or stable rock socket	Cast-in-place	All	3
Enclosed by steel pipe, tube, permanent casing, or stable rock socket	Cast-in-place	All	1-1/2
Permanently in contact with ground	Precast-nonprestressed	All	1-1/2
	Precast-prestressed		
Exposed to seawater	Precast-nonprestressed	All	2-1/2
	Precast-prestressed	All	2

20.5.1.3.5 For bundled bars, specified concrete cover shall be at least the smaller of (a) and (b):

- (a) The equivalent diameter of the bundle
- (b) 2 in.


and for concrete cast against and permanently in contact with ground, the specified cover shall be at least 3 in.

20.5.1.3.6 For headed shear stud reinforcement, specified concrete cover for the heads and base rails shall be at least that required for the reinforcement in the member.


R20.5.1.3.6 Concrete cover requirements for headed shear stud reinforcement are illustrated in Fig. R20.5.1.3.6.

CODE

COMMENTARY



(a) Slab with top and bottom bars



(b) Footing with only bottom bars

Fig. R20.5.1.3.6—Concrete cover requirements for headed shear stud reinforcement.

20.5.1.4 Specified concrete cover requirements for corrosive environments**R20.5.1.4 Specified concrete cover requirements for corrosive environments**

Corrosive environments are defined in 19.3.1, R19.3.1, and R19.3.2. Additional information on corrosion in parking structures is given in ACI PRC-362.1.

20.5.1.4.1 In corrosive environments or other severe exposure conditions, the specified concrete cover shall be increased as deemed necessary. The applicable requirements for concrete based on exposure categories in 19.3 shall be satisfied, or other protection shall be provided.

R20.5.1.4.1 Where concrete will be exposed to external sources of chlorides in service, such as deicing chemicals, brackish water, seawater, spray from these sources, and airborne chlorides as described in R19.3.1, concrete should be proportioned to satisfy the requirements for the applicable exposure class in Chapter 19. These include maximum w/cm , minimum strength for normalweight and lightweight

CODE

20.5.1.4.2 For prestressed concrete members classified as Class T or C in 24.5.2 and exposed to corrosive environments or other severe exposure categories such as those given in 19.3, the specified concrete cover for prestressed reinforcement shall be at least one and one-half times the cover in 20.5.1.3.2 for cast-in-place members and in 20.5.1.3.3 for precast members.

20.5.1.4.3 If the precompressed tension zone is not in tension under sustained loads, 20.5.1.4.2 need not be satisfied.

20.5.2 Nonprestressed coated reinforcement

20.5.2.1 Nonprestressed coated reinforcement shall conform to Table 20.5.2.1.

Table 20.5.2.1—Nonprestressed coated reinforcement

Type of coating	Applicable ASTM specifications		
	Bar	Wire	Welded wire
Zinc-coated	A767	Not permitted	A1060
Epoxy-coated	A775 or A934	A884	A884
Zinc and epoxy dual-coated	A1055	Not permitted	Not permitted

20.5.2.2 Deformed bars to be zinc-coated, epoxy-coated, or zinc and epoxy dual-coated shall conform to 20.2.1.3(a), (b), or (c).

20.5.2.3 Wire and welded wire reinforcement to be epoxy-coated shall conform to 20.2.1.7(a).

20.5.3 Corrosion protection for unbonded prestressing reinforcement

20.5.3.1 Unbonded prestressing reinforcement shall be encased in sheathing, and the space between the prestressing reinforcement and the sheathing shall be completely filled with a material formulated to inhibit corrosion. Sheathing shall be watertight and continuous over the unbonded length.

COMMENTARY

concrete, and maximum chloride ion in the concrete. Additionally, for corrosion protection, a specified concrete cover for reinforcement not less than 2 in. for walls and slabs and not less than 2-1/2 in. for other members is recommended. For precast concrete members manufactured under plant control conditions, a specified concrete cover not less than 1-1/2 in. for walls and slabs and not less than 2 in. for other members is recommended.

R20.5.2 Nonprestressed coated reinforcement

R20.5.2.1 Zinc-coated (hot-dipped galvanized) bars (ASTM A767), epoxy-coated bars (ASTM A775 and A934), and zinc and epoxy dual-coated bars (ASTM A1055) are used in applications where corrosion resistance of reinforcement is of particular concern such as in parking structures, bridge structures, and other highly corrosive environments.

R20.5.3 Corrosion protection for unbonded prestressing reinforcement

R20.5.3.1 Material for corrosion protection of unbonded prestressing reinforcement should have the properties identified in 19.1 of Breen et al. (1994).

Typically, sheathing is a continuous, seamless, high-density polyethylene material that is extruded directly onto the coated prestressing reinforcement.

CODE

20.5.3.2 The sheathing shall be connected to all stressing, intermediate, and fixed anchorages in a watertight fashion.

20.5.3.3 Unbonded single-strand tendons shall be protected to provide resistance to corrosion in accordance with [ACI SPEC-423.7](#).

20.5.4 *Corrosion protection for grouted tendons*

20.5.4.1 Ducts for grouted tendons shall be grout-tight and nonreactive with concrete, prestressing reinforcement, grout, and corrosion inhibitor admixtures.

20.5.4.2 Ducts shall be maintained free of water.

20.5.4.3 Ducts for grouted single-wire, single-strand, or single-bar tendons shall have an inside diameter at least 1/4 in. larger than the diameter of the prestressing reinforcement.

20.5.4.4 Ducts for grouted multiple wire, multiple strand, or multiple bar tendons shall have an inside cross-sectional area at least two times the cross-sectional area of the prestressing reinforcement.

20.5.5 *Corrosion protection for post-tensioning anchorages, couplers, and end fittings*

20.5.5.1 Anchorages, couplers, and end fittings shall be protected to provide long-term resistance to corrosion.

20.5.6 *Corrosion protection for external post-tensioning*

20.5.6.1 External tendons and tendon anchorage regions shall be protected to provide resistance to corrosion.

COMMENTARY

R20.5.4 *Corrosion protection for grouted tendons*

R20.5.4.2 Water in ducts may cause corrosion of the prestressing reinforcement, may lead to bleeding and segregation of grout, and may cause distress to the surrounding concrete if subjected to freezing conditions. A corrosion inhibitor should be used to provide temporary corrosion protection if prestressing reinforcement is exposed in the ducts for prolonged periods of time before grouting ([ACI SPEC-423.7](#)).

R20.5.5 *Corrosion protection for post-tensioning anchorages, couplers, and end fittings*

R20.5.5.1 For recommendations regarding protection, refer to [ACI PRC-423.3](#) and [ACI SPEC-423.7](#).

R20.5.6 *Corrosion protection for external post-tensioning*

R20.5.6.1 Corrosion protection can be achieved by a variety of methods. The corrosion protection provided should be suitable to the environment in which the tendons are located. Some conditions will require that the prestressing reinforcement be protected by concrete cover or by cement grout in polyethylene or metal tubing; other conditions will permit the protection provided by coatings such as paint or grease. Corrosion protection methods should meet the fire protection requirements of the general building code, unless the installation of external post-tensioning is to only improve serviceability.

CODE

COMMENTARY

20.6—Embedments

20.6.1 Embedments shall not significantly impair the strength of the structure and shall not reduce fire protection.

20.6.2 Embedment materials shall not be harmful to concrete or reinforcement.

20.6.3 Aluminum embedments shall be coated or covered to prevent aluminum-concrete reaction and electrically isolated to prevent electrolytic action between aluminum and steel or other embedded metals.

20.6.4 Reinforcement with an area at least 0.002 times the area of the concrete section shall be provided perpendicular to pipe embedments.

20.6.5 Specified concrete cover for pipe embedments with their fittings shall be at least 1-1/2 in. for concrete exposed to earth or weather, and at least 3/4 in. for concrete not exposed to weather, or not in contact with ground.

R20.6—Embedments

R20.6.1 The placement of nonstructural embedments such as conduit and piping in stress-critical regions and joints should be avoided. Where unavoidable, care should be taken to ensure that the embedments will not impair the strength or serviceability of the structure. The contractor should not be permitted to install conduits, pipes, ducts, or sleeves that are not shown in the construction documents or not approved by the licensed design professional.

R20.6.3 The Code prohibits the use of aluminum in structural concrete unless it is effectively protected. Coatings and coverings prevent aluminum reaction with concrete, which can cause expansion and cracking. Electrical isolation prevents electrolytic reactions with steel or other embedded metals, which can cause corrosion. The presence of chloride ions in the concrete increases the rate of reaction in both cases. Aluminum electrical conduits present a special problem because of likely contact with reinforcing steel and any stray electric current accelerates the adverse reaction. Provision prohibits calcium chloride or any admixture containing chloride, other than background amounts as an impurity in the admixture ingredients, from being used in concrete with aluminum embedments.

Notes



CHAPTER 21—STRENGTH REDUCTION FACTORS

CODE

COMMENTARY

21.1—Scope

21.1.1 This chapter shall apply to the selection of strength reduction factors used in design, except as permitted by [Chapter 27](#).

21.2—Strength reduction factors for structural concrete members and connections

21.2.1 Strength reduction factors ϕ shall be in accordance with Table 21.2.1, except as modified by 21.2.2, 21.2.3, 21.2.4, and 21.2.5.

R21.1—Scope

R21.1.1 The purposes of strength reduction factors ϕ are: (1) to account for the probability of under-strength members due to variations in material strengths and dimensions; (2) to account for inaccuracies in the design equations; (3) to reflect the available ductility and required reliability of the member under the load effects being considered; and (4) to reflect the importance of the member in the structure ([MacGregor 1976](#); [Winter 1979](#)).

R21.2—Strength reduction factors for structural concrete members and connections

R21.2.1 The strength reduction factors in the Code are compatible with the [ASCE/SEI 7](#) load combinations, which are the basis for the required factored load combinations in [Chapter 5](#).

The following notes pertain to the table entries by letter identifier:

(e) Bracket and corbel behavior is predominantly controlled by shear; therefore, a single value of $\phi = 0.75$ is used for all potential modes of failure.

(f) The strength reduction factor ϕ for plain concrete members is the same for all potential modes of failure. Because both the flexural tension strength and shear strength for plain concrete depend on the tensile strength of the concrete, without the reserve strength or ductility that might otherwise be provided by reinforcement, equal strength reduction factors for moment and shear are considered to be appropriate.

(h) Laboratory tests of post-tensioned anchorage zones ([Breen et al. 1994](#)) indicate a wide range of scatter in the results. This observation is addressed with a ϕ -factor of 0.85 and by limiting the nominal compressive strength of unconfined concrete in the general zone to $0.7\lambda f_{ci}'$ in [25.9.4.5.2](#), where λ is defined in [19.2.4](#). Thus, the effective design strength of unconfined concrete is $0.85 \times 0.7\lambda f_{ci}' = 0.6\lambda f_{ci}'$ in the general zone.

(l) Non-redundant connections are those without alternate load paths. Such connections can result in sudden failure. Refer to [R17.5.3](#).

(m) Redundant connections are those with alternate load paths. Refer to [R17.5.3](#).

CODE

COMMENTARY

Table 21.2.1—Strength reduction factors ϕ

Action		ϕ	Exceptions
(a)	Moment, axial force, or combined moment and axial force	0.65 to 0.90 in accordance with 21.2.2	Near ends of pretensioned members where strands are not fully developed, ϕ shall be in accordance with 21.2.3.
(b)	Shear	0.75	Additional requirements are given in 21.2.4 for structures designed to resist earthquake effects.
(c)	Torsion	0.75	—
(d)	Bearing	0.65	—
Structural Element			
(e)	Brackets and corbels	0.75	—
(f)	Plain concrete elements	0.60	—
(g)	Struts, ties, nodal zones, and bearing areas designed in accordance with strut-and-tie method in Chapter 23	0.75	—
Anchorage Condition			
(h)	Post-tensioned anchorage zones	0.85	—
(i)	Components of connections of precast members controlled by yielding of steel elements in tension	0.90	—
(j)	Anchorage of reinforcing bars for breakout strength of reinforcing bar groups in accordance with 25.4.1.5 and 25.4.11.	0.75	Development length of reinforcement calculated in accordance with 25.4.2 through 25.4.9 does not require ϕ . Additional requirements are given in 21.2.5 for structures designed to resist earthquake effects.
(k)	Anchor reinforcement in accordance with 17.5.2.1	0.90	—
(l)	Concrete failure of anchors in tension, nonredundant	0.65	—
(m)	Concrete failure of anchors in tension, redundant	0.75	—
(n)	Concrete failure of anchors in shear	0.75	—
(o)	Anchor steel, tension, ductile ^{[1],[2]}	0.75	ϕ is based on using f_{uta} to determine the nominal strength of anchors.
(p)	Anchor steel, tension, nonductile ^{[1],[2]}	0.65	—
(q)	Anchor steel, shear, ductile ^{[1],[2]}	0.65	ϕ accounts for non-uniform distribution of shear in connections with multiple anchors.
(r)	Anchor steel, shear, nonductile ^{[1],[2]}	0.60	—

^[1]Anchor components such as bolt or sleeve.

^[2]Ductility established in accordance with ACI CODE-355.2 or ACI CODE-355.4.

21.2.2 Strength reduction factor for moment, axial force, or combined moment and axial force shall be in accordance with Table 21.2.2, except as modified by 21.2.2.3.

R21.2.2 The nominal strength of a member that is subjected to moment or combined moment and axial force is determined for the condition where the strain in the extreme compression fiber is equal to the assumed strain limit of 0.003. The net tensile strain ϵ_t is the tensile strain calculated in the extreme tension reinforcement at nominal strength, exclusive of strains due to prestress, creep, shrinkage, and temperature. The net tensile strain in the extreme tension reinforcement is determined from a linear strain distribution at nominal strength, shown in Fig. R21.2.2a for a nonprestressed member.

CODE

COMMENTARY

Members subjected to only axial compression are considered to be compression-controlled and members subjected to only axial tension are considered to be tension-controlled.

If the net tensile strain in the extreme tension reinforcement is sufficiently large ($\geq \epsilon_{ty} + 0.003$), the section is defined as tension-controlled, for which warning of failure by excessive deflection and cracking may be expected. The limit $\geq \epsilon_{ty} + 0.003$ provides sufficient ductility for most applications. Before the 2019 Code, the tension-controlled limit on ϵ_t was defined as 0.005 established primarily on the basis of Grade 60 nonprestressed reinforcement and prestressed reinforcement, with some consideration given to higher grades of nonprestressed reinforcement (Mast 1992). Beginning with the 2019 Code, to accommodate nonprestressed reinforcement of higher grades, the tension-controlled limit on ϵ_t in Table 21.2.2 is defined as $\epsilon_{ty} + 0.003$. This expression is consistent with the recommendations of Mast (1992) for the general case of reinforcement other than Grade 60, and test data show that the expression leads to elements with adequate ductility.

One condition where greater ductile behavior is required is in design for redistribution of moments in continuous members and frames, which is addressed in 6.6.5. Because redistribution of moment depends on the ductility available in the hinge regions, redistribution of moment is limited to sections that have a net tensile strain of at least 0.0075.

If the net tensile strain in the extreme tension reinforcement is small ($\leq \epsilon_{ty}$), a brittle compression failure condition is expected, with little warning of impending failure. Before ACI CODE-318-14, the compression-controlled strain limit was defined as 0.002 for Grade 60 reinforcement and all prestressed reinforcement, but it was not explicitly defined for other types of reinforcement. The compression-controlled strain limit ϵ_{ty} is defined in 21.2.2.1 and 21.2.2.2 for deformed and prestressed reinforcement, respectively.

Beams and slabs are usually tension-controlled, whereas columns may be compression-controlled. Some members, such as those with small axial forces and large bending moments, experience net tensile strain in the extreme tension reinforcement between the limits of ϵ_{ty} and $(\epsilon_{ty} + 0.003)$. These sections are in a transition region between compression-controlled and tension-controlled.

This section specifies the appropriate strength reduction factors for tension-controlled and compression-controlled sections, and for intermediate cases in the transition region. Beginning with the 2019 Code, the expression $(\epsilon_{ty} + 0.003)$ defines the limit on ϵ_{ty} for tension-controlled behavior in Table 21.2.2. For sections subjected to combined axial force and moment, design strengths are determined by multiplying both P_n and M_n by the appropriate single value of ϕ .

A lower ϕ -factor is used for compression-controlled sections than for tension-controlled sections because compression-controlled sections have less ductility, are more sensitive to variations in concrete strength, and generally occur in members that support larger loaded areas than members

CODE

COMMENTARY

with tension-controlled sections. Columns with spiral reinforcement are assigned a higher ϕ -factor than columns with other types of transverse reinforcement because spiral columns have greater ductility and toughness. For sections within the transition region, the value of ϕ may be determined by linear interpolation, as shown in Fig. R21.2.2b.

The variation of ϕ with P_n in accordance with 21.2.2.3 is shown in Fig. R21.2.2.c. If $P_{n,bal}$ is less than $0.1f'_cA_g$, 21.2.2.3 does not apply and ϕ is determined from Table 21.2.2. For nonprestressed members with flanged sections or with asymmetric reinforcement, the design axial compressive strength ϕP_n computed with ϕ from Table 21.2.2 can exceed $\phi_{cc}P_{n,bal}$ in the transition and tension-controlled regions and become unconservative in some cases (Lequesne and Pincheira 2014). The requirements of 21.2.2.3 are intended to prevent this occurrence. For some sections, the transition in Fig. R21.2.2c can result in lower axial and flexural design strengths than those calculated with the 2019 edition of the Code.

Table 21.2.2—Strength reduction factor ϕ for moment, axial force, or combined moment and axial force based on net tensile strain ε_t

Net tensile strain ε_t	Classification	ϕ			
		Type of transverse reinforcement			
		Spirals conforming to 25.7.3		Other	
$\varepsilon_t \leq \varepsilon_{ty}$	Compression-controlled	0.75	(a)	0.65	(b)
$\varepsilon_{ty} < \varepsilon_t < \varepsilon_{ty} + 0.003$	Transition ^[1]	$0.75 + 0.15 \frac{(\varepsilon_t - \varepsilon_{ty})}{(0.003)}$	(c)	$0.65 + 0.25 \frac{(\varepsilon_t - \varepsilon_{ty})}{(0.003)}$	(d)
$\varepsilon_t \geq \varepsilon_{ty} + 0.003$	Tension-controlled	0.90	(e)	0.90	(f)

^[1]For sections classified as transition, it shall be permitted to use ϕ corresponding to compression-controlled sections.




Fig. R21.2.2a—Strain distribution and net tensile strain in a nonprestressed member.

CODE

COMMENTARY




Fig. R21.2.2b—Variation of ϕ with net tensile strain in extreme tension reinforcement, ϵ_t .




Fig. R21.2.2c—Variation of ϕ with P_n in accordance with 21.2.2.3.

21.2.2.1 For deformed reinforcement, ϵ_{ty} shall be f_y/E_s . For Grade 60 deformed reinforcement, it shall be permitted to take ϵ_{ty} equal to 0.002.

21.2.2.2 For all prestressed reinforcement, ϵ_{ty} shall be taken as 0.002.

21.2.2.3 For nonprestressed members subject to combined moment and axial compression with $0.1f'_cA_g \leq P_n \leq P_{n,bal}$, ϕ computed from Table 21.2.2 shall not exceed that determined from linear interpolation between 0.9 at $0.1f'_cA_g$ and ϕ_{cc} at $P_{n,bal}$.

21.2.3 For sections in pretensioned flexural members where all strands are not fully developed, ϕ for moment shall be calculated in accordance with Table 21.2.3, where ℓ_{tr} is calculated using Eq. (21.2.3), ϕ_p is the value of ϕ determined in accordance with Table 21.2.2 at the cross section closest to the end of member where all strands are developed, and ℓ_d is given in 25.4.8.1.

$$\ell_{tr} = \left(\frac{f_{se}}{3000} \right) d_b \quad (21.2.3)$$

R21.2.3 If a critical section along a pretensioned member occurs in a region where not all the strands are fully developed, bond slip failure may occur. This mode of failure resembles a brittle shear failure; hence, ϕ values for flexure are reduced relative to the value of ϕ at the cross section where all strands are fully developed. For sections between the end of the transfer length and the end of the development length, the value of ϕ may be determined by linear interpolation, as shown in Fig. R21.2.3a, where ϕ_p corresponds to the value of ϕ at the cross section closest to the end of the member where all strands are fully developed.

CODE

Table 21.2.3—Strength reduction factor ϕ for sections near the end of pretensioned members

Condition near end of member	Stress in concrete under service load ^[1]	Distance from end of member to section under consideration	ϕ	
All strands bonded	Not applicable	$\leq \ell_{tr}$	0.75	(a)
		ℓ_{tr} to ℓ_d	Linear interpolation from 0.75 to ϕ_p ^[2]	(b)
One or more strands debonded	No tension calculated	$\leq (\ell_{db} + \ell_{tr})$	0.75	(c)
		$(\ell_{db} + \ell_{tr})$ to $(\ell_{db} + \ell_d)$	Linear interpolation from 0.75 to ϕ_p ^[2]	(d)
	Tension calculated	$\leq (\ell_{db} + \ell_{tr})$	0.75	(e)
		$(\ell_{db} + \ell_{tr})$ to $(\ell_{db} + 2\ell_d)$	Linear interpolation from 0.75 to ϕ_p ^[2]	(f)

^[1]Stress calculated using gross cross-sectional properties in extreme concrete fiber of precompressed tension zone under service loads after allowance for all prestress losses at section under consideration.

^[2]It shall be permitted to use a strength reduction factor of 0.75.

COMMENTARY

Where bonding of one or more strands does not extend to the end of the member, instead of more rigorous analysis, ϕ should be taken as 0.75 from the end of the member to the end of the transfer length of the strand with the longest debonded length. Beyond this point, ϕ may be varied linearly to ϕ_p at the cross section where all strands are developed, as shown in Fig. R21.2.3b. Alternatively, the value of ϕ may be taken as 0.75 until all strands are fully developed. Embedment of debonded strand is considered to begin at the termination of the debonding sleeves. Beyond this point, the provisions of 25.4.8.1 are used to determine whether the strands develop over a length of ℓ_d or $2\ell_d$, depending on the calculated stress in the precompressed tension zone under service loads (Fig. R21.2.3b).





Fig. R21.2.3a—Variation of ϕ with distance from the free end of strand in pretensioned member with fully bonded strands.



Note: The location of the end of development length depends on the calculated stresses in the extreme concrete fiber of the precompressed tension zone under service loads.

Fig. R21.2.3b—Variation of ϕ with distance from the free end of strand in pretensioned member with debonded strands.

CODE

21.2.4 For structures that rely on elements in (a), (b), or (c) to resist earthquake effects E , the value of ϕ for shear shall be modified in accordance with 21.2.4.1 through 21.2.4.4:

- (a) Special moment frames
- (b) Special structural walls
- (c) Intermediate precast structural walls in structures assigned to Seismic Design Category D, E, or F

21.2.4.1 For any member designed to resist E , except for walls where $\Omega_v \geq 1.5$ or if $\omega_v \Omega_v$ is taken equal to Ω_o , ϕ for shear shall be 0.60 if the nominal shear strength of the member is less than the shear corresponding to the development of the nominal moment strength of the member. The nominal moment strength shall be the maximum value calculated considering factored axial loads from load combinations that include E .

21.2.4.2 For diaphragms, ϕ for shear shall not exceed the least value of ϕ for shear used for the vertical components of the primary seismic-force-resisting system.

21.2.4.3 For foundation elements supporting the primary seismic-force-resisting system, ϕ for shear shall not exceed the least value of ϕ for shear used for the vertical components of the primary seismic-force-resisting system.

21.2.4.4 For beam-column joints of special moment frames and diagonally reinforced coupling beams, ϕ for shear shall be 0.85.

21.2.5 For reinforcing bar groups governed by concrete breakout in seismic-force-resisting systems, ϕ for tension shall be 0.65.

COMMENTARY

R21.2.4.1 This provision addresses shear-controlled members, such as low-rise walls, portions of walls between openings, or diaphragms, for which nominal shear strength is less than the shear corresponding to development of nominal flexural strength for the pertinent loading conditions. The reduced value of ϕ does not apply to a wall designed with $\Omega_v \geq 1.5$ or if $\omega_v \Omega_v$ is taken equal to Ω_o because design shear forces have been amplified to account for flexural overstrength.

R21.2.4.2 Short structural walls were the primary vertical elements of the lateral-force-resisting system in many of the parking structures that sustained damage during the 1994 Northridge earthquake. In some cases, walls remained essentially linear elastic, while diaphragms responded inelastically. This provision is intended to increase strength of the diaphragm and its connections in buildings for which the shear strength reduction factor for walls is 0.60, as those structures tend to have relatively high overstrength.

R21.2.4.3 This provision is intended to provide consistent reliability for shear in foundation elements that support shear-controlled walls designed with a strength reduction factor of 0.6.

R21.2.5 The reduced ϕ factor is based on judgment and reflects a lack of data on the performance of bar groups under earthquake loading.

Notes



CHAPTER 22—SECTIONAL STRENGTH

CODE

COMMENTARY

22.1—Scope

22.1.1 This chapter shall apply to calculating nominal strength at sections of members, including (a) through (g):

- (a) Flexural strength
- (b) Axial strength or combined flexural and axial strength
- (c) One-way shear strength
- (d) Two-way shear strength
- (e) Torsional strength
- (f) Bearing
- (g) Shear friction

22.1.2 Sectional strength requirements of this chapter shall be satisfied unless the member or region of the member is designed in accordance with **Chapter 23**.

22.1.3 Design strength at a section shall be taken as the nominal strength multiplied by the applicable strength reduction factor ϕ given in **Chapter 21**.

22.2—Design assumptions for moment and axial strength**22.2.1** *Equilibrium and strain compatibility*

22.2.1.1 Equilibrium shall be satisfied at each section.

22.2.1.2 Strain in concrete and nonprestressed reinforcement shall be assumed proportional to the distance from neutral axis.

22.2.1.3 Strain in prestressed concrete and in bonded and unbonded prestressed reinforcement shall include the strain due to effective prestress.

22.2.1.4 Changes in strain for bonded prestressed reinforcement shall be assumed proportional to the distance from neutral axis.

R22.1—Scope

R22.1.1 The provisions in this chapter apply where the strength of the member is evaluated at critical sections.

R22.1.2 Chapter 23 provides methods for designing discontinuity regions where section-based methods do not apply.

R22.2—Design assumptions for moment and axial strength**R22.2.1** *Equilibrium and strain compatibility*

R22.2.1.1 The flexural and axial strength of a member calculated by the strength design method of the Code requires that two basic conditions be satisfied: 1) equilibrium; and 2) compatibility of strains. Equilibrium refers to the balancing of forces acting on the cross section at nominal strength. The relationship between the stress and strain for the concrete and the reinforcement at nominal strength is established within the design assumptions allowed by 22.2.

R22.2.1.2 It is reasonable to assume a linear distribution of strain over the depth of a reinforced concrete cross section for bending moment up to nominal strength, except in deep beams described in 9.9 and discontinuity regions addressed in Chapter 23. This assumption allows the determination of strain and corresponding stress in the reinforcement.

R22.2.1.4 The change in strain for bonded prestressed reinforcement is influenced by the change in strain at the section under consideration. For unbonded prestressed reinforcement, the change in strain is influenced by external load, reinforcement location, and boundary conditions along the length of the reinforcement. Current Code equations for calculating f_{ps} for unbonded tendons, as provided in 20.3.2.4, have been correlated with test results

CODE**22.2.2** *Design assumptions for concrete*

22.2.2.1 Maximum strain at the extreme concrete compression fiber shall be assumed equal to 0.003.

22.2.2.2 Tensile strength of concrete shall be neglected in flexural and axial strength calculations.

22.2.2.3 The relationship between concrete compressive stress and strain shall be represented by a rectangular, trapezoidal, parabolic, or other shape that results in prediction of strength in substantial agreement with results of comprehensive tests.

22.2.2.4 The equivalent rectangular concrete stress distribution in accordance with 22.2.2.4.1 through 22.2.2.4.3 satisfies 22.2.2.3.

22.2.2.4.1 Concrete stress of $0.85f'_c$ shall be assumed uniformly distributed over an equivalent compression zone bounded by edges of the cross section and a line parallel to the neutral axis located a distance a from the fiber of maximum compressive strain, as calculated by:

$$a = \beta_1 c \quad (22.2.2.4.1)$$

22.2.2.4.2 Distance from the fiber of maximum compressive strain to the neutral axis, c , shall be measured perpendicular to the neutral axis.

22.2.2.4.3 Values of β_1 shall be in accordance with Table 22.2.2.4.3.

COMMENTARY**R22.2.2** *Design assumptions for concrete*

R22.2.2.1 The maximum concrete compressive strain at crushing of the concrete has been observed in tests of various kinds to vary from 0.003 to higher than 0.008 under special conditions. However, the strain at which strength of the member is developed is usually 0.003 to 0.004 for members of normal proportions, materials, and strength.

R22.2.2.2 The tensile strength of concrete in flexure (modulus of rupture) is a more variable property than the compressive strength and is approximately 10 to 15 percent of the compressive strength. Tensile strength of concrete in flexure is conservatively neglected in calculating the nominal flexural strength. The strength of concrete in tension, however, is important in evaluating cracking and deflections at service loads.

R22.2.2.3 At high strain levels, the stress-strain relationship for concrete is nonlinear (stress is not proportional to strain). As stated in 22.2.2.1, the maximum usable strain is set at 0.003 for design.

The actual distribution of concrete compressive stress within a cross section is complex and usually not known explicitly. The important properties of the concrete stress distribution can be approximated closely using any one of several different assumptions for the shape of the stress distribution.

R22.2.2.4 For design, the Code allows the use of an equivalent rectangular compressive stress distribution (stress block) to replace the more detailed approximation of the concrete stress distribution.

R22.2.2.4.1 The equivalent rectangular stress distribution does not represent the actual stress distribution in the compression zone at nominal strength, but does provide essentially the same nominal combined flexural and axial compressive strength as obtained in tests (Mattock et al. 1961).

R22.2.2.4.3 The values for β_1 were determined experimentally. The lower limit of β_1 is based on experimental data from beams constructed with concrete strengths greater than 8000 psi (Leslie et al. 1976; Karr et al. 1978).

CODE

COMMENTARY

Table 22.2.2.4.3—Values of β_1 for equivalent rectangular concrete stress distribution

f'_c , psi	β_1	
$2500 \leq f'_c \leq 4000$	0.85	(a)
$4000 < f'_c < 8000$	$0.85 - \frac{0.05(f'_c - 4000)}{1000}$	(b)
$f'_c \geq 8000$	0.65	(c)

22.2.3 Design assumptions for nonprestressed reinforcement

22.2.3.1 Deformed reinforcement used to resist tensile or compressive forces shall conform to 20.2.1.

22.2.3.2 Stress-strain relationship and modulus of elasticity for deformed reinforcement shall be idealized in accordance with 20.2.2.1 and 20.2.2.2.

22.2.4 Design assumptions for prestressed reinforcement

22.2.4.1 For members with bonded prestressed reinforcement conforming to 20.3.1, stress at nominal flexural strength, f_{ps} , shall be calculated in accordance with 20.3.2.3.

22.2.4.2 For members with unbonded prestressed reinforcement conforming to 20.3.1, f_{ps} shall be calculated in accordance with 20.3.2.4.

22.2.4.3 If the embedded length of the prestressed strand is less than ℓ_d , the design stress of the prestressed strand shall not exceed the value given in 25.4.8.3, as modified by 25.4.8.1(b).

22.3—Flexural strength**22.3.1 General**

22.3.1.1 Nominal flexural strength M_n shall be calculated in accordance with the assumptions of 22.2.

22.3.2 Prestressed concrete members

22.3.2.1 Deformed reinforcement conforming to 20.2.1, provided in conjunction with prestressed reinforcement, shall be permitted to be considered to contribute to the tensile force and be included in flexural strength calculations at a stress equal to f_y .

22.3.2.2 Other nonprestressed reinforcement shall be permitted to be considered to contribute to the flexural strength if a strain compatibility analysis is performed to calculate stresses in such reinforcement.

R22.3—Flexural strength**R22.3.2 Prestressed concrete members**

R22.3.2.2 Bond length for nontensioned prestressing strand (Salmons and McCrate 1977; PCA 1980) should be sufficient to develop the stress consistent with strain compatibility analysis at the critical section.

CODE**22.3.3 Composite concrete members**

22.3.3.1 Provisions of 22.3.3 apply to members constructed in separate placements but connected so that all elements resist loads as a unit.

22.3.3.2 For calculation of M_n for composite concrete slabs and beams, use of the entire composite section shall be permitted.

22.3.3.3 For calculation of M_n for composite concrete slabs and beams, no distinction shall be made between shored and unshored members.

22.3.3.4 For calculation of M_n for composite concrete members where the specified concrete compressive strength of different elements varies, properties of the individual elements shall be used in design. Alternatively, it shall be permitted to use the value of f'_c for the element that results in the most critical value of M_n .

22.4—Axial strength or combined flexural and axial strength**22.4.1 General**

22.4.1.1 Nominal flexural and axial strength shall be calculated in accordance with the assumptions of 22.2.

22.4.2 Maximum axial compressive strength

22.4.2.1 Nominal axial compressive strength P_n shall not exceed $P_{n,max}$ in accordance with Table 22.4.2.1, where P_o is calculated by Eq. (22.4.2.2) for nonprestressed members and by Eq. (22.4.2.3) for prestressed members. The value of f_y shall be limited to a maximum of 80,000 psi.

Table 22.4.2.1—Maximum axial strength

Member	Transverse reinforcement	$P_{n,max}$	
Nonprestressed	Ties conforming to 22.4.2.4	$0.80P_o$	(a)
	Spirals conforming to 22.4.2.5	$0.85P_o$	(b)
Prestressed	Ties	$0.80P_o$	(c)
	Spirals	$0.85P_o$	(d)
Deep foundation member	Ties conforming to Ch. 13	$0.80P_o$	(e)

22.4.2.2 For nonprestressed members, P_o shall be calculated by:

COMMENTARY**R22.3.3 Composite concrete members**

R22.3.3.1 The scope of Chapter 22 is intended to include composite concrete flexural members. Where separate placements of concrete are designed to act as a unit, the interface is designed for the forces that will be transferred across the interface. Composite structural steel-concrete beams are not covered in the Code. Design provisions for these types of composite members are covered in [ANSI/AISC 360](#).

R22.4—Axial strength or combined flexural and axial strength**R22.4.2 Maximum axial compressive strength**

R22.4.2.1 To account for accidental eccentricity, the design axial strength of a section in pure compression is limited to 80 to 85% of the nominal axial strength. These percentage values approximate the axial strengths at eccentricity-to-depth ratios of 0.10 and 0.05 for tied and spirally reinforced members conforming to 22.4.2.4 and 22.4.2.5, respectively. The same axial load limitation applies to both cast-in-place and precast compression members. The value of f_y is limited to 80,000 psi because the compression capacity of the concrete is likely to be reached before this stress is exceeded. The transverse reinforcement requirements for columns do not apply to deep foundation members. [Chapter 13](#) provides the detailing requirements for these members.

CODE

$$P_o = 0.85f'_c(A_g - A_{st}) + f_y A_{st} \quad (22.4.2.2)$$

where A_{st} is the total area of nonprestressed longitudinal reinforcement.

22.4.2.3 For prestressed members, P_o shall be calculated by:

$$P_o = 0.85f'_c(A_g - A_{st} - A_{pd}) + f_y A_{st} - (f_{se} - 0.003E_p)A_{pt} \quad (22.4.2.3)$$

where A_{pt} is the total area of prestressing reinforcement, and A_{pd} is the total area occupied by duct, sheathing, and prestressing reinforcement; the value of f_{se} shall be at least $0.003E_p$. For grouted, post-tensioned tendons, it shall be permitted to assume A_{pd} equals A_{pt} .

22.4.2.4 Tie reinforcement for lateral support of longitudinal reinforcement in compression members shall satisfy **10.7.6.2** and **25.7.2**.

22.4.2.5 Spiral reinforcement for lateral support of longitudinal reinforcement in compression members shall satisfy **10.7.6.3** and **25.7.3**.

22.4.3 Maximum axial tensile strength

22.4.3.1 Nominal axial tensile strength of a nonprestressed or prestressed member, P_{nt} , shall not be taken greater than $P_{nt,max}$, calculated by:

$$P_{nt,max} = f_y A_{st} + (f_{se} + \Delta f_p) A_{pt} \quad (22.4.3.1)$$

where $(f_{se} + \Delta f_p)$ shall not exceed f_{py} , and A_{pt} is zero for nonprestressed members.

22.5—One-way shear strength**22.5.1 General**

22.5.1.1 Nominal one-way shear strength at a section, V_n , shall be calculated by:

$$V_n = V_c + V_s \quad (22.5.1.1)$$

COMMENTARY

R22.4.2.3 The effects of prestressing on the axial strength of compression members are taken into account in Eq. (22.4.2.3). Equation (22.4.2.3) is similar to Eq. (22.4.2.2) for nonprestressed compression members. The effective area of concrete subjected to the limiting stress of $0.85f'_c$ is reduced by the term A_{pd} to account for the area of ducts, sheathing, and prestressing reinforcement. A third term is added to account for the reduction of column capacity due to the prestress force. At nominal strength, the stress in the prestressed reinforcement, f_{se} , is decreased by $0.003E_p$, where 0.003 is the assumed compressive strain at the axial capacity of the member.

R22.5—One-way shear strength**R22.5.1 General**

R22.5.1.1 In a member without shear reinforcement, shear is assumed to be resisted by the concrete. In a member with shear reinforcement, a portion of the shear strength is assumed to be provided by the concrete and the remainder by the shear reinforcement.

The one-way shear equations for nonprestressed concrete were changed in the **2019 Code** with the primary objectives of including effect of member depth, commonly referred to as the “size effect,” and the effects of the longitudinal reinforcement ratio on shear strength.

The shear strength is based on an average shear stress over the effective cross section, $b_w d$.

Chapter 23 allows the use of the strut-and-tie method in the shear design of any structural concrete member, or discontinuity region in a member.

CODE

22.5.1.2 Cross-sectional dimensions shall be selected to satisfy Eq. (22.5.1.2).

$$V_u \leq \phi(V_c + 8\sqrt{f'_c} b_w d) \quad (22.5.1.2)$$

22.5.1.3 For nonprestressed members, V_c shall be calculated in accordance with 22.5.5.

22.5.1.4 For prestressed members, V_c shall be calculated in accordance with 22.5.6 or 22.5.7.

22.5.1.5 For calculation of V_c , V_{ci} , and V_{cw} , λ shall be in accordance with 19.2.4.

22.5.1.6 V_s shall be calculated in accordance with 22.5.8.

22.5.1.7 Effect of any openings in members shall be considered in calculating V_n .

22.5.1.8 Effect of axial tension due to creep and shrinkage in members shall be considered in calculating V_c .

22.5.1.9 Effect of inclined flexural compression in variable depth members shall be permitted to be considered in calculating V_c .

22.5.1.10 The interaction of shear forces acting along orthogonal axes shall be permitted to be neglected if (a) or (b) is satisfied.

$$(a) \frac{V_{u,x}}{\phi V_{n,x}} \leq 0.5 \quad (22.5.1.10a)$$

$$(b) \frac{V_{u,y}}{\phi V_{n,y}} \leq 0.5 \quad (22.5.1.10b)$$

COMMENTARY

R22.5.1.2 The limit on cross-sectional dimensions in 22.5.1.2 is intended to control cracking under service load and to minimize the likelihood of diagonal compression failure.

R22.5.1.7 Openings in the web of a member can reduce its shear strength. The effects of openings are discussed in Section 4.7 of *Joint ACI-ASCE Committee 426 (1973)*, *Barney et al. (1977)*, and *Schlaich et al. (1987)*. The strut-and-tie method as addressed in *Chapter 23* can be used to design members with openings.

R22.5.1.8 Consideration of axial tension requires engineering judgment. Axial tension often occurs due to volume changes, but it may be low enough not to be detrimental to the performance of a structure with adequate expansion joints and satisfying minimum longitudinal reinforcement requirements. It may be desirable to design shear reinforcement to resist the total shear if there is uncertainty about the magnitude of axial tension.

R22.5.1.9 In a member of variable depth, the internal shear at any section is increased or decreased by the vertical component of the inclined flexural stresses.

R22.5.1.10 and R22.5.1.11 Reinforced concrete members, such as columns and beams, may be subjected to biaxial shear. For symmetrically reinforced circular sections, nominal one-way shear strength about any axis is the same. Therefore, when a circular section is subjected to shear along two centroidal axes, shear strength can be evaluated using the resultant shear. However, for rectangular and other cross sections, calculating nominal one-way shear strength along the axis of the resultant shear is not practical. Tests and analytical results for columns have indicated that for biaxial shear loading, the shear strength follows an elliptical interaction diagram that requires calculating nominal one-way shear strength along two orthogonal directions (*Umehara and Jirsa 1984*). Considering shear along each centroidal axis independently can be unconservative. Thus, linear interaction accounts for biaxial shear.

CODE

22.5.1.11 If $\frac{V_{u,x}}{\phi V_{n,x}} > 0.5$ and $\frac{V_{u,y}}{\phi V_{n,y}} > 0.5$ then Eq. (22.5.1.11) shall be satisfied.

$$\frac{V_{u,x}}{\phi V_{n,x}} + \frac{V_{u,y}}{\phi V_{n,y}} \leq 1.5 \quad (22.5.1.11)$$

22.5.2 Geometric assumptions

22.5.2.1 For calculation of V_c and V_s , it shall be permitted to assume (a) through (d) :

- (a) d equal to $0.8h$ for rectangular columns
- (b) d equal to 0.8 times the diameter for circular sections
- (c) b_w equal to the diameter for solid circular sections
- (d) b_w equal to twice the wall thickness for hollow circular sections

22.5.2.2 For calculation of V_c and V_s in prestressed members, d shall be taken as the distance from the extreme compression fiber to the centroid of prestressed and any nonprestressed longitudinal reinforcement but need not be taken less than $0.8h$.

22.5.3 Limiting material strengths

22.5.3.1 The value of $\sqrt{f'_c}$ used to calculate V_c , V_{ci} , and V_{cw} for one-way shear shall not exceed 100 psi, unless allowed in 22.5.3.2.

22.5.3.2 Values of $\sqrt{f'_c}$ greater than 100 psi shall be permitted in calculating V_c , V_{ci} , and V_{cw} for reinforced or prestressed concrete beams and concrete joist construction having minimum web reinforcement in accordance with 9.6.3.4 or 9.6.4.2.

22.5.3.3 The values of f_y and f_{yt} used to calculate V_s shall not exceed the limits in 20.2.2.4.

COMMENTARY

R22.5.2 Geometric assumptions

R22.5.2.1 The computation of d for rectangular columns and circular sections can be complicated considering variations in axial load as well as multiple layers of reinforcement. While the actual d can be used, simplified definitions of d are provided. Experimental results indicate that d computed as 80% of the overall column dimension is appropriate and results in good accuracy (Sezen et al. 2021).

Although the transverse reinforcement in a circular section may not consist of straight legs, tests indicate that Eq. (22.5.8.5.3) is conservative if d is taken as defined in 22.5.2.1 (Faradji and Diaz de Cossio 1965; Khalifa and Collins 1981).

R22.5.2.2 Although the value of d may vary along the span of a prestressed beam, studies (MacGregor and Hanson 1969) have shown that, for prestressed concrete members, d need not be taken less than $0.8h$. The beams considered had some straight prestressed reinforcement or reinforcing bars at the bottom of the section and had stirrups that enclosed the longitudinal reinforcement.

R22.5.3 Limiting material strengths

R22.5.3.1 Because of a lack of test data and practical experience with concretes having compressive strengths greater than 10,000 psi, the Code imposes a maximum value of 100 psi on $\sqrt{f'_c}$ for use in the calculation of shear strength of concrete members. Exceptions to this limit are permitted in beams and joists if the transverse reinforcement satisfies the requirements in 22.5.3.2.

R22.5.3.2 Based on the beam test results in Mphonde and Frantz (1984), Elzanaty et al. (1986), Roller and Russell (1990), Johnson and Ramirez (1989), and Ozcebe et al. (1999), an increase in the minimum amount of transverse reinforcement is required for high-strength concrete. These tests indicate a reduction in reserve shear strength occurs as f'_c increases in beams reinforced with transverse reinforcement providing an effective shear stress of 50 psi. By providing minimum transverse reinforcement, which increases as f'_c increases, the reduction in shear strength is offset.

R22.5.3.3 The upper limit of 60,000 psi on the value of f_y and f_{yt} used in design is intended to control diagonal crack widths.

CODE

22.5.4 Composite concrete members

22.5.4.1 This section shall apply to members constructed in separate placements but connected so that all elements resist loads as a unit.

22.5.4.2 For calculation of V_n for composite concrete members, no distinction shall be made between shored and unshored members.

22.5.4.3 For calculation of V_n for composite concrete members where the specified concrete compressive strength, unit weight, or other properties of different elements vary, properties of the individual elements shall be used in design. Alternatively, it shall be permitted to use the properties of the element that results in the most critical value of V_n .

22.5.4.4 If an entire composite concrete member is assumed to resist vertical shear, it shall be permitted to calculate V_c assuming a monolithically cast member of the same cross-sectional shape.

22.5.4.5 If an entire composite concrete member is assumed to resist vertical shear, it shall be permitted to calculate V_s assuming a monolithically cast member of the same cross-sectional shape if shear reinforcement is fully anchored into the interconnected elements in accordance with 25.7.

22.5.5 V_c for nonprestressed members

22.5.5.1 For nonprestressed members, V_c shall be calculated in accordance with Table 22.5.5.1 and 22.5.5.1.1 through 22.5.5.1.3.

Table 22.5.5.1— V_c for nonprestressed members

Criteria	V_c	
$A_v \geq A_{v,min}$	Either of:	$\left[2\lambda \sqrt{f'_c} + \frac{N_u}{6A_g} \right] b_w d$ (a)
		$\left[8\lambda(\rho_w)^{1/3} \sqrt{f'_c} + \frac{N_u}{6A_g} \right] b_w d$ (b)
$A_v < A_{v,min}$		$\left[8\lambda_s \lambda(\rho_w)^{1/3} \sqrt{f'_c} + \frac{N_u}{6A_g} \right] b_w d$ (c)

Notes:

1. Axial load N_u is positive for compression and negative for tension.
2. V_c shall not be taken less than zero.

COMMENTARY

R22.5.4 Composite concrete members

R22.5.4.1 The scope of Chapter 22 includes composite concrete members. Composite structural steel-concrete beams are not covered in the Code. Design provisions for such composite members are covered in [ANSI/AISC 360](#).

R22.5.5 V_c for nonprestressed members

R22.5.5.1 Test results for nonprestressed members without shear reinforcement indicate that measured shear strength, attributed to concrete, does not increase in direct proportion with member depth. This phenomenon is often referred to as “size effect.” For example, if member depth doubles, shear at failure for the deeper beam may be less than twice the shear at failure for the shallower beam ([Sneed and Ramirez 2010](#)). Research ([Angelakos et al. 2001](#); [Lubell et al. 2004](#); [Brown et al. 2006](#); [Becker and Buettner 1985](#); [Anderson 1978](#); [Bažant et al. 2007](#)) has shown that shear stress at failure is lower for beams and slabs with increased depth and a reduced area of longitudinal reinforcement. Changes were made in the ACI 318-19 code ([Kuchma et al. 2019](#)) to account for size effect and the effect of longitudinal reinforcement ratio on shear strength of members.

In Table 22.5.5.1, for $A_v > A_{v,min}$, either equation for V_c may be used. Equation (a) is provided as a simpler option.

When calculating V_c by Table 22.5.5.1, an axial tension force can cause V_c to have a negative value. In those cases, the Code specifies that V_c should be taken equal to zero.

The criteria column in Table 22.5.5.1 references $A_{v,min}$, which is defined in [7.6.3.3](#) for one-way slabs, [9.6.3.4](#) for beams, and [10.6.2.2](#) for columns and referenced throughout the Code.

CODE

22.5.5.1.1 V_c shall not be taken greater than $5\lambda\sqrt{f'_c}b_wd$. V_c need not be taken less than $\lambda\sqrt{f'_c}b_wd$ except in cases (a) or (b):

- (a) elements subjected to net axial tension
- (b) if 18.6.5.2 or 18.7.6.2.1 apply.

22.5.5.1.2 In Table 22.5.5.1, the value of $N_u/6A_g$ shall not be taken greater than $0.05f'_c$.

22.5.5.1.3 The size effect modification factor, λ_s , shall be determined by

$$\lambda_s = \frac{2}{1 + \frac{d}{10}} \leq 1 \quad (22.5.5.1.3)$$

22.5.5.1.4 For nonprestressed beams and one-way slabs constructed with steel fiber-reinforced concrete, conforming to 26.4.1.6.1(a), 26.4.2.2(h), and 26.12.8.1(a), V_c shall be the greater of Eq. (a) and 1.3 times Equation (b) of Table 22.5.5.1.

22.5.6 V_c for prestressed members

22.5.6.1 This section shall apply to the calculation of V_c for post-tensioned and pretensioned members in regions where the effective force in the prestressed reinforcement is fully transferred to the concrete. For regions of pretensioned members where the effective force in the prestressed reinforcement is not fully transferred to the concrete, 22.5.7 shall govern the calculation of V_c .

22.5.6.2 For prestressed members, V_c shall be permitted to be the lesser of V_{ci} calculated in accordance with 22.5.6.2.1 and V_{cw} calculated in accordance with 22.5.6.2.2 or 22.5.6.2.3.

COMMENTARY

R22.5.5.1.1 Because of the compounded effect of λ_s and ρ_w in Eq. 22.5.5.1c, V_c may tend to zero for large, lightly reinforced concrete members. The lower bound $\lambda\sqrt{f'_c}b_wd$ is intended to result in a concrete shear strength consistent with earlier, successful practice.

R22.5.5.1.3 The parameters within the size effect modification factor, λ_s , are consistent with fracture mechanics theory for reinforced concrete (Bažant et al. 2007; Frosch et al. 2017).

R22.5.5.1.4 The use of Eq. (a) and (b) in Table 22.5.5.1 for steel fiber-reinforced concrete and associated dosages in Chapter 26 are supported by experimental results (Dinh et al. 2010; Shoaib et al. 2014; Zarrinpour and Chao 2017). The presence of steel fibers is not considered in determining the value of A_{vmin} . Requirements for steel fibers are included in Chapter 26.

R22.5.6 V_c for prestressed members

R22.5.6.1 Editions of the Code prior to 2025 included an approximate method for the calculation of V_c for prestressed members. This method was removed because the method in Section 22.5.6.2 is a better predictor of shear strength.

R22.5.6.2 Two types of inclined cracking occur in concrete beams: web-shear cracking and flexure-shear cracking. These two types of inclined cracking are illustrated in Fig. R22.5.6.2.

Web-shear cracking begins from an interior point in a member when the principal tensile stresses exceed the tensile strength of the concrete. Flexure-shear cracking is initiated by flexural cracking. When flexural cracking occurs, the shear stresses in the concrete above the crack are increased. The flexure-shear crack develops when the combined shear and flexural-tensile stress exceeds the tensile strength of the concrete.

The nominal shear strength provided by the concrete, V_c , is assumed equal to the lesser of V_{ci} and V_{cw} . The derivations of Eq. (22.5.6.2.1a) and Eq. (22.5.6.2.2) are summarized in SP-10 (1965).

CODE

COMMENTARY




Fig. R22.5.6.3—Types of cracking in concrete beams.

22.5.6.2.1 The flexure-shear strength V_{ci} shall be calculated by (a) but need not be taken less than (b) or (c):

$$(a) V_{ci} = 0.6\lambda\sqrt{f'_c}b_wd_p + V_d + \frac{V_iM_{cre}}{M_{max}} \quad (22.5.6.2.1a)$$

$$(b) \text{ For members with } A_{ps}f_{se} < 0.4(A_{ps}f_{pu} + A_s f_y),$$

$$V_{ci} = 1.7\lambda\sqrt{f'_c}b_wd \quad (22.5.6.2.1b)$$

$$(c) \text{ For members with } A_{ps}f_{se} \geq 0.4(A_{ps}f_{pu} + A_s f_y),$$

$$V_{ci} = 2\lambda\sqrt{f'_c}b_wd \quad (22.5.6.2.1c)$$

where d_p need not be taken less than $0.80h$, the values of M_{max} and V_i shall be calculated from the load combinations causing maximum factored moment to occur at section considered, and M_{cre} shall be calculated by:

$$M_{cre} = \left(\frac{I}{y_i}\right)(6\lambda\sqrt{f'_c} + f_{pe} - f_d) \quad (22.5.6.2.1d)$$

R22.5.6.2.1 In deriving Eq. (22.5.6.2.1a), it was assumed that V_{ci} is the sum of the shear required to cause a flexural crack at the section in question given by:

$$V = \frac{V_iM_{cre}}{M_{max}} \quad (R22.5.6.2.1a)$$

plus an additional increment of shear required to change the flexural crack to a flexure-shear crack. The externally applied factored loads, from which V_i and M_{max} are determined, include superimposed dead load and live load. In calculating M_{cre} for substitution into Eq. (22.5.6.2.1a), I and y_i are the properties of the section resisting the externally applied loads.

For a composite concrete member, where part of the dead load is resisted by only a part of the section, appropriate section properties should be used to calculate f_d . The shear due to dead loads, V_d , and that due to other loads, V_i , are separated in this case. V_d is then the total shear force due to unfactored dead load acting on that part of the section resisting the dead loads acting prior to composite action plus the unfactored superimposed dead load acting on the composite member. The terms V_i and M_{max} may be taken as

$$V_i = V_u - V_d \quad (R22.5.6.2.1b)$$

$$M_{max} = M_u - M_d \quad (R22.5.6.2.1c)$$

where V_u and M_u are the factored shear and moment due to the total factored loads, and M_d is the moment due to unfactored dead load (the moment corresponding to f_d).

For noncomposite, uniformly loaded beams, the total cross section resists all the shear, and the live and dead load shear force diagrams are similar. In this case, Eq. (22.5.6.2.1a) and Eq. (22.5.6.2.1d) reduce to

$$V_{ci} = 0.6\lambda\sqrt{f'_c}b_wd + \frac{V_uM_{ct}}{M_u} \quad (R22.5.6.2.1d)$$

where

$$M_{ct} = (I/y_t)(6\lambda\sqrt{f'_c} + f_{pe}) \quad (R22.5.6.2.1e)$$

CODE

22.5.6.2.2 The web-shear strength V_{cw} shall be calculated by:

$$V_{cw} = (3.5\lambda\sqrt{f'_c} + 0.3f_{pc})b_wd_p + V_p \quad (22.5.6.2.2)$$

where d_p need not be taken less than $0.80h$, and V_p is the vertical component of the effective prestress.

22.5.6.2.3 As an alternative to 22.5.6.2.2, it shall be permitted to calculate V_{cw} as the shear force corresponding to dead load plus live load that results in a principal tensile stress of $4\lambda\sqrt{f'_c}$ at location (a) or (b):

- (a) Where the centroidal axis of the prestressed cross section is in the web, the principal tensile stress shall be calculated at the centroidal axis.
- (b) Where the centroidal axis of the prestressed cross section is in the flange, the principal tensile stress shall be calculated at the intersection of the flange and the web.

22.5.6.2.4 In composite concrete members, the principal tensile stress shall be calculated at the location specified in 22.5.6.2.3 for the composite section, considering superposition of stresses calculated cross sections that resist the corresponding loads.

22.5.7 V_c for pretensioned members in regions of reduced prestress force

22.5.7.1 When calculating V_c , the transfer length of prestressed reinforcement, ℓ_{tr} , shall be assumed to be $50d_b$ for strand and $100d_b$ for wire.

COMMENTARY

The cracking moment M_{cr} in the two preceding equations represents the total moment, including dead load, required to cause cracking at the extreme fiber in tension. This is not the same as M_{cre} in Eq. (22.5.6.2.1a) where the cracking moment is that due to all loads except the dead load. In Eq. (22.5.6.2.1a), the dead load shear is added as a separate term.

M_u is the factored moment on the beam at the section under consideration, and V_u is the factored shear force occurring simultaneously with M_u . Because the same section properties apply to both dead and live load stresses, there is no need to calculate dead load stresses and shears separately. M_{cr} reflects the total stress change from effective prestress to a tension of $6\lambda\sqrt{f'_c}$, assumed to cause flexural cracking.

R22.5.6.2.2 Equation (22.5.6.2.2) is based on the assumption that web-shear cracking occurs at a shear level causing a principal tensile stress of approximately $4\lambda\sqrt{f'_c}$ at the centroidal axis of the cross section. V_p is calculated from the effective prestress force without load factors.

R22.5.6.2.4 Generally, in unshored construction the principal tensile stresses due to dead load are caused before composite action and principal tensile stresses due to live load are caused after composite action is developed in a member. In shored construction the principal tensile stresses due to both the dead load and live load are caused after composite action is developed.

R22.5.7 V_c for pretensioned members in regions of reduced prestress force

R22.5.7.1 The effect of the reduced prestress near the ends of pretensioned beams on the shear strength should be taken into account. Provision 22.5.7.2 relates to the reduced shear strength at sections within the transfer length of prestressed reinforcement when bonding of prestressed reinforcement extends to the end of the member. Provision 22.5.7.3 relates to the reduced shear strength at sections within the length over which some of the prestressed reinforcement is not bonded to the concrete, or within the transfer length of

CODE

COMMENTARY

22.5.7.2 If bonding of strands extends to the end of the member, (a) and (b) shall apply:

(a) The effective prestress force shall be assumed to vary linearly from zero at the end of the prestressed reinforcement to a maximum at a distance ℓ_{tr} from the end of the prestressed reinforcement.

(b) The reduced effective prestress force shall be used to calculate V_{cw} in 22.5.6.2.

22.5.7.3 If bonding of strands does not extend to the end of the member, (a) and (b) shall apply:

(a) The effective prestress force shall be assumed to vary linearly from zero at the point where bonding commences to a maximum at a distance ℓ_{tr} from that point.

(b) The reduced effective prestress force shall be used to calculate V_c in accordance with 22.5.6.2.

22.5.8 One-way shear reinforcement

22.5.8.1 At each section where $V_u > \phi V_c$, transverse reinforcement shall be provided such that Eq. (22.5.8.1) is satisfied.

$$V_s \geq \frac{V_u}{\phi} - V_c \quad (22.5.8.1)$$

22.5.8.2 For one-way members reinforced with transverse reinforcement, V_s shall be calculated in accordance with 22.5.8.5.

22.5.8.3 For one-way members reinforced with bent-up longitudinal bars, V_s shall be calculated in accordance with 22.5.8.6.

22.5.8.4 If more than one type of shear reinforcement is provided to reinforce the same portion of a member, V_s shall be the sum of the V_s values for the various types of shear reinforcement.

22.5.8.5 One-way shear strength provided by transverse reinforcement

22.5.8.5.1 In nonprestressed and prestressed members, shear reinforcement satisfying (a), (b), or (c) shall be permitted:

(a) Stirrups, ties, or hoops perpendicular to longitudinal axis of member

(b) Welded wire reinforcement with wires located perpendicular to longitudinal axis of member

the prestressed reinforcement for which bonding does not extend to the end of the beam.

R22.5.8 One-way shear reinforcement

R22.5.8.2 Provisions of 22.5.8.5 apply to all types of transverse reinforcement, including stirrups, ties, hoops, crossties, and spirals.

R22.5.8.5 One-way shear strength provided by transverse reinforcement

R22.5.8.5.1 Design of shear reinforcement is based on a modified truss analogy. In the truss analogy, the force in vertical ties is resisted by shear reinforcement. Shear reinforcement needs to be designed to resist only the shear exceeding that which causes inclined cracking, provided the diagonal members in the truss are assumed to be inclined at 45 degrees. The concrete is assumed to contribute to the shear capacity through resistance across the concrete compressive

CODE

(c) Spiral reinforcement

22.5.8.5.2 Inclined stirrups making an angle of at least 45 degrees with the longitudinal axis of the member and crossing the plane of the potential shear crack shall be permitted to be used as shear reinforcement in nonprestressed members.

22.5.8.5.3 V_s for shear reinforcement in 22.5.8.5.1 shall be calculated by:

$$V_s = \frac{A_v f_{yt} d}{s} \quad (22.5.8.5.3)$$

where s is the spiral pitch or the longitudinal spacing of the shear reinforcement, and A_v is given in 22.5.8.5.5 or 22.5.8.5.6.

22.5.8.5.4 V_s for shear reinforcement in 22.5.8.5.2 shall be calculated by:

$$V_s = \frac{A_v f_{yt} (\sin \alpha + \cos \alpha) d}{s} \quad (22.5.8.5.4)$$

where α is the angle between the inclined stirrups and the longitudinal axis of the member, s is measured parallel to the longitudinal reinforcement, and A_v is given in 22.5.8.5.5.

22.5.8.5.5 For each rectangular tie, stirrup, hoop, or crosstie, A_v shall be the effective area of all bar legs or wires within spacing s .

22.5.8.5.6 For each circular tie or spiral, A_v shall be two times the area of the bar or wire within spacing s .

22.5.8.6 *One-way shear strength provided by bent-up longitudinal bars*

22.5.8.6.1 The center three-fourths of the inclined portion of bent-up longitudinal bars shall be permitted to be used as shear reinforcement in nonprestressed members if the angle α between the bent-up bars and the longitudinal axis of the member is at least 30 degrees.

22.5.8.6.2 If shear reinforcement consists of a single bar or a single group of parallel bars having an area A_v , all bent

COMMENTARY

zone, aggregate interlock, and dowel action in an amount equivalent to that which caused inclined cracking.

Equations (22.5.8.5.3), (22.5.8.5.4), and (22.5.8.6.2a) are presented in terms of nominal shear strength provided by shear reinforcement, V_s . Where shear reinforcement perpendicular to the axis of the member is used, the required area of shear reinforcement, A_v , and its spacing, s , are calculated by

$$\frac{A_v}{s} = \frac{V_u - \phi V_c}{\phi f_{yt} d} \quad (R22.5.8.5)$$

R22.5.8.5.2 Although inclined stirrups crossing the plane of the potential shear cracks are permitted, their use is not appropriate where the direction of net shear reverses due to changes in transient load.

R22.5.8.5.4 To be effective, it is critical that inclined stirrups cross potential shear cracks. If the inclined stirrups are generally oriented parallel to the potential shear cracks, the stirrups provide no shear strength.

R22.5.8.5.6 Although the transverse reinforcement in a circular section may not consist of straight legs, tests indicate that Eq. (22.5.8.5.3) is conservative if d is taken as defined in 22.5.2.2 (Faradji and Diaz de Cossio 1965; Khalifa and Collins 1981).

R22.5.8.6 *One-way shear strength provided by bent-up longitudinal bars*

R22.5.8.6.1 To be effective, it is critical that the inclined portion of the bent-up longitudinal bar cross potential shear cracks. If the inclined bars are generally oriented parallel to the potential shear cracks, the bars provide no shear strength.

CODE**COMMENTARY**

the same distance from the support, V_s shall be the lesser of (a) and (b):

$$(a) V_s = A_v f_y \sin \alpha \quad (22.5.8.6.2a)$$

$$(b) V_s = 3\sqrt{f'_c} b_w d \quad (22.5.8.6.2b)$$

where α is the angle between bent-up reinforcement and longitudinal axis of the member.

22.5.8.6.3 If shear reinforcement consists of a series of parallel bent-up bars or groups of parallel bent-up bars at different distances from the support, V_s shall be calculated by Eq. (22.5.8.5.4).

22.6—Two-way shear strength**R22.6—Two-way shear strength**

Factored two-way shear stress due to shear and moment transfer is calculated in accordance with the requirements of 8.4.4. Section 22.6 provides requirements for determining nominal shear strength, either without shear reinforcement or with shear reinforcement in the form of stirrups or headed shear studs. Factored shear demand and strength are calculated in terms of stress, permitting superposition of effects from direct shear and moment transfer.

Design provisions for shearheads have been eliminated from the Code because this type of shear reinforcement is seldom used in current practice. Shearheads may be designed following the provisions of ACI CODE-318-14.

22.6.1 General**R22.6.1 General**

22.6.1.1 Provisions 22.6.1 through 22.6.8 apply to the nominal two-way shear strength of members with and without shear reinforcement.

22.6.1.2 Nominal two-way shear strength for members without shear reinforcement shall be calculated by

$$v_n = v_c \quad (22.6.1.2)$$

22.6.1.3 Nominal two-way shear strength for members with shear reinforcement shall be calculated by

$$v_n = v_c + v_s \quad (22.6.1.3)$$

22.6.1.4 Two-way shear shall be resisted by a section with a depth d and an assumed critical perimeter b_o as defined in 22.6.4.

R22.6.1.4 The critical section perimeter b_o is defined in 22.6.4.

22.6.1.5 v_c for two-way shear shall be calculated in accordance with 22.6.5. For two-way shear in members with shear reinforcement, v_c shall not exceed the limits in 22.6.6.1.

22.6.1.6 For calculation of v_c , λ shall be in accordance with 19.2.4.

CODE

22.6.1.7 For two-way shear in members reinforced with single- or multiple-leg stirrups, v_s shall be calculated in accordance with 22.6.7.

22.6.1.8 For two-way shear in members reinforced with headed shear stud reinforcement, v_s shall be calculated in accordance with 22.6.8.

22.6.2 Effective depth

22.6.2.1 For calculation of v_c and v_s for two-way shear, d shall be the average of the effective depths in the two orthogonal directions.

22.6.2.2 For two-way shear in prestressed members, d need not be taken less than $0.8h$.

22.6.3 Limiting material strengths

22.6.3.1 The value of $\sqrt{f'_c}$ used to calculate v_c for two-way shear shall not exceed 100 psi.

22.6.3.2 The value of f_{yt} used to calculate v_s shall not exceed the limits in 20.2.2.4.

22.6.4 Critical sections for two-way shear

22.6.4.1 For two-way shear, critical sections shall be located so that the perimeter b_o is a minimum but need not be closer than $d/2$ to (a) and (b):

- (a) Edges or corners of columns, concentrated loads, or reaction areas
- (b) Changes in slab or footing thickness, such as edges of capitals, drop panels, or shear caps

22.6.4.1.1 For square or rectangular columns, concentrated loads, or reaction areas, critical sections for two-way shear in accordance with 22.6.4.1(a) and (b) shall be permitted to be defined assuming straight sides.

22.6.4.1.2 For a circular or regular polygon-shaped column, critical sections for two-way shear in accordance

COMMENTARY

R22.6.3 Limiting material strengths

R22.6.3.1 There are limited test data on the two-way shear strength of high-strength concrete slabs. Until more experience is obtained for two-way shear in slabs constructed with concretes that have compressive strengths greater than 10,000 psi, it is prudent to limit $\sqrt{f'_c}$ to 100 psi for the calculation of shear strength.

R22.6.3.2 The upper limit of 60,000 psi on the value of f_{yt} used in design is intended to control cracking.

R22.6.4 Critical sections for two-way shear

R22.6.4.1 The critical section defined in 22.6.4.1(a) for two-way shear in slabs and footings follows the perimeter at the edge of the loaded area (Joint ACI-ASCE Committee 326 1962). Loaded area for two-way shear in slabs and footings includes columns, concentrated loads, and reaction areas. An idealized critical section located a distance $d/2$ from the periphery of the loaded area is considered.

For members of uniform thickness without shear reinforcement, it is sufficient to check shear using one section. For slabs with changes in thickness or with shear reinforcement, it is necessary to check shear at multiple sections as defined in 22.6.4.1(a) and (b) and 22.6.4.2.

For columns near an edge or corner, the critical perimeter may extend to the edge of the slab.

CODE

with 22.6.4.1(a) and (b) shall be permitted to be defined assuming a square column of equivalent area.

22.6.4.2 For members reinforced for two-way shear with headed shear reinforcement or single- or multi-leg stirrups, a critical section with perimeter b_o located $d/2$ beyond the outermost peripheral line of shear reinforcement shall also be considered. The shape of this critical section shall be a polygon selected to minimize b_o .

COMMENTARY

R22.6.4.2 For members reinforced for two-way shear with stirrup or headed stud shear reinforcement, it is required to check shear stress in concrete at a critical section located a distance $d/2$ beyond the point where shear reinforcement is discontinued. Calculated shear stress at this section must not exceed the limits given in expressions (a) and (e) in Table 22.6.6.1. The shape of this outermost critical section should correspond to the minimum value of b_o , as depicted in Fig. R22.6.4.2a, b, and c. Note that these figures depict slabs reinforced with stirrups. The shape of the outermost critical section is similar for slabs with headed shear reinforcement. The square or rectangular critical sections described in 22.6.4.1.1 will not result in the minimum value of b_o for the cases depicted in these figures. Additional critical section checks are required at a distance $d/2$ beyond any point where variations in shear reinforcement occur, such as changes in size, spacing, or configuration.




Fig. R22.6.4.2a—Critical sections for two-way shear in slab with shear reinforcement at interior column.

CODE

COMMENTARY




Fig. R22.6.4.2b—Critical sections for two-way shear in slab with shear reinforcement at edge column.




Fig. R22.6.4.2c—Critical sections for two-way shear in slab with shear reinforcement at corner column.


22.6.4.3 If an opening is located closer than $4h$ from the periphery of a column, concentrated load, or reaction area, the portion of b_o enclosed by straight lines projecting from the centroid of the column, concentrated load or reaction area and tangent to the boundaries of the opening shall be considered ineffective.

R22.6.4.3 Provisions for design of openings in slabs (and footings) were developed in [Joint ACI-ASCE Committee 326 \(1962\)](#). The locations of the effective portions of the critical section near typical openings and free edges are shown by the dashed lines in Fig. R22.6.4.3. Research ([Joint ACI-ASCE Committee 426 1974](#)) has confirmed that these provisions are conservative.

Research ([Genikomsou and Polak 2017](#)) has shown that when openings are located at distances greater than $4d$ from the periphery of a column, the punching shear strength is the same as that for a slab without openings.

CODE

COMMENTARY



Note: Openings shown are located within $10h$ of column.

Fig. R22.6.4.3—Effect of openings and free edges (effective perimeter shown with dashed lines).

22.6.5 Two-way shear strength provided by concrete in members without shear reinforcement

22.6.5.1 For nonprestressed members, v_c shall be calculated in accordance with 22.6.5.2. For prestressed members, v_c shall be calculated in accordance with (a) or (b):

- (a) 22.6.5.2
- (b) 22.6.5.5, if the conditions of 22.6.5.4 are satisfied

22.6.5.2 v_c shall be calculated in accordance with Table 22.6.5.2.

Table 22.6.5.2—Two-way shear strength v_c for members without shear reinforcement

v_c		
Least of (a), (b), and (c):	$4\lambda_s\lambda\sqrt{f'_c}$	(a)
	$\left(2 + \frac{4}{\beta}\right)\lambda_s\lambda\sqrt{f'_c}$	(b)
	$\left(2 + \frac{\alpha_s d}{b_o}\right)\lambda_s\lambda\sqrt{f'_c}$	(c)

Notes: (i) λ_s is the size effect factor given in 22.5.5.1.3. (ii) β is the ratio of long to short sides of the column, concentrated load, or reaction area. (iii) α_s is given in 22.6.5.3.

R22.6.5 Two-way shear strength provided by concrete in members without shear reinforcement

R22.6.5.2 Experimental evidence indicates that the measured two-way concrete shear strength of members without shear reinforcement does not increase in direct proportion with member depth. This phenomenon is referred to as the “size effect.” The modification factor λ_s accounts for the dependence of two-way shear strength of slabs on effective depth.

For nonprestressed two-way slabs without a minimum amount of shear reinforcement and with $d > 10$ in., the size effect specified in 22.5.5.1.3 reduces the shear strength of two-way slabs below $4\sqrt{f'_c}b_o d$ (Hawkins and Ospina 2017; Dönmez and Bažant 2017).

For square columns, the stress corresponding to the nominal two-way shear strength provided by concrete in slabs subjected to bending in two directions is limited to $4\lambda_s\sqrt{f'_c}$. However, tests (Joint ACI-ASCE Committee 426 1974)

CODE

COMMENTARY

have indicated that the value of $4\lambda_s\sqrt{f'_c}$ is unconservative when the ratio β of the lengths of the long and short sides of a rectangular column or loaded area is larger than 2.0. In such cases, the actual shear stress on the critical section at punching shear failure varies from a maximum of approximately $4\lambda_s\sqrt{f'_c}$ around the corners of the column or loaded area, down to $2\lambda_s\sqrt{f'_c}$ or less along the long sides between the two end sections. Other tests (Vanderbilt 1972) indicate that v_c decreases as the ratio b_o/d increases. Expressions (b) and (c) in Table 22.6.5.2 were developed to account for these two effects.

For shapes other than rectangular, β is taken to be the ratio of the longest overall dimension of the effective loaded area to the largest overall perpendicular dimension of the effective loaded area, as illustrated for an L-shaped reaction area in Fig. R22.6.5.2. The effective loaded area is that area totally enclosing the actual loaded area, for which the perimeter is a minimum.




Fig. R22.6.5.2—Value of β for a nonrectangular loaded area.

22.6.5.3 The value of α_s is 40 for interior columns, 30 for edge columns, and 20 for corner columns.

22.6.5.4 For two-way shear in prestressed members, it shall be permitted to calculate v_c using 22.6.5.5, provided that (a) through (c) are satisfied:

- (a) Bonded reinforcement is provided in accordance with 8.6.2.3 and 8.7.5.3
- (b) No portion of the column cross section is closer to a discontinuous edge than four times the slab thickness h

R22.6.5.3 The terms “interior columns,” “edge columns,” and “corner columns” in this provision refer to critical sections with a continuous slab on four, three, and two sides, respectively.

R22.6.5.4 For prestressed members, modified forms of expressions (b) and (c) in Table 22.6.5.2 are specified. Research (ACI PRC-423.3) indicates that the shear strength of two-way prestressed slabs around interior columns is conservatively calculated by the expressions in 22.6.5.5, where v_c corresponds to a diagonal tension failure of the concrete initiating at the critical section defined in 22.6.4.1. The mode of failure differs from a punching shear failure around the perimeter of the loaded

CODE

(c) Effective prestress f_{pc} in each direction is not less than 125 psi

22.6.5.5 For two-way shear in prestressed members conforming to 22.6.5.4, v_c shall be permitted to be the lesser of (a) and (b)

$$(a) v_c = 3.5\lambda\sqrt{f'_c} + 0.3f_{pc} + \frac{V_p}{b_o d} \quad (22.6.5.5a)$$

$$(b) v_c = \left(1.5 + \frac{\alpha_s d}{b_o}\right)\lambda\sqrt{f'_c} + 0.3f_{pc} + \frac{V_p}{b_o d} \quad (22.6.5.5b)$$

where α_s is given in 22.6.5.3; the value of f_{pc} is the average of f_{pc} in the two directions and shall not exceed 500 psi; V_p is the vertical component of all effective prestress forces crossing the critical section; and the value of $\sqrt{f'_c}$ shall not exceed 70 psi.

22.6.6 Two-way shear strength provided by concrete in members with shear reinforcement

22.6.6.1 For members where shear reinforcement is required to resist two-way shear, v_c at critical sections shall be calculated in accordance with Table 22.6.6.1.

COMMENTARY

area of a nonprestressed slab calculated using expression (b) in Table 22.6.5.2. Consequently, the expressions in 22.6.5.5 differ from those for nonprestressed slabs. Values for $\sqrt{f'_c}$ and f_{pc} are restricted in design due to limited test data available beyond the specified limits. When calculating f_{pc} , loss of prestress due to restraint of the slab by structural walls and other structural elements should be taken into account.

R22.6.6 Two-way shear strength provided by concrete in members with shear reinforcement

Critical sections for members with shear reinforcement are defined in 22.6.4.1 for the sections adjacent to the column, concentrated load, or reaction area, and 22.6.4.2 for the section located just beyond the outermost peripheral line of stirrup or headed shear stud reinforcement. Values of maximum v_c for these critical sections are given in Table 22.6.6.1. Limiting values of v_u for the critical sections defined in 22.6.4.1 are given in Table 22.6.6.3.

The maximum v_c and limiting value of v_u at the innermost critical section (defined in 22.6.4.1) are higher where headed shear stud reinforcement is provided than the case where stirrups are provided (refer to R8.7.7). Maximum v_c values at the critical sections defined in 22.6.4.2 beyond the outermost peripheral line of shear reinforcement are independent of the type of shear reinforcement provided.

R22.6.6.1 For slabs with stirrups, the maximum value of v_c is taken as $2\lambda_s\lambda\sqrt{f'_c}$ because the stirrups resist all the shear beyond that at inclined cracking (which occurs at approximately half the capacity of a slab without shear reinforcement (that is, $0.5 \times 4\lambda_s\lambda\sqrt{f'_c} = 2\lambda_s\lambda\sqrt{f'_c}$) (Hawkins 1974). The higher value of v_c for slabs with headed shear stud reinforcement is based on research (Elgabry and Ghali 1987).

CODE

Table 22.6.6.1—Two-way shear strength v_c for members with shear reinforcement

Type of shear reinforcement	Critical sections	v_c	
Stirrups	All	$2\lambda_s\lambda\sqrt{f'_c}$	(a)
Headed shear stud reinforcement	According to 22.6.4.1	$3\lambda_s\lambda\sqrt{f'_c}$	(b)
		$\left(2 + \frac{4}{\beta}\right)\lambda_s\lambda\sqrt{f'_c}$	(c)
		$\left(2 + \frac{a_s d}{b_o}\right)\lambda_s\lambda\sqrt{f'_c}$	(d)
	According to 22.6.4.2	$2\lambda_s\lambda\sqrt{f'_c}$	(e)

Notes: (i) λ_s is the size effect factor given in 22.5.5.1.3. (ii) β is the ratio of long to short sides of the column, concentrated load, or reaction area. (iii) a_s is given in 22.6.5.3.

22.6.6.2 It shall be permitted to take λ_s as 1.0 if (a) or (b) is satisfied:

- (a) Stirrups are designed and detailed in accordance with 8.7.6 and $A_v/s \geq 2\sqrt{f'_c}b_o/f_{yt}$.
- (b) Smooth headed shear stud reinforcement with stud shaft length not exceeding 10 in. is designed and detailed in accordance with 8.7.7 and $A_v/s \geq 2\sqrt{f'_c}b_o/f_{yt}$.

COMMENTARY

R22.6.6.2 The size effect in slabs with $d > 10$ in. can be mitigated if a minimum amount of shear reinforcement is provided. The ability of ordinary (smooth) headed shear stud reinforcement to effectively mitigate the size effect on the two-way shear strength of slabs may be compromised if studs longer than 10 in. are used. Until experimental evidence becomes available, it is not permitted to use λ_s equal to 1.0 for slabs with $d > 10$ in. without headed shear stud reinforcement with stud shaft length not exceeding 10 in. Stacking or “piggybacking” of headed shear studs, as shown in Fig. R22.6.6.2, introduces an intermediate head that contributes to further anchor the stacked stud.




Fig. R22.6.6.2—Stacking (piggybacking) of headed shear stud reinforcement.

22.6.6.3 For members with shear reinforcement, effective depth shall be selected such that two-way shear stress v_u calculated at critical sections does not exceed the values in Table 22.6.6.3.

CODE

COMMENTARY

Table 22.6.6.3—Maximum two-way shear stress v_u for members with shear reinforcement

Type of shear reinforcement	Maximum v_u at critical sections defined in 22.6.4.1	
Stirrups	$\phi 6\sqrt{f'_c}$	(a)
Headed shear stud reinforcement	$\phi 8\sqrt{f'_c}$	(b)

22.6.7 Two-way shear strength provided by single- or multiple-leg stirrups

22.6.7.1 Single- or multiple-leg stirrups fabricated from bars or wires shall be permitted to be used as shear reinforcement in slabs and footings satisfying (a) and (b):

(a) d is at least 6 in.

(b) d is at least $16d_b$, where d_b is the diameter of the stirrups

22.6.7.2 For members with stirrups, v_s shall be calculated by:

$$v_s = \frac{A_v f_{yt}}{b_o s} \quad (22.6.7.2)$$

where A_v is the sum of the area of all legs of reinforcement on one peripheral line that is geometrically similar to the perimeter of the column section, and s is the spacing of the peripheral lines of shear reinforcement in the direction perpendicular to the column face.

22.6.8 Two-way shear strength provided by headed shear stud reinforcement

22.6.8.1 Headed shear stud reinforcement shall be permitted to be used as shear reinforcement in slabs and footings if the placement and geometry of the headed shear stud reinforcement satisfies 8.7.7.

22.6.8.2 For members with headed shear stud reinforcement, v_s shall be calculated by:

$$v_s = \frac{A_v f_{yt}}{b_o s} \quad (22.6.8.2)$$

where A_v is the sum of the area of all shear studs on one peripheral line that is geometrically similar to the perimeter of the column section, and s is the spacing of the peripheral

R22.6.7 Two-way shear strength provided by single- or multiple-leg stirrups

R22.6.7.2 Because shear stresses are used for two-way shear in this chapter, shear strength provided by transverse reinforcement is averaged over the cross-sectional area of the critical section.

R22.6.8 Two-way shear strength provided by headed shear stud reinforcement

Tests (ACI PRC-421.1) show that headed shear stud reinforcement mechanically anchored as close as practicable to the top and bottom of slabs is effective in resisting punching shear. The critical section beyond the shear reinforcement is generally assumed to have a polygonal shape (refer to Fig. R22.6.4.2a, R22.6.4.2b, and R22.6.4.2c). Equations for calculating shear stresses on such sections are given in ACI PRC-421.1.

R22.6.8.2 Because shear stresses are used for two-way shear in this chapter, shear strength provided by transverse reinforcement is averaged over the cross-sectional area of the critical section.

CODE

lines of headed shear stud reinforcement in the direction perpendicular to the column face.

22.6.8.3 If headed shear stud reinforcement is provided, A_v/s shall satisfy:

$$\frac{A_v}{s} \geq 2\sqrt{f'_c} \frac{b_o}{f_{yt}} \quad (22.6.8.3)$$

22.7—Torsional strength**COMMENTARY****R22.7—Torsional strength**

The design for torsion in this section is based on a thin-walled tube space truss analogy. A beam subjected to torsion is idealized as a thin-walled tube with the core concrete cross section in a solid beam neglected as shown in Fig. R22.7(a). Once a reinforced concrete beam has cracked in torsion, its torsional strength is provided primarily by closed stirrups and longitudinal bars located near the surface of the member. In the thin-walled tube analogy, the strength is assumed to be provided by the outer skin of the cross section roughly centered on the closed stirrups. Both hollow and solid sections are idealized as thin-walled tubes both before and after cracking.

In a closed thin-walled tube, the product of the shear stress τ and the wall thickness t at any point in the perimeter is known as the shear flow, $q = \tau t$. The shear flow q due to torsion acts as shown in Fig. R22.7(a) and is constant at all points around the perimeter of the tube. The path along which it acts extends around the tube at midthickness of the walls of the tube. At any point along the perimeter of the tube, the shear stress due to torsion is $\tau = T/(2A_o t)$, where A_o is the gross area enclosed by the shear flow path, shown shaded in Fig. R22.7(b), and t is the thickness of the wall at the point where τ is being calculated. For a hollow member with continuous walls, A_o includes the area of the hole.

The concrete contribution to torsional strength is ignored, and in cases of combined shear and torsion, the concrete contribution to shear strength does not need to be reduced. The design procedure is derived and compared with test results in [MacGregor and Ghoneim \(1995\)](#) and [Hsu \(1997\)](#). Detailed information on the thin-walled tube space truss analogy is provided in [ACI PRC-445.1](#).

CODE

COMMENTARY





Fig. R22.7—(a) Thin-walled tube; and (b) area enclosed by shear flow path.

22.7.1 General

22.7.1.1 This section shall apply to members if $T_u \geq \phi T_{th}$, where ϕ is given in Chapter 21 and threshold torsion T_{th} is given in 22.7.4. If $T_u < \phi T_{th}$, it shall be permitted to neglect torsional effects.

22.7.1.2 Nominal torsional strength shall be calculated in accordance with 22.7.6.

22.7.1.3 For calculation of T_{th} and T_{cr} , λ shall be in accordance with 19.2.4.

22.7.2 Limiting material strengths

22.7.2.1 The value of $\sqrt{f'_c}$ used to calculate T_{th} and T_{cr} shall not exceed 100 psi.

22.7.2.2 The values of f_y and f_{yt} for longitudinal and transverse torsional reinforcement shall not exceed the limits in 20.2.2.4.

R22.7.1 General

R22.7.1.1 Torsional moments that do not exceed the threshold torsion T_{th} will not cause a structurally significant reduction in either flexural or shear strength and can be ignored.

R22.7.2 Limiting material strengths

R22.7.2.1 Because of a lack of test data and practical experience with concretes having compressive strengths greater than 10,000 psi, the Code imposes a maximum value of 100 psi on $\sqrt{f'_c}$ for use in the calculation of torsional strength.

R22.7.2.2 The upper limit of 60,000 psi on the value of f_y and f_{yt} used in design is intended to control diagonal crack width.

CODE

22.7.3 Factored design torsion

COMMENTARY

R22.7.3 Factored design torsion

In designing for torsion in reinforced concrete structures, two conditions may be identified (Collins and Lampert 1973; Hsu and Burton 1974):

(a) The torsional moment cannot be reduced by redistribution of internal forces (22.7.3.1). This type of torsion is referred to as equilibrium torsion because the torsional moment is required for the structure to be in equilibrium. For this condition, illustrated in Fig. R22.7.3(a), torsional reinforcement must be provided to resist the total design torsional moments.

(b) The torsional moment can be reduced by redistribution of internal forces after cracking (22.7.3.2) if the torsion results from the member twisting to maintain compatibility of deformations. This type of torsion is referred to as compatibility torsion.

For this condition, illustrated in Fig. R22.7.3(b), the torsional stiffness before cracking corresponds to that of the uncracked section according to St. Venant's theory. At torsional cracking, however, a large twist occurs under an essentially constant torsional moment, resulting in a large redistribution of forces in the structure (Collins and Lampert 1973; Hsu and Burton 1974). The cracking torsional moment under combined shear, moment, and torsion corresponds to a principal tensile stress somewhat less than the $4\lambda\sqrt{f'_c}$ used in R22.7.5.

If the torsional moment exceeds the cracking torsional moment (22.7.3.2), a maximum factored torsional moment equal to the cracking torsional moment may be assumed to occur at critical sections. The maximum factored torsional moment has been established to limit the width of torsional cracks.

Provision 22.7.3.2 applies to typical and regular framing conditions. With layouts that impose significant torsional rotations within a limited length of the member, such as a large torsional moment located close to a stiff column, or a column that rotates in the reverse directions because of other loading, a more detailed analysis is advisable.

If the factored torsional moment from an elastic analysis based on uncracked section properties is between ϕT_{th} and ϕT_{cr} , torsional reinforcement should be designed to resist the calculated torsional moments.

CODE

COMMENTARY




Fig. R22.7.3a—Equilibrium torsion, the design torsional moment may not be reduced (22.7.3.1).




Fig. R22.7.3b—Compatibility torsion, the design torsional moment may be reduced (22.7.3.2).

22.7.3.1 If $T_u \geq \phi T_{cr}$ and T_u is required to maintain equilibrium, the member shall be designed to resist T_u .

22.7.3.2 In a statically indeterminate structure where $T_u \geq \phi T_{cr}$ and a reduction of T_u can occur due to redistribution of internal forces after torsional cracking, it shall be permitted to reduce T_u to ϕT_{cr} , where the cracking torsion T_{cr} is calculated in accordance with 22.7.5.

22.7.3.3 If T_u is redistributed in accordance with 22.7.3.2, the factored moments and shears used for design of the adjoining members shall be in equilibrium with the reduced torsion.

CODE

COMMENTARY

22.7.4 Threshold torsion

R22.7.4 Threshold torsion

The threshold torsion is defined as one-fourth the cracking torsional moment T_{cr} . For sections of solid members, the interaction between the cracking torsional moment and the inclined cracking shear is approximately circular or elliptical. For such a relationship, a threshold torsional moment of T_{th} , as used in 22.7.4.1, corresponds to a reduction of less than 5% in the inclined cracking shear, which is considered negligible.

For torsion, a hollow section is defined as having one or more longitudinal voids, such as a single-cell or multiple-cell box girder. Small longitudinal voids, such as ungrouted post-tensioning ducts that result in $A_g/A_{cp} \geq 0.95$, can be ignored when calculating T_{th} . The interaction between torsional cracking and shear cracking for hollow sections is assumed to vary from the elliptical relationship for members with small voids, to a straight-line relationship for thin-walled sections with large voids. For a straight-line interaction, a torsional moment of T_{th} would cause a reduction in the inclined cracking shear of approximately 25%, which was considered to be significant. Therefore, the expressions for solid sections are modified by the factor $(A_g/A_{cp})^2$ to develop the expressions for hollow sections. Tests of solid and hollow beams (Hsu 1968) indicate that the cracking torsional moment of a hollow section is approximately (A_g/A_{cp}) times the cracking torsional moment of a solid section with the same outside dimensions. An additional multiplier of (A_g/A_{cp}) reflects the transition from the circular interaction between the inclined cracking loads in shear and torsion for solid members, to the approximately linear interaction for thin-walled hollow sections.

22.7.4.1 Threshold torsion T_{th} shall be calculated in accordance with Table 22.7.4.1(a) for solid cross sections and Table 22.7.4.1(b) for hollow cross sections, where N_u is positive for compression and negative for tension.

Table 22.7.4.1(a)—Threshold torsion for solid cross sections

Type of member	T_{th}	
Nonprestressed member	$\lambda \sqrt{f'_c} \left(\frac{A_{cp}^2}{p_{cp}} \right)$	(a)
Prestressed member	$\lambda \sqrt{f'_c} \left(\frac{A_{cp}^2}{p_{cp}} \right) \sqrt{1 + \frac{f_{pc}}{4\lambda \sqrt{f'_c}}}$	(b)
Nonprestressed member subjected to axial force	$\lambda \sqrt{f'_c} \left(\frac{A_{cp}^2}{p_{cp}} \right) \sqrt{1 + \frac{N_u}{4A_g \lambda \sqrt{f'_c}}}$	(c)

CODE

COMMENTARY

Table 22.7.4.1(b)—Threshold torsion for hollow cross sections

Type of member	T_{th}	
Nonprestressed member	$\lambda\sqrt{f'_c}\left(\frac{A_g^2}{p_{cp}}\right)$	(a)
Prestressed member	$\lambda\sqrt{f'_c}\left(\frac{A_g^2}{p_{cp}}\right)\sqrt{1+\frac{f_{pc}}{4\lambda\sqrt{f'_c}}}$	(b)
Nonprestressed member subjected to axial force	$\lambda\sqrt{f'_c}\left(\frac{A_g^2}{p_{cp}}\right)\sqrt{1+\frac{N_u}{4A_g\lambda\sqrt{f'_c}}}$	(c)

22.7.5 Cracking torsion

22.7.5.1 Cracking torsion T_{cr} shall be calculated in accordance with Table 22.7.5.1 for solid and hollow cross sections, where N_u is positive for compression and negative for tension.

Table 22.7.5.1—Cracking torsion

Type of member	T_{cr}	
Nonprestressed member	$4\lambda\sqrt{f'_c}\left(\frac{A_{cp}^2}{p_{cp}}\right)$	(a)
Prestressed member	$4\lambda\sqrt{f'_c}\left(\frac{A_{cp}^2}{p_{cp}}\right)\sqrt{1+\frac{f_{pc}}{4\lambda\sqrt{f'_c}}}$	(b)
Nonprestressed member subjected to axial force	$4\lambda\sqrt{f'_c}\left(\frac{A_{cp}^2}{p_{cp}}\right)\sqrt{1+\frac{N_u}{4A_g\lambda\sqrt{f'_c}}}$	(c)

R22.7.5 Cracking torsion

R22.7.5.1 The cracking torsional moment under pure torsion, T_{cr} , is derived by replacing the actual section with an equivalent thin-walled tube with a wall thickness t prior to cracking of $0.75A_{cp}/p_{cp}$ and an area enclosed by the wall centerline A_o equal to $2A_{cp}/3$. Cracking is assumed to occur when the principal tensile stress reaches $4\lambda\sqrt{f'_c}$. The stress at cracking, $4\lambda\sqrt{f'_c}$, has purposely been taken as a lower-bound value. In a nonprestressed beam loaded with torsion alone, the principal tensile stress is equated to the torsional shear stress, $\tau = T/(2A_o t)$. Thus, cracking occurs when τ reaches $4\lambda\sqrt{f'_c}$, giving the cracking torsional moment T_{cr} as defined by expression (a) in Table 22.7.5.1.

For prestressed members, the torsional cracking load is increased by the prestress given by expression (b) in Table 22.7.5.1. A Mohr's Circle analysis based on average stresses indicates the torsional moment required to cause a principal tensile stress equal to $4\lambda\sqrt{f'_c}$ is $\sqrt{1+f_{pc}/(4\lambda\sqrt{f'_c})}$ times the corresponding torsional cracking moment in a nonprestressed beam. A similar modification is made in expression (c) in Table 22.7.5.1 for members subjected to axial force and torsion.

If the factored torsional moment exceeds ϕT_{cr} in a statically indeterminate structure, a maximum factored torsional moment equal to ϕT_{cr} may be assumed to occur at critical sections. This limit has been established to control the width of the torsional cracks. The replacement of A_{cp} with A_g , as in the calculation of T_{th} for hollow sections in 22.7.4.1, is not applied here. Thus, the torsional moment after redistribution is larger and, hence, more conservative.

22.7.6 Nominal torsional strength**R22.7.6 Nominal torsional strength**

In the calculation of T_n , all the torsion is assumed to be resisted by stirrups and longitudinal reinforcement, neglecting any concrete contribution to torsional strength. At the same time, the nominal shear strength provided by concrete, V_c , is assumed to be unchanged by the presence of torsion.

22.7.6.1 For nonprestressed and prestressed members, T_n shall be the lesser of (a) and (b):

R22.7.6.1 Equation (22.7.6.1a) is based on the space truss analogy shown in Fig. R22.7.6.1a with compression diago-

CODE

$$(a) T_n = \frac{2A_o A_t f_{yt}}{s} \cot \theta \quad (22.7.6.1a)$$

$$(b) T_n = \frac{2A_o A_t f_y}{p_h} \tan \theta \quad (22.7.6.1b)$$

where A_o shall be determined by analysis; θ shall not be taken less than 30 degrees nor greater than 60 degrees; A_t is the area of one leg of a closed stirrup resisting torsion; A_ℓ is the area of longitudinal torsional reinforcement; and p_h is the perimeter of the centerline of the outermost closed stirrup.

COMMENTARY

nals at an angle θ , assuming the concrete resists no tension and the reinforcement yields. After torsional cracking develops, the torsional strength is provided mainly by closed stirrups, longitudinal reinforcement, and compression diagonals. The concrete outside these stirrups is relatively ineffective. For this reason A_o , the gross area enclosed by the shear flow path around the perimeter of the tube, is defined after cracking in terms of A_{oh} , the area enclosed by the centerline of the outermost closed transverse torsional reinforcement.

The shear flow q in the walls of the tube, discussed in R22.7, can be resolved into the shear forces V_1 to V_4 acting in the individual sides of the tube or space truss, as shown in Fig. R22.7.6.1a.

As shown in Figure R22.7.6.1b, on a given wall of the tube, the shear flow V_i is resisted by a diagonal compression component, $D_i = V_i / \sin \theta$, in the concrete. An axial tension force, $N_i = V_i (\cot \theta)$, is required in the longitudinal reinforcement to complete the resolution of V_i .

Because the shear flow due to torsion is constant at all points around the perimeter of the tube, the resultants of D_i and N_i act through the midheight of side i . As a result, half of N_i can be assumed to be resisted by each of the top and bottom chords as shown. Longitudinal reinforcement with a strength $A_\ell f_y$ is required to resist the sum of the N_i forces, $\sum N_i$, acting in all of the walls of the tube.

In the derivation of Eq. (22.7.6.1b), axial tension forces are summed along the sides of the area A_o . These sides form a perimeter length p_o approximately equal to the length of the line joining the centers of the bars in the corners of the tube. For ease in calculation, this has been replaced with the perimeter of the closed stirrups, p_h .




Fig. R22.7.6.1a—Space truss analogy.

CODE

COMMENTARY




Fig. R22.7.6.1b—Resolution of shear force V_i into diagonal compression force D_i and axial tension force N_i in one wall of tube.

22.7.6.1.1 In Eq. (22.7.6.1a) and (22.7.6.1b), it shall be permitted to take A_o equal to $0.85A_{oh}$.

R22.7.6.1.1 The area A_{oh} is shown in Fig. R22.7.6.1.1 for various cross sections. In I-, T-, L-shaped, or circular sections, A_{oh} is taken as that area enclosed by the outermost transverse reinforcement.®




Fig. R22.7.6.1.1—Definition of A_{oh} .

22.7.6.1.2 In Eq. (22.7.6.1a) and (22.7.6.1b), it shall be permitted to take θ equal to (a) or (b):

- (a) 45 degrees for nonprestressed members or members with $A_{ps}f_{se} < 0.4(A_{ps}f_{pu} + A_s f_y)$
- (b) 37.5 degrees for prestressed members with $A_{ps}f_{se} \geq 0.4(A_{ps}f_{pu} + A_s f_y)$

R22.7.6.1.2 The angle θ can be obtained by analysis (Hsu 1990) or may be taken equal to the values given in 22.7.6.1.2(a) or (b). The same value of θ is required to be used in both Eq. (22.7.6.1a) and (22.7.6.1b). With smaller values of θ , the amount of stirrups required by Eq. (22.7.6.1a) decreases. At the same time, the amount of longitudinal reinforcement required by Eq. (22.7.6.1b) increases.

22.7.7 Cross-sectional limits

22.7.7.1 Cross-sectional dimensions shall be selected such that (a) or (b) is satisfied:

- (a) For solid sections

R22.7.7 Cross-sectional limits

R22.7.7.1 The size of a cross section is limited for two reasons: first, to reduce excessive cracking, and second, to minimize the potential for crushing of the surface concrete due to inclined compressive stresses due to shear and torsion. In Eq. (22.7.7.1a) and (22.7.7.1b), the two terms on the left-

CODE

$$\sqrt{\left(\frac{V_u}{b_w d}\right)^2 + \left(\frac{T_u p_h}{1.7 A_{oh}^2}\right)^2} \leq \phi \left(\frac{V_c}{b_w d} + 8 \sqrt{f'_c} \right) \quad (22.7.7.1a)$$

(b) For hollow sections

$$\left(\frac{V_u}{b_w d} \right) + \left(\frac{T_u p_h}{1.7 A_{oh}^2} \right) \leq \phi \left(\frac{V_c}{b_w d} + 8 \sqrt{f'_c} \right) \quad (22.7.7.1b)$$

COMMENTARY

hand side are the shear stresses due to shear and torsion. The sum of these stresses may not exceed the stress causing shear cracking plus $8\sqrt{f'_c}$, similar to the limiting strength given in 22.5.1.2 for shear without torsion. The limit is expressed in terms of V_c to allow its use for nonprestressed or prestressed concrete. It was originally derived on the basis of crack control. It is not necessary to check against crushing of the web because crushing occurs at higher shear stresses.

In a hollow section, the shear stresses due to shear and torsion both occur in the walls of the box as shown in Fig. R22.7.7.1(a) and hence are directly additive at Point A as given in Eq. (22.7.7.1b). In a solid section, the shear stresses due to torsion act in the tubular outside section while the shear stresses due to V_u are spread across the width of the section, as shown in Fig. R22.7.7.1(b). For this reason, stresses are combined in Eq. (22.7.7.1a) using the square root of the sum of the squares rather than by direct addition.




Fig. R22.7.7.1—Addition of torsional and shear stresses.

22.7.7.1.1 For prestressed members, the value of d used in 22.7.7.1 need not be taken less than $0.8h$.

R22.7.7.1.1 Although the value of d may vary along the span of a prestressed beam, studies (MacGregor and Hanson 1969) have shown that, for prestressed concrete members, d need not be taken less than $0.8h$. The beams considered had some straight prestressed reinforcement or reinforcing bars at the bottom of the section and had stirrups that enclosed the longitudinal reinforcement.

CODE

22.7.7.1.2 For hollow sections where the wall thickness varies around the perimeter, Eq. (22.7.7.1b) shall be evaluated at the location where the term

$$\left(\frac{V_u}{b_w d}\right) + \left(\frac{T_u p_h}{1.7 A_{oh}^2}\right)$$

is a maximum.

22.7.7.2 For hollow sections where the wall thickness is less than A_{oh}/p_h , the term $(T_u p_h/1.7 A_{oh}^2)$ in Eq. (22.7.7.1b) shall be taken as $(T_u/1.7 A_{oh} t)$, where t is the thickness of the wall of the hollow section at the location where the stresses are being checked.

22.8—Bearing**22.8.1 General**

22.8.1.1 Section 22.8 shall apply to the calculation of bearing strength of concrete members.

22.8.1.2 Bearing strength provisions in 22.8 shall not apply to post-tensioned anchorage zones.

22.8.2 Required strength

22.8.2.1 Factored compressive force transferred through bearing shall be calculated in accordance with the factored load combinations defined in **Chapter 5** and analysis procedures defined in **Chapter 6**.

22.8.3 Design strength

22.8.3.1 Design bearing strength shall satisfy:

$$\phi B_n \geq B_u \quad (22.8.3.1)$$

for each applicable factored load combination.

22.8.3.2 Nominal bearing strength B_n shall be calculated in accordance with Table 22.8.3.2, where A_1 is the loaded area, and A_2 is the area of the lower base of the largest frustum of a pyramid, cone, or tapered wedge contained wholly within the support and having its upper base equal to the loaded area. The sides of the pyramid, cone, or tapered wedge shall be sloped 1 vertical to 2 horizontal.

COMMENTARY

R22.7.7.1.2 Generally, the maximum torsional stress will be on the wall where the torsional and shearing stresses are additive (Point A in Fig. R22.7.7.1(a)). If the top or bottom flanges are thinner than the vertical webs, it may be necessary to evaluate Eq. (22.7.7.1b) at Points B and C in Fig. R22.7.7.1(a). At these points, the stresses due to the shear are usually negligible

R22.8—Bearing**R22.8.1 General**

R22.8.1.2 Because post-tensioned anchorage zones are usually designed in accordance with 25.9, the bearing strength provisions in 22.8 are not applicable.

R22.8.3 Design strength

R22.8.3.2 The permissible bearing stress of $0.85f'_c$ is based on tests reported in **Hawkins (1968)**. Where the supporting area is wider than the loaded area on all sides, the surrounding concrete confines the bearing area, resulting in an increase in bearing strength. No minimum depth is given for the support, which will most likely be controlled by the punching shear requirements of 22.6.

A_1 is the loaded area but not greater than the bearing plate or bearing cross-sectional area.

Where the top of the support is sloped or stepped, advantage may still be taken of the condition that the supporting member is larger than the loaded area, provided the supporting member does not slope at too great an angle. Figure R22.8.3.2 illustrates the application of the frustum to find A_2 for a support under vertical load transfer.

CODE

Table 22.8.3.2—Nominal bearing strength

Geometry of bearing area	B_n	
Supporting surface is wider on all sides than the loaded area	Lesser of (a) and (b)	$\sqrt{A_2/A_1}(0.85f'_cA_1)$ (a)
		$2(0.85f'_cA_1)$ (b)
Other cases	$0.85f'_cA_l$ (c)	

COMMENTARY

Adequate bearing strength needs to be provided for cases where the compression force transfer is in a direction other than normal to the bearing surface. For such cases, this section applies to the normal component and the tangential component needs to be transferred by other methods, such as anchor bolts or shear lugs.

The frustum should not be confused with the path by which a load spreads out as it progresses downward through the support. Such a load path would have steeper sides. However, the frustum described has somewhat flat side slopes to ensure that there is concrete immediately surrounding the zone of high stress at the bearing.

Where tensile forces occur in the plane of bearing, it may be desirable to reduce the allowable bearing stress, provide confinement reinforcement, or both. Guidelines are provided in the *PCI Design Handbook* for precast and prestressed concrete (PCI MNL 120).



CODE

COMMENTARY




Fig. R22.8.3.2—Application of frustum to find A_2 in stepped or sloped supports.

22.9—Shear friction

22.9.1 General

22.9.1.1 This section shall apply where it is appropriate to consider shear transfer across any given plane, such as an existing or potential crack, an interface between dissimilar materials, or an interface between two concretes cast at different times.

R22.9—Shear friction

R22.9.1 General

R22.9.1.1 The purpose of this section is to provide a design method to address possible failure by shear sliding on a plane. Such conditions include a plane formed by a crack in monolithic concrete, an interface between concrete and steel, and an interface between concretes cast at different times (Birkeland and Birkeland 1966; Mattock and Hawkins 1972).

Although uncracked concrete is relatively strong in direct shear, there is always the possibility that a crack will form in an unfavorable location. The shear-friction concept

CODE

22.9.1.2 The required area of shear-friction reinforcement across the assumed shear plane, A_{vf} , shall be calculated in accordance with 22.9.4. Alternatively, it shall be permitted to use shear transfer design methods that result in prediction of strength in substantial agreement with results of comprehensive tests.

22.9.1.3 The value of f_y used to calculate V_n for shear friction shall not exceed the limit in 20.2.2.4.

22.9.1.4 Surface preparation of the shear plane assumed for design shall be specified in the construction documents.

22.9.2 Required strength

22.9.2.1 Factored forces across the assumed shear plane shall be calculated in accordance with the factored load combinations defined in Chapter 5 and analysis procedures defined in Chapter 6.

22.9.3 Design strength

22.9.3.1 Design shear strength across the assumed shear plane shall satisfy:

$$\phi V_n \geq V_u \quad (22.9.3.1)$$

COMMENTARY

assumes that such a crack will form, and that reinforcement is provided across the crack to resist relative displacement along it. When shear acts along a crack, one crack face slips relative to the other. If the crack faces are rough and irregular, this slip is accompanied by separation of the crack faces. At nominal strength, the separation is sufficient to stress, in tension, the reinforcement crossing the crack to its specified yield strength. The reinforcement in tension provides a clamping force $A_{vf}f_y$ across the crack faces. The applied shear is then resisted by friction between the crack faces, by resistance to the shearing off of protrusions on the crack faces, and by dowel action of the reinforcement crossing the crack. Successful application of this section depends on proper selection of the location of an assumed crack (PCI MNL 120; Birkeland and Birkeland 1966).

The requirements of 22.9 were developed based on monotonic testing and may be unconservative for interfaces that are part of the seismic-force-resisting system and experience strength degradation due to force and displacement reversals. Palieraki et al. (2022) provides design guidance for interfaces subject to cyclic loading that could cause sliding.

R22.9.1.2 The relationship between shear-transfer strength and the reinforcement crossing the shear plane can be expressed in various ways. Equations (22.9.4.2) and (22.9.4.3) are based on the shear-friction model and provide a conservative estimate of the shear-transfer strength.

Other relationships that provide a more accurate estimate of shear-transfer strength can be used under the requirements of this section. Examples of such procedures can be found in the *PCI Design Handbook* (PCI MNL 120), Mattock et al. (1976b), and Mattock (1974).

R22.9.1.4 For concrete cast against hardened concrete or structural steel, 26.5.6.1 requires the licensed design professional to specify the surface preparation in the construction documents.

CODE

for each applicable factored load combination.

22.9.4 Nominal shear strength

22.9.4.1 Value of V_n across the assumed shear plane shall be calculated in accordance with 22.9.4.2 or 22.9.4.3. V_n shall not exceed the value calculated in accordance with 22.9.4.4.

22.9.4.2 If shear-friction reinforcement is perpendicular to the shear plane, nominal shear strength across the assumed shear plane shall be calculated by:

$$V_n = \mu(A_{vf}f_y + N_u) \quad (22.9.4.2)$$

where μ is the coefficient of friction in accordance with Table 22.9.4.2, and N_u is the minimum factored compressive force acting concurrently with V_u . It shall be permitted to take N_u equal to zero even if compression across the interface is present.

Table 22.9.4.2—Coefficients of friction

Contact surface condition	Coefficient of friction $\mu^{(1)}$	
Concrete placed monolithically	1.4λ	(a)
Concrete placed against hardened concrete that is clean, free of laitance, and intentionally roughened to a trough-to-peak amplitude of approximately 1/4 in. ⁽²⁾	1.0λ	(b)
Concrete placed against hardened concrete that is clean, free of laitance, and not intentionally roughened	0.6	(c)
Concrete placed against as-rolled structural steel that is clean, free of paint, and with shear transferred across the contact surface by headed studs or by welded deformed bars or wires.	0.7λ	(d)

⁽¹⁾ $\lambda = 1.0$ for normalweight concrete. For lightweight concrete, λ is calculated as given in 19.2.4, but shall not exceed 0.85.

⁽²⁾Refer to 26.5.6.2(e) for compliance requirements for intentional roughening.

22.9.4.3 If shear-friction reinforcement is inclined to the shear plane and the shear force induces tension in the shear-friction reinforcement, nominal shear strength across the assumed shear plane shall be calculated by:

COMMENTARY**R22.9.4 Nominal shear strength**

R22.9.4.2 The required area of shear-friction reinforcement, A_{vf} , is calculated using:

$$A_{vf} = \frac{V_u - \phi\mu N_u}{\phi f_y \mu} \quad (R22.9.4.2)$$

Only compressive normal force is considered in Eq. (22.9.4.2); 22.9.4.5 requires reinforcement across the interface to resist net factored tension. Normal force U is factored in accordance with the load combinations of **Chapter 5**. All applicable load combinations should be considered to determine the most critical design condition, recognizing that non-permanent loads should only be considered if they add to V_u and load combinations that include a 0.9 factor on dead load should be considered.

The upper limit on shear strength that can be achieved using Eq. (22.9.4.2) is given in 22.9.4.4.

In the shear-friction method of calculation, it is assumed that all the shear resistance is due to the friction between the crack faces. It is therefore necessary to use artificially high values of the coefficient of friction in the shear-friction equations so that the calculated shear strength will be in reasonable agreement with test results.

For concrete cast against hardened concrete not roughened in accordance with 22.9.4.2, shear resistance is primarily due to dowel action of the reinforcement. Test results (**Mattock 1977**) indicate that the reduced value of $\mu = 0.6$ specified for this case is appropriate.

Beginning with the 2025 Code, the λ factor was removed from (c) of Table 22.9.4.2 based on research by Krc et al. (2016), which examined the use of λ for different concrete interface conditions. For contact surfaces not intentionally roughened, the lower strength of lightweight aggregate does not reduce shear transfer strength because the interfacial crack does not propagate through the aggregate.

For concrete placed against as-rolled structural steel, the shear-transfer reinforcement may be either reinforcing bars or headed studs. The design of shear connectors for composite action of concrete slabs and steel beams is not covered by these provisions. **ANSI/AISC 360** contains design provisions for these systems.

R22.9.4.3 Inclined shear-friction reinforcement is illustrated in Fig. R22.9.4.3a (Mattock 1974), where α is the acute angle between the bar and the shear plane. Equation (22.9.4.3) applies only when the shear force component parallel to the reinforcement produces tension in the rein-

CODE

$$V_n = A_{vf}f_y(\mu \sin \alpha + \cos \alpha) + \mu N_u \quad (22.9.4.3)$$

where α is the angle between shear-friction reinforcement and assumed shear plane, and μ and N_u are as defined in 22.9.4.2.

COMMENTARY

forcement and the force component parallel to the shear plane resists part of the shear, as shown in Fig. R22.9.4.3a.

If the shear-friction reinforcement is inclined such that the shear force component parallel to the reinforcement produces compression in the reinforcement, as shown in Fig. R22.9.4.3b, then shear friction does not apply ($V_n = 0$).




Fig. R22.9.4.3a—Tension in shear friction reinforcement.




Fig. R22.9.4.3b—Compression in reinforcement.

22.9.4.4 The value of V_n across the assumed shear plane shall not exceed the limits in Table 22.9.4.4. Where concretes of different strengths are cast against each other, the lesser value of f'_c shall be used in Table 22.9.4.4.

R22.9.4.4 Upper limits on shear friction strength are necessary, as Eq. (22.9.4.2) and (22.9.4.3) may become unconservative for some cases (Kahn and Mitchell 2002; Mattock 2001).

CODE

COMMENTARY

Table 22.9.4.4—Maximum V_n across the assumed shear plane

Condition	Maximum V_n	
Normalweight concrete placed monolithically or placed against hardened concrete that is clean, free of laitance, and intentionally roughened to a trough-to-peak amplitude of approximately 1/4 in. ^[1]	$0.2f_c'A_c$	(a)
	$(480 + 0.08f_c')A_c$	(b)
	$1600A_c$	(c)
Other cases	Lesser of (d) and (e)	
	$0.2f_c'A_c$	(d)
	$800A_c$	(e)

^[1]Refer to 26.5.6.2(e) for compliance requirements for intentional roughening.

22.9.4.5 Area of reinforcement required to resist a net factored tension across an assumed shear plane shall be added to the area of reinforcement required for shear friction crossing the assumed shear plane.

R22.9.4.5 Tension across the shear plane may be caused by restraint of deformations due to temperature change, creep, and shrinkage.

Where moment acts on a shear plane, the flexural compression and tension forces are in equilibrium and do not change the resultant compression A_vf_y acting across the shear plane or the shear-friction resistance. It is therefore not necessary to provide additional reinforcement to resist the flexural tension stresses, unless the required flexural tension reinforcement exceeds the amount of shear-transfer reinforcement provided in the flexural tension zone ([Mattock et al. 1975](#)).

22.9.5 Detailing for shear-friction reinforcement**R22.9.5 Detailing for shear-friction reinforcement**

22.9.5.1 Reinforcement crossing the shear plane to satisfy 22.9.4 shall develop f_y in tension on both sides of the shear plane.

R22.9.5.1 If no moment acts across the shear plane, reinforcement should be uniformly distributed along the shear plane to minimize crack widths. If a moment acts across the shear plane, the shear-transfer reinforcement should be placed primarily in the flexural tension zone.

Anchorage may be developed by bond, by a mechanical device, or by threaded dowels and screw inserts. Space limitations often require the use of mechanical anchorage devices. For anchorage of headed studs in concrete, refer to *PCI Design Handbook* for precast and prestressed concrete ([PCI MNL 120](#)).

The shear-friction reinforcement anchorage should engage the primary reinforcement; otherwise, a potential crack may pass between the shear-friction reinforcement and the body of the concrete. This requirement applies particularly to welded headed studs used with steel inserts.

22.9.5.2 It shall be permitted to consider inverted U-bars extending into composite topping slabs sufficient to develop f_y in tension at the interface if specified details satisfy (a) through (c):


- (a) U-bar size does not exceed No. 7.
- (b) Cross-leg of each U-bar extends at least $5d_b$ above the interface, where d_b is the diameter of the U-bar leg.
- (c) Upper corners of each U-bar enclose a bar or strand.

R22.9.5.2 Detailing requirements of this provision are based on tests by [Mattock \(1987\)](#) and [Waweru et al. \(2018\)](#) and are illustrated in Fig. R22.9.5.2. Although inverted U-bars are typically used, this provision is intended to also apply to rectangular ties. The top leg of the U-bar should extend as close to the top surface as cover requirements permit.


CODE

(d) Spacing between U-bar legs in both directions is at least $8d_b$.

(e) Below the interface, vertical legs of the U-bars develop f_y in tension in accordance with 25.4.2.

COMMENTARY

a) Transverse Section



b) Longitudinal Section

Fig. R22.9.5.2—Details for development of U-bars across a shear-friction interface.

Notes



CHAPTER 23—STRUT-AND-TIE METHOD

CODE

COMMENTARY

23.1—Scope

R23.1—Scope

A discontinuity in stress distribution occurs at a change in the geometry of a structural element or at a concentrated load or reaction. St. Venant's principle indicates that the stresses due to axial force and bending approach a linear distribution at a distance approximately equal to the overall depth of the member, h , away from the discontinuity. For this reason, discontinuity regions are assumed to extend a distance h from the section where the load or change in geometry occurs.

Shaded regions in Fig. R23.1(a) and (b) show typical D-regions (Schlaich et al. 1987). The plane sections assumption of 22.2.1.2 is not applicable in such regions. In general, any portion of a member outside a D-region is a B-region where the plane sections assumptions of flexural theory can be applied. The strut-and-tie design method, as described in this chapter, is based on the assumption that D-regions can be analyzed and designed using hypothetical pin-jointed trusses consisting of struts and ties connected at nodes.

The idealized truss specified in 23.2.1, which forms the basis of the strut-and-tie method, is not intended to apply to structural systems configured as actual trusses because secondary effects, such as moments, are not included in the model.

CODE

23.2—General

23.2.1 Strut-and-tie models shall consist of struts and ties connected at nodes to form an idealized truss in two or three dimensions.

COMMENTARY

R23.2—General

R23.2.1 For the idealized truss, struts are the compression members, ties are the tension members, and nodes are the joints. Uniformly distributed loads are usually idealized as a series of concentrated loads applied at nodes. Similarly, distributed reinforcement is usually modeled as discrete ties representing groups of individual bars or wires. Additional information is provided in “Strut-and-Tie Method Guidelines for ACI 318-19—Guide” (ACI PRC-445.2-21). Design examples for the strut-and-tie method are given in ACI SP-208 (Reineck 2002) and ACI SP-273 (Reineck and Novak 2010). The process of designing by the strut-and-tie method to support imposed forces acting on and within a D-region is referred to as the strut-and-tie method, and it includes the following four steps:

- (1) Define and isolate each D-region.
- (2) Calculate resultant forces on each D-region boundary.
- (3) Select the model and calculate the forces in the struts and ties to transfer resultant forces across the D-region. The axes of the struts and ties are chosen to approximately coincide with the axes of the compression and tension fields, respectively.
- (4) Design the struts, ties, and nodal zones so that they have sufficient strength. Widths of struts and nodal zones are determined considering the effective concrete strengths defined in 23.4.3 and 23.9.2. Reinforcement is provided for the ties considering the steel strengths defined in 23.7.2. Reinforcement should be anchored in or beyond the nodal zones.

Components of a strut-and-tie model of a single-span deep beam loaded with two concentrated loads are identified in Fig. R23.2.1. Cross-sectional dimensions of a strut or tie are designated as thickness and width, and both directions are perpendicular to the axis of the strut or tie. Thickness is perpendicular to the plane, and width is in the plane of the strut-and-tie model. A tie consists of nonprestressed or prestressed reinforcement plus a portion of the surrounding concrete that is concentric with the axis of the tie.




Fig. R23.2.1—Description of strut-and-tie model.

CODE

23.2.2 Geometry of the idealized truss shall be consistent with the dimensions of the struts, ties, nodal zones, bearing areas, and supports.

COMMENTARY

R23.2.2 The struts, ties, and nodal zones making up the strut-and-tie model all have finite widths, typically in the plane of the model, and thicknesses, typically the out-of-plane dimension of the structure, which should be taken into account in selecting dimensions of the truss. Figures R23.2.2(a) and (b) show a node and the corresponding nodal zone. The vertical and horizontal forces equilibrate the forces in the inclined strut.

If more than three forces act on a nodal zone in a two-dimensional strut-and-tie model, as shown in Fig. R23.2.2(a), it is suggested to resolve some of the forces to form three forces that intersect at a single point. The strut forces acting on Faces A-E and C-E in Fig. R23.2.2(a) can be replaced with one force acting on Face A-C as shown in Fig. R23.2.2(b). This force passes through the node at D.

If the width of the support, or a loaded region, in the direction perpendicular to the member is less than the width of the member, transverse reinforcement may be required to restrain splitting in the plane of the node. This can be modeled using a transverse strut-and-tie model.




Fig. R23.2.2—Resolution of forces on a nodal zone.

23.2.3 Strut-and-tie models shall be capable of transferring all factored loads to supports or adjacent B-regions.

23.2.4 The internal forces in strut-and-tie models shall be in equilibrium with the applied loads and reactions.

23.2.5 Ties shall be permitted to cross struts and other ties.

23.2.6 Struts shall intersect or overlap only at nodes.

R23.2.3 Analysis results from the strut-and-tie method represent lower-bound strength limit states. Section 23.5.1 requires distributed reinforcement in D-regions designed by this chapter unless struts are laterally restrained. Distributed reinforcement in D-regions will improve serviceability performance. In addition, crack widths in a tie can be controlled using 24.3.2, assuming the tie is encased in a prism of concrete corresponding to the area of the tie from R23.8.1.

R23.2.6 A hydrostatic nodal zone, by definition, has equal stresses on the loaded faces; these faces are perpendicular to the axes of the struts and ties that act on the node. This type of node is considered a hydrostatic nodal zone because in-plane stresses are the same in all directions. Strictly speaking, this terminology is incorrect because the in-plane stresses are not equal to the out-of-plane stresses.

CODE

COMMENTARY

Figure R23.2.6a(i) shows a C-C-C nodal zone. If stresses on the face of the nodal zone are the same in all three struts, the ratios of lengths of sides of the nodal zone, $w_{n1}:w_{n2}:w_{n3}$, are in the same proportions as the three forces, $C_1:C_2:C_3$.

A C-C-T nodal zone can be represented as a hydrostatic nodal zone if the tie is assumed to extend through the node and is anchored by a plate on the far side of the node, as shown in Fig. R23.2.6a(ii), provided that the size of the plate results in bearing stresses that are equal to the stresses in the struts. The bearing plate on the left side of Fig. R23.2.6a(ii) is used to represent an actual tie anchorage. The tie force can be anchored by a plate or through embedment of straight bars (Fig. R23.2.6a(iii)), headed bars, or hooked bars. For non-hydrostatic nodes, the face with the highest stress will control the dimensions of the node.

The lightly shaded area in Fig. R23.2.6b is an extended nodal zone. An extended nodal zone is that portion of a member bounded by the intersection of the effective strut width w_s and the effective tie width w_t .

For equilibrium, at least three forces should act on each node in a strut-and-tie model, as shown in Fig. R23.2.6c. Nodes are classified according to the signs of these forces. A C-C-C node resists three compressive forces, a C-C-T node resists two compressive forces and one tensile force, and a C-T-T node resists one compressive force and two tensile forces.




Fig. R23.2.6a—Hydrostatic nodes.

CODE

COMMENTARY




Fig. R23.2.6b—Extended nodal zone showing the effect of the distribution of the force.




Fig. R23.2.6c—Classification of nodes.

CODE

23.2.7 The angle between the axes of any strut and any tie entering a single node shall be at least 25 degrees.

COMMENTARY

R23.2.7 The angle between the axes of a strut and a tie acting on a node should be large enough to mitigate cracking and to avoid incompatibilities due to shortening of the strut and lengthening of the tie occurring in approximately the same direction. This limitation on the angle prevents modeling shear spans in slender beams using struts inclined at less than 25 degrees from the longitudinal reinforcement (Muttoni et al. 1997).

In some cases, strut-and-tie models can be adjusted to satisfy this requirement without excluding transverse reinforcement close to concentrated loads or reactions as illustrated in Fig. R23.2.7.




Fig. R23.2.7—Strut and tie model of dapped connection illustrating adjustment to comply with 23.2.7.

23.2.8 The effects of prestressing shall be included in the strut-and-tie model as external loads with load factors in accordance with 5.3.16. For pretensioned members, it shall be permitted to assume that the prestress force is applied at the end of the strand transfer length.

R23.2.8 The flow of forces in the strut-and-tie model is unrealistic if prestressing effects are not considered as external loads. Including prestressing effects as external loads is required to identify regions where the effects of other external loads exceed the precompression force and vice versa. Prestressing effects are simulated by concentrated loads at the anchorages and transverse loads equivalent to the effects of tendon deviation or curvature. Provision 5.3.16 requires different load factors depending on the effects of prestressing on the strut-and-tie model. Applying the prestressing force at the end of the transfer length may require a deformed bar tie where the prestress force is being transferred.

CODE

COMMENTARY

23.2.9 Deep beams designed using the strut-and-tie method shall satisfy 9.9.2.1, 9.9.3.1, and 9.9.4.

23.2.10 Walls designed using the strut-and-tie method shall satisfy 11.6, 11.7.2, and 11.7.3.

23.2.11 Brackets and corbels with shear span-to-depth ratio $a_v/d < 2.0$ designed using the strut-and-tie method shall satisfy 16.5.2, 16.5.6, and Eq. (23.2.11).

$$A_{sc} \geq 0.04(f'_c/f'_y)(b_w d) \quad (23.2.11)$$

23.2.12 The shear-friction requirements of 22.9 shall apply where it is appropriate to consider shear transfer across any given plane, such as an existing or potential crack, an interface between dissimilar materials, or an interface between two concretes cast at different times.

23.2.13 Members designed using strut-and-tie models that are part of seismic-force-resisting system shall meet the additional requirements of 23.11, if applicable.

R23.2.12 A construction joint between a corbel and face of a column is an example of an interface where shear-friction requirements of 22.9 apply.

23.3—Design strength

23.3.1 For each applicable factored load combination, design strength of each strut, tie, and nodal zone in a strut-and-tie model shall satisfy $\phi S_n \geq U$, including (a) through (c):

- (a) Struts: $\phi F_{ns} \geq F_{us}$
- (b) Ties: $\phi F_{nt} \geq F_{ut}$
- (c) Nodal zones: $\phi F_{nn} \geq F_{un}$

23.3.2 ϕ shall be in accordance with 21.2.

R23.3—Design strength

R23.3.1 Factored loads are applied to the strut-and-tie model, and forces in all struts, ties, and nodal zones are calculated. If several load combinations exist, each should be investigated separately. For a given strut, tie, or nodal zone, F_{us} , F_{ut} , or F_{un} is the largest force in that element for all load combinations considered.

23.4—Strength of struts

23.4.1 The nominal compressive strength of a strut, F_{ns} , shall be calculated by (a) or (b):

- (a) Strut without longitudinal reinforcement

$$F_{ns} = f_{ce} A_{cs} \quad (23.4.1a)$$

- (b) Strut with longitudinal reinforcement

$$F_{ns} = f_{ce} A_{cs} + A_s f'_s \quad (23.4.1b)$$

where F_{ns} shall be evaluated at each end of the strut and taken as the lesser value; A_{cs} is the cross-sectional area at the end of the strut under consideration; f_{ce} is given in 23.4.3; A_s is the area of compression reinforcement along the length of the strut; and f'_s is the stress in the compression reinforcement at the nominal axial strength of the strut. It shall be permitted to take f'_s equal to f_y for Grade 40 or 60 reinforcement.

R23.4—Strength of struts

R23.4.1 The width of strut, w_s , used to calculate A_{cs} is the dimension perpendicular to the axis of the strut at the ends of the strut. This strut width is illustrated in Fig. R23.2.6a(i) and Fig. R23.2.6b. If two-dimensional strut-and-tie models are appropriate, such as for deep beams, the thickness of the struts may be taken as the width of the member except at bearing supports where the thickness of the strut must equal the least thickness of the member or supporting element.

The contribution of reinforcement to the strength of the strut is given by the last term in Eq. (23.4.1b). The stress f'_s in the reinforcement in a strut at nominal strength can be obtained from the strain in the strut when the strut crushes. Detailing requirements in 23.6 must be met including confinement reinforcement to prevent buckling of the strut reinforcement.

CODE

23.4.2 Effective compressive strength of concrete in a strut, f_{ce} , shall be calculated in accordance with 23.4.3.

23.4.3 Effective compressive strength of concrete in a strut, f_{ce} , shall be calculated by:

$$f_{ce} = 0.85\beta_c\beta_sf'_c \quad (23.4.3)$$

where β_s is in accordance with Table 23.4.3(a) and β_c is in accordance with Table 23.4.3(b).

Table 23.4.3(a)—Strut coefficient β_s

Strut location	Strut type	Reinforcement	Member dimensions	β_s	
Tension members or tension zones of members	Any	Any	Any	0.4	(a)
Beam-column joints	Interior	Satisfying applicable strength and detailing provisions of Chapters 15 and 18		0.75	(b)
All other cases	Boundary	Any	Any	1.0	(c)
	Interior	Satisfying (a) or (b) of Table 23.5.1	Any	0.75	(d)
		Not satisfying (a) or (b) of Table 23.5.1	Satisfying 23.4.4	0.75	(e)
			Not satisfying 23.4.4	0.4	(f)

Table 23.4.3(b)—Strut and node confinement modification factor β_c

Location	β_c	
• End of a strut connected to a node that includes a bearing surface • Node that includes a bearing surface	Lesser of	$\sqrt{A_2/A_1}$, where A_1 is defined by the bearing surface
		2.0
Other cases	1.0	

COMMENTARY

R23.4.2 In design, struts are usually idealized as prismatic compression members. If the area of a strut differs at its two ends, due either to different nodal zone strengths at the two ends or to different bearing lengths, the strut is idealized as a uniformly tapered compression member.

R23.4.3 The strength coefficient $0.85f'_c$ in Eq. (23.4.3) represents the effective concrete strength in compression.

The value of β_s in (a) of Table 23.4.3(a) applies, for example, to a transverse model of a ledger beam used to proportion hanger and ledge reinforcement, where longitudinal tension in the flange reduces the strength of the transverse struts. The low value of β_s reflects that these struts need to transfer compression in a zone where tensile stresses act perpendicular to the plane of the strut-and-tie model.

The value of β_s in (b) of Table 23.4.3(a) reflects the requirements for reinforcement or confinement for beam-column joints in Chapters 15 and 18.

The value of β_s in (c) of Table 23.4.3(a) applies to a boundary strut and results in a stress state that is comparable to the rectangular stress block in the compression zone of a beam or column. Boundary struts are not subject to transverse tension and therefore have a higher effective strength, f_{ce} , than interior struts (Fig. R23.2.1).

The value of β_s in (d) of Table 23.4.3(a) reflects the beneficial effect of distributed reinforcement.

The value of β_s in (e) of Table 23.4.3(a) applies to interior struts in regions with sufficient diagonal tension strength to satisfy Eq. (23.4.4).

The value of β_s in (f) of Table 23.4.3(a) is reduced to preclude diagonal tension failure in regions without transverse reinforcement that do not meet or are not evaluated under 23.4.4. Evaluation of test results from the ACI shear database for members without transverse reinforcement indicates that diagonal tension failures are precluded if struts are proportioned based on β_s of 0.4 (Reineck and Todisco 2014). The ACI shear database includes test results for specimens with an average d of 15 in. and not exceeding 38 in.; therefore, size effect would not be expected to significantly reduce the strength of members of this size. Because size effect may be significant for deeper members without transverse reinforcement, evaluation in accordance with Eq. (23.4.4) is considered appropriate.

The influence of concrete confinement on the effective compressive strength of a strut or node is taken into account by β_c . The bearing surface can be a bearing plate or the area from a well-defined compressive load from another member, such as a column. It is the same confining effect as used for bearing areas in 22.8.3. The increase in compressive strength associated with confinement provided by surrounding concrete for a strut-and-tie model is described by Tuchscherer et al. (2010) and Breen et al. (1994).

CODE

23.4.4 If use of β_s of 0.75 is based on line (e) of Table 23.4.3(a), member dimensions shall be selected to satisfy Eq. (23.4.4), where λ_s is defined in 23.4.4.1.

$$V_u \leq \phi 5 \tan(\theta) \lambda \lambda_s \sqrt{f'_c} b_w d \quad (23.4.4)$$

23.4.4.1 The size effect modification factor, λ_s , shall be determined by (a) or (b), as applicable:

- (a) If distributed reinforcement is provided in accordance with 23.5, λ_s shall be taken as 1.0.
- (b) If distributed reinforcement is not provided in accordance with 23.5, λ_s shall be taken in accordance with Eq. (23.4.4.1).

$$\lambda_s = \sqrt{\frac{2}{1 + \frac{d}{10}}} \leq 1 \quad (23.4.4.1)$$

23.5—Minimum distributed reinforcement

23.5.1 In D-regions designed using the strut-and-tie method, minimum distributed reinforcement shall be in accordance with Table 23.5.1.

COMMENTARY

R23.4.4 Equation (23.4.4) is intended to preclude diagonal tension failure. In discontinuity regions, diagonal tension strength increases as the strut angle increases. For very steeply inclined struts, V_u can exceed $\phi 10 \lambda \lambda_s \sqrt{f'_c} b_w d$.

R23.5—Minimum distributed reinforcement

The strut-and-tie method is derived from the lower-bound theorem of plasticity; therefore, a member designed using this method requires sufficient reinforcement to promote redistribution of internal forces in the cracked state (Marti 1985). In addition to allowing force redistribution, distributed reinforcement controls cracking at service loads and promotes ductile behavior (Smith and Vantsiotis 1982; Rogowsky and MacGregor 1986; Tan et al. 1977).

Interior struts are typically oriented parallel to compression fields and are therefore oriented perpendicular to diagonal tension fields. Tensile stresses across the strut may also develop where compressive stress at the node spreads out along the length of a strut. Minimum distributed reinforcement helps control cracking from these tensile stresses.

The distributed reinforcement ratio required by 23.5.1 is the total on both faces plus any interior layers placed in wide members. Figure R23.5.1 illustrates unidirectional distributed reinforcement crossing interior struts at angle α .

Although minimum distributed reinforcement is not required where interior struts are laterally restrained, distributed reinforcement may be beneficial in large discontinuity regions. A continuous corbel supporting a slab is an example of a discontinuity region that includes struts that are laterally restrained in accordance with 23.5.3(a). Pile caps and beam ledges supporting concentrated loads are examples of discontinuity regions that include struts that are laterally restrained in accordance with 23.5.3(b). Side faces of the strut in 23.5.3(b) are the faces parallel to the plane of the model. For pile caps evaluated using three-dimensional strut-and-tie models, the plane of the model in 23.5.3 is defined by the strut in question and the pile to which it connects.


R23.5.1 More restrictive requirements than 23.5.1 and 23.5.2 may be applicable as defined in the respective member chapters. Refer to 23.2.9 to 23.2.13.

CODE

Table 23.5.1—Minimum distributed reinforcement

Lateral restraint of strut	Reinforcement configuration	Minimum distributed reinforcement ratio	
Not restrained	Orthogonal grid	0.0025 in each direction	(a)
	Reinforcement in one direction crossing strut at angle α	$\frac{0.0025}{\sin^2 \alpha_1}$	(b)
Restrained in accordance with 23.5.3	Distributed reinforcement not required		(c)

COMMENTARY



Distributed reinforcement crossing interior struts. Note that α_1 is different for the two struts above; the minimum distributed reinforcement ratio is controlled by the smaller angle α_1 .

Fig. R23.5.1—Distributed reinforcement crossing interior struts.

23.5.2 Distributed reinforcement required by 23.5.1 shall be determined based on the entire cross-sectional area of the member and shall satisfy (a) through (f) :

- (a) Reinforcement shall be developed beyond the extent of the strut in accordance with 25.4.
- (b) Reinforcement satisfying the “Not restrained” strut conditions in row (a) or (b) of Table 23.5.1 shall have spacing s_{td} and s_{tds} measured in the plane defined by the strut-and-tie model, not exceeding 12 in.
- (c) Angle α_1 shall not be less than 40 degrees.
- (d) For members with a cross-sectional dimension greater than 10 in. measured perpendicular to the plane defined by the strut-and-tie model, distributed reinforcement required by 23.5.1 shall be placed in at least two planes with one near each side face.
- (e) Where at least two planes of reinforcement are required in accordance with 23.5.2(d), the spacing between adjacent reinforcement planes s_{wd} shall not exceed 24 in.
- (f) Where concrete extends beyond the node by more than 12 in., reinforcement shall be provided to connect the extension to the concrete within the strut-and-tie model.


R23.5.2 Because the primary purpose of the distributed reinforcement is to control cracking, the quantity of distributed reinforcement is evaluated based on the entire cross section, even for cases where the node geometry or strut dimension is narrower than the overall member thickness. Spacing limits are consistent with the maximum spacing of shear reinforcement legs in 9.7.6.2.2. Distributed reinforcement in a planar member satisfying row (a) of Table 23.5.1 is similar to the configuration illustrated in R9.9.4.3.

Concrete extending beyond the volume defined by the strut-and-tie model will be subjected to three dimensional stresses arising from deformation compatibility, including the influence of axial and transverse strain distributions that differ from the uniform axial strain conditions in idealized struts. Reinforcement to control cracking and provide integrity for the concrete in these regions should be provided in multiple directions. Figure R23.5.2 illustrates the requirements in accordance with 23.5.2(d) through (f) for a wide member designed using a strut-and-tie model width narrower than the member width.


To the extent practicable, multiple planes of reinforcement, whether parallel with the member or strut depth or width, should be placed symmetrically with respect to the center plane of the member.

CODE

COMMENTARY



(a) Plan view



(b) Section A-A

Fig. R23.5.2—Reinforcement in a wide member designed with a narrow strut-and-tie model

CODE

23.5.3 Struts are considered laterally restrained if they are restrained perpendicular to the plane of the strut-and-tie model in accordance with (a), (b), or (c):

- (a) The discontinuity region is continuous perpendicular to the plane of the strut-and-tie model.
- (b) The concrete restraining the strut extends beyond each side face of the strut a distance not less than half the width of the strut.
- (c) The strut is in a joint that is restrained in accordance with **15.5.2.5**.

23.6—Strut reinforcement detailing

23.6.1 Compression reinforcement in struts shall be parallel to the axis of the strut and enclosed along the length of the strut by closed ties in accordance with 23.6.3 or by spirals in accordance with 23.6.4.

23.6.2 Compression reinforcement in struts shall develop f'_s in compression at the face of the nodal zone, where f'_s is calculated in accordance with 23.4.1.

23.6.3 Closed ties enclosing compression reinforcement in struts shall satisfy **25.7.2** and this section.

23.6.3.1 Spacing of closed ties, s , along the length of the strut shall not exceed the smallest of (a) through (c):

- (a) Smallest dimension of cross section of strut
- (b) $48d_b$ of bar or wire used for closed tie reinforcement
- (c) $16d_b$ of compression reinforcement

23.6.3.2 The first closed tie shall be located not more than $0.5s$ from the face of the nodal zone at each end of a strut.

23.6.3.3 Closed ties shall be arranged such that every corner and alternate longitudinal bar shall have lateral support provided by crossties or the corner of a tie with an included angle of not more than 135 degrees and no longitudinal bar shall be farther than 6 in. clear on each side along the tie from such a laterally supported bar.

23.6.4 Spirals enclosing compression reinforcement in struts shall satisfy **25.7.3**.

23.7—Strength of ties

23.7.1 Tie reinforcement shall be nonprestressed or prestressed.

23.7.2 The nominal tensile strength of a tie, F_{nt} , shall be calculated by:

COMMENTARY**R23.6—Strut reinforcement detailing**

R23.6.1 Refer to R23.4.1.

R23.6.3.3 Refer to **R25.7.2.3**.

R23.7—Strength of ties

R23.7.2 The tie strength in 23.7.2 is based on including any effects of prestressing as external loads in accordance

CODE

$$F_{nt} = A_{is}f_y + A_{tp}\Delta f_p \quad (23.7.2)$$

where A_{tp} is zero for nonprestressed members.

23.7.2.1 In Eq. (23.7.2), it shall be permitted to take Δf_p equal to 60,000 psi for bonded prestressed reinforcement and 10,000 psi for unbonded prestressed reinforcement. Higher values of Δf_p shall be permitted if justified by analysis, but Δf_p shall not be taken greater than $(f_{py} - f_{se})$.

23.8—Tie reinforcement detailing

23.8.1 The centroidal axis of the tie reinforcement shall coincide with the axis of the tie assumed in the strut-and-tie model.

23.8.2 If located within the tie, distributed reinforcement in 23.5 may also be considered as tie reinforcement.

23.8.3 The transverse spacing of tie reinforcement across the thickness of a node shall not exceed the lesser of (a) or (b):

- (a) 24 in.
- (b) The maximum reinforcement spacing defined in the respective member chapters.

23.8.4 Tie reinforcement shall be anchored by mechanical devices, post-tensioning anchorage devices, standard hooks, or straight bar development in accordance with 23.8.5,

COMMENTARY

with 23.2.8. The total strength of a prestressed tie is $A_{tp}(f_{se} + \Delta f_p)$.

R23.8—Tie reinforcement detailing

R23.8.1 The effective tie height assumed in design, w_t , can vary between the following limits, depending on the distribution of the tie reinforcement:

- (a) If bars in the tie are in one layer and spaced transversely through the thickness of the member, the effective tie height w_t can be taken as the diameter of the bars in the tie plus twice the cover to the surface of the bars, as shown in Fig. R23.2.6b(i).
- (b) A practical upper limit of the tie height can be taken as the corresponding dimension of a hydrostatic nodal zone, calculated as $w_{t,max} = F_{nt}/(f_{ce}b_s)$, where f_{ce} is calculated for the nodal zone in accordance with 23.9.2.

If the tie height exceeds the value from (a), the tie reinforcement should be distributed approximately uniformly over the tie height, as shown in Fig. R23.2.6b(ii), and over the member thickness. Spacing of tie reinforcement in the thickness direction should satisfy 23.8.3.

R23.8.3 If geometric or other constraints prevent the inclusion of transverse tie reinforcement spaced in accordance with 23.8.3 across the full member width, multiple strut-and-tie models each occupying a portion of the overall member width may be used. In this case, each model should be aligned with the tie reinforcement locations. The individual strut-and-tie models should also be connected together with an adequate load path to allow load sharing and deformation compatibility. It is good practice to include not less than the minimum distributed reinforcement in 23.5 in the regions between the individual models. Refer to **ACI PRC-445.2**.

More restrictive requirements than 23.8.3 may be applicable as defined in the respective member chapters. Refer to 23.2.9 to 23.2.13.

R23.8.4 Anchorage of ties often requires special attention in nodal zones of corbels or in nodal zones adjacent to exterior supports of deep beams. The reinforcement in a tie

CODE

except for ties extending from curved-bar nodes designed in accordance with 23.10.

COMMENTARY

should be anchored before it exits the extended nodal zone at the point defined by the intersection of the centroid of the bars in the tie and the extensions of the outlines of either the strut or bearing area. This length is ℓ_{anc} . In Fig. R23.2.6b, this occurs where the outline of the extended nodal zone is crossed by the centroid of the reinforcement in the tie. Some of the anchorage may be achieved by extending the reinforcement through the nodal zone, as shown in Fig. R23.2.6a(iii) and R23.2.6b, and developing it beyond the nodal zone. If the tie is anchored using 90-degree hooks, the hooks should be confined within reinforcement to avoid cracking along the outside of the hooks in the support region.

Figure R23.8.4 shows two ties anchored at a nodal zone. Development is required where the centroid of the tie crosses the outline of the extended nodal zone.

The development length of the tie reinforcement can be reduced through hooks, headed bars, mechanical devices, additional confinement, or by splicing it with layers of smaller bars.




Fig. R23.8.4—Extended nodal zone anchoring two ties.

23.8.5 Tie force shall be developed in each direction at the point where the centroid of the reinforcement in the tie leaves the extended nodal zone.

23.9—Strength of nodal zones

23.9.1 The nominal compressive strength of a nodal zone, F_{nn} , shall be calculated by:

$$F_{nn} = f_{ce} A_{nz} \quad (23.9.1)$$

where f_{ce} is defined in 23.9.2 or 23.9.3 and A_{nz} is given in 23.9.4 or 23.9.5.

23.9.2 The effective compressive strength of concrete at a face of a nodal zone, f_{ces} , shall be calculated by:

R23.9—Strength of nodal zones

R23.9.2 Nodes in two-dimensional models can be classified as shown in Fig. R23.2.6c. The effective compressive

CODE

$$f_{ce} = 0.85\beta_n\beta_c f'_c \quad (23.9.2)$$

where β_n shall be in accordance with Table 23.9.2 and β_c is in accordance with Table 23.4.3(b).

Table 23.9.2—Nodal zone coefficient β_n

Configuration of nodal zone	β_n	
Nodal zone bounded by struts, bearing areas, or both	1.0	(a)
Nodal zone anchoring one tie	0.80	(b)
Nodal zone anchoring two or more ties	0.60	(c)

23.9.3 If confining reinforcement is provided within the nodal zone and its effect is documented by tests and analyses, it shall be permitted to use an increased value of f_{ce} when calculating F_{mn} .

23.9.4 The area of each face of a nodal zone, A_{nz} , shall be taken as the smaller of (a) and (b):

- (a) Area of the face of the nodal zone perpendicular to the line of action of F_{us}
- (b) Area of a section through the nodal zone perpendicular to the line of action of the resultant force on the section

23.9.5 In a three-dimensional strut-and-tie model, the area of each face of a nodal zone shall be at least that given in 23.9.4, and the shape of each face of the nodal zone shall be similar to the shape of the projection of the end of the strut onto the corresponding face of the nodal zone.

23.10—Curved-bar nodes

23.10.1 Curved-bar nodes shall be designed and detailed in accordance with this section.

23.10.2 If specified clear cover to the side face normal to plane of bend is $1.5d_b$ or greater, the bend radius r_b shall be in accordance with (a) or (b), but shall not be less than half the minimum bend diameter specified in 25.3.

- (a) Curved bar nodes with bends less than 180 degrees:

$$r_b \geq \frac{2A_{ts}f_y}{b_s f'_c} \quad (23.10.2a)$$

- (b) Ties anchored by 180-degree bends:

COMMENTARY

strength of the nodal zone is given by Eq. (23.9.2) where the value for β_n is given in Table 23.9.2.

Lower β_n values reflect the increasing degree of disruption of the nodal zones due to incompatibility of tensile strains in the ties and compressive strains in the struts. The stress on any face of the nodal zone or on any section through the nodal zone should not exceed the value given by Eq. (23.9.2).

As described in R23.4.3, β_c accounts for the effect of concrete confinement on the effective compressive strength of a node containing a bearing surface. β_c is the same for the node as for the node-strut interface.

R23.9.4 If stresses in all struts meeting at a node are equal, a hydrostatic nodal zone can be used. Faces of such a nodal zone are perpendicular to the axes of the struts, and widths of faces of the nodal zone are proportional to forces in the struts.

Stresses on nodal faces that are perpendicular to the axes of struts and ties are principal stresses, and 23.9.4(a) is used. If, as shown in Fig. R23.2.6b(ii), the face of a nodal zone is not perpendicular to the axis of the strut, there will be both shear stresses and normal stresses on the face of the nodal zone. Typically, these stresses are replaced by the normal (principal compressive) stress acting on the cross-sectional area, A_{nz} , of the strut, taken perpendicular to the axis of the strut as given in 23.9.4(a).

R23.10—Curved-bar nodes

R23.10.1 A curved-bar node is formed by the bend region of a continuous reinforcing bar (or bars) where two ties extending from the bend region are intersected by a strut or the resultant of two or more struts (Fig. R23.10.5), or where a single tie is anchored by a 180-degree bend (Fig. R23.10.2).

R23.10.2 Equations (23.10.2a) and (23.10.2b) are intended to avoid f_{ce} exceeding the limit for C-T-T nodes given by 23.9.2 (Klein 2008). In Eq. (23.10.2a), b_s is the width of the strut transverse to the plane of the strut-and-tie model. Equation (23.10.2a) applies whether tie forces at the node are equal or different; where tie forces are different, the larger tie force is considered in determining A_{ts} .

Ties anchored by 180-degree bends can be used at C-C-T or C-T-T nodes. Parallel straight legs of the bar(s) that extend into the member form a single tie, where A_{ts} is taken as the

CODE

$$r_b \geq \frac{A_{ts}f_y}{w_t f_c'} \quad (23.10.2b)$$

COMMENTARY

total area of reinforcement extending from both ends of the bend(s). Equation (23.10.2b) is intended to ensure that f_{ce} does not exceed the limit for C-T-T nodes given by 23.9.2. Width w_t is the effective tie width as illustrated in Fig. R23.10.2.




Fig. R23.10.2—C-C-T node using ties anchored by 180-degree bends.

23.10.3 If specified clear cover to the side face normal to plane of bend is less than $1.5d_b$, r_b required by 23.10.2 shall be multiplied by the ratio $1.5d_b/c_c$, where c_c is the specified clear cover to the side face.

R23.10.3 Larger bar bend radii at curved-bar nodes are required to reduce the likelihood of side splitting where concrete cover perpendicular to the plane of the bend is limited. The multiplier on d_b/c_c was changed from 2 to 1.5 for the 2025 Code based on testing of knee joints with a range of clear cover ([Wang 2020](#)).

23.10.4 If curved-bar nodes are formed by more than one layer of reinforcement, A_{ts} shall be taken as the total area of tie reinforcement, and r_b shall be taken as the bend radius of the innermost layer.

R23.10.4 Figure R23.10.4 illustrates the use of a curved-bar node with two layers of reinforcing bars. In such cases, the total area of tie reinforcement contributes to the compressive stress on the face of the nodal zone (Face ab in Fig. R23.10.4).

CODE

COMMENTARY




Fig. R23.10.4—Curved-bar node with two layers of reinforcement (nodal zone is shaded).

23.10.5 At frame corners, the joint and reinforcement shall be proportioned such that the center of bar curvature is located within the joint.

R23.10.5 The radius of the bend should be consistent with the geometry of the truss used for the strut-and-tie model. Figure R23.10.5 illustrates the region in which the center of curvature must be located for a typical frame corner.




Fig. R23.10.5—Permissible zone for the center of curvature of a curved-bar node at a frame corner.

23.11—Earthquake-resistant design using the strut-and-tie method

23.11.1 Regions of a seismic-force-resisting system assigned to Seismic Design Category (SDC) D, E, or F and designed with the strut-and-tie method shall be in accordance with (a) and (b):

R23.11—Earthquake-resistant design using the strut-and-tie method

R23.11.1 Strut-and-tie elements of a seismic-force-resisting system may experience strength degradation due to force and displacement reversals. Strut-and-tie elements do not require seismic detailing when the design force is amplified by Ω_o . It is preferable that the strength of the seismic-force-resisting system not be limited by the strength of the discontinuity region designed by the strut-and-tie method.

CODE

(a) Chapter 18

(b) 23.11.2 through 23.11.5 unless design earthquake-induced force, E , in the strut-and-tie element is multiplied by an overstrength factor, Ω_o , not less than 2.5 unless a smaller value of Ω_o can be justified by a detailed analysis.

23.11.2 Strut strength

23.11.2.1 Effective compressive strength determined in accordance with 23.4 shall be multiplied by 0.8.

23.11.3 Strut detailing

23.11.3.1 Struts shall have reinforcement satisfying the detailing requirements of 23.11.3.2 or 23.11.3.3.

23.11.3.2 Struts shall be reinforced with a minimum of four longitudinal bars with a bar in each corner of the transverse reinforcement. Transverse reinforcement shall be placed perpendicular to the direction of the strut and satisfy (a) through (d):

- (a) Detailed in accordance with 18.7.5.2(a) through (e)
- (b) A_{sh}/sb_c determined in accordance with Table 23.11.3.2(a)
- (c) Spacing satisfying 18.7.5.3(d) and not exceeding the values specified in Table 23.11.3.2(b)
- (d) Continued through the nodal zone

Table 23.11.3.2(a)—Transverse reinforcement for struts^{[1][2]}

Transverse reinforcement	Applicable expressions		
A_{sh}/sb_c for rectilinear hoops	Greater of	$0.3 \left(\frac{A_{cs}}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$	(a)
		$0.09 \frac{f'_c}{f_{yt}}$	(b)

^[1] A_{ch} is measured to the outside edges of the transverse reinforcement for the strut.

^[2]It shall be permitted to configure hoops using two pieces of reinforcement as specified in 18.6.4.3.

COMMENTARY

For diaphragm design that includes amplified seismic forces, an additional amplification factor is not required.

Load combinations are provided in 5.3.1, and Eq. (5.3.1e) and (5.3.1g) are used for seismic design. The effects of E may cause reversal of forces in strut and tie elements. In such cases, different strut-and-tie models are developed for each loading direction.

R23.11.2 Strut strength

R23.11.2.1 A reduction factor is applied to account for cracking that is likely to develop in struts located in a region subjected to force reversals.

R23.11.3 Strut detailing

R23.11.3.1 Two confinement options for struts are permitted. For 23.11.3.2, each strut contains longitudinal and transverse reinforcement as required for columns of special moment frames. For 23.11.3.3, the entire cross section of the region or member containing the struts are confined instead of the individual struts.

Expressions (a) and (b) in Table 23.11.3.2(a) are the same as those in Table 18.7.5.4 for columns of special moment frames with the exception of A_{cs} substituted for A_g .

CODE

COMMENTARY

Table 23.11.3.2(b)—Transverse reinforcement spacing limitation

Reinforcement	Maximum transverse bar spacing	
Grade 60	Lesser of	$6d_b$
		6 in.
Grade 80	Lesser of	$5d_b$
		6 in.
Grade 100	Lesser of	$4d_b$
		6 in.

23.11.3.3 Transverse reinforcement shall be provided in each orthogonal direction and through the thickness of the entire member cross section or for the region of the member containing struts and shall satisfy (a) through (d).

- (a) Detailed in accordance with 18.7.5.2(a) through (e)
- (b) A_{sh}/sb_c determined in accordance with Table 23.11.3.3.
- (c) Spacing measured along the longitudinal axis of the member not exceeding the values specified in Table 23.11.3.2(b).
- (d) Spacing of crossties or legs of hoops both vertically and horizontally in the plane of the member cross section shall not exceed 8 in. Each crosstie and each hoop leg shall engage a longitudinal bar of equal or greater diameter.

Table 23.11.3.3—Transverse reinforcement for the entire member cross section

Transverse reinforcement	Applicable expressions		
A_{sh}/sb_c for rectilinear hoops	Greater of	$0.3 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}}$	(a)
		$0.09 \frac{f'_c}{f_{yt}}$	(b)

23.11.4 Strength of ties

23.11.4.1 Tie reinforcement shall develop $1.25f_y$ in tension in accordance with 25.4.

23.11.5 Strength of nodes

23.11.5.1 The nominal compressive strength of a nodal zone calculated in accordance with 23.9 shall be multiplied by 0.8.

R23.11.4 Strength of ties

R23.11.4.1 Because the actual yield strength of tie reinforcement may exceed the specified yield strength and strain hardening of the reinforcement is likely to occur, development lengths for tie reinforcement are determined considering a stress of $1.25f_y$.

R23.11.5 Strength of nodes

R23.11.5.1 A reduction of the nominal compressive strength at nodes is provided to account for tie yielding and the effect of reversed cyclic loading (Mansour and Hsu 2005; To et al. 2009; Ruggiero et al. 2016).

CHAPTER 24—SERVICEABILITY

CODE

COMMENTARY

24.1—Scope

24.1.1 This chapter shall apply to member design for minimum serviceability, including (a) through (d):

- (a) Deflections due to service-level gravity loads (24.2)
- (b) Distribution of flexural reinforcement in one-way slabs and beams to control cracking (24.3)
- (c) Shrinkage and temperature reinforcement (24.4)
- (d) Permissible stresses in prestressed flexural members (24.5)

24.2—Deflections due to service-level gravity loads

24.2.1 Members subjected to flexure shall be designed with adequate stiffness to limit deflections or deformations that adversely affect strength or serviceability of a structure.

R24.1—Scope

R24.1.1 This chapter prescribes serviceability requirements that are referenced by other chapters of the Code to provide adequate performance of structural members. This chapter does not stand on its own as a complete and cohesive compilation of serviceability requirements for the design of structural members. This chapter has no specific requirements for vibrations.

Cast-in-place floor systems designed in accordance with the minimum thickness and deflection requirements of 7.3, 8.3, 9.3, and 24.2 have generally been found, through experience, to provide vibration performance suitable for human comfort under typical service conditions. However, there may be situations where serviceability conditions are not satisfied, for example:

- (a) Long spans and open floor plans
- (b) Floors with strict vibration performance requirements such as precision manufacturing and laboratory spaces
- (c) Facilities subject to rhythmic loadings or vibrating mechanical equipment

Prestressed floor systems are not subject to the minimum thickness requirements of 7.3, 8.3, and 9.3, and if precast they are frequently simple span systems. Consequently, these floor systems can be more susceptible to vibration.

Guidance on the consideration of vibrations in the design of floor systems and the evaluation of vibration frequency and amplitude for concrete floor systems is contained in the *PCI Design Handbook* (PCI MNL 120), *ATC Design Guide 1* (Applied Technology Council 1999), *Mast* (2001), *Fanella and Mota* (2014), and *Wilford and Young* (2006). An example application is described by *West et al.* (2008).

R24.2—Deflections due to service-level gravity loads

R24.2.1 This section is concerned only with deflections or deformations that may occur at service load levels. When time-dependent deflections are calculated, only the dead load and those portions of other loads that are sustained need be considered.

For nonprestressed one-way slabs and beams, including composite concrete members, the minimum overall thickness required by 7.3.1 and 9.3.1 is considered to satisfy the requirements of the Code for members not supporting or attached to nonstructural elements likely to be damaged by large deflections. For nonprestressed two-way construction, the minimum thickness required by 8.3.1 is considered to satisfy the requirements of the Code.

For nonprestressed members that do not meet these minimum thickness requirements, for nonprestressed one-way members that support or are attached to nonstructural elements likely to be damaged by large deflections, and for prestressed flexural members, deflections are required to be calculated by 24.2.3 through 24.2.5. Calculated deflections are limited to the values in Table 24.2.2.

CODE

24.2.2 Deflections calculated in accordance with 24.2.3 through 24.2.5 shall not exceed the limits in Table 24.2.2.

COMMENTARY

R24.2.2 The limitations given in Table 24.2.2 relate only to supported or attached nonstructural elements. For those structures in which structural members are likely to be affected by deflection or deformation of members to which they are attached in such a manner as to affect adversely the strength of the structure, these deflections and the resulting forces should be considered explicitly in the analysis and design of the structures as required by 24.2.1 (ACIPRC-209).

When time-dependent deflections are calculated, the portion of the deflection before attachment of the nonstructural elements may be deducted. In making this correction, use may be made of the curve in Fig. R24.2.4.1 for members of usual sizes and shapes.

Table 24.2.2—Maximum permissible calculated deflections

Member	Condition		Deflection to be considered	Deflection limitation ^[1]
Flat roofs	Not supporting or attached to nonstructural elements likely to be damaged by large deflections		Immediate deflection due to maximum of L_r , S , and R	$\ell/180$ ^[2]
Floors			Immediate deflection due to L	$\ell/360$
Roof or floors	Supporting or attached to nonstructural elements	Likely to be damaged by large deflections	That part of the total deflection occurring after attachment of nonstructural elements, which is the sum of the time-dependent deflection due to all sustained loads and the immediate deflection due to any additional live load ^[3]	$\ell/480$ ^[4]
		Not likely to be damaged by large deflections		$\ell/240$ ^[5]

^[1]For cantilevered members, ℓ shall be taken as twice the clear projection of the cantilever.

^[2]Limit not intended to safeguard against ponding. Ponding shall be checked by calculations of deflection, including added deflections due to ponded water, and considering time-dependent effects of sustained loads, camber, construction tolerances, and reliability of provisions for drainage.

^[3]Time-dependent deflection shall be calculated in accordance with 24.2.4, but shall be permitted to be reduced by amount of deflection calculated to occur before attachment of nonstructural elements. This amount shall be calculated on basis of accepted engineering data relating to time-deflection characteristics of members similar to those being considered.

^[4]Limit shall be permitted to be exceeded if measures are taken to prevent damage to supported or attached elements.

^[5]Limit shall not exceed tolerance provided for nonstructural elements.

24.2.3 Calculation of immediate deflections

24.2.3.1 Immediate deflections shall be calculated using methods or formulas for elastic deflections, considering effects of cracking and reinforcement on member stiffness.

24.2.3.2 Effect of variation of cross-sectional properties, such as haunches, shall be considered when calculating deflections.

24.2.3.3 Deflections in two-way slab systems shall be calculated taking into account size and shape of the panel, conditions of support, and nature of restraints at the panel edges.

R24.2.3 Calculation of immediate deflections

R24.2.3.1 For calculation of immediate deflections of uncracked prismatic members, the usual methods or formulas for elastic deflections may be used with a constant value of $E_c I_g$ along the length of the member. However, if the member is expected to crack at one or more sections, or if its depth varies along the span, a more rigorous calculation becomes necessary.

R24.2.3.3 For immediate deflections, the values of E_c and I_g specified in 24.2.3.4 and 24.2.3.5, respectively, may be used (ACI PRC-209). However, other procedures and other values of the stiffness $E_c I_g$ may be used if they result in predictions of deflection in reasonable agreement with the results of comprehensive tests. Additional information on

CODE

24.2.3.4 Modulus of elasticity, E_c , shall be permitted to be calculated in accordance with 19.2.2.

24.2.3.5 For nonprestressed members, unless obtained by a more comprehensive analysis, effective moment of inertia, I_e , shall be calculated in accordance with Table 24.2.3.5 using:

$$M_{cr} = \frac{f_r I_g}{y_t} \quad (24.2.3.5)$$

Table 24.2.3.5—Effective moment of inertia, I_e

Service moment	Effective moment of inertia, I_e , in. ⁴	
$M_a \leq (2/3)M_{cr}$	I_g	(a)
$M_a > (2/3)M_{cr}$	$\frac{I_{cr}}{1 - \left(\frac{(2/3)M_{cr}}{M_a}\right)^2 \left(1 - \frac{I_{cr}}{I_g}\right)}$	(b)

24.2.3.6 For continuous one-way slabs and beams, I_e shall be permitted to be taken as the average of values obtained from Table 24.2.3.5 for the critical positive and negative moment sections.

24.2.3.7 For prismatic one-way slabs and beams, I_e shall be permitted to be taken as the value obtained from Table 24.2.3.5 at midspan for simple and continuous spans, and at the support for cantilevers.

24.2.3.8 For prestressed Class U slabs and beams as defined in 24.5.2, it shall be permitted to calculate deflections based on I_g .

24.2.3.9 For prestressed Class T and Class C slabs and beams as defined in 24.5.2, deflection calculations shall be based on a cracked transformed section analysis. It shall be permitted to base deflection calculations on a bilinear moment-deflection relationship or I_e in accordance with Eq. (24.2.3.9a)

$$I_e = \left(\frac{M_{cr}}{M_a}\right)^3 I_g + \left[1 - \left(\frac{M_{cr}}{M_a}\right)^3\right] I_{cr} \quad (24.2.3.9a)$$

where M_{cr} is calculated as

$$M_{cr} = \frac{(f_r + f_{pe})I_g}{y_t} \quad (24.2.3.9b)$$

COMMENTARY

deflection of nonprestressed concrete structures is provided in **ACI PRC-435**.

R24.2.3.5 The effective moment of inertia approximation, developed by **Bischoff (2005)**, has been shown to result in calculated deflections that have sufficient accuracy for a wide range of reinforcement ratios (**Bischoff and Scanlon 2007**). M_{cr} is multiplied by two-thirds to consider restraint that can reduce the effective cracking moment as well as to account for reduced tensile strength of concrete during construction that can lead to cracking that later affects service deflections (**Scanlon and Bischoff 2008**).

Before 2019, ACI 318 used a different equation (**Branson 1965**) to calculate I_e . The previous equation has subsequently been shown to underestimate deflections for members with low reinforcement ratios, which often occur in slabs, and does not consider the effects of restraint. For members with greater than 1 percent reinforcement and a service moment at least twice the cracking moment, there is little difference between deflections calculated using Branson (1965) or Bischoff and Scanlon (2007). Refer to ACI PRC-435.

R24.2.3.7 The use of the midspan section properties for continuous prismatic members is considered satisfactory in approximate calculations primarily because the midspan stiffness (including the effect of cracking) has the dominant effect on deflections, as shown by **ACI PRC-435.5**, **ACI Committee 435 (1978)**, and **Sabnis et al. (1974)**.

R24.2.3.8 Immediate deflections of Class U prestressed concrete members may be calculated by the usual methods or formulas for elastic deflections using the moment of inertia of the gross (uncracked) concrete section and the modulus of elasticity for concrete specified in 19.2.2.1.

R24.2.3.9 The effective moment of inertia equation in 24.2.3.5 was revised in the **2019 Code**. The revision is not applicable to prestressed members. Equation (24.2.3.9a) maintains the provisions of previous editions of the Code for these types of members. The **PCI Design Handbook (PCI MNL 120)** gives information on deflection calculations using a bilinear moment-deflection relationship and using an effective moment of inertia. **Mast (1998)** gives additional information on deflection of cracked prestressed concrete members.

Shaikh and Branson (1970) shows that the I_e method can be used to calculate deflections of Class C and Class T prestressed members loaded above the cracking load. For

CODE

24.2.4 Calculation of time-dependent deflections**24.2.4.1 Nonprestressed members**

COMMENTARY

this case, the cracking moment should take into account the effect of prestress as provided in Eq. (24.2.3.9).

A method for predicting the effect of nonprestressed tension reinforcement in reducing creep camber is also given in [Shaikh and Branson \(1970\)](#), with approximate forms given in [ACI PRC-209](#) and [Branson \(1970\)](#).

R24.2.4 Calculation of time-dependent deflections**R24.2.4.1 Nonprestressed members**

Shrinkage and creep cause time-dependent deflections in addition to the elastic deflections that occur when loads are first placed on the structure. Such deflections are influenced by temperature, humidity, curing conditions, age at time of loading, amount of compression reinforcement, and magnitude of the sustained load. The expression given in this section is considered satisfactory for use with the Code procedures for the calculation of immediate deflections, and with the limits given in Table 24.2.2. The deflection calculated in accordance with this section is the additional time-dependent deflection due to the dead load and those portions of other loads that will be sustained for a sufficient period to cause significant time-dependent deflections.

Equation (24.2.4.1.1) was developed in [Branson \(1971\)](#). In Eq. (24.2.4.1.1), the term $(1 + 50\rho')$ accounts for the effect of compression reinforcement in reducing time-dependent deflections. $\xi = 2.0$ represents a nominal time-dependent factor for a 5-year duration of loading. The curve in Fig. R24.2.4.1 may be used to estimate values of ξ for loading periods less than 5 years.

If it is desired to consider creep and shrinkage separately, approximate equations provided in Branson (1965, 1971, 1977) and [ACI Committee 435 \(1966\)](#) may be used.

Because available data on time-dependent deflections of two-way slabs are too limited to justify more elaborate procedures, calculation of the additional time-dependent deflection for two-way construction in accordance with Eq. (24.2.4.1.1) is required to use the multipliers given in 24.2.4.1.3.




Fig. R24.2.4.1—Multipliers for time-dependent deflections.

CODE

24.2.4.1.1 Unless obtained from a more comprehensive analysis, additional time-dependent deflection resulting from creep and shrinkage of flexural members shall be calculated as the product of the immediate deflection caused by sustained load and the factor λ_{Δ}

$$\lambda_{\Delta} = \frac{\xi}{1 + 50\rho'} \quad (24.2.4.1.1)$$

24.2.4.1.2 In Eq. (24.2.4.1.1), ρ' shall be calculated at midspan for simple and continuous spans, and at the support for cantilevers.

24.2.4.1.3 In Eq. (24.2.4.1.1), values of the time-dependent factor for sustained loads, ξ , shall be in accordance with Table 24.2.4.1.3.

Table 24.2.4.1.3—Time-dependent factor for sustained loads

Sustained load duration, months	Time-dependent factor ξ
3	1.0
6	1.2
12	1.4
60 or more	2.0

24.2.4.2 Prestressed members

24.2.4.2.1 Additional time-dependent deflection of prestressed concrete members shall be calculated considering stresses in concrete and reinforcement under sustained load, and the effects of creep and shrinkage of concrete and relaxation of prestressed reinforcement.

COMMENTARY

R24.2.4.2 Prestressed members

R24.2.4.2.1 Calculations should consider not only the increased deflections due to flexural stresses, but also the time-dependent deflections resulting from time-dependent shortening of the flexural member.

Prestressed concrete members are susceptible to increased time-dependent deflections. Prestressed concrete members shorten more with time than similar nonprestressed members due to the precompression in the slab or beam, which causes creep. Creep combined with concrete shrinkage can result in significant shortening of flexural members that continues for several years after construction. This shortening can reduce the tension in the prestressed reinforcement and increase time-dependent deflections.

Another factor that can influence time-dependent deflections of prestressed flexural members is adjacent concrete or masonry that is nonprestressed in the direction of the prestressed member. This can be a slab nonprestressed in the beam direction adjacent to a prestressed beam or a nonprestressed slab system. As the prestressed member tends to shrink and creep more than the adjacent nonprestressed concrete, the structure will tend to reach a compatibility of the shortening effects. This results in a reduction of the precompression in the prestressed member as the adjacent concrete absorbs the compression. This reduction in precompression of the prestressed member can occur over a period of years and will result in additional time-dependent deflections and an increase in tensile stresses in the prestressed member.

CODE

24.2.5 *Calculation of deflections of composite concrete construction*

24.2.5.1 If composite concrete flexural members are shored during construction so that, after removal of temporary supports, the dead load is resisted by the full composite section, it shall be permitted to consider the composite member equivalent to a monolithically cast member for calculation of deflections.

24.2.5.2 If composite concrete flexural members are not shored during construction, the magnitude and duration of load before and after composite action becomes effective shall be considered in calculating time-dependent deflections.

24.2.5.3 Deflections resulting from differential shrinkage of precast and cast-in-place components, and of axial creep effects in prestressed members, shall be considered.

24.3—Distribution of flexural reinforcement in one-way slabs and beams

24.3.1 Bonded reinforcement shall be distributed to control flexural cracking in tension zones of nonprestressed and Class C prestressed slabs and beams reinforced for flexure in one direction only.

COMMENTARY

Any suitable method for calculating time-dependent deflections of prestressed members may be used, provided all effects are considered. Guidance may be found in [ACI PRC-209](#), [ACI Committee 435 \(1963\)](#), [Branson et al. \(1970\)](#), and [Ghali and Favre \(1986\)](#).

R24.2.5 *Calculation of deflections of composite concrete construction*

R24.2.5.1 Composite concrete members are designed to meet the horizontal shear strength requirements of [16.4](#). Because few tests have been made to study the immediate and time-dependent deflections of composite members, the requirements given in this section are based on the judgment of ACI Committee 318 and on experience.

In [22.3.3.3](#), it is stated that distinction need not be made between shored and unshored members. This refers to strength calculations, not to deflections. Construction documents should indicate whether composite concrete design is based on shored or unshored construction, as required by [26.11.1.1](#).

R24.3—Distribution of flexural reinforcement in one-way slabs and beams

R24.3.1 Where service loads result in high stresses in the reinforcement, visible cracks should be expected, and steps should be taken in detailing of the reinforcement to control cracking. For reasons of durability and appearance, many fine cracks are preferable to a few wide cracks. Detailing practices limiting bar spacing will usually lead to adequate crack control where Grade 60 reinforcement is used.

Extensive laboratory experiments ([Gergely and Lutz 1968](#); [Kaar 1966](#); [Base et al. 1966](#)) involving deformed bars demonstrated that crack width at service loads is proportional to reinforcement stress. The significant variables reflecting reinforcement detailing were found to be thickness of concrete cover and the spacing of reinforcement.

Crack width is inherently subject to wide scatter even in careful laboratory experiments and is influenced by shrinkage and other time-dependent effects. Improved crack control is obtained where the reinforcement is well distributed over the zone of maximum concrete tension. Several bars at moderate spacing are much more effective in controlling cracking than one or two larger bars of equivalent area.

CODE

24.3.2 Spacing of bonded reinforcement closest to the tension face shall not exceed the limits in Table 24.3.2, where c_c is the least distance from surface of deformed or prestressed reinforcement to the tension face. Calculated stress in deformed reinforcement, f_s , and calculated change in stress in bonded prestressed reinforcement, Δf_{ps} , shall be in accordance with 24.3.2.1 and 24.3.2.2, respectively.

Table 24.3.2—Maximum spacing of bonded reinforcement in nonprestressed and Class C prestressed one-way slabs and beams

Reinforcement type	Maximum spacing s	
Deformed bars or wires	Lesser of:	$15\left(\frac{40,000}{f_s}\right) - 2.5c_c$
		$12\left(\frac{40,000}{f_s}\right)$
Bonded prestressed reinforcement	Lesser of:	$\left(\frac{2}{3}\right)\left[15\left(\frac{40,000}{\Delta f_{ps}}\right) - 2.5c_c\right]$
		$\left(\frac{2}{3}\right)\left[12\left(\frac{40,000}{\Delta f_{ps}}\right)\right]$
Combined deformed bars or wires and bonded prestressed reinforcement	Lesser of:	$\left(\frac{5}{6}\right)\left[15\left(\frac{40,000}{\Delta f_{ps}}\right) - 2.5c_c\right]$
		$\left(\frac{5}{6}\right)\left[12\left(\frac{40,000}{\Delta f_{ps}}\right)\right]$

24.3.2.1 Stress f_s in deformed reinforcement closest to the tension face at service loads shall be calculated based on the unfactored moment, or it shall be permitted to take f_s as $(2/3)f_y$.

24.3.2.2 Change in stress, Δf_{ps} , in bonded prestressed reinforcement at service loads shall be equal to the calculated stress based on a cracked section analysis minus the decompression stress f_{dc} . It shall be permitted to take f_{dc} equal to the effective stress in the prestressed reinforcement f_{se} . The value of Δf_{ps} shall not exceed 36,000 psi. If Δf_{ps} does not exceed 20,000 psi, the spacing limits in Table 24.3.2 need not be satisfied.

24.3.3 If there is only one bonded bar, pretensioned strand, or bonded tendon nearest to the extreme tension face, the width of the extreme tension face shall not exceed s determined in accordance with Table 24.3.2

24.3.4 If the flange of a T-beam is in tension, the portion of the bonded flexural tension reinforcement not located over the beam web shall be distributed within the lesser of the effective flange width, as defined in accordance with 6.3.2 and $\ell_n/10$. If $\ell_n/10$ controls, additional bonded longitudinal reinforcement

COMMENTARY

R24.3.2 The spacing of reinforcement is limited to control cracking (Beeby 1979; Frosch 1999; ACI Committee 318 1999). For the case of beams with Grade 60 reinforcement and 2 in. clear cover to the primary reinforcement, with $f_s = 40,000$ psi, the maximum bar spacing is 10 in.

Crack widths in structures are highly variable. The Code provisions for spacing are intended to limit surface cracks to a width that is generally acceptable in practice but may vary widely in a given structure.

The role of cracks in the corrosion of reinforcement is controversial. Research (Darwin et al. 1985; Oesterle 1997) shows that corrosion is not clearly correlated with surface crack widths in the range normally found with reinforcement stresses at service load levels. For this reason, the Code does not differentiate between interior and exterior exposures.

Only tension reinforcement nearest the tension face need be considered in selecting the value of c_c used in calculating spacing requirements. To account for prestressed reinforcement, such as strand, having bond characteristics less effective than deformed reinforcement, a two-thirds effectiveness factor is used in Table 24.3.2.

For post-tensioned members designed as cracked members, it will usually be advantageous to provide crack control by the use of deformed reinforcement, for which the provisions in Table 24.3.2 for deformed bars or wires may be used. Bonded reinforcement required by other provisions of the Code may also be used as crack control reinforcement.

R24.3.2.1 For applications in which crack control is critical, the designer should consider reducing the value of f_s to help control cracking. Research by Frosch et al. (2014) and Puranam (2018) supports the use of these design provisions for Grade 100 reinforcement.

R24.3.2.2 It is conservative to take the decompression stress f_{dc} equal to f_{se} , the effective stress in the prestressed reinforcement. The maximum limitation of 36,000 psi for Δf_{ps} is intended to be similar to the maximum allowable stress in Grade 60 reinforcement ($f_s = 40,000$ psi). The exemption for members with Δf_{ps} less than 20,000 psi reflects that many structures designed by working stress methods and with low reinforcement stress served their intended functions with very limited flexural cracking.

R24.3.4 In a T-beam, distribution of the negative moment reinforcement for control of cracking should take into account two considerations: 1) wide spacing of the reinforcement across the full effective width of flange may cause some wide cracks to form in the slab near the web; and 2) close spacing near the web leaves the outer regions of the flange

CODE

satisfying 24.4.3.1 shall be provided in the outer portions of the flange.

24.3.5 The spacing of bonded flexural reinforcement in nonprestressed and Class C prestressed one-way slabs and beams subject to fatigue, designed to be watertight, or exposed to corrosive environments, shall be selected based on investigations and precautions specific to those conditions and shall not exceed the limits of 24.3.2.

24.4—Shrinkage and temperature reinforcement

24.4.1 Reinforcement to resist shrinkage and temperature stresses shall be provided in accordance with 24.4.3 or 24.4.4.

24.4.2 If shrinkage and temperature movements are restrained, the effects of T shall be considered in accordance with 5.3.6.

COMMENTARY

unprotected. The one-tenth limitation is to guard against a spacing that is too wide, with some additional reinforcement required to protect the outer portions of the flange.

For T-beams designed to resist negative moments due to gravity and wind loads, all tensile reinforcement required for strength is located within the lesser of the effective flange width and $\ell_n/10$. Common practice is to place more than half of the reinforcement over the beam web. For T-beams resisting load combinations including earthquake effects, all reinforcement placed within the effective flange width may contribute to the beam flexural strength for the anticipated drift (refer to 18.7.3).

R24.3.5 Although a number of studies have been conducted, clear experimental evidence is not available regarding the crack width beyond which a corrosion danger exists (ACI PRC-222). Exposure tests indicate that concrete quality, adequate consolidation, and ample concrete cover may be of greater importance for corrosion protection than crack width at the concrete surface (Schießl and Raupach 1997).

Provisions related to increased concrete cover and durability of reinforcement is covered in 20.5, while durability of concrete is covered in 19.3.

R24.4—Shrinkage and temperature reinforcement

R24.4.1 Shrinkage and temperature reinforcement is provided at right angles to the principal reinforcement to control cracking and to tie the structure together. The provisions of this section are not intended for slabs-on-ground, unless the slab-on-ground is designed as a structural diaphragm.

R24.4.2 The area of shrinkage and temperature reinforcement required by 24.4.3.2 has been satisfactory where shrinkage and temperature movements are permitted to occur. Where structural walls or columns provide significant restraint to shrinkage and temperature movements, the restraint of volume changes causes tension in slabs, as well as displacements, shear forces, and flexural moments in columns or walls. In these cases, it may be necessary to increase the amount of slab reinforcement required by 24.4.3.2 due to the shrinkage and thermal effects in both principal directions (PCI MNL 120; Gilbert 1992). Top and bottom reinforcement are both effective in controlling cracks. Control strips during the construction period, which permit initial shrinkage to occur without causing an increase in stress, are also effective in reducing cracks caused by restraint.

Topping slabs also experience tension due to restraint of differential shrinkage between the topping and the precast elements or metal deck (which has zero shrinkage) that should be considered in reinforcing the slab. Consideration should be given to strain demands on reinforcement crossing joints of precast elements where most of the restraint is likely to be relieved.

CODE

24.4.3 Nonprestressed reinforcement

24.4.3.1 Deformed reinforcement to resist shrinkage and temperature stresses shall conform to Table 20.2.2.4(a) and shall be in accordance with 24.4.3.2 through 24.4.3.5.

24.4.3.2 The ratio of deformed shrinkage and temperature reinforcement area to gross concrete area shall be greater than or equal to 0.0018.

24.4.3.3 The spacing of deformed shrinkage and temperature reinforcement shall not exceed the lesser of $5h$ and 18 in.

24.4.3.4 At all sections where required, deformed reinforcement used to resist shrinkage and temperature stresses shall develop f_y in tension.

24.4.3.5 For one-way precast slabs and one-way precast, prestressed wall panels, shrinkage and temperature reinforcement is not required in the direction perpendicular to the flexural reinforcement if (a) through (c) are satisfied.

- (a) Precast members are not wider than 12 ft
- (b) Precast members are not mechanically connected to cause restraint in the transverse direction
- (c) Reinforcement is not required to resist transverse flexural stresses

24.4.4 Prestressed reinforcement

24.4.4.1 Prestressed reinforcement to resist shrinkage and temperature stresses shall conform to Table 20.3.2.2, and the effective prestress after losses shall provide an average compressive stress of at least 100 psi on gross concrete area.

COMMENTARY

R24.4.3 Nonprestressed reinforcement

R24.4.3.2 The minimum ratio of deformed bar or welded wire reinforcement area to gross concrete area of 0.0018 is empirical but has been used satisfactorily for many years. The resulting area of reinforcement may be distributed within the member as deemed appropriate for specific conditions. Previous editions of the Code permitted a reduction in shrinkage and temperature reinforcement for reinforcement with yield strength greater than 60,000 psi. However, the mechanics of cracking suggest that increased yield strength provides no benefit for the control of cracking. If crack width or leakage prevention is a design limit state, refer to **ACI PRC-224** or **ACI CODE-350** for recommended reinforcement ratios.

R24.4.3.4 Splices and end anchorages of shrinkage and temperature reinforcement are to be designed to develop the specified yield strength of the reinforcement in accordance with **Chapter 25**.

R24.4.3.5 For precast, prestressed concrete members not wider than 12 ft, such as hollow-core slabs, solid slabs, or slabs with closely spaced ribs, there is usually no need to provide reinforcement to withstand shrinkage and temperature stresses in the short direction. This is generally also true for precast, nonprestressed floor and roof slabs. The 12 ft width is less than that in which shrinkage and temperature stresses can build up to a magnitude requiring reinforcement. In addition, much of the shrinkage occurs before the members are tied into the structure. Once in the final structure, the members are usually not as rigidly connected transversely as monolithic concrete, thus, the transverse restraint stresses due to both shrinkage and temperature change are significantly reduced.

The waiver does not apply where reinforcement is required to resist flexural stresses, such as in thin flanges of precast single and double tees.

R24.4.4 Prestressed reinforcement

R24.4.4.1 Prestressed reinforcement requirements have been selected to provide an effective force on the slab approximately equal to the force required to yield nonprestressed shrinkage and temperature reinforcement. This amount of prestressing—100 psi on the gross concrete area—has been used successfully on a large number of projects.

CODE

COMMENTARY

24.5—Permissible stresses in prestressed concrete flexural members**24.5.1 General**

24.5.1.1 Concrete stresses in prestressed flexural members shall be limited in accordance with 24.5.2 through 24.5.4 unless it is shown by test or analysis that performance will not be impaired.

24.5.1.2 For calculation of stresses at transfer of prestress, at service loads, and at cracking loads, elastic theory shall be used with assumptions (a) and (b):

- (a) Strains vary linearly with distance from neutral axis in accordance with 22.2.1.
- (b) At cracked sections, concrete resists no tension.

24.5.2 Classification of prestressed flexural members

24.5.2.1 Prestressed flexural members shall be classified as Class U, T, or C in accordance with Table 24.5.2.1, based on the extreme fiber stress in tension f_t in the precompressed tension zone calculated at service loads assuming an uncracked section.

Table 24.5.2.1—Classification of prestressed flexural members based on f_t

Assumed behavior	Class	Limits of f_t
Uncracked	U ^[1]	$f_t \leq 7.5\sqrt{f'_c}$
Transition between uncracked and cracked	T	$7.5\sqrt{f'_c} < f_t \leq 12\sqrt{f'_c}$
Cracked	C	$f_t > 12\sqrt{f'_c}$

^[1]Prestressed two-way slabs shall be designed as Class U with $f_t \leq 6\sqrt{f'_c}$.

R24.5—Permissible stresses in prestressed concrete flexural members**R24.5.1 General**

R24.5.1.1 Permissible stresses in concrete address serviceability but do not ensure adequate design strength, which should be checked in accordance with other Code requirements.

A mechanism is provided such that Code limits on stress need not inhibit the development of new products, materials, and techniques in prestressed concrete construction. Approvals for the design should be in accordance with 1.10 of the Code.

R24.5.2 Classification of prestressed flexural members

R24.5.2.1 Three classes of behavior of prestressed flexural members are defined. Class U members are assumed to behave as uncracked members. Class C members are assumed to behave as cracked members. The behavior of Class T members is assumed to be in transition between uncracked and cracked. These classes apply to both bonded and unbonded prestressed flexural members, but prestressed two-way slab systems are required to be designed as Class U with $f_t \leq 6\sqrt{f'_c}$.

The serviceability requirements for each class are summarized in Table R24.5.2.1. For comparison, Table R24.5.2.1 also shows corresponding requirements for nonprestressed members. Due to lack of strain compatibility, it is inappropriate to include the area of unbonded prestressed reinforcement in the calculation of gross or cracked section properties, although the effective prestress force should be considered when determining the location of the neutral axis. Conversely, the calculation of section properties should account for the area of the voids created by the sheathing or duct for unbonded prestressed reinforcement. A method for evaluating stresses, deflections, and crack control in cracked prestressed members is given in Mast (1998).

The precompressed tension zone is that portion of a prestressed member where flexural tension, calculated using gross section properties, would occur under unfactored dead and live loads if the prestress force was not present.

CODE

COMMENTARY

Prestressed concrete is usually designed so that the prestress force introduces compression into this zone, thus effectively reducing the magnitude of the tensile stress.

For corrosive environments, defined as an environment in which chemical attack (such as seawater, corrosive industrial atmosphere, or sewer gas) is encountered, cracking at service loads becomes more critical to long-term performance. For these conditions, cover should be increased in accordance with 20.5.1.4, and tensile stresses in the concrete reduced to minimize possible cracking at service loads.

Table R24.5.2.1—Serviceability design requirements

	Prestressed			Nonprestressed
	Class U	Class T	Class C	
Assumed behavior	Uncracked	Transition between uncracked and cracked	Cracked	Cracked
Section properties for stress calculation at service loads	Gross section 24.5.2.2	Gross section 24.5.2.2	Cracked section 24.5.2.3	No requirement
Allowable stress at transfer	24.5.3	24.5.3	24.5.3	No requirement
Allowable compressive stress based on uncracked section properties	24.5.4	24.5.4	No requirement	No requirement
Tensile stress at service loads 24.5.2.1	$\leq 7.5\sqrt{f'_c}$	$7.5\sqrt{f'_c} < f_t \leq 12\sqrt{f'_c}$	No requirement	No requirement
Deflection calculation basis	24.2.3.8, 24.2.4.2 Gross section	24.2.3.9, 24.2.4.2 Cracked section, bilinear	24.2.3.9, 24.2.4.2 Cracked section, bilinear	24.2.3, 24.2.4.1 Effective moment of inertia
Crack control	No requirement	No requirement	24.3	24.3
Computation of Δf_{ps} or f_s for crack control	—	—	Cracked section analysis	$M/(A_s \times \text{lever arm})$, or $2/3f_y$
Side skin reinforcement	No requirement	No requirement	9.7.2.3	9.7.2.3

24.5.2.2 For Class U and T members, stresses at service loads shall be permitted to be calculated using the uncracked section.

24.5.2.3 For Class C members, stresses at service loads shall be calculated using the cracked transformed section.

R24.5.2.3 Prestressed members are classified based on the magnitude of the stress in the precompressed tension zone, calculated assuming the section remains uncracked. Once it is determined that a member is Class C, with $f_t > 12\sqrt{f'_c}$, subsequent calculations of service load stresses are based on the cracked transformed section.

24.5.3 *Permissible concrete stresses at transfer of prestress*

R24.5.3 *Permissible concrete stresses at transfer of prestress*

The concrete stresses at this stage are caused by the weight of the member and the force in the prestressed reinforcement after jacking reduced by the losses due to seating of the prestressed reinforcement and elastic shortening of the concrete. Shrinkage, creep, and relaxation effects are generally not included at this stage. These stresses apply to both pretensioned and post-tensioned concrete with proper modifications of the losses at transfer. Minimum values of f_{ci}' are provided in 19.2.1.4 for pretensioned members and 25.9.4.5.4 for post-tensioning.

CODE

24.5.3.1 Calculated extreme concrete fiber stress in compression immediately after transfer of prestress, but before time-dependent prestress losses, shall not exceed the limits in Table 24.5.3.1.

Table 24.5.3.1—Concrete compressive stress limits immediately after transfer of prestress

Location	Concrete compressive stress limits
End of simply-supported members	$0.70f_{ci}'$
All other locations	$0.60f_{ci}'$

24.5.3.2 Calculated extreme concrete fiber stress in tension immediately after transfer of prestress, but before time-dependent prestress losses, shall not exceed the limits in Table 24.5.3.2, unless permitted by 24.5.3.2.1.

Table 24.5.3.2—Concrete tensile stress limits immediately after transfer of prestress, without additional bonded reinforcement in tension zone

Location	Concrete tensile stress limits
Ends of simply-supported members	$6\sqrt{f_{ci}'}$
All other locations	$3\sqrt{f_{ci}'}$

24.5.3.2.1 The limits in Table 24.5.3.2 shall be permitted to be exceeded where additional bonded reinforcement in the tension zone resists the total tensile force in the concrete calculated with the assumption of an uncracked section.

24.5.4 Permissible concrete compressive stresses at service loads

24.5.4.1 For Class U and T members, the calculated extreme concrete fiber stress in compression at service loads, after allowance for all prestress losses, shall not exceed the limits in Table 24.5.4.1.

Table 24.5.4.1—Concrete compressive stress limits at service loads

Load condition	Concrete compressive stress limits
Prestress plus sustained load	$0.45f_c'$
Prestress plus total load	$0.60f_c'$

COMMENTARY

R24.5.3.1 The permissible concrete compressive stresses at transfer of prestress are higher at ends of simply supported members than at other locations based on research in the precast, prestressed concrete industry (Castro et al. 2004; Dolan and Krohn 2007; Hale and Russell 2006).

R24.5.3.2 The tensile stress limits of $3\sqrt{f_{ci}'}$ and $6\sqrt{f_{ci}'}$ refer to tensile stresses at transfer of prestress at locations other than the precompressed tension zone. Where tensile stresses exceed the permissible values, the total force in the tensile stress zone may be calculated and reinforcement proportioned on the basis of this force at a stress of $0.6f_y$, but not more than 30,000 psi. The effects of creep and shrinkage begin to reduce the tensile stress almost immediately; however, some tension remains in these locations after allowance is made for all prestress losses.

R24.5.4 Permissible concrete compressive stresses at service loads

R24.5.4.1 The compressive stress limit of $0.45f_c'$ was originally established to decrease the probability of failure of prestressed concrete members due to repeated loads. This limit also seemed reasonable to preclude excessive creep deformation. At higher values of stress, creep strains tend to increase more rapidly as applied stress increases.

Fatigue tests of prestressed concrete beams have shown that concrete compressive failures are not the controlling criterion. Therefore, the stress limit of $0.60f_c'$ permits a one-third increase in allowable compressive stress for members subject to transient loads.

Sustained live load is any portion of the service live load that will be sustained for a sufficient period to cause significant time-dependent deflections. Thus, when the sustained live and dead loads are a large percentage of the total service load, the $0.45f_c'$ limit of Table 24.5.4.1 typically controls. On the other hand, when a large portion of the total service load consists of a transient or temporary service live load, the increased stress limit of $0.60f_c'$ typically controls.

The compression limit of $0.45f_c'$ for prestress plus sustained loads will continue to control the time-dependent behavior of prestressed members.

CHAPTER 25—REINFORCEMENT DETAILS

CODE	COMMENTARY
------	------------

25.1—Scope

25.1.1 This chapter shall apply to reinforcement details, including:

- (a) Minimum spacing
- (b) Standard hooks, seismic hooks, and crossties
- (c) Development and anchorage of reinforcement
- (d) Splices
- (e) Bundled reinforcement
- (f) Transverse reinforcement
- (g) Post-tensioning anchorages and couplers

25.1.2 Provisions of 25.9 shall apply to anchorage zones for post-tensioned tendons.

25.2—Minimum spacing of reinforcement

25.2.1 For parallel nonprestressed reinforcement in a horizontal layer, clear spacing shall be at least the greatest of 1 in., d_b , and $(4/3)d_{agg}$.

25.2.2 For parallel nonprestressed reinforcement placed in two or more horizontal layers, reinforcement in the upper layers shall be placed directly above reinforcement in the bottom layer with a clear spacing between layers of at least 1 in.

R25.1—Scope

Recommended methods and standards for preparing design drawings, typical details, and drawings for the fabrication and placing of steel reinforcement in reinforced concrete structures are given in the *ACI Detailing Manual* (MNL-66).

All provisions in the Code relating to bar, wire, or strand diameter (and area) are based on the nominal dimensions of the reinforcement as given in the appropriate ASTM specification. Nominal dimensions are equivalent to those of a circular area having the same weight per foot as the ASTM designated bar, wire, or strand sizes. Cross-sectional area of reinforcement is based on nominal dimensions.

R25.1.1 In addition to the requirements in this chapter that affect detailing of reinforcement, detailing specific to particular members is given in the corresponding member chapters. Additional detailing associated with structural integrity requirements is covered in 4.10.

R25.2—Minimum spacing of reinforcement

The minimum limits are set to permit concrete to flow readily into spaces between bars and between bars and forms without honeycombs, and to ensure against concentration of bars on a line that may cause shear or shrinkage cracking. Use of nominal bar diameter to define minimum spacing permits a uniform criterion for all bar sizes. In 2014, the size limitations on aggregates were translated to minimum spacing requirements, and are provided to promote proper encasement of reinforcement and to minimize honeycombing. The limitations associated with aggregate size need not be satisfied if, in the judgment of the licensed design professional, the workability and methods of consolidation of the concrete are such that the concrete can be placed without creating honeycombs or voids.

The development lengths given in 25.4 are a function of the bar spacing and cover. As a result, it may be desirable to use larger than minimum bar spacing or cover in some cases.

CODE

25.2.3 For longitudinal reinforcement in columns, pedestals, struts, and boundary elements in walls, clear spacing between bars shall be at least the greatest of 1.5 in., $1.5d_b$, and $(4/3)d_{agg}$.

25.2.4 For pretensioned strands at ends of a member, minimum center-to-center spacing s shall be the greater of the value in Table 25.2.4, and $[(4/3)d_{agg} + d_b]$.

Table 25.2.4—Minimum center-to-center spacing of pretensioned strands at ends of members

f_{ci} , psi	Nominal strand diameter, in.	Minimum s
< 4000	All	$4d_b$
≥ 4000	< 0.5 in.	$4d_b$
	0.5 in.	1-3/4 in.
	0.6 in.	2 in.

25.2.5 For pretensioned wire at ends of a member, minimum center-to-center spacing, s , shall be the greater of $5d_b$ and $[(4/3)d_{agg} + d_b]$.

25.2.6 Reduced vertical spacing including bundling of prestressed reinforcement shall be permitted in the middle portion of a span.

25.2.7 For parallel nonprestressed reinforcement in shotcrete members, the clear spacing shall be in accordance with (a) or (b):

- (a) The clear spacing between bars shall be at least the greater of $6d_b$ and 2-1/2 in.
- (b) If two curtains of reinforcement are provided, the clear spacing between bars in the curtain nearer the nozzle shall be at least $12d_b$. The clear spacing between bars in the remaining curtain shall conform to (a).

25.2.7.1 It shall be permitted to use a clear spacing that does not meet 25.2.7(a) or 25.2.7(b) provided shotcrete mockup panels are used to demonstrate proper reinforcement encasement in accordance with (a) and (b):

- (a) The shotcrete mockup panels shall be representative of the most complex reinforcement configurations to be encountered.
- (b) The licensed design professional shall specify the shotcrete mock-up panel quantity, frequency of shooting per nozzle man and member type, and panel thickness to verify reinforcement encasement.

25.2.8 For prestressed strands in shotcrete members, minimum center-to-center spacing, s , shall satisfy 25.2.4, except as permitted in 25.2.6.

25.2.9 For prestressed wire in shotcrete members, minimum center-to-center spacing, s , shall satisfy the

COMMENTARY

R25.2.4 The decreased spacing for transfer strengths of 4000 psi or greater is based on [Deatherage et al. \(1994\)](#) and [Russell and Burns \(1996\)](#).

R25.2.7.1 Information on shotcrete mockup panels is provided in [ACI PRC-506](#), and information on evaluating shotcrete is provided in [ACI PRC-506.4](#).

CODE

requirements for wire in 25.2.5, except as permitted in and 25.2.6.

25.2.10 For ties, hoops, and spiral reinforcement in columns to be placed with shotcrete, minimum clear spacing shall be 3 in.

25.2.10.1 It shall be permitted to use a clear spacing other than 3 in. provided shotcrete mockup panels are used to demonstrate proper encasement of the reinforcement in accordance with 25.2.7.1

25.3—Standard hooks, seismic hooks, crossties, and minimum inside bend diameters

25.3.1 Standard hooks for the development of deformed bars in tension shall conform to Table 25.3.1.



COMMENTARY

R25.2.10 Shotcrete is usually not used in new construction for columns because the close spacing between ties, hoops, or spiral reinforcement makes it difficult to achieve adequate encasement of the column longitudinal reinforcement. Spacing closer than required in 25.2.10 requires approval by the licensed design professional based on shotcrete mockup panels demonstrating that the reinforcement can be encased without voids.

R25.3—Standard hooks, seismic hooks, crossties, and minimum inside bend diameters

R25.3.1 Standard bends in reinforcing bars are described in terms of the inside diameter of bend because the inside bend diameter is easier to measure than the radius of bend. The primary factors affecting the minimum bend diameter are feasibility of bending without breakage and avoidance of crushing the concrete inside the bend.

Table 25.3.1—Standard hook geometry for development of deformed bars in tension

Type of standard hook	Bar size	Minimum inside bend diameter, in.	Straight extension ^[1] ℓ_{ext} , in.	Type of standard hook
90-degree hook	No. 3 through No. 8	$6d_b$	$12d_b$	
	No. 9 through No. 11	$8d_b$		
	No. 14 and No. 18	$10d_b$		
180-degree hook	No. 3 through No. 8	$6d_b$	Greater of $4d_b$ and 2.5 in.	
	No. 9 through No. 11	$8d_b$		
	No. 14 and No. 18	$10d_b$		

^[1]A standard hook for deformed bars in tension includes the specific inside bend diameter and straight extension length. It shall be permitted to use a longer straight extension at the end of a hook. A longer extension shall not be considered to increase the anchorage capacity of the hook.

25.3.2 Minimum inside bend diameters for bars used as transverse reinforcement and standard hooks for bars used to anchor stirrups, ties, hoops, and spirals shall conform to Table 25.3.2. Standard hooks shall enclose longitudinal reinforcement.

R25.3.2 Standard stirrup, tie, and hoop hooks are limited to No. 8 bars and smaller, and the 90-degree hook with $6d_b$ extension is further limited to No. 5 bars and smaller, as the result of research showing that larger bar sizes with 90-degree hooks and $6d_b$ extensions tend to spall off the cover concrete when the reinforcement is stressed and the hook straightens.

The minimum $4d_b$ bend for the bar sizes commonly used for stirrups, ties, and hoops is based on accepted industry practice in the United States. Use of a stirrup bar size No. 5




CODE

COMMENTARY

or smaller for the 90-, 135-, or 180-degree standard stirrup hook will permit multiple bending on standard stirrup bending equipment.

Constructibility issues should be considered in selecting anchorage details. In particular, the use of 180-degree hooks should be avoided in closed stirrups, ties, and hoops made of continuous reinforcement.

Table 25.3.2—Minimum inside bend diameters and standard hook geometry for stirrups, ties, and hoops

Type of standard hook	Bar size	Minimum inside bend diameter, in.	Straight extension ^[1] ℓ_{ext} , in.	Type of standard hook
90-degree hook	No. 3 through No. 5	$4d_b$	Greater of $6d_b$ and 3 in.	
	No. 6 through No. 8	$6d_b$	$12d_b$	
135-degree hook	No. 3 through No. 5	$4d_b$	Greater of $6d_b$ and 3 in.	
	No. 6 through No. 8	$6d_b$		
180-degree hook	No. 3 through No. 5	$4d_b$	Greater of $4d_b$ and 2.5 in.	
	No. 6 through No. 8	$6d_b$		

^[1]A standard hook for stirrups, ties, and hoops includes the specific inside bend diameter and straight extension length. It shall be permitted to use a longer straight extension at the end of a hook. A longer extension shall not be considered to increase the anchorage capacity of the hook.

25.3.3 Minimum inside bend diameters for welded wire reinforcement used as stirrups or ties shall not be less than $4d_b$ for deformed wire larger than D6 and $2d_b$ for all other wires. Bends with inside diameter of less than $8d_b$ shall not be less than $4d_b$ from nearest welded intersection.

R25.3.3 Welded wire reinforcement can be used for stirrups and ties. The wire at welded intersections does not have the same uniform ductility and bendability as in areas that were not heated by welding in the manufacture of the welded wire reinforcement. These effects of the welding temperature are usually dissipated in a distance of approximately four wire diameters. Minimum bend diameters permitted are in most cases the same as those required in the ASTM bend tests for wire (ASTM A1064 and A1022).

25.3.4 Seismic hooks used to anchor stirrups, ties, hoops, and crossties shall be in accordance with (a) and (b):

- (a) Minimum bend of 90 degrees for circular hoops and 135 degrees for all other hoops
- (b) Hook shall engage longitudinal reinforcement and the extension shall project into the interior of the stirrup or hoop

25.3.5 Crossties shall be in accordance with (a) through (e):

- (a) Crosstie shall be continuous between ends
- (b) There shall be a seismic hook at one end
- (c) There shall be a standard hook at other end with minimum bend of 90 degrees
- (d) Hooks shall engage peripheral longitudinal bars

R25.3.5 Crossties are illustrated in Fig. R25.3.5.

CODE

(c) 90-degree hooks of two successive crossties engaging the same longitudinal bars shall be alternated end for end, unless crossties satisfy 18.6.4.3 or 25.7.1.6.1

COMMENTARY

Alternate hook position of each successive crosstie




Fig. R25.3.5—Crosstie.

25.4—Development and anchorage of reinforcement

25.4.1 General

25.4.1.1 Calculated tension or compression in reinforcement at each section of a member shall be developed on each side of that section by embedment length, hook, headed deformed bar, mechanical device, or a combination thereof.

25.4.1.2 Hooks and heads shall not be used to develop bars in compression.

25.4.1.3 Development lengths do not require a strength reduction factor ϕ . The design strength of reinforcing bar groups associated with breakout failure requires a ϕ -factor in accordance with Table 21.2.1 (j).

R25.4—Development and anchorage of reinforcement

R25.4.1 General

R25.4.1.1 The development length concept is based on the attainable average bond stress over the length of embedment of the reinforcement (ACI Committee 408 1966). Development lengths are required because of the tendency of highly stressed bars to split relatively thin sections of restraining concrete. A single bar embedded in a mass of concrete should not require as great a development length, although a row of bars, even in mass concrete, can create a weakened plane with longitudinal splitting along the plane of the bars.

In application, the development length concept requires minimum lengths or extensions of reinforcement beyond all points of peak stress in the reinforcement. Such peak stresses generally occur at the points of maximum stress and points where reinforcement is bent or terminated. From a point of peak stress in reinforcement, some length of reinforcement or anchorage is necessary to develop the stress. This development length or anchorage is necessary on both sides of such peak stress points. Often, the reinforcement continues for a considerable distance on one side of a critical stress point so that calculations need involve only the other side, for example, the negative moment reinforcement continuing through a support to the middle of the next span. The requirement for a minimum value of K_{tr} along development and splice lengths in 9.7.1.4, 10.7.1.3, 25.4.2.2, and 25.5.1.5 improves ductility.

R25.4.1.2 Hooks and heads are ineffective in compression. No data are available to demonstrate that hooks and heads can reduce development length in compression.

R25.4.1.3 The strength reduction factor ϕ is not used in the development length and lap splice length equations. An allowance for strength reduction is already included in the expressions for determining development and splice lengths. The strength reduction factor ϕ for anchorage of reinforcing bar groups where the strength is controlled by concrete breakout failure modes is aligned with the reliability required for anchors in concrete.

CODE

25.4.1.4 The values of $\sqrt{f'_c}$ used to calculate development length shall not exceed 100 psi.

25.4.1.5 For reinforcing bar groups in tension terminating in an anchorage region, the anchorage requirements of 25.4.11 shall be satisfied in addition to development length requirements.

25.4.1.6 Post-installed reinforcing bars designed in accordance with this section shall be qualified in accordance with **ACI CODE-355.5**.

25.4.2 *Development of deformed bars and deformed wires in tension*

25.4.2.1 Development length ℓ_d for deformed bars and deformed wires in tension shall be the greater of (a) and (b):

- (a) Length calculated in accordance with 25.4.2.3 or 25.4.2.4 using the applicable modification factors of 25.4.2.5
- (b) 12 in.

25.4.2.2 For bars with $f_y \geq 80,000$ psi spaced closer than 6 in. on center, transverse reinforcement shall be provided such that K_{tr} shall not be smaller than $0.5d_b$.

25.4.2.3 For deformed bars or deformed wires, ℓ_d shall be calculated in accordance with Table 25.4.2.3.

COMMENTARY

R25.4.1.4 **Darwin et al. (1996)** shows that the force developed in a bar in development and lap splice tests increases at a lesser rate than $\sqrt{f'_c}$ with increasing compressive strength. Using $\sqrt{f'_c}$, however, is sufficiently accurate for values of $\sqrt{f'_c}$ up to 100 psi, and because of the long-standing use of the $\sqrt{f'_c}$ in design, ACI Committee 318 has chosen not to change the exponent applied to the compressive strength used to calculate development and lap splice lengths, but rather to set an upper limit of 100 psi on $\sqrt{f'_c}$.

R25.4.1.5 The strength of reinforcing bar groups may be limited by concrete breakout failure (**Chicchi 2020; Kim and Chun 2022**).

R25.4.1.6 Post-installed deformed reinforcing bars qualified in accordance with ACI CODE-355.5 are expected to exhibit a performance equivalent to cast-in bars of equal diameter and embedment for bond development and response to tension loading. ACI CODE-355.5 addresses critical aspects associated with the use of pourable or injectable bonding materials intended for use in post-installed reinforcing bar applications, including bond strength, stiffness, long-term stability, and suitability for use with the full range of bar diameters and associated embedments permitted by the Code.

R25.4.2 *Development of deformed bars and deformed wires in tension*

R25.4.2.1 This provision gives a two-tier approach for the calculation of tension development length. The user can either use the simplified provisions of 25.4.2.3 or the general development length equation (Eq. (25.4.2.4a)). In Table 25.4.2.3, ℓ_d is based on two preselected values of $(c_b + K_{tr})/d_b$, whereas ℓ_d from Eq. (25.4.2.4a) is based on the actual $(c_b + K_{tr})/d_b$.

Although there is no requirement for transverse reinforcement along the tension development or lap splice length, research (**Azizinamini et al. 1999a,b**) indicates that in concrete with very high compressive strength, brittle anchorage failure may occur for bars with inadequate transverse reinforcement. In lap splice tests of No. 8 and No. 11 bars in concrete with an f'_c of approximately 15,000 psi, transverse reinforcement improved ductile anchorage behavior.

R25.4.2.3 This provision recognizes that many current practical construction cases use spacing and cover values along with confining reinforcement, such as stirrups or ties, that result in a value of $(c_b + K_{tr})/d_b$ of at least 1.5. Examples include a minimum clear cover of d_b along with either minimum clear spacing of $2d_b$, or a combination of minimum clear spacing of d_b and minimum ties or stirrups.

CODE

Table 25.4.2.3—Development length for deformed bars and deformed wires in tension

Spacing and cover	No. 6 and smaller bars and deformed wires	No. 7 and larger bars
Clear spacing of bars or wires being developed or lap spliced not less than d_b , clear cover at least d_b , and stirrups or ties throughout ℓ_d not less than the Code minimum or Clear spacing of bars or wires being developed or lap spliced at least $2d_b$ and clear cover at least d_b	$\left(\frac{f_y \psi_t \psi_e \psi_s \psi_g}{25 \lambda \sqrt{f'_c}} \right) d_b$	$\left(\frac{f_y \psi_t \psi_e \psi_s \psi_g}{20 \lambda \sqrt{f'_c}} \right) d_b$
Other cases	$\left(\frac{3 f_y \psi_t \psi_e \psi_s \psi_g}{50 \lambda \sqrt{f'_c}} \right) d_b$	$\left(\frac{3 f_y \psi_t \psi_e \psi_s \psi_g}{40 \lambda \sqrt{f'_c}} \right) d_b$

COMMENTARY

For these frequently occurring cases, the development length for larger bars can be taken as $\ell_d = [f_y \psi_t \psi_e \psi_s \psi_g / (20 \lambda \sqrt{f'_c})] d_b$. In the formulation of the provisions in **ACI 318-95**, a comparison with past provisions and a check of a database of experimental results indicated that for No. 6 deformed bars and smaller, as well as for deformed wire, the development lengths could be reduced 20 percent using $\psi_s = 0.8$. This is the basis for the *No. 6 and smaller bars and deformed wires* column of Table 25.4.2.3. With less cover and in the absence of minimum ties or stirrups, the minimum clear spacing limits of 25.2.1 and the minimum concrete cover requirements of 20.5.1.3 result in minimum values of c_b equal to d_b . Thus, for “other cases,” the values are based on using $(c_b + K_{tr})/d_b = 1.0$ in Eq. (25.4.2.4a).

The user may easily construct simple, useful expressions. For example, in all members with normalweight concrete ($\lambda = 1.0$), uncoated reinforcement ($\psi_e = 1.0$), No. 7 and larger bottom bars ($\psi_t = 1.0$) with $f'_c = 4000$ psi, and Grade 60 reinforcement ($\psi_g = 1.0$), the expressions reduce to

$$\ell_d = \frac{(60,000)(1.0)(1.0)(1.0)}{20(1.0)\sqrt{4000}} d_b = 47d_b$$

or

$$\ell_d = \frac{3(60,000)(1.0)(1.0)(1.0)}{40(1.0)\sqrt{4000}} d_b = 71d_b$$

Thus, as long as minimum cover of d_b is provided along with a minimum clear spacing of $2d_b$, or a minimum clear cover of d_b and a minimum clear spacing of d_b are provided along with minimum ties or stirrups, then $\ell_d = 47d_b$. The penalty for spacing bars closer or providing less cover is the requirement that $\ell_d = 71d_b$.

25.4.2.4 For deformed bars or deformed wires, ℓ_d shall be calculated by:

$$\ell_d = \left(\frac{3}{40} \frac{f_y}{\lambda \sqrt{f'_c}} \frac{\psi_t \psi_e \psi_s \psi_g}{\left(\frac{c_b + K_{tr}}{d_b} \right)} \right) d_b \quad (25.4.2.4a)$$

in which the confinement term $(c_b + K_{tr})/d_b$ shall not exceed 2.5, and

$$K_{tr} = \frac{40A_{tr}}{sn} \quad (25.4.2.4b)$$

where n is the number of bars or wires being developed or lap spliced along the plane of splitting. It shall be permitted to use $K_{tr} = 0$ as a design simplification even if transverse reinforcement is present or required.

R25.4.2.4 Equation (25.4.2.4a) includes the effects of all variables controlling the development length. In Eq. (25.4.2.4a), c_b is a factor that represents the least of the side cover, the concrete cover to the bar or wire (in both cases measured to the center of the bar or wire), or one-half the center-to-center spacing of the bars or wires. K_{tr} is a factor that represents the contribution of confining reinforcement across potential splitting planes. ψ_t is the reinforcement location factor to reflect the effect of the casting position (that is, formerly denoted as “top bar effect”). ψ_e is a coating factor reflecting the effects of epoxy coating. There is a limit on the product $\psi_t \psi_e$. The reinforcement size factor ψ_s reflects the more favorable performance of smaller-diameter reinforcement. ψ_g is the reinforcement grade factor accounting for the yield strength of the reinforcement. A limit of 2.5 is placed on the term $(c_b + K_{tr})/d_b$. When $(c_b + K_{tr})/d_b$ is less than 2.5, splitting failures are likely to occur. For values above 2.5, a pullout failure is expected, and an increase in cover or transverse reinforcement is unlikely to increase the anchorage capacity.

Many practical combinations of side cover, clear cover, and confining reinforcement can be used with 25.4.2.4 to produce significantly shorter development lengths than allowed by

CODE

COMMENTARY

25.4.2.5 For the calculation of ℓ_d , modification factors shall be in accordance with Table 25.4.2.5.

Table 25.4.2.5—Modification factors for development of deformed bars and deformed wires in tension

Modification factor	Condition	Value of factor
Lightweight λ	Lightweight concrete	0.75
	Normalweight concrete	1.0
Reinforcement grade ψ_g	Grade 40 or Grade 60	1.0
	Grade 80	1.15
	Grade 100	1.3
Epoxy ^[1] ψ_e	Epoxy-coated or zinc and epoxy dual-coated reinforcement with clear cover less than $3d_b$ or clear spacing less than $6d_b$	1.5
	Epoxy-coated or zinc and epoxy dual-coated reinforcement for all other conditions	1.2
	Uncoated or zinc-coated (galvanized) reinforcement	1.0
Size ψ_s	No. 7 and larger bars	1.0
	No. 6 and smaller bars and deformed wires	0.8
Casting position ^[1] ψ_t	More than 12 in. of fresh concrete placed below horizontal reinforcement	1.3
	Other	1.0

^[1]The product $\psi_s\psi_e$ need not exceed 1.7.

25.4.2.3. For example, bars or wires with minimum clear cover not less than $2d_b$ and minimum clear spacing not less than $4d_b$ and without any confining reinforcement would have a $(c_b + K_{tr})/d_b$ value of 2.5 and would require a development length of only $28d_b$ for the example in R25.4.2.3.

Before ACI 318-08, Eq. (25.4.2.4b) for K_{tr} included the yield strength of transverse reinforcement. The current expression includes only the area and spacing of the transverse reinforcement and the number of wires or bars being developed or lap spliced because tests demonstrate that transverse reinforcement rarely yields during a bond failure (Azizinamini et al. 1995).

Terms in Eq. (25.4.2.4a) may be disregarded if such omission results in longer and, hence, more conservative, development lengths.

R25.4.2.5 The lightweight factor λ for calculating development length of deformed bars and deformed wire in tension is the same for all types of lightweight concrete. Research does not support the variations of this factor in Codes prior to 1989 for all-lightweight and sand-lightweight concrete (ACI PRC-408).

The reinforcement grade factor ψ_g accounts for the effect of reinforcement yield strength on required development length. Research has shown that required development length increases disproportionately with increases in yield strength (Orangun et al. 1977; Canbay and Frosch 2005).

The epoxy factor ψ_e is based on studies (Treece and Jirsa 1989; Johnston and Zia 1982; Mathey and Clifton 1976) of the anchorage of epoxy-coated bars that show bond strength is reduced because the coating prevents adhesion and lowers the coefficient of friction between the bar and the concrete. The factors reflect the type of anchorage failure likely to occur. If the cover or spacing is small, a splitting failure can occur and the anchorage or bond strength is substantially reduced. If the cover and spacing between bars is large, a splitting failure is precluded and the effect of the epoxy coating on anchorage strength is not as large. Studies (Orangun et al. 1977) have shown that although the cover or spacing may be small, the anchorage strength may be increased by adding transverse reinforcement crossing the plane of splitting, and restraining the splitting crack.

Because the bond of epoxy-coated bars or zinc and epoxy dual-coated bars is already reduced due to the loss of adhesion and lower coefficient of friction between the bar and the concrete, an upper limit of 1.7 is established for the product of the factors for top reinforcement casting position and epoxy-coated reinforcement or zinc and epoxy dual-coated reinforcement.

The reinforcement size factor ψ_s reflects the more favorable performance of smaller-diameter reinforcement.

The reinforcement location or casting position factor ψ_t accounts for the position of the reinforcement in freshly placed concrete. The factor 1.3 is based on research (Jirsa and Breen 1981; Jeanty et al. 1988). The application of the

CODE

25.4.2.6 For post-installed reinforcing bars, (a) and (b) shall be permitted in the calculation of ℓ_d .

- (a) casting position factor, $\psi_t = 1.0$
- (b) include transverse reinforcement, crossing the potential plane of splitting, in the calculation of K_{tr}

25.4.2.7 Transverse reinforcement used to confine a straight bar being developed or lap spliced shall be developed on each side of potential splitting planes or shall consist of stirrups satisfying 25.7.1, ties satisfying 25.7.2, spirals satisfying 25.7.3, or hoops satisfying 25.7.4.

25.4.3 Development of standard hooks in tension

25.4.3.1 Development length ℓ_{dh} for deformed bars in tension terminating in a standard hook shall be the greater of (a) through (c):

- (a) $\frac{f_y \psi_e \psi_s \psi_{cc} \psi_r}{50 \lambda \sqrt{f'_c}} d_b$ with ψ_e , ψ_s , ψ_{cc} , ψ_r , and λ given in 25.4.3.2
- (b) $8d_b$
- (c) 6 in.

25.4.3.2 For the calculation of ℓ_{dh} , modification factors ψ_e , ψ_r , ψ_s , ψ_{cc} , and λ shall be in accordance with Table 25.4.3.2. Factors ψ_{cc} and ψ_r shall be permitted to be taken as 1.0. At discontinuous ends of members, 25.4.3.3 shall apply.

COMMENTARY

casting position factor should be considered in determination of development lengths for inclined reinforcement.

R25.4.3 Development of standard hooks in tension

R25.4.3.1 The provisions for hooked bars are only applicable to standard hooks (refer to 25.3.1). The development length ℓ_{dh} is measured from the critical section to the outside end (or edge) of the hook. Failure of hooked bar anchorages is typically due to splitting of the concrete cover in the plane of the hook or breakout failure. The required length to avoid these failures is influenced by reinforcement diameter, epoxy coating, and yield strength, as well as other factors that influence splitting and breakout strengths such as concrete strength, lightweight aggregate, cover dimensions, and confinement provided by transverse reinforcement enclosing the hooked reinforcement. The expression in 25.4.3.1(a) restores the equation for hooked bar development used in **ACI 318-14** and several previous editions of the Code with minor modifications. Revisions to 25.4.3.1 introduced in **ACI 318-19** were found to result in appreciably increased values of ℓ_{dh} for common cases, a result which the committee later found to be without adequate justification.

Minimum values of ℓ_{dh} are specified to prevent failure by direct pullout in cases where a hook may be located near the critical section. Hooks in beam-column joints and corbels should be placed as close as practical to the back face of the joint.

R25.4.3.2 Unlike straight bar development, no distinction is made for casting position.

The epoxy factor ψ_e is based on tests (**Hamad et al. 1993**) that indicate the development length for hooked bars should be increased by 20% to account for reduced bond when reinforcement is epoxy coated.

The reinforcement size factor ψ_s is based on test results (**Banaeipour et al. 2023**) that indicate that large bars may require increased development length compared with that calculated using the ACI 318-14 provisions. The confining reinforcement factor ψ_r is based on tests (**Jirsa and Marques 1975**) that indicate closely spaced ties at or near the bend portion of a hooked bar are most effective in confining the

CODE

Table 25.4.3.2—Modification factors for development of hooked bars in tension

Modification factor	Condition	Value of factor
Lightweight λ	Lightweight concrete	0.75
	Normalweight concrete	1.0
Epoxy ψ_e	Epoxy-coated or zinc and epoxy dual-coated reinforcement	1.2
	Uncoated or zinc-coated (galvanized) reinforcement	1.0
Size ψ_s	No. 9 bars and smaller	1.0
	No. 10 and No. 11 bars	1.15
	No. 14 bars	1.3
	No. 18 bars	1.5
Cover ψ_{cc}	For No. 11 bar and smaller hooks with side cover (normal to plane of hook) $\geq 2\text{-}1/2$ in. and for 90-degree hook with cover on bar extension beyond hook ≥ 2 in.	0.7
	Other	1.0
Confining reinforcement ψ_r ^[2]	For 90-degree hooks of No. 11 and smaller bars (1) enclosed along ℓ_{dh} within ties or stirrups ^[1] perpendicular to ℓ_{dh} at $s \leq 3d_b$, or (2) enclosed along the bar extension beyond hook including the bend within ties or stirrups ^[1] perpendicular to ℓ_{ext} at $s \leq 3d_b$	0.8
	For 180-degree hooks of No. 11 and smaller bars enclosed along ℓ_{dh} within ties or stirrups ^[1] perpendicular to ℓ_{dh} at $s \leq 3d_b$	
	Other	1.0

^[1]The first tie or stirrup shall enclose the bent portion of the hook within $2d_b$ of the outside of the bend.

^[2] d_b is nominal diameter of hooked bar.

COMMENTARY

hooked bar. For construction purposes, this is not always practicable. The cases where the modification factor ψ_r may be used are illustrated in Fig. R25.4.3.2a and R25.4.3.2b. Figure R25.4.3.2a shows placement of ties or stirrups parallel to the bar being developed along the length of the tail extension of the hook plus bend. This configuration would be typical in a beam-column joint. R25.4.3.2b shows placement of ties or stirrups perpendicular to the bar being developed, spaced along the development length ℓ_{dh} of the hook.




Fig. R25.4.3.2a—Ties or stirrups placed parallel to the bar being developed, spaced along the length of the tail extension of the hook plus bend.

CODE

25.4.3.3 For bars being developed by a standard hook at discontinuous ends of members with both side cover and top (or bottom) cover to hook less than 2-1/2 in., (a) through (c) shall be satisfied:

- (a) The hook shall be enclosed along ℓ_{dh} within ties or stirrups perpendicular to ℓ_{dh} at $s \leq 3d_b$.
- (b) The first tie or stirrup shall enclose the bent portion of the hook within $2d_b$ of the outside of the bend.
- (c) ψ_r shall be taken as 1.0 in calculating ℓ_{dh} in accordance with 25.4.3.1(a), where d_b is the nominal diameter of the hooked bar.

COMMENTARY




Fig. R25.4.3.2b—Ties or stirrups placed perpendicular to the bar being developed, spaced along the development length ℓ_{dh} .

R25.4.3.3 Bar hooks are especially susceptible to a concrete splitting failure if both side cover (perpendicular to plane of hook) and top or bottom cover (in plane of hook) are small (refer to Fig. R25.4.3.3). With minimum confinement provided by concrete, additional confinement provided by ties or stirrups is essential, especially if full bar strength is to be developed by a hooked bar with such small cover. Cases where hooks may require ties or stirrups for confinement are at ends of simply-supported beams, at the free end of cantilevers, and at ends of members framing into a joint where members do not extend beyond the joint. In contrast, if the calculated bar stress is so low that the hook is not needed for bar anchorage, ties or stirrups are not necessary. This provision does not apply for hooked bars at discontinuous ends of slabs where confinement is provided by the slab on both sides and perpendicular to the plane of the hook.

Section 25.7.1.8.4 prohibits reinforcement anchored with a head from being considered as contributing to confinement of hooked bars due to a lack of test data.




Fig. R25.4.3.3—Concrete cover according to 25.4.3.3.

CODE

25.4.4 Development of headed deformed bars in tension

25.4.4.1 Use of a head to develop a deformed bar in tension shall be permitted if conditions (a) through (f) are satisfied:

- (a) Bar shall conform to 20.2.1.6
- (b) Bar size shall not exceed No. 11
- (c) Net bearing area of head A_{brg} shall be at least $4A_b$ for Grade 60 bars, and at least $6A_b$ for Grade 80 and Grade 100 bars
- (d) Concrete shall be normalweight
- (e) Clear cover for bar shall be at least $2d_b$
- (f) Center-to-center spacing between bars shall be at least $3d_b$

25.4.4.2 Development length ℓ_{dt} for headed deformed bars in tension shall be the longest of (a) through (c):

- (a) $\left(\frac{f_y \psi_e \psi_p \psi_o \psi_c}{90 \sqrt{f'_c}} \right) d_b^{1.5}$ with ψ_e , ψ_p , ψ_o , and ψ_c , given in 25.4.4.3
- (b) $8d_b$
- (c) 6 in.

COMMENTARY

R25.4.4 Development of headed deformed bars in tension

R25.4.4.1 As used in this section, development describes cases in which the force in the bar is transferred to the concrete through a combination of a bearing force at the head and bond forces along the bar. In contrast, Chapter 17 anchorage provisions describe cases in which the force in the bar is transferred through bearing to the concrete at the head alone. Headed bars are limited to those types that meet the criteria in 20.2.1.6 for Class HA heads.

The provisions for headed deformed bars were formulated with due consideration of the provisions for anchorage in Chapter 17 (Shao et al. 2016). Chapter 17 contains provisions for headed anchors related to the individual failure modes of concrete breakout, side-face blowout, and pullout. These failure modes were considered in the formulation of 25.4.4.2. The restrictions to maximum bar size of No. 11 and normalweight concrete are based on a lack of data for larger bars or lightweight concrete (Thompson et al. 2005, 2006a,b; Shao et al. 2016). The upper limit of 60,000 psi on f_y that appeared prior to the 2019 Code has been removed.

For bars in tension, heads allow the bars to be developed in a shorter length than required for standard hooks, but otherwise perform in a similar manner (Thompson et al. 2005, 2006a,b; Shao et al. 2016). The head is considered to be part of the bar for the purposes of satisfying the specified cover requirements in 20.5.1.3 and aggregate size requirements of 26.4.2.1(a)(5).

Headed bars with $A_{brg} < 4A_b$ have been used in practice, but their performance is not accurately represented by the provisions in 25.4.4.2, and they should be used only with designs that are supported by test results under 25.4.5. These provisions do not address the design of studs or headed stud assemblies used for shear reinforcement.

R25.4.4.2 The provisions for developing headed deformed bars give the length of bar, ℓ_{dt} , measured from the critical section to the bearing face of the head, as shown in Fig. R25.4.4.2a. The provisions are primarily based on tests of simulated beam-column joints (Shao et al. 2016).

If longitudinal headed deformed bars from a beam, slab, or corbel terminate in a supporting member, such as the column shown in Fig. R25.4.4.2b, the bars should extend through the joint to the far face of the confined core of the supporting member, allowing for cover and avoidance of interference with column reinforcement, even though the resulting anchorage length may exceed ℓ_{dt} . Extending the bar to the far side of the column core helps engage the entire joint in resisting the anchorage forces and thereby improves the performance of the joint.

If closely spaced headed bars are used, the potential for concrete breakout failure exists. For joints as shown in Fig. R25.4.4.2c and R25.4.4.2d, anchorage strengths will be generally higher if the anchorage length is equal to or greater than $d/1.5$ (Eligehausen 2006b), as shown in Fig. R25.4.4.2c,

CODE

COMMENTARY

or by providing reinforcement in the form of hoops and ties to establish a load path in accordance with strut-and-tie modeling principles, as shown in Fig. R25.4.4.2d. Strut-and-tie models should be verified in accordance with Chapter 23. Note that the strut-and-tie models illustrated in Fig. R25.4.4.2c and R25.4.4.2d rely on a vertical strut from a column extending above the joint. Beam-column joints at roof-level and portal frames are vulnerable to joint failure and should be properly detailed to restrain diagonal cracking through the joint and breakout of the bars through the top surface.

For cases where development length cannot be designed in accordance with 25.4.4.2, use of the provisions of Chapter 17 should be considered.




Fig. R25.4.4.2a—Development of headed deformed bars.




Fig. R25.4.4.2b—Headed deformed bar extended to far side of column core with anchorage length that exceeds ℓ_{dt} .

CODE

COMMENTARY




Fig. R25.4.4.2c—Breakout failure precluded in joint by keeping anchorage length greater than or equal to $d/1.5$.




Fig. R25.4.4.2d—Breakout failure precluded in joint by providing transverse reinforcement to enable a strut-and-tie mechanism.

25.4.4.3 For the calculation of ℓ_{dt} , modification factors ψ_e , ψ_p , ψ_o , and ψ_c shall be in accordance with Table 25.4.4.3.

R25.4.4.3 The epoxy factor 1.2 is based conservatively on the value used for epoxy-coated standard hooks. The location factor ψ_o accounts for the confinement provided by the reinforcement within columns and large side cover for other members.

CODE

Table 25.4.4.3—Modification factors for development of headed bars in tension

Modification factor	Condition	Value of factor
Epoxy ψ_e	Epoxy-coated or zinc and epoxy dual-coated reinforcement	1.2
	Uncoated or zinc-coated (galvanized) reinforcement	1.0
Parallel tie reinforcement $\psi_p^{[2,3]}$	$s^{[1]} \geq 8d_b$ or $A_{tr} \geq 0.30A_{hs}$	1.0
	Other	$2 - \frac{s}{8d_b} \leq 1.6$
Location ψ_o	For headed bars: (1) Terminating inside column core with side cover to bar ≥ 2.5 in.; or (2) With side cover to bar $\geq 6d_b$	1.0
	Other	1.25
Concrete strength ψ_c	For $f'_c < 6000$ psi	$f'_c/15,000 + 0.6$
	For $f'_c \geq 6000$ psi	1.0

^[1] s is minimum center-to-center spacing of headed bars.

^[2] d_b is nominal diameter of headed bar.

^[3]Refer to 25.4.4.5.

25.4.4.4 Parallel tie reinforcement confining headed bars in beam-column joints used in the calculation of A_{tr} shall be in accordance with 25.4.4.4.1 through 25.4.4.4.3.

COMMENTARY

The factor ψ_p for headed reinforcement is similar to the confining reinforcement factor for hooked bars (Shao et al. 2016). Parallel ties are more effective for closely-spaced headed bars, and the effects of increasing the area of parallel ties and increasing the spacing of headed bars are not directly additive. Thus, spacing and confinement effects are treated separately for simplicity in design. Test results indicate that only tie or hoop reinforcement parallel to headed bars contributes to anchorage strength and reduces development length (Thompson et al. 2005, 2006a,b).

R25.4.4.4 Reinforcement oriented parallel to the development length of the headed bars, located within the region defined in 25.4.4.4.2 (Fig. R25.4.4.4) contributes to anchorage strength in proportion to its area (Ghimire 2019a,b). This reinforcement serves to tie concrete near the head to concrete on the other side of the failure surface, thus mobilizing additional anchorage strength. With the exception of vertical joint reinforcement in the form of stirrups that are well anchored to the far side of the joint, reinforcement oriented perpendicular to the development length has been shown in a number of cases to be ineffective in improving the anchorage of headed deformed bars (Thompson et al. 2005, 2006a,b). Both legs of individual stirrups and ties parallel to the headed bars contribute to A_{tr} . Section 25.7.1.8.4 prohibits reinforcement anchored with a head from contributing to A_{tr} due to a lack of test data.

CODE

COMMENTARY




Fig. R25.4.4.4—Ties or stirrups placed parallel to the headed beam bars being developed in a beam-column joint that contribute to anchorage strength.

CODE

25.4.4.4.1 Parallel tie reinforcement shall be oriented parallel to ℓ_{dt} and consist of closed stirrups, ties, or hoops.

25.4.4.4.2 Parallel tie reinforcement shall be located within $8d_b$ of the centerline of the headed bar toward the middle of the joint, where d_b is the nominal diameter of the headed bar.

25.4.4.4.3 The area of parallel tie reinforcement, A_{tt} , shall be calculated as the cross-sectional area of all legs of closed stirrups, ties, or hoops comprising the parallel tie reinforcement.

25.4.4.5 For anchorages other than in beam-column joints, tie reinforcement, A_{tt} , shall not be considered.

25.4.4.6 If beam negative moment reinforcement is provided by headed deformed bars that terminate in a joint, the column shall extend above the top of the joint a distance at least the depth h of the joint, where h is the horizontal dimension of the joint in the direction of the forces being considered. Alternatively, the beam reinforcement shall be enclosed by additional vertical joint reinforcement providing equivalent confinement to the top face of the joint.

25.4.5 *Development of mechanically anchored deformed bars in tension*

25.4.5.1 Any mechanical attachment or device capable of developing f_y of deformed bars shall be permitted, provided it is approved by the building official in accordance with **1.10**. Development of deformed bars shall be permitted to consist of a combination of mechanical anchorage plus additional embedment length of the deformed bars between the critical section and the mechanical attachment or device.

25.4.6 *Development of welded deformed wire reinforcement in tension*

25.4.6.1 Development length ℓ_d for welded deformed wire reinforcement in tension measured from the critical section to the end of wire shall be the greater of (a) and (b), where wires in the direction of the development length shall all be deformed D31 or smaller.

- (a) Length calculated in accordance with 25.4.6.2
- (b) 8 in.

25.4.6.2 For welded deformed wire reinforcement, ℓ_d shall be calculated from 25.4.2.3 or 25.4.2.4, times welded deformed wire reinforcement factor ψ_w from 25.4.6.3 or 25.4.6.4. For epoxy-coated welded deformed wire reinforcement,

COMMENTARY

R25.4.4.5 No evidence is available regarding the effect of parallel reinforcement on the development length of headed bars except in beam-column joints.

R25.4.4.6 This provision refers to a corner joint in which beam reinforcement terminates with headed deformed bars. Such joints require confinement of the headed beam bars along the top face of the joint. This confinement can be provided by either: a) a column that extends above the top of the joint; or b) vertical reinforcement hooked around the beam top reinforcing bars and extending downward into the joint in addition to the column longitudinal reinforcement. Detailing guidance and design recommendations for vertical joint reinforcement may be found in **ACI PRC-352**.

R25.4.5 *Development of mechanically anchored deformed bars in tension*

R25.4.5.1 Anchorage of deformed bars through the use of mechanical devices within concrete that do not meet the requirements in **20.2.1.6**, or are not developed in accordance with 25.4.4, may be used if tests demonstrate the ability of the head and bar system to develop or anchor the desired force in the bar, as described in this provision.

R25.4.6 *Development of welded deformed wire reinforcement in tension*

R25.4.6.1 **ASTM A1064** for welded deformed wire reinforcement requires the same strength of the weld as required for welded plain wire reinforcement. Some of the development is assigned to welds and some assigned to the length of deformed wire.

R25.4.6.2 The welded deformed wire reinforcement factor ψ_w is applied to the deformed wire development length calculated from 25.4.2.3 or 25.4.2.4.

Tests (**Bartoletti and Jirsa 1995**) have indicated that epoxy-coated welded deformed wire reinforcement has essentially

CODE

ment meeting 25.4.6.3, it shall be permitted to use $\psi_e = 1.0$ in 25.4.2.3 or 25.4.2.4.

25.4.6.3 For welded deformed wire reinforcement with at least one cross wire within ℓ_d that is at least 2 in. from the critical section, ψ_w shall be the greater of (a) and (b), and need not exceed 1.0:

$$(a) \left(\frac{f_y - 35,000}{f_y} \right)$$

$$(b) \left(\frac{5d_b}{s} \right)$$

where s is the spacing between the wires to be developed.

25.4.6.4 For welded deformed wire reinforcement with no cross wires within ℓ_d or with a single cross wire less than 2 in. from the critical section, ψ_w shall be taken as 1.0.

25.4.6.5 Where any plain wires, or deformed wires larger than D31, are present in the welded deformed wire reinforcement in the direction of the development length, the reinforcement shall be developed in accordance with 25.4.7.

25.4.6.6 Zinc-coated (galvanized) welded deformed wire reinforcement shall be developed in accordance with 25.4.7.

25.4.7 Development of welded plain wire reinforcement in tension

25.4.7.1 Development length ℓ_d for welded plain wire reinforcement in tension measured from the critical section to the outermost cross wire shall be the greater of (a) and (b) and shall require a minimum of two cross wires within ℓ_d .

- (a) Length calculated in accordance with 25.4.7.2
(b) 6 in.

25.4.7.2 ℓ_d shall be the greater of (a) and (b):

- (a) spacing of cross wires + 2 in.
(b) $0.27 \left(\frac{f_y}{\lambda \sqrt{f'_c}} \right) \left(\frac{A_b}{s} \right)$, where s is the spacing between the wires to be developed, and λ is given in Table 25.4.2.5.

COMMENTARY

the same development and splice strengths as uncoated welded deformed wire reinforcement because the cross wires provide the primary anchorage for the wire. Therefore, ψ_e of 1.0 is used for development and splice lengths of epoxy-coated welded deformed wire reinforcement with cross wires within the splice or development length.

R25.4.6.3 Figure R25.4.6.3 shows the development requirements for welded deformed wire reinforcement with one cross wire within the development length.




Fig. R25.4.6.3—Development of welded deformed wire reinforcement.

R25.4.6.5 Deformed wire larger than D31 is treated as plain wire because tests show that D45 wire will achieve only approximately 60% of the bond strength in tension given by Eq. (25.4.2.4a) (Rutledge and DeVries 2002).

R25.4.7 Development of welded plain wire reinforcement in tension

R25.4.7.1 **ASTM A1064** for welded plain wire reinforcement requires the same strength of the weld as required for welded deformed wire reinforcement. All of the development is assigned to the welded cross wires; consequently, welded plain wire reinforcement requires at least two cross wires.

R25.4.7.2 Figure R25.4.7.2 shows the development requirements for welded plain wire reinforcement with development primarily dependent on the location of cross wires.

For welded plain wire reinforcement made with small wires, an embedment of at least two cross wires 2 in. or more beyond the point of critical section is adequate to develop the yield strength of the anchored wires. However, for welded

CODE

COMMENTARY

plain wire reinforcement made with larger closely spaced wires, a longer embedment is required with the development length controlled by 25.4.7.2(b).




Fig. R25.4.7.2—Development of welded plain wire reinforcement.

25.4.8 Development of pretensioned seven-wire strands in tension

R25.4.8 Development of pretensioned seven-wire strands in tension

Development requirements for pretensioned strand are intended to provide bond integrity for the strength of the member. Provisions are based on tests performed on normal-weight concrete members with a minimum cover of 2 in. These tests may not represent the behavior of strand in no-slump concrete. Concrete placement operations should ensure consolidation of concrete around the strand with complete contact between the steel and concrete.

The bond of strand is a function of a number of factors, including the configuration and surface condition of the steel, the stress in the steel, the depth of concrete beneath the strand, and the method used to transfer the force in the strand to the concrete. For bonded applications, quality assurance procedures should be used to confirm that the strand is capable of adequate bond (Rose and Russell 1997; Logan 1997). The precast concrete manufacturer may rely on certification from the strand manufacturer that the strand has bond characteristics that comply with this section.

This section does not apply to plain wires, to end-anchored tendons, or to unstressed strand. The development length for plain wire could be considerably greater due to the absence of mechanical interlock. Flexural bond failure would occur with plain wire when first slip occurred. Nontensioned prestressing steel is sometimes used as integrity reinforcement in precast concrete structures; however, there are limited data available regarding the bond length required to ensure development of the yield strength of the reinforcement (Salmons and McCrate 1977; PCA 1980).

CODE

25.4.8.1 Development length ℓ_d of pretensioned seven-wire strands in tension shall be in accordance with (a) and (b):

$$(a) \ell_d = \left(\frac{f_{se}}{3000} \right) d_b + \left(\frac{f_{ps} - f_{se}}{1000} \right) d_b \quad (25.4.8.1)$$

(b) If bonding of a strand does not extend to end of member, and design includes tension at service loads in the precompressed tension zone, ℓ_d calculated by Eq. (25.4.8.1) shall be doubled.

25.4.8.2 Seven-wire strand shall be bonded at least ℓ_d beyond the critical section except as provided in 25.4.8.3.

25.4.8.3 Embedment less than ℓ_d shall be permitted at a section of a member, provided the design strand stress at that section does not exceed values obtained from the bilinear relationship defined by Eq. (25.4.8.1).

COMMENTARY

R25.4.8.1 The first term in Eq. (25.4.8.1) represents the transfer length of the strand, that is, the distance over which the strand should be bonded to the concrete to develop the effective prestress in the prestressed reinforcement, f_{se} . The second term represents the additional length over which the strand should be bonded so that the stress in the prestressed reinforcement at nominal strength of the member, f_{ps} , may develop.

Exploratory tests (Kaar and Magura 1965) that studied the effect of debonded strand (bond not permitted to extend to the ends of members) on performance of pretensioned girders indicated that the performance of these girders with embedment lengths twice those required by Eq. (25.4.8.1) closely matched the flexural performance of similar pretensioned girders with strand fully bonded to ends of girders. Accordingly, twice the development length is required for strand not bonded through to the end of a member. Subsequent tests (Rabbat et al. 1979) indicated that in pretensioned members designed for zero tension in the concrete under service load conditions (refer to 24.5.2), the development length for debonded strands need not be increased by a factor of 2. For analysis of sections with debonded strands at locations where strand is not fully developed, the procedure outlined in 21.2.3 is provided.

R25.4.8.3 Figure R25.4.8.3 shows the relationship between steel stress and the distance over which the strand is bonded to the concrete represented by Eq. (25.4.8.1). This idealized variation of strand stress may be used for analyzing sections within the development region (Martin and Korkosz 1995; PCI MNL 120). The expressions for transfer length and for the additional bonded length necessary to develop an increase in stress of $(f_{ps} - f_{se})$ are based on tests of members prestressed with clean, 1/4, 3/8, and 1/2 in. diameter strands for which the maximum value of f_{ps} was 275,000 psi (Kaar and Magura 1965; Hanson and Kaar 1959; Kaar et al. 1963).

CODE

COMMENTARY




Fig. R25.4.8.3—Idealized bilinear relationship between steel stress and distance from the free end of strand.

25.4.9 Development of deformed bars and deformed wires in compression

25.4.9.1 Development length ℓ_{dc} for deformed bars and deformed wires in compression shall be the greater of (a) and (b)

- (a) Length calculated in accordance with 25.4.9.2
- (b) 8 in.

25.4.9.2 ℓ_{dc} shall be the greater of (a) and (b), using the modification factors of 25.4.9.3:

- (a) $\left(\frac{f_y \psi_r}{50 \lambda \sqrt{f'_c}} \right) d_b$
- (b) $0.0003 f_y \psi_r d_b$

25.4.9.3 For the calculation of ℓ_{dc} , modification factors shall be in accordance with Table 25.4.9.3, except ψ_r shall be permitted to be taken as 1.0.

R25.4.9 Development of deformed bars and deformed wires in compression

R25.4.9.1 The weakening effect of flexural tension cracks is not present for bars and wires in compression, and usually end bearing of the bars on the concrete is beneficial. Therefore, shorter development lengths are specified for compression than for tension.

R25.4.9.2 The constant 0.0003 has units of in.²/lb.

The term λ is provided in the expression for development in 25.4.9.2 recognizing that there are no known test data on compression development in lightweight concrete but that splitting is more likely in lightweight concrete.

R25.4.9.3 The development length may be reduced 25 percent when the reinforcement is enclosed within closely spaced spirals, ties, or hoops.

CODE

COMMENTARY

Table 25.4.9.3—Modification factors for deformed bars and wires in compression

Modification factor	Condition	Value of factor
Lightweight λ	Lightweight concrete	0.75
	Normalweight concrete	1.0
Confining reinforcement ψ_r	Reinforcement enclosed within (1), (2), (3), or (4): (1) a spiral (2) a circular continuously wound tie with $d_b \geq 1/4$ in. and pitch ≤ 4 in. (3) No. 4 bar or D20 wire ties in accordance with 25.7.2 spaced ≤ 4 in. on center (4) hoops in accordance with 25.7.4 spaced ≤ 4 in. on center	0.75
	Other	1.0

25.4.10 Reduced embedment of straight reinforcement

25.4.10.1 Except as provided in 25.4.10.2, embedment of straight reinforcement less than that prescribed for development shall be permitted if area of reinforcement provided, $A_{s,provided}$, exceeds area of reinforcement required, $A_{s,required}$. Embedment length beyond the critical section shall equal or exceed ℓ_d multiplied by $(A_{s,required})/(A_{s,provided})$, and shall not be less than the applicable minimum development lengths specified in 25.4.2.1(b), 25.4.6.1(b), 25.4.7.1(b), or 25.4.9.1(b).

25.4.10.2 Reduced embedment in accordance with 25.4.10.1 shall not be permitted for (a) through (f)

- (a) At noncontinuous supports
- (b) At locations where anchorage or development for f_y is required
- (c) Where bars are required to be continuous
- (d) For hooked, headed, and mechanically anchored deformed reinforcement
- (e) In seismic-force-resisting systems in structures assigned to Seismic Design Categories C, D, E, or F
- (f) Anchorage of concrete piles and concrete filled pipe piles to pile caps in structures assigned to Seismic Design Categories C, D, E, or F

R25.4.10 Reduced embedment of straight reinforcement

R25.4.10.1 Reduced reinforcement embedment is permitted in limited circumstances.

R25.4.10.2 Embedment of straight bars less than that required for development should not be used if reinforcement is expected to permit redistribution of stress or if ductile behavior is required. Embedment of tension-loaded straight bars in closely spaced groups can result in concrete breakout failure (Chicchi 2020). Reducing bar embedment in such cases greatly increases the likelihood of such failures. Refer to 25.4.1.5. The excess reinforcement factor $(A_{s,required}/A_{s,provided})$, is not applicable for hooked or headed bars, where a reduction in development length with the application of the excess reinforcement factor could result in a potential concrete breakout failure.

Where a flexural member is part of the seismic-force-resisting-system, loads greater than those anticipated in design may cause reversal of moment at supports; some positive reinforcement should be developed into the support. This anchorage is required to ensure ductile response in the event of serious overstress, such as from earthquake or blast. It is not sufficient to use more reinforcement at lower stresses.

The reduction factor based on area is not to be used in those cases where anchorage development for f_y is required. For example, the excess reinforcement factor does not apply for development of shrinkage and temperature reinforcement according to 24.4.3.4 or for development of reinforcement provided according to 7.7.7, 8.7.4.2, 8.8.1.6, 9.7.7, and 9.8.1.6.

CODE

25.4.11 Anchorage of bar groups in tension

25.4.11.1 The design breakout strength of a reinforcing bar group, ϕN_{rg} , shall be greater than or equal to the required strength of the reinforcing bar group. The nominal breakout strength is defined in 25.4.11.2 through 25.4.11.6.

25.4.11.1.1 Beam-column joints designed in accordance with (a), (b) or (c) are deemed to satisfy 25.4.11.

- (a) Joints with hooked bar groups designed in accordance with **Chapter 15**
- (b) Joints with headed bar groups designed in accordance with Chapter 15 and in which the provided embedment length is greater than or equal to the beam effective depth divided by 1.5
- (c) Joints designed in accordance with **18.4.4** or **18.8**

25.4.11.2 The nominal breakout strength of the bar group, N_{rg} , shall be calculated as

$$N_{rg} = N_{cbg} + N_{srg} \quad (25.4.11.2)$$

25.4.11.2.1 Alternatively, it shall be permitted to calculate the nominal breakout strength of the bar group, N_{rg} , based on a design model that results in prediction of strength in substantial agreement with results of comprehensive tests.

25.4.11.3 ϕ shall be determined in accordance with Table 21.2.1(j) for anchorage of reinforcing bars.

25.4.11.4 N_{cbg} shall be calculated according to **17.6.2** with the following modifications:

- (a) Effective embedment depth, h_{ef} , of straight, hooked, or headed reinforcement shall be as defined in **Chapter 2**.
- (b) For the calculation of concrete breakout strength in the anchorage region, it shall be permitted to take k_c in Eq. 17.6.2.2.1 as:
 - (i) 35 for straight reinforcing bars
 - (ii) 40 for hooked and headed reinforcement.
- (c) Alternatively, for the calculation of concrete breakout strength of headed reinforcement in the anchorage region, it shall be permitted to use 5/3 times the value calculated with Eq. 17.6.2.2.3.
- (d) The breakout cracking factor, $\psi_{c,N}$, shall be taken as 1.0.

COMMENTARY

R25.4.11 Anchorage of bar groups in tension

R25.4.11.1 The required strength of a reinforcing bar group depends on the applicable design provisions. Some reinforcing bars are required to develop a force from the applicable load combination, others are required to develop a force associated with f_y , and yet others are required to develop a force associated with $1.25f_y$.

CODE

25.4.11.5 If reinforcement satisfying 25.4.11.6 is distributed within the region extending throughout the projected concrete failure area of the reinforcing bar group, N_{srg} shall be calculated according to Eq. 25.4.11.5. Otherwise, N_{srg} shall be taken as zero.

$$N_{srg} = \rho_t A_{c,eff} f_y \quad (25.4.11.5)$$

COMMENTARY

R25.4.11.5 Section 25.4.11 permits the inclusion of reinforcement in the breakout calculation based on laboratory tests and numerical analysis (Worsfold et al. 2022; Worsfold and Moehle 2023a,b). The limits on the contribution of transverse reinforcement as a function of maximum reinforcement spacing reflect tests of column-foundation joints and special moment frame joints, whereby the closer spacing of confinement reinforcement in special moment frames is correlated with a low likelihood of concrete breakout as a controlling failure mode (Worsfold and Moehle 2023b; Lee et al. 2024). Figure R25.4.11.5a illustrates uplift tension on a bar group terminating in a foundation. The theoretical concrete failure area projecting to the free surface is shown. The strain field associated with this failure area is complex and will produce multiple nested fracture planes prior to formation of the final breakout surface. Therefore, bars located within and adjacent to the bar group contribute to N_{rg} regardless of whether they are developed beyond the theoretical failure surface (Worsfold and Moehle 2023b). In accordance with the definition of $A_{c,eff}$, reinforcement parallel to the developed bars and within a distance $0.75h_{ef}$ from the outside boundary of the bar group is additive to the calculated breakout strength provided the requirements of 25.4.11.6 are met. Where possible, hooked reinforcement should engage perpendicular reinforcement.

Figure R25.4.11.5b illustrates a similar case with haunch reinforcement whereby closed hoops within $0.75h_{ef}$ above and below the primary corbel reinforcement are additive to the calculated breakout strength.

The inclusion of nearby reinforcement in the breakout calculation as provided in 25.4.11.2 is distinct from reinforcement designed to carry the entire anchorage force (anchor reinforcement). Alternatively, anchor reinforcement as provided in 17.5.2.1 could be applied to this condition whereby the breakout strength calculation is avoided. However, the requirements that anchor reinforcement be used exclusively to carry the anchorage tension force and satisfy development length requirements on both sides of the theoretical breakout surface should be considered.

CODE

COMMENTARY




Fig. R25.4.11.5a—Use of shear reinforcement to increase the breakout strength of a group of column bars in tension




Fig. R25.4.11.5b—Use of closed tie reinforcement to increase the breakout strength of corbel primary reinforcement in tension

25.4.11.6 Distributed reinforcement effective for the calculation of N_{srg} shall satisfy (a) through (f):

- (a) Reinforcement shall be parallel to the bar group and located within $A_{c,eff}$.
- (b) If $N_{rg} \leq 2.5N_{cbg}$, reinforcement shall be spaced no greater than $0.5h_{ef}$ in each orthogonal direction.
- (c) If $N_{rg} > 2.5N_{cbg}$, reinforcement shall be spaced no greater than $0.25h_{ef}$ in each orthogonal direction.

CODE

(d) Reinforcement shall extend over at least 90 percent of the embedment depth of the bar group and terminate beyond the end of the bar group.

(e) Reinforcement shall be provided with a head or hook at each end, and hooked bars shall satisfy the requirements for stirrups in 25.7.1.3.

(f) Reinforcing bar diameter shall not exceed the diameter of the smallest bar in the bar group.

25.4.11.7 If the strength in the anchorage region is determined using anchor reinforcement conforming to 17.5.2.1, it shall not be additive to the breakout strength.

25.5—Splices**25.5.1 General**

25.5.1.1 Lap splices shall not be permitted for bars larger than No. 11, except as provided in 25.5.5.3.

25.5.1.2 For contact lap splices, minimum clear spacing between the contact lap splice and adjacent splices or bars shall be in accordance with the requirements for individual bars in 25.2.1.

25.5.1.3 For noncontact splices in flexural members, the transverse center-to-center spacing of spliced bars shall not exceed the lesser of one-fifth the required lap splice length and 6 in.

25.5.1.4 Reduced embedment in accordance with 25.4.10 shall not apply to lap splice lengths.

25.5.1.5 For bars with $f_y \geq 80,000$ psi spaced closer than 6 in. on center, transverse reinforcement shall be provided such that K_{tr} shall not be smaller than $0.5d_b$.

25.5.1.6 Non-contact lap splices for reinforcement in shotcrete shall have clear spacing in accordance with (a) or (b):

(a) For No. 6 and smaller bars, the clear spacing between bars shall be at least greater of $6d_b$ and 2-1/2 in.

(b) For No. 7 and larger bars, the clear spacing shall be established using a shotcrete mockup panel to demonstrate that the reinforcement is properly encased.

COMMENTARY**R25.5—Splices****R25.5.1 General**

Lap splice lengths of longitudinal reinforcement in columns should be calculated in accordance with 10.7.5, 18.7.4.4, and this section.

R25.5.1.1 Because of lack of adequate experimental data on lap splices of No. 14 and No. 18 bars in compression and in tension, lap splicing of these bar sizes is prohibited except as permitted in 25.5.5.3 for compression lap splices of No. 14 and No. 18 bars with smaller bars.

R25.5.1.3 If individual bars in noncontact lap splices are too widely spaced, an unreinforced section is created. Forcing a potential crack to follow a zigzag line (5-to-1 slope) is considered a minimum precaution. The 6 in. maximum spacing is added because most research available on the lap splicing of deformed bars was conducted with reinforcement within this spacing.

R25.5.1.6 and R25.5.1.7 Information on shotcrete mockup panels is provided in ACI PRC-506, and information on evaluating shotcrete is provided in ACI PRC-506.4.

CODE

25.5.1.7 Contact lap splices for reinforcement in shotcrete shall be oriented with the plane of the spliced bars perpendicular to the surface of the shotcrete and approved by the licensed design professional based on a shotcrete mockup panel to demonstrate that the reinforcement is properly encased.

25.5.1.8 Lap splices of bundled bars shall be in accordance with 25.6.1.7.

25.5.2 *Lap splice lengths of deformed bars and deformed wires in tension*

25.5.2.1 Tension lap splice length ℓ_{st} for deformed bars and deformed wires in tension shall be in accordance with Table 25.5.2.1, where ℓ_d shall be in accordance with 25.4.2.1(a).

Table 25.5.2.1—Lap splice lengths of deformed bars and deformed wires in tension

$A_{s,provided}/A_{s,required}^{(1)}$ over length of splice	Maximum percent of A_s spliced within required lap length	Splice type		ℓ_{st}
≥ 2.0	50	Class A	Greater of:	$1.0\ell_d$ and 12 in.
	100	Class B	Greater of:	$1.3\ell_d$ and 12 in.
< 2.0	All cases	Class B		

⁽¹⁾Ratio of area of reinforcement provided to area of reinforcement required by analysis at splice location.

25.5.2.2 If bars of different size are lap spliced in tension, ℓ_{st} shall be the greater of ℓ_d of the larger bar and ℓ_{st} of the smaller bar.

25.5.3 *Lap splice lengths of welded deformed wire reinforcement in tension*

25.5.3.1 Tension lap splice length ℓ_{st} of welded deformed wire reinforcement in tension with cross wires within the lap splice length shall be the greater of $1.3\ell_d$ and 8 in., where ℓ_d is calculated in accordance with 25.4.6.1(a), provided (a) and (b) are satisfied:

- (a) Overlap between outermost cross wires of each reinforcement sheet shall be at least 2 in.

COMMENTARY

R25.5.2 *Lap splice lengths of deformed bars and deformed wires in tension*

R25.5.2.1 Lap splices in tension are classified as Class A or B, with length of lap a multiple of the tensile development length ℓ_d calculated in accordance with 25.4.2.3 or 25.4.2.4. The two-level lap splice requirements encourage splicing bars at points of minimum stress and staggering splices to improve behavior of critical details. For the purpose of calculating ℓ_d for staggered splices, the clear spacing is taken as the minimum distance between adjacent splices, as illustrated in Fig. R25.5.2.1. 

The tension lap splice requirements encourage the location of splices away from regions of high tensile stress to locations where the area of steel provided is at least twice that required by analysis.





Fig. R25.5.2.1—Clear spacing of lap-spliced bars for determination of ℓ_d for staggered splices.

R25.5.3 *Lap splice lengths of welded deformed wire reinforcement in tension*


R25.5.3.1 Splice provisions for welded deformed wire reinforcement are based on available tests (Lloyd and Kesler 1969). Lap splices for welded deformed wire reinforcement meeting the requirements of this provision and 25.5.3.1.1 are illustrated in Fig. R25.5.3.1. If no cross wires are within the lap length, the provisions for deformed wire apply.

CODE

(b) Wires in the direction of the development length shall all be deformed D31 or smaller

COMMENTARY

Lap splice satisfies R25.5.3.1a



Lap splice satisfies R25.5.3.1.1

Fig. R25.5.3.1—Lap splices of welded deformed wire reinforcement.

25.5.3.1.1 If 25.5.3.1(a) is not satisfied, ℓ_{st} shall be calculated in accordance with 25.5.2.

25.5.3.1.2 If 25.5.3.1(b) is not satisfied, ℓ_{st} shall be calculated in accordance with 25.5.4.

25.5.3.1.3 If the welded deformed wire reinforcement is zinc-coated (galvanized), ℓ_{st} shall be calculated in accordance with 25.5.4.

25.5.4 Lap splice lengths of welded plain wire reinforcement in tension

25.5.4.1 Tension lap splice length ℓ_{st} of welded plain wire reinforcement in tension between outermost cross wires of each reinforcement sheet shall be at least the greatest of (a) through (c):

- (a) $s + 2$ in.
- (b) $1.5\ell_d$
- (c) 6 in.

where s is the spacing of cross wires and ℓ_d is calculated in accordance with 25.4.7.2(b).

R25.5.3.1.2 Where any plain wires, or deformed wires larger than D31, are present in the welded deformed wire reinforcement in the direction of the lap splice or where welded deformed wire reinforcement is lap spliced to welded plain wire reinforcement, the reinforcement should be lap spliced in accordance with the plain wire reinforcement lap splice requirements. Deformed wire larger than D31 is treated as plain wire because tests show that D45 wire will achieve only approximately 60 percent of the bond strength in tension given by Eq. (25.4.2.4a) (Rutledge and DeVries 2002).

R25.5.4 Lap splice lengths of welded plain wire reinforcement in tension

R25.5.4.1 The strength of lap splices of welded plain wire reinforcement is dependent primarily on the anchorage obtained from the cross wires rather than on the length of wire in the splice. For this reason, the lap is specified in terms of overlap of cross wires (in inches) rather than in wire diameters or length. The 2 in. additional lap required is to provide adequate overlap of the cross wires and to provide space for satisfactory consolidation of the concrete between cross wires. Research (Lloyd 1971) has shown an increased splice length is required when welded wire reinforcement of large, closely spaced wires is lapped and, as a consequence, additional splice length requirements are provided for this

CODE

25.5.4.2 If $A_{s,provided}/A_{s,required} \geq 2.0$ over the length of the splice, ℓ_{st} measured between outermost cross wires of each reinforcement sheet shall be permitted to be the greater of (a) and (b).

- (a) $1.5\ell_d$
- (b) 2 in.

where ℓ_d is calculated by 25.4.7.2(b).


25.5.5 Lap splice lengths of deformed bars in compression

25.5.5.1 Compression lap splice length ℓ_{sc} of No. 11 or smaller deformed bars in compression shall be calculated in accordance with (a), (b), or (c):

- (a) For $f_y \leq 60,000$ psi: ℓ_{sc} is the longer of $0.0005f_y d_b$ and 12 in.
- (b) For $60,000 \text{ psi} < f_y \leq 80,000$ psi: ℓ_{sc} is the longer of $(0.0009f_y - 24)d_b$ and 12 in.

COMMENTARY


reinforcement in addition to an absolute minimum of 6 in. Splice requirements are illustrated in Fig. R25.5.4.1. If $A_{s,provided}/A_{s,required} \geq 2$ over the length of the splice, ℓ_{st} can be determined from 25.5.4.2.



$$A_{s,provided}/A_{s,required} < 2$$

Fig. R25.5.4.1—Lap splices of plain welded wire reinforcement where $A_{s,provided}/A_{s,required} < 2$.

R25.5.4.2 Where $A_{s,provided}/A_{s,required} \geq 2$, the lap splice for plain welded wire reinforcement is illustrated in Fig. R25.5.4.2.



$$A_{s,provided}/A_{s,required} \geq 2$$

Fig. R25.5.4.2—Lap splices of plain welded wire reinforcement where $A_{s,provided}/A_{s,required} \geq 2$.

R25.5.5 Lap splice lengths of deformed bars in compression

Bond research has been primarily related to bars in tension. Bond behavior of compression bars is not complicated by the problem of transverse tension cracking and thus compression splices do not require provisions as strict as those specified for tension splices.

Lap splice requirements particular to columns are provided in Chapter 10.

R25.5.5.1 Tests (ACI Committee 408 1966; Pfister and Mattock 1963) have shown that splice strengths in compression depend considerably on end bearing and do not increase proportionally in strength when the splice length is doubled. Accordingly, for specified yield strengths above 60,000 psi, compression lap lengths are significantly increased.

CODE

(c) For $f_y > 80,000$ psi, ℓ_{sc} is the longer of $(0.0009f_y - 24)d_b$ and ℓ_{st} calculated in accordance with 25.5.2.1.

For $f_c' < 3000$ psi, the length of lap shall be increased by one-third.

25.5.5.2 Compression lap splices shall not be used for bars larger than No. 11, except as permitted in 25.5.5.3.

25.5.5.3 Compression lap splices of No. 14 or No. 18 bars to No. 11 or smaller bars shall be permitted and shall be in accordance with 25.5.5.4.

25.5.5.4 Where bars of different size are lap spliced in compression, ℓ_{sc} shall be the longer of ℓ_{dc} of larger bar calculated in accordance with 25.4.9.1 and ℓ_{sc} of smaller bar calculated in accordance with 25.5.5.1 as appropriate.

25.5.6 *End-bearing splices of deformed bars in compression*

25.5.6.1 For bars required for compression only, transmission of compressive stress by end bearing of square-cut ends held in concentric contact by a suitable device shall be permitted.

25.5.6.2 End-bearing splices shall be permitted only in members containing closed stirrups, ties, spirals, or hoops.

25.5.6.3 Bar ends shall terminate in flat surfaces within 1.5 degrees of a right angle to the axis of the bars and shall be fitted within 3 degrees of full bearing after assembly.

25.5.7 *Mechanical and welded splices of deformed bars in tension or compression*

25.5.7.1 Mechanical splices shall satisfy the requirements of **ASTM A1034** except as required in 25.5.7.2 and 25.5.7.6. Requirements in this Code shall take precedence over those in ASTM A1034.

25.5.7.2 Mechanical splices shall be classified as Class L, Class G, or Class S in accordance with the requirements of Table 25.5.7.2, with associated prequalification testing requirements specified in 25.5.7.6. Use of mechanical splices shall be in accordance with (a) and (b):

(a) Class L mechanical splices shall not be permitted for use in locations where yielding of reinforcement is expected under applicable load combinations of **5.3**

COMMENTARY

R25.5.5.3 Lap splices are generally prohibited for No. 14 or No. 18 bars. For compression only, however, lap splices are permitted between No. 14 or No. 18 bars and No. 11 or smaller bars.

R25.5.6 *End-bearing splices of deformed bars in compression*

R25.5.6.1 Experience with end-bearing splices has been almost exclusively with vertical bars in columns. If bars are significantly inclined from the vertical, attention is required to ensure that adequate end-bearing contact can be achieved and maintained.

R25.5.6.2 This limitation ensures a minimum shear resistance in sections containing end-bearing splices.

R25.5.6.3 These tolerances represent practice based on tests of full-size members containing No. 18 bars.

R25.5.7 *Mechanical and welded splices of deformed bars in tension or compression*

R25.5.7.1 The mechanical splice requirements of 25.5.7.2 replace the mechanical splice requirements given in ASTM A1034, including classification of mechanical splices and names of classes. The prequalification testing requirements of 25.5.7.6 replace similar testing requirements given in ASTM A1034.

R25.5.7.2 Requirements for three classes of mechanical splices are provided based on **Sharma et al. (2025)**: Class L, Class G, and Class S. These classifications replace the former classifications of Type 1 and Type 2. Additional requirements for mechanical splices used in seismic applications are given in **Chapter 18**. Class L (Limited) mechanical splices are restricted to applications where development of actual yield in the reinforcing bars at the location of the mechanical splice is not anticipated. Applications where Class L mechanical splices are not permitted include, but

CODE

(b) Class L mechanical splices shall not be permitted for splicing the following reinforcement:

- (i) integrity reinforcement
- (ii) reinforcement in regions where moment redistribution has been applied in design
- (iii) reinforcement in regions where moments are determined using the simplified method of analysis of 6.5
- (iv) reinforcement in regions where moments are determined using the direct design method

Table 25.5.7.2 — Mechanical splice requirements

Property	Prequalification tests	Mechanical splice classification		
		Class L	Class G	Class S
		Requirement		
Tensile strength, minimum, and compressive strength, minimum	25.5.7.6(a) and 25.5.7.6(b)	f_u		
Tensile strain, minimum	25.5.7.6(c)	No requirement	2%	6%
Elastic cyclic endurance, minimum	25.5.7.6(d)	No requirement	20 cycles	
Residual slip, maximum	25.5.7.6(e)	No requirement	0.02 in.	
Inelastic cyclic endurance, minimum	25.5.7.6(f)	No requirement		30 cycles

25.5.7.2.1 Where Class S mechanical splices are required, reinforcement shall conform to 20.2.2.5.

COMMENTARY

may not be limited to, locations where bar yielding may occur under non-cyclic loading, where yielding may occur under wind loading as anticipated by the performance-based design provisions of [Appendix B](#), where integrity reinforcement is mechanically spliced, and where design is based on analysis methods that implicitly consider yielding of reinforcement such as moment redistribution, the simplified method of analysis of 6.5, and the direct design method for two-way slabs. Restrictions on use of Class L mechanical splices in seismic applications are given in [Chapter 18](#).

Class G (General) mechanical splices are intended for applications where development of actual yield in the reinforcing bars at the location of the mechanical splice may occur, but where significant inelastic cyclic loading is not anticipated and strain-hardening demands on the reinforcement will be limited. The minimum tensile strain capacity of 2 percent specified for a Class G mechanical splice is intended to develop, under non-cyclic loading, the actual yield strength and a limited degree of strain hardening in the bars being spliced. Restrictions on the use of Class G mechanical splices in seismic applications are given in [Chapter 18](#).

Class S (Special) mechanical splices are intended for applications where development of considerable inelastic strain in the reinforcing bars at the location of the mechanical splice may occur, either monotonically or cyclically, such as under earthquake loads. The minimum tensile strain capacity specified for a Class S mechanical splice is intended to provide strain capacities approaching the specified minimum uniform elongation of the reinforcement. For Class G and Class S mechanical splices, the elastic cyclic testing requirement is intended to provide for limited elastic cyclic endurance. For Class G and Class S mechanical splices, the requirement to assess slip, potentially occurring at the interface between the mechanical splicing device and the reinforcing bars being joined, is intended to control concrete crack widths at service loads and aggregate interlock at factored loads. Control of slip also promotes capacity for cyclic energy dissipation in bars spliced with a Class S mechanical splice, because slip can cause pinching of hysteretic loops under inelastic cyclic loads.

The inelastic cyclic endurance requirement for the Class S mechanical splice is intended to provide an inelastic, yield-reversal cyclic endurance for the mechanical splice comparable to the 5th percentile of the number of cycles to failure of an unspliced bar under similar cyclic inelastic strain loading ([Slavin and Ghannoum 2015](#); [Ghannoum and Slavin 2016](#); [Sokoli et al. 2019](#)).

R25.5.7.2.1 [ASTM A706](#) reinforcement is required to be used in Class S mechanical splices because it is the only reinforcing bar specification that includes requirements for minimum uniform elongation, which equal or exceed the minimum tensile strain requirement in [Table 25.5.7.2](#) for Class S mechanical splices. Additionally, the radius at the deformation base is controlled with [ASTM A706](#) reinforcement, which allows the [ASTM A706](#) reinforcing bar in the

CODE

COMMENTARY

25.5.7.2.2 Reinforcing bars in a Class S mechanical splice shall be longitudinally aligned.

25.5.7.2.3 Test lots for a mechanical splice of a given combination of bar grade and bar size satisfying all Class S prequalification testing requirements shall be deemed to satisfy Class G and Class L prequalification testing requirements for the given combination of bar grade and bar size. Test lots for a mechanical splice of a given combination of bar grade and bar size satisfying all Class G prequalification testing requirements shall be deemed to satisfy Class L prequalification testing requirements for the given combination of bar grade and bar size.

25.5.7.2.4 Test lots for a mechanical splice of a given combination of bar grade and bar size satisfying prequalification testing requirements for a particular Class shall be deemed to satisfy prequalification testing requirements for that Class for lower grade reinforcing bars of the same size.

25.5.7.2.5 Mechanical splices that are prequalified to Type 2 mechanical splice requirements of **ACI CODE-318-19** shall be deemed to satisfy the requirements of Class L mechanical splices, provided that the methods used for prequalification conform to the test methods specified in 20.5.7.6 for Class L mechanical splices.

25.5.7.3 Welded splices shall satisfy (a) through (d):

- (a) The weld in a welded splice shall be proportioned to develop in tension or compression, as required, at least the specified minimum tensile strength of the bars being spliced.
- (b) Welding of reinforcing bars shall conform to **26.6.4**.
- (c) Welded splices shall not be permitted for use in locations where yielding of reinforcement is expected under applicable load combinations of **5.3**.
- (d) Welded splices used in seismic applications shall be in accordance with **18.2.8**.

Class S mechanical splice system to develop the inelastic cyclic endurance specified in Table 25.5.7.2. Reinforcing bars that are manufactured according to any standard lacking these particular requirements, such as **ASTM A615**, **ASTM A955**, **ASTM A996**, and **ASTM A1035**, are not permitted for use in Class S splices because the reinforcing bar itself may not satisfy the Class S tensile strain and cyclic endurance requirements of Table 25.5.7.2. Consequently, where a Class S mechanical splicing device is used with reinforcement other than ASTM A706, the resulting mechanical splice may not satisfy Class S requirements.

R25.5.7.2.2 Use of an aligned configuration of the reinforcing bars being mechanically spliced is intended to minimize effects of eccentricity. The two bars joined with a Class S mechanical splice have longitudinal centerlines aligned. Mechanical splice devices that connect overlapping bars cannot be Class S.

R25.5.7.2.5 Class L mechanical splices have requirements equivalent to Type 2 mechanical splices in the 2019 edition of the Code.

R25.5.7.3 Welded splices are restricted to locations where yielding of reinforcing bars at the location of the welded splice is not anticipated.

A welded splice is primarily intended for No. 6 bars and larger. The requirement to develop at least the specified tensile strength of the bars being spliced is intended to provide sound welding that is also adequate for compression.

While direct butt welds are not required, AWS D1.4 states that wherever practical, direct butt welds are preferable for No. 7 bars and larger.

CODE

25.5.7.4 Mechanical or welded splices need not be staggered except as required by 25.5.7.5.

25.5.7.5 Splices in tension tie members shall be made with a mechanical or welded splice in accordance with 25.5.7. Splices in adjacent bars shall be staggered at least 30 in.

25.5.7.6 Prequalification testing of mechanical splices to demonstrate conformance with the requirements of Table 25.5.7.2 shall be in accordance with (a) through (g):

- (a) Tensile strength and tensile strain shall be determined by monotonic tension tests to fracture. For Class G and Class S mechanical splices, the monotonic tensile test to fracture shall be performed on the test specimen from the elastic endurance test after application of the specified minimum number of elastic endurance cycles and after measurement of residual slip.
- (b) Compressive strength shall be determined by monotonic compression tests, performed on test specimens not subject to any prior testing.
- (c) For Class G and Class S mechanical splices, strain shall be measured and recorded throughout the cyclic endurance test and monotonic tension test. Strain shall be measured in the reinforcing bar adjacent to but not including the mechanical splicing device and related features, and outside of any portion of the reinforcing bar that has been altered by the mechanical splice installation and fabrication. Minimum gauge length for measurement of strain shall be $2d_b$.
- (d) Cycles of loading for the elastic endurance test shall be tension-compression cycles, between $0.95f_y$ in tension and $0.5f_y$ in compression, with forces determined using the nominal area of the reinforcing bar being spliced. The minimum number of elastic load cycles applied shall be in accordance with Table 25.5.7.2. All specimens tested for elastic endurance shall survive the specified minimum number of cycles without fracture. Slip across the mechanical splicing device shall be measured and recorded throughout the cyclic endurance test. The measurement

COMMENTARY

R25.5.7.4 Although mechanical and welded splices need not be staggered, staggering is encouraged and may be necessary to provide for installation of the splice or to meet clear spacing requirements. Staggering splices will also help to avoid creating a discontinuity in the section that could promote the development of a concentrated crack at the discontinuity.

R25.5.7.5 A tension tie member has the following characteristics: member having an axial tensile force sufficient to create tension over the cross section; and limited concrete cover on all sides. Examples of members that may be classified as tension ties are arch ties, hangers carrying load to an overhead supporting structure, and main tension elements in a truss.

In determining if a member should be classified as a tension tie, consideration should be given to the importance, function, proportions, and stress conditions of the member related to the above characteristics. For example, a usual large circular tank, with many bars and with splices well staggered and widely spaced, should not be classified as a tension tie member.

R25.5.7.6 It is anticipated that conformance of a mechanical splicing device with the requirements of Table 25.5.7.2 will be demonstrated by prequalification testing. Applicable test methods may, in part, be found in **ASTM A370** Test Methods and Definitions for Mechanical Testing of Steel Products, **ASTM E8/E8M** Test Methods for Tension Testing of Metallic Materials, and **ASTM E9** Standard Test Methods of Compression Testing of Metallic Materials at Room Temperature. There is no single, consensus-based standard test method that comprehensively addresses laboratory testing related to the requirements given Table 25.5.7.2. These tests are not intended for field or project-specific quality control.

(d) The specified elastic cyclic loading is identical to the Stage 1 elastic cyclic loading provided in **ICC-ES Acceptance Criteria AC133 (2020)**. A common loading rate for the elastic cyclic testing is approximately 4 cycles per minute.

(d and e) The cyclic loading for slip is the same as the Stage 1 elastic cyclic loading provided in AC133 (2020). The maximum limit on slip of 0.016 in. is based on common design practices for crack width control and differs from the 0.012 in. limit in AC133.

(f) During inelastic cycling, the yielding state in the reinforcing bar will alternate between yielding in tension and yielding in compression. Consequently, the inelastic cycles should be applied at a relatively slow rate. Commonly used rates are approximately 0.5 to 1.0 cycles per minute (**Slavin and Ghannoum 2015**).

CODE

gauge length for slip shall include the mechanical splicing device plus d_b to $2d_b$ beyond each end of the mechanical splicing device.

(e) Residual slip shall be determined as the distance between the slip measurement gauge points specified in 25.5.7.6(d) at zero force in the reinforcing bar, taken at the end of unloading from tension upon completion of the last load cycle of the elastic cyclic endurance test specified in 25.5.7.6(d), minus the distance between the same gauge points prior to the application of any load at the start of the first load cycle of the elastic cyclic endurance test.

(f) Cycles of loading for the inelastic cyclic endurance test shall be inelastic strain cycles between 2% strain in tension and 0.5% strain in compression, where the strain shall be measured in the reinforcing bar adjacent to but not including the mechanical splicing device. Clear distance between the face of a test machine grip and each end of the mechanical splicing device shall be no less than $1.5d_b$. Minimum gauge length for measurement of strain shall be $1.5d_b$ in the bar beyond each end of the mechanical splicing device, and the strains measured beyond each end of the mechanical splicing device shall be averaged. It shall be permitted to laterally brace the test specimen, provided that the lateral braces do not attract axial forces from the test loads applied to the test specimen. The minimum number of inelastic load cycles applied shall be in accordance with Table 25.5.7.2. Each inelastic cyclic endurance test shall be performed on a test specimen not subject to any prior testing.

(g) One lot of tests shall be performed for each applicable test type for a given combination of mechanical splice class, bar grade, and bar size. Each lot of tests shall consist of five tests of the same test type on replicate mechanical splice specimens of the same combination of mechanical splice device, bar grade, and bar size. The results of the tests for a given test lot are acceptable if all five tests satisfy the applicable requirements of Table 25.5.7.2. If only four of the five tests in the test lot satisfy the applicable requirements of Table 25.5.7.2, then two additional tests of that test type shall be performed on additional replicate mechanical splice specimens. If both additional tests satisfy the applicable requirements of Table 25.5.7.2, the test lot is acceptable. For a mechanical splicing device to be acceptable for use as a given class of mechanical splice on a given combination of bar grade and bar size, all lots of tests for test types applicable to the given class of mechanical splice shall be acceptable.

COMMENTARY**25.6—Bundled reinforcement****25.6.1 Nonprestressed reinforcement**

25.6.1.1 Groups of parallel reinforcing bars bundled in contact to act as a unit shall be limited to four in any one bundle.

R25.6—Bundled reinforcement**R25.6.1 Nonprestressed reinforcement**

R25.6.1.1 The Code phrase “bundled in contact to act as a unit” is intended to preclude bundling more than two bars in the same plane. Typical bundle shapes in cross section are triangular, L-shaped, or square-shaped patterns for three- or

CODE

25.6.1.2 Bundled bars shall be enclosed within transverse reinforcement. Bundled bars in compression members shall be enclosed by transverse reinforcement at least No. 4 in size.

25.6.1.3 Bars larger than a No. 11 shall not be bundled in beams.

25.6.1.4 Individual bars within a bundle terminated within the span of flexural members shall terminate at different points with at least $40d_b$ stagger.

25.6.1.5 Development length for individual bars within a bundle, in tension or compression, shall be that of the individual bar, increased 20% for a three-bar bundle, and 33% for a four-bar bundle.

25.6.1.6 A unit of bundled bars shall be treated as a single bar with an area equivalent to that of the bundle and a centroid coinciding with that of the bundle. The diameter of the equivalent bar shall be used for d_b in (a) through (e):

- (a) Spacing limitations based on d_b
- (b) Cover requirements based on d_b
- (c) Spacing and cover values in 25.4.2.3
- (d) Confinement term in 25.4.2.4
- (e) ψ_e factor in 25.4.2.5

25.6.1.7 Lap splices of bars in a bundle shall be based on the lap splice length required for individual bars within the bundle, increased in accordance with 25.6.1.5. Individual bar splices within a bundle shall not overlap. Entire bundles shall not be lap spliced.

25.6.2 Post-tensioning ducts

25.6.2.1 Bundling of post-tensioning ducts shall be permitted if shown that concrete can be satisfactorily placed and if provision is made to prevent the prestressed reinforcement from breaking through the duct.

COMMENTARY

four-bar bundles. As a practical caution, bundles more than one bar deep in the plane of bending should not be hooked or bent as a unit. Where end hooks are required, it is preferable to stagger the individual bar hooks within a bundle.

R25.6.1.3 A limitation that bars larger than No. 11 not be bundled in beams is a practical limit for application to building size members. (AASHTO LRFDUS Article 5.9.4 permits two-bar bundles for No. 14 and No. 18 bars in bridge girders.) Conformance to the crack control requirements of 24.3 will effectively preclude bundling of bars larger than No. 11 as tension reinforcement.

R25.6.1.4 Bond research (ACI Committee 408 1966) has shown that cutoff points within bundles should be staggered.

R25.6.1.5 An increased development length for individual bars is required when three or four bars are bundled together. The extra extension is needed because the grouping makes it more difficult to mobilize bond resistance from the core between the bars.

The development of bundled bars by a standard hook of the bundle is not covered by the provisions of 25.4.3.

R25.6.1.6 Although splice and development lengths of bundled bars are a multiple of the diameter of the individual bars being spliced increased by 20 or 33 percent, as appropriate, it is necessary to use an equivalent diameter of the entire bundle derived from the equivalent total area of bars for determining the spacing and cover values in 25.4.2.3, the confinement term, $[(c_b + K_{tr})/d_b]$, in 25.4.2.4, and the ψ_e factor in 25.4.2.5. For bundled bars, bar diameter d_b outside the brackets in the expressions of 25.4.2.3 and of Eq. (25.4.2.4a) is that of a single bar.

R25.6.1.7 The increased length of lap required for bars in bundles is based on the reduction in the exposed perimeter of the bars. Only individual bars are lap spliced along the bundle.

R25.6.2 Post-tensioning ducts

R25.6.2.1 Where ducts for prestressing reinforcement in a beam are arranged closely together vertically, provisions should be made to prevent the prestressed reinforcement from breaking through the duct when tensioned. Horizontal arrangement of ducts should allow proper placement of concrete. A clear spacing of one and one-third times the

CODE

25.7—Transverse reinforcement

25.7.1 *Stirrups*

25.7.1.1 Stirrups shall extend as close to the extreme compression and tension surfaces of the member as cover requirements and proximity of other reinforcement permits and shall be anchored at both ends. Where used as shear reinforcement, stirrups shall extend a distance d from extreme compression fiber.

25.7.1.2 Between anchored ends, each bend in the continuous portion of a single or multiple U-stirrup and each bend in a closed stirrup shall enclose a longitudinal bar or strand.

25.7.1.3 Anchorage of deformed bar and wire with one or more bends shall be in accordance with (a), (b), or (c):

- (a) For No. 5 bar and D31 wire, and smaller, and for No. 6 through No. 8 bars with $f_{yt} \leq 40,000$ psi, a standard hook around longitudinal reinforcement
- (b) For No. 6 through No. 8 bars with $f_{yt} > 40,000$ psi, a standard hook around a longitudinal bar plus an embedment between midheight of the member and the outside end of the hook equal to or greater than $0.014d_b f_{yt} / (\lambda \sqrt{f'_c})$, with λ as given in Table 25.4.3.2
- (c) In joist construction, for No. 4 bar and D20 wire and smaller, a standard hook

25.7.1.4 Anchorage of each leg of welded wire reinforcement forming a single U-stirrup shall be in accordance with (a) or (b):

COMMENTARY

nominal maximum size of the coarse aggregate, but not less than 1 in., has proven satisfactory.

Where concentration of tendons or ducts tends to create a weakened plane in the concrete cover, reinforcement should be provided to control cracking.

R25.7—Transverse reinforcement

R25.7.1 *Stirrups*

R25.7.1.1 Stirrup legs should be extended as close as practicable to the compression face of the member because, near ultimate load, the flexural tension cracks penetrate deeply toward the compression zone.

It is essential that transverse reinforcement be developed on both sides of the shear plane. This generally requires a hook, head, or bend at the end of the reinforcement as provided by this section.

R25.7.1.3 Straight deformed bar and wire anchorage is not permitted because it is difficult to hold such a stirrup in position during concrete placement. Moreover, the lack of a standard stirrup hook may make the stirrup ineffective as it crosses shear cracks near the end of the stirrup.

For a No. 5 or D31 or smaller stirrup, anchorage is provided by a standard hook, as defined in 25.3.2, hooked around a longitudinal bar.

For a No. 6, No. 7, or No. 8 stirrup with f_{yt} of only 40,000 psi, a standard stirrup hook around a longitudinal bar provides sufficient anchorage. For a No. 6, No. 7, or No. 8 stirrup with higher strength, the embedment should be checked. A 135-degree or 180-degree hook is preferred, but a 90-degree hook may be used provided the free end of the 90-degree hook is extended the full 12 bar diameters as required in 25.3.2. Because it is not possible to bend a No. 6, No. 7, or No. 8 stirrup tightly around a longitudinal bar and due to the force in a bar with a design stress greater than 40,000 psi, stirrup anchorage depends on both the type of hook and whatever development length is provided. A longitudinal bar within a stirrup hook limits the width of any flexural cracks, even in a tension zone. Because such a stirrup hook cannot fail by splitting parallel to the plane of the hooked bar, the hook strength as used in 25.4.3.1(a) has been adjusted to reflect cover and confinement around the stirrup hook.

In joists, a small bar or wire can be anchored by a standard hook not engaging longitudinal reinforcement, allowing a continuously bent bar to form a series of single-leg stirrups along the length of the joist.

R25.7.1.4 The requirements for anchorage of welded wire reinforcement stirrups are illustrated in Fig. R25.7.1.4.

CODE

- (a) Two longitudinal wires spaced at a 2 in. spacing along the member at the top of the U
- (b) One longitudinal wire located not more than $d/4$ from the compression face and a second wire closer to the compression face and spaced not less than 2 in. from the first wire. The second wire shall be permitted to be located on the stirrup leg beyond a bend, or on a bend with an inside diameter of at least $8d_b$.

COMMENTARY




Fig. R25.7.1.4—Anchorage in compression zone of welded wire reinforcement U-stirrups.

25.7.1.5 Anchorage of each end of a single leg stirrup of welded wire reinforcement shall be with two longitudinal wires at a minimum spacing of 2 in. in accordance with (a) and (b):

- (a) Inner longitudinal wire at least the greater of $d/4$ or 2 in. from $d/2$
- (b) Outer longitudinal wire at tension face shall not be farther from the face than the portion of primary flexural reinforcement closest to the face

R25.7.1.5 Welded wire reinforcement for shear reinforcement is commonly used in the precast, prestressed concrete industry. The rationale for acceptance of straight sheets of welded wire reinforcement as shear reinforcement is presented in a report by the [Joint PCI/WRI Ad Hoc Committee on Welded Wire Fabric for Shear Reinforcement \(1980\)](#).

The provisions for anchorage of single-leg welded wire reinforcement in the tension face emphasize the location of the longitudinal wire at the same depth as the primary flexural reinforcement to avoid a splitting problem at the level of the tension reinforcement. Figure R25.7.1.5 illustrates the anchorage requirements for single-leg welded wire reinforcement. For anchorage of single-leg welded wire reinforcement, the Code permits hooks and embedment length in the compression and tension faces of members (refer to 25.7.1.3(a) and 25.7.1.4), and embedment only in the compression face (refer to 25.7.1.3(b)). This section provides for anchorage of straight, single-leg, welded wire reinforcement using longitudinal wire anchorage with adequate embedment length in compression and tension faces of members.

CODE

COMMENTARY




Fig. R25.7.1.5—Anchorage of single-leg welded wire reinforcement for shear.

25.7.1.6 Stirrups used for torsion or integrity reinforcement shall be closed stirrups perpendicular to the axis of the member. Where welded wire reinforcement is used, transverse wires shall be perpendicular to the axis of the member. Such stirrups shall be anchored by (a) or (b):

- (a) Ends shall terminate with 135-degree standard hooks around a longitudinal bar
- (b) In accordance with 25.7.1.3(a) or (b) or 25.7.1.4, where the concrete surrounding the anchorage is restrained against spalling by a flange or slab or similar member


R25.7.1.6 Both longitudinal and closed transverse reinforcement are required to resist the diagonal tension stresses due to torsion. The stirrups should be closed because inclined cracking due to torsion may occur on all faces of a member.

In the case of sections subjected primarily to torsion, the concrete side cover to the stirrups spalls off at high torsional moments (Mitchell and Collins 1976). This renders lap-spliced stirrups ineffective, leading to a premature torsional failure (Behera and Rajagopalan 1969). In such cases, closed stirrups should not be made up of pairs of U-stirrups lapping one another.


When a rectangular beam fails in torsion, the corners of the beam tend to spall off due to the inclined compressive stresses in the concrete diagonals of the space truss changing direction at the corner as shown in Fig. R25.7.1.6(b). In tests (Mitchell and Collins 1976), closed stirrups anchored by 90-degree hooks failed when this occurred. For this reason, 135-degree standard hooks or seismic hooks are preferable for torsional stirrups in all cases. In regions where this spalling is prevented by an adjacent slab or flange, 25.7.1.6(a) relaxes this requirement and allows 90-degree hooks because of the added confinement from the slab (refer to Fig. R25.7.1.6(a)).

CODE

COMMENTARY



(a) Sectional elevation



(b) Detail at corner

Fig. R25.7.1.6—Spalling of corners of beams subjected to torsion.

25.7.1.6.1 Stirrups used for torsion or integrity reinforcement shall be permitted to be made up of two pieces of reinforcement: a single U-stirrup anchored according to 25.7.1.6(a) closed by a crosstie where the 90-degree hook of the crosstie shall be restrained against spalling by a flange or slab or similar member.

R25.7.1.6.1 Figure R25.7.1.6.1 shows an example of a two-piece stirrup that satisfies the requirement of 25.7.1.6.1. The 90-degree hook of the cap tie is located on the slab side so that it is better confined. Pairs of U-stirrups lapping one another as defined in 25.7.1.7 are not permitted in perimeter or spandrel beams. In the event of damage to the side concrete cover, the top longitudinal reinforcement may tend to tear out of the concrete and will not be adequately restrained by the exposed lap splice of the stirrup. Thus, the top longitudinal reinforcement will not provide the catenary action needed to bridge over a damaged region. Further, lapped U-stirrups will not be effective at high torsional moments as discussed in R25.7.1.6.

CODE

COMMENTARY




Fig. R25.7.1.6.1—Example of a two-piece stirrup that complies with the requirements of 25.7.1.6.1.

25.7.1.7 Except where used for torsion, integrity reinforcement, or at beam ends in intermediate or special moment frames, closed stirrups are permitted to be made using pairs of U-stirrups spliced to form a closed unit where lap lengths are at least $1.3\ell_d$. In members with a total depth of at least 18 in., such splices with $A_b f_{yt} \leq 9000$ lb per leg shall be considered adequate if stirrup legs extend the full available depth of member.

R25.7.1.7 Requirements for lapping of double U-stirrups to form closed stirrups control over the lap splice provisions of 25.5.2. Figure R25.7.1.7 illustrates closed stirrup configurations created with lap splices.




Fig. R25.7.1.7—Closed stirrup configurations.

25.7.1.8 Stirrups anchored with a head

R25.7.1.8 Stirrups anchored with a head

25.7.1.8.1 Stirrups anchored with a head conforming to 20.2.1.6 shall be permitted if 25.7.1.8.2 and 25.7.1.8.3 are satisfied, except as prohibited by 25.7.1.8.4.

R25.7.1.8.1 Tests of beams have demonstrated that heads can be an effective alternative to standard hooks for anchoring shear reinforcement when detailed in accordance with these provisions (Al-Sabawy et al. 2020; Yang et al. 2021).

These provisions do not address headed shear stud reinforcement conforming to 20.4.

25.7.1.8.2 If stirrups are anchored with a head, (a) through (c) shall be satisfied:

CODE

- (a) Stirrup shall be fabricated from a deformed bar conforming to 20.2.1.3
- (b) The deformed bar shall be a No. 9 or smaller, except in foundations with overall depth h greater than 48 in., where the deformed bar shall be a No. 11 or smaller
- (c) Concrete shall be normalweight

25.7.1.8.3 Stirrups anchored with a head shall be secured to prevent movement during concrete placement and arranged to satisfy (a) through (e):

- (a) Clear concrete side cover to a stirrup leg terminating with a head shall be at least $8d_b$, where d_b is the nominal diameter of the stirrup
- (b) At least one longitudinal bar shall be located between the side of a stirrup leg terminating with a head and any surface of the member parallel to the stirrup leg
- (c) Except in foundations with overall depth h greater than 48 in., the end of each stirrup leg terminating with a head shall be in contact with a longitudinal bar
- (d) Center-to-center spacing of stirrup legs terminating with a head shall be at least $6d_b$, where d_b is the nominal diameter of the stirrup
- (e) The embedment length between midheight of the member and the bearing face of the head shall be at least $0.014d_b f_y t / \sqrt{f'_c}$.


COMMENTARY

R25.7.1.8.3 To avoid side-face blowout failures, a minimum side cover of $8d_b$ is required for stirrup legs terminating with a head, and at least one longitudinal bar is required within that side cover. These requirements can be satisfied when headed deformed bars are used as through-thickness reinforcement in slabs or foundations or in combination with hooked stirrups in beams (Fig. R25.7.1.8.3). If inclined crack widths are a serviceability concern, stirrup legs anchored with hooks should be placed along the side faces of the member (Fig. R25.7.1.8.3(c)).


While contact with longitudinal reinforcement improves anchorage, physical limitations may prevent the bottom of stirrup legs terminating with a head from being secured to a longitudinal bar in foundations with overall depths h greater than 48 in.

CODE


COMMENTARY



(a) Headed stirrups in a mat foundation



(b) Headed U-shaped stirrup in a beam in combination with a closed stirrup



(c) Headed single-leg stirrups in a beam in combination with a closed stirrup

Fig. R25.7.1.8.3—Permissible headed shear reinforcement details.

CODE

25.7.1.8.4 Stirrups anchored with a head are prohibited in applications (a) through (e):

- (a) An alternative to, or component of, closed stirrups, ties, or hoops
- (b) Torsion reinforcement
- (c) Integrity reinforcement
- (d) Confining reinforcement for hooked bars or parallel ties for headed bars
- (e) Confining reinforcement for straight bar development or lap splices

25.7.2 Ties

25.7.2.1 Ties shall consist of a closed loop of deformed bar with spacing in accordance with (a) and (b):

- (a) Clear spacing of at least $(4/3)d_{agg}$
- (b) Center-to-center spacing shall not exceed the least of $16d_b$ of longitudinal bar, $48d_b$ of tie bar, and smallest dimension of member

25.7.2.2 Diameter of tie bar shall be at least (a) or (b):

- (a) No. 3 enclosing No. 10 or smaller longitudinal bars
- (b) No. 4 enclosing No. 11 or larger longitudinal bars or bundled longitudinal bars

25.7.2.2.1 As an alternative to deformed bars, deformed wire or welded wire reinforcement of equivalent area to that required in 25.7.2.1 shall be permitted subject to the requirements of Table 20.2.2.4(a).

25.7.2.3 Rectilinear ties shall be arranged to satisfy (a) and (b):

- (a) Every corner and alternate longitudinal bar shall have lateral support provided by the corner of a tie with an included angle of not more than 135 degrees
- (b) No unsupported bar shall be farther than 6 in. clear on each side along the tie from a laterally supported bar

COMMENTARY

R25.7.1.8.4 Headed stirrups are prohibited in applications that require the bars to be continuous around or near the perimeter of a cross section, including closed stirrups, ties, and hoops; stirrups used to confine bars being developed; or stirrups used for torsion or integrity reinforcement. If a closed stirrup has interior legs that are used to resist shear, the interior legs are permitted to terminate with a head (Fig. R25.7.1.8.3(c)).

R25.7.2 Ties

R25.7.2.2 These provisions apply to cross-ties as well as ties.

R25.7.2.3 The maximum permissible included angle of 135 degrees and the exemption of bars located within 6 in. clear on each side along the tie from adequately tied bars are illustrated in Fig. R25.7.2.3a. Limited tests (Pfister 1964) on full-size, axially-loaded, tied columns containing full-length bars (without splices) showed that ties on alternate longitudinal bars within 6 in. clear of a laterally supported longitudinal bar are adequate in columns subjected to axial force.

Continuously wound bars or wires can be considered as ties, provided their pitch and area are at least equivalent to the area and spacing of separate ties. Anchorage at the end of a continuously wound bar or wire should be by a standard hook as for separate bars or by one additional turn of the tie pattern (refer to Fig. R25.7.2.3b). A circular, continuously wound bar or wire is considered a spiral if it conforms to 25.7.3; otherwise, it is considered a tie.

CODE

COMMENTARY







Fig. R25.7.2.3a—Illustrations to clarify measurements between laterally supported column bars and rectilinear tie anchorage.

CODE

COMMENTARY




Fig. R25.7.2.3b—Continuous tie anchorage.

25.7.2.3.1 Anchorage of rectilinear ties shall be provided by standard hooks that conform to 25.3.2 and engage a longitudinal bar. A tie shall not be made up of interlocking headed deformed bars.

25.7.2.4 Circular ties shall be permitted where longitudinal bars are located around the perimeter of a circle.

25.7.2.4.1 Anchorage of individual circular ties shall be in accordance with (a) through (c):

- (a) Ends shall overlap by at least 6 in.
- (b) Ends shall terminate with standard hooks in accordance with 25.3.2 that engage a longitudinal bar
- (c) Overlaps at ends of adjacent circular ties shall be staggered around the perimeter enclosing the longitudinal bars

R25.7.2.3.1 Standard tie hooks are intended for use with deformed bars only and should be staggered where possible.

R25.7.2.4 While the transverse reinforcement in members with longitudinal bars located around the periphery of a circle can be either spirals or circular ties, spirals are usually more effective.

R25.7.2.4.1 Vertical splitting and loss of tie restraint are possible where the overlapped ends of adjacent circular ties are anchored at a single longitudinal bar. Adjacent circular ties should not engage the same longitudinal bar with end hook anchorages (refer to Fig. R25.7.2.4.1).

CODE

COMMENTARY




Fig. R25.7.2.4.1—Circular tie anchorage.

25.7.2.5 Ties to resist torsion shall be perpendicular to the axis of the member anchored by either (a) or (b):

- (a) Ends shall terminate with 135-degree standard hooks or seismic hooks around a longitudinal bar
- (b) In accordance with 25.7.1.3(a) or (b) or 25.7.1.4, where the concrete surrounding the anchorage is restrained against spalling

R25.7.2.5 Refer to R25.7.1.6.

25.7.3 Spirals

25.7.3.1 Spirals shall consist of evenly spaced continuous bar or wire with clear spacing conforming to (a) and (b):

- (a) At least the greater of 1 in. and $(4/3)d_{agg}$
- (b) Not greater than 3 in.

25.7.3.2 For cast-in-place construction, spiral bar or wire diameter shall be at least 3/8 in.

25.7.3.3 Except for transverse reinforcement in deep foundations, the volumetric spiral reinforcement ratio ρ_s shall satisfy Eq. (25.7.3.3)

$$\rho_s \geq 0.45 \left(\frac{A_g}{A_{ch}} - 1 \right) \frac{f'_c}{f_{yt}} \quad (25.7.3.3)$$

where the value of f_{yt} shall not be taken greater than 100,000 psi.

R25.7.3 Spirals

R25.7.3.1 Spirals should be held firmly in place, at proper pitch and alignment, to prevent displacement during concrete placement.

R25.7.3.2 For practical considerations in cast-in-place construction, the minimum diameter of spiral reinforcement is 3/8 in. (No. 3 deformed or plain bar, or D11 deformed or W11 plain wire).

Standard spiral sizes are 3/8, 1/2, and 5/8 in. diameter for hot-rolled or cold-drawn material, plain or deformed.

R25.7.3.3 The effect of spiral reinforcement in increasing the strength of the concrete within the core is not fully realized until the column has been subjected to a load and deformation sufficient to cause the concrete shell outside the core to spall off. The amount of spiral reinforcement required by Eq. (25.7.3.3) is intended to provide additional strength for concentrically loaded columns equal to or slightly greater than the strength lost when the shell spalls off. The deriva-

CODE

25.7.3.4 Spirals shall be anchored by 1-1/2 extra turns of spiral bar or wire at each end.

COMMENTARY

tion of Eq. (25.7.3.3) is given by **Richart (1933)**. Tests and experience show that columns containing the amount of spiral reinforcement required by this section exhibit considerable toughness and ductility. Research (**Richart et al. 1929**; Richart 1933; **Pessiki et al. 2001**; **Saatcioglu and Razvi 2002**) has also indicated that up to 100,000 psi yield strength reinforcement can be effectively used for confinement.

R25.7.3.4 Spiral anchorage is illustrated in Fig. R25.7.3.4.




Fig. R25.7.3.4—Spiral anchorage.

25.7.3.5 Spirals are permitted to be spliced by (a) or (b):

- (a) Mechanical or welded splices in accordance with 25.5.7
- (b) Lap splices in accordance with 25.7.3.6 for f_{yt} not exceeding 60,000 psi

25.7.3.6 Spiral lap splices shall be at least the greater of 12 in. and the lap length in Table 25.7.3.6.

CODE

COMMENTARY

Table 25.7.3.6—Lap length for spiral reinforcement

Reinforcement	Coating	Ends of lapped spiral bar or wire	Lap length, in.
Deformed bar	Uncoated or zinc-coated (galvanized)	Hook not required	$48d_b$
	Epoxy-coated or zinc and epoxy dual-coated	Hook not required	$72d_b$
		Standard hook of 25.3.2 ^[1]	$48d_b$
Deformed wire	Uncoated	Hook not required	$48d_b$
	Epoxy-coated	Hook not required	$72d_b$
		Standard hook of 25.3.2 ^[1]	$48d_b$
Plain bar	Uncoated or zinc-coated (galvanized)	Hook not required	$72d_b$
		Standard hook of 25.3.2 ^[1]	$48d_b$
Plain wire	Uncoated	Hook not required	$72d_b$
		Standard hook of 25.3.2 ^[1]	$48d_b$

^[1] Hooks shall be embedded within the core confined by the spiral.

25.7.4 Hoops

25.7.4.1 Hoops shall consist of a continuous closed tie or continuously wound tie having seismic hooks at both ends that conform to 25.3.4. A hoop shall not be made up of interlocking headed deformed bars.

25.7.4.2 It shall be permitted to overlap hoops.

R25.7.4 Hoops

R25.7.4.1 Refer to R25.7.2.4.

R25.7.4.2 Overlapping hoops may be required in boundary elements of special structural walls depending on the longitudinal reinforcement layout and the boundary element dimensions (refer to 18.10.6.4f).

25.8—Post-tensioning anchorages and couplers

25.8.1 Anchorages and couplers for tendons shall develop at least 95% of f_{pu} when tested in an unbonded condition, without exceeding anticipated set.

R25.8—Post-tensioning anchorages and couplers

R25.8.1 The required strength of the tendon-anchorage or tendon-coupler assemblies for both unbonded and bonded tendons, when tested in an unbonded state, is based on 95% of the specified tensile strength of the prestressing reinforcement in the test. The prestressing reinforcement is required to comply with the minimum provisions of the applicable ASTM standards as prescribed in 20.3.1. The specified strength of anchorages and couplers exceeds the maximum design strength of the prestressing reinforcement by a substantial margin and, at the same time, recognizes the stress-riser effects associated with most available post-tensioning anchorages and couplers. Anchorage and coupler strength should be attained with a minimum amount of permanent deformation and successive set, recognizing that some deformation and set will occur when testing to failure.

CODE

25.8.2 Anchorages and couplers for bonded tendons shall be located so that 100% of f_{pu} shall be developed at critical sections after the post-tensioned reinforcement is bonded in the member.

25.8.3 In unbonded construction subject to repetitive loads, the possibility of fatigue of prestressed reinforcement in anchorages and couplers shall be considered.

25.8.4 Couplers shall be placed at locations approved by the licensed design professional and enclosed in housings long enough to permit necessary movements.

25.9—Anchorage zones for post-tensioned tendons

25.9.1 General

25.9.1.1 Anchorage regions of post-tensioned tendons shall consist of two zones, (a) and (b):

- (a) The local zone shall be assumed to be a rectangular prism (or equivalent rectangular prism for circular or oval anchorages) of concrete immediately surrounding the anchorage device and any confining reinforcement
- (b) The general zone includes the local zone and shall be assumed to be the portion of the member through which the concentrated prestressing force is transferred to the concrete and distributed more uniformly across the section

COMMENTARY

Tendon assemblies should conform to the 2 percent elongation requirements in **ACI SPEC-423.7**.

Static and fatigue test methods for anchorage and couplers are provided in **ICC-ES Acceptance Criteria AC303 (2011)**.

R25.8.2 Anchorages and couplers for bonded tendons that develop less than 100% of the specified tensile strength of the prestressing reinforcement should be used only where the bond transfer length between the anchorage or coupler and critical sections equals or exceeds that required to develop the prestressed reinforcement strength. This bond length may be calculated based on the results of tests of bond characteristics of non-tensioned prestressing strand (**Salmons and McCrate 1977**; **PCA 1980**), or bond tests on other prestressing reinforcement, as appropriate.

R25.8.3 A discussion on fatigue loading is provided in **ACI PRC-215**.

Detailed recommendations on tests for static and cyclic loading conditions for tendons and anchorage fittings of unbonded tendons are provided in **ACI PRC-423.3-17** (Section 4.1.3) and **ACI SPEC-301-20** (Section 15.2.2).

R25.9—Anchorage zones for post-tensioned tendons

R25.9.1 General

The detailed provisions in the AASHTO LRFD Bridge Design Specifications (**AASHTO LRFDUS**) for analysis and reinforcement detailing of post-tensioned anchorage zones are considered to satisfy the more general requirements of this Code. In the specific areas of anchorage device evaluation and acceptance testing, this Code references the detailed AASHTO provisions.

R25.9.1.1 Based on St. Venant's principle, the extent of the anchorage zone may be estimated as approximately equal to the largest dimension of the cross section. Local zones and general zones are shown in Fig. R25.9.1.1a.

When anchorage devices located away from the end of the member are tensioned, large local tensile stresses are generated ahead of and behind the device. These tensile stresses are induced by incompatibility of deformations. The entire shaded region shown in Fig. R25.9.1.1b should be considered in the design of the general zone.

CODE

COMMENTARY





Fig. R25.9.1.1a—Local and general zones.



Section through slab at anchorage

Fig. R25.9.1.1b—Local and general zones for anchorage device located away from the end of a member.

25.9.1.2 The local zone shall be designed in accordance with 25.9.3.

25.9.1.3 The general zone shall be designed in accordance with 25.9.4.

25.9.1.4 Compressive strength of concrete required at time of post-tensioning shall be specified as required by 26.10.

25.9.1.5 Stressing sequence shall be considered in the design process and specified as required by 26.10.

R25.9.1.5 The sequence of anchorage device stressing can have a significant effect on the general zone stresses. Therefore, it is important to consider not only the final stage

CODE

25.9.2 Required strength

25.9.2.1 Factored prestressing force at the anchorage device, P_{pu} , shall exceed the least of (a) through (c), where 1.2 is the load factor from **5.3.15**:

- (a) $1.2(0.94f_{py})A_{ps}$
- (b) $1.2(0.80f_{pu})A_{ps}$
- (c) Maximum jacking force designated by the supplier of anchorage devices multiplied by 1.2

25.9.3 Local zone

25.9.3.1 The design of local zone in post-tensioned anchorages shall meet the requirements of (a), (b), or (c):

- (a) Monostrand or single 5/8 in. or smaller diameter bar anchorage devices shall meet the bearing resistance and local zone requirements of **ACI SPEC-423.7**
- (b) Basic multistrand anchorage devices shall meet the bearing resistance requirements of **AASHTO LRFD Bridge Design Specifications**, Article 5.8.4.4.2, except that the load factors shall be in accordance with 5.3.15 and ϕ shall be in accordance with **21.2.1**
- (c) Special anchorage devices shall satisfy the tests required in **AASHTO LRFD Bridge Design Specifications**, Article 5.8.4.4.3, and described in **AASHTO LRFD Bridge Construction Specifications**, Article 10.3.2.3

25.9.3.2 Where special anchorage devices are used, supplementary skin reinforcement shall be provided in

COMMENTARY

of a stressing sequence with all tendons stressed, but also intermediate stages during construction. The most critical bursting forces caused by each of the sequentially post-tensioned tendon combinations, as well as that of the entire group of tendons, should be taken into account.

R25.9.2 Required strength

R25.9.2.1 The factored prestressing force is the product of the load factor and the maximum prestressing force permitted. The maximum permissible tensile stresses during jacking are defined in **20.3.2.5.1**.

R25.9.3 Local zone

The local zone resists very high local stresses introduced by the anchorage device and transfers them to the remainder of the anchorage zone. The behavior of the local zone is strongly influenced by the specific characteristics of the anchorage device and its confining reinforcement, and is less influenced by the geometry and loading of the overall structure. Local-zone design sometimes cannot be completed until specific anchorage devices are selected. If special anchorage devices are used, the anchorage device supplier should furnish test information to demonstrate that the device is satisfactory under Article 10.3.2.3 of the **AASHTO LRFD Bridge Construction Specifications (LRFD CONS)** and provide information regarding necessary conditions for use of the device. The main considerations in local-zone design are the effects of high bearing pressure and the adequacy of any confining reinforcement provided to increase concrete bearing resistance.

CODE

addition to the confining reinforcement specified for the anchorage device.

25.9.3.2.1 Supplementary skin reinforcement shall be similar in configuration and at least equivalent in volumetric ratio to any supplementary skin reinforcement used in the qualifying acceptance tests of the anchorage device.

25.9.4 General zone**COMMENTARY**

R25.9.3.2.1 Skin reinforcement is placed near the outer faces in the anchorage zone to limit local crack width and spacing. Reinforcement in the general zone for other actions (such as shrinkage and temperature) may be used in satisfying the supplementary skin reinforcement requirement. Determination of the supplementary skin reinforcement depends on the anchorage device hardware used and frequently cannot be determined until the specific anchorage devices are selected.

R25.9.4 General zone

Within the general zone, the assumption that plane sections remain plane is not valid. Tensile stresses that can be caused by the tendon anchorage device, including bursting, spalling, and edge tension, as shown in Fig. R25.9.4, should be considered in design. In addition, the compressive stresses immediately ahead of the local zone should be checked (Fig. R25.9.1.1b).




Fig. R25.9.4—Tensile stress zones within the general zone.

25.9.4.1 The extent of the general zone is equal to the largest dimension of the cross section. In the case of slabs with anchorages or groups of anchorages spaced along the slab edge, the depth of the general zone shall be taken as the spacing of the tendons.

R25.9.4.1 The depth of the general zone in slabs is defined in AASHTO LRFD Bridge Design Specifications (**LRFDUS**), Article 5.9.5.6 as the spacing of the tendons (Fig. R25.9.4.1). Refer to 25.9.4.4.6 for monostrand anchorages.

CODE

COMMENTARY




Fig. R25.9.4.1—Dimensions of general zone in post-tensioned slab.

25.9.4.2 For anchorage devices located away from the end of a member, the general zone shall include the disturbed regions ahead of and behind the anchorage devices.

25.9.4.3 Analysis of general zones

25.9.4.3.1 Methods (a) through (c) shall be permitted for design of general zones:

- (a) The strut-and-tie method in accordance with **Chapter 23**
- (b) Linear stress analysis, including finite element analysis or equivalent
- (c) Simplified equations in **AASHTO LRFD Bridge Design Specifications**, Article 5.8.4.5, except where restricted by 25.9.4.3.2

The design of general zones by other methods shall be permitted, provided that the specific procedures used for design result in prediction of strength in substantial agreement with results of comprehensive tests.

R25.9.4.2 The dimensions of the general zone for anchorage devices located away from the end of the member are defined in Fig. R25.9.1.1b.

R25.9.4.3 Analysis of general zones

R25.9.4.3.1 The design methods include those procedures for which guidelines have been given in AASHTO LRFDUS and **Breen et al. (1994)**. These procedures have been shown to be conservative predictors of strength compared to test results (Breen et al. 1994). The use of the strut-and-tie method is especially helpful for general zone design (Breen et al. 1994). In many anchorage applications, where substantial or massive concrete regions surround the anchorages, simplified equations based on AASHTO LRFDUS and Breen et al. (1994) can be used except in the cases noted in 25.9.4.3.2.

Values for the magnitude of the bursting force, T_{burst} , and for its centroidal distance from the major bearing surface of the anchorage, d_{burst} , may be estimated from Eq. (R25.9.4.3.1a) and (R25.9.4.3.1b), respectively. The terms used in these equations are shown in Fig. R25.9.4.3.1 for a prestressing force with a small eccentricity. In the application of these equations, the specified stressing sequence should be considered if more than one tendon is present.

$$T_{burst} = 0.25 \sum P_{pu} \left(1 - \frac{h_{anc}}{h} \right) \quad (\text{R25.9.4.3.1a})$$

$$d_{burst} = 0.5(h - 2e_{anc}) \quad (\text{R25.9.4.3.1b})$$

where $\sum P_{pu}$ is the sum of the P_{pu} forces from the individual tendons; h_{anc} is the depth of the anchorage device or single group of closely spaced devices in the direction considered; and e_{anc} is the eccentricity (always taken as positive) of the

CODE

COMMENTARY

anchorage device or group of closely spaced devices with respect to the centroid of the cross section (Fig. R25.9.4.3.1).

Anchorage devices should be treated as closely spaced if their center-to-center spacing does not exceed 1.5 times the width of the anchorage device in the direction considered.




Fig. R25.9.4.3.1—Definition of terms used to define the general zone.

25.9.4.3.2 Simplified equations as permitted by 25.9.4.3.1(c) shall not be used for the design of a general zone if any of the situations listed in (a) through (g) occur:

- (a) Member cross sections are nonrectangular
- (b) Discontinuities in or near the general zone cause deviations in the force flow path
- (c) Minimum edge distance is less than 1.5 times the anchorage device lateral dimension in that direction
- (d) Multiple anchorage devices are used in other than one closely spaced group
- (e) Centroid of the tendons is located outside the kern
- (f) Angle of inclination of the tendon in the general zone is less than -5 degrees from the centerline of axis of the member, where the angle is negative if the anchor force points away from the centroid of the section
- (g) Angle of inclination of the tendon in the general zone is greater than $+20$ degrees from the centerline of axis of the member, where the angle is positive if the anchor force points towards the centroid of the section

25.9.4.3.3 Three-dimensional effects shall be considered in design and analyzed by (a) or (b):

- (a) Three-dimensional analysis procedures
- (b) Approximated by considering the summation of effects for two orthogonal planes

25.9.4.4 Reinforcement limits

25.9.4.4.1 Tensile strength of concrete shall be neglected in calculations of reinforcement requirements.

R25.9.4.3.2 The simplified equations in the **AASHTO LRFDUS** are not applicable in several common situations listed in 25.9.4.3.2. In these cases, a detailed analysis is required. In addition, in the post-tensioning of thin sections, flanged sections, or irregular sections, or where the tendons have appreciable curvature within the general zone, more general procedures such as those of AASHTO LRFDUS Articles 5.8.2.7 and 5.8.3 are required. Detailed recommendations for design principles that apply to all design methods are given in Article 5.9.5.6.5b of the AASHTO LRFDUS.

Groups of monostrand tendons with individual monostrand anchorage devices are often used in beams. If a beam has a single anchorage device or a single group of closely spaced anchorage devices, the use of simplified equations such as those given in R25.9.4.3.1 is permitted, unless 25.9.4.3.2 governs. More complex conditions can be designed using the strut-and-tie method. Detailed recommendations for use of such models are given in AASHTO LRFDUS and **Breen et al. (1994)**.

R25.9.4.3.3 The provision for three-dimensional effects is to ensure that the effects perpendicular to the main plane of the member, such as bursting forces in the thin direction of webs or slabs are considered. In many cases, these effects can be determined independently for each direction, but some applications require a full three-dimensional analysis (for example, diaphragms for the anchorage of external tendons).

R25.9.4.4 Reinforcement limits

CODE

25.9.4.4.2 Reinforcement shall be provided in the general zone to resist bursting, spalling, and longitudinal edge tension forces induced by anchorage devices, as applicable. Effects of abrupt changes in section and stressing sequence shall be considered.

COMMENTARY

R25.9.4.4.2 In some cases, reinforcement requirements cannot be determined until specific tendon and anchorage device layouts are selected. Design and approval responsibilities should be clearly assigned in the construction documents.

Abrupt changes in section can cause substantial deviation in force paths. These deviations can greatly increase tensile forces, as shown in Fig. R25.9.4.4.2.




Fig. R25.9.4.4.2—Effect of cross section change.

25.9.4.4.3 For anchorage devices located away from the end of the member, bonded reinforcement shall be provided to transfer at least $0.35P_{pu}$ into the concrete section behind the anchor. Such reinforcement shall be placed symmetrically around the anchorage device and shall be developed both behind and ahead of the anchorage device.

R25.9.4.4.3 Where anchorages are located away from the end of a member, local tensile stresses are generated behind these anchorages (Fig. R25.9.1.1b) due to compatibility of deformations ahead of and behind the anchorages. Bonded tie-back reinforcement parallel to the tendon is required in the immediate vicinity of the anchorage to limit the extent of cracking behind the anchorage. The requirement of $0.35P_{pu}$ was derived using 25% of the unfactored prestressing force being resisted by reinforcement at $0.6f_y$, considering a load factor of 1.2. Therefore, the full yield strength of the reinforcement, f_y , should be used in calculating the provided capacity.

CODE

25.9.4.4.4 If tendons are curved in the general zone, bonded reinforcement shall be provided to resist radial and splitting forces, except for monostrand tendons in slabs or where analysis shows reinforcement is not required.

25.9.4.4.5 Reinforcement with a nominal tensile strength equal to 2 percent of the factored prestressing force shall be provided in orthogonal directions parallel to the loaded face of the anchorage zone to limit spalling, except for monostrand tendons in slabs or where analysis shows reinforcement is not required.

25.9.4.4.6 For monostrand anchorage devices for 1/2 in. or smaller diameter strands in normalweight concrete slabs, reinforcement satisfying (a) and (b) shall be provided in the anchorage zone, unless a detailed analysis in accordance with 25.9.4.3 shows that this reinforcement is not required:

(a) Two horizontal bars at least No. 4 in size shall be provided within the local zone parallel to the slab edge ahead of the bearing face of the anchorage device. They shall be permitted to be in contact with the bearing face of the anchorage device, the center of the bars shall be no farther than 4 in. ahead of the bearing face of the device, and the bars shall extend at least 6 in. either side of the outer edges of the device.

(b) If the center-to-center spacing of anchorage devices is 12 in. or less, the anchorage devices shall be considered as a group. For each group of six or more anchorage devices, at least $n + 1$ hairpin bars or closed stirrups at least No. 3 in size shall be provided, where n is the number of anchorage devices. One hairpin bar or stirrup shall be placed between adjacent anchorage devices and one on each side of the group. The hairpin bars or stirrups shall be placed with the horizontal legs extending into the slab perpendicular to the edge. The center line of the vertical leg of the hairpin bars, or the vertical leg of stirrups closest to the anchorage device, shall be placed $3h/8$ to $h/2$ ahead of the bearing face of the anchorage device. Hairpin bars or stirrups shall be detailed in accordance with 25.7.1.1 and 25.7.1.2.

COMMENTARY

R25.9.4.4.5 The spalling force for tendons for which the centroid lies within the kern of the section may be estimated as 2 percent of the total factored prestressing force, except for multiple anchorage devices with center-to-center spacing greater than 0.4 times the depth of the section.

R25.9.4.4.6 For monostrand slab tendons, the anchorage-zone minimum reinforcement requirements are based on the recommendations of [Breen et al. \(1994\)](#) and confirmed based on analysis of other test results by [Roberts-Wollmann and Wollmann \(2008\)](#). Typical details are shown in Fig. R25.9.4.4.6. For slabs not thicker than 8 in., with groups of anchors requiring hairpins, the bars parallel to the loaded face can satisfy 25.9.4.4.6(a) and also provide anchorage for the hairpin bars. Thicker slabs require two bars for 25.9.4.4.6 (a) and two additional bars to provide anchorage for the hairpins in accordance with 25.7.1.2. The horizontal bars parallel to the edge required by 25.9.4.4.6(a) should be continuous where possible.

The tests on which the recommendations of Breen et al. (1994) were based were limited to anchorage devices for 1/2 in. diameter, Grade 270 strand, and unbonded tendons in normalweight concrete. For larger strand anchorage devices or for use in lightweight concrete slabs, ACI Committee 423 recommends that the amount and spacing of reinforcement should be conservatively adjusted to provide for the larger anchorage force and smaller splitting tensile strength of lightweight concrete ([ACI PRC-423.3](#)).


ACI PRC-423.3 and Breen et al. (1994) both recommend that hairpin bars also be furnished for anchorages located within 12 in. of slab corners to resist edge tension forces. The meaning of “ahead of” in 25.9.4.4.6 is illustrated in Fig. R25.9.1.1b.

In those cases where multistrand anchorage devices are used for slab tendons, all provisions of 25.9.4 are to be satisfied.

CODE


For slab with $h > 8$ in., provide #4 or larger straight bars parallel to slab edge, in contact with or not farther than 4 in. ahead of bearing face of anchorage device

No. 3 or larger hairpins required if $s \leq 12$ in.




(a) Plan view

COMMENTARY



(b) Sectional A-A for slabs with $h > 8$ in.



(c) Section A-A for slabs with $h \leq 8$ in.

Fig. R25.9.4.4.6—Anchorage zone reinforcement for groups of 1/2 in. or smaller diameter tendons in slabs (other reinforcement not shown).

25.9.4.5 Limiting stresses in general zones

25.9.4.5.1 Maximum design tensile stress in reinforcement at nominal strength shall not exceed the limits in Table 25.9.4.5.1.

Table 25.9.4.5.1—Maximum design tensile stress in reinforcement

Type of reinforcement	Maximum design tensile stress
Nonprestressed reinforcement	f_y
Bonded, prestressed reinforcement	f_{py}
Unbonded, prestressed reinforcement	$f_{se} + 10,000$

25.9.4.5.2 Compressive stress in concrete at nominal strength shall not exceed $0.7\lambda f'_{ci}$, where λ is defined in 19.2.4.

R25.9.4.5 Limiting stresses in general zones

R25.9.4.5.1 The value for maximum design tensile stress of bonded prestressed reinforcement is limited to the yield strength of the prestressing reinforcement because Eq. (20.3.2.3.1) may not apply to these nonflexural applications. The value for unbonded prestressed reinforcement is based on 20.3.2.4.1, but limited for these short-length, nonflexural applications.

R25.9.4.5.2 Some inelastic deformation of concrete within general zones is expected because anchorage zone design is based on a strength approach. Unless shown by tests, the λ factor for lightweight concrete should be applied to reflect a lower tensile strength, which is an indirect factor in limiting compressive stresses, as well as the wide scatter and brittleness exhibited in some lightweight concrete anchorage zone tests.

CODE

25.9.4.5.3 If concrete is confined by spirals or hoops and the effect of confining reinforcement is documented by tests and analysis, it shall be permitted to use an increased value of compressive stress in concrete when calculating the nominal strength of the general zone.

25.9.4.5.4 Prestressing reinforcement shall not be stressed until compressive strength of concrete, as indicated by tests of cylinders cured in a manner consistent with curing of the member, is at least 2500 psi for single-strand or bar tendons or at least 4000 psi for multistrand tendons unless 25.9.4.5.5 is satisfied.

25.9.4.5.5 Provisions of 25.9.4.5.4 need not be satisfied if (a) or (b) is satisfied:

- (a) Oversized anchorage devices are used to compensate for a lower concrete compressive strength
- (b) Prestressing reinforcement is stressed to no more than 50% of the final prestressing force

25.9.5 Reinforcement detailing

25.9.5.1 Selection of reinforcement size, spacing, cover, and other details for anchorage zones shall make allowances for tolerances on fabrication and placement of reinforcement; for the size of aggregate; and for adequate placement and consolidation of the concrete.

COMMENTARY

R25.9.4.5.3 For well-confined concrete, the effective compressive strength may be increased (Breen et al. 1994). Test results given in Breen et al. (1994) indicate that the compressive stress introduced by auxiliary prestressing applied perpendicular to the axis of the main tendons can be effective in increasing anchorage zone strength.

R25.9.4.5.4 To limit early shrinkage cracking, monostrand tendons are sometimes stressed at concrete strengths less than 2500 psi. In such cases, either oversized monostrand anchorages are used, or the strands are stressed in stages, often to levels one-third to one-half of the final prestressing force as permitted by 25.9.4.5.5.

CHAPTER 26—CONSTRUCTION DOCUMENTS AND INSPECTION

CODE

COMMENTARY

26.1—Scope

R26.1—Scope

This chapter establishes the minimum requirements for information that must be included in the construction documents as applicable to the project. The requirements include information developed in the structural design that must be conveyed to the contractor, provisions directing the contractor on required quality, and inspection requirements to verify compliance with the construction documents.

This chapter is directed to the licensed design professional to address the necessary design and construction requirements for the contractor to achieve compliance with the Code. The contractor should not be required to read and interpret the Code.

A general reference in the construction documents requiring compliance with the Code or references to specific Code provisions should be avoided because it is the intention of the Code that all necessary provisions be appropriately restated in the construction documents. Reference to ACI and ASTM standards as well as to other documents is expected.

The provisions in this chapter for inclusion in construction documents are not intended as an all-inclusive list; additional items may be applicable to the Work or required by the building official. **ACI 301** is a reference construction specification that is written to be consistent with the requirements of the Code.

26.1.1 This chapter addresses (a) through (c):

- (a) Design information that the licensed design professional shall specify in the construction documents, if applicable.
- (b) Compliance requirements that the licensed design professional shall specify in the construction documents, if applicable.
- (c) Inspection requirements that the licensed design professional shall specify in the construction documents, if applicable.

R26.1.1

(a) and (b) Except for the inspection requirements of 26.13, the provisions of this chapter are organized into design information and compliance requirements.

Design information is project specific and developed during the structural design. It describes the basis of the design or provides information regarding the construction of the Work. Only design information that is applicable to the Work need be provided.

Compliance requirements are general provisions that provide a minimum acceptable level of quality for construction of the Work. The licensed design professional is not required to incorporate verbatim the compliance requirements into the construction documents. Some of these requirements may not be applicable to a specific project. Construction documents that incorporate the minimum applicable compliance requirements of this chapter are considered to comply with the Code, even if the requirements are stated differently, exceed these minimum requirements, or provide more detail.

(c) Section 26.13 provides inspection provisions to be used in the absence of general building code inspection provisions. These inspection requirements are intended to provide verification that the Work complies with the construction documents.

The inspection requirements of the governing jurisdiction or the general building code take precedence over those included in this chapter. **ACI PRC-311.4** provides

CODE

26.2—Design criteria

26.2.1 Design information:

- (a) Name and year of issue of the Code, general building code, and any supplements governing design.
- (b) Loads used in design.
- (c) Portion of the design delegated to the contractor including applicable design criteria.

26.2.2 Compliance requirements:

- (a) Design delegated to the contractor shall be performed by a specialty engineer.
- (b) The contractor's specialty engineer, relying on the documents identifying the portion of delegated design, shall produce a design that is compatible with the construction documents and the design criteria provided by the licensed design professional in charge of the overall design.
- (c) The contractor shall submit necessary information to the licensed design professional to confirm that the specialty engineer complied with the documents identifying the portion of the delegated design.

26.3—Member information

26.3.1 Design information:

- (a) Member size, location, and related tolerances.
- (b) Members to be constructed using shotcrete.
- (c) Identify structural members for which modulus of elasticity testing of concrete mixtures is required.

26.3.2 Compliance requirements:

- (a) Use of shotcrete for structural members not identified in the construction documents as required to be placed by shotcrete shall be permitted in accordance with the project contract documents.

26.4—Concrete materials, mixture requirements, and grouts

26.4.1 Concrete materials

26.4.1.1 Cementitious materials

26.4.1.1.1 Compliance requirements:

- (a) Cementitious materials shall conform to the specifications in Table 26.4.1.1.1(a), except as permitted in 26.4.1.1.1(b).

COMMENTARY

guidance for inspection of concrete construction, and **ACI SPEC-311.6** is a reference specification for testing services for ready-mixed concrete.

R26.2—Design criteria

R26.2.1

- (a) and (b) Refer to the applicable version of the documents that govern the design including essential loading information, such as gravity and lateral loading, to be included in the construction documents.
- (c) Examples of design criteria include dimensions, loads, and assumptions used that may affect the portion of the design delegated to the contractor.

R26.3—Member information

R26.3.1(a) Construction tolerances for member size and location can be incorporated in construction documents by referring to **ACI SPEC-117** for cast-in-place construction or to **ACI ITG-7** for precast construction. Specific project tolerances that are more restrictive or that are not covered in these references should be included in the construction documents.

R26.3.2(a) If the contractor submits a request to use shotcrete for portions of the structure, the licensed design professional should make the contractor aware that the proposal must take into consideration provisions governing shotcrete listed in **R4.2.1.1**.

R26.4—Concrete materials, mixture requirements, and grouts

R26.4.1 Concrete materials

R26.4.1.1 Cementitious materials

R26.4.1.1.1

- (a) There are two types of ground-glass pozzolans that conform to **ASTM C1866**, Types GE and GS. Type GE

CODE

Table 26.4.1.1(a)—Specifications for cementitious materials

Cementitious material	Specification
Portland cement	ASTM C150
Blended hydraulic cements	ASTM C595, excluding Type IS (≥ 70) and Type IT ($S \geq 70$)
Expansive hydraulic cement	ASTM C845
Hydraulic cement	ASTM C1157
Fly ash and natural pozzolan	ASTM C618
Slag cement	ASTM C989
Silica fume	ASTM C1240
Ground-glass pozzolan	ASTM C1866
Blended supplementary cementitious materials	ASTM C1697

(b) Alternative cementitious materials shall be permitted if approved by the licensed design professional and the building official. Approval shall be based upon test data documenting that the proposed concrete mixture made with the alternative cement meets the performance requirements for the application including structural, fire, and durability.

COMMENTARY

ground-glass pozzolan has a low total equivalent alkali content typically ranging from 0 to 1%, reported as $\text{Na}_2\text{O}_{\text{eq}}$, while Type GS ground-glass pozzolan has a high total equivalent alkali content typically ranging from 10 to 15%, reported as $\text{Na}_2\text{O}_{\text{eq}}$. Refer to 26.4.2.1(a)(11) for restrictions on the use of Type GS ground-glass pozzolan in concrete to be placed in W1 or W2 exposures.

(b) Provisions for strength and durability in [Chapter 19](#) and many requirements in Chapter 26 are based on test data and experience using concretes made with cementitious materials meeting the specifications in Table 26.4.1.1(a). Some alternative cements may not be suitable for use in structural concrete covered by the Code. Therefore, requirements are included for evaluating the suitability of alternative cements. Recommendations for concrete properties to be evaluated are discussed in [Becker et al. \(2019\)](#), [ACI ITG-10](#), and [ACI ITG-10.1](#).

In addition to test data, documentation of prior successful use of the proposed alternative cement in structural concrete for conditions with essentially equivalent performance requirements as those of the project can be helpful to the licensed design professional determining whether to allow use of the material. As with all new technologies, a project owner should be informed of the risks and rewards.

26.4.1.2 Aggregates**26.4.1.2.1 Compliance requirements:**

- (a) Aggregates shall conform to (1) or (2):
- (1) Normalweight aggregate: [ASTM C33](#).
 - (2) Lightweight aggregate: [ASTM C330](#).
- (b) Aggregates not conforming to ASTM C33 or ASTM C330 are permitted if they have been shown by test or actual service to produce concrete of adequate strength and durability and are approved by the building official.

(c) Crushed hydraulic-cement concrete or recycled aggregate shall be permitted if approved by the licensed design professional and the building official based on documentation that demonstrates compliance with (1) and (2).

- (1) Concrete incorporating the specific aggregate proposed for the Work has been demonstrated to provide the mechanical properties and durability required in structural design.

R26.4.1.2 Aggregates**R26.4.1.2.1**

(b) Aggregates conforming to ASTM specifications are not always economically available and, in some instances, materials that do not conform to ASTM C33 or C330 may have a documented history of satisfactory performance under similar exposure. Such nonconforming materials are permitted if acceptable evidence of satisfactory performance is provided.

(c) The Code requires that concrete made with crushed hydraulic-cement concrete or recycled aggregate be specifically approved for use in a particular project. Properties of fresh and hardened concrete made with these aggregates are influenced by the nature, quality, and variability of the source concrete that is crushed to produce aggregate; nature and variability of the waste-stream from

CODE

(2) A testing program to verify aggregate consistency and a quality control program to achieve consistency of properties of the concrete are conducted throughout the duration of the project.

COMMENTARY

which recycled aggregate is extracted; and the grading, proportions, and uniformity of the resulting aggregate.

ASTM C33 notes that use of such aggregates “may require some additional precautions.” Areas of special concern include evidence of alkali-silica reactivity, chloride content, and sulfate content of concrete. The Code requires documentation to verify that concrete made with crushed hydraulic-cement concrete or recycled aggregate can consistently provide the mechanical properties and durability required in design. Properties of concrete made with crushed hydraulic-cement concrete or recycled aggregate can be significantly more variable than those of comparable concretes made with conventional normal-weight aggregates. (Bezerra Cabral et al. 2010). Such properties may have been calculated or assumed in the design process, but may not have been specified in contract documents. Specific criteria for approval of concrete made with recycled aggregates including crushed hydraulic-cement concrete are expected to be unique to each project and set of exposure conditions. The project-specific test program and acceptance criteria should be established by the licensed design professional.

ACI PRC-555 provides information on issues that should be considered in verifying required performance.

26.4.1.3 Mineral fillers**26.4.1.3.1 Compliance requirements:**

(a) Mineral fillers shall conform to **ASTM C1797**.

R26.4.1.3 Mineral fillers**R26.4.1.3.1**

(a) Mineral fillers are finely ground products derived from aggregate that can be used in self-consolidating concrete or in any concrete mixture to improve the properties of fresh and hardened concrete by optimizing particle packing. ASTM C1797 defines Types A and B mineral fillers derived from carbonate aggregate and Type C mineral fillers derived from quarried stone of any mineralogy. Refer to 26.4.2 for restrictions on use of carbonate-based mineral filler in concrete exposed to sulfates.

26.4.1.4 Water**26.4.1.4.1 Compliance requirements:**

(a) Mixing water shall conform to **ASTM C1602**.

R26.4.1.4 Water

R26.4.1.4.1 Potable water is acceptable for use as mixing water for making concrete. Excessive impurities in mixing water from non-potable sources may affect setting time, concrete strength, and volume stability, and may cause efflorescence or corrosion of reinforcement.

ASTM C1602 permits the use of potable water without testing and includes methods for qualifying nonpotable sources of water, such as from concrete production operations, with consideration of effects on setting time and strength. Testing frequencies are established to ensure continued monitoring of water quality.

ASTM C1602 includes optional limits for chlorides, sulfates, alkalis, and solids in mixing water that can be invoked if appropriate.

CODE

26.4.1.5 *Admixtures*

26.4.1.5.1 Compliance requirements:

- (a) Admixtures shall conform to (1) through (4):
- (1) Water reduction and setting time modification: **ASTM C494**.
 - (2) Air entrainment: **ASTM C260**.
 - (3) Inhibiting chloride-induced corrosion: **ASTM C1582**.

(b) Admixtures that do not conform to the specifications in 26.4.1.5.1(a) shall be permitted if approved by the licensed design professional prior to use.

(c) Admixtures used in concrete containing expansive cements conforming to **ASTM C845** shall be compatible with the cement and produce no deleterious effects.

26.4.1.6 *Steel fiber reinforcement*

26.4.1.6.1 Compliance requirements:

- (a) Steel fiber reinforcement used for shear resistance shall satisfy (1) and (2):
- (1) Be deformed and conform to **ASTM A820**.
 - (2) Have a length-to-diameter ratio of at least 50 and not exceeding 100.

26.4.2 *Concrete mixture requirements*

26.4.2.1 Design information:

(a) Requirements (1) through (13) for each concrete mixture, based on assigned exposure classes or design of members:

- (1) Members to be constructed using each concrete mixture
- (2) Minimum specified compressive strength of concrete, f'_c .
- (3) Minimum modulus of elasticity of concrete, E_c , if specified in accordance with **19.2.2.2**.
- (4) Test age, if different from 28 days, for demonstrating compliance with f'_c and E_c if specified.
- (5) Maximum w/cm applicable to most restrictive assigned durability exposure class from **19.3.2.1**.

COMMENTARY

R26.4.1.5 *Admixtures*

R26.4.1.5.1

(a) ASTM C494 includes Type S—specific performance admixtures—that can be specified if performance characteristics not listed in 26.4.1.5.1(a) are desired, such as viscosity-modifying admixtures. The basic requirement for a Type S admixture is that it will not have adverse effects on the properties of concrete when tested in accordance with ASTM C494. Meeting the requirements of Type S does not ensure that the admixture will perform its described function. The manufacturer of an admixture presented as conforming to Type S should be required to provide data that the product will meet the performance claimed.

The specification for producing flowing concrete, **ASTM C1017**, was withdrawn by ASTM in 2022. ASTM C494 covers water-reducing and high-range water-reducing admixtures.

(c) In some cases, the use of admixtures in concrete containing ASTM C845 expansive cements has resulted in reduced levels of expansion or increased shrinkage values. Refer to **ACI PRC-223**.

R26.4.1.6 *Steel fiber reinforcement*

R26.4.1.6.1

(a) Deformations in steel fibers enhance mechanical anchorage with the concrete. The limits for the fiber length-to-diameter ratio are based on available test data (**Parra-Montesinos 2006**).

R26.4.2 *Concrete mixture requirements*

R26.4.2.1

(a) The requirements for each concrete mixture used for the Work are to be stated in the construction documents. These are determined from applicable concrete design requirements in **19.2** and durability requirements in **19.3**. The most restrictive requirements that apply are to be stated.

(a)(5) In accordance with Table 19.3.2.1, the w/cm is based on all cementitious and supplementary cementi-

CODE

(6) Nominal maximum size of coarse aggregate not to exceed the least of (i) through (iii):

- (i) One-fifth the narrowest dimension between sides of forms
- (ii) One-third the depth of slabs
- (iii) Three-fourths the minimum specified clear spacing between individual reinforcing bars or wires, bundles of bars, prestressed reinforcement, individual tendons, bundled tendons, or ducts

These limitations shall not apply if, in the judgment of the licensed design professional, workability and methods of consolidation are such that concrete can be placed without honeycombs or voids.

(7) For shotcrete, nominal maximum size of coarse aggregate shall not exceed 1/2 in.

(8) For members assigned to Exposure Classes F1 or F2, applicable target air content from 19.3.3.1 or 19.3.3.3

(9) For members assigned to Exposure Class F2 or Exposure Classes F2 and C2, and that will be in a location susceptible to scaling, requirements to address scaling.

(10) For members assigned to Exposure Class S:

- (i) Permitted cementitious materials from 19.3.2.1
- (ii) If alternative combinations of cementitious materials are permitted, qualification shall be in accordance with 26.4.2.2(b).
- (iii) For Exposure Class S1, S2 or S3, prohibition of mineral fillers derived from carbonate aggregate unless approved by the licensed design professional.

(iv) For Exposure Class S2 or S3, prohibition of calcium chloride.

(11) For members assigned to Exposure Class W1 or W2:

COMMENTARY

tious materials in the concrete mixture. The w/cm of concrete made with alternative cements may not reflect the strength and durability characteristics of the concrete made with portland cement and supplementary cementitious materials permitted in Table 26.4.1.1.1(a). As noted in R26.4.1.1.1(b), it is imperative that testing be conducted to determine the performance of concrete made with alternative cements and to develop an appropriate project specification.

(a)(6) The size limitations on aggregates are provided to facilitate placement of concrete around the reinforcement without honeycombing due to blockage by closely spaced reinforcement. The licensed design professional should specify the appropriate nominal maximum size aggregate in the construction documents for each concrete mixture. Using a larger maximum aggregate size with a concurrent reduction in paste volume can beneficially impact concrete properties. Benefits include reduced potential for cracking due to shrinkage or thermal effects, reduced permeability, lower cost of concrete, and support of sustainable construction goals.

(a)(8) **ASTM C94** and **ASTM C685** include a tolerance for air content as delivered of ± 1.5 percentage points. This same tolerance is acceptable for shotcrete.

(a)(9) The risk of scaling can be reduced by specifying appropriate materials, specifying appropriate air content for the exposure, testing to determine if specified air content is obtained, and requiring inspection to verify that appropriate finishing and curing procedures are followed. The licensed design professional should review local construction practice, consult local concrete producers, or both, to determine if any limitations are necessary for supplementary cementitious materials in placements where scaling may be a concern.

(a)(10)(iii) If concrete members are assigned to Exposure Class S1, S2, or S3, the use of mineral fillers derived from carbonate aggregate in concrete mixtures can result in a form of sulfate attack. Information is provided in **ACI PRC-201.2**. **ASTM C1797** Type C mineral fillers that are derived from noncarbonate quarried stone can be used in concrete exposed to sulfates. If the quantity of Type A, B, or C mineral filler derived from carbonate aggregate proposed for use is such that the total calcium carbonate content from cement and mineral filler is equal to or less than 15 percent by mass of the cementitious materials, then sulfate resistance can be evaluated by **ASTM C1012** to comply with the expansion criteria in Table 26.4.2.2(c).

CODE

(i) requirements for the evaluation of the potential for alkali-aggregate reactivity.

(ii) **ASTM C1866** Type GS ground-glass pozzolan is prohibited in combination with potentially alkali-reactive aggregates unless approved by the licensed design professional.

(12) For members assigned to Exposure Category C, applicable water-soluble chloride ion limits from 19.3.2.1.

(13) For lightweight concrete:

(i) Equilibrium density.

(ii) If Table 19.2.4.1(b) is used as the basis for determining λ for design, requirement for submittal of volumetric fractions of aggregate.

(14) Requirements for steel fiber-reinforced concrete if used for shear resistance in accordance with **9.6.3.1**.

COMMENTARY

(a)(11)(i) Members assigned to exposure class W1 or W2 are potentially susceptible to two types of alkali-aggregate reaction. (1) alkali-silica reaction (ASR), which involves various types of reactive siliceous minerals; and (2) alkali-carbonate reaction (ACR), which involves certain types of aggregates that contain dolomite. Both types of reaction can result in expansion and cracking of concrete elements under prolonged exposure to moisture, leading to a reduction in the structural strength and service life of a concrete structure. Options for mitigating ASR, including use of supplementary cementitious materials or limiting alkali content of the concrete, are provided in **ASTM C1778**. There are no proven measures for effectively preventing damaging expansion with aggregates determined to be susceptible to ACR; therefore, they should not be used in concrete mixtures.

(a)(11)(ii) Because of its high alkali content, use of **ASTM C1866** Type GS ground-glass pozzolan in concrete made with potentially alkali-silica reactive aggregates should be avoided in W1 and W2 exposures unless data showing satisfactory concrete prism expansion in accordance with **ASTM C1293** are available following the guidance provided in **ASTM C1778**. Refer to R26.4.2.2(c). Additional information, including the use of ground-glass pozzolan in combination with other supplementary cementitious materials, is provided in the Appendix of ASTM C1866.

(a)(13) The equilibrium density of lightweight concrete is determined in accordance with **ASTM C567** and is an estimate of the density of hardened lightweight concrete assuming some degree of drying after construction. Equilibrium density is used in determining a number of design parameters, including fire resistance ratings, static structural self-weight, dynamic seismic mass, modulus of elasticity, and the value of λ .

(a)(14) If steel fibers are used for shear resistance, there are specific requirements for the steel fiber-reinforced concrete: 26.4.1.6 provides fiber requirements; 26.4.2.2(h) provides minimum dosage requirements; and 26.12.8.1(a) provides acceptance criteria. Fibers are typically specified by fiber type, fiber length, aspect ratio (ℓ/d), and dosage rate (**ACI PRC-544.3**).

For structural applications, the Code only addresses the use of discontinuous deformed steel fibers in resisting shear. For other structural applications where it is desired to use discontinuous deformed steel fibers, **Section 1.10** provides a procedure for approval. There are nonstructural applications or functional purposes where discontinuous steel fibers are used in concrete. The provisions of the Code that address use of steel

CODE

(b) At the option of the licensed design professional, exposure classes based on the severity of the anticipated exposure of members.

(c) The required compressive strength at designated stages of construction for each part of the structure designed by the licensed design professional.

26.4.2.2 Compliance requirements:

(a) The required compressive strength at designated stages of construction for each part of the structure not designed by the licensed design professional shall be submitted for review.

(b) For concrete mixtures to be used in members identified in construction documents to be exposed to sulfate, alternative combinations of cementitious materials to those specified in 26.4.2.1(a)(9) are permitted if tests for sulfate resistance satisfy the criteria in Table 26.4.2.2(b).

Table 26.4.2.2(b)—Requirements for establishing suitability of combinations of cementitious materials for Exposure Category S

Exposure class		Maximum length change for tests in accordance with ASTM C1012, percent		
		At 6 months	At 12 months	At 18 months
S1		0.10	No requirement	No requirement
S2		0.05	0.10 ^[1]	No requirement
S3	Option 1	No requirement	No requirement	0.10
	Option 2	0.05	0.10 ^[1]	No requirement

^[1]The 12-month expansion limit applies only if the measured expansion exceeds the 6-month maximum expansion limit.

COMMENTARY

fibers for shear strength are not intended for such nonstructural applications.

(b) **Section 19.3.1** requires the licensed design professional to assign exposure classes for different members in the structure. Concrete mixtures should be specified accordingly, but the Code does not require the assigned exposure classes to be stated in the construction documents. If the licensed design professional is requiring the contractor to determine requirements for concrete by specifying **ACI SPEC-301**, the assigned exposure classes for all members will need to be stated in the construction documents.

(c) If design or construction requirements dictate that in-place strength of concrete be achieved at specific ages or stages of construction, these requirements should be stated in the construction documents. Typical stages of construction when the required compressive strength of concrete should be specified include: at removal of formwork and shores, for precast concrete as provided in 26.9.1(d), and for post-tensioned concrete at the application of post-tensioning as provided in 26.10.2(h).

For portions of the structure that are not designed by the licensed design professional, refer to 26.4.2.2(a).

R26.4.2.2 Table 26.4.2.2(b) in previous editions of the Code, which provided maximum allowable amounts of supplementary cementitious materials, has been withdrawn from the 2025 Code because: 1) there is a lack of data to support the table; 2) the test method upon which the table was based (ASTM C672) has been withdrawn as not being representative of field conditions; and, 3) scaling depends upon finishing and curing practices as well as the materials used in the concrete.

(b) Mixture requirements for Exposure Category S are given in **19.3.2.1**. **ASTM C1012** may be used to evaluate the sulfate resistance of concrete mixtures using alternative combinations of cementitious materials to those listed in Table 19.3.2.1. More detailed guidance on qualification of such mixtures using ASTM C1012 is given in **ACI PRC-201.2**. The expansion criteria in Table 26.4.2.2(c) for testing in accordance with ASTM C1012 are the same as those in ASTM C595 and **C1157** for moderate sulfate resistance (Optional Designation MS) in Exposure Class S1 and for high sulfate resistance (Optional Designation HS) in Exposure Class S2 and Exposure Class S3 Option 2. The 18-month expansion limit only applies for Exposure Class S3, Option 1.

CODE

(c) For concrete mixtures to be used in members identified in construction documents to be exposed to water in service, evidence shall be submitted that the concrete mixture complies with (1) and (2).

(1) Aggregates are not alkali-silica reactive or measures to mitigate alkali-silica reactivity have been established.

(2) Aggregates are not alkali-carbonate reactive.

(d) Compliance with the specified limits on water-soluble chloride contributed by concrete materials shall be demonstrated by (1) or (2). In either case, the chloride content is expressed as a percentage by mass of the total cementitious materials. The mass of supplementary cementitious material used to determine the chloride content shall not exceed the mass of portland cement (ASTM C150) or portland-limestone cement (ASTM C595 Type IL).

(1) Calculating total chloride ion content of the concrete mixture on the basis of measured total chloride ion content from concrete materials and concrete mixture proportions.

(2) Determining water-soluble chloride ion content of hardened concrete in accordance with ASTM C1218 at age between 28 and 42 days.

(e) For prestressed concrete, admixtures containing intentionally added calcium chloride and any combination of admixtures causing the water-soluble chloride ion content to exceed the limits in Table 19.3.2.1 are prohibited.

(f) For concrete placed on or against stay-in-place galvanized steel forms, maximum water soluble chloride ion content shall be 0.30 percent by mass of cementitious materials unless a more stringent limit for the member is specified.

(g) Properties of lightweight concrete mixtures to be used in the Work shall be determined in accordance with (1) and (2):

(1) The specified equilibrium density shall be determined in accordance with ASTM C567.

(2) The fresh density for the same mixture shall be measured in accordance with ASTM C138.

COMMENTARY

(c) Documentation that the potential for AAR has been evaluated can be provided by the concrete supplier. ASTM C1778 provides methods and criteria for determining the reactivity of aggregates and guidance for reducing the risk of deleterious alkali-aggregate reactions in concrete.

(d)(1) It is common practice for total chloride ion content of a proposed concrete mixture to be evaluated by summing the chloride ion content of the constituent materials based on the mixture proportions. The chloride content of solids is typically measured on a solution of the material obtained using a strong acid. Chloride ion content of cementitious materials is determined in accordance with ASTM C114. ASTM C1602 includes a test method to measure chloride content of batch water. Chloride ion content of aggregates can be determined on an aggregate sample prepared as specified for concrete samples and tested in accordance with ASTM C1152. Total chloride ion content of admixtures is reported by the supplier. Calculated total chloride ion content of the concrete mixture determined in this manner is conservative. If calculated total chloride ion content exceeds the limits in Table 19.3.2.1, the concrete materials can be adjusted until compliance is achieved, or water-soluble chloride ion content can be determined using 26.4.2.2(e)(2).

(d)(2) To estimate the water-soluble chloride ion content in the concrete that can impact corrosion, ASTM C1218 is used after a period of hydration. The chlorides in some materials, like aggregates, are not available as water-soluble chlorides. Furthermore, some chlorides initially in solution will be bound by hydration of cementitious materials. Chlorides insoluble in water are not considered to accelerate corrosion of embedded metals.

(f) Because of the critical nature of placements against stay-in-place galvanized steel forms, the Code requires a more stringent chloride ion limit than that required if the member was assigned to Exposure Class C0.

(g) In 26.12.6, the Code requires that the fresh density, determined and submitted for the same mixture, be used as the basis for acceptance of lightweight concrete. Acceptance is based on fresh density because determination of equilibrium density according to ASTM C567 can take more than 2 months. As noted by ASTM C94 (Note 7), "The density of fresh concrete is the only measurable density of lightweight concrete at the time of delivery. The density of fresh concrete is always higher than the equilibrium or oven-dry density." The difference between fresh

CODE

(h) Steel fiber-reinforced concrete used for shear resistance shall satisfy (1) and (2):

- (1) Conform to **ASTM C1116**.
- (2) Contain at least 70 lb of deformed steel fibers per cubic yard of concrete for normalweight concrete and 100 lb of deformed steel fibers per cubic yard of concrete for lightweight concrete.

26.4.3 Proportioning of concrete mixtures

26.4.3.1 Compliance requirements:

(a) Concrete mixture proportions shall be established so that the concrete satisfies (1) through (4):

- (1) Can be placed without segregation and fully encase reinforcement.
- (2) Meets durability requirements given in the construction documents.
- (3) Conforms to strength test requirements for standard-cured specimens for concrete applications or strength requirements for drilled cores taken from test panels for shotcrete.

(4) Conforms to modulus of elasticity requirements (i) through (iii) for mixtures requiring testing in accordance with construction documents.

- (i) The modulus of elasticity shall be determined as the average modulus obtained from at least three cylinders made from the same sample of concrete and tested at 28 days or at test age designated for E_c .
- (ii) Cylinders used to determine modulus of elasticity shall be made and cured in the laboratory in accordance with **ASTM C192** and tested in accordance with **ASTM C469**.
- (iii) Modulus of elasticity of a concrete mixture shall be acceptable if the measured value equals or exceeds the specified value.

(b) Concrete mixture proportions shall be established in accordance with Article 4.2.3 of **ACI SPEC-301-20** or by an alternative method acceptable to the licensed design professional. Alternative methods shall have a probability of satisfying the strength requirements for acceptance tests of standard-cured specimens that meets or exceeds the probability associated with the method in Article 4.2.3 of **ACI SPEC-301-20**. If Article 4.2.3 of **ACI SPEC-301-20** is used, the strength test records used for establishing and

COMMENTARY

density and equilibrium density is specific to materials, proportions, and aggregate moisture.

(h) Minimum steel fiber dosage for lightweight concrete is specified at 100 lb per cubic yard of concrete due to limited experimental results.

R26.4.3 Proportioning of concrete mixtures

R26.4.3.1

(a) The concrete is required to be workable, cohesive, and conform to the durability and strength requirements of the Code. The required workability will depend on reinforcement congestion, member geometry, and the placement and consolidation methods to be used. Construction requirements of the contractor should be considered in establishing required workability of the concrete.

The Code does not include provisions for especially severe exposures, such as aggressive chemical contact (**ACI PRC-201.2**), high temperatures, temporary freezing-and-thawing conditions during construction, abrasive conditions, or other unique durability considerations pertinent to the structure. The Code also does not address aesthetic considerations such as surface finishes. If applicable, these items should be covered specifically in the construction documents. Strength test requirements for standard-cured specimens are given in 26.12.3. Strength requirements for drilled cores taken from test panels for acceptance testing of shotcrete are given in 26.12.5.

(a)(4) Modulus of elasticity testing may be required for the development of concrete mixtures to verify that specified modulus of elasticity can be obtained. It is necessary to specify both E_c and test age. Testing to verify that the specified modulus of elasticity is being attained during construction is at the discretion of the licensed design professional, including specification of acceptance criteria. Field testing may also be required by the local building official.

(b) Article 4.2.3 of **ACI SPEC-301** contains the statistical procedures for selecting the required average strength. Alternatively, the concrete producer may provide evidence acceptable to the licensed design professional that the concrete can be proportioned by another method to meet the project requirements and the acceptance criteria of 26.12.3. The Code presumes that the probability of not meeting the acceptance criteria in 26.12.3 is not more than 1 in 100. Following the method of proportioning in **ACI**

CODE

documenting concrete mixture proportions shall not be more than 24 months old.

(c) The concrete materials used to develop the concrete mixture proportions shall correspond to those to be used in the Work.

(d) If different concrete mixtures are to be used for different portions of the Work, each mixture shall comply with the concrete mixture requirements stated in the construction documents.

26.4.4 Documentation of concrete mixture characteristics**26.4.4.1 Compliance requirements:**

(a) Documentation of concrete or shotcrete mixture characteristics shall be submitted for review by the licensed design professional before the mixture is used and before making changes to mixtures already in use. Evidence of the ability of the proposed concrete or shotcrete mixture to comply with the fresh and hardened concrete mixture requirements in the construction documents shall be included in the documentation. The evidence shall include records of consecutive strength tests, as defined in 26.12.1.1, of the same concrete mixture used in previous projects or the results of laboratory trial batches of the proposed mixture.

(b) If field or laboratory test data are not available, and $f'_c \leq 5000$ psi, concrete proportions shall be based on other experience or information, if approved by the licensed design professional. If $f'_c > 5000$ psi, test data documenting the characteristics of the proposed mixtures are required.

(c) It shall be permitted to modify mixtures during the course of the Work. Before using the modified mixture, evidence acceptable to the licensed design professional shall be submitted to demonstrate that the modified mixture complies with the concrete mixture requirements in the construction documents.

26.4.5 Grout materials and construction requirements**26.4.5.1 Packaged hydraulic cement grout for use with steel base plates and steel shear lugs of columns****26.4.5.1.1 Design information:**

(a) Specified compressive strength of grout

COMMENTARY

SPEC-301 will maintain this level of risk. A key factor in evaluating any proposed alternative proportioning method should be its ability to preserve this presumed level of risk. Refer to **ACI PRC-214** for additional information.

(d) A change in concrete constituents, such as sources or types of cementitious materials, aggregates, or admixtures, is considered a different mixture. A minor change in mixture proportions made in response to field conditions is not considered a new mixture.

R26.4.4 Documentation of concrete mixture characteristics**R26.4.4.1**

(a) The licensed design professional typically reviews the documentation of proposed concrete or shotcrete mixtures to evaluate the likelihood that it will meet the strength-test acceptance requirements of 26.12.3 for conventional concrete applications or 26.12.5 for shotcrete and that acceptable materials are used. The statistical principles discussed in ACI PRC-214 can be useful in evaluating the likelihood that a proposed mixture will meet the strength-test requirements of 26.12.3 or 26.12.5.

(b) If $f'_c \leq 5000$ psi and test data are not available, concrete mixture proportions should be established to produce a sufficiently high average strength such that the likelihood that the concrete would not meet the strength acceptance criteria would be acceptably low. The purpose of this provision is to allow construction to continue when there is an unexpected interruption in concrete supply and there is not sufficient time for testing and evaluation. It also applies for a small project where the cost of trial mixture data is not justified.

(c) It is sometimes necessary or beneficial to adjust concrete mixtures during the course of a project. Conditions that could result in mixture adjustments include changes in concrete materials, seasonal temperature fluctuations, or changes in conveying and placing methods. Additionally, an adjustment to a concrete mixture may be required or appropriate if strength tests are lower or higher than required.

R26.4.5 Grout materials and construction requirements**R26.4.5.1 Packaged hydraulic cement grout for use with steel base plates and steel shear lugs of columns**

R26.4.5.1.1 ACI PRC-351.1 provides an overview of current practices for grout placement and testing with an emphasis on various types of grouts used to support equip-

CODE

(b) Limits on grout materials as required for durability and performance

(c) Grout consistency, if required
(d) Test method and age for demonstrating compliance with specified strength, if required

26.4.5.1.2 Compliance requirements:

(a) Packaged, dry materials for hydraulic-cement grout specified for use in grout pads under steel base plates, or with steel shear lugs designed integrally with grout pads under column base plates, shall conform to **ASTM C1107**.
(b) Surface preparation of concrete substrate and mixing, placement, thermal control, and curing of grout shall conform to the manufacturer's instructions.

26.5—Concrete production and construction

26.5.1 Concrete production

26.5.1.1 Compliance requirements:

(a) Cementitious materials and aggregates shall be stored to prevent deterioration or contamination.
(b) Material that has deteriorated or has been contaminated shall not be used in concrete.
(c) Equipment for mixing and transporting concrete shall conform to **ASTM C94** or **ASTM C685**.
(d) Ready-mixed and site-mixed concrete shall be batched, mixed, and delivered in accordance with ASTM C94 or ASTM C685.

COMMENTARY

ment and machinery. **ACI SPEC-351.4** can be used as a basis for specifying grouting at load transfer conditions. **Mullins and Parker (2019)** provide recommendations for the specification of grouted joints including grout types, placement procedures, and quality control.

(b) Packaged, hydraulic cementitious grout durability or performance requirements typically include limits on permissible shrinkage or expansion, chloride content, and calcium sulfate dihydrate (gypsum) content.

(d) Field testing of base plate grout is uncommon in most typical situations. If needed, the licensed design professional should specify the type of test, test age, and frequency of testing. Testing of unconfined 2 in. cube specimens may not correlate well to actual in-place strength due to aspect ratio and confinement of the in-situ grout placement.

R26.5—Concrete production and construction

Detailed recommendations for mixing, handling, transporting, and placing concrete are given in **ACI PRC-304**.

R26.5.1 Concrete production

R26.5.1.1

(d) ASTM C94 is a specification for ready mixed concrete whereby materials are primarily measured by mass (weight) and production is by batches. This is the more common method of concrete production, and it is also used in precast concrete plants. ASTM C685 is a specification for concrete where materials are measured by volume and the production is by continuous mixing. These specifications include provisions for capacity of mixers, accuracy of measuring devices, batching accuracy, mixing and delivery, and tests for evaluating the uniformity of mixed concrete.

CODE

26.5.2 Concrete placement and consolidation**26.5.2.1 Design information:**

- (a) Requirements for acceptance of consolidation of concrete cast in insulating concrete forms (ICF).

26.5.2.2 Compliance requirements:

- (a) Debris and ice shall be removed from spaces to be occupied by concrete before placement.
- (b) Standing water shall be removed from place of deposit before concrete is placed unless a tremie is to be used or unless otherwise permitted by both the licensed design professional and the building official.

- (c) Equipment used to convey concrete from the mixer to the location of final placement shall have capabilities to achieve the placement requirements.

- (d) Concrete shall not be pumped through pipe made of aluminum or aluminum alloys.

- (e) Concrete shall be placed in accordance with (1) through (5):

- (1) At a rate to provide an adequate supply of concrete at the location of placement.
- (2) At a rate so concrete at all times has sufficient workability such that it can be consolidated by the intended methods.
- (3) Without segregation or loss of materials.
- (4) Without interruptions sufficient to permit loss of workability between successive placements that would result in cold joints.
- (5) Deposited as near to its final location as practicable to avoid segregation due to rehandling or flowing.

COMMENTARY

R26.5.2 Concrete placement and consolidation

R26.5.2.1 Consolidation of concrete in insulating concrete forms (ICF) can be achieved through a combination of placing concrete with adequate workability, limiting lift pour heights, and effective internal vibration. Consolidation may be verified by various means, including visually during placement, by probing, or by cutting sections of insulation at a specified frequency after concrete has hardened. Frequency may be based on wall length, wall square footage, or volume of wall concrete placed.

If probing, test cuts, or removal of insulation reveals poor consolidation, more extensive examination of the concrete should be required. Ground penetrating radar (GPR) has been reported to identify voids in concrete placed in ICF walls. (Gajda and Dowell 2003).

R26.5.2.2

- (a) Forms need to be cleaned before beginning to place concrete. In particular, sawdust, nails, wood pieces, and other debris that may collect inside forms need to be removed.

- (b) The tremie referred to in this provision is not a short tube or “elephant trunk.” It is a full-depth pipe used in accordance with accepted procedures for placing concrete under water. Information regarding placing concrete using a tremie is given in **ACI PRC-304**.

- (d) Loss of strength can result if concrete is pumped through pipe made of aluminum or aluminum alloy. This loss is caused by the formation of hydrogen gas generated by the reaction between the cement alkalis and the aluminum eroded from the interior of the pipe surface. The strength reduction has been shown to be as much as 50% (Newlon and Ozol 1969). Short chutes used to convey concrete from a truck mixer are not a concern.

- (e) Concrete should be available at a supply rate consistent with the capacity of the placement equipment and the placement crew. Concrete supplied at a faster rate than can be accommodated by placement equipment or crew can result in loss of workability of concrete in equipment waiting to discharge. Excessive delays in the supply of concrete can cause previous placements to stiffen and result in the formation of cold joints.

Rehandling and transferring concrete over large distances from delivery vehicles to the point of placement in the structure can cause segregation of materials. The Code therefore requires that concrete be deposited as close to its final location as possible. However, self-consolidating concrete mixtures can be developed to flow longer distances and maintain their stability with minimal segregation. Guidance on self-consolidating concrete is provided in **ACI PRC-237**.

CODE

(f) Concrete that has been contaminated or has lost its initial workability to the extent that it can no longer be consolidated by the intended methods shall not be used.

(g) Retempering concrete in accordance with the limits of **ASTM C94** shall be permitted unless otherwise restricted by the licensed design professional.

(h) After starting, concreting shall be carried on as a continuous operation until the completion of a panel or section, as defined by its boundaries or predetermined joints.

(i) Concrete shall be consolidated by suitable means during placement and shall be worked around reinforcement and embedments and into corners of forms.

(j) For shotcrete, (1) through (7) shall apply:

(1) Before placement of a new layer of shotcrete, rebound and overspray from adjacent placements shall be removed.

(2) Cuttings and rebound shall not be incorporated into the Work.

(3) Shotcrete surfaces intended to receive subsequent shotcrete placement shall be roughened to a full amplitude of approximately 1/4 in. before the shotcrete has reached final set.

(4) Before placing additional material onto hardened shotcrete, laitance shall be removed, joints shall be cleaned, and the surface shall be dampened.

(5) In-place fresh shotcrete that exhibits sags, sloughs, segregation, honeycombing, or sand pockets shall be removed and replaced.

(6) A certified shotcrete nozzle operator shall place all shotcrete.

(7) If a shotcrete mockup panel is required, each nozzle operator shall demonstrate the ability to properly place shotcrete under similar placement conditions by satisfying (i) or (ii)

(i) Shoot an approved shotcrete mockup panel

(ii) Provide documentation of previous shotcrete placement acceptable to the licensed design professional.

26.5.3 Curing

26.5.3.1 Design information:

(a) If supplementary tests of field-cured specimens are required to verify adequacy of curing and protection, the number and size of test specimens and the frequency of these supplementary tests.

26.5.3.2 Compliance requirements:

COMMENTARY

(g) ASTM C94 permits water addition to mixed concrete before concrete is discharged to bring it up to the specified slump range as long as prescribed limits on the maximum mixing time and w/cm are not violated.

(i) Detailed recommendations for consolidation of concrete are given in **ACI PRC-309**. Recommendations for consolidation of concrete in insulated concrete forms are given in **ACI PRC-560**.

(j)(1 and 2) Rebound material is aggregate and mortar that bounces off when shotcrete collides with formwork, reinforcement, or a hardened shotcrete surface.

Overspray is the paste-rich material that separates from the stream during shotcreting and adheres to nearby reinforcement and formwork. Adjacent surfaces are typically protected from overspray.

Cuttings refers to shotcrete that has been applied beyond the finish face and is cut off during trimming or rod finishing.

Rod finishing refers to the use of a hard-edged tool or rod to cut excess material by trimming, slicing, or scraping the exposed shotcrete to a true line and grade.

(j)(5) If the shotcrete sags because of improper consistency, adjacent vibration, or improper finishing, those sections should also be removed and replaced. **ACI PRC-506.4** provides additional recommendations for repairing shotcrete.

(j)(6) Each shotcrete nozzle operator should be certified in accordance with the applicable ACI certification program for dry-mix or wet-mix shotcrete (both are covered by **ACI CPP 660.1**).

(j)(7) Documentation of previous experience may include records of past work with similar section thickness, reinforcement layout, shotcrete mixture, embedments, penetrations, and type of equipment. Refer to **ACI PRC-506.4** and **ACI SPEC-506.2** for additional information.

R26.5.3 Curing

ACI PRC-308 presents basic principles of proper curing and describes the various methods, procedures, and materials for curing of concrete.

R26.5.3.2

CODE

(a) Except as provided in 26.5.3.2(b) and (c), concrete shall be maintained in a condition that retains water in the concrete for the duration given in (1), (2), or (3).

(1) For 7 days after placement with concrete maintained at a temperature of at least 50°F.

(2) For 3 days after placement with concrete maintained at a temperature of at least 50°F and proportioned to attain a strength of $0.7f_c'$ within 3 days.

(i) Strength shall be demonstrated by test specimens cured in accordance with **ASTM C192** and tested in accordance with **ASTM C39**.

(ii) Results shall be documented in accordance with 26.4.4.

(3) Until the in-place concrete strength estimated by a method approved by the licensed design professional reaches at least $0.7f_c'$. If required by the licensed design professional, the correlation between compressive strength and the results of the in-place test method shall be submitted to the licensed design professional for review.

(b) Concrete in members assigned to Exposure Class C2 or S3 shall be maintained in a condition that retains water in the concrete for the duration given in (1) or (2).

(1) For 14 days after placement with concrete maintained at a temperature of at least 50°F.

(2) Until the in-place concrete strength estimated by a method approved by the licensed design professional reaches at least $0.9f_c'$. If required by the licensed design professional, the correlation between compressive strength and the results of the in-place test method shall be submitted to the licensed design professional for review.

(c) Curing methods to accelerate strength gain and reduce the time of curing are permitted using high-pressure

COMMENTARY

(a) Curing methods involve maintaining an adequate temperature and sufficient water in the concrete so that its potential strength and durability properties can develop. Curing methods described in ACI PRC-308 include:

a. Application of sheet materials conforming to **ASTM C171**

b. Application of membrane-forming curing compound conforming to **ASTM C309** or **ASTM C1315**

c. Ponding on horizontal surfaces

d. Continuous sprinkling of exposed surfaces

e. Continuous fogging of air surrounding exposed surfaces

f. Application of pre-wetted absorbent material that is kept continuously damp

g. Internal curing by using pre-soaked lightweight fine aggregates, conforming to **ASTM C1761**, in the concrete mixture as described in **ACI PRC-308-213**

Maintaining formwork in place may not be sufficient to ensure adequate curing of the surface concrete, especially if severe exposure is anticipated. Refer to **ACI PRC-308** for recommendations on curing formed surfaces.

The curing durations in 26.5.3.2(a)(1) and (2) have been in the Code for many years and have a proven history of providing adequate curing. The 2025 edition of the Code introduced an alternative criterion for termination of curing based on in-place strength. The alternative criterion in 26.5.3.2(a)(3) is included in **ACI SPEC-308.1** and takes advantage of the heat of hydration in reducing the time to achieve a sufficient degree of reaction of the cementitious material before curing procedure termination. This requirement is distinct from the in-place strength requirement for formwork removal or prestressing application, for which the required in-place strength depends on the loads to be resisted at that stage of construction.

Applicable methods for estimating in-place concrete strength as the basis for curing termination are the same as in R26.11.2.1(e) for evaluation of in-place strength before formwork removal. For methods requiring a correlation with the compressive strength of molded cylinders, the correlation basis should be included in the submittal. Refer to **ACI PRC-228.1**.

(b) The durability of concrete assigned to Exposure Class C2 or S3 relies on the resistance to fluid penetration of the surface layer. Therefore, it is critical that exposed surfaces receive adequate curing. In practice, a curing period of 14 days or the time to achieve an in-place strength of $0.9f_c'$ is considered adequate to achieve a durable surface layer for these exposure classes.

(c) This provision permits accelerated curing methods for precast or cast-in-place elements. **EB-001.17**, **PCI MNL**

CODE

steam, steam at atmospheric pressure, heat and moisture, or other process acceptable to the licensed design professional. Accelerated curing shall not impair concrete durability. The concrete strength at curing termination shall be at least the strength required for that stage of construction.

(d) If required by the building official or licensed design professional, test results for cylinders made and cured in accordance with (1) and (2) shall be provided in addition to test results for standard-cured cylinders.

- (1) At least two 4 x 8 in. or two 6 x 12 in. cylinders to be field cured shall be molded at the same time and from the same concrete sample as standard-cured cylinders.
- (2) Field-cured cylinders shall be cured in accordance with the field curing procedure of **ASTM C31** and tested in accordance with ASTM C39.

(e) Procedures for protecting and curing concrete shall be considered adequate if (1) or (2) are satisfied:

- (1) Average strength of field-cured cylinders at test age designated for determination of f'_c is equal to or at least 85% of that of companion standard-cured cylinders.
- (2) Average strength of field-cured cylinders at test age exceeds f'_c by more than 500 psi.

COMMENTARY

116, and **PCI MNL 117** provide general information on accelerated curing. Accelerated curing procedures require careful attention to obtain uniform, consistent, and satisfactory results. Preventing moisture loss during the curing is essential.

The compressive strength of accelerated-cured concrete is not as high at later ages as that of nominally identical concrete continuously cured under moist conditions at moderate temperatures. The modulus of elasticity, E_c , of accelerated-cured specimens may also vary from that of specimens moist-cured at normal temperatures. In addition, high concrete temperatures during curing can increase the risk of delayed ettringite formation (DEF). **ACI PRC-201.2** and **PCI MNL 116** provide guidance on mitigating the risk of DEF.

(d) Strengths of cylinders cured under field conditions may be required to evaluate the adequacy of curing and protection of concrete in the structure.

The Code provides a specific criterion in 26.5.3.2(e) for determining the adequacy of curing and protection afforded to the structure. For a valid comparison, field-cured cylinders and companion standard-cured cylinders need to be made from the same sample. Field-cured cylinders are to be cured, as nearly as possible, under the same conditions as the structure. The field-cured cylinders should not be treated more favorably than the structural members they represent.

In evaluating test results of field-cured cylinders, it should be recognized that even if cylinders are protected in the same manner as the structure, they may not experience the same temperature history as the concrete in the structure. Heat of hydration may be dissipated differently in the cylinders than in the structural member.

(e) Research (**Bloem 1968**) has shown that the strength of cylinders protected and cured to simulate good field practice should be at least about 85% of standard-cured cylinders if both are tested at the age designated for f'_c . Thus, a value of 85% has been set as a rational basis for determining the adequacy of field curing. The comparison is made between the measured strengths of companion field-cured and standard-cured cylinders, not between the strength of field-cured cylinders and the value of f'_c . Test results for the field-cured cylinders are considered satisfactory, however, if the strength of field-cured cylinders exceeds f'_c by more than 500 psi, even though they fail to reach 85% of the strength of companion standard-cured cylinders.

The 85% criterion is based on the assumption that concrete is maintained above 50°F and in a moist condition for at least the first 7 days after placement, or high-early-strength concrete is maintained above 50°F and in a moist condition for at least the first 3 days after placement.

If the field-cured cylinders do not provide satisfactory strength by this comparison, steps need to be taken to improve the curing. If the tests indicate a possible serious deficiency in strength of concrete in the structure, core

CODE

- (f) Shotcrete shall be cured in accordance with (1) through (3).
- (1) For 24 hours from completion of placement, initial curing shall be provided by one of the following methods:
 - (i) Ponding, fogging, or continuous sprinkling;
 - (ii) Absorptive mat, fabric, or other protective covering kept continuously moist;
 - (iii) Application of a membrane-forming curing compound.
 - (2) After 24 hours from completion of placement, final curing shall be provided by one of the following methods:
 - (i) Same method used in the initial curing process;
 - (ii) Sheet materials;
 - (iii) Other moisture-retaining covers kept continuously moist.
 - (3) Final curing shall be maintained for a minimum duration of:
 - (i) 7 days,
 - (ii) 3 days if either a high-early-strength cement or an accelerating admixture is used.

26.5.4 Concreting in cold weather**26.5.4.1 Design information:**

- (a) Temperature limits for concrete as delivered in cold weather.
- (b) Minimum temperature for embedments, forms, and reinforcement before concrete placement in cold weather.
- (c) Maximum allowable temperature decrease measured at the concrete surface during the first 24 hours after thermal protection removal.

26.5.4.2 Compliance requirements:

- (a) A cold weather concreting plan shall be submitted by the contractor to be reviewed by the licensed design professional.

COMMENTARY

tests may be required, with or without supplemental wet curing, to evaluate the structural adequacy, as provided in 26.12.7.

- (f) If using a curing compound, it will usually be necessary to apply the compound at a higher rate than the manufacturer's recommendation because of the rougher surface of many shotcrete applications.

R26.5.4 Concreting in cold weather

Recommendations for cold weather concreting are given in **ACI PRC-306** and recommended specifications are provided in **ACI SPEC-301**. ACI SPEC-301 provides recommended concrete temperature limits after placement based on section dimensions.

R26.5.4.1

- (a) **ASTM C94**, ACI PRC-306, and ACI SPEC-301 contain requirements and recommendations for concrete temperature based on section size.
- (b) Cold embedments, forms, and reinforcement can freeze adjacent concrete and weaken the concrete locally where strength may be critical for anchoring the embedment or for bonding with reinforcement. ACI SPEC-301 and ACI PRC-306 provide recommended temperature limits for embedments, forms, and reinforcement in cold weather.
- (c) ACI SPEC-301 and ACI PRC-306 provide maximum allowable temperature decreases during the first 24 hours after removal of thermal protection based on section minimum dimensions.

R26.5.4.2

- (a) The cold weather concreting plan should contain means and methods to: (i) retain water, (ii) provide or retain sufficient heat in the concrete during the curing period, such

CODE

- (b) Aggregates that contain frozen lumps or ice shall not be used.
- (c) Forms, fillers, and ground with which concrete is to come in contact shall be free from frost and ice.

26.5.5 Concreting in hot weather

26.5.5.1 Design information:

- (a) Temperature limits for concrete as delivered in hot weather.
- (b) Maximum temperature for embedments, forms, and reinforcement before concrete placement in hot weather.
- (c) Maximum allowable temperature decrease measured at the concrete surface during the first 24 hours after thermal protection removal.

26.5.5.2 Compliance requirements:

- (a) A hot weather concreting plan shall be submitted by the contractor to be reviewed by the licensed design professional.

26.5.6 Construction, contraction, and isolation joints

COMMENTARY

that cementitious materials react to develop required properties, and (iii) control the decrease in surface temperature during the first 24 hours after thermal protection removal.

R26.5.5 Concreting in hot weather

Recommendations for hot weather concreting are given in **ACI PRC-305**, which identifies factors that affect concrete properties and construction practices and recommends measures to mitigate undesirable effects. Recommended specifications for concreting in hot weather are provided in ACI SPEC-301 and **ACI SPEC-305.1**.

R26.5.5.1

- (a) ACI SPEC-301 and ACI SPEC-305.1 limit the maximum concrete temperature to 95°F at the time of placement, unless otherwise approved or specified by the licensed design professional.
- (c) ACI SPEC-305.1 requires the concrete surface be protected from rapid temperature decreases and requires any protective materials to be removed in a manner to limit thermal cracking. The allowable maximum temperature decrease during the first 24 hours after protection removal in hot weather concreting should be the same as for cold weather concreting. **ACI SPEC-301** and **ACI PRC-306** provide recommended maximum allowable temperature decreases during the first 24 hours after removal of thermal protection based on section minimum dimensions.

R26.5.5.2

- (a) The hot weather concreting plan should contain means and methods to: (i) provide concrete mixtures that will retain the required workability during placement and consolidation, (ii) control concrete temperature at delivery, (iii) retain water, and (iv) control the decrease in surface temperature during the first 24 hours after thermal protection removal.

R26.5.6 Construction, contraction, and isolation joints

Deviations of joint locations indicated in construction documents should be approved by the licensed design professional. Construction or other joints should be located where they will cause the least weakness in the structure. Lateral force design may require additional consideration of joints during design.

CODE**26.5.6.1** Design information:

- (a) If required by the design, locations and details of construction, isolation, and contraction joints.
- (b) Details required for transfer of shear and other forces through construction joints.
- (c) Surface preparation, including identification of contact surfaces that are to be intentionally roughened.
- (d) Locations where shear is transferred between structural steel and concrete using headed studs or welded reinforcing bars requiring steel to be clean and free of paint.
- (e) Required surface preparation if composite topping slabs are to be cast in place on a precast floor or roof intended to act structurally with the precast members.
- (f) For shotcrete, location of construction joints for which square joints are permitted.

26.5.6.2 Compliance requirements:

- (a) Joint locations or joint details not shown or that differ from those indicated in construction documents shall be submitted for review by the licensed design professional before placement of concrete or shotcrete.
- (b) Except for prestressed concrete, construction joints in floor and roof systems shall be located within the middle third of spans of slabs, beams, and girders unless otherwise approved by the licensed design professional.
- (c) Construction joints in girders shall be offset a distance of at least two times the width of intersecting beams, measured from the face of the intersecting beam, unless otherwise approved by the licensed design professional.
- (d) Construction joints shall be cleaned and laitance removed before new concrete is placed.
- (e) If intentional roughening is specified, contact surfaces shall be clean, free of laitance, and roughened to a trough-to-peak amplitude of approximately 1/4 in.
- (f) If contact surfaces that are at least lightly textured is specified, troweled or otherwise very smooth surfaces are not permitted.

COMMENTARY**R26.5.6.1**

(b) Shear keys, intermittent shear keys, diagonal dowels, or shear friction may be used where force transfer is required. If shear friction at a joint interface in accordance with 22.9 is invoked in the design, include applicable construction requirements in the construction documents.

(d) The locations referenced are those for which design for shear friction is in accordance with 22.9.

R26.5.6.2

(a) The contractor should submit joint locations not shown or that differ from those in construction documents to the licensed design professional for review to determine that the proposed locations do not impact the performance of the structure.

(b) Tendons of continuous post-tensioned slabs and beams are usually stressed at a point along the span where the tendon profile is at or near the centroid of the concrete cross section. Therefore, interior construction joints are usually located within the end thirds of the span rather than the middle third of the span. Construction joints located within the end thirds of continuous post-tensioned slab and beam spans have a long history of satisfactory performance; therefore, 26.5.6.2(b) is not applicable to prestressed concrete.

(e) ICRI Concrete Surface Profile comparison chips, as described in **IRCI 310.2R**, are useful for evaluation of contact surface roughness. The maximum distances between peaks and troughs of Concrete Surface Profile (CSP) 10 are approximately 1/4 in., and the chip can be used for comparison where 1/4 in. amplitude is specified. Roughness visually comparable to CSP 10 satisfies the requirement for intentional roughening in 26.5.6.2(e).

(f) Texture that is visually comparable to CSP 3 or greater satisfies the requirement for surfaces specified to be at least lightly textured in accordance with Table 16.4.4.1.

CODE

- (g) Immediately before new concrete is placed, construction joints shall be prewetted and standing water removed.
- (h) For shotcrete, construction joint surfaces shall be cut at a 45-degree angle to the finished surface, unless a square joint is designated in the construction documents.

26.5.7 Construction of concrete members**26.5.7.1 Design information:**

- (a) Details required to accommodate dimensional changes resulting from prestressing, creep, shrinkage, and temperature.
- (b) Identify if a slab-on-ground is designed as a structural diaphragm or part of the seismic-force-resisting system.
- (c) Details for construction of sloped or stepped footings designed to act as a unit.
- (d) Locations where floor system and column concrete placements are required to be integrated during placement in accordance with **15.5**.
- (e) Locations where steel fiber-reinforced concrete is required for shear resistance in accordance with **9.6.3.1**.

26.5.7.2 Compliance requirements:

- (a) Beams, girders, or slabs supported by columns or walls shall not be cast until concrete in the vertical support members is no longer plastic.
- (b) Beams, girders, haunches, drop panels, shear caps, and capitals shall be placed monolithically as part of a slab system, unless otherwise shown in construction documents.
- (c) At locations where floor system and column concrete placements are required to be integrated during placement, column concrete shall extend full depth of the floor system at least 2 ft into the floor system from face of column and be integrated with floor system concrete.
- (d) Saw cutting or construction of joints that can affect the integrity of a slab-on-ground identified in the construction documents as structural diaphragms or part of the seismic-force-resisting system shall not be permitted unless specifically indicated or approved by the licensed design professional.

26.5.8 Construction of deep foundation members**26.5.8.1 Compliance requirements:****COMMENTARY****R26.5.7 Construction of concrete members****R26.5.7.1**

(b) A slab-on-ground may be designed to act as a structural diaphragm or to provide required ties between foundations. The construction documents should clearly identify any slab on ground that is a structural diaphragm, and state that saw cutting or joints are prohibited unless approved by the licensed design professional. Joints can affect the integrity of the slab and its ability to act as a structural diaphragm, unless structural repairs are made. Refer also to 26.5.7.2(d).

R26.5.7.2

- (a) Delay in placing concrete in members supported by columns and walls is necessary to minimize potential cracking at the interface of the slab and supporting member caused by bleeding and settlement of plastic concrete in the supporting member.
- (b) Separate placement of slabs and beams, haunches, or similar elements is permitted if shown in the construction documents and if provision has been made to transfer forces as required in **22.9**.
- (c) Application of the concrete placement procedure described in **15.8** may require the placing of two different concrete mixtures in the floor system. It is the responsibility of the licensed design professional to indicate in the construction documents where the higher- and lower-strength concretes are to be placed.
- (d) This restriction applies to slabs identified as structural diaphragms in 26.5.7.1(b).

R26.5.8 Construction of deep foundation members

R26.5.8.1 Unlike drilled cast-in-place concrete piles, caged reinforcement for augered cast-in-place piles cannot be installed prior to filling the deep foundation member hole

CODE

(a) Reinforcement shall be assembled, tied, and installed in a deep foundation member as a unit before the reinforced portion of the member is filled with concrete or grout, except as permitted by (1), (2), or (3).

(1) Reinforcement dowels embedded 5 ft or less shall be permitted to be installed after concrete placement, while the concrete is still workable.

(2) For augered cast-in-place piles installed with a hollow-stem auger, reinforcement shall be installed after grout is placed while the grout is still workable. Longitudinal reinforcement without ties, shall be permitted to be placed through the hollow stem of the auger prior to grouting.

(3) For deep foundations supporting light frame construction of up to two stories in height for residential or utility occupancies, reinforcement shall be permitted to be installed after concrete placement, while the concrete is still workable. The concrete cover requirement is permitted to be reduced to 2 in., provided that the construction method can be demonstrated to the satisfaction of the building official.

COMMENTARY

with grout because the hollow-stem auger must be positioned in the hole at all times during drilling and grouting operations. Grout placed in augered cast-in-place piles (also referred to as auger cast piles) is usually a mixture of cementitious materials, water, aggregate with a nominal maximum size of 3/8 in., and any admixtures. Use of larger aggregate may inhibit the installation of reinforcement after grout placement.

26.6—Reinforcement materials and construction requirements

26.6.1 General

26.6.1.1 Design information:

(a) ASTM designation, Supplementary Requirements S1, if **ASTM A706** is specified, and grade of reinforcement

(b) Type, size, location requirements, detailing, and embedment length of reinforcement.

(c) Concrete cover to reinforcement.

(d) Location and length of lap splices.

(e) Class and location of mechanical splices.

(f) Type and location of end-bearing splices.

(g) Type and location of welded splices and other required welding of reinforcing bars.

(h) ASTM designation for protective coatings of nonprestressed reinforcement.

(i) Corrosion protection for exposed reinforcement intended to be bonded with extensions on future construction.

26.6.1.2 Compliance requirements:

(a) **ASTM A706** reinforcement shall be specified to include ASTM A706, Supplementary Requirements S1.

(b) Mill test reports for reinforcement shall be submitted.

R26.6—Reinforcement materials and construction requirements

R26.6.1 General

R26.6.1.1

(a) For ASTM A706 reinforcement, specification of Supplementary Requirements S1 is required. ASTM A706 Supplementary Requirements S1 require reference in the construction documents. ASTM A706 requires the bar purchaser specify the Supplementary Requirements S1.

(d) Lap splices should, if possible, be located away from points of maximum tensile stress. The lap splice requirements of **25.5.2** encourage this practice.

(e) Refer to **R25.5.7.2**.

(g) Refer to **R25.5.7.3** and R26.6.4.

R26.6.1.2

(a) Refer to R26.6.1.1.

CODE

(c) Test reports or evaluation service reports for mechanical splices shall be submitted, demonstrating compliance with the tensile strength, compressive strength, tensile strain, elastic and inelastic cyclic endurance, and residual slip requirements applicable for the class of mechanical splice, and grade and size of bar being used.

(d) Mechanical splices shall be installed by qualified installers.

(e) Mechanical splicing devices shall be installed in accordance with construction documents and the manufacturer's published installation instructions.

(f) Nonprestressed reinforcement with rust, mill scale, or a combination of both shall be considered satisfactory, provided a hand-wire-brushed representative test specimen of the reinforcement complies with the applicable ASTM specification for the minimum dimensions (including height of deformations) and weight per unit length.

(g) Prestressing reinforcement shall be free of mill scale, pitting, and excessive rust. A light coating of rust shall be permitted.

(h) At the time concrete is placed, reinforcement to be bonded shall be clean of ice, mud, oil, or other deleterious coatings that decrease bond.

26.6.2 Placement

26.6.2.1 Design information:

(a) Tolerances on location of reinforcement taking into consideration tolerances on d and specified concrete cover in accordance with Table 26.6.2.1(a).

Table 26.6.2.1(a)—Tolerances on d and specified cover

d , in.	Tolerance on d , in.	Tolerance on specified concrete cover, in. ^[1]	
≤ 8	±3/8	Smaller of:	−3/8
			− (1/3) · specified cover
> 8	±1/2	Smaller of:	−1/2
			− (1/3) · specified cover

^[1]Tolerance for cover to formed soffits is −1/4 in.

COMMENTARY

(c) Requirements for mechanical splices are found in Table 25.5.7.2 and testing is described in 25.5.7.6.

(d) Installers should obtain instruction through product-specific training offered by manufacturers of mechanical splicing devices.

(f) Specific limits on rust are based on tests (Kemp et al. 1968) plus a review of earlier tests and recommendations. Kemp et al. (1968) provides guidance with regard to the effects of rust and mill scale on bond characteristics of deformed reinforcing bars. Research has shown that a normal amount of rust increases bond. Handling during construction activities generally removes any loosely-adhering rust on the reinforcing bars that may otherwise impair the bond of the bars with the surrounding concrete. (g) Guidance for evaluating the degree of rusting on strand is given in Sason (1992).

(h) The use of epoxy coating in accordance with 20.5.2 is permitted. Materials used for the protection of prestressed reinforcement against corrosion in unbonded tendons are not considered to be contaminants as described in this provision.

R26.6.2 Placement

R26.6.2.1 Generally accepted practice, as reflected in ACI SPEC-117, has established tolerances on total depth (formwork or finish) and fabrication of closed ties, stirrups, spirals, and truss bent reinforcing bars. The licensed design professional should specify more restrictive tolerances than those permitted by the Code when necessary to minimize the accumulation of tolerances resulting in excessive reduction in effective depth or cover.

More restrictive tolerances have been placed on minimum clear distance to formed soffits because of their importance for durability and fire protection and because reinforcement is usually supported in such a manner that the specified tolerance is practical.

More restrictive tolerances than those required by the Code may be desirable for prestressed concrete. In such cases, the construction documents should specify the necessary tolerances. Recommendations are provided in ACI ITG-7.

The Code permits a reinforcement placement tolerance on effective depth d that is directly related to the flexural and shear strength of the member. Because reinforcement is placed with respect to edges of members and formwork surfaces, d is not always conveniently measured in the field. This provision is included in the design information section

CODE

(b) Tolerance for longitudinal location of bends and ends of reinforcement in accordance with Table 26.6.2.1(b). The tolerance for specified concrete cover in Table 26.6.2.1(a) shall also apply at discontinuous ends of members.

(c) Tolerance for spacing of hoops in members of intermediate and special seismic systems:

- (1) Lesser of $+1\frac{1}{2}$ in. and $+1.5d_b$ of the smallest longitudinal bar.
- (2) Lesser of -1 in. per ft of least side dimension of member and -3 in.
- (3) Spacing adjustments shall result in no more than two hoops being in contact with each other.

Table 26.6.2.1(b)—Tolerances for longitudinal location of bends and ends of reinforcement

Location of bends or reinforcement ends	Tolerances, in.
Discontinuous ends of brackets and corbels	$\pm 1/2$
Discontinuous ends of other members	± 1
Other locations	± 2

26.6.2.2 Compliance requirements:

(a) Reinforcement, including bundled bars, shall be placed within required tolerances and supported to prevent displacement beyond required tolerances during concrete placement.

(b) Spiral units shall be continuous bar or wire placed with even spacing and without distortion beyond the tolerances for the specified dimensions.

(c) Splices of reinforcement shall be made only as permitted in the construction documents, or as authorized by the licensed design professional.

(d) For longitudinal column bars forming an end-bearing splice, the bearing of square cut ends shall be held in concentric contact.

COMMENTARY

because tolerances on d should be considered in member design. Placement tolerances for cover are also provided.

Tolerances for placement of reinforcement should be specified in accordance with ACI SPEC-117 unless stricter tolerances are required. The more restrictive tolerance for spacing of hoops in members of intermediate and special seismic systems is to provide better control against premature buckling of longitudinal bars.

R26.6.2.2

(a) Reinforcement, including bundled bars, should be adequately supported in the forms to prevent displacement by concrete placement or workers. Bundled bars should be tied or otherwise fastened together to maintain their position, whether vertical or horizontal. Beam stirrups should be supported on the bottom form of the beam by supports such as continuous longitudinal beam bolsters. If only the longitudinal beam bottom reinforcement is supported, construction traffic can dislodge the stirrups as well as any top beam reinforcement tied to the stirrups.

(b) Spirals should be held firmly in place, at proper pitch and alignment, to prevent displacement during concrete placement. The Code has traditionally required spacers to hold the fabricated spiral cage in place, but alternate methods of installation are also permitted. If spacers are used, the following may be used for guidance: for spiral bar or wire smaller than $5/8$ in. diameter, a minimum of two spacers should be used for spirals less than 20 in. in diameter, three spacers for spirals 20 to 30 in. in diameter, and four spacers for spirals greater than 30 in. in diameter. For spiral bar or wire $5/8$ in. diameter or larger, a minimum of three spacers should be used for spirals 24 in. or less in diameter, and four spacers for spirals greater than 24 in. in diameter.

(d) Experience with end-bearing splices has been almost exclusively with vertical bars in columns. If bars are significantly inclined from the vertical, attention is required to ensure that adequate end-bearing contact can be achieved and maintained.

CODE

(e) Bar ends shall terminate in flat surfaces within 1.5 degrees of a right angle to the axis of the bars and shall be fitted within 3 degrees of full bearing after assembly.

26.6.3 Bending**26.6.3.1 Design information:**

(a) Nonstandard bend geometry.

26.6.3.2 Compliance requirements:

(a) Reinforcement shall be bent cold prior to placement, unless otherwise permitted by the licensed design professional.

(b) Field bending of reinforcement partially embedded in concrete shall not be permitted, except as shown in the construction documents or permitted by the licensed design professional.

(c) Offset bars shall be bent before placement in the forms.

26.6.4 Welding**COMMENTARY**

(e) These tolerances represent practice based on tests of full-size members containing No. 18 bars.

R26.6.3 Bending

R26.6.3.1 Bend radii larger than the minimums of Tables 25.3.1 and 25.3.2 may be required by geometric constraints or by 23.10 for discontinuity regions designed using the strut-and-tie method with curved-bar nodes. Nonstandard bends should be indicated on the drawings.

R26.6.3.2

(b) Construction conditions may make it necessary to bend bars that have been embedded in concrete. Such field bending should not be done without authorization of the licensed design professional. Construction documents should specify whether the bars will be permitted to be bent cold or if heating should be used. Bends should be gradual and should be straightened as required.

Tests (Black 1973; Stecich et al. 1984) have shown that ASTM A615 Grade 40 and Grade 60 reinforcing bars can be cold bent and straightened up to 90 degrees at or near the minimum diameter specified in 25.3. If cracking or breakage is encountered, preheating the reinforcing bar to between 1100 and 1200°F may avoid this condition for the remainder of the bars. Bars that fracture during bending or straightening can be spliced outside the bend region.

Heating should be performed in a manner that will avoid damage to the concrete. If the bend area is within approximately 6 in. of the concrete, some protective insulation may need to be applied. Heating of the bar should be controlled by temperature-indicating crayons or other suitable means. The heated bars should not be artificially cooled (with water or forced air) until after cooling to at least 600°F.

R26.6.4 Welding

If welding of reinforcing bars is required, the weldability of the steel and compatible welding procedures need to be considered. The provisions in AWS D1.4 cover aspects of welding reinforcing bars, including criteria to qualify welding procedures.

Weldability of the steel is based on its carbon equivalent (CE), calculated from the chemical composition of the steel. AWS D1.4 establishes preheat and interpass temperatures for a range of carbon equivalents and reinforcing bar sizes. AWS D1.4 has two expressions for calculating CE. The expression considering only the elements carbon and

CODE**COMMENTARY**

manganese is to be used for bars other than **ASTM A706**. A more comprehensive CE expression is given for ASTM A706 bars, which is identical to the CE formula presented in ASTM A706.

ASTM A706 covers low-alloy steel reinforcing bars intended for applications that require controlled tensile properties, welding, or both. Weldability is accomplished in ASTM A706 by requiring the CE not to exceed 0.55 percent and controlling the chemical composition. The manufacturer is required by ASTM A706 to report the chemical analysis and carbon equivalent (**Gustafson and Felder 1991**). When welding reinforcing bars other than ASTM A706, the construction documents should specifically require that the mill test report include chemical analysis results to permit calculation of the carbon equivalent.

It is often necessary to weld to existing reinforcing bars in a structure when no mill test report of the existing reinforcement is available. This condition is particularly common in alterations or building expansions. AWS D1.4 states for such bars that a chemical analysis may be performed on representative bars. If the chemical composition is not known or obtained, AWS D1.4 requires a minimum preheat. For bars other than **ASTM A706**, the minimum preheat required is 300°F for No. 6 bars or smaller, and 500°F for No. 7 bars or larger. The required preheat for all sizes of ASTM A706 bars is to be the temperature given in the Welding Code's table for minimum preheat corresponding to the range of CE "over 0.45 percent to 0.55 percent." Welding of the particular bars should be performed in accordance with **AWS D1.4**. It should also be determined if additional precautions are necessary, based on other considerations such as stress level in the bars, consequences of failure, and heat damage to existing concrete due to welding operations.

AWS D1.4 requires the contractor to prepare welding procedure specifications (WPSs) conforming to the requirements of the Welding Code. Appendix A in AWS D1.4 contains a suggested form that shows the information required for a WPS.

Welding of wire to wire, and of wire or welded wire reinforcement to reinforcing bars or structural steel elements is not covered by AWS D1.4. If welding of this type is required on a project, the construction documents should specify requirements or performance criteria for this welding. If cold-drawn wires are to be welded, the welding procedures should address the potential loss of yield strength and ductility achieved by the cold-working process (during manufacture) when such wires are heated by welding. These potential concerns are not an issue for machine and resistance welding as used in the manufacture of welded plain and deformed wire reinforcement covered by **ASTM A1064**.

CODE

26.6.4.1 Design information:

(a) Details for welding of anchor bars at the front face of brackets or corbels designed by the licensed design professional in accordance with **16.5.6.3(a)**.

26.6.4.2 Compliance requirements:

(a) Welding of all nonprestressed bars shall conform to the requirements of **AWS D1.4**. ASTM specifications for bar reinforcement, except for **ASTM A706**, shall be supplemented to require a mill test report of material properties that demonstrate conformance to the requirements in AWS D1.4.

(b) Welding of crossing bars shall not be used for assembly of reinforcement except at the front face of brackets or corbels or as otherwise permitted by the licensed design professional.

COMMENTARY

R26.6.4.2

(b) “Tack” welding (welding crossing bars) can seriously weaken a bar at the point welded by creating a metallurgical notch effect. This operation can be performed safely only when the material welded and welding operations are under continuous competent control, as in the manufacture of welded wire reinforcement. Welding of anchor bars at the front face of brackets or corbels is addressed in **R16.5.6.3**.

26.7—Anchoring to concrete**26.7.1** Design information:

(a) Requirements for assessment and qualification of anchors for the applicable conditions of use shall be in accordance with **17.1.2**. Requirements for assessment and qualification of post-installed reinforcing bars shall be in accordance with **17.1.3**.

(b) Type, size, location requirements, effective embedment depth, and installation requirements for anchors.

(c) Type, size, and location or location requirements for anchor reinforcement designed to develop the anchor strength in accordance with **17.5.2.1**, as well as transverse confinement reinforcement for anchors installed in the tops of columns or pedestals in accordance with **10.7.6.1.5**.

(d) Type, size, and location for shear lugs designed to develop shear strength in accordance with **17.11**.

(e) Size and location of base plate holes to permit inspection and vent air when placing concrete or grout per **17.11.1.2**.

(f) Minimum edge distance of anchors in accordance with **17.9**.

(g) Corrosion protection for exposed anchors intended for attachment with future construction.

(h) For post-installed anchors, parameters associated with the design strength in accordance with **17.5**, including anchor category, concrete strength, aggregate type, type of lightweight concrete, required installation torque, and requirements for hole drilling and preparation.

R26.7—Anchoring to concrete

R26.7.1 Minimum requirements for specification of anchors in the construction documents for conformance with the Code are listed.

(a) Post-installed anchor strength and deformation capacity are assessed by acceptance testing under **ACI CODE-355.2** or ACI CODE-355.4. These tests are carried out assuming installation in accordance with the manufacturer’s recommended procedures (in the case of adhesive anchors, the Manufacturer’s Printed Installation Instructions [MPII]).

(h) Certain types of anchors can be sensitive to variations in hole diameter, cleaning conditions, orientation of the axis, magnitude of the installation torque, crack width, and other variables. Some of this indirectly accounted for in the assigned ϕ values for the different anchor categories, which depend in part on the results of the installation

CODE

(i) For adhesive anchors in tension, parameters associated with the characteristic bond stress used for design in accordance with 17.6.5, including concrete temperature range, moisture condition of concrete at time of installation, type of lightweight concrete, if applicable, and requirements for hole drilling and preparation.

(j) Identification of adhesive anchors and post-installed reinforcing bars installed in a horizontal or upwardly inclined orientation to resist sustained tensile loads.

(k) Identification of adhesive anchors requiring proof loading in accordance with ACI CODE-355.4 or the inspection program established by the licensed design professional.

(l) Specify certification required for installers of adhesive anchors and post-installed reinforcing bars including adhesive anchors and post-installed reinforcing bars that are installed in a horizontal or upwardly inclined orientation to resist sustained tensile loads.

COMMENTARY

safety tests. If anchor components are altered or if anchor installation procedures deviate from those specified, the anchor may fail to comply with the acceptance criteria of ACI CODE-355.2 or ACI CODE-355.4.

(i) Due to the sensitivity of bond strength to installation, on-site quality control is important for adhesive anchors and post-installed reinforcing bars. The construction documents must provide all parameters relevant to the characteristic bond stress used in design. These parameters may include, but are not limited to:

- (a) Acceptable anchor installation environment (dry or saturated concrete; concrete temperature range)
- (b) Acceptable drilling methods
- (c) Required hole cleaning procedures
- (d) Anchor type and size range (threaded rod or reinforcing bar)

Hole cleaning is intended to ensure that drilling debris and dust do not impair bond. Depending on the Manufacturer's Printed Installation Instructions (MPII), type of qualified anchor, and on-site conditions, hole cleaning may involve operations to remove drilling debris from the hole with vacuum or compressed air mechanical brushing of the hole wall to remove surface dust, and a final step to evacuate any remaining dust or debris, usually with compressed air. If wet core drilling is used, holes may be flushed with water and then dried with compressed air. Compressed air must be free of oil and moisture. For post-installed anchors and reinforcing bars installed in locations where the concrete is saturated (for example, outdoor locations exposed to rain-fall), the resulting drilling mud must be removed by other means. In all cases, the procedures used should be clearly described by the MPII accompanying the product. If the installation procedures are not clearly described, contact the manufacturer. These printed installation instructions, which also describe the limits on concrete temperature and the presence of water during installation as well as the procedures necessary for void-free adhesive injection and adhesive cure requirements, constitute an integral part of the adhesive anchor or post-installed reinforcing bar system and are part of the assessment performed in accordance with ACI CODE-355.4 or, for post-installed reinforcing bars, ACI CODE-355.5.

(l) Adhesive anchors and post-installed reinforcing bars are sensitive to installation orientation. This sensitivity, combined with variability in strength of adhesive anchors and post-installed reinforcing bars subjected to sustained tensile loading, requires installation by certified installers. Certification may also be appropriate for other

CODE

26.7.2 Compliance requirements:

(a) Cast-in anchors, their attachments, and anchor reinforcement, shall be securely positioned in the formwork and oriented in accordance with the construction documents. Concrete shall be consolidated around anchors and anchor reinforcement using suitable means during placement.

(b) Proper consolidation of concrete or grout around shear lugs shall be verified by use of base plate inspection holes.

(c) Post-installed anchors and post-installed reinforcing bars shall be installed in accordance with the manufacturer's instructions. Post-installed adhesive anchors shall be installed in accordance with the Manufacturer's Printed Installation Instructions (MPII).

(d) Post-installed anchors and post-installed reinforcing bars shall be installed by qualified installers.

(e) Adhesive anchors and post-installed reinforcing bars identified in the construction documents as installed in a horizontal or upwardly inclined orientation to resist sustained tensile loads shall be installed by certified personnel. Certification shall be through an independent, third party program as defined by the ACI Adhesive Anchor Installer Certification Program (ACI CCP 680.1-17), or equivalent. The acceptability of certification other than the ACI Adhesive Anchor Installation Certification Program shall be the responsibility of the licensed design professional.

(f) Adhesive anchors and post-installed reinforcing bars shall be installed in concrete having a minimum age of 21 days at time of anchor installation.

COMMENTARY

safety-related applications. Installers can become certified through testing and training programs that include written and performance examinations as defined by the ACI Adhesive Anchor Installer Certification program (ACI CPP 680.1-17) or similar programs with equivalent requirements. The acceptability of certification other than the ACI Adhesive Anchor Installer Certification should be determined by the Licensed Design Professional. In addition, installers should obtain instruction through product-specific training offered by manufacturers of qualified adhesive anchor and post-installed reinforcing bar systems.

An equivalent certified installer program should test the installer's knowledge and skill by an objectively fair and unbiased administration and grading of a written and performance exam. Programs should reflect the knowledge and skill required to install available commercial anchor systems. The effectiveness of a written exam should be verified through statistical analysis of the questions and answers. An equivalent program should provide a responsive and accurate mechanism to verify credentials, which are renewed on a periodic basis.

R26.7.2

(c) The Manufacturer's Printed Installation Instructions (MPII) contain information required for the proper installation of post-installed adhesive anchors. Additional requirements may apply for specific cases in accordance with 26.7.1(f) and 26.7.1(g). For adhesive anchors, application-dependent requirements for qualification of installers and inspection requirements may apply.

(e) Many anchor performance characteristics depend on proper installation of the anchor. Horizontally or upwardly inclined adhesive anchors resisting sustained tension load are required to be installed by personnel certified for the adhesive anchor system and installation procedures being used. Construction personnel can establish qualifications by becoming certified through certification programs.

(f) Adhesive anchors qualified in accordance with ACI CODE-355.4 are tested in concrete with compressive strengths within two ranges: 2500 to 4000 psi and 6500 to

CODE**COMMENTARY**

8500 psi. Bond strength is, in general, not highly sensitive to concrete compressive strength. The design performance of adhesive anchors cannot be ensured by establishing a minimum concrete compressive strength at the time of installation in early-age concrete. Therefore, a minimum concrete age of 21 days at the time of adhesive anchor installation was adopted.

26.8—Embedments**26.8.1** Design information:

- (a) Type, size, details, and location of embedments designed by the licensed design professional.
- (b) Reinforcement required to be placed perpendicular to pipe embedments.
- (c) Specified concrete cover for pipe embedments with their fittings.
- (d) Corrosion protection for exposed embedments intended to be connected with future construction.

26.8.2 Compliance requirements:

- (a) Type, size, details, and location of embedments not shown in the construction documents shall be submitted for review by the licensed design professional.
- (b) If aluminum embedments are used, (1) through (3) shall apply:
 - (1) Aluminum embedments shall be coated or covered to prevent aluminum-concrete reaction;
 - (2) Aluminum embedments shall be electrically isolated from steel or other metals;
 - (3) Calcium chloride and admixtures containing chlorides other than background amounts of chlorides as an impurity in the admixture ingredients are prohibited.
- (c) Pipes and fittings not shown in the construction documents shall be designed to resist effects of the material, pressure, and temperature to which they will be subjected.
- (d) No liquid, gas, or vapor, except water not exceeding 90°F or 50 psi pressure, shall be placed in the pipes until the concrete has attained its specified strength.
- (e) In solid slabs, piping, except for radiant heating or snow melting, shall be placed between top and bottom reinforcement.
- (f) Conduit and piping shall be fabricated and installed so that cutting, bending, or displacement of reinforcement from its specified location is not required.

26.9—Additional requirements for precast concrete**26.9.1** Design information:

- (a) Dimensional tolerances for precast members and interfacing members.

R26.9—Additional requirements for precast concrete**R26.9.1**

- (a) Design of precast members and connections is particularly sensitive to tolerances on the dimensions of individual members and on their location in the structure. To prevent misunderstanding, the tolerances used in

CODE

(b) If designed by the licensed design professional, details of lifting devices, embedments, and related reinforcement required to resist temporary loads from handling, storage, transportation, and erection.

(c) If designed by the licensed design professional, location, size, and jacking stress of pretensioned reinforcement.

(d) If designed by the licensed design professional, minimum specified compressive strength of concrete at transfer of prestress, f_{ci} , and at other designated stages of construction.

26.9.2 Compliance requirements:

(a) Members shall be marked to indicate location and orientation in the structure and date of manufacture.

(b) Identification marks on members shall correspond to erection drawings.

(c) Design and details of lifting devices, embedments, and related reinforcement required to resist temporary loads from handling, storage, transportation, and erection shall be provided if not designed by the licensed design professional.

(d) During erection, precast members and structures shall be supported and braced to ensure proper alignment, strength, and stability until permanent connections are completed.

(e) If approved by the licensed design professional, items embedded while the concrete is in a plastic state shall satisfy (1) through (4):

(1) Embedded items shall protrude from the precast concrete members or remain exposed for inspection.

(2) Embedded items are not required to be hooked or tied to reinforcement within the concrete.

(3) Embedded items shall be maintained in the correct position while the concrete remains plastic.

(4) The concrete shall be consolidated around embedded items.

COMMENTARY

design should be specified in the construction documents. Instead of specifying individual tolerances, the standard industry tolerances assumed in design may be specified. It is important to specify any deviations from standard industry tolerances.

The tolerances required by 26.6.2 are considered to be a minimum acceptable standard for reinforcement in precast concrete. Industry-standard product and erection tolerances are provided in **ACI ITG-7**. Interfacing tolerances for precast concrete with cast-in-place concrete are provided in **ACI SPEC-117**.

(b) If the devices, embedments, or related reinforcement are not designed by the licensed design professional, these details should be provided in shop drawings in accordance with 26.9.2(c).

(c) If location, size, and jacking stress of pretensioned reinforcement are not designed by the licensed design professional, these details should be provided in shop drawings.

(d) **Section 19.2.1.4** provides a minimum required compressive strength at transfer of prestress for pretensioned members. Additional designated stages of construction for precast concrete include stripping from the forms, handling, shipping, and erection. **PCI MNL-116** and **PCI MNL-120** provide guidance on minimum compressive strengths for these other stages.

R26.9.2

(c) Refer to R26.9.1(b). At the option of the licensed design professional, specifications can require that shop drawings, calculations, or both be submitted for the items included in this provision when their design is delegated to the contractor.

(d) All temporary erection connections, bracing, and shoring as well as the sequencing of removal of these items should be shown in construction documents or erection drawings, depending on the assignment of responsibility for the means and methods of construction.

(e) Many precast products are manufactured in such a way that it is difficult, if not impossible, to position reinforcement that protrudes from the concrete before the concrete is placed. Such items as ties for horizontal shear and inserts can be placed while the concrete is plastic, if proper precautions are taken. This provision is not applicable to reinforcement that is completely embedded, or to embedded items that will be hooked or tied to embedded reinforcement.

CODE

(f) Initial force in pretensioned reinforcement shall be verified by (1) and (2):

(1) Measured elongation of prestressed reinforcement compared with elongation calculated using the modulus of elasticity determined from tests or as reported by the manufacturer.

(2) Jacking force measured using calibrated equipment.

(g) A difference in force determined by (1) and (2) of 26.9.2(f) that exceeds 5% shall be ascertained and corrected, unless approved by the licensed design professional.

(h) Loss of prestress force due to unreplaced broken pretensioned reinforcement shall not exceed 2% of the total prestress force in prestressed concrete members, unless approved by the licensed design professional.

(i) Flame cutting or welding operations near prestressing reinforcement shall be performed in such a manner that prestressing reinforcement is not subject to welding sparks, ground currents, or temperatures that could affect the reinforcement properties.

(j) If the transfer of force from the anchorages of the pretensioning bed to the concrete is accomplished by flame cutting prestressed reinforcement, the cutting locations and cutting sequence shall be selected to avoid undesired temporary stresses in pretensioned members.

(k) Long lengths of exposed pretensioned strand shall be cut near the member to minimize shock to the concrete.

COMMENTARY

(f) Verification of initial force in pretensioned reinforcement should be performed in accordance with PCI MNL-116. Equipment used to measure jacking force includes hydraulic pressure gauges, dynamometers, and load cells. PCI MNL-116 provides requirements for calibration and measurement resolution of this equipment.

(g) The 5% tolerance reflects experience with production of pretensioned members and accuracy of the verification methods. PCI MNL-116 provides guidance if the difference exceeds 5%.

26.10—Additional requirements for post-tensioned concrete**26.10.1 Design information:**

- (a) Magnitude and location of prestressing forces.
- (b) Stressing sequence of tendons.

(c) Type, size, details, and location of post-tensioning anchorages for systems selected by the licensed design professional.

(d) Tolerances for placement of tendons and post-tensioning ducts in accordance with Table 26.6.2.1(a).

(e) Materials and details of corrosion protection for tendons, couplers, end fittings, post-tensioning anchorages, and anchorage regions.

R26.10—Additional requirements for post-tensioned concrete**R26.10.1**

(b) The sequence of anchorage device stressing can have a significant effect on general zone stresses. Therefore, it is important to consider not only the final stage of a stressing sequence with all tendons stressed, but also intermediate stages during construction. The most critical bursting forces caused by each of the sequentially post-tensioned tendon combinations, as well as that of the entire group of tendons, should be taken into account.

(e) For recommendations regarding protection, refer to Sections 4.2 and 4.3 of [ACI PRC-423.3](#), and Sections 3.4, 3.6, 5, 6, and 8.3 of [ACI SPEC-423.7](#). Also refer to [20.5.1.4.2](#) for corrosion protection requirements.

Corrosion protection can be achieved by a variety of methods. The corrosion protection provided should be suitable for the environment in which the tendons are located. Some conditions will require that the prestressed reinforcement be protected by concrete cover or by cement grout in metal or plastic duct; other conditions will

CODE

- (f) Requirements for ducts for bonded tendons.
- (g) Requirements for grouting of bonded tendons, including maximum water-soluble chloride ion (Cl^-) content requirements in [19.4.1](#).

26.10.2 Compliance requirements:

- (a) Type, size, details, and location of post-tensioning anchorage systems not shown in the construction documents shall be submitted to the licensed design professional for review.
- (b) Tendons and post-tensioning ducts shall be placed within required tolerances and supported to prevent displacement beyond required tolerances during concrete placement.
- (c) Couplers shall be placed in areas approved by the licensed design professional and enclosed in housings long enough to permit necessary movements.
- (d) Burning or welding operations in the vicinity of prestressing reinforcement shall be performed in such a manner that prestressing reinforcement is not subject to welding sparks, ground currents, or temperatures that degrade the properties of the reinforcement.
- (e) Prestressing force and friction losses shall be verified by (1) and (2).
 - (1) Measured elongation of prestressed reinforcement compared with elongation calculated using the modulus of elasticity determined from tests or as reported by the manufacturer.
 - (2) Jacking force measured using calibrated equipment such as a hydraulic pressure gauge, load cell, or dynamometer.
- (f) The cause of any difference in force determination between (1) and (2) of 26.10.2(e) that exceeds 7% shall be ascertained and corrected, unless approved by the licensed design professional.
- (g) Loss of prestress force due to unreplaced broken prestressed reinforcement shall not exceed 2% of the total prestress force in prestressed concrete members, unless approved by the licensed design professional.
- (h) Prestressing reinforcement shall not be stressed until the concrete compressive strength is at least 2500 psi for

COMMENTARY

permit the protection provided by coatings such as paint or grease. Corrosion protection methods should meet the fire protection requirements of the general building code unless the installation of external post-tensioning is to only improve serviceability.

(f) Guidance for specifying duct requirements for bonded tendons is provided in [PTI M50.3](#).

(g) Guidance for specifying grouting requirements for bonded tendons is provided in [PTI M55.1](#).

R26.10.2

(e) Elongation measurements for post-tensioning should be in accordance with the procedures outlined in [PTI M10.3](#) and [PTI C30.4](#).

(f) Elongation measurements for post-tensioned construction are affected by several factors. The friction along prestressing reinforcement may be affected to varying degrees by placing tolerances and small irregularities in tendon profile due to tendon and concrete placement. The friction coefficients between the prestressing reinforcement and the duct are also subject to variation.

(g) This provision applies to all prestressed concrete members. For cast-in-place post-tensioned slab systems, a member should be that portion considered as an element in the design, such as the joist and effective slab width in one-way joist systems, or the column strip or middle strip in two-way flat plate systems. Some members can be shown to accommodate more than 2% loss of prestress due to unreplaced broken prestressed reinforcement.

CODE

single-strand or bar tendons, 4000 psi for multistrand tendons, or a higher strength, if required. An exception to these strength requirements is provided in 26.10.2(i).

(i) Lower concrete compressive strength than required by 26.10.2(h) shall be permitted if (1) or (2) is satisfied:

- (1) Oversized anchorage devices are used to compensate for a lower concrete compressive strength.
- (2) Prestressing reinforcement is stressed to no more than 50% of the final prestressing force.

(j) The estimate of in-place concrete strength shall be based on tests of field-cured cylinders prepared in accordance with 26.5.3.2(d). Alternately, it may be based on other procedures approved by the licensed design professional and, when requested, approved by the building official.

26.11—Formwork**26.11.1 Design of formwork****26.11.1.1 Design information:**

- (a) Requirement for the contractor to design, fabricate, install, and remove formwork.
- (b) Location of composite members requiring shoring.
- (c) Requirements for removal of shoring of composite members.

26.11.1.2 Compliance requirements:

- (a) Design of formwork shall consider (1) through (6):
 - (1) Method of concrete placement.
 - (2) Rate of concrete placement.
 - (3) Construction loads, including vertical, horizontal, and impact.
 - (4) Avoidance of damage to previously constructed members.
 - (5) For post-tensioned members, allowance for movement of the member during tensioning of the prestressing reinforcement without damage to the member.
 - (6) For post-tensioned members, allowance for load redistribution on formwork resulting from tensioning of the prestressing reinforcement.

COMMENTARY

(i) To limit early shrinkage cracking, monostrand tendons are sometimes stressed at concrete strengths less than 2500 psi. In such cases, either oversized monostrand anchorages are used, or the strands are stressed in stages, often to levels one-third to one-half the final prestressing force.

(j) Acceptance criteria for field-cured cylinders are provided in 26.12.4.

R26.11—Formwork**R26.11.1 Design of formwork**

Typically, the contractor is responsible for formwork design, and the Code provides the minimum formwork performance requirements necessary for public health and safety. Detailed information on design and construction of formwork for concrete is given in “Guide to Formwork for Concrete” (ACI PRC-347).

ACI SPEC-301-20 Section 2 provides specifications for design and construction of formwork. *Formwork for Concrete*, ACI SP-4, provides practical guidance for contractors, engineers, and architects on planning, building, and using formwork.

R26.11.1.1 Section 24.2.5 covers the requirements pertaining to deflections of shored and unshored members.

CODE

(b) Formwork fabrication and installation shall result in a final structure that conforms to shapes, lines, and dimensions of the members as required by the construction documents.

(c) Formwork shall be sufficiently tight to inhibit leakage of paste or mortar.

(d) Formwork shall be braced or tied together to maintain position and shape.

26.11.2 Removal of formwork

26.11.2.1 Compliance requirements:

(a) Before starting construction, the contractor shall develop a procedure and schedule for removal of formwork and installation of reshores, and shall calculate the loads transferred to the structure during this process.

(b) Structural analysis and concrete strength requirements used in planning and implementing the formwork removal and reshore installation shall be furnished by the contractor to the licensed design professional and to the building official, when requested.

(c) No construction loads shall be placed on, nor any formwork removed from, any part of the structure under construction except when that portion of the structure in combination with remaining formwork has sufficient strength to support safely its weight and loads placed thereon and without impairing serviceability.

(d) Sufficient strength shall be demonstrated by structural analysis considering anticipated loads, strength of formwork, and an estimate of in-place concrete strength.

(e) The estimate of in-place concrete strength shall be based on tests of field-cured cylinders or on other procedures to evaluate concrete strength approved by the licensed design professional and, when requested, approved by the building official.

COMMENTARY

R26.11.2 Removal of formwork

R26.11.2.1 In determining the time for removal of formwork, consideration should be given to the construction loads and load combinations, in-place strength of concrete, and possibility of deflections greater than acceptable to the licensed design professional (ACI PRC-347, **ACI PRC-347.2**, and **ASCE/SEI 37**). Construction loads may be greater than the specified live loads. Even though a structure may have adequate strength to support the applied loads at early ages, deflections can cause serviceability problems.

The removal of formwork for multistory construction should be a part of a planned procedure developed by the contractor that considers the temporary support of the entire structure as well as each individual member. Such a procedure should be planned before construction and should be based on a structural analysis taking into account at least (a) through (e):

- (a) The structural system that exists at the various stages of construction, and the construction loads corresponding to those stages;
- (b) The in-place strength of the concrete at the various stages during construction;
- (c) The influence of deformations of the structure and shoring system on the distribution of dead loads and construction loads during the various stages of construction;
- (d) The strength and spacing of shores or shoring systems used, as well as the method of shoring, bracing, shore removal, and reshoring including the minimum time interval between the various operations;
- (e) Any other loading or condition that affects the safety or serviceability of the structure during construction.

ACI 347.2R provides information for shoring and reshoring multistory buildings.

(e) Evaluation of in-place concrete compressive strength during construction may be demonstrated by field-cured test cylinders in accordance with **ASTM C31**. Acceptance criteria for strength of field-cured cylinders are provided in 26.12.4. Alternative procedures to estimate in-place compressive strength include (a) through (e):

- (a) Tests of cast-in-place cylinders in accordance with **ASTM C873**. This method is limited to use for slabs where the depth of concrete is between 5 to 12 in.
- (b) Penetration resistance in accordance with **ASTM C803**

CODE

- (f) Formwork shall be removed in such a manner not to impair safety and serviceability of the structure.
- (g) Concrete exposed by formwork removal shall have sufficient strength not to be damaged by the removal.
- (h) Formwork supports for post-tensioned members shall not be removed until sufficient post-tensioning has been applied to enable post-tensioned members to support their dead load and anticipated construction loads.
- (i) No construction loads exceeding the combination of superimposed dead load plus live load including reduction shall be placed on any unshored portion of the structure under construction, unless analysis indicates adequate strength to support such additional loads and without impairing serviceability.

26.12—Evaluation and acceptance of hardened concrete**26.12.1 General****26.12.1.1 Compliance requirements:**

- (a) Evaluation of hardened concrete shall be based on strength tests. A strength test is the average of the compressive strengths of at least two 4 x 8 in. or two 6 x 12 in. cylinders made from the same sample of concrete taken in accordance with **ASTM C172** at the point of delivery, handled and standard-cured in accordance with **ASTM C31**, and tested in accordance with **ASTM C39** at 28 days or at test age designated for f'_c .
- (b) For shotcrete, a strength test shall be the average strength of at least three 3 in. nominal diameter cores taken from a test panel prepared in accordance with **ASTM C1140** and tested at 28 days from time of placement or at test age designated for f'_c .
- (c) The testing agency performing acceptance testing shall comply with **ASTM C1077**.

COMMENTARY

- (c) Pullout strength in accordance with **ASTM C900**
- (d) Maturity index measurements and correlation in accordance with **ASTM C1074**
- (e) Temperature-match curing of cylinders in accordance with **AASHTO R72**

Procedures (b), (c), and (d) require sufficient data for the materials used in the Work to demonstrate correlation of measurements on the structure with the compressive strength of molded cylinders or drilled cores. **ACI 228.1R** discusses the use of these methods to evaluate the in-place strength of concrete.

Procedure (e), temperature-match curing of cylinders in accordance with **AASHTO R72**, may be used to more closely represent the temperature within the concrete member during curing.

- (i) The nominal live load specified on the drawings is frequently reduced for members supporting large floor areas, and the limit on construction loads needs to account for such reductions. Information on loads, load factors, and load combinations for construction is presented in **ASCE/SEI 37**.

R26.12—Evaluation and acceptance of hardened concrete**R26.12.1 General****R26.12.1.1**

- (a) Previous editions of the Code required the use of at least three 4 x 8 in. cylinders for a strength test because available data for 4 x 8 in. cylinders made under laboratory conditions (**Carino et al. 1994**) indicated a higher within-test variability compared with 6 x 12 in. cylinders. Recent test data including cylinders prepared in the field, indicate the difference between the within-test variability of tests of 4 x 8 in. cylinders and 6 x 12 in. cylinders is not statistically significant (**Day 1994; Detwiler et al. 2006, 2009**). Accordingly, the Code now permits the use of at least two cylinders for a strength test for either 4 x 8 in. or 6 x 12 in. cylinders. Casting and testing more than the minimum number of cylinders may be desirable in case it becomes necessary to discard an outlying individual cylinder strength in accordance with **ACI PRC-214**. If individual cylinder strengths are discarded in accordance with **ACI PRC-214**, a strength test is valid provided the measured strength of at least two individual cylinders of the same size are averaged. All individual cylinder

CODE

(d) Certified field testing technicians shall perform tests on fresh concrete at the job site, prepare specimens for standard curing, prepare specimens for field curing, if required, and record the temperature of the fresh concrete when preparing specimens for strength tests.

(e) Certified laboratory technicians shall perform required laboratory tests.

(f) All reports of acceptance tests shall be provided to the licensed design professional, contractor, concrete producer, and, if requested, to the owner and the building official.

COMMENTARY

strengths that are not discarded in accordance with ACI PRC-214 are to be used to calculate the average strength. The size of specimens representing a strength test should be the same for each concrete mixture. The cylinder size should be agreed upon by the owner, licensed design professional, and testing agency before construction.

Representative concrete samples for making strength-test specimens are obtained from concrete as delivered to the project site. For example, samples of concrete delivered in a truck mixer would be obtained from the truck chute at discharge. **ASTM C172** provides requirements for sampling concrete from different equipment used in the production or transportation of concrete.

Note that the term “strength test” does not apply to results of tests on cylinders field cured in or on the structure as described in **ASTM C31**, nor does it apply to results of tests on cylinders from laboratory trial batches.

(c) **ASTM C1077** defines the duties, responsibilities, and minimum technical requirements of testing agency personnel and defines the technical requirements for equipment used in testing concrete and concrete aggregates. Agencies that test cylinders or cores to determine compliance with Code requirements should be accredited or inspected for conformance to the requirements of **ASTM C1077** by a recognized evaluation authority.

(d) Technicians can become certified through testing and training programs that include written and performance examinations. Field technicians in charge of sampling concrete; testing for slump, density (unit weight), yield, air content, and temperature; and making and curing test specimens should be certified in accordance with the ACI Concrete Field Testing Technician—Grade 1 Certification Program (**ACI CPP 610.1-18**) or an equivalent program meeting the requirements of **ASTM C1077**.

(e) Concrete laboratory testing technicians performing strength testing should be certified in accordance with the ACI Concrete Strength Testing Technician Certification Program (**ACI CPP 620.2-12**) or an equivalent program meeting the requirements of **ASTM C1077**.

(f) The Code requires testing reports to be distributed to the parties responsible for the design, concrete production, construction, and approval of the Work. Such distribution of test reports should be indicated in contracts for inspection and testing services. Prompt distribution of testing reports allows for timely identification of either compliance or the need for corrective action. A complete record of testing allows the concrete producer to reliably establish appropriate mixture proportions for future projects.

CODE

26.12.2 Frequency of testing**26.12.2.1 Compliance requirements:**

(a) For concrete evaluated and accepted based upon standard-cured cylinders, (1) through (3) shall apply:

(1) Samples for preparing strength-test specimens of each concrete mixture placed each day shall be taken in accordance with (i) through (iii):

- (i) At least once a day.
- (ii) At least once for each 150 yd³ of concrete.
- (iii) At least once for each 5000 ft² of surface area for slabs or walls.

(2) On a given project, if total volume of concrete is such that frequency of testing would provide fewer than five strength tests for a given concrete mixture, strength test specimens shall be made from at least five randomly selected batches or from each batch if fewer than five batches are used.

(3) If the total quantity of a given concrete mixture is less than 50 yd³, strength tests are not required if evidence of satisfactory strength is submitted to and approved by the building official.

(b) For shotcrete evaluated and accepted based on drilled cores taken from test panels, prepare a shotcrete test panel for each mixture and each nozzle operator at least once per day or for every 50 yd³ placed, whichever results in the greater number of panels.

26.12.3 Acceptance criteria for standard-cured specimens**26.12.3.1 Compliance requirements:**

(a) Strength level of a concrete mixture shall be acceptable if (1) and (2) are satisfied:

- (1) Every average of any three consecutive strength tests equals or exceeds f'_c .
- (2) No strength test falls below f'_c by more than 500 psi if f'_c is 5000 psi or less; or by more than $0.10f'_c$ if f'_c exceeds 5000 psi.

(b) If either of the requirements of 26.12.3.1(a) is not satisfied, steps shall be taken to increase subsequent strength tests.

COMMENTARY

R26.12.2 Frequency of testing**R26.12.2.1**

(a)(1) Concrete samples for preparing strength-test specimens are to be taken on a strictly random basis if they are to measure properly the acceptability of the concrete. To be representative within the period of placement, the choice of sampling times, or the concrete batches to be sampled, is to be made on the basis of chance alone. Batches are not sampled on the basis of appearance, convenience, or another possibly biased criterion, because the statistical analyses will lose their validity. **ASTM D3665** describes procedures for random selection of the batches to be tested. Specimens for one strength test (as defined in 26.12.1.1(a)) are to be made from a single batch, and **ASTM C172** requires that the sample be taken only after all adjustments to the batch are made.

In calculating surface area, only one side of the slab or wall is considered. Criterion (iii) will require more frequent sampling than once for each 150 yd³ placed if average wall or slab thickness is less than 9-3/4 in.

R26.12.3 Acceptance criteria for standard-cured specimens

R26.12.3.1 Evaluation and acceptance of the concrete can be determined as test results are received during the course of the Work. Strength tests failing to meet these criteria will occur occasionally, with a probability of approximately once in 100 tests (**ACI PRC-214**) even though concrete strength and uniformity are satisfactory. Allowance should be made for such statistically expected variations in deciding whether the strength being produced is adequate. The strength acceptance criteria of 26.12.3.1(a) apply to test results from either 4 x 8 in. or 6 x 12 in. test cylinders permitted in 26.12.1.1(a). The average difference (**Carino et al. 1994**) between test results obtained by the two specimen sizes is not considered to be significant in design.

(b) The steps taken to increase the values of subsequent strength tests will depend on the particular circumstances but could include one or more of (a) through (g):

- (a) Increase in cementitious materials content;
- (b) Reduction in or better control of water content;
- (c) Use of a water-reducing admixture to improve the dispersion of cementitious materials;
- (d) Other changes in mixture proportions;
- (e) Reduction in delivery time;
- (f) Closer control of air content;

CODE

(c) Requirements of 26.12.7 for investigating strength tests shall apply if the requirements of 26.12.3.1(a)(2) are not met.

26.12.4 Acceptance criteria for field-cured specimens

26.12.4.1 Compliance requirements

(a) Before application of prestressing forces or removal of shoring and formwork supporting beams and slabs, the compressive strength of field-cured cylinders shall be acceptable if the strengths of all cylinders made from the same sample and tested in accordance with ASTM C39 equal or exceed the strength required for that stage of construction, unless otherwise approved by the licensed design professional.

26.12.5 Acceptance criteria for shotcrete

26.12.5.1 Compliance requirements:

(a) Specimens for acceptance tests shall be in accordance with (1) and (2):

- (1) Test panels shall be prepared in the same orientation and by the same nozzle operator placing shotcrete.
- (2) Cores shall be obtained, conditioned, and tested in accordance with **ASTM C1604**.

(b) Strength of a shotcrete mixture shall be acceptable if the average compressive strength of three cores from a single test panel is not less than $0.85f'_c$ with no core having a strength less than $0.75f'_c$.

(c) If the requirement of 26.12.5.1(b) is not satisfied, steps shall be taken to increase the average of subsequent strength results.

(d) Requirements for investigating low strength-test results shall apply if the requirement of 26.12.5.1(b) is not met.

COMMENTARY

(g) Improvement in the quality of the testing, including strict compliance with **ASTM C172**, **ASTM C31**, and **ASTM C39**.

Such changes in operating procedures or small changes in cementitious materials content or water content should not require a formal resubmission of mixture proportions; however, changes in sources of cement, aggregates, or admixtures should be accompanied by evidence submitted to the licensed design professional that the concrete strength will be improved.

R26.12.4 Acceptance criteria for field-cured specimens

R26.12.4.1 Compliance requirements

Typically, the required in-place compressive strengths at designated construction stages are minimum values. Therefore, the strengths of all field-cured cylinders made from the same concrete sample must be at or above the required strength, rather than using the average strength. Criteria provided in 26.5.3.2(e) for the strength of field-cured cylinders are intended for evaluating the adequacy of procedures for protecting and curing concrete and are not appropriate for determining the adequacy of in-place strength at designated construction stages. Criteria provided in 26.12.3.1 for concrete acceptance based on strength tests of standard-cured cylinders are also not applicable to field-cured cylinders. The Code allows for exceptions to requiring all cylinders meet or exceed the required strength when approved by the licensed design professional, such as in cases where there is evidence that one or more cylinders have been mishandled. Other exceptions may be approved by the licensed design professional to suit project-specific conditions.

R26.12.5 Acceptance criteria for shotcrete

R26.12.5.1

(a) Cores taken from shotcrete test panels, made in accordance with **ASTM C1140**, typically have length-to-diameter ratios less than 1.75. Therefore the core strengths used for comparison with the acceptance criteria are the values after correction for the length to diameter ratio in accordance with ASTM C1604.

CODE

26.12.6 *Acceptance criteria for density of lightweight concrete***26.12.6.1** Compliance requirements:

- (a) Frequency of sampling for determining fresh density shall be according to 26.12.2.
- (b) Sampling of lightweight concrete for determining fresh density shall be at the point of delivery in accordance with **ASTM C172**.
- (c) Fresh density of lightweight concrete shall be determined in accordance with **ASTM C138**.
- (d) Acceptance of lightweight concrete for density shall be based on the submitted fresh concrete density in accordance with 26.4.2.2g.
- (e) Unless otherwise permitted by the licensed design professional, fresh density of lightweight concrete shall be acceptable if within $\pm 4.0 \text{ lb/ft}^3$ of the fresh density corresponding to the specified equilibrium density.

26.12.7 *Investigation of strength tests***26.12.7.1** Compliance requirements:

COMMENTARY

R26.12.6 *Acceptance criteria for density of lightweight concrete***R26.12.6.1**

- (e) The permitted tolerance for fresh density of a lightweight concrete mixture designed for the specified equilibrium density, w_c , is intended to account for variations in aggregate moisture, air content, batch quantities, and type of lightweight concrete. The impact of the density tolerance on the value of λ assumed in design is deemed to be acceptable. The licensed design professional can consider permitting a different tolerance on fresh density to accommodate expected variations if appropriate.

R26.12.7 *Investigation of strength tests*

R26.12.7.1 Requirements are provided if strength tests have failed to meet the acceptance criterion of 26.12.3.1(a)(2) or if the average strengths of field-cured cylinders do not comply with 26.5.3.2(e). These requirements are applicable only for evaluation of in-place strength at the time of construction. Strength evaluation of existing structures is covered by **Chapter 27**. The licensed design professional and building official should apply judgment as to the significance of low test results and whether they indicate need for concern. If further investigation is deemed necessary, such investigation may include in-place tests as described in **ACI PRC-228.1** or, in extreme cases, measuring the compressive strength of cores taken from the structure.

In-place tests of concrete, such as probe penetration (**ASTM C803**), rebound hammer (**ASTM C805**), or pullout test (**ASTM C900**), may be useful in determining whether a portion of the structure actually contains low-strength concrete. Unless these in-place tests have been correlated with compressive strength using accepted procedures, such as described in **ACI PRC-228.1**, they are of value primarily for comparisons within the same structure rather than as quantitative estimates of strength.

For cores, if required, conservative acceptance criteria are provided that should ensure structural adequacy for virtually any type of construction (**Bloem 1965, 1968; Malhotra 1976, 1977**). Lower-than-specified strength may be tolerated under many circumstances, but this is a matter of judgment on the part of the licensed design professional and building

CODE

(a) If any strength test of standard-cured cylinders falls below f_c' by more than the limit allowed for acceptance, or if tests of field-cured cylinders indicate deficiencies in protection and curing, steps shall be taken to ensure that structural adequacy of the structure is not jeopardized.

(b) If the likelihood of low-strength concrete is confirmed and calculations indicate that structural adequacy is significantly reduced, tests of cores drilled from the area in question in accordance with **ASTM C42** shall be permitted. In such cases, three cores shall be taken for each strength test that falls below f_c' by more than the limit allowed for acceptance.

(c) The licensed design professional or the building official shall be permitted to modify details of core tests as stated in **ASTM C42**.

(d) Cores shall be obtained, moisture-conditioned by storage in watertight bags or containers, transported to the testing agency, and tested in accordance with ASTM C42. Cores shall be tested between 5 days after last being wetted and 7 days after coring unless otherwise approved by the licensed design professional or building official.

(e) Concrete in an area represented by core tests shall be considered structurally adequate if (1) and (2) are satisfied:

(1) The average of three cores is equal to at least 85% of f_c' .

(2) No single core is less than 75% of f_c' .

COMMENTARY

official. If time and conditions permit, an effort may be made to improve the strength of the concrete in place by supplemental wet curing. Effectiveness of supplemental curing should be verified by further strength evaluation using procedures previously discussed.

The Code, as stated, concerns itself with achieving structural safety, and the requirements for investigation of low strength-test results (26.12.7) are aimed at that objective. It is not the function of the Code to assign responsibility for strength deficiencies.

(a) If the strength of field-cured cylinders does not conform to 26.5.3.2(e), steps need to be taken to improve the curing. If supplemental in-place tests confirm a possible deficiency in strength of concrete in the structure, core tests may be required to evaluate structural adequacy.

(c) Some default requirements in ASTM C42 are permitted to be altered by the “specifier of the tests,” who is defined in ASTM C42 as “the individual responsible for analysis or review and acceptance of core test results.” For the purposes of ACI CODE-318, the “specifier of the tests” is the licensed design professional or the building official.

(d) The use of a water-cooled core barrel or a water-cooled saw for end trimming results in a core with a moisture gradient between the exterior surface and the interior. This gradient lowers the apparent compressive strength of the core (**Bartlett and MacGregor 1994**). The requirement of at least 5 days between the time of last being wetted and time of testing provides time for the moisture gradient to be reduced. The maximum time of 7 days between coring and testing is intended to ensure timely testing of cores if strength of concrete is in question.

Research (**Bartlett and MacGregor 1994**) has also shown that other moisture conditioning procedures, such as soaking or air drying, affect measured core strengths and result in conditions that are not representative of the in-place concrete. Therefore, to provide reproducible moisture conditions that are representative of in-place conditions, a standard moisture conditioning procedure that permits dissipation of moisture gradients is prescribed for cores. ASTM C42 permits the specifier of the tests to modify the default duration of moisture conditioning before testing. The specifier of the tests, however, must be aware of the potential reduction in strength if cores are tested before moisture gradients are allowed to dissipate.

(e) An average core strength of 85% of the specified strength is realistic (**Bloem 1968**). It is not realistic, however, to expect the average core strength to be equal to f_c' , because of differences in the size of specimens,

CODE

(f) Additional testing of cores extracted from locations represented by erratic core strength results shall be permitted.

(g) If criteria for evaluating structural adequacy based on core strength results are not met, and if the structural adequacy remains in doubt, the responsible authority shall be permitted to order a strength evaluation in accordance with **Chapter 27** for the questionable portion of the structure or take other appropriate action.

26.12.8 Acceptance of steel fiber-reinforced concrete

26.12.8.1 Compliance requirements:

(a) Steel fiber-reinforced concrete used for shear resistance shall satisfy (1) through (3):

- (1) The compressive strength acceptance criteria for standard-cured specimens
- (2) The residual strength obtained from flexural testing in accordance with **ASTM C1609** at a midspan deflection of 1/300 of the span length is at least the greater of (i) and (ii):
 - (i) 90% of the measured first-peak strength obtained from a flexural test and
 - (ii) 90% of the strength corresponding to $7.5\sqrt{f'_c}$
- (3) The residual strength obtained from flexural testing in accordance with **ASTM C1609** at a midspan deflection of 1/150 of the span length is at least the greater of (i) and (ii):
 - (i) 75% of the measured first-peak strength obtained from a flexural test and
 - (ii) 75% of the strength corresponding to $7.5\sqrt{f'_c}$

26.13—Inspection

26.13.1 General

COMMENTARY

conditions of obtaining specimens, degree of consolidation, and curing conditions. The acceptance criteria for core strengths have been established with consideration that cores for investigating low strength-test results will typically be extracted at an age later than specified for f'_c . For the purpose of satisfying 26.12.7.1(e), the Code does not intend that core strengths be adjusted for the age of the cores.

R26.12.8 Acceptance of steel fiber-reinforced concrete

R26.12.8.1 The performance criteria for the **ASTM C1609** tests are based on results from flexural tests (**Chen et al. 1995**) conducted on steel fiber-reinforced concretes with fiber types and contents similar to those used in the tests of beams that served as the basis for **9.6.3.1**.

The term “residual strength” is defined in **ASTM C1609** and is related to the ability of cracked fiber-reinforced concrete to resist tension. The strength of $7.5\sqrt{f'_c}$ is consistent with the design modulus of rupture of the concrete provided by Eq. (19.2.3.1).

R26.13—Inspection

R26.13.1 General

Inspection is necessary to verify that construction is in accordance with construction documents.

Some general building codes have incorporated inspection requirements based upon established procedures such as **PCI Plant Certification**.

CODE

26.13.1.1 Concrete construction shall be inspected as required by the general building code, and as a minimum, the inspection shall comply with the requirements provided in 26.13. In the absence of a general building code, concrete construction shall be inspected in accordance with the provisions of this Code.

26.13.1.2 Inspection of concrete construction shall be conducted by the licensed design professional responsible for the design, a person under the supervision of the licensed design professional, or a qualified inspector. The inspection shall verify conformance with construction documents throughout the various stages of construction. If an inspector conducts inspection of formwork, concrete placement, reinforcement, and embedments, the inspector shall be certified.

COMMENTARY

R26.13.1.1 By inspection, this Code does not intend that the inspector should supervise the construction. Rather, it means the inspector should visit the project as necessary to observe the various stages of construction and determine if it is being performed in general conformance with the construction documents. The frequency of inspections should follow 26.13.3 for items requiring continuous or periodic inspection.

Inspection does not relieve the contractor from the obligation to follow the construction documents and to provide the designated quality and quantity of materials and workmanship for all stages of the Work.

This Code prescribes minimum requirements for inspection of all structures within its scope. This Code is not a construction specification and any user of this Code may require higher standards of inspection than cited in the general building code or this Code if additional requirements are necessary. **ACI PRC-311.4** describes the recommended procedure for organizing and conducting concrete inspection. **ACI MNL-2** describes methods of inspecting concrete construction.

R26.13.1.2 The licensed design professional responsible for the design is in the best position to determine if construction is in conformance with the construction documents. However, if the licensed design professional responsible for the design is not retained, inspection of construction through other licensed design professionals or through separate inspection organizations with demonstrated capability for performing the inspection may be used.

Inspectors should be certified to inspect and record the results of concrete construction, including pre-placement, placement, and post-placement through the ACI Concrete Construction Special Inspector Certification Program (**ACI CPP 630.1-15**) or equivalent.

In some jurisdictions, legislation has established registration or licensing procedures for persons performing certain inspection functions. The general building code should be reviewed, or the building official should be consulted to determine if any such requirements exist within a specific jurisdiction. The building official may be contacted for clarification of the inspection requirements if not clearly identified in the general building code.

If inspection is conducted independently of the licensed design professional responsible for the design, it is recommended that the licensed design professional responsible for the design review inspection reports and observe portions of the Work to verify that the design requirements are properly executed.

Inspection reports should be distributed promptly to the owner, licensed design professional responsible for the design, contractor, appropriate subcontractors, appropriate suppliers, and the building official to allow timely identification of compliance or the need for corrective action.

Inspection responsibility and the degree of inspection required should be set forth in the contracts between

CODE

26.13.1.3 Inspection of concrete placement and reinforcement for special moment frames, boundary elements of special structural walls, coupling beams, and precast concrete diaphragms assigned to SDC C, D, E, or F using moderate or high-deformability connections, shall be performed under the supervision of the licensed design professional responsible for the design, by a person under the supervision of a licensed design professional with demonstrated capability to supervise inspection of these elements or by a certified inspector. Installation tolerances of precast concrete diaphragm connections shall be inspected for compliance with **ACI CODE-550.5**.

26.13.1.4 Inspection of reinforcement welding shall be performed by a qualified welding inspector in accordance with **AWS D1.4**. The weldability of reinforcement other than **ASTM A706** shall be confirmed by documentation in accordance with 26.6.4.

26.13.1.5 Inspection of the installation of post-installed expansion (torque-controlled and displacement-controlled), screw, and undercut anchors shall be performed by a certified inspector or a qualified inspector specifically approved for that purpose by the Licensed Design Professional and the building official.

26.13.1.6 The installation inspection of all adhesive anchors shall be performed by a certified inspector.

26.13.2 Inspection reports

26.13.2.1 Inspection reports shall document inspected items and be developed throughout each stage of the

COMMENTARY

the owner, architect, engineer, contractor, and inspector. Adequate resources should be provided to properly perform and oversee the inspection.

R26.13.1.3 Installed reinforcement for elements in special seismic systems is required to be inspected by personnel who are certified to inspect these elements. Certification of inspectors should be acceptable to the jurisdiction enforcing the general building code and as described in R26.13.1.2.

Continuous construction inspection is needed for completion of connections for precast concrete diaphragms designed in accordance with **18.12.1.1** to verify the tolerances specified in **ACI CODE-550.5** are met.

R26.13.1.5 The International Building Code (**IBC 2021**) requires inspection of all post-installed anchors. For post-installed expansion (torque-controlled and displacement-controlled), screw, and undercut anchors, monitoring of installation by a certified inspector is recommended to ensure required installation procedures are followed. Certification is established through an independent assessment such as the ACI Post-Installed Concrete Anchor Installation Inspector program (**ACI CPP 681.2-19**), or similar program with equivalent requirements.

R26.13.1.6 The installation of all adhesive anchors requires inspection by a certified inspector. Certification is established through an independent assessment such as the ACI Adhesive Anchor Installation Inspector program (**ACI CPP 681.1-17**), the ACI Post-Installed Concrete Anchor Installation Inspector program (**ACI CPP 681.2-19**), or similar program with equivalent requirements.

The installation of adhesive anchors identified in the construction documents as resisting sustained tensile loads in horizontal or upwardly inclined orientations (clockwise from 9 o'clock to 3 o'clock) poses challenges to the installer and requires particular attention to execution quality as well as an enhanced level of oversight. It is required that these anchor installations be inspected by a certified inspector who is continuously present when and where the installations are being performed.

R26.13.2 Inspection reports

R26.13.2.1 A record of inspection is required in case questions subsequently arise concerning the performance

CODE

construction. Records of the inspection shall be preserved by the party performing the inspection for at least 2 years after completion of the project.

26.13.2.2 Inspection reports shall document (a) through (f):

- (a) General progress of the Work.
- (b) Any significant construction loadings on completed floors, members, or walls.
- (c) The date and time of mixing, quantity of concrete placed, identification of mixtures used, approximate placement location in the structure, and results of tests for fresh and hardened concrete properties for all concrete mixtures used in the Work.
- (d) Concrete temperatures and protection given to concrete during placement and curing if the ambient temperature falls below 40°F or rises above 95°F.
- (e) Placement of reinforcement and tensioning of prestressing reinforcement including measurement and recording of tendon elongation and force from a calibrated gauge.
- (f) Post-tensioning tendon finishing operations, including: 1) trimming the tendon tail, 2) installation of the encapsulation cap or permanent grout cap, 3) preparation and filling of the stressing pocket, and 4) closure of grout vents.

26.13.2.3 For **ASTM A615** deformed reinforcement used in special seismic systems, verify mill test reports for compliance with the construction documents.

26.13.2.4 Test reports shall be verified to confirm weldability of reinforcement other than **ASTM A706**, if weldability is required.

26.13.2.5 For post-installed expansion (torque-controlled and displacement-controlled), screw, and undercut anchors and adhesive anchors, materials, and installation procedures shall be verified for conformance with the approved construction documents and the manufacturer's recommended procedures, which are the Manufacturer's Printed Installation Instructions (MPII) in the case of adhesive anchors. Confirm procedures and results of proof loading where required in accordance with 26.7.1(k).

26.13.3 Items requiring inspection

26.13.3.1 Unless otherwise specified in the general building code, items shall be continuously or periodically inspected in accordance with 26.13.3.2 and 26.13.3.3, respectively.

COMMENTARY

or safety of the structure or members. Photographs documenting construction progress are also desirable.

The general building code or other legal documents may require these records be preserved longer than two years after completion of the project.

R26.13.2.2

(d) The term “ambient temperature” means the temperature of the environment to which the concrete is directly exposed. Concrete temperature as used in this section may be taken as the surface temperature of the concrete. Surface temperatures may be determined by placing temperature sensors in contact with concrete surfaces or between concrete surfaces and covers used for curing, such as insulation blankets or plastic sheeting.

R26.13.2.3 If ASTM A615 reinforcement is used for special seismic applications, it is important that the inspector review the mill certificates for compliance with the applicable requirements provided in the construction documents.

R26.13.3 Items requiring inspection

R26.13.3.1 Table 1705 in Chapter 17 of the **2024 IBC** was used to determine which items require continuous or periodic inspection.

CODE**COMMENTARY**

26.13.3.2 Items requiring verification and continuous inspection shall include (a) through (e):

- (a) Prior to placement, concrete mixture for intended location.
- (b) Tensioning of prestressing reinforcement and grouting of bonded tendons.
- (c) Placement of reinforcement for special moment frames, boundary elements of special structural walls, and coupling beams.
- (d) Welding of reinforcement for special moment frames, boundary elements of special structural walls, and coupling beams.
- (e) Post-installed anchor installation, if required as a condition of the anchor assessment or if adhesive anchors are installed in horizontal or upwardly inclined orientations to resist sustained tensile loads.

26.13.3.3 Items requiring verification and periodic inspection shall include (a) through (m):

- (a) Placement of reinforcement, embedments, and post-tensioning tendons.
- (b) Welding of reinforcement except as required in 26.13.3.2(d).
- (c) Curing method and duration of curing for each member.
- (d) Construction and removal of forms and reshoring.
- (e) Consolidation of concrete placed in insulating concrete forms (ICF).
- (f) Sequence of erection and connection of precast members.
- (g) Verification of in-place strength of concrete before stressing post-tensioned tendons and before removal of shores and formwork from beams and structural slabs.
- (h) Placement of cast-in-anchors and anchor reinforcement, including tolerances required for location of anchor reinforcement.
- (i) Installation of post-installed expansion (torque-controlled and displacement-controlled) screw, and undercut anchors.
- (j) Installation of adhesive anchors, except as required in 26.13.3.2(e).
- (k) Proof loading of anchors if required in accordance with 26.13.2.5.

R26.13.3.3

(f) Some jurisdictions may require continuous inspection of sequence of erection and connection of precast members, and also may require inspection of the shoring, bracing, or other temporary measures.

(j) Inspection requirements for adhesive anchors are different from other post-installed anchors and are derived from four sources: a) the general building code, which requires periodic inspection for anchors in concrete; b) the assessment and qualification of the anchor under the provisions of **ACI CODE-355.4**, which may require either periodic inspection or continuous inspection with proof loading depending on the strength reduction factors assigned to the anchor; c) the requirements of 26.13.3.2(e), which mandate continuous inspection for anchors in a horizontal or upwardly inclined orientation to resist sustained tension loads; and d) the proof loading requirement of 26.13.2.5.

CODE

(l) Tendon finishing at post-tensioned tendon anchorages.

(m) Placement of grout for steel base plates and steel shear lugs of columns.

COMMENTARY

(l) Guidance on tendon finishing is provided in **PTI M10.2**, **PTI M10.3**, **PTI/ASBI M50.3** and **PTI M55.1**.



CHAPTER 27—STRENGTH EVALUATION OF EXISTING STRUCTURES

CODE

27.1—Scope

27.1.1 Provisions of this chapter shall apply to strength evaluation of existing structures by analytical means or by load testing.

27.2—General

27.2.1 If there is doubt that a part or all of a structure meets the safety requirements of this Code and the structure is to remain in service, a strength evaluation shall be carried out as required by the licensed design professional or building official.

27.2.2 If the effect of a strength deficiency is well understood and it is practical to measure the dimensions and determine the material properties of the members required for analysis, an analytical evaluation of strength based on this information is permitted. Required data shall be determined in accordance with 27.3.

27.2.3 If the effect of a strength deficiency is not well understood or it is not practical to measure the dimensions and determine the material properties of the members required for analysis, a load test is required in accordance with 27.4.

27.2.4 If uncertainty about the strength of part or all of a structure involves deterioration, and if the observed response during the load test satisfies the acceptance criteria in 27.5 or 27.6 for the selected load test procedure, the structure or part of the structure is permitted to remain in service for a time period specified by the licensed design professional. If

COMMENTARY

R27.1—Scope

R27.1.1 Provisions of this chapter may be used to evaluate whether a structure or a portion of a structure satisfies the safety requirements of the Code. A strength evaluation may be required if the materials are considered to be deficient in quality, if there is evidence indicating faulty construction, if a building will be used for a new function, or if, for any reason, a structure or a portion of it does not appear to satisfy the requirements of the Code. In such cases, this chapter provides guidance for investigating the safety of the structure. This chapter does not cover load testing for the approval of new design or construction methods. Acceptance of alternative materials or systems is covered in 1.10.

R27.2—General

R27.2.2 Strength considerations related to axial load, flexure, and combined axial load and flexure are well understood. There are reliable theories relating strength and short-term displacement to load in terms of member dimensional and material data. To determine the strength of the structure by analysis, calculations should be based on data gathered on the actual dimensions of the structure, properties of the materials in place, and all pertinent details. Additional guidance on evaluation of existing structures is provided in **ACI PRC-437** and Chapter 6 of **ACI CODE-562-25**.

R27.2.3 If a load test is to be conducted as part of the strength evaluation process, it is desirable for all parties to agree on the region to be loaded, the magnitude of the load, the load test procedure, and acceptance criteria before any load tests are conducted. If the safety concerns are related to an assemblage of members or an entire structure, it is not feasible to load test every member and section. In such cases, it is appropriate that an investigation plan be developed to address the specific safety concerns.

If the shear or bond strength of a member is critical in relation to the doubt expressed about safety, a test may be the most efficient solution to eliminate or confirm the doubt. A test may also be appropriate if it is not feasible to determine the material and dimensional properties required for analysis, even if the cause of the concern relates to flexure or axial load. Wherever possible and appropriate, the results of the load test should be supported by analysis.

R27.2.4 For a deteriorating structure, acceptance provided by the load test is, by necessity, limited in terms of future service life. In such cases, a periodic inspection program is useful. A program that involves physical tests and periodic inspection can justify a longer period in service. Another option for maintaining the structure in service, while the

CODE

deemed necessary by the licensed design professional, periodic reevaluations shall be conducted.

27.2.5 If the structure under investigation does not satisfy conditions or criteria of 27.3, 27.5, or 27.6, the structure shall be permitted for use at a lower load rating, based on the results of the load test or analysis, and if approved by the building official.

27.3—Analytical strength evaluation

27.3.1 *Verification of as-built condition*

27.3.1.1 As-built dimensions of members shall be field-verified at critical sections.

27.3.1.2 Locations and sizes of reinforcement shall be determined by measurement. It shall be permitted to base reinforcement locations on available drawings if field-verified at representative locations to confirm the information on the drawings.

27.3.1.3 If required, an estimated equivalent f'_c shall be based on analysis of results of cylinder tests from the original construction, tests of cores removed from the structure, or both sets of data. Original cylinder data and core test data shall be representative of the area of concern.

27.3.1.4 The method for obtaining and testing cores shall be in accordance with [ASTM C42](#).

COMMENTARY

periodic inspection program continues, is to limit the live load to a level determined to be appropriate in accordance with 27.2.5. The length of the specified time period between inspections should be based on consideration of: a) the nature of the deterioration; b) environmental and load effects; c) service history of the structure; and d) scope of the periodic inspection program. At the end of a specified time period, further strength evaluation is required if the structure is to remain in service. With the agreement of all concerned parties, procedures may be devised for periodic testing that do not necessarily conform to the loading and acceptance criteria specified within this chapter.

R27.2.5 Except for load tested members that have failed under a test (refer to 27.4.5), the building official may permit the use of a structure or member at a lower load rating that is judged to be safe and appropriate on the basis of the strength evaluation.

R27.3—Analytical strength evaluation

R27.3.1 *Verification of as-built condition*

R27.3.1.1 As-built dimensions at critical locations requiring field verification are those dimensions necessary to quantify the performance at those sections. Critical sections for different load effects, such as moment, shear force, and axial force, are locations where stresses caused by such effects reach their maximum value and as further defined for various member types in the Code. Additionally, critical sections may be defined by specific conditions in the structure being evaluated, such as localized member deterioration.

R27.3.1.2 If investigating individual members, the amount, size, arrangement, and location of reinforcement designed to resist applied load should be determined at the critical sections. Nondestructive investigation methods are generally acceptable. In structures with many critical sections, the frequency of measurements may be reduced if the field measurements are consistent.

R27.3.1.3 Guidance on estimating equivalent f'_c from original cylinder data can be found in [Bartlett \(2012\)](#).

ACI Committee 214 has developed two methods for determining an equivalent f'_c from cores taken from an existing structure. These methods are described in [ACI PRC-214.4](#) and rely on statistical analysis techniques. The procedures should not be used to investigate low cylinder strength test results in new construction, which is considered in [26.12.4](#). The number of core tests may depend on the size of the structure and the sensitivity of structural safety to concrete strength.

CODE

27.3.1.5 The properties of reinforcement are permitted to be based on tensile tests of representative samples of the material in the structure.

27.3.2 Strength reduction factors

27.3.2.1 If dimensions, size, and location of reinforcement, and material properties are determined in accordance with 27.3.1, it is permitted to increase ϕ from the design values elsewhere in this Code; however, ϕ shall not exceed the limits in Table 27.3.2.1.

Table 27.3.2.1—Maximum permissible strength reduction factors

Strength	Classification	Transverse reinforcement	Maximum permissible ϕ
Flexure, axial, or both	Tension controlled	All cases	1.0
	Compression controlled	Spirals ^[1]	0.9
		Other	0.8
Shear, torsion, or both			0.8
Bearing			0.8

^[1]Spirals shall satisfy 10.7.6.3, 20.2.2, and 25.7.3.

27.4—Strength evaluation by load test

27.4.1 Load tests shall be conducted either monotonically in accordance with 27.5 or cyclically in accordance with 27.6.

27.4.2 Load tests shall be conducted in a manner that provides for safety of life and the structure during the test.

27.4.3 Safety measures shall not interfere with the load test or affect the results.

27.4.4 The portion of the structure subject to the test load shall be at least 56 days old. If the owner of the structure, the contractor, the licensed design professional, and all other involved parties agree, it shall be permitted to perform the load test at an earlier age.

27.4.5 A precast member to be made composite with cast-in-place concrete shall be permitted to be tested in flexure as a precast member alone in accordance with (a) and (b):

(a) Test loads shall be applied only when calculations indicate the isolated precast member will not fail by compression or buckling.

COMMENTARY

R27.3.1.5 The number of tests required depends on the uniformity of the material within the structure and should be determined by the licensed design professional responsible for the evaluation.

R27.3.2 Strength reduction factors

R27.3.2.1 The strength reduction factors are larger than those defined in **Chapter 21**. These increased values are justified by the use of field-obtained material properties and actual in-place dimensions.

R27.4—Strength evaluation by load test

R27.4.1 The monotonic load test procedure is recommended if the strength of the structure being evaluated may be limited by the concrete strength or the expected structural failure is controlled by shear or reinforcement development. The sustained load applied during the monotonic test allows greater time for widening and propagation of cracks, creep, and slip of reinforcement, as compared with the cyclic procedure.

R27.4.4 Other involved parties may include building officials, concrete subcontractors, and persons with a future interest in the structure.

CODE

(b) The test load, when applied to the precast member alone, shall induce the same total force in the tensile reinforcement as would be produced by loading the composite concrete member with the test load in accordance with 27.4.6.

27.4.6 Test load arrangement and load factors

27.4.6.1 Test load arrangements shall be selected to maximize the load effects in the critical regions of the members being evaluated.

27.4.6.2 The total test load T_t , including dead load already in place, shall be at least the greatest of (a), (b), and (c):

$$(a) T_t = 1.0D_w + 1.1D_s + 1.6L + 0.5(L_r \text{ or } S \text{ or } R) \quad (27.4.6.2a)$$

$$(b) T_t = 1.0D_w + 1.1D_s + 1.0L + 1.6(L_r \text{ or } S \text{ or } R) \quad (27.4.6.2b)$$

$$(c) T_t = 1.0D_w + 1.1D_s + 1.0L + 1.6(L_r \text{ or } S \text{ or } R) \quad (27.4.6.2c)$$

27.4.6.3 It is permitted to reduce L in 27.4.6.2 in accordance with the general building code.

27.4.6.4 The load factor on the live load L in 27.4.6.2(b) shall be permitted to be reduced to 0.5 except for parking structures, areas occupied as places of public assembly, or areas where L is greater than 100 lb/ft².

27.4.6.5 Unless documentation or tests are available to confirm the density of normalweight concrete used in the structure, the density shall be taken as 150 lb/ft³. For other types of concrete materials, the density shall be determined based upon test results or from other documentation.

27.5—Monotonic load test procedure**27.5.1 Test load application**

27.5.1.1 Total test load T_t shall be applied in at least four approximately equal increments.

COMMENTARY**R27.4.6 Test load arrangement and load factors**

R27.4.6.1 It is important to apply the load at locations so the effects on the suspected deficiency are a maximum and sharing of the applied load with unloaded members is minimized. In cases where it is shown by analysis that adjoining unloaded members will help resist some of the load, the test load should be adjusted to produce appropriate load effects in the critical region of the members being evaluated.

R27.4.6.2 Test loads were changed in **ACI CODE-318-19** to be consistent with the requirements in **ACI CODE-437.2** for tests on a portion of a structure and for statically indeterminate structures. The test load separates the dead load into self-weight dead load and the superimposed dead load on the structure during the load test. **ACI PRC-437.1** provides additional discussion of test loads for concrete structures.

R27.4.6.3 The live load L may be reduced as permitted by the general building code governing safety considerations for the structure. The test load should be increased to compensate for resistance provided by unloaded portions of the structure in question. The increase in test load is determined from analysis of the loading conditions in relation to the selected pass/fail criterion for the test.

R27.4.6.5 Documentation to support a different unit weight may include test results showing concrete unit weight during placement or measured unit weight of concrete core samples. For other types of concrete materials (such as lightweight concrete), the unit weight should be determined based upon concrete core test results or other documentation. The calculation of D_w may include determination of the weight of bonded concrete materials, such as a topping slab to be placed on precast members, not present during a load test. D_s may also include the weight from structural framing members.

R27.5—Monotonic load test procedure**R27.5.1 Test load application**

R27.5.1.1 Inspecting the area of the structure subject to test loading for signs of distress after each load increment is advisable (refer to R27.5.3.1).

CODE

27.5.1.2 Uniform T_i shall be applied in a manner that ensures uniform distribution of the load transmitted to the structure or portion of the structure being tested. Arching action in the test load apparatus shall be avoided.

27.5.1.3 After the final load increment is applied, T_i shall remain on the structure for at least 24 hours unless signs of distress, as noted in 27.5.3, are observed.

27.5.1.4 After all response measurements are recorded, the test load shall be removed as soon as practical.

27.5.2 Response measurements

27.5.2.1 Response measurements, such as deflection, strain, slip, and crack width, shall be made at locations where maximum response is expected. Additional measurements shall be made if required.

27.5.2.2 The initial value for all applicable response measurements shall be obtained not more than 1 hour before applying the first load increment.

27.5.2.3 A set of response measurements shall be recorded after each load increment is applied and after T_i has been applied on the structure for at least 24 hours.

27.5.2.4 A set of final response measurements shall be made 24 hours after T_i is removed.

27.5.3 Acceptance criteria

27.5.3.1 The portion of the structure tested shall show no spalling or crushing of concrete, or other evidence of failure.

COMMENTARY

R27.5.1.2 Arching refers to the tendency for the load to be transmitted nonuniformly to the flexural member being tested. For example, if a slab is loaded by a uniform arrangement of bricks, arching of bricks in contact would result in reduction of the load on the slab near the midspan of the slab.

R27.5.3 Acceptance criteria

R27.5.3.1 Evidence of failure includes distress (cracking, spalling, or deflection) of such magnitude and extent that the observed result is obviously excessive and incompatible with the safety requirements of the structure. No simple rules have been developed for application to all types of structures and conditions. If sufficient damage has occurred so that the structure is considered to have failed that test, retesting is not permitted because it is considered that damaged members should not be put into service even at a lower load rating.

Local spalling or flaking of the compressed concrete in flexural members related to casting imperfections need not indicate overall structural distress. Crack widths are good indicators of the state of the structure and should be observed to help determine whether the structural strength and behavior are satisfactory. However, accurate prediction or measurement of crack widths in structural concrete members is not likely to be achieved under field conditions. It is advisable to establish criteria before the test relative to the types of cracks anticipated; where the cracks will be measured; how they will be measured; and approximate limits or criteria to evaluate new cracks or limits for the changes in crack width.

CODE

27.5.3.2 Members tested shall not exhibit cracks indicating imminent shear failure.

27.5.3.3 In regions of members without transverse reinforcement, structural cracks inclined to the longitudinal axis and having a horizontal projection greater than the depth of the member shall be evaluated. For variable-depth members, the depth shall be measured at the midlength of the crack.

27.5.3.4 In regions of anchorage and lap splices of reinforcement, short inclined cracks or horizontal cracks along the line of reinforcement shall be evaluated.

27.5.3.5 Measured deflections shall satisfy:

$$\Delta_r \leq \frac{\Delta_1}{4} \quad (27.5.3.5)$$

27.5.3.6 If the maximum deflection measured during the test, Δ_1 , does not exceed the larger of 0.05 in. or $\ell_t/2000$, the residual deflection requirements in 27.5.3.5 shall be permitted to be waived.

27.5.3.7 If 27.5.3.5 or 27.5.3.6 is not satisfied, it shall be permitted to repeat the load test, provided that the second load test begins no earlier than 72 hours after removal of externally applied loads from the first load test.

27.5.3.8 Portions of the structure tested in the second load test shall be considered acceptable if:

$$\Delta_r \leq \frac{\Delta_2}{5} \quad (27.5.3.8)$$

27.6—Cyclic load test procedure

27.6.1 A cyclic load test in accordance with **ACI CODE-437.2** shall be permitted to be used to evaluate the strength of an existing structure.

COMMENTARY

R27.5.3.2 Forces are transmitted across a shear crack plane by aggregate interlock at the interface of the crack that is enhanced by clamping action of transverse reinforcement and by dowel action of stirrups crossing the crack. The member is assumed to be approaching imminent shear failure when crack lengths increase to approach a horizontal projected length equal to the depth of the member and concurrently widen to the extent that aggregate interlock cannot occur, and as transverse stirrups, if present, begin to yield or display loss of anchorage so as to threaten their integrity.

R27.5.3.3 Inclined cracks may lead to brittle failure of members without transverse reinforcement. Assessment of all inclined cracks is advisable where transverse reinforcement is not present.

R27.5.3.4 Cracking along the axis of the reinforcement in anchorage zones may be related to high stresses associated with the transfer of forces between the reinforcement and the concrete. These cracks may be indicators of impending brittle failure of the member if they are associated with the development of main reinforcement. It is important that their causes and consequences be evaluated.

R27.5.3.5 If the structure shows no evidence of failure, recovery of deflection after removal of the test load is used to determine whether the strength of the structure is satisfactory.

R27.5.3.6 In the case of a very stiff structure, errors in measurements under field conditions may be of the same order as the actual deflections and recovery. To avoid penalizing a satisfactory structure in such a case, recovery measurements are waived if the maximum deflection does not exceed the larger of 0.05 in. or $\ell_t/2000$.

R27.6—Cyclic load test procedure

R27.6.1 Cyclic load testing involves the cyclic application and removal of load to a structure or structural element. The cyclic load test protocol described in **ACI CODE-437.2** involves the application of increasing levels of load to a structure in repeated load cycles. The measured load-deformation response of the structure is used to evaluate the

CODE

27.6.2 Acceptance criteria for cyclic load test results shall be in accordance with **ACI CODE-437.2**.

27.6.3 If a member fails a cyclic load test, it shall be permitted to retest the member or structure in accordance with ACI CODE-437.2. It shall be permitted to waive the maximum deflection limit ($\ell_f/180$) in ACI CODE-437.2 that precludes a retest.

COMMENTARY

performance of the tested element. The acceptance criteria for the cyclic test are based upon deviation of the load deformation response from linear elastic behavior, permanency of deflections during each cycle of the load test, and recovery of deflection after completion of the load test.

R27.6.3 ACI CODE-437.2 precludes a retest if the member exceeds a maximum deflection limit of $\ell_f/180$ (Section 6.4.4.2 in ACI CODE-437.2-13). For consistency with the monotonic testing protocol, this limit is waived.



Notes



APPENDIX A—DESIGN VERIFICATION USING NONLINEAR RESPONSE HISTORY ANALYSIS

CODE

COMMENTARY

A.1—Notation and terminology

A.1.1 Notation

- B = bias factor to adjust nominal strength to seismic target reliabilities
- D_u = ultimate deformation capacity; the largest deformation at which the hysteresis model is deemed valid given available laboratory data or other substantiating evidence
- $\sqrt{f'_{ce}}$ = square root of expected compressive strength of concrete, psi
- f'_{ce} = expected compressive strength of concrete, psi
- f_{ue} = expected tensile strength for nonprestressed reinforcement, psi
- f_{ye} = expected yield strength for nonprestressed reinforcement, psi
- ℓ_p = plastic-hinge length for analysis purposes, in.
- R_{ne} = expected yield strength
- V_{ne} = expected shear strength, lb
- θ_y = yield rotation, radians
- ϕ = seismic resistance factor for force-controlled actions

A.1.2 Terminology

distributed plasticity (fiber) model—component model consisting of discrete fibers explicitly representing nonlinear stress-strain or force-deformation responses.

structural wall panel zone—portion of a structural wall common to intersecting wall segments where forces from adjacent wall segments are resolved.

The following actions shall be as defined by [ASCE/SEI 7 Chapter 16](#):

- action, deformation-controlled**
- action, force-controlled**
- action, force-controlled critical**
- action, force-controlled ordinary**
- action, force-controlled noncritical**

A.2—Scope

A.2.1 This appendix shall supplement the requirements of Chapter 16 of [ASCE/SEI 7](#) when performing nonlinear response history analysis to determine the design of earthquake-resistant concrete structures.

A.2.2 The provisions of Appendix A shall be in addition to the provisions of [Chapters 1 through 26](#).

A.2.3 This appendix shall be used in conjunction with Chapter 16 of [ASCE/SEI 7](#) for additional general requirements, ground motions, load combinations, modeling, and analysis for design of new reinforced concrete structures, including:

- (a) Structural systems designated as part of the seismic force-resisting system, including diaphragms, moment-resisting frames, structural walls, and foundations.

RA.1—Notation and terminology

RA.1.2 Terminology

Force-controlled and deformation-controlled actions are classified in [A.7](#) for design using nonlinear analysis of concrete structures.

RA.2—Scope

RA.2.3 This appendix is intended to complement documents such as Chapter 16 of [ASCE/SEI 7](#), [TBI \(2017\)](#), and [LATBSDC \(2023\)](#). This appendix provides requirements specific to nonlinear response history analysis and design of concrete members. For additional analysis and modeling requirements that are not specific to concrete members, refer to Chapter 16 of [ASCE/SEI 7](#), [TBI \(2017\)](#), and [LATBSDC \(2023\)](#).

CODE

(b) Members not designated as part of the seismic force-resisting system but required to support other loads while sustaining deformations and forces associated with earthquake effects.

A.2.4 All concrete structures designed or verified by this Appendix shall be proportioned and detailed as required by **Chapter 18** and the requirements of A.12 when applicable.

A.2.5 It shall be permitted to use the provisions of Appendix A to demonstrate the adequacy of a structural system as required by **18.2.1.7**.

A.2.6 Independent structural design review consistent with A.13 shall be required for use of Appendix A.

A.2.7 The licensed design professional shall provide justification for any interpretation required for the application of Appendix A, and if accepted by the independent structural design reviewers, justification shall be provided to the building official for acceptance.

A.3—General

A.3.1 Action Classification and Criticality in A.7, and Acceptance Criteria in A.10 and A.11 provide a comprehensive design approach following the intent of Chapter 16 of ASCE/SEI 7 and the general building code, and shall take precedence over those of Chapter 16 of ASCE/SEI 7.

A.4—Earthquake ground motions

A.4.1 Nonlinear response history analysis shall include the effects of horizontal earthquake ground motions.

A.4.2 Vertical earthquake ground motion shall be considered simultaneously with horizontal earthquake ground motions where inclusion of vertical ground motion will substantially affect the structural design requirements.

A.4.3 Earthquake ground motion acceleration histories shall be selected and modified in accordance with procedures established by the general building code.

COMMENTARY

RA.2.7 It is anticipated that the initial design of an earthquake-resistant structure will be performed using elastic analysis combined with engineering judgment. A nonlinear response history analysis following the requirements of this Appendix can then be performed to demonstrate the design, which may not fully comply with all provisions of **ASCE/SEI 7** or the general building code.

R.3—General

RA.3.1 Due to inconsistencies between ACI CODE-318 and Chapter 16 of ASCE/SEI 7 in the approach to Action Classification and Acceptance Criteria for concrete members, the requirements in this Appendix take precedence over those of ASCE/SEI 7.

RA.4—Earthquake ground motions

RA.4.1 Nonlinear response history analysis commonly is performed using two horizontal components of earthquake ground motion applied to a three-dimensional model of the building.

RA.4.2 Structures with vertical discontinuities in the gravity-load-resisting systems can experience vertical earthquake response that can affect building performance. Examples include columns or walls that terminate on beams or slabs. Some structures with long spans or long cantilevers can be sensitive to vertical ground motion. Engineering judgment should be exercised when considering the sensitivity of structures to vertical ground motions.

RA.4.3 The analysis procedures in Appendix A are based on ground motion selection and scaling consistent with Chapter 16 of ASCE/SEI 7, which includes scaling to a risk-targeted maximum considered earthquake ground acceleration. ASCE/SEI 7 describes appropriate procedures for selection and modification of earthquake ground motions in terms of acceptable hazard and risk levels.

CODE

A.5—Load factors and combinations

A.5.1 Load combinations for nonlinear response history analysis shall conform to the requirements of the general building code.

A.6—Modeling and analysis

A.6.1 Models for analysis shall be three-dimensional and shall conform to the requirements of the general building code.

A.6.2 Modeling of member nonlinear behavior, including effective stiffness, expected strength, expected deformation capacity, and hysteresis under force or deformation reversals, shall be substantiated by applicable physical test data and shall not be extrapolated beyond the limits of testing.

A.6.3 Degradation in member strength or stiffness shall be included in the numerical models unless it can be demonstrated that the demand is not sufficiently large to produce these effects. If degradation in component strength is included in the numerical model, the model formulation shall be such that structural deformation at onset of strength loss is not affected by mesh configuration in the finite element model.

COMMENTARY

RA.5—Load factors and combinations

RA.5.1 Load combinations for response history analysis used in conjunction with this Appendix are intended to be similar to those of Chapter 16 of *ASCE/SEI 7*, *TBI (2017)*, and *LATBSDC (2023)*.

For nonlinear response history analysis, the principles of linear superposition do not apply. Therefore, it would be incorrect to conduct separate analyses considering various loads and then combine the load effects. Instead, it is necessary to conduct an analysis for each factored load combination and take the design value as the envelope of the analysis results. For any nonlinear analysis including earthquake effects, gravity loads are to be applied to the model first and then the ground shaking simulations are applied in the presence of the gravity loads.

There is a low probability that maximum considered earthquake shaking and factored design gravity load combinations of the general building code will occur simultaneously. A more representative load combination is the occurrence of expected, realistic gravity loading combined with maximum considered earthquake shaking.

One load combination is typically considered for analysis, which includes expected dead load concurrent with expected live load and Maximum Considered Earthquake shaking. Chapter 16 of *ASCE/SEI 7* requires consideration of a second load combination without live load. It should be noted that this case will seldom govern the design of a tall building.

Accidental torsion is not commonly considered in cases where linear analysis indicates that torsional irregularities are negligible.

Load combinations used in the nonlinear analysis may differ from load combinations used to evaluate force-controlled actions (refer to A.11).

RA.6—Modeling and analysis

RA.6.2 Multiple element formulations and material models are appropriate for use in inelastic dynamic analysis of concrete structures. *ASCE/SEI 41*, *ACI PRC-374.3*, *ACI CODE-369.1*, and *NIST GCR 17-917-46* provide guidance on modeling and defining model parameters. Selecting model parameters at the mean value of experimental data, as is recommended by the aforementioned documents, avoids skewing analysis results and produces a more reliable evaluation of concrete building response.

RA.6.3 The model mesh size selected should allow determination of the structural responses in sufficient detail and with sufficient accuracy. Some systems will exhibit mesh-dependent response, with a reduction in mesh size resulting in reduced deformation capacity and more rapid strength loss. For these systems, material softening should be defined using a measure of mesh size, or the chosen material model

CODE

A.6.4 For structural walls with aspect ratio $h_w/\ell_w \geq 2$, the numerical model of the wall and its connection to surrounding elements shall represent kinematic effects associated with wall rotation and uplift, including the effect of migration of the neutral axis as a function of applied axial force and lateral deformation, unless it can be demonstrated that such effects do not affect the structural design requirements.

A.7—Action classification and criticality

A.7.1 All actions shall be classified as deformation-controlled or force-controlled in accordance with A.7.2 and A.7.3.

A.7.2 Deformation-controlled actions

A.7.2.1 Deformation-controlled actions shall satisfy the requirements of A.10.

A.7.2.2 The following shall be designated as deformation-controlled actions:

- (a) Moment in beams, coupling beams, and slab-column connections
- (b) Shear in diagonally reinforced coupling beams that meet the requirements of 18.10.7.4
- (c) Moment in columns when combined with axial force for columns meeting the requirements of 18.7.4, 18.7.5, and 18.7.6
- (d) Moment in walls when combined with axial force for walls controlled by tensile yielding of longitudinal reinforcement
- (e) Axial tensile force
- (f) Other actions accepted by the independent structural design reviewer(s) based on substantiating test data or analysis

A.7.3 Force-controlled actions

A.7.3.1 Force-controlled actions shall satisfy the requirements of A.11.

A.7.3.2 The following shall be designated as ordinary force-controlled actions:

- (a) Shear and moment in perimeter basement walls
- (b) In-plane shear in non-transfer diaphragms
- (c) In-plane normal forces in diaphragms other than collectors
- (d) Moment in shallow foundation members, including spread footings and mat foundations
- (e) Moment in deep foundation members

COMMENTARY

parameters and mesh size should be shown, using an appropriate experimental data set, to provide accurate simulation of onset of strength loss.

RA.7—Action classification and criticality

RA.7.2 Deformation-controlled actions

RA.7.2.2 Similar to the requirements of 18.14.3.3, if columns are detailed with sufficient confinement and reinforcement detailing, column moment can be evaluated as a deformation-controlled action rather than as a force-controlled action.

RA.7.3 Force-controlled actions

RA.7.3.2 For diaphragm shear to be considered an ordinary force-controlled action, the shear should not be related to a transfer of force between lateral-force-resisting system components.

CODE

A.7.3.3 Noncritical force-controlled actions shall be designated as actions in any component where failure will not result in: (a) collapse of the structure; (b) loss of the earthquake resistance of the structure; and (c) falling hazard.

A.7.3.4 All actions not designated as deformation controlled, ordinary force-controlled, or noncritical force-controlled shall be classified as critical-force controlled.

A.8—Effective stiffness

A.8.1 Member stiffness shall include effects of deformations due to flexure, shear, axial elongation or shortening, and reinforcement slip along its development length.

A.8.2 If cracking is anticipated as a result of combined effects of applied forces, displacements, and volume change effects associated with shrinkage, temperature, or creep, effects of concrete cracking on effective member stiffness shall be modeled.

A.8.3 If yielding of reinforcement or nonlinear response of concrete is anticipated as a result of combined effects of applied forces, displacements, and volume change effects associated with shrinkage, temperature, or creep, the structural model shall be capable of representing member stiffness for loading near the onset of inelastic response, as well as behavior past the onset of inelastic response.

COMMENTARY

RA.8—Effective stiffness

RA.8.1 Software for nonlinear analysis generally is capable of directly modeling deformations due to flexure, shear, and axial elongation or shortening. Additional deformation may occur due to slip of longitudinal reinforcement from adjacent anchorages. Such effects commonly occur where beams frame into beam-column joints or walls, where columns frame into beam-column joints or foundations, and where walls frame into foundations. If such effects are considered important to the performance of the structure, appropriate assumptions should be included in the analytical model, either directly or by adjustment of flexural stiffness.

RA.8.2 Effects of cracking on stiffness reduction can be considered directly by using models that represent stiffness reduction as calculated stress reaches the cracking stress or indirectly by reducing the effective stiffness relative to the gross-section stiffness. Where the latter approach is used, the degree of stiffness reduction should be consistent with the degree of cracking anticipated under earthquake loading. Structural walls that are lightly cracked, including basement walls, have traditionally been modeled using effective flexural stiffness in the range 0.5 to 1.0 times gross-section stiffness. Diaphragms at major force transfer levels are commonly modeled using effective axial stiffness in the range 0.10 to 0.5 times gross-section stiffness. **TBI (2017)** and **LATBSDC (2023)** provide additional effective stiffness recommendations while NIST GCR 17-917-46v1 (**NIST 2017a**) and NIST GCR 17-917-46v3 (**NIST 2017b**) provide more detailed guidance on modeling of diaphragms and frame elements.

For stiffness of beams, columns, and structural walls other than basement walls, refer to RA.8.3.

RA.8.3 If calculations indicate nonlinear response under load combinations including earthquake effects, the nonlinear model should be capable of representing an effective secant stiffness from zero loading to a point corresponding to yield-level forces (slope from A to B in Fig. RA.8.3). The model should also be capable of representing stiffness reduction past the yield point. Degradation in element strength or stiffness should be included in the analytical model unless it can be demonstrated that the demand is not sufficiently large as to produce these effects.

CODE

COMMENTARY

A.8.4 It shall be permitted to represent member stiffness near the onset of inelastic response using an effective stiffness based on analysis substantiated by physical test data. Alternatively, it shall be permitted to represent member stiffness near the onset of inelastic response using the effective stiffness values in Table A.8.4.




Fig. RA.8.3—Generalized force-deformation relations.

RA.8.4 The effective stiffness values are intended to represent the slope from A to B in Fig. RA.8.3, where B corresponds to expected yield strength. Effective stiffness values for beams and columns are based on [Elwood et al. \(2007\)](#), and incorporate the effects of reinforcement slip along the development length. Tabulated values for structural walls are appropriate to use where the wall is represented by a line element. In some building models, structural walls will be represented by distributed fiber models, in which case the fiber model should directly represent effects of concrete cracking and reinforcement yielding, such that the stiffness values in Table A.8.4 do not apply. Basement walls are unlikely to respond at yield-level forces; therefore, larger stiffness values may be more applicable than those in Table A.8.4 for walls. Diaphragm stiffnesses provided in Table A.8.4 represent typical values. Prestressed and nonprestressed diaphragms mainly resisting single-floor in-plane earthquake forces are commonly modeled as rigid, as allowed by [ASCE/SEI 7](#). Diaphragms transferring relatively large in-plane earthquake forces from multiple floor levels can have effective stiffnesses somewhat lower than those represented in Table A.8.4. In cases where analysis results are sensitive to diaphragm stiffness assumptions, it may be prudent to “bound” the solution by analyzing the structure using a range of diaphragm stiffnesses and selecting the design values as the larger forces from the two analyses. Coupling beam effective stiffnesses are intended to represent values for beams cast monolithically with floor slabs. Values are based on equations presented by [Vu et al. \(2014\)](#), but are adjusted to account for the presence of a slab, differences in modeling approach, and typical shear levels ([TBI 2017](#)). Engineering judgment should be used to evaluate effective shear stiffness values, noting that due to typical software implementation limitations, gross area is used in lieu of effective area.

CODE

COMMENTARY

Table A.8.4—Effective stiffness values^[1]

Component		Axial	Flexural	Shear
Beams	nonprestressed	$1.0E_cA_g$	$0.3E_cI_g$	$0.4E_cA_{shear}$
	prestressed	$1.0E_cA_g$	$1.0E_cI_g$	$0.4E_cA_{shear}$
Columns with compression caused by design gravity loads ^[2]	$\geq 0.5A_gf'_c$	$1.0E_cA_g$	$0.7E_cI_g$	$0.4E_cA_{shear}$
	$\leq 0.1A_gf'_c$ with tension	$1.0E_cA_g$ (compression) $1.0E_sA_{st}$ (tension)	$0.3E_cI_g$	$0.4E_cA_{shear}$
Structural walls ^[3]	in-plane	$1.0E_cA_g$	$0.35E_cI_g$	$0.2E_cA_{shear}$
	out-of-plane	$1.0E_cA_g$	$0.25E_cI_g$	$0.4E_cA_{shear}$
Diaphragms (in-plane only) ^[4]	nonprestressed	$0.25E_cA_g$	$0.25E_cI_g$	$0.25E_cA_{shear}$
	prestressed	$0.5E_cA_g$	$0.5E_cI_g$	$0.4E_cA_{shear}$
Coupling beams	with or without diagonal reinforcement	$1.0E_cA_g$	$0.07\left(\frac{t_s}{h}\right)E_cI_g \leq 0.3E_cI_g$	$0.4E_cA_{shear}$
Mat foundations	in-plane	$0.5E_cA_g$	$0.5E_cI_g$	$0.4E_cA_{shear}$
	out-of-plane ^[5]		$0.5E_cI_g$	

^[1]Tabulated values for axial, flexural, and shear shall be applied jointly in defining effective stiffness of an element, unless alternative combinations are justified.

^[2]For columns with axial compression falling between the limits provided, flexural stiffness shall be determined by linear interpolation.

^[3]Tabulated values are appropriate where members are modeled using line elements to represent their properties.

^[4]Diaphragms shall be permitted to be modeled as rigid in-plane if this does not result in differences in analysis outcomes.

^[5]Specified stiffness values for mat foundations pertain for the general condition of the mat. Where the wall or other vertical members imposed sufficiently large forces, including local force reversals across stacked wall openings, the stiffness values may need to be reduced.

A.8.5 In beam-column joints if joint flexibility is not modeled explicitly, it shall be permitted to model joint flexibility implicitly by defining the effective stiffness of beams and columns framing into the joint to include joint flexibility and by introducing beam and column rigid end offsets that extend to the center of the joint.

RA.8.5 In reinforced concrete frames detailed to resist earthquake forces, joints are not expected to experience significant degradation. In lieu of a more rigorous representation of joint shear stiffness, rigid offsets of beam and column members extending the length of the joint dimensions are permitted (Birely et al. 2012). A sensitivity study on stiffness assumptions indicates that overall building stiffness may be more sensitive to the choice of effective stiffness for frame and wall members than for joints (Kwon and Ghanoum 2016). The rigid joint offset approach is compatible with the effective stiffness values presented in Table A.8.4, which account for the softening effects of longitudinal bar slip within the joints.

A.8.6 If beams other than coupling beams are cast monolithically with slabs, the effective slab width defined in 6.3.2 shall be included in the evaluation of beam flexural and axial stiffnesses.

A.9—Expected material strength

A.9.1 Expected material strength shall be defined based on applicable project-specific data or data from projects using similar materials and construction. If applicable data are not available, the expected material strengths in Table A.9.1 shall be permitted.

RA.9—Expected material strength

RA.9.1 The multiplier on f'_c may be smaller for high-strength concrete when higher quality control measures are in place or when fly ash or other additives are used. Refer to ACI PRC-232.2 for discussion of impacts of fly ash. Default values for other steel grades have not been provided in Table A.9.1 due to insufficient data.

CODE

COMMENTARY

Table A.9.1—Expected material strengths

Material		Expected strength	
Concrete		$f_{ce}' = 1.3f_c^{(1)}$	
Reinforcing steel		Expected yield strength, f_{ys} , psi	Expected tensile strength, f_{ue} , psi
A615	Grade 60	70,000	106,000
A706	Grade 60	69,000	95,000
	Grade 80	85,000	112,000

⁽¹⁾Expected strength f_{ce}' is strength expected at approximately 1 year or longer.

A.10—Acceptance criteria for deformation-controlled actions

A.10.1 Deformations in any of the response history analyses shall not exceed the ultimate deformation capacity D_u unless (a) or (b) is satisfied.

- (a) The analysis assumes the strength associated with this mode of deformation is negligible for the remainder of that analysis, and the structure is evaluated for stability and strength.
- (b) The analysis is considered to have an unacceptable response as defined by [ASCE/SEI 7](#).

A.10.2 D_u shall be determined by (a), (b), or (c):

- (a) D_u of the component shall be taken as the valid range of modeling as demonstrated by comparison of the hysteresis model with suitable laboratory test data including the appropriate gravity load effect.
- (b) If special structural walls are modeled using distributed plasticity (fiber) models, D_u shall be evaluated using the average vertical strain. The strain shall be evaluated over a height of the plastic hinge length, ℓ_p , where ℓ_p is the longer of (i) and (ii):
 - (i) $\ell_p = 0.2\ell_w + 0.03h_w$ (A.10.2.a)
 - (ii) $\ell_p = 0.08h_w + 0.00015f_y d_b$ (A.10.2.b)
 but not exceeding the story height, where d_b and f_y are determined based on the wall longitudinal reinforcement.
- (c) If structural components are modeled using lumped plasticity (concentrated hinge) or distributed plasticity (fiber) models, D_u shall be permitted to be in accordance with [ACI CODE-369.1](#) or as substantiated by laboratory testing.

RA.10—Acceptance criteria for deformation-controlled actions

RA.10.1 These acceptance criteria are consistent with the component acceptance criteria in [TBI \(2017\)](#), which are different from those in [ASCE/SEI 7](#) and [LATBSDC \(2023\)](#). More detailed discussion regarding the differences of evaluation approaches of deformation-controlled actions in [ASCE/SEI 7](#) and [TBI \(2017\)](#) are provided in [TBI \(2017\)](#).

RA.10.2 Ultimate deformation capacity D_u is typically obtained from statistical analysis of the available test data and can be closely related to Collapse Prevention Acceptance Criteria in [ACI CODE-369.1](#) and [ASCE/SEI 41](#). D_u is based on the deformation where substantial loss of gravity load-carrying capacity occurs or, if tests do not progress to this deformation, the limiting deformation for which testing was performed. An example of D_u in the hysteresis curve of an analysis model is shown in Fig. RA.10.2. The Collapse Prevention Acceptance Criteria in [ACI CODE-369.1](#) and [ASCE/SEI 41](#) are typically less than mean experimental values due to scatter in data sets used to develop these criteria. The [ASCE/SEI 41](#) approach also evaluates deformation as the mean of the maximum absolute response from each response history analysis. Appendix A, however, evaluates deformation as the maximum of any of the response history analyses.

Hysteresis behavior of the structural component simulated using fiber material models should be evaluated and adjusted using experimental data for the range of deformation demands and behaviors simulated in the analyses. [ACI PRC-374.3](#) and [ACI CODE-369.1](#) provide nonlinear modeling parameters that can be the basis for hysteresis shape based on experimental data. Figure RA.10.2 shows a hysteresis curve generated using adjusted fiber material models based on such nonlinear modeling parameters to simulate the component behavior observed in laboratory tests.

If D_u is defined by average strain, the length over which strain is defined in the analysis should be consistent with the length over which strain limits are established from experi-

CODE

COMMENTARY

mental data or are specified in documents such as **ASCE/SEI 41**, **ACI CODE-369.1**, **TBI**, or **LATBSDC**.

Sufficient number of fibers along the cross section should be used to allow the strain values at fiber centerlines to be extrapolated to locations where strain values are calculated to compare with strain limits, such as, at the extreme edge of the wall compression zone.

For structural walls or coupling beams modeled using fiber elements, deformation acceptance criteria can be represented in either a strain or member deformation basis. The strain results can be obtained directly from the fiber model. The member deformation results, such as plastic hinge rotation, story drift, or chord rotation, can be obtained by aggregated deformation over a group of fiber elements representing the member. Plastic hinge length Eq. (A.10.2a) and (A.10.2b) for walls are from **Paulay and Priestley (1992)**.

An example of acceptance criteria for strain limits is provided in **TBI (2017)**. The unconfined concrete model includes a peak stress at a compressive strain of 0.002, with a descending backbone to 50% of the peak stress value at a compressive strain of 0.003 (the ultimate deformation capacity D_u). The confined concrete model, used where confinement meeting the requirements of 18.10.6.4(e) and (f) are provided, includes a peak stress at a compressive strain 0.008, with a descending backbone to 80% of the peak stress value at a compressive strain of 0.015 (the ultimate deformation capacity D_u). The longitudinal reinforcement tensile strain limit of 0.05 (the ultimate deformation capacity D_u) is based on tensile rupture with consideration of low-cycle fatigue effects, which is corroborated by **Segura and Wallace (2018)**.

Additional references for ultimate deformation capacity, such as **ACI CODE-369.1**, **TBI (2017)**, and **LATBSDC (2023)**, may be used subject to approval of the independent structural design review.




Fig. RA.10.2— D_u in response hysteresis from an analysis model.

A.11—Expected strength for force-controlled actions

A.11.1 Force-controlled actions shall be evaluated in accordance with the general building code, with expected strength taken as $\phi_s BR_n$.

RA.11—Expected strength for force-controlled actions

RA.11.1 Currently, strength reduction factors ϕ are not specifically calibrated to the seismic reliability targets specified in **ASCE/SEI 7**. Rather, these strength reduction factors are calibrated to the target reliabilities for other loads

CODE

COMMENTARY

A.11.2 ϕ_s shall be in accordance with Table A.11.2, with ϕ determined in accordance with **Chapter 21**, except that 21.2.4.1 shall not apply.

Table A.11.2—Seismic resistance factor

Force-controlled action	ϕ_s
Critical	ϕ
Ordinary	$\phi/0.9 \leq 1.0$
Noncritical	$\phi/0.85 \leq 1.0$

A.11.3 A.11.3 Bias factor, B , shall be taken as 1.0. Alternatively, it shall be permitted to calculate B using Eq. (A.11.3):

$$B = 0.9R_{ne}/R_n \geq 1.0 \quad (\text{A.11.3})$$

A.11.3.1 Nominal strength, R_n , shall be in accordance with **Chapter 18**, **22**, or **23**.

A.11.3.2 The expected strength, R_{ne} , is permitted to be defined in accordance with the nominal strength provisions of Chapters 18, 22, or 23, with f_{ce}' substituted for f_c' and f_{ye} substituted for f_y or f_{yt} , except as provided in A.11.3.2.1 and A.11.3.2.2.

A.11.3.2.1 For structural walls where $h_w/\ell_w \geq 2$ meeting (a) through (d), the requirements of A.11.3.2.1.1 and A.11.3.2.1.2 shall apply.

- (a) Wall is modeled with fiber elements in accordance with A.10.2(b)
- (b) Strains calculated as the mean of the maximum demand from a suite of response history analyses
- (c) Calculated concrete compressive strain < 0.005
- (d) Calculated longitudinal tensile strain < 0.01

A.11.3.2.1.1 $V_{ne} = 1.5A_{cv}(2\lambda\sqrt{f_{ce}'} + \rho_t f_{ye})$

A.11.3.2.1.2 For all vertical wall segments sharing a common lateral force, V_{ne} shall not be taken greater than $12A_{cv}$. For any individual vertical wall segments, V_{ne} shall not be taken greater than $15A_{cv}\sqrt{f_c'}$.

A.11.3.2.2 For structural wall panel zones, V_{ne} shall be calculated in accordance with A.11.3.2.1.1. V_{ne} shall not be taken greater than $25A_{cv}\sqrt{f_c'}$.

(ASCE/SEI 7-22 Table 1.3-1). The bias factor B is provided to adjust the resistance factors specified by the materials standards to the seismic target reliabilities, considering the inherent bias in the nominal strength equations contained in the materials standards. This bias is a function of both the ratio of expected material strength to minimum specified strength and also inherent conservatism in the predictive equations specified by the materials standards.

RA.11.2 For ordinary and noncritical actions, the resistance factors are relaxed in order to accept a higher probability of failure.

More detailed discussion regarding the differences of evaluation approaches of force-controlled actions in ASCE/SEI 7, TBI (2017), and LATBSDC (2023) are provided in TBI (2017) and LATBSDC (2023). Additional background on this approach is provided in Wallace et al. (2013) and Kim and Wallace (2017).

RA.11.3.2.1 The shear strength determined from these provisions is applicable only to walls with relatively low flexural ductility demands (Wallace et al. 2013; LATBSDC 2023).

CODE

A.12—Enhanced detailing requirements

A.12.1 If the mean maximum deformation from the set of response history analyses exceeds $0.5D_u$ of confined concrete, members shall be subject to the added detailing requirements of this section.

A.12.2 *Special moment frames*

A.12.2.1 For beams of special moment frames, the spacing of transversely supported flexural reinforcing bars as required by 18.6.4.2 shall not exceed 8 in.

A.12.2.2 The sum of the column strengths at any joint as required by 18.7.3.2 shall be at least 1.4 times the sum of the beam strengths at the joint.

A.12.2.3 For tied columns of special moment frames, every longitudinal bar shall have lateral support by a corner of a hoop or a seismic hook as required in 18.7.5.2(f) regardless of axial load or concrete strength.

A.12.2.4 When deformations of beams of special moment frames exceed $0.5D_u$, the column dimension parallel to the beam longitudinal reinforcement required in 18.8.2.3 shall be increased by 20 percent.

A.12.3 *Special structural walls*

A.12.3.1 Boundary elements shall be provided in accordance with 18.10.6 with transverse reinforcement conforming with A.12.2.3.

A.12.3.2 If boundary elements are required, splices of shear reinforcement shall be made with mechanical or welded splices, or lap splices enclosed in transverse reinforcement spaced at the smaller of $6d_b$ of the spliced bars or 6 in.

A.12.3.3 If the floor or roof slab is shown by analysis to undergo inelastic response at a slab-wall connection, the slab

COMMENTARY

RA.12—Enhanced detailing requirements

RA.12.1 The requirements for earthquake-resisting systems and detailing have been developed over many years using actual earthquake damage observations, research, and engineering judgment. These requirements are codified in ASCE/SEI 7, IBC, and ACI CODE-318. In recent years, enhanced computational abilities allow engineers to model and calculate seismic response in great detail.

Designs that exceed the prescriptive limits of the general building code are sometimes prepared, verified, and justified. In some instances, these new designs have not been tested in strong ground shaking, and there is some concern that these designs may be extrapolating beyond the collective knowledge. Therefore, these enhanced details are provided to improve inelastic response ductility and are appropriate when using Appendix A for designs beyond prescriptive code limits.

RA.12.2 *Special moment frames*

RA.12.2.3 This code has allowed crossties in compression members with a seismic hook at only one end and with crossties alternated recognizing their ease in construction. However, recent earthquakes and research tests have shown that 90-degree hooks do not always provide adequate support (Moehle and Cavanagh 1985).

RA.12.3 *Special structural walls*

CODE

flexural reinforcement shall be extended through the slab-wall joint and anchored for structural integrity.

A.12.3.4 If shear force exceeds $4A_{cv}\lambda\sqrt{f'_c}$, enhanced construction joint detailing shall be provided with thorough roughening of concrete, intermittent shear keys in the concrete, or both, to reduce the possibility of slip along the construction joint.

A.13—Independent structural design review

A.13.1 The analysis and design shall be reviewed by an independent structural design reviewer. The independent structural design reviewer shall act under the direction of the building official.

A.13.2 The independent structural design review shall be performed by one or more individuals acceptable to the building official and possessing knowledge of (a) through (d):

- (a) Selection and scaling of ground motions for use in nonlinear response history analysis.
- (b) Behavior of structural systems of the type under consideration when subjected to earthquake loading.
- (c) Analytical structural modeling for use in nonlinear response history analysis, including use of physical tests in the creation and calibration of the structural analysis models, and knowledge of soil-structure interaction if used in the analysis or in the development of ground motions.
- (d) The requirements of Appendix A as they pertain to design of the type of structure under consideration.

A.13.3 The scope of the independent structural design review shall be approved by the building official and shall include a minimum of (a) through (h):

- (a) Basis of design document, including the earthquake-performance objectives, the overall earthquake-resistant design methodology, and acceptance criteria
- (b) Proposed structural system

COMMENTARY

RA.12.3.3 Analysis of tall buildings with structural core wall systems have shown inelastic response in slabs at their connection to core walls. Integrity of this connection is critical to the overall performance of the structure. Enhanced details, which include properly anchored or continuous reinforcement and post-tensioning tendons, providing additional integrity are required.

RA.12.3.4 Sliding at horizontal construction joints of walls has been observed in earthquakes and in laboratory testing of structural walls. Enhanced detailing is required in regions of high shear to minimize slip or sliding at construction joints.

RA.13—Independent structural design review

RA.13.1 The independent structural design reviewer provides an independent, objective, technical review of those aspects of the structural design of the building that relate to earthquake-performance and advises the building official whether the design meets the acceptance criteria and the expected building performance.

Review by the independent structural design reviewer is not intended to replace quality assurance measures ordinarily exercised by the licensed design professional. Responsibility for the structural design remains solely with the licensed design professional in responsible charge of the structural design.

RA.13.2 On many projects, independent structural design review may be provided by a review team approved by the building official. Each member of the review team may possess specialized knowledge and expertise, and jointly meet the requirements of A.13.2.

An independent structural design reviewer should not have conflicts of interest with respect to the project and should not be part of the design team for the project.

RA.13.3 The scope of the independent structural design review should be clearly defined and acceptable to the building official.

CODE

- (c) Earthquake hazard determination, and selection and modification of earthquake ground motions
- (d) Modeling approaches for components
- (e) Structural analysis model, including soil-structure interaction as applicable, and verification that the structural analysis model adequately represents the properties of the structural system
- (f) Review of structural analysis results and determination of whether calculated response meets approved acceptance criteria
- (g) Design and detailing of structural components
- (h) Drawings, specifications, and quality control/quality assurance and inspection provisions in the design documents

A.13.4 The independent structural design review shall be documented as follows:

- (a) The independent structural design reviewer shall issue comments and questions to the licensed design professional.
- (b) The licensed design professional shall provide written responses to the independent structural design reviewer.
- (c) The independent structural design reviewer shall summarize the review in a letter addressed to the building official that shall include a log of all questions or comments and responses. Any items that lack resolution or consensus shall be clearly explained with reasons for lack of agreement.

COMMENTARY

RA.13.4 A statement of agreement with the design should be provided. However, there may be occasions where complete agreement between the independent structural design reviewer and the licensed design professional cannot be reached. These items should be documented in the summary review letter.

Notes



APPENDIX B—PERFORMANCE-BASED WIND DESIGN (*NEW APPENDIX*)

CODE

COMMENTARY

B.1—Notation and Terminology

B.1.1 Notation

E_{ce} = expected modulus of elasticity of concrete, psi

f_{ce}' = expected compressive strength of concrete, psi

f_{ye} = expected yield strength for nonprestressed reinforcement, psi

f_{ue} = expected tensile strength for nonprestressed reinforcement, psi

h_{sx} = story height for story x

M_{ne} = flexural strength at section, determined using expected material strengths, in.-lb

P_{ne} = axial compressive strength of member, determined using expected material strengths, lb

P_{nte} = axial tensile strength of member, determined using expected material strengths, lb

R_n = nominal strength

$R_{ne,w}$ = expected strength of reinforced concrete member using f_{ce}' and f_{ye}

W_{MRI} = wind effect with specified mean recurrence interval (MRI)

Δ_L = deformation limit (strain, rotation, displacement)

$\delta_{x,w}$ = maximum story drift ratio expected in story x , according to analyses for wind demands. Drift ratio is calculated as relative difference of lateral displacement between the top and bottom of a story, divided by the story height.

ϵ_{ye} = expected yield strain of reinforcement

θ_{ye} = expected yield rotation of member determined using expected material strengths, radians

B.1.2 Terminology

action, deformation-controlled—action allowed to exceed the expected yield deformation of the element being evaluated.

action, force-controlled—action not allowed to exceed the design strength of the element being evaluated.

basis of design—formal document prepared by the licensed design professional expressing the performance objectives, acceptance criteria, analysis methods, and design methods to be used in the overall building design.

equivalent static wind load (ESWL)—wind load statically applied to the building, representing the wind-tunnel determined combination of the background and resonant wind components.

expected strength, wind—strength of a member or cross section calculated in accordance with provisions and

RB.1—Notation and Terminology

RB.1.1 Notation

E_{ce} = Expected modulus of elasticity of concrete is calculated using expected compressive strength of concrete

W_{MRI} = Wind effect with specified mean recurrence interval (MRI) depends on the risk category of the building and is provided in ASCE/SEI Prestandard for Performance-Based Wind Design.

RB.1.2 Terminology

action, deformation-controlled—Deformation-controlled actions are those under which elements exhibit acceptable degree of inelastic response and are deemed to have failed upon exceedance of a predefined deformation level or number of cycles.

action, force-controlled—Force-controlled actions are those under which elements exhibit limited ductility and are deemed to have failed upon exceedance of design strength.

CODE

assumptions of this Code using expected material strengths provided in B.9.

performance-based wind design (PBWD)—alternative design procedure to the prescriptive provisions in the general building code and referenced standards, which considers direct evaluation of the wind demand on the structure and evaluates the building performance as it relates to occupant comfort, operational performance, and continuous occupancy, limited interruption performance objectives.

performance objective—specific desired outcome for an action, element, or system of a building during or following a wind event as chosen by the project stakeholders and licensed design professionals.

performance objective, continuous occupancy, limited interruption—specific desired outcome in which damage to the main wind-force-resisting system does not significantly disrupt or impair the continued operation and functionality of the structure.

performance objective, occupant comfort—specific desired outcome in which the accelerations from wind-induced sway motions remain within acceptable limits for occupant comfort and for equipment to maintain the functionality of the building.

performance objective, operational—specific desired outcome in which the main wind-force-resisting system remains essentially elastic and the building systems remain operational during the designated risk category-based event.

B.2—Scope

B.2.1 This appendix shall be in addition to the requirements of **ASCE/SEI 7** and the general building code for performance-based wind design or evaluation of the main wind-force-resisting system of reinforced concrete structures.

B.2.2 The provisions of Appendix B shall be in addition to the provisions of **Chapters 1** through **26**, excluding **Chapter 18** and **Appendix A**, unless specifically referenced.

B.3—General

B.3.1 Operational performance evaluation shall be permitted using (a), (b), or (c).

COMMENTARY

performance objective, continuous occupancy, limited interruption—Continued operation and functionality of the structure is implicitly achieved when the main wind-force-resisting system is designed for a wind event corresponding to the designated building risk category to achieve the target reliability for structural stability that is consistent with the building code.

performance objective, occupant comfort—Although the occupant comfort performance objective is part of performance-based wind design, it is outside of the scope of Appendix B.

performance objective, operational—Members in reinforced concrete structures are considered cracked when concrete tensile stresses exceed the stress corresponding to the tensile strength. Even though the force-deformation relationship becomes nonlinear immediately after cracking, when performing the lateral analysis for the operational performance objective, it is assumed that the structure is essentially elastic, and its behavior is adequately represented using the secant stiffness for peak response for the risk category-based event.

RB.2—Scope

RB.2.1 Performance-based wind design is permitted by **ASCE/SEI 7**. This appendix is intended to supplement the **ASCE/SEI** Prestandard for Performance-Based Wind Design (2023). This appendix provides requirements specific to linear static, linear response history, and nonlinear response history analyses and design of reinforced concrete structures subjected to wind loading.

RB.2.2 Chapter 18 and Appendix A are not invoked using performance-based wind design unless specifically referenced. However, Chapter 18 is potentially applicable for seismic design depending on the Seismic Design Category and the seismic force-resisting system.

RB.3—General

RB.3.1 Acceptance criteria for the operational performance objective are provided in the **ASCE/SEI** Prestandard for Performance-Based Wind Design. Linear analyses

CODE

- (a) Linear static analysis
- (b) Linear response history analysis
- (c) Nonlinear response history analysis

B.3.2 Continuous occupancy, limited interruption performance evaluation shall use linear static analysis to evaluate minimum strength requirements followed by (a), (b), or (c):

- (a) Method 1: Linear or nonlinear response history analysis meeting the requirements of B.11.
- (b) Method 2: Nonlinear response history analysis with a reliability-based conditional probability assessment meeting the requirements of B.12.
- (c) Method 3: Probabilistic nonlinear response history analysis with a fully coupled reliability assessment meeting the requirements of B.12.

COMMENTARY

are typically used for models developed for the operational performance objective. Nonlinear analysis may be used for the operational performance objective.

B.3.2 Table RB.3.2 summarizes the applicability of the provisions of Appendix B as they are typically applied when using different methods to satisfy the continuous occupancy, limited interruption performance objective. Step 1 using linear static analysis is needed for all three methods. Method 1 may be conducted in two or three steps.

Table RB.3.2—Analysis procedure for evaluating Continuous Occupancy, Limited Interruption performance objective

Method	Step	Analysis type	Lateral loads	Sections of Appendix B to be satisfied	Notes
1	1	Linear static	Equivalent static lateral loads from building code ^[1]	B.11.2 Force-controlled actions and deformation-controlled actions	Minimum strength requirement for Method 1.
	2	Linear static or Linear response history	Equivalent static lateral loads from building code ^[1] or wind load histories in critical wind directions	B.11.3.1 Force-controlled actions B.11.3.2 Deformation-controlled actions	If acceptance criteria in B.11.3.1 are met and demands in members for deformation-controlled actions are less than $R_{ne,w}$, Step 3 is not needed. If acceptance criteria in B.11.3.1 or B.11.3.2 are not met, nonlinear analysis (Step 3) can be performed or the structure can be redesigned. Alternatively, it is permitted to implement Step 3 directly without performing Step 2.
	3	Nonlinear response history	Wind load histories in critical wind directions	B.11.4.1 Force-controlled actions B.11.4.2 Deformation-controlled actions	
2	1	Linear static	Equivalent static lateral loads from building code ^[1]	B.12.2 Force-controlled actions and deformation-controlled actions	Minimum strength requirement for Methods 2 and 3.
	2	Nonlinear response history	Wind load histories in critical wind directions	B.12.3 Target reliability of components and connections	Refer to ASCE/SEI Prestandard for Performance-Based Wind Design.
3	1	Linear static	Equivalent static lateral loads from building code ^[1]	B.12.2 Force-controlled actions and deformation-controlled actions	Minimum strength requirement for Methods 2 and 3.
	2	Probabilistic nonlinear response history	Wind load histories in all wind directions	B.12.3 Target reliability of lateral load resisting system	Refer to ASCE/SEI Prestandard for Performance-Based Wind Design.

^[1]Wind tunnel equivalent static loads can be used instead of loads from the directional procedure of the building code if the wind tunnel loads are scaled such that the base overturning moment is not less than 80% of that using the general building code loads (or not less than 80% of the base shear if the first mode period is less than 1 second)

CODE

B.3.3 Action Classifications in B.7 and Required Strength and Acceptance Criteria in B.10 through B.12 for the continuous occupancy, limited interruption performance objective shall take precedence over those of the ASCE/SEI Prestandard for Performance-Based Wind Design.

B.3.4 Independent structural design review consistent with B.14 shall be required when Appendix B provisions are used.

B.3.5 The licensed design professional shall provide justification for any interpretation required for the application of Appendix B and, if accepted by the independent structural design reviewer, justification shall be provided to the building official for acceptance.

B.4—Wind loading

B.4.1 Wind hazard analysis, wind tunnel testing, and wind tunnel data analysis shall satisfy the requirements of the general building code and the requirements of B.4.2 through B.4.4.

B.4.2 Probabilistic wind climate analysis shall be used to determine wind speeds, directionality, and duration of wind loading.

B.4.3 Appropriate wind tunnel test methodologies shall be used in the determination of load and response effects of interest.

B.4.4 The duration of wind load histories from wind tunnel testing shall be of sufficient length to enable the peak wind event duration to be modeled reliably, permit evaluation of nonlinear response within the Performance-Based Wind Design (PBWD) framework, and permit development of a loading protocol for testing deformation-controlled elements.

COMMENTARY

RB.3.3 Action Classifications in B.7 and Acceptance Criteria in B.10 through B.12 provide a comprehensive design approach following the intent of **ASCE/SEI 7** and the general building code. Because of inconsistencies between ACI 318 and the ASCE/SEI Prestandard for Performance-Based Wind Design in the approach to Action Classifications and Acceptance Criteria for reinforced concrete members, the requirements in this Appendix take precedence over those of the ASCE/SEI Prestandard for Performance-Based Wind Design. For example, a moment frame column under axial load is considered a force-controlled element in the ASCE/SEI Prestandard for Performance-Based Wind Design. However, according to ACI CODE-318, a concrete column with axial load and moment may be force-controlled or deformation-controlled based on the level of axial load.

RB.4—Wind loading

RB.4.1 Design of concrete structures for wind requires characterization of the wind loading and responses.

RB.4.2 Chapter 6 of ASCE/SEI 49-21 (Wind Tunnel Testing for Buildings and Other Structures) and Chapter 26 of ASCE/SEI 7-22 (Minimum Design Loads and Associated Criteria for Buildings and Other Structures) provide guidance on wind hazard analysis. Code-specified basic wind speeds for a range of mean recurrence intervals (MRIs) can be obtained for any location in the United States using the ASCE/SEI 7 Hazard Tool.

RB.4.3 Appropriate methodologies are discussed in Chapter 2 of ASCE/SEI 49-21 (Wind Tunnel Testing for Buildings and Other Structures) and Chapter 31 of ASCE/SEI 7-22 (Minimum Design Loads and Associated Criteria for Buildings and Other Structures).

RB.4.4 The ASCE/SEI Prestandard for Performance-Based Wind Design, Chapters 3 through 5 of ASCE/SEI 49-21 (Wind Tunnel Testing for Buildings and Other Structures), and Chapter 31 of ASCE/SEI 7-22 (Minimum Design Loads and Associated Criteria for Buildings and Other Structures) provide guidance on wind tunnel data analysis. The peak responses and cumulative damage to components of the structure depend on wind demand amplitude, duration, and history. Traditional design of buildings and structures

CODE

COMMENTARY

B.5—Load factors and combinations

B.5.1 For evaluating the continuous occupancy, limited interruption performance objective, required strength U shall be at least equal to the effects of factored loads in Table B.5.1.

Table B.5.1—Load combinations

Method of evaluation	Load combination	Equation
Method 1	$U = 1.0D + 1.0L + (0.5L_r \text{ or } 0.3S \text{ or } 0.5R) + 1.0W_{MRI}$	(B.5.1a)
	$U = 0.9D + 1.0W_{MRI}$	(B.5.1b)
Methods 2 and 3	$U = 1.0D + 1.0L + 1.0W_{MRI}$	(B.5.1c)

B.5.1.1 In combination Eq. (B.5.1a), S shall be taken as either the flat roof snow load or the sloped roof snow load as specified in ASCE/SEI 7.

B.5.1.2 The load factor on live load L in Eq. (B.5.1a) and (B.5.1c) shall be permitted to equal 0.5 except for (a), (b), or (c):

- (a) Areas occupied as garages
- (b) Areas occupied as places of public assembly
- (c) Areas where L is greater than 100 lb/ft²

B.5.1.3 Load combination B.5.1b need not be considered if (a) and (b) are satisfied:

- (a) Sum of the expected in-service live load L over the entire structure does not exceed 25% of the total dead load D
- (b) Live load intensity over at least 75% of the structure is less than 100 lb/ft²

for wind assumes an equivalent static wind load approach. Effective static wind loads are developed for the target Mean Recurrence Interval (MRI) based on statistics of the wind tunnel measurements and the wind climate analysis.

For Performance-Based Wind Design (PBWD) of structures, it is prudent to record wind load histories of sufficient duration, and at sufficiently small time steps, to permit the structure-wind dynamic response of interest to be adequately represented.

The duration of strong wind events may be extracted from the statistics of the wind data, storm simulation, or both. For hurricane-prone regions, statistical investigations of event durations can be found in [Kopp et al. \(2021\)](#) and [Wang and Wu \(2022\)](#).

RB.5—Load factors and combinations

RB.5.1 Load combinations for response history analysis used in conjunction with this appendix are intended to follow the ASCE/SEI Prestandard for Performance-Based Wind Design (PBWD). For nonlinear response history analysis, the principles of linear superposition do not apply. Therefore, it would be incorrect to conduct separate analyses considering various loads and then combine the load effects. Instead, as stated in the ASCE/SEI Prestandard for Performance-Based Wind Design, it is necessary to conduct an analysis for each factored load combination and take the design value as the demand from the governing load combinations of the analysis results. For any nonlinear analysis including wind load effects, gravity loads are to be applied to the model first, and then the wind load histories are applied in the presence of the gravity loads.

RB.5.1.3 The exception in B.5.1.3 is based on ASCE/SEI Prestandard for Performance-Based Wind Design.

CODE**B.6—Modeling and analysis**

B.6.1 Analytical models shall be three-dimensional.

B.6.2 Models for linear static and linear response history analyses shall meet the requirements of B.6.2.1. Models for nonlinear response history analyses shall meet the requirements of B.6.2.2.

B.6.2.1 Requirements for linear analysis models

B.6.2.1.1 Models for linear analyses shall consider the expected effective stiffness values of members at the force level appropriate for different performance objectives and shall consider second-order effects.

COMMENTARY**RB.6—Modeling and analysis**

RB.6.1 Three-dimensional models represent proper structural behavior under the spatial distribution of wind loads. Effects of bidirectional wind loading and torsion cannot be adequately represented with two-dimensional models. Certain elements of reinforced concrete structures can be designated as part of the main wind-force-resisting system. These elements should be included in the three-dimensional model. Other elements that may be essential to the gravity-load-resisting system may be designated as not part of the main wind-load-resisting system and may be excluded from the analysis model if the second-order effects due to gravity loads on such elements are accounted for in the analysis. Refer to B.6.3 for elements that are not part of the main wind-load-resisting system and should be included in the analysis model. Performance of elements that are not modeled should be evaluated for forces, deformations, or both due to compatibility with the lateral-load-resisting elements.

RB.6.2 Analysis procedures depend on the performance objective. The ASCE/SEI Prestandard for Performance-Based Wind Design outlines the requirements for analysis procedures permitted for each performance objective.

Linear static analysis of a structural system uses linear elastic properties and includes second-order effects and spatial distribution of mass and loads. Linear elastic properties for each component should reflect effective stiffness values at the expected load level. Equivalent static wind loads that include effects of dynamic response are applied. Linear analyses are typically used for models developed for the operational performance objective and minimum strength checks for Methods 1, 2, and 3 as described in Table RB.3.2.

Linear response history analysis of a structural system is based on linear elastic properties and includes second-order effects and spatial distribution of mass and loads. Linear elastic properties should reflect the effective stiffness at the expected load level. Along-wind, crosswind, and torsional wind load histories determined from wind tunnel testing are applied to the model, and dynamic response is computed step-by-step in the time domain or by use of frequency domain procedures.

Nonlinear response history analysis is similar to linear response history analysis except that the structural system explicitly accounts for changes in element and connection stiffness and strength due to cyclic nonlinear response. Along-wind, crosswind, and torsional wind loads are applied simultaneously through the application of wind load histories, and dynamic response is computed step-by-step in the time domain.

RB.6.2.1 Requirements for linear analysis models

RB.6.2.1.1 Second-order analysis should consider the influence of axial loads, presence of cracked regions along the length of the member, and effects of load duration.

CODE

B.6.2.1.2 Effective stiffness in accordance with B.8 shall be permitted for linear static and linear dynamic analysis.

B.6.2.2 *Requirements for nonlinear analysis models*

B.6.2.2.1 Models for nonlinear analysis shall consider the effects of stiffness decay, which shall be substantiated by applicable physical test data and shall not be extrapolated beyond the limits of testing.

B.6.2.2.2 Nonlinear force-deformation curves used to estimate load-deformation relationships for elements in the analytical model shall be developed based on test results.

B.6.2.2.3 Substantiating laboratory test data for force-deformation relationships shall include deformation or load reversals with a number of inelastic cycles greater than or equal to that expected at wind demands corresponding to the continuous occupancy, limited interruption performance objective.

B.6.2.2.4 Wind loads applied to the model shall represent the effects of spatial distribution of loads vertically and horizontally throughout the building. The wind loads shall represent the spectral content established through wind tunnel testing.

B.6.2.2.5 It shall be permitted to use effective stiffness values in accordance with B.8 in nonlinear response history analysis for elements that remain elastic.

B.6.3 Analytical models for evaluation of the continuous occupancy, limited interruption performance objective shall include gravity-load-resisting elements unless it is demonstrated that their design is not affected by their interaction with the main wind-force-resisting system.

COMMENTARY

RB.6.2.2 *Requirements for nonlinear analysis models*

RB.6.2.2.2 Multiple element formulations and material models are appropriate for use in nonlinear dynamic analysis of concrete structures. [ASCE/SEI 41](#), [ACI PRC-374.3](#), [ACI CODE-369.1](#), and [NIST GCR 17-917-46](#) provide guidance on modeling for seismic design and may be applicable to wind design. Force-deformation curves provided in these documents for seismic design, however, may not necessarily be appropriate for wind design. Mean values of modeling parameters from experimental data should be used as is recommended in [ASCE/SEI 41](#), [ACI PRC-374.3](#), [ACI CODE-369.1](#), and [NIST GCR 17-917-46](#) because this approach produces more reliable results.

RB.6.2.2.3 Duration of loading is important to consider any ratcheting of drifts in a particular direction and to account for the effect of fatigue on the behavior of the component.

RB.6.2.2.4 Effects of distribution of wind loads may be simulated with concentrated lateral loads applied to rigid floor diaphragms with additional moments to account for torsion. In consultation with the wind testing consultant, wind loads may be applied in multi-story loading blocks provided the resulting main wind-force-resisting system shear and flexure effects are maintained.

RB.6.3 It is difficult to accurately determine forces on certain elements due to compatibility of displacements unless they are modeled with the main wind-force-resisting system. Elements listed below are examples of gravity-load-resisting elements that should be modeled regardless of whether they are designated to resist lateral wind load:

- (a) Columns in proximity to structural walls
- (b) Columns supporting or supported by transfer beams
- (c) Sloping columns
- (d) Transfer beams

CODE

B.7—Action classification and requirements

B.7.1 Actions shall be classified as deformation-controlled or force-controlled in accordance with B.7.2 and B.7.3, respectively, and shall satisfy the requirements of B.10 through B.12.

B.7.2 *Deformation-controlled actions*

B.7.2.1 The following actions shall be permitted to be designated as deformation-controlled:

- (a) Moment in slabs, beams, and coupling beams
- (b) Shear in diagonally reinforced coupling beams that meet the requirements of 18.10.7.4
- (c) Moment combined with axial force in tension-controlled columns
- (d) Moment in walls when combined with axial force for walls controlled by tensile yielding of longitudinal reinforcement.
- (e) Axial tensile force
- (f) Other actions accepted by the independent structural design reviewer based on substantiating test data or analysis

B.7.3 *Force-controlled actions*

B.7.3.1 Actions not designated as deformation-controlled shall be classified as force-controlled.

B.8—Effective stiffness

B.8.1 Methods that include the effects of deformations due to flexure, shear, axial elongation or shortening, and slip of reinforcement along embedment length shall be permitted to determine the stiffness of an element subjected to the level of wind force considered. Alternatively, effective stiffness values substantiated by physical test data shall be permitted.

B.8.2 Effective member stiffness values shall be determined based on the level of cracking anticipated as a result of the combined effects of applied forces, displacements,

COMMENTARY

Performance of elements that are not modeled should be evaluated for forces, deformations, or both due to compatibility with the lateral-load-resisting elements.

RB.7—Action classification and requirements

RB.7.2 *Deformation-controlled actions*

RB.7.2.1 Refer to B.11.3.3 for determination of columns that may be classified as deformation-controlled. Yielding is permitted in members with deformation-controlled actions provided there is capability to resist gravity load. Therefore, axial force and moment in columns that are classified as tension controlled are permitted to be considered as deformation-controlled actions whereas axial force and moment in compression-controlled or transition columns are considered as force-controlled actions. Axial force and flexure in deep foundations may be considered as a deformation-controlled action depending on the strain demand in the reinforcing steel following the requirements of B.7.2.1(e). Similarly, flexure in shallow foundation members, including spread footings and mat foundations, may be considered a deformation-controlled action.

RB.8—Effective stiffness

RB.8.1 It is important to recognize that the effective stiffness of a reinforced concrete member depends on the demand level, and wind gust effects increase as the structural stiffness decreases. Software for analysis is capable of directly calculating deformations due to flexure, shear, and axial forces, including the effects of cracking. Additional reduction in stiffness may occur due to slip of longitudinal reinforcement embedment. The effective stiffness should consider the combination of these effects. If such effects are deemed important to the performance of the structure, appropriate assumptions should be included in the analytical model, either directly or by adjustment of stiffness. Effective stiffness values are often used in linear analysis by adjusting the elastic stiffness of the gross concrete section to account for such additional deformations. Table A.8.4 provides effective stiffness values for components near the onset of yielding. Higher values may be appropriate for components subjected to lower demand levels.

RB.8.2 Effects of cracking on stiffness reduction can be considered directly by using models that represent stiffness reduction as calculated stress reaches the cracking stress or indirectly by using the effective stiffness as a fraction of

CODE

and volume change associated with shrinkage, temperature, and creep.

B.8.3 If yielding of reinforcement or nonlinear response is anticipated as a result of the combined effects of applied forces, displacements, and volume changes associated with shrinkage, temperature, and creep, the structural model shall be capable of representing member stiffness for loading near the onset of inelastic response and for post-yield behavior.

B.8.4 It shall be permitted to represent effective member stiffness based on the secant stiffness to yield level based on analysis of physical test data.

COMMENTARY

the gross section stiffness. If the latter approach is used, the degree of stiffness reduction should be consistent with the degree of cracking anticipated considering the level of wind loading. The effective member stiffness is also affected by the large number of loading cycles associated with wind loading.

RB.8.3 After cracking, reinforced concrete members exhibit a reduction in stiffness as reflected in the change in slope at point B in the idealized force-deformation relationship shown in Fig. RB.8.3. Stiffness reduction past the yield point (point C in Fig. RB.8.3) should be included in the behavioral model (Abdullah et al. 2020, 2021). The deformation limit Δ_L is determined in accordance with B.11.4.2, which will typically exceed the deformation associated with $R_{ne,w}$.




Fig. RB.8.3—Idealized force-deformation relationship.

RB.8.4 These provisions permit rational methods for evaluation of stiffness, which will depend on the nature of the building, location, demand levels, exposure, and geometry. These stiffness assumptions will be reviewed and accepted by the independent structural design reviewer as required by B.14. The values of effective stiffness for the continuous occupancy, limited interruption performance objective should consider demands corresponding to member yielding capacities. The effective stiffness of prestressed beams and slabs is expected to be greater than that of conventionally reinforced beams and slabs. Columns supporting outriggers can be subjected to tensile forces under wind loads, and the effective axial stiffness of columns under tension should be reduced based on the level of axial strain (ACI PRC-224.2). Industry standard is to use 1 and 10-year MRI winds for the occupant comfort performance objective. The ASCE/SEI Prestandard for Performance-Based Wind Design considers 10-year to 50-year MRI winds for the operational performance objective based on the risk category of the building. Similarly, 700-year to 3000-year MRI wind, based on the risk category of a building, are used for the continuous occupancy, limited interruption performance objective. Accordingly, it would be appropriate to use different effective stiffness values for evaluating the occupant comfort performance objective, the operational performance objective, and

CODE

B.9—Expected material strength

B.9.1 Expected material strength shall be defined based on applicable project-specific data or data from projects using similar materials and construction.

B.9.2 If applicable data are not available, expected material strengths provided in Table B.9.2 shall be permitted to be used.

Table B.9.2—Expected material strengths

Concrete $f_{ce}' = 1.3f_c'^{(1)}$						
Reinforcing steel						
Steel type	Grade 60		Grade 80		Grade 100	
	A615	A706	A615	A706	A615	A1035
f_{ye}	71,000	69,000	89,000	87,000	107,000	128,000
f_{ue}	105,000	95,000	120,000	115,000	138,000	163,000

⁽¹⁾Expected strength f_{ce}' is the strength assumed to occur approximately 1 year or later.

B.10—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective—general

B.10.1 The continuous occupancy, limited interruption performance objective shall be evaluated using any of the three methods provided in B.3.2 and shall meet the requirements of B.10.2 through B.10.5.

B.10.2 Nominal strength R_n shall be in accordance with Chapter 22.

B.10.3 Expected strength $R_{ne,w}$ is permitted to be defined in accordance with the nominal strength provisions of Chapter 22, with f_{ce}' substituted for f_c' and f_{ye} substituted for f_y .

B.10.4 ϕ shall be determined in accordance with Chapter 21.

B.10.5 For any member that is part of the lateral force resisting system, response beyond the onset of strength decay in any of the response history analyses of this Appendix shall not be permitted.

COMMENTARY

the continuous occupancy, limited interruption performance objective. Recommended values for effective stiffness for reinforced concrete members subjected to various wind load demands are given in ACI SP-240 (Horvilleur et al. 2006) and Manuals and Reports on Engineering Practice, MOP 243 (2020).

RB.9—Expected material strength

RB.9.2 The multiplier of 1.3 on f_c' may be smaller for high-strength concrete and may be affected by the use of fly ash and other additives. Refer to ACI PRC-232.2 for discussion of effects of fly ash. Values provided in Table B.9.2 are based on data reported by Abdullah et al. (2022) and Mander and Matamoros (2019). ASTM A706 Grade 100 values are not in the table due to limited data.

RB.10—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective—general

RB.10.1 The ASCE/SEI Prestandard for Performance-Based Wind Design provides three methods to evaluate the performance objective for continuous occupancy, limited interruption. Method 1 requires provision of minimum strength for equivalent static wind loads, followed by linear response history analysis or nonlinear response history analysis. Refer to Figure RB.11.1 for the Method 1 flow-chart. Methods 2 and 3 require minimum strength for equivalent static wind loads and use of nonlinear response history analysis for carrying out reliability-based conditional probability assessment and fully coupled reliability assessment respectively.

CODE

B.10.6 Method 1 requirements and acceptance criteria shall be in accordance with B.11.

B.10.7 Method 2 and Method 3 requirements and acceptance criteria shall be in accordance with B.12.

B.10.8 Where analysis indicates an element is yielding, design shear force shall be taken as 1.1 times the forces calculated by nonlinear response history analysis.


B.11—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Method 1

B.11.1 If Method 1 is used, the requirements of B.11.2 through B.11.4 shall be satisfied.

COMMENTARY

RB.10.8 Design shear forces are amplified to account for actual yield strength variability versus f_{ye} .

RB.11—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Method 1



Notes:

1. Minimum requirement utilizing the ASCE/SEI 7 Directional Procedure or vertical distribution from wind tunnel static loads.
2. It is permitted to omit the linear response history analysis and proceed directly to a nonlinear response history analysis.

Fig. RB.11.1—Method 1 for continuous occupancy, limited interruption performance objective.

CODE

B.11.2 Required strength from a linear analysis using equivalent static wind loads associated with force-controlled and deformation-controlled actions shall not exceed $1.25\phi R_{ne,w}$.

B.11.3 If required strength is calculated using linear static or linear response history analysis, the requirements of B.11.3.1 through B.11.3.3 shall be satisfied.

B.11.3.1 Required strength in members for force-controlled actions shall not exceed ϕR_n .

B.11.3.2 Required strength in members for deformation-controlled actions shall not exceed $1.25R_{ne,w}$.

B.11.3.3 For columns, where P_u and M_u occur simultaneously, (a) or (b) shall be satisfied:

(a) If the column axial load is less than or equal to the design axial strength associated with the tension-controlled limit, the action shall be permitted to be classified as deformation-controlled and B.11.3.2 shall apply. The tension-controlled limit shall be determined based

COMMENTARY

RB.11.2 The minimum strength provisions in the ASCE/SEI Prestandard for Performance-Based Wind Design stipulate lower bound limits for demands from the static wind loads according to ASCE/SEI 7 or the wind tunnel procedure according to ASCE/SEI 7-22 Chapter 31. Minimum strength for members with force-controlled and deformation-controlled actions is established by requiring an analysis using equivalent static wind loads and associated acceptance criteria to provide a consistent minimum strength level regardless of response history analysis results. Note that if an equivalent static analysis is performed for Method 1, ϕR_n will govern for force-controlled actions in accordance with B.11.3.1.

RB.11.3 The ASCE/SEI Prestandard for Performance-Based Wind Design permits elastic static or linear response history analysis. A nonlinear response history analysis may be required according to B.11.4.

RB.11.3.2 Yielding is permitted in members for deformation-controlled actions provided there is ability to resist gravity load post-yielding.

RB.11.3.3 Actions can only be classified as deformation-controlled if the axial load is below the tension-controlled limit to ensure there is ability to resist gravity loads. Refer to Fig. RB.11.3.3 for a representative interaction curve indicating the distinction between the strengths associated with deformation-controlled and force-controlled actions for combined axial load and moment. Refer to 21.2.2 for more information.




Fig. RB.11.3.3—P-M diagrams for Method 1.

CODE

on the ϕ factor in accordance with Chapter 21 and the nominal strength in accordance with Chapter 22.

(b) The action shall be classified as force-controlled and B.11.3.1 shall apply.

B.11.4 For cases where linear response history analysis according to B.11.3 indicates required strength in members for deformation-controlled actions exceed $R_{ne,w}$, or if a linear response history analysis is not performed, a nonlinear response history analysis shall be required. The nonlinear response history analysis shall satisfy the requirements of B.11.4.1 through B.11.4.2.

B.11.4.1 Required strength in members for force-controlled actions shall not exceed ϕR_n .

B.11.4.2 The response of members with deformation-controlled actions shall not exceed the deformation limit Δ_L , where Δ_L shall be determined by (a), (b), or (c):

- (a) For beams and columns modeled using lumped plasticity models, Δ_L , evaluated at the chord rotation, shall not exceed $1.5 \theta_{ye}$.
- (b) For walls modeled using distributed plasticity models, Δ_L shall be evaluated using the average vertical strain at the extreme compression and tension fibers over a story height, and the strain shall not exceed the greater of 0.0015 in compression and $1.5\epsilon_{ye}$ in tension.
- (c) Other values accepted by the independent structural design reviewer based on substantiating test data or analysis.

B.12—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Methods 2 and 3

B.12.1 If Method 2 or 3 is used, the requirements in B.12.2 through B.12.5 shall be satisfied.

COMMENTARY

RB.11.4.2 The deformation limit on beams and columns is established to provide a reliable mechanism to dissipate energy without compromising strength and stability of the member or structure (Abdullah and Wallace 2021). The expected yield rotation may be determined as the rotation associated with the expected strength based on the laboratory test results used to develop the nonlinear force-deformation curves required by B.6.2.2.2. For walls, a higher value of average vertical strain over the story height may be permitted where confinement reinforcement consistent with a special boundary element (Section 18.10.6.4) is provided. Inelastic strain at 1.5 times reinforcement yield should be limited to approximately 10 cycles, unless higher limits are shown acceptable through testing. A higher number of lesser magnitude inelastic cycles are acceptable if validated through laboratory testing or calculations using an approach such as the Coffin Manson relationship (Coffin 1954). The deformation limit may also be substantiated by test data or analysis provided that the testing meets or exceeds the magnitude and quantity of inelastic cycles required by the response history analysis. The testing or analysis should demonstrate adequate performance at an appropriate number of cycles to prevent low-cycle fatigue failure.

RB.12—Required strength and acceptance criteria for continuous occupancy, limited interruption performance objective by Methods 2 and 3

RB.12.1 Method 2 outlined in the ASCE/SEI Prestandard for Performance-Based Wind Design is based upon a conditional probability assessment in which the response of the structure is characterized through nonlinear response history analysis. Method 3 is based on a fully coupled reliability-based assessment in which the response of the structure is characterized through nonlinear response history analysis or other appropriate nonlinear analysis methods. The two methods differ as follows:

CODE

B.12.2 Required strength from a linear analysis using equivalent static wind loads associated with force-controlled and deformation-controlled actions shall not exceed $1.5\phi R_{ne,w}$.

B.12.3 Using nonlinear response history analysis, members with force-controlled actions, deformation-controlled actions, or both in the main wind-force-resisting system shall satisfy the target reliability stated in the general building code. The reliability analysis shall consider uncertainties in capacity in accordance with B.12.4 and B.12.5. Depending on the capacity model adopted, uncertainty in the parameters of the model shall be included and documented for peer review.

B.12.4 Compressive strength of concrete shall consider a lognormal probability distribution with f_{ce}' for the mean, where f_{ce}' is defined in B.9, and a coefficient of variation ≥ 0.2 .

B.12.5 The yield strength of reinforcement shall consider a lognormal probability distribution with f_{ye} for the mean, where f_{ye} is defined in B.9, and a coefficient of variation ≥ 0.1 .

B.13—Detailing requirements

B.13.1.1 Requirements of B.13.2 through B.13.8 shall apply to portions of the main wind-force-resisting system where deformations calculated by nonlinear response history analysis exceed yield deformations.

B.13.1.2 The requirements of B.13.9 shall apply to all elements or parts of elements that are not part of the main wind-force-resisting system.

B.13.1.3 If requirements in B.13 conflict with other requirements in this Code, the most conservative requirement(s) shall govern.

COMMENTARY

Method 2 requires a design wind scenario to be determined where structural performance is characterized using simplified probabilistic calculations.

Method 3 requires the consideration of many possible wind scenarios and does not consider simplified probabilistic calculations in estimating performance.

RB.12.2 The minimum strength provisions in the ASCE/SEI Prestandard for Performance-Based Wind Design stipulate lower bound limits for demands estimated from the static wind loads according to ASCE/SEI 7 or the wind tunnel procedure according to ASCE/SEI 7-22 Chapter 31. Minimum strength for members with force-controlled and deformation-controlled actions is established by requiring an analysis using equivalent static wind loads and associated acceptance criteria to provide a consistent minimum strength level regardless of response history analysis results. Yielding is permitted in members for deformation-controlled actions provided there is the ability to resist gravity loads after yielding has occurred. In addition to the acceptance criteria for members with force-controlled and deformation-controlled actions, the structure also needs to meet the target reliability provided in ASCE/SEI 7.

RB.12.3 The ASCE/SEI Prestandard for Performance-Based Wind Design provides a framework to demonstrate satisfactory response using reliability analysis. Target reliabilities for components and connections are based on ASCE/SEI 7-22 Table 1.3.1a. Target reliabilities for the system are provided in the ASCE/SEI Prestandard for Performance-Based Wind Design. With more detailed reliability analysis, minimum strength requirements using static loads (B.12.2.1) are reduced compared to the methodology used in B.11.2.

RB.12.4 The value for the minimum coefficient of variation was established based on analysis of material test data reported in Nowak et al. (2011).

RB.12.5 The value for the minimum coefficient of variation was established based on analysis of material test data reported in Nowak et al. (2011).

RB.13—Detailing requirements

RB.13.1.1 The requirements of this section are intended to ensure moderately ductile response consistent with the deformation and force limits specified in this appendix and avoid brittle failures.

CODE

B.13.2 *Structural walls and wall piers*

B.13.2.1 The distributed web longitudinal reinforcement ratio ρ_ℓ in structural walls and wall piers shall not be less than 0.0025.

B.13.2.2 Structural walls or wall piers with $h_w/\ell_w \geq 2.0$ shall satisfy (a) through (c).

- (a) Longitudinal reinforcement ratio within $0.15\ell_w$ from the end of a vertical wall segment, and over a width equal to the wall thickness, shall be at least $6\sqrt{f'_c}/f_y$ at the critical section.
- (b) Longitudinal reinforcement required by (a) shall extend vertically above and below the critical section at least the greater of ℓ_w and $M_u/3V_u$.
- (c) No more than 50% of the reinforcement required by (a) shall be terminated at any one section.

B.13.3 *Beams*

B.13.3.1 Provisions 9.6.1.3, 9.6.2.2, and Table 9.6.3.1 shall not apply to beams.

B.13.3.2 A minimum area of shear reinforcement, $A_{v,min}$, as defined in Table 9.6.3.4, shall be provided along the entire length of beams for which analysis indicates yielding of longitudinal reinforcement may occur.

B.13.3.3 Spacing of transverse reinforcement shall not exceed the smaller of (a) through (d) in beams for which analysis indicates yielding of longitudinal reinforcement may occur:

- (a) $d/4$
- (b) Eight times the diameter of the smallest longitudinal bar enclosed
- (c) 24 times the diameter of the smallest transverse reinforcing bar
- (d) 12 in.

B.13.3.4 Beams shall have at least two continuous top and two continuous bottom bars. Continuous bottom bars shall

COMMENTARY

RB.13.2 *Structural walls and wall piers*

Minimum longitudinal reinforcement is intended to result in sectional flexural capacities exceeding the cracking moment to promote the formation of well-distributed flexural cracks in yielding regions. The critical section refers to any section where flexural yielding is indicated by analysis to occur. The requirement for the longitudinal reinforcement ratio within $0.15\ell_w$ from the end of a vertical wall segment is the same as 18.10.2.4(a).

RB.13.3 *Beams*

RB.13.3.1 This provision is intended to result in flexural strength exceeding the cracking strength regardless of the analysis results. Provisions 9.6.1.3, 9.6.2.2, and Table 9.6.3.1 are not permitted for beams of main wind-force-resisting systems if nonlinear response history shows yielding because those provisions bypass requirements meant to produce deformation-controlled elements.

RB.13.3.2 Minimum shear reinforcement is required to produce deformation-controlled beams.

RB.13.3.3 Continuity of longitudinal reinforcement is required in beams of the main wind-force-resisting systems indicated by analysis to yield. This requirement does not exist elsewhere in the code for interior beams in non-seismic applications.

CODE

have a total area not less than one-fourth the maximum area of bottom bars along the span. These bars shall develop f_{ye} in tension at the face of the support in accordance with 25.4 by substituting a bar stress of f_{ye} for f_y .

B.13.4 Columns

B.13.4.1 Columns indicated by analysis to yield shall be spirally reinforced in accordance of 25.7.3 or shall meet the requirements of B.13.4.1.1 through B.13.4.1.5.

B.13.4.1.1 At both ends of the column, hoop and crosstie reinforcement satisfying 25.7.2 and 25.7.4 shall be provided at spacing s_o over a length ℓ_o measured from the joint face.

B.13.4.1.2 Spacing s_o shall not exceed the least of (a) through (c):

- (a) For Grade 60, the smaller of $8d_b$ of the smallest longitudinal bar enclosed and 8 in.
- (b) For Grade 80, the smaller of $6d_b$ of the smallest longitudinal bar enclosed and 6 in.
- (c) One-half of the smallest cross-sectional dimension of the column

B.13.4.1.3 Length ℓ_o shall not be taken less than the greatest of (a), (b), and (c):

- (a) Depth of the column at the joint face or at the section where flexural yielding is likely to occur
- (b) One-sixth of the clear span of the column
- (c) 18 in.

B.13.4.1.4 The first hoop shall be located not more than $s_o/2$ from the joint face.

B.13.4.1.5 Outside of length ℓ_o , spacing of hoops or ties shall be in accordance with 10.7.6.5.2.

B.13.4.2 Columns supporting reactions from discontinuous stiff members, such as walls, shall be reinforced with spirals satisfying 25.7.3 or hoops and crossties satisfying 25.7.2, 25.7.4, and B.13.4.1.2 over the full height beneath the level at which the discontinuity occurs if the portion of factored axial compressive force in these members related to wind load effects exceeds $f_c'A_g/10$. If design forces have been magnified to account for the overstrength of the vertical elements of the main wind-force-resisting system, the limit of $f_c'A_g/10$ shall be increased to $f_c'A_g/4$. Transverse reinforcement shall extend above and below the column at least ℓ_d of the largest longitudinal column bar. Where the column terminates on a footing or mat, the required transverse reinforcement shall extend at least 12 in. into the footing or mat.

COMMENTARY**RB.13.4 Columns**

RB.13.4.1 Minimum detailing is required for columns indicated by analysis to yield to ensure their response is ductile.

RB.13.4.1.1 Columns indicated by analysis to yield are required to have hoops within a distance ℓ_o from joint faces. Outside the distance ℓ_o , either hoops or ties can be provided.

CODE

COMMENTARY

B.13.5 *Beam-column joints*

B.13.5.1 Beam-column joints shall be in accordance with B.13.5.2 if analysis indicates yielding in one or more components framing into the joint.

B.13.5.2 Beam-column joints shall be in accordance with Chapter 15. In 15.4.2.1, V_u shall be calculated on a plane at mid-height of the joint using column shear and tensile and compressive beam forces consistent with expected moment strengths.

B.13.6 *Anchors*

B.13.6.1 Anchors of structural elements indicated by analysis to yield shall be in accordance with 17.10.5 and 17.10.6, with wind-induced forces substituted for earthquake-induced forces.

B.13.6.2 Anchor reinforcement used in main wind-force-resisting system shall be deformed reinforcement and shall be in accordance with the anchor reinforcement requirements of 20.2.2.

B.13.6.3 Post-installed anchors are not permitted to be used in portions of the main wind-force-resisting system indicated by analysis to yield.

B.13.7 *Development and lap splice lengths*

B.13.7.1 Within a distance equal to the member depth from the column or beam face for moment frames, and within a distance equal to the lesser of the story height and wall length from critical sections for structural walls where analysis indicates yielding of the reinforcement, (a) and (b) shall be satisfied.

(a) Development length and lap-splice length of longitudinal bars in tension shall be calculated using f_{ye} .

(b) Concrete cover measured to the lap-spliced longitudinal bars shall be at least $1.5d_b$ of the largest longitudinal bar unless confinement reinforcement is provided such that $K_{tr} \geq 1.35$. Clear spacing between lap-spliced longitudinal bars shall be at least $3d_b$ of the longitudinal bar.

B.13.8 *Foundations*

B.13.8.1 If analysis indicates yielding of column reinforcement and structural wall reinforcement due to forces induced by wind load effects, column and wall longitudinal reinforcement shall extend into the footing, mat, or pile cap and shall develop f_{ye} in tension at the interface.

B.13.9 *Members not designated as part of the main wind-force-resisting system*

B.13.9.1 Members not designated as part of the main wind-force-resisting system shall have sufficient deformation capacity to accommodate the deformations calculated to occur in the main wind-force-resisting system.

RB.13.8 *Foundations*

RB.13.8.1 Reinforcement in foundations is required to provide a load path for tensile vertical forces associated with yielding of the superstructure.

RB.13.9 *Members not designated as part of the main wind-force-resisting system*

RB.13.9.1 The term member is used here in the same sense it is used in 18.14 and refers exclusively to structural members. Nevertheless, the engineer should give consideration to the effects of the expected deformations and motions on nonstructural building components and equipment.

CODE

B.13.9.2 For slab-column connections of two-way slabs without beams, slab shear reinforcement satisfying the requirements of B.13.9.2.2 and either 8.7.6 or 8.7.7 shall be provided at any slab critical section defined in 22.6.4.1 for the following conditions:

- (a) Nonprestressed slabs where $\delta_{x,w}/h_{sx} \geq 0.035 - (1/20)(v_{uv}/\phi v_c)$
- (b) Unbonded post-tensioned slabs with f_{pc} in each direction meeting the requirements of 8.6.2.1, where $\delta_{x,w}/h_{sx} \geq 0.040 - (1/20)(v_{uv}/\phi v_c)$

The value of $(\delta_{x,w}/h_{sx})$ shall be taken as the greater of the values of the adjacent stories above and below the slab-column connection, and v_c shall be calculated in accordance with 22.6.5 except that the value of V_p shall be taken as zero for unbonded post-tensioned slabs.

B.13.9.2.1 The shear reinforcement requirements of B.13.9.2 need not be satisfied if (a) or (b) is met:

- (a) $\delta_{x,w}/h_{sx} \leq 0.005$ for nonprestressed slabs
- (b) $\delta_{x,w}/h_{sx} \leq 0.01$ for unbonded post-tensioned slabs with f_{pc} in each direction meeting the requirements of 8.6.2.1

B.13.9.2.2 Required slab shear reinforcement shall provide $v_s \geq 3.5\sqrt{f'_c}$ at the slab critical section and shall extend at least four times the slab thickness from the face of the support adjacent to the slab critical section.

B.14—Independent structural design review

B.14.1 The analysis and design shall be reviewed by an independent structural design reviewer. The independent structural design reviewer shall act under the direction of the building official.

B.14.2 The independent structural design review shall be performed by one or more individuals acceptable to the building official and shall possess, at a minimum, knowledge of (a) through (d):

- (a) Selection of critical wind directions and their use in linear and nonlinear response history analysis.
- (b) Behavior of structural systems of the type under consideration subjected to static and dynamic wind loading.
- (c) Analytical structural modeling for use in nonlinear response history analysis, including the use of physical

COMMENTARY

RB.13.9.2 Slab-column connections should be proportioned to reduce the likelihood of slab punching shear failure. v_{uv} should be obtained from load combination 5.3.1d, and drift $\delta_{x,w}$ should be taken as the maximum story drift expected for wind demands based on nonlinear response history analyses.

RB.14—Independent structural design review

RB.14.1 The independent structural design reviewer (also known as a peer reviewer) should provide an independent, objective, technical review of those aspects of the structural design of the building that relate to wind performance and advises the building official on whether the design meets the acceptance criteria and the expected building performance. A review by the independent structural design reviewer is not intended to replace quality assurance measures ordinarily exercised by the licensed design professional, nor is it intended to replace regular plan check review by the building official. Responsibility for the structural design remains solely with the licensed design professional in responsible charge of the structural design.

RB.14.2 On many projects, an independent structural design review may be provided by a review team approved by the building official. Each member of the review team should possess specialized knowledge and expertise and jointly meet the requirements of B.14.2. An independent structural design reviewer should not have conflicts of interest with respect to the project and should not be part of the design team for the project.

CODE

tests in the creation and calibration of the structural analysis models and knowledge of parameters that affect wind loading, including damping.

(d) Requirements of Appendix B as pertaining to the design of the type of structure under consideration.

B.14.3 The scope of the independent structural design review shall be approved by the building official and shall include a minimum of (a) through (h):

- (a) Basis of design document, including the performance objectives related to wind loading, the overall wind force-resistant design methodology, and acceptance criteria
- (b) Proposed structural system
- (c) Wind load determination by wind tunnel testing and selection of the critical wind directions
- (d) Modeling approaches for components
- (e) Structural analysis model, including soil-structure interaction as applicable, and verification that the structural analysis model adequately represents the properties of the structural system
- (f) Structural analysis results and determination of whether calculated response meets approved acceptance criteria
- (g) Design and detailing of structural components
- (h) Drawings, specifications, and quality control/quality assurance and inspection provisions in the construction documents

B.14.4 The independent structural design review shall be documented and submitted to the building official in accordance with jurisdictional requirements.

B.14.4.1 Absent any formal requirements by the building official, local jurisdiction, or both, the independent structural design review shall be documented as follows:

- (a) The independent structural design reviewer shall issue comments and questions to the licensed design professional.
- (b) The licensed design professional shall provide written responses to the independent structural design reviewer.
- (c) The independent structural design reviewer shall summarize the review in a letter addressed to the building official that shall include a log of all questions or comments and responses. Any items that lack resolution or consensus shall be clearly explained with reasons for lack of agreement.

COMMENTARY

RB.14.3 The scope of the independent structural design review should be clearly defined and acceptable to the building official.

RB.14.4 A statement of agreement with the design should be provided. However, there may be occasions where complete agreement between the independent structural design reviewer and the licensed design professional cannot be reached. These items should be documented in the summary review letter.

Notes



APPENDIX C—SUSTAINABILITY AND RESILIENCE (*NEW APPENDIX*)

CODE COMMENTARY

C.1—Terminology

C.1.1 Terminology

class of concrete—characterization of concrete of various qualities or usages, usually by compressive strength.

environmental product declaration (EPD)—declaration providing environmental data using predetermined parameters meeting the requirements of ISO 21930.

global warming potential (GWP)—index used to determine the energy absorption caused by the emissions of different gases associated with a product, normalized to an equivalent mass of carbon dioxide over a period of 100 years.

hazard event—potential cause of damage to a structure and the magnitude or intensity associated with that cause.

life cycle assessment (LCA)—compilation and evaluation of the inputs, outputs, and potential environmental impacts of a product throughout its life cycle.

resilient design—design process that anticipates, addresses, and mitigates risks associated with known natural or human-caused hazards by balancing construction cost, material consumption, recovery of functionality, and potential financial loss should a particular hazard event occur.

sustainable design—design process that considers the balance among social, economic, and environmental principles from the Work's conception through the end of its service life.

RC.1—Terminology

RC.1.1 Terminology

global warming potential (GWP)—This index was developed as a single parameter to estimate the global warming impact of different gaseous emissions.

hazard event—Selecting the demands for which a structure will be designed requires establishing the hazards to which the structure may be subjected and the intensities of those hazards for target risk levels. For example, a structure might be subjected to frequent earthquakes with small intensities and very infrequent earthquakes with large intensities.

resilient design—The design of resilient concrete structural systems includes: 

- (a) Assessing the importance of the structure with respect to its functional, social, and economic roles in the community
- (b) Evaluating the hazards to which the structure may be exposed (such as flood or earthquake) and the estimated magnitudes associated with target risk levels in the present and in the future
- (c) Assessing the vulnerability and sensitivity of the structure to damage
- (d) Assessing the consequences of damage to the structure caused by the hazard event(s)
- (e) Evaluating the interdependent effects of the structure on other physical and social systems

In the context of the community of which individual structures are a part, resilience may include the community's ability to absorb disturbances while retaining the same basic structure and functionality, the capacity for self-organization, and the capacity to adapt to stress and change. The hazard design criteria and required recovery time following a hazard event should be based on the use, importance, and occupancy of the structure.

sustainable design—The design of sustainable concrete structural systems seeks to achieve balance between the production of concrete elements and the required performance characteristics in all phases of the structural system's life cycle. This approach includes measures to reduce the consumption of resources, including but not limited to water, aggregates, cementitious materials, reinforcing steel, and fuels; considers economic value and societal and cultural impacts; and minimizes impacts on the environment. When considering sustainable design, the Code places emphasis on the environmental impacts. Users should also consider social and economic principles of sustainable design that are not directly addressed

CODE

Whole Building Life Cycle Assessment (WBLCA)—life cycle assessment (LCA) of the complete building.

C.2—Scope

C.2.1 This appendix provides requirements for the sustainable design and resilient design of structures when required by the owner or the authority having jurisdiction.

C.2.2 The requirements of Appendix C shall be in addition to those in **Chapters 1** through **26**.

C.2.3 If the provisions of Appendix C are incorporated in a design, the licensed design professional shall identify and state the applicable sustainability and resilience requirements in the construction documents.

C.3—Evaluation of Sustainability of Structural Concrete Systems

C.3.1 If structural system sustainability is to be quantified, an assessment shall be required. The assessment shall be deemed to be satisfied by (a) and (b).

COMMENTARY

by the Code. The principles of resilience and resilient design should be considered in sustainable design.

RC.2—Scope

RC.2.1 This appendix provides requirements specific to design, concrete materials and mixtures, and construction procedures to support the sustainability and resilience goals for the Work.

Strength, serviceability, and durability are implicit attributes for achieving a sustainable and resilient design.

Selecting materials that minimize environmental impact may improve the sustainability of structural concrete. These materials may include but are not limited to alternative cementitious materials, supplementary cementitious materials, alternative aggregates, and recycled materials.

Whole Building Life Cycle Assessment (WBLCA) may be used to demonstrate the quantitative improvement of a sustainable design.

The design of sustainable concrete structures should also consider resilience. Structures that cannot be economically repaired or reoccupied after being damaged by a hazard event are demolished (and sometimes replaced) or abandoned, often resulting in a loss to the community. Demolishing structures is an unsustainable practice as it generates waste that impacts human health and the environment and contributes to the embodied energy of the demolished structure, often with little benefit to society. Structures designed for resilience are not necessarily sustainable, although their designs may incorporate sustainable materials or principles.

RC.2.3 Establishing stakeholders' sustainability and resilience goals during design and construction allows for optimization of design, materials, and construction and consideration of innovative technologies to achieve reduced environmental, societal, and economic impacts throughout all phases of the life of the structure.

The owner or licensed design professional may specify requirements that exceed the minimum requirements of the Code. Such requirements may include higher strengths, more restrictive deflection limits, enhanced durability, increased sustainability, and improved resilience. Identifying hazard events to which a structure may be subjected during its life, evaluating the risks associated with those hazards, and accepting or mitigating those risks are steps of establishing the resilience goals for the Work.

RC.3—Evaluation of Sustainability of Structural Concrete Systems

RC.3.1 Comparing the relative sustainability of different structural systems is an important part of sustainable design.

CODE

- (a) The quantification shall be part of a whole building life cycle assessment (WBLCA) conducted in accordance with **ASTM E2921**.
- (b) The WBLCA shall include the following:
 - (1) At a minimum, the environmental impact categories included in the WBLCA shall include global warming potential, acidification potential, eutrophication potential, ozone depletion potential, and smog potential.
 - (2) The life cycle inventory categories included in the WBLCA shall include water consumption, solid waste, total energy demand, and total nonrenewable energy demand.
 - (3) It shall be permitted to include operational energy in the WBLCA.

COMMENTARY

Life cycle assessment (LCA) is a tool to evaluate the environmental impacts associated with any product throughout its life cycle. Whole building life cycle assessment (WBLCA) is an adaptation of an LCA that studies the whole building as a system.

If a WBLCA is to be conducted, the owner should designate a member of the project team who is responsible for gathering the design information from the designers and conducting the WBLCA. The WBLCA may be performed by the structural engineer, architect, specialty sustainability consultant, or other designee.

It is possible to affect the sustainability of a structural system by making adjustments to various elements of the system, and the code does not preclude the use of comparisons between individual parts of the system. However, WBLCA is the only method available to quantify the environmental impacts of the entire system.

ASTM E2921 establishes criteria for conducting a WBLCA. ASTM E2921 requires that a defined service life be used to compare the building design to a reference building. WBLCA can be used to review a variety of impacts during different phases of the building life cycle. Requirements of ASTM E2921 are based on **ISO 14040** and **ISO 14044** and provides guidelines on service life, life cycle stages, product replacement, operational energy, comparison to a reference building, and analysis tools.

ASTM E2921 does not define strategies to improve upon the reference building. Practitioners can, however, reference **Yang (2018)** and **Kestner et al. (2010)** for guidelines on the reference building and strategies to improve upon it. Strategies outlined in these references include structural material quantity reduction, optimized concrete mixtures, structure as the finish, alternate structural systems, performance-based design, carbon-sequestering materials, salvaged materials, and many others.

For more information on WBLCA implementation, practitioners may also reference **Simonen (2014)**, **Bayer et al. (2010)**, and **Bowick et al. (2014)**.

(b)(1) These environmental impact categories are mandatory according to **ISO 21930**, the standard that governs environmental product declarations (EPDs) for building products.

(b)(3) Inclusion of operational energy in the WBLCA captures the potential reduced energy use in the building due to the thermal mass effects of the concrete.

Many WBLCAs require operational equivalence between comparisons, but this does not mean operational energy can be excluded from the analysis. One part of operational equivalence assumes the occupants experience given comfort levels in terms of temperature, but this assumption does not adequately capture thermal mass effects. Using different amounts of concrete in other locations in the building will affect occupant comfort.

Annual energy use is calculated using a whole building energy simulation. In a whole building energy simulation,

CODE

COMMENTARY

C.3.2 The building alternative chosen for the Work shall show improvement over the reference building assessed in the WBLCA.

C.4—Resilience

C.4.1 If resilience provisions beyond building code requirements are to be considered in the structural design of the concrete structural system, the provisions of C.4 shall be permitted to be used.

C.4.2 The design of the concrete structural system and the elements of which it is composed shall consider resilience for appropriate hazards in accordance with (a) through (e):

- (a) intended use of the structure
- (b) risks associated with geographic location
- (c) consequences of damage or loss of use
- (d) tolerance of the owner for varying levels of damage or loss
- (e) associated time required to recover from a damaged state

a thermodynamic model of a building is created, and software simulates the operation and response of the building. During the whole building energy simulation, the heating and cooling loads of each space in a building over a defined period are calculated, typically over a calendar year. Based on these loads, the operation and response of the equipment and systems that control temperature and humidity, and distribute heating, cooling, and ventilation to the building are simulated. This analysis is required to determine the fuel and electricity used to provide the necessary heating, cooling, and electricity. Modeling must be performed using non-steady-state methods to fully capture thermal mass effects.

Recommendations for consideration of thermal mass effects are included in [ACI PRC-122](#), [Gajda and VanGeem \(2000\)](#), [VanGeem \(1987\)](#), and [VanGeem et al. \(1983\)](#).

Including operational energy is necessary for a full WBLCA to capture the impact of thermal mass effects from concrete elements.

RC.3.2 Because a WBLCA includes building components whose design and optimization falls outside the scope of a structural concrete code, the code does not require specific improvement. Project teams should determine the appropriate improvement while considering specific project goals or governing general building codes. For example, an improvement of 5% in three environmental impact categories is a common starting point for minimum requirements.

RC.4—Resilience

RC.4.1 The resilience of a structure is commonly described in terms of functional resilience. The Portland Cement Association defines functional resilience as “a building’s capacity to provide viable operations through extended service life, adaptive re-use, and during the challenges of natural and man-made disasters” ([PCA 2022](#)). [Abrahams et al. \(2021\)](#) discuss functional recovery.

RC.4.2 A partial list of hazards that the designer and owner should consider include fire, flood, wave action, wind, snow, earthquake, foundation settlement or heave, corrosion, and deterioration. These primary hazards can result in secondary hazards. For example, earthquakes can result in loss of electrical power, interior flooding, and release of hazardous materials.

The Fortified Commercial Wind Standards, developed by the Insurance Institute for Building and Home Safety (IIBHS), provide guidance on identifying hazards for a specific site. It covers a range of hazards including hurricane, tornado, hail, and high wind ([IIBHS 2020](#)).

RELi is a rating system adopted by the U.S. Green Building Council (USGBC). Related to resilience, it guides planning, design, maintenance, and operations; risk adaptation and mitigation for acute events; comprehensive adaptation and mitigation for a resilient present and future;

CODE

C.4.3 The required levels of performance above the minimum requirements of this Code shall be included in the construction documents.

COMMENTARY

and applied creativity and contextual factors for resiliency ([USGBC 2021](#)).

In the U.S. Resiliency Council (USRC) rating system, buildings are rated in three areas (safety, damage, and recovery) corresponding to the average performance of a building under consideration, given a single earthquake causing ground shaking at the site of the building consistent with the Design Basis Event ($2/3MCE_R$) as defined in the ASCE 7-16 provisions ([USRC 2019](#)).

National Institute of Standards and Technology (NIST) Special Publication 1190, Community Resilience Planning Guide for Buildings and Infrastructure Systems, Volumes I and II provide guidance on reviewing hazards and design considerations ([NIST 2016a,b](#)).

Other guidance for determining hazards includes:

- (a) FEMA Flood Map Service Center web search portal ([FEMA Flood Map Service Center n.d.](#))
- (b) Coastal Flooding Tools ([Data.gov n.d.](#))
- (c) Climate Central's "Surging Seas" sea level rise analysis for coastal U.S. states ([Climate Central n.d.](#))
- (d) FEMA Wind Zone Map ([FEMA Wind Zone Map n.d.](#))
- (e) NOAA National Weather Service's National Hurricane Center ([NOAA National Hurricane Center n.d.](#))
- (f) NOAA National Climatic Data Center's U.S. Tornado Climatology ([NOAA U.S. Tornado Climatology n.d.](#))
- (g) USGS Earthquake Hazards Program maps ([USGS n.d.](#))
- (h) FEMA map Wildfire Activity by County 1994 – 2013 ([FEMA Wildfire Activity 2024](#))
- (i) FEMA Federal Fire Occurrence Map Viewer ([FEMA Federal Fire n.d.](#))
- (j) U.S. Drought Monitor updated weekly ([U.S. Drought Monitor n.d.](#))

Passive survivability is defined by the Better Buildings Solution Center at the U.S. Department of Energy as "the ability of buildings to maintain habitable conditions in the event of a heating/cooling system loss." ([DOE 2021](#))

Concrete buildings can support passive survivability, which is related to extending essential services, public safety, and thermal comfort of the occupants after a natural or human-caused disaster. Resources related to this concept include:

- (a) CBE Thermal Comfort Tool ([CBE n.d.](#))
- (b) Occupational Exposure to Heat and Hot Environments ([DHS 2016](#))

RC.4.3 Model building codes, such as the International Building Code, provide minimum requirements to safeguard public health, safety, and general welfare of the occupants of buildings and structures. A building owner may require that a concrete structural system be designed with more robust performance, serviceability, and durability than the building code prescribes, and these requirements should be included in the construction documents. Enhanced performance may require designing and detailing the structural system for

CODE

C.5—Concrete Mixtures

C.5.1 Specified sustainable design metrics for concrete mixtures shall satisfy the requirements of at least one of C.5.1.1, C.5.1.2, or C.5.1.3 as defined by the licensed design professional or building official.

C.5.1.1 The maximum global warming potential (GWP) limit for each class of concrete per unit volume shall be defined in accordance with C.5.1.1.1 and C.5.1.1.2.

C.5.1.1.1 The limit shall be defined as a GWP maximum limit for a class of concrete in accordance with (a) through (c) and C.5.2:

COMMENTARY

increased magnitudes of load events, or more stringent deformation requirements. Consideration of the slow onset of hazard events that develop over time (for example, drought or melting of permafrost) may also be required. Enhanced durability features may include increased concrete cover, decreased permeability, increased corrosion resistance, or other design enhancements to increase service life.

RC.5—Concrete Mixtures

RC.5.1 The design metrics used to specify sustainable design should account for the local availability of sustainability data and the sustainable design goals for the Work. The design metrics included in C.5.1.1 and C.5.1.2 are related to global warming potential reductions, and these alternatives are geared toward locations with different levels of available data for environmental impact of concrete mixtures. C.5.1.3 allows for the licensed design professional or building official to specify other sustainable design metrics.

The choice of a sustainable design metric may depend on the local data available for that metric. Design metric limits should be based on information derived from similar local projects or applicable benchmarks that are achievable in the local market.

Strategies for developing concrete mixtures that meet the Work's sustainability requirements include, but are not limited to:

- (a) Use of lower impact primary cement, such as a blended cement
- (b) Use of lower impact supplementary cementitious materials as a portion of the total cementitious materials
- (c) Maximization of cement efficiency by optimizing concrete mixtures
- (d) Specifying a later age at which design strength is required (for example, 56 or 90 days instead of 28 days if possible)
- (e) Use of performance-based rather than prescriptive requirements for concrete mixtures (refer to **ACI PRC-329**)
- (f) Use of technologies, such as additives and greenhouse gas sequestering, that reduce the defined sustainability metric while achieving required concrete properties
- (g) Use of lower carbon processes for material production

RC.5.1.1 The use of C.5.1.1 is dependent on the availability of GWP data for concrete mixtures local to the Work. Therefore, applying this design metric should consider the ability of local producers to supply GWP data.

Similar to C.5.1.1, **ACI CODE-323** includes a process for establishing limits on global warming potential (GWP) for concrete mixtures on projects.

RC.5.1.1.1 Concrete mixtures used in some applications tend to have higher GWP values than other concrete mixtures with the same f'_c value. Considering such appli-

CODE

- (a) Limits shall be assigned to classes of concrete based on f_c' unless data regarding specific applications is available.
- (b) If data regarding specific applications is available, limits for those applications as a class of concrete shall be permitted.
- (c) If a limit is assigned to a class of concrete based on f_c' , the concrete in the Work shall be permitted to be categorized to the class of concrete of the same f_c' regardless of the age required to achieve that strength.

C.5.1.1.2 The GWP per unit volume for the concrete mixtures used in the Work shall be documented as defined in C.5.3.

C.5.1.2 A concrete-producer-specific demonstration of a reduction in concrete mixture GWP impacts shall be required in accordance with C.5.1.2.1 through C.5.1.2.4.

C.5.1.2.1 Demonstration shall compare each proposed concrete mixture to the average of all mixtures of a defined class from a single concrete producer.

C.5.1.2.2 The defined class of concrete mixtures shall meet the performance requirements of the Work and be available from the concrete producer's plants in the vicinity of the Work. Performance requirements shall include concrete mixture specified qualities and application type.

C.5.1.2.3 The required method of demonstrating GWP impact reduction shall be defined.

C.5.1.2.4 Reduction values reported for C.5.1.2 shall not be compared to reduction values reported by other producers.

C.5.1.3 A measurable sustainability limitation or requirement shall be specified by the licensed design professional or building official.

COMMENTARY

cations separately allows achievable GWP limits specific to these applications to be set.

If the class of concrete is defined by f_c' , the GWP associated with the f_c' design strength at any age can be compared to the GWP limit even if the GWP limit is determined from a benchmark f_c' at a different age. While most benchmarks utilize 28-day f_c' data, designers may specify longer time-frames to achieve an f_c' value as a strategy to reduce GWP.

RC.5.1.2 This option can be specified where there are a limited number of concrete producers in the vicinity of the Work and GWP data for concrete mixtures is not widely available. This design metric can also be specified in cases where regional industry average values for GWP are largely different from that achievable in the local area of the Work.

RC.5.1.2.2 The intent of this provision is to compare the proposed mixtures with all mixtures from a producer that meet the same performance requirements. These requirements would include strength, air content, shrinkage limits, application (shotcrete for example), and any other defined performance requirements.

RC.5.1.2.3 Reduction could include the demonstration of a reduction in the amount of cement used per unit volume, the impact of the type of cement used, or other method defined by the licensed design professional or building official. If limitation on cement content is defined, the reduction reported would need to include a listing of the mass of cement per volume used in all the mixtures from the supplier that meet the specifications. In addition, a required reduction from the average mass of cement used in these mixes could be specified.

RC.5.1.2.4 Reduction values are unique to a concrete producer and should not be compared with those of other regional producers. If a comparison between producers is required, an approach that compares producers to a common benchmark should be used.

RC.5.1.3 This provision is intended to allow for sustainability limitations that are unrelated to GWP. The requirements in C.5.1.1 and C.5.1.2 are intended for GWP reduction and may not cover all the sustainability goals of the Work. C.5.1.3 may be used in combination with one of the GWP limiting requirements.

CODE

C.5.2 GWP maximum limits

C.5.2.1 The maximum limits for each concrete class required in C.5.1.1.1 shall be defined as a GWP value per unit volume. Limits shall not be exceeded except as allowed in C.5.2.1.1. Where limits are referenced with respect to a benchmark, the benchmark shall be as defined in C.5.4.

C.5.2.1.1 Maximum limits of GWP for individual concrete mixtures shall be permitted to be exceeded provided the concrete GWP for all concrete in the Work does not exceed the concrete GWP total limit for the Work. The concrete GWP total limit for the Work shall be defined as the sum of the volume for each class of concrete multiplied by the corresponding GWP limit for that class of concrete.

C.5.3 GWP documentation

C.5.3.1 GWP values for concrete mixtures shall be documented in one of the following:

- (a) an independently verified life cycle assessment (LCA) report
- (b) an independently verified product-specific environmental product declaration (EPD)
- (c) an independently verified LCA tool.

LCA reports, EPDs, and LCA tools shall conform to ISO 14044 and the relevant product category rule that conforms to ISO 21930.

C.5.3.2 Industry average reports and regional benchmarks shall be based on life cycle assessments complying with ISO 14044 and the relevant product category rule that conforms to ISO 21930.

C.5.4 GWP Benchmark Definition

C.5.4.1 The GWP benchmark shall be defined in terms of an industry, regional, or local average. The GWP for this benchmark shall be documented as defined in C.5.3.

COMMENTARY

Commonly tracked sustainability metrics include total primary energy consumption, ozone depletion potential, acidification potential, eutrophication potential, photochemical ozone creation/smog potential, total water consumption, and depletion of non-renewable material resources that may include the use of recycled material. Information about many of these parameters can be found in [ISO 14044](#), [ISO 21930](#), and environmental product declarations (EPDs). The licensed design professional or building official may set limits on one or more of these metrics.

RC.5.2 GWP maximum limits

RC.5.2.1 Maximum GWP limits for concrete classes should be set based on values known to be achievable in the concrete market local to the Work. For example, EPDs for concrete mixtures used in the local market or regional benchmarks, as described in RC.5.4.1, could be used.

RC.5.2.1.1 Maximum limits may need to be exceeded to accommodate constructability, early-age requirements, or other needs for certain applications. A GWP total limit for the Work allows for the GWP of individual concrete mixtures to exceed their class limit as long as the total limit for the Work is met. A weighted average approach, similar to that used in [ACI CODE-323](#), could be used to set a GWP total limit for the Work.

RC.5.3 GWP documentation

RC.5.3.1 An EPD, in accordance with ISO 21930 and a valid concrete Product Category Rule (PCR), such as the PCR for Concrete V2.1 ([NSF International 2021](#)), can be used for GWP data. The EPD should include a minimum of life cycle stages A1-A3, which are equivalent to raw material supply, transport, and manufacturing.

GWP values used to comply with this section are to be developed using the same PCR as the benchmark, per the comparability requirements of ISO 21930.

RC.5.4 GWP Benchmark Definition

RC.5.4.1 The benchmark values included in Appendix C of NRMCA's regional benchmark report ([Athena Sustainable Materials Institute 2022](#)) or a benchmark report that follows the requirements of C.5.3 can be used to define the GWP benchmark.

APPENDIX D—STEEL REINFORCEMENT INFORMATION

CODE	COMMENTARY
-------------	-------------------

Appendix D.1.1 As an aid to users of the ACI Building Code, information on sizes, areas, and weights of various steel reinforcement is presented.

ASTM STANDARD REINFORCING BARS

Bar size, no.	Nominal diameter, in.	Nominal area, in. ²	Nominal weight, lb/ft
3	0.375	0.11	0.376
4	0.500	0.20	0.668
5	0.625	0.31	1.043
6	0.750	0.44	1.502
7	0.875	0.60	2.044
8	1.000	0.79	2.670
9	1.128	1.00	3.400
10	1.270	1.27	4.303
11	1.410	1.56	5.313
14	1.693	2.25	7.65
18	2.257	4.00	13.60

ASTM STANDARD PRESTRESSING STRANDS, WIRES, AND BARS

Type*	Nominal diameter, in.	Nominal area, in. ²	Nominal weight, lb/ft
Seven-wire strand (Grade 250)	1/4 (0.250)	0.036	0.122
	5/16 (0.313)	0.058	0.197
	3/8 (0.375)	0.080	0.272
	7/16 (0.438)	0.108	0.367
	1/2 (0.500)	0.144	0.490
	(0.600)	0.216	0.737
Seven-wire strand (Grade 270)	3/8 (0.375)	0.085	0.290
	7/16 (0.438)	0.115	0.390
	1/2 (0.500)	0.153	0.520
	(0.520)	0.167	0.570
	(0.563)	0.192	0.650
	(0.600)	0.217	0.740
Prestressing wire	(0.620)	0.231	0.780
	(0.700)	0.294	1.000
	0.192	0.029	0.098
	0.196	0.030	0.102
Prestressing bars (Type I, plain)	0.250	0.049	0.170
	0.276	0.060	0.204
	3/4	0.44	1.50
	7/8	0.60	2.04
	1	0.78	2.67
	1-1/8	0.99	3.38
Prestressing bars (Type II, deformed)	1-1/4	1.23	4.17
	1-3/8	1.48	5.05
	5/8	0.28	0.98
	3/4	0.42	1.49
	1	0.85	3.01
	1-1/4	1.25	4.39
	1-3/8	1.58	5.56
	1-3/4	2.58	9.10
	2-1/2	5.16	18.20
	3	6.85	24.09

*Availability of some strand, wire, and bar sizes should be investigated in advance.

WRI STANDARD WIRE REINFORCEMENT*

W & D size		Nominal diameter, in.	Nominal area, in. ²	Nominal weight, lb/ft	Area, in. ² /ft of width for various spacings						
					Center-to-center spacing, in.						
Plain	Deformed				2	3	4	6	8	10	12
W31	D31	0.628	0.310	1.054	1.86	1.24	0.93	0.62	0.46	0.37	0.31
W30	D30	0.618	0.300	1.020	1.80	1.20	0.90	0.60	0.45	0.36	0.30
W28	D28	0.597	0.280	0.952	1.68	1.12	0.84	0.56	0.42	0.33	0.28
W26	D26	0.575	0.260	0.884	1.56	1.04	0.78	0.52	0.39	0.31	0.26
W24	D24	0.553	0.240	0.816	1.44	0.96	0.72	0.48	0.36	0.28	0.24
W22	D22	0.529	0.220	0.748	1.32	0.88	0.66	0.44	0.33	0.26	0.22
W20	D20	0.505	0.200	0.680	1.20	0.80	0.60	0.40	0.30	0.24	0.20
W18	D18	0.479	0.180	0.612	1.08	0.72	0.54	0.36	0.27	0.21	0.18
W16	D16	0.451	0.160	0.544	0.96	0.64	0.48	0.32	0.24	0.19	0.16
W14	D14	0.422	0.140	0.476	0.84	0.56	0.42	0.28	0.21	0.16	0.14
W12	D12	0.391	0.120	0.408	0.72	0.48	0.36	0.24	0.18	0.14	0.12
W11	D11	0.374	0.110	0.374	0.66	0.44	0.33	0.22	0.16	0.13	0.11
W10.5		0.366	0.105	0.357	0.63	0.42	0.315	0.21	0.15	0.12	0.105
W10	D10	0.357	0.100	0.340	0.60	0.40	0.30	0.20	0.15	0.12	0.10
W9.5		0.348	0.095	0.323	0.57	0.38	0.285	0.19	0.14	0.11	0.095
W9	D9	0.338	0.090	0.306	0.54	0.36	0.27	0.18	0.13	0.10	0.09
W8.5		0.329	0.085	0.289	0.51	0.34	0.255	0.17	0.12	0.10	0.085
W8	D8	0.319	0.080	0.272	0.48	0.32	0.24	0.16	0.12	0.09	0.08
W7.5		0.309	0.075	0.255	0.45	0.30	0.225	0.15	0.11	0.09	0.075
W7	D7	0.299	0.070	0.238	0.42	0.28	0.21	0.14	0.10	0.08	0.07
W6.5		0.288	0.065	0.221	0.39	0.26	0.195	0.13	0.09	0.07	0.065
W6	D6	0.276	0.060	0.204	0.36	0.24	0.18	0.12	0.09	0.07	0.06
W5.5		0.265	0.055	0.187	0.33	0.22	0.165	0.11	0.08	0.06	0.055
W5	D5	0.252	0.050	0.170	0.30	0.20	0.15	0.10	0.07	0.06	0.05
W4.5		0.239	0.045	0.153	0.27	0.18	0.135	0.09	0.06	0.05	0.045
W4	D4	0.226	0.040	0.136	0.24	0.16	0.12	0.08	0.06	0.04	0.04
W3.5		0.211	0.035	0.119	0.21	0.14	0.105	0.07	0.05	0.04	0.035
W3		0.195	0.030	0.102	0.18	0.12	0.09	0.06	0.04	0.03	0.03
W2.9		0.192	0.029	0.098	0.174	0.116	0.087	0.058	0.04	0.03	0.029
W2.5		0.178	0.025	0.085	0.15	0.10	0.075	0.05	0.03	0.03	0.025
W2		0.160	0.020	0.068	0.12	0.08	0.06	0.04	0.03	0.02	0.02
W1.4		0.134	0.014	0.049	0.084	0.056	0.042	0.028	0.02	0.01	0.014

*Reference "Structural Welded Wire Reinforcement Manual of Standard Practice," Wire Reinforcement Institute, Hartford, CT, sixth edition, Apr. 2001, 38 pp.

APPENDIX E—EQUIVALENCE BETWEEN SI-METRIC, MKS-METRIC, AND U.S. CUSTOMARY UNITS OF NONHOMOGENEOUS EQUATIONS IN THE CODE COMMENTARY

A table of equivalence between SI-Metric, MKS-Metric, and U.S. Customary Units of nonhomogeneous equations in the Code may be downloaded at the ACI Bookstore. Search for "318-25 Appendix E."

COMMENTARY REFERENCES

ACI Committee documents and documents published by other organizations that are cited in the commentary are listed first by document number, year of publication, and full title, followed by authored documents listed alphabetically.

American Association of State Highway and Transportation Officials (AASHTO)

AASHTO R72-2016(2020)—Standard Practice for Match Curing of Concrete Test Specimens

LRFDCONS-4-2017—LRFD Bridge Construction Specifications, Fourth Edition

LRFDUS-8-2020—LRFD Bridge Design Specifications, Ninth Edition

American Concrete Institute (ACI)

ACI SPEC-117-10(15)—Specification for Tolerances for Concrete Construction and Materials

ACI PRC-122-14—Guide to Thermal Properties of Concrete and Masonry Systems

ACI PRC-201.2-23—Durable Concrete—Guide

ACI PRC-209-92(08)—Prediction of Creep, Shrinkage, and Temperature Effects in Concrete Structures

ACI PRC-211.1-22—Selecting Proportions for Normal-Density and High-Density Concrete—Guide

ACI PRC-213-14(23)—Structural Lightweight-Aggregate Concrete—Guide

ACI PRC-214-11(19)—Guide to Evaluation of Strength Test Results of Concrete

ACI PRC-214.4-21—Obtaining Cores and Interpreting Core Compressive Strength Results—Guide

ACI PRC-215-21—Concrete Structure Design for Fatigue Loading—Report

ACI CODE-216.1-14(19)—Code Requirements for Determining Fire Resistance of Concrete and Masonry Construction Assemblies

ACI PRC-222-19—Protection of Metals in Concrete against Corrosion

ACI PRC-223-21—Shrinkage-Compensating Concrete—Guide

ACI PRC-224-01(08)—Control of Cracking in Concrete Structures

ACI PRC-224.2-92(04)—Cracking of Concrete Members in Direct Tension

ACI PRC-228.1-19—Report on In-Place Methods for Estimating In-Place Concrete Strength

ACI PRC-232.2-18—Report on the Use of Fly Ash in Concrete

ACI PRC-233-17—Guide to the Use of Slag Cement in Concrete and Mortar

ACI PRC-234-06(12)—Guide for the Use of Silica Fume in Concrete

ACI PRC-237-07(19)—Self-Consolidating Concrete

ACI SPEC-301-20—Specifications for Concrete Construction

ACI PRC-302.1-15—Guide to Concrete Floor and Slab Construction

ACI PRC-304-00(09)—Guide for Measuring, Mixing, Transporting, and Placing Concrete

ACI PRC-305-20—Guide to Hot Weather Concreting

ACI SPEC-305.1-14(20)—Specification for Hot Weather Concreting

ACI PRC-306-16—Guide to Cold Weather Concreting

ACI SPEC-306.1-90(02)—Standard Specification for Cold Weather Concreting

ACI CODE-307-23—Reinforced Concrete Chimneys—Code and Commentary

ACI PRC-308-16—Guide to External Curing of Concrete

ACI PRC-308-213-13—Report on Internally Cured Concrete Using Prewetted Absorptive Lightweight Aggregate

ACI SPEC-308.1-23—External Curing of Cast-in-Place Concrete—Specification

ACI PRC-309-05—Guide for Consolidation of Concrete

ACI PRC-311.4-05—Guide for Concrete Inspection

ACI SPEC-311.6-18—Specification for Ready Mixed Concrete Testing Services

ACI CODE-313-16—Design Specification for Concrete Silos and Stacking Tubes for Storing Granular Materials and Commentary

ACI SPEC-313-16—Design Specification for Concrete Silos and Stacking Tubes for Storing Granular Materials and Commentary

ACI CODE-318-83—Building Code Requirements for Structural Concrete

ACI CODE-318-95—Building Code Requirements for Structural Concrete (ACI 318-95) and Commentary

ACI CODE-318-08—Building Code Requirements for Structural Concrete (ACI 318-08) and Commentary

ACI CODE-318-11—Building Code Requirements for Structural Concrete (ACI 318-11) and Commentary

ACI CODE-318-14—Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary

ACI CODE-318-19—Building Code Requirements for Structural Concrete (ACI 318-19) and Commentary

ACI CODE-318.2-25—Building Code Requirements for Concrete Thin Shells and Commentary

ACI CODE-323-24—Low-Carbon Concrete—Code Requirements and Commentary

ACI PRC-329-14—Report on Performance-Based Requirements for Concrete

ACI CODE-332-20—Code Requirements for Residential Concrete Code and Commentary

ACI PRC-334.1-22—Concrete Shell Structures Guide

ACI PRC-336.2-88(02)—Suggested Analysis and Design Procedures for Combined Footings and Mats

ACI PRC-336.3-(14)—Design and Construction of Drilled Piers

ACI PRC-347-14(21)—Formwork for Concrete—Guide

ACI PRC-347.2-17—Guide for Shoring/Reshoring of Concrete Multistory Buildings

ACI CODE-349-23—Nuclear Safety-Related Concrete Structures—Code Requirements and Commentary

ACI CODE-350-20—Code Requirements for Environmental Engineering Concrete Structures and Commentary

ACI PRC-351.1-12—Report on Grouting Between Foundations and Bases for Support of Equipment and Machinery

ACI SPEC-351.4-24—Cementitious Grout Installation between Foundations and Equipment Bases—Specification

ACI PRC-352-02(10)—Recommendations for Design of Beam-Column Connections in Monolithic Reinforced Concrete Structures

ACI PRC-352.1-11—Guide for Design of Slab-Column Connections in Monolithic Concrete Structures

ACI CODE-355.2-24—Post Installed Mechanical Anchors in Concrete—Qualification Requirements and Commentary

ACI CODE-355.4-24—Post-Installed Adhesive Anchors in Concrete—Qualification Requirements and Commentary

ACI CODE-355.5-24—Post-Installed Reinforcing Bar Systems in Concrete—Qualification Requirements and Commentary

ACI PRC-360-10—Guide to Design of Slabs-on-Ground

ACI PRC-362.1-12(24)—Guide for the Design and Construction of Durable Parking Structures

ACI PRC-363-10—Report on High-Strength Concrete

ACI CODE-369.1-22—Seismic Evaluation and Retrofit of Existing Concrete Buildings—Code and Commentary

ACI PRC-372-13—Guide to Design and Construction of Circular Wire- and Strand-Wrapped Prestressed Concrete Structures

ACI CODE-374.1-05(19)—Acceptance Criteria for Moment Frames Based on Structural Testing and Commentary

ACI PRC-374.3-16—Guide to Nonlinear Modeling Parameters for Earthquake-Resistant Structures

ACI PRC-408-03(12)—Bond and Development of Straight Reinforcing Bars in Tension

ACI PRC-408.2-12—Report on Bond of Steel Reinforcing Bars Under Cyclic Loads

ACI PRC-421.1-20—Guide for Shear Reinforcement for Slabs

ACI PRC-423.3-17—Recommendations for Concrete Members Prestressed with Unbonded Tendons

ACI SPEC-423.7-14—Specification for Unbonded Single-Strand Tendon Materials

ACI PRC-423.10-16—Guide to Estimating Prestress Losses

ACI PRC-435-20—Report on Deflection of Nonprestressed Concrete Structures

ACI PRC-435.5-73(89)—Deflections of Continuous Concrete Beams

ACI PRC-437-19—Strength Evaluation of Existing Concrete Buildings

ACI PRC-437.1-07—Load Tests of Concrete Structures: Methods, Magnitude, Protocols, and Acceptance Criteria

ACI CODE-437.2-22—Load Testing of Existing Concrete Structures—Code and Commentary

ACI PRC-440.1-15—Guide for the Design and Construction of Structural Concrete Reinforced with Fiber-Reinforced Polymer Bars

ACI PRC-440.2-23—Design and Construction of Externally Bonded Fiber-Reinforced Polymer (FRP) Systems for Strengthening Concrete Structures—Guide

ACI CODE-440.11-22—Building Code Requirements for Structural Concrete Reinforced with Glass Fiber-Reinforced Polymer (GFRP) Bars—Code and Commentary

ACI PRC-445-99(15)—Recent Approaches to Shear Design of Structural Concrete

ACI PRC-445.1-12(21)—Report on Torsion in Structural Concrete

ACI PRC-445.2-21—Strut-and-Tie Method Guidelines for ACI 318-19—Guide

ACI PRC-506-(22)—Shotcrete—Guide

ACI SPEC-506.2-(18)—Specification for Shotcrete

ACI PRC-506.4-19—Guide for the Evaluation of Shotcrete

ACI PRC-543-12—Guide to Design, Manufacture, and Installation of Concrete Piles

ACI PRC-544.3-08—Guide for Specifying, Proportioning, and Production of Fiber-Reinforced Concrete

ACI CODE-550.3-13—Design Specification for Unbonded Post-Tensioned Precast Concrete Special Moment Frames Satisfying ACI 374.1 and Commentary

ACI CODE-550.4-18—Qualification of Precast Concrete Diaphragm Connections and Reinforcement at Joints for Earthquake Loading and Commentary

ACI CODE-550.5-18—Code Requirements for the Design of Precast Concrete Diaphragms for Earthquake Motions and Commentary

ACI CODE-550.6-19—Acceptance Criteria for Special Unbonded Post-Tensioned Precast Structural Walls Based on Validation Testing and Commentary

ACI CODE-550.7-19—Requirements for Design of a Special Unbonded Post-Tensioned Precast Shear Wall Satisfying ACI 550.6 and Commentary

ACI PRC-551.2-15—Guide for the Design of Tilt-Up Concrete Panels

ACI PRC-551.3-21—Pitfalls of Deviating from 318 Slender Wall Provisions—TechNote

ACI PRC-555-01—Removal and Reuse of Hardened Concrete

ACI PRC-560-16—Report on Design and Construction with Insulating Concrete Forms (ICFs)

ACI PRC-560-22—Report on Design and Construction with Insulating Concrete Forms Design and Construction (ICFs)—Report

ACI CODE-562-25—Assessment, Repair, and Rehabilitation of Existing Concrete Structures—Code and Commentary

ACI CPP 610.1-18—American Concrete Institute Certification Policies for Concrete Field Testing Technician - Grade I

ACI CPP 620.2-19—American Concrete Institute Certification Policies for Concrete Strength Testing Technician

ACI CPP 630.1-15—American Concrete Institute Certification Policies for Concrete Construction Special Inspector

ACI CPP 660.1-24—American Concrete Institute Certification Policies for Shotcrete and Shotcrete-in-Training

ACI CPP 680.1-20—American Concrete Institute Certification Policies for Adhesive Anchor Installer

ACI CPP 681.1-17—American Concrete Institute Certification Policies for Adhesive Anchor Installation Inspector

ACI CPP 681.2-19—American Concrete Institute Certification Policies for Post-Installed Concrete Anchor Installation Inspector

ACI CT-23—Concrete Terminology

ACI ITG-7-09—Specification for Tolerances for Precast Concrete

ACI ITG-10R-18—Practitioner's Guide for Alternative Cements

ACI ITG-10.1R-18—Report on Alternative Cements

ACI MNL-2(19)—Manual of Concrete Inspection, 11th Edition

ACI MNL-17(21)—ACI Reinforced Concrete Design Handbook

MNL-66(20)—ACI Detailing Manual

SP-4(14)—Formwork for Concrete, Eighth Edition

SP-10 (1965)—Commentary on Building Code Requirements for Reinforced Concrete (ACI 318-63)

SP-17(09)—ACI Design Handbook

American Institute of Steel Construction (AISC)

ANSI/AISC 341-22—ANSI/AISC Seismic Provisions for Structural Steel Buildings

ANSI/AISC 360-22—ANSI/AISC Specification for Structural Steel Buildings

American Iron and Steel Institute (AISI)

AISI D100-17—Cold-Formed Steel Design Manual

AISI S100-16—North American Specification for the Design of Cold-Formed Steel Structural Members

American Society of Civil Engineers (ASCE)

ASCE/SEI 7-05—Minimum Design Loads for Buildings and Other Structures

ASCE/SEI 7-22—Minimum Design Loads and Associated Criteria for Buildings and Other Structures including Supplements 1 and 2

ASCE/SEI 37-14(2019)—Design Loads on Structures During Construction

ASCE/SEI 41-23—Seismic Evaluation and Retrofit of Existing Buildings

ASCE/SEI 49-21—Wind Tunnel Testing for Buildings and Other Structures

ASCE 61-14—Seismic Design of Piers and Wharves

American Society of Mechanical Engineers (ASME)

ASME BPVC III-2—Code for Concrete Containments

ASME B1.1-24—Unified Inch Screw Threads (UN, UNR, and UNJ Thread Forms)

ASME B18.2.1-12(21)—Square and Hex Bolts and Screws, Inch Series

ASME B18.2.6-19—Fasteners for Use in Structural Applications

ASME B31.1-22—Power Piping

ASME B31.3-22—Process Piping

American Welding Society (AWS)

AWS D1.1/D1.1M:2015—Structural Welding Code—Steel

AWS D1.1/D1.1M:2020—Structural Welding Code — Steel

AWS D1.4/D1.4M:2018—Structural Welding Code — Steel Reinforcing Bars

ASTM International

ASTM A36/A36M-19—Standard Specification for Carbon Structural Steel

ASTM A307-21—Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60000 PSI Tensile Strength

ASTM A370-24—Standard Test Methods and Definitions for Mechanical Testing of Steel Products

ASTM A416/A416M-24—Standard Specification for Steel Strand, Uncoated Seven-Wire for Prestressed Concrete

ASTM A421/A421M-21—Standard Specification for Stress-Relieved Steel Wire for Prestressed Concrete

ASTM A615/A615M-24—Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement

ASTM A706/A706M-24—Standard Specification for Deformed and Plain Low-Alloy Steel Bars for Concrete Reinforcement

ASTM A722/A722M-18—Standard Specification for Uncoated High-Strength Steel Bars for Prestressed Concrete

ASTM A767/A767M-19—Standard Specification for Zinc-Coated (Galvanized) Steel Bars for Concrete Reinforcement

ASTM A775/A775M-22—Standard Specification for Epoxy-Coated Steel Reinforcing Bars

ASTM A934/A934M-22—Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars

ASTM A955/A955M-20a—Standard Specification for Deformed and Plain Stainless-Steel Bars for Concrete Reinforcement

ASTM A970/A970M-24—Standard Specification for Headed Steel Bars for Concrete Reinforcement, including Annex A1 Requirements for Class HA Head Dimensions

ASTM A996/A996M-24—Standard Specification for Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement

ASTM A1022/A1022M-22a—Standard Specification for Deformed and Plain Stainless-Steel Wire and Welded Wire for Concrete Reinforcement

ASTM A1035/A1035M-24—Standard Specification for Deformed and Plain, Low-Carbon, Chromium, Steel Bars for Concrete Reinforcement

ASTM A1044/A1044M-22a—Standard Specification for Steel Stud Assemblies for Shear Reinforcement of Concrete

ASTM A1055/A1055M-22—Standard Specification for Zinc and Epoxy Dual-Coated Steel Reinforcing Bars

ASTM A1064/A1064M-24—Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete

ASTM C31/C31M-24b—Standard Practice for Making and Curing Concrete Test Specimens in the Field

ASTM C33/C33M-24—Standard Specification for Concrete Aggregates

ASTM C39/C39M-24—Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens

ASTM C42/C42M-20—Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete

ASTM C94/C94M-24b—Standard Specification for Ready-Mixed Concrete

ASTM C114-24—Standard Test Methods for Chemical Analysis of Hydraulic Cement

ASTM C150/C150M-21—Standard Specification for Portland Cement

ASTM C171-20—Standard Specification for Sheet Materials for Curing Concrete

ASTM C172/C172M-17—Standard Practice for Sampling Freshly Mixed Concrete

ASTM C173/C173M-24—Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method

ASTM C192/C192M-19—Standard Practice for Making and Curing Concrete Test Specimens in the Laboratory

ASTM C231/C231M-24—Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method

ASTM C309-19—Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete

ASTM C330/C330M-23—Standard Specification for Lightweight Aggregates for Structural Concrete

ASTM C457/C457M-24—Standard Test Method for Microscopical Determination of Parameters of the Air-Void System in Hardened Concrete

ASTM C469/C469M-22—Standard Test Method for Static Modulus of Elasticity and Poisson's Ratio of Concrete in Compression

ASTM C494/C494M-24—Standard Specification for Chemical Admixtures for Concrete

ASTM C567/567M-19—Standard Test Method for Determining Density of Structural Lightweight Concrete

ASTM C595/C595M-24—Standard Specification for Blended Hydraulic Cements

ASTM C618-23^{e1}—Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete

ASTM C685/C685M-24—Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing

ASTM C803/803M-23—Standard Test Method for Penetration Resistance of Hardened Concrete

ASTM C805/C805M-18—Standard Test Method for Rebound Number of Hardened Concrete

ASTM C845/C845M-18—Standard Specification for Expansive Hydraulic Cement

ASTM C873/873CM-23—Standard Test Method for Compressive Strength of Concrete Cylinders Cast in Place in Cylindrical Molds

ASTM C900-23—Standard Test Method for Pullout Strength of Hardened Concrete

ASTM C989/C989M-24—Standard Specification for Slag Cement for Use in Concrete and Mortars

ASTM C1012/C1012M-24—Standard Test Method for Length Change of Hydraulic-Cement Mortars Exposed to a Sulfate Solution

ASTM C1017/C1017M-13e1—Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete (Withdrawn 2022)

ASTM C1074-19^{e1}—Standard Practice for Estimating Concrete Strength by the Maturity Method

ASTM C1077-24—Standard Practice for Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation

ASTM C1140/C1140M-11(2019)—Standard Practice for Preparing and Testing Specimens from Shotcrete Test Panels

ASTM C1152/C1152M-20—Standard Test Method for Acid-Soluble Chloride in Mortar and Concrete

ASTM C1157/C1157M-23—Standard Performance Specification for Hydraulic Cement

ASTM C1202-22^{e1}—Standard Test Method for Electrical Indication of Concrete's Ability to Resist Chloride Ion Penetration

ASTM C1218/C1218M-20—Standard Test Method for Water-Soluble Chloride in Mortar and Concrete

ASTM C1240-20—Standard Specification for Silica Fume Used in Cementitious Mixtures

ASTM C1293/C1293M-23a—Standard Test Method for Determination of Length Change of Concrete Due to Alkali-Silica Reaction

ASTM C1315-19—Standard Specification for Liquid Membrane-Forming Compounds Having Special Properties for Curing and Sealing Concrete

ASTM C1602/C1602M-22—Standard Specification for Mixing Water Used in Production of Hydraulic Cement Concrete

ASTM C1604/C1604M-05(2019)—Standard Test Method for Obtaining and Testing Drilled Cores of Shotcrete

ASTM C1609/C1609M-24—Standard Test Method for Flexural Performance of Fiber-Reinforced Concrete (Using Beam With Third-Point Loading)

ASTM C1761/C1761M-23—Standard Specification for Lightweight Aggregate for Internal Curing of Concrete

ASTM C1778-23—Standard Guide for Reducing the Risk of Deleterious Alkali-Aggregate Reaction in Concrete

ASTM C1797-17—Standard Specification for Ground Calcium Carbonate and Aggregate Mineral Fillers for use in Hydraulic Cement Concrete

ASTM C1866/C1866M-20—Standard Specification for Ground-Glass Pozzolan for Use in Concrete

ASTM D3665-12(2017)—Standard Practice for Random Sampling of Construction Materials

ASTM E8/E8M-24—Standard Test Methods for Tension Testing of Metallic Materials

ASTM E9-19—Standard Test Methods of Compression Testing of Metallic Materials at Room Temperature

ASTM F1554-20—Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength

ASTM E2921-22—Standard Practice for Minimum Criteria for Comparing Whole Building Life Cycle Assessments for Use with Building Codes and Rating Systems

Federal Emergency Management Agency (FEMA)

FEMA P-749-22—Earthquake-Resistant Design Concepts: An Introduction to the Seismic Provisions for New Buildings and Other Structures

FEMA P-750-09—NEHRP Recommended Seismic Provisions for New Buildings and Other Structures (2009 edition)

FEMA P-751-12—NEHRP Recommended Seismic Provisions: Design Examples (2009 edition)

International Code Council (ICC)

2021 IBC—International Building Code

2024 IBC—International Building Code

ICC-ES AC133-20—Acceptance Criteria for Mechanical Splice Systems for Steel Reinforcing Bars

ICC-ES AC193-17(24)—Acceptance Criteria for Mechanical Anchors in Concrete Elements

ICC-ES AC303-11—Acceptance Criteria for Post-Tensioning Anchorages and Couplers of Prestressed Concrete

International Concrete Repair Institute (ICRI)

ICRI 310.2R-2013—Selecting and Specifying Concrete Surface Preparation for Sealers, Coatings, Polymer Overlays, and Concrete Repair

International Organization for Standardization (ISO)

ISO 14040:2006—Environmental Management—Life Cycle Assessment: Principles and Framework

ISO 14040:2020—Environmental Management—Life Cycle Assessment: Principles and Framework AMENDMENT 1

ISO 14044:2006—Environmental Management—Life Cycle Assessment: Requirements and Guidelines

ISO 21930:2017—Sustainability in Buildings and Civil Engineering Works—Core Rules for Environmental Product Declarations of Construction Products and Services

National Fire Protection Association (NFPA)

NFPA 5000-2024—Building Construction Safety Code

National Institute of Standards and Technology (NIST)

NISTGCR 17-917-46—Guidelines for Nonlinear Structural Analysis for Design of Buildings

NSF International

Product Category Rule (PCR) for Concrete (2021 edition)

Portland Cement Association (PCA)

PCA EB001.15-21—Design and Control of Concrete Mixtures, 17th edition

PCA EB001.17-21—Design and Control of Concrete Mixtures, 17th edition

Precast/Prestressed Concrete Institute (PCI)

PCI MNL 116-21—Manual for Quality Control for Plants and Production of Structural Precast Concrete Products

PCI MNL 117-13—Manual for Quality Control for Plants and Production of Architectural Precast Concrete Products

PCI MNL 120-17—Design Handbook: Precast and Prestressed Concrete, Eighth Edition

PCI MNL 123-88—Design and Typical Details of Connections for Precast and Prestressed Concrete

PCI MNL 126-15—PCI Manual for the Design of Hollow Core Slabs and Walls

Post-Tensioning Institute (PTI)

PTI/ASBI M50.3-19—Specification for Multistrand and Grouted Post-Tensioning

PTI C30.4-21—Training and Certification of Field Personnel for Bonded Post-Tensioning

PTI DC10.5-19—Standard Requirements for Design and Analysis of Shallow Post-Tensioned Concrete Foundations of Expansive and Stable Soils

PTI DC20.8-04—Design of Post-Tensioned Slabs Using Unbonded Tendons

PTI M10.2-17—Specifications for Unbonded Single Strand Tendons

PTI M10.3-16—Field Procedures Manual for Unbonded Single Strand Tendons

PTIM50.3-19—Specification for Multistrand and Grouted Post-Tensioning

PTI M55.1-19—Specification for Grouting of Post-Tensioned Structures

PTITAB.1-23—Post-Tensioning Manual, Seventh Edition

Standards New Zealand

NZS 3101-2006—Concrete Structure Standard, Part 1: The Design of Concrete Structures (NZS3101.1): Part 2: Commentary on the Design of Concrete Structures (NZS3101.2)

Steel Deck Institute (SDI)

SD-2022—ANSI/SDI Standard for Steel Deck

Authored documents

Aaleti, S.; Brueggen, B. L.; Johnson, B.; French, C. E.; and Sritharan, S., 2013, “Cyclic Response of Reinforced Concrete Walls with Different Anchorage Details: Experimental Investigation,” *Journal of Structural Engineering*, V. 139, No. 7, July, pp. 1181-1191. doi: [10.1061/\(ASCE\)ST.1943-541X.0000732](https://doi.org/10.1061/(ASCE)ST.1943-541X.0000732)

Abdullah, S. A., and Wallace, J. W., 2019, “Drift Capacity of Reinforced Concrete Structural Walls with Special Boundary Elements,” *ACI Structural Journal*, V. 116, No. 1, Jan., pp. 183-194. doi: [10.14359/51710864](https://doi.org/10.14359/51710864)

Abdullah, S. A., and Wallace, J. W., 2020, “A Reliability-Based Design Methodology for Reinforced Concrete Structural Walls with Special Boundary Elements,” *ACI Structural Journal*, V. 117, No. 3, May, pp. 17-29. doi: [10.14359/51721375](https://doi.org/10.14359/51721375)

Abdullah, S. A., and Wallace, J. W., 2021, “Review of Tests on Reinforced Concrete Coupling Beams with Web Penetrations,” *Proceedings of 2021 Structural Engineers Association of California*, San Diego, CA.

Abdullah, S. A.; Aswegan, K.; Jaberansari, S.; Klemencic, R.; and Wallace, J. W., 2020, “Performance of Reinforced Coupling Beams Subjected to Simulated Wind Loading,” *ACI Structural Journal*, V. 117, No. 3, May-June, pp. 283-295. doi: [10.14359/51724555](https://doi.org/10.14359/51724555)

Abdullah, S.; Aswegan, K.; Klemencic, R.; and Wallace, W., 2021, “Performance of Concrete Coupling Beams Subjected to Simulated Wind Loading—Phase II,” *ACI Structural Journal*, V. 118, No. 3, Mar., pp. 101-116. doi: [10.14359/51729356](https://doi.org/10.14359/51729356)

Abdullah, S.; Aswegan, K.; Klemencic, R.; and Wallace, W., 2022, “Recommendations for Modeling Concrete Coupling Beams Using Performance-Based Wind Design,” UCLA SEERL 2022/01, Technical Report Submitted to Magnusson Klemencic Associates (MKA) Foundation, University of California, Los Angeles, CA.

Abdullah, S. A.; Rafiq, S. K.; Fields, D.; and Wallace, J. W., 2023, “Seismic Performance of Diagonally Reinforced Concrete Coupling Beams with Penetrations,” *ACI*

Structural Journal, V. 120, No. 1, Jan., pp. 317-331. doi: [10.14359/51736118](https://doi.org/10.14359/51736118)

Abrahams, L.; Van Pay, L.; Sattar, S.; Johnson, K.; McKittrick, A.; Bartels, L.; Butcher, L. M.; Rubinyi, L.; Mahoney, M.; Heintz, J.; Kersting, R.; and McCabe, S., 2021, “NIST-FEMA Post-Earthquake Functional Recovery Workshop Report,” *NIST Special Publication 1269*, National Institute of Standards and Technology, Gaithersburg, MD, 52 pp. doi: [10.6028/NIST.SP.1269](https://doi.org/10.6028/NIST.SP.1269)

ACI Committee 318, 1965, “Commentary on Building Code Requirements for Reinforced Concrete (ACI 318-63),” SP-10, American Concrete Institute, Farmington Hills, MI, pp. 78-84.

ACI Committee 318, 1999, “Closure to Public Comments on ACI 318-99,” *Concrete International*, V. 21, No. 5, May, pp. 318-1 to 318-50. doi: [10.14359/19333](https://doi.org/10.14359/19333)

ACI Committee 408, 1966, “Bond Stress—The State of the Art,” *ACI Journal Proceedings*, V. 63, No. 11, Nov., pp. 1161-1188. doi: [10.14359/7665](https://doi.org/10.14359/7665)

ACI Committee 435, 1963, “Deflections of Prestressed Concrete Members (ACI 435.1R-63),” *ACI Journal Proceedings*, V. 60, No. 12, Dec., pp. 1697-1728. doi: [10.14359/19413](https://doi.org/10.14359/19413)

ACI Committee 435, 1966, “Deflections of Reinforced Concrete Flexural Members (ACI 435.2R-66),” *ACI Journal Proceedings*, V. 63, No. 6, June, pp. 637-674. doi: [10.14359/7643](https://doi.org/10.14359/7643)

ACI Committee 435, 1968, “Allowable Deflections (ACI 435.3R-68),” *ACI Journal Proceedings*, V. 65, No. 6, June, pp. 433-444. doi: [10.14359/7482](https://doi.org/10.14359/7482)

ACI Committee 435, 1978, “Proposed Revisions by Committee 435 to ACI Building Code and Commentary Provisions on Deflections,” *ACI Journal Proceedings*, V. 75, No. 6, June, pp. 229-238. doi: [10.14359/10935](https://doi.org/10.14359/10935)

Adebar, P.; Kuchma, D.; and Collins, M. P., 1990, “Strut-and-Tie Models for the Design of Pile Caps: An Experimental Study,” *ACI Structural Journal*, V. 87, No. 1, Jan.-Feb., pp. 81-92. doi: [10.14359/2945](https://doi.org/10.14359/2945)

Ajaam, A.; Yasso, S.; Darwin, D.; O'Reilly, M.; and Sperry, J., 2018, “Anchorage Strength of Closely Spaced Hooked Bars,” *ACI Structural Journal*, V. 115, No. 4, July, pp. 1143-1152. doi: [10.14359/51702065](https://doi.org/10.14359/51702065)

Al-Sabawy, A.; Lequesne, R. D.; O'Reilly, M.; Darwin, D.; and Lepage, A., 2020, “Headed and High-Strength Shear Reinforcement in Concrete Members,” *SM Report No. 139*, University of Kansas Center for Research, Inc., Lawrence, KS, May, 498 pp. hdl.handle.net/1808/30355

ASCE, 2023, “Prestandard for Performance-Based Wind Design,” American Society of Civil Engineers, Reston, VA, 127 pp.

Anderson, A. R., 1978, “Shear Strength of Hollow Core Members,” *Technical Bulletin 78-81*, Concrete Technology Associates, Tacoma, WA, Apr., 33 pp. doi: [10.14359/19270](https://doi.org/10.14359/19270)

Anderson, N. S., and Meinhart, D. F., 2005, “Pryout Capacity of Cast-In Headed Stud Anchors,” *PCI Journal*,

- V. 50, No. 2, Mar.-Apr., pp. 90-112. doi: [10.15554/pci.03012005.90.112](https://doi.org/10.15554/pci.03012005.90.112)
- Anderson, N. S., and Meinheit, D. F., 2007, "A Review of Headed Stud-Design Criteria," *PCI Journal*, V. 52, No. 1, Jan.-Feb., pp. 82-100. doi: [10.15554/pci.01012007.82.100](https://doi.org/10.15554/pci.01012007.82.100)
- Anderson, N. S., and Ramirez, J. A., 1989, "Detailing of Stirrup Reinforcement," *ACI Structural Journal*, V. 86, No. 5, Sept.-Oct., pp. 507-515. doi: [10.14359/3005](https://doi.org/10.14359/3005)
- Angelakos, D.; Bentz, E. C.; and Collins, M. D., 2001, "Effect of Concrete Strength and Minimum Stirrups on Shear Strength of Large Members," *ACI Structural Journal*, V. 98, No. 3, May-June, pp. 290-300. doi: [10.14359/10220](https://doi.org/10.14359/10220)
- Aoyama, H., ed., 2001, *Design of Modern Highrise Reinforced Concrete Structures*, Imperial College Press, London, UK, 442 pp.
- Applied Technology Council, 1978, "ATC 3-06: Tentative Provisions for the Development of Seismic Regulations for Buildings"
- Applied Technology Council, 1999, "ATC Design Guide 1: Minimizing Floor Vibration," Redwood City, CA, 64 pp.
- Arteta, C. A., 2015, "Seismic Response Assessment of Thin Boundary Element Specimens of Special Concrete Shear Walls," PhD dissertation, University of California, Berkeley, Berkeley, CA, 240 pp.
- ASCE Joint Committee, 1940, "Recommended Practice and Standard Specification for Concrete and Reinforced Concrete," Proceedings, ASCE, V. 66, No. 6, Part 2, June, 81 pp.
- Asmus, J., 1999, "Verhalten von Befestigungen bei der Versagensart Spalten des Betons (Behavior of Fastenings with the Failure Mode Splitting of Concrete)," dissertation, Universität Stuttgart, Stuttgart, Germany.
- Aswad, A., and Jacques, F. J., 1992, "Behavior of Hollow-Core Slabs Subject to Edge Loads," *PCI Journal*, V. 37, No. 2, Mar.-Apr., pp. 72-86. doi: [10.15554/pci.03011992.72.84](https://doi.org/10.15554/pci.03011992.72.84)
- Athena Sustainable Materials Institute, 2022, "A Cradle-to-Gate Life Cycle Assessment of Ready-Mixed Concrete Manufactured by NRMCA Members – Version 3.2 – Appendix C," National Ready Mixed Concrete Association, Alexandria, VA, July, 94 pp.
- Athey, J. W., ed., 1982, "Test Report on Slender Walls," Southern California Chapter of the American Concrete Institute and Structural Engineers Association of Southern California, Los Angeles, CA, 129 pp.
- Azizinamini, A.; Chisala, M.; and Ghosh, S. K., 1995, "Tension Development Length of Reinforcing Bars Embedded in High-Strength Concrete," *Engineering Structures*, V. 17, No. 7, pp. 512-522. doi: [10.1016/0141-0296\(95\)00096-P](https://doi.org/10.1016/0141-0296(95)00096-P)
- Azizinamini, A.; Darwin, D.; Eligehausen, R.; Pavel, R.; and Ghosh, S. K., 1999b, "Proposed Modifications to ACI 318-95 Development and Splice Provisions for High-Strength Concrete," *ACI Structural Journal*, V. 96, No. 6, Nov.-Dec., pp. 922-926. doi: [10.14359/766](https://doi.org/10.14359/766)
- Azizinamini, A.; Pavel, R.; Hatfield, E.; and Ghosh, S. K., 1999a, "Behavior of Spliced Reinforcing Bars Embedded in High-Strength Concrete," *ACI Structural Journal*, V. 96, No. 5, Sept.-Oct., pp. 826-835. doi: [10.14359/737](https://doi.org/10.14359/737)
- Banaeipour, A.; Darwin, D.; O'Reilly, M.; Lequesne, R. D.; Lepage, A.; and Blessent, M., 2023, "Development of Large High-Strength Reinforcing Bars with Standard Hooks and Heads," *SM Report No. 153*, University of Kansas Center for Research, Inc., Lawrence, KS, July, 392 pp.
- Barda, F.; Hanson, J. M.; and Corley, W. G., 1977, "Shear Strength of Low-Rise Walls with Boundary Elements," *Reinforced Concrete Structures in Seismic Zones*, SP-53, American Concrete Institute, Farmington Hills, MI, pp. 149-202. doi: [10.14359/17697](https://doi.org/10.14359/17697)
- Barney, G. B.; Corley, W. G.; Hanson, J. M.; and Parmelee, R. A., 1977, "Behavior and Design of Prestressed Concrete Beams with Large Web Openings," *PCI Journal*, V. 22, No. 6, Nov.-Dec., pp. 32-61. doi: [10.15554/pci.11011977.32.61](https://doi.org/10.15554/pci.11011977.32.61)
- Barney, G. B.; Shiu, K. N.; Rabbat, B. G.; Fiorato, A. E.; Russell, H. G.; and Corley, W. G., 1980, "Behavior of Coupling Beams under Load Reversals (RD068.01B)," Portland Cement Association, Skokie, IL. doi: [10.14359/51685458](https://doi.org/10.14359/51685458)
- Bartlett, F. M., 2012, "Using Historical Cylinder Data for Structural Evaluation," *Andy Scanlon Symposium on Serviceability and Safety of Concrete Structures: From Research to Practice*, SP-284, P. H. Bischoff, E. Musselman, S. Gross, and H. Nassif, eds., American Concrete Institute, Farmington Hills, MI, 12 pp. doi: [10.14359/51683800](https://doi.org/10.14359/51683800)
- Bartlett, M. F., and MacGregor, J. G., 1994, "Effect of Moisture Condition on Concrete Core Strengths," *ACI Materials Journal*, V. 91, No. 3, May-June, pp. 227-236. doi: [10.14359/4328](https://doi.org/10.14359/4328)
- Bartoletti, S. J., and Jirsa, J. O., 1995, "Effects of Epoxy Coating on Anchorage and Development of Welded Wire Fabric," *ACI Structural Journal*, V. 92, No. 6, Nov.-Dec., pp. 757-764. doi: [10.14359/9669](https://doi.org/10.14359/9669)
- Base, G. D.; Reed, J. B.; Beeby, A. W.; and Taylor, H. P. J., 1966, "An Investigation of the Crack Control Characteristics of Various Types of Bar in Reinforced Concrete Beams," *Research Report No. 18*, Cement and Concrete Association, London, UK, Dec., 44 pp. doi: [10.14359/51685142](https://doi.org/10.14359/51685142)
- Bayer, C.; Gamble, M.; Gentry, R.; and Joshi, S., 2010, *AIA Guide to Building Life Cycle Assessment in Practice*, The American Institute of Architects, Washington, DC, 193 pp.
- Bazant, Z. P.; Yu, Q.; Gerstle, W.; Hanson, J.; and Ju, J., 2007, "Justification of ACI 446 Code Provisions for Shear Design of Reinforced Concrete Beams," *ACI Structural Journal*, V. 104, No. 5, Sept.-Oct., pp. 601-610. doi: [10.14359/18862](https://doi.org/10.14359/18862)
- Becker, R. J., and Buettner, D. R., 1985, "Shear Tests of Extruded Hollow Core Slabs," *PCI Journal*, V. 30, No. 2, Mar.-Apr., pp. 40-54. doi: [10.15554/pci.03011985.40.54](https://doi.org/10.15554/pci.03011985.40.54)
- Becker, R. J.; Holland, T. C.; and Malits, F. S., 2019, "Structural Concrete Using Alternative Cements," *Concrete International*, V. 41, No. 6, June, pp. 39-44. doi: [10.14359/51716910](https://doi.org/10.14359/51716910)

Beeby, A. W., 1979, "The Prediction of Crack Widths in Hardened Concrete," *The Structural Engineer*, V. 57A, No. 1, Jan., pp. 9-17. doi: [10.14359/51685143](https://doi.org/10.14359/51685143)

Behera, U., and Rajagopalan, K. S., 1969, "Two-Piece U-Stirrups in Reinforced Concrete Beams," *ACI Journal Proceedings*, V. 66, No. 7, July, pp. 522-524. doi: [10.14359/51685214](https://doi.org/10.14359/51685214)

Bertrand, J., and Vezina, D., 1994, "The Development of Air Entrained Durable Shotcrete for Structural Repairs," *Proceedings of Shotcrete for Underground Support VII*, pp. 58-65.

Bezerra Cabral, A. E.; Schalch, V.; Dal Molin, D. C. C.; and Ribeiro, J. L. D., 2010, "Mechanical Properties Modeling of Recycled Aggregate Concrete," *Construction and Building Materials*, V. 24, No. 4, Apr., pp. 421-430. doi: [10.1016/j.conbuildmat.2009.10.011](https://doi.org/10.1016/j.conbuildmat.2009.10.011)

Bianchini, A. C.; Woods, R. E.; and Kesler, C. E., 1960, "Effect of Floor Concrete Strength on Column Strength," *ACI Journal Proceedings*, V. 56, No. 11, May, pp. 1149-1169. doi: [10.14359/8135](https://doi.org/10.14359/8135)

Birely, A. C.; Lowes, L. N.; and Lehman, D. E., 2012, "Linear Analysis of Concrete Frames Considering Joint Flexibility," *ACI Structural Journal*, V. 109, No. 3, May-June, pp. 381-391. doi: [10.14359/51683752](https://doi.org/10.14359/51683752)

Birkeland, P. W., and Birkeland, H. W., 1966, "Connections in Precast Concrete Construction," *ACI Journal Proceedings*, V. 63, No. 3, Mar., pp. 345-368. doi: [10.14359/7627](https://doi.org/10.14359/7627)

Bischoff, P. H., 2005, "Revaluation of Deflection Prediction for Concrete Beams Reinforced with Steel and Fiber Reinforced Polymer Bars," *Journal of Structural Engineering*, V. 131, No. 5, May, pp. 752-767. doi: [10.1061/\(ASCE\)0733-9445\(2005\)131:5\(752\)](https://doi.org/10.1061/(ASCE)0733-9445(2005)131:5(752))

Bischoff, P. H., and Scanlon, A., 2007, "Effective Moment of Inertia for Calculating Deflections of Concrete Members Containing Steel Reinforcement and Fiber-Reinforced Polymer Reinforcement," *ACI Structural Journal*, V. 104, No. 1, Jan.-Feb., pp. 68-75. doi: [10.14359/18434](https://doi.org/10.14359/18434)

Black, W. C., 1973, "Field Corrections to Partially Embedded Reinforcing Bars," *ACI Journal Proceedings*, V. 70, No. 10, Oct., pp. 690-691. doi: [10.14359/51684023](https://doi.org/10.14359/51684023)

Bloem, D. L., 1965, "Concrete Strength Measurement—Cores vs. Cylinders," *Proceedings, ASTM*, V. 65, pp. 668-696.

Bloem, D. L., 1968, "Concrete Strength in Structures," *ACI Journal Proceedings*, V. 65, No. 3, Mar., pp. 176-187. doi: [10.14359/7465](https://doi.org/10.14359/7465)

Blume, J. A.; Newmark, N. M.; and Corning, L. H., 1961, *Design of Multistory Reinforced Concrete Buildings for Earthquake Motions*, Portland Cement Association, Skokie, IL, 318 pp. doi: [10.14359/16796](https://doi.org/10.14359/16796)

BOCA, 1999, "BOCA National Building Code," 13th edition, Building Officials and Code Administration International, Inc., Country Club Hills, IL.

Bondy, K. B., 2003, "Moment Redistribution: Principles and Practice Using ACI 318-02," *PTI Journal*, V. 1, No. 1, Jan., pp. 3-21. doi: [10.14359/19230](https://doi.org/10.14359/19230)

Bowick, M.; O'Connor, J.; and Meil, J., 2014, "Athena Guide to Whole-Building LCA in Green Building Programs," Athena Sustainable Materials Institute, Ottawa, ON, Canada, 41 pp.

Branson, D. E., 1965, "Instantaneous and Time-Dependent Deflections on Simple and Continuous Reinforced Concrete Beams," *HPR Report No. 7, Part 1*, Alabama Highway Department, Bureau of Public Roads, Aug., pp. 1-78.

Branson, D. E., 1970, discussion of "Proposed Revision of ACI 318-63: Building Code Requirements for Reinforced Concrete," *ACI Journal Proceedings*, V. 67, No. 9, Sept., pp. 692-695.

Branson, D. E., 1971, "Compression Steel Effect on Long-Time Deflections," *ACI Journal Proceedings*, V. 68, No. 8, Aug., pp. 555-559. doi: [10.14359/16519](https://doi.org/10.14359/16519)

Branson, D. E., 1977, *Deformation of Concrete Structures*, McGraw-Hill Book Co., New York, 546 pp.

Branson, D. E.; Meyers, B. L.; and Kripanarayanan, K. M., 1970, "Time-Dependent Deformation of Noncomposite and Composite Prestressed Concrete Structures," Symposium on Concrete Deformation, Highway Research Record 324, Highway Research Board, pp. 15-43. doi: [10.14359/19393](https://doi.org/10.14359/19393)

Breen, J. E.; Burdet, O.; Roberts, C.; Sanders, D.; Wollmann, G.; and Falconer, B., 1994, "Anchorage Zone Requirements for Post-Tensioned Concrete Girders," *NCHRP Report 356*, Transportation Research Board, National Academy Press, Washington, DC. doi: [10.14359/19236](https://doi.org/10.14359/19236)

Briss, G. R.; Paulay, T.; and Park, R., 1978, "Elastic Behavior of Earthquake Resistant R. C. Interior Beam-Column Joints," *Report 78-13*, University of Canterbury, Department of Civil Engineering, Christchurch, New Zealand, Feb. doi: [10.14359/19340](https://doi.org/10.14359/19340)

Broms, C. E., 1990, "Shear Reinforcement for Deflection Ductility of Flat Plates," *ACI Structural Journal*, V. 87, No. 6, Nov.-Dec., pp. 696-705. doi: [10.14359/2988](https://doi.org/10.14359/2988)

Brown, M. D.; Bayrak, O.; and Jirsa, J. O., 2006, "Design for Shear Based on Loading Conditions," *ACI Structural Journal*, V. 103, No. 4, July-Aug., pp. 541-550. doi: [10.14359/16430](https://doi.org/10.14359/16430)

Budek, A.; Priestley, M.; and Lee, C., 2002, "Seismic Design of Columns with High-Strength Wire and Strand as Spiral Reinforcement," *ACI Structural Journal*, V. 99, No. 5, Sept.-Oct., pp. 660-670. doi: [10.14359/12306](https://doi.org/10.14359/12306)

Burns, N. H., and Hemakom, R., 1977, "Test of Scale Model Post-Tensioned Flat Plate," *Journal of the Structural Division*, V. 103, June, pp. 1237-1255. doi: [10.14359/16870](https://doi.org/10.14359/16870)

Canbay, E., and Frosch, R. J., 2005, "Bond Strength of Lap-Spliced Bars," *ACI Structural Journal*, V. 102, No. 4, July-Aug., pp. 605-614. doi: [10.14359/14565](https://doi.org/10.14359/14565)

Carino, N. J.; Guthrie, W. F.; Lagergren, E. S.; and Mullings, G. M., 1994, "Effects of Testing Variables on the Strength of High-Strength (90 MPa) Concrete Cylinders,"

- High-Performance Concrete*, SP-149, V. M. Malhotra, ed., American Concrete Institute, Farmington Hills, MI, pp. 589-632. doi: [10.14359/4176](https://doi.org/10.14359/4176)
- Carter, J. W. III; Hawkins, N. M.; and Wood, S. L., 1993, "Seismic Response of Tilt-Up Construction," SRS No. 581, Civil Engineering Series, University of Illinois, Urbana, IL, Dec., 224 pp. doi: [10.14359/19661](https://doi.org/10.14359/19661)
- Castro, A.; Kreger, M.; Bayrak, O.; Breen, J. E.; and Wood, S. L., 2004, "Allowable Design Release Stresses for Pretensioned Concrete Beams," Report No. FHWA/TX-04/0-4086-2, Center for Transportation Research, University of Texas at Austin, Austin, TX, Aug., 127 pp.
- CEB, 1994, "Fastenings to Concrete and Masonry Structures, State of the Art Report," Comité Euro-International du Béton (CEB), Bulletin No. 216, Thomas Telford Services Ltd., London, UK, 249 pp.
- CEB, 1997, Design of Fastenings in Concrete, Comité Euro-International du Béton (CEB), Thomas Telford Services Ltd., London, UK, Jan.
- Center for the Built Environment (CBE), 2024, "CBE Thermal Comfort Tool," <https://cbe.berkeley.edu/research/cbe-thermal-comfort-tool/>, accessed August 12, 2024.
- Chen, L.; Mindess, S.; Morgan, D. R.; Shah, S. P.; Johnston, C. D.; and Pigeon, M., 1995, "Comparative Toughness Testing of Fiber Reinforced Concrete," *Testing of Fiber Reinforced Concrete*, SP-155, American Concrete Institute, Farmington Hills, MI, pp. 41-69. doi: [10.14359/928](https://doi.org/10.14359/928)
- Cheng, M. Y.; Hung, S. C.; Lequesne, R. D.; and Lepage, A., 2016, "Earthquake-Resistant Squat Walls Reinforced with High-Strength Steel," *ACI Structural Journal*, V. 113, No. 5, Sept.-Oct., pp. 1065-1076. doi: [10.14359/51688825](https://doi.org/10.14359/51688825)
- Chesson, E.; Faustino, N. L.; and Munse, W. H., 1965, "High-Strength Bolts Subjected to Tension and Shear," *Journal of the Structural Division*, V. 91, Oct., pp. 155-180. doi: [10.1061/JSDEAG.0001327](https://doi.org/10.1061/JSDEAG.0001327)
- Chicchi, R.; Varma, A. H.; Seo, J.; Bradt, T.; and McCarty, E., 2020, "Experimental Testing of Tension-Loaded Deformed Anchors in Concrete," *ACI Structural Journal*, V. 117, No. 5, Sept., pp. 133-146. doi: [10.14359/51724670](https://doi.org/10.14359/51724670)
- Chow, L.; Conway, H.; and Winter, G., 1953, "Stresses in Deep Beams," *Transactions of the American Society of Civil Engineers*, V. 118, pp. 686-708. doi: [10.14359/19672](https://doi.org/10.14359/19672)
- Climate Central, <https://coastal.climatecentral.org/>
- Clough, R. W., 1960, "Dynamic Effects of Earthquakes," *Journal of the Structural Division*, V. 86, Apr., pp. 49-65. doi: [10.14359/19323](https://doi.org/10.14359/19323)
- Cohn, M. A., 1965, "Rotational Compatibility in the Limit Design of Reinforced Concrete Continuous Beams," *Flexural Mechanics of Reinforced Concrete*, SP-12, American Concrete Institute/American Society of Civil Engineers, Farmington Hills, MI, pp. 35-46. doi: [10.14359/16724](https://doi.org/10.14359/16724)
- Coffin, L. F., 1954, "A Study of the Effects of Cyclic Thermal Stresses on a Ductile Metal," *Transactions of ASME*, V. 76, No. 6, pp. 931-949. doi: [10.1115/1.4015020](https://doi.org/10.1115/1.4015020)
- Collins, M. P., and Lampert, P., 1973, "Redistribution of Moments at Cracking—The Key to Simpler Torsion Design?" *Analysis of Structural Systems for Torsion*, SP-35, American Concrete Institute, Farmington Hills, MI, pp. 343-383. doi: [10.14359/17486](https://doi.org/10.14359/17486)
- Collins, M. P., and Mitchell, D., 1991, *Prestressed Concrete Structures*, Prentice Hall Inc., Englewood Cliffs, NJ, 766 pp.
- Collins, M. P., and Mitchell, D., 1997, *Prestressed Concrete Structures*, Response Publications, Canada, pp. 517-518. doi: [10.14359/19232](https://doi.org/10.14359/19232)
- Column Research Council, 1966, "Guide to Design Criteria for Metal Compression Members," second edition, Fritz Engineering Laboratory, Lehigh University, Bethlehem, PA, 117 pp. doi: [10.14359/19273](https://doi.org/10.14359/19273)
- Cook, R. A., and Klingner, R. E., 1992a, "Behavior of Ductile Multiple-Anchor Steel-to-Concrete Connections with Surface-Mounted Baseplates," *Anchors in Concrete: Design and Behavior*, SP-130, G. A. Senkiw and H. B. Lancelot III, eds., American Concrete Institute, Farmington Hills, MI, pp. 61-122. doi: [10.14359/1268](https://doi.org/10.14359/1268)
- Cook, R. A., and Klingner, R. E., 1992b, "Ductile Multiple-Anchor Steel-to-Concrete Connections," *Journal of Structural Engineering*, V. 118, No. 6, June, pp. 1645-1665. doi: [10.1061/\(ASCE\)0733-9445\(1992\)118:6\(1645\)](https://doi.org/10.1061/(ASCE)0733-9445(1992)118:6(1645))
- Cook, R. A.; Kunz, J.; Fuchs, W.; and Konz, R. C., 1998, "Behavior and Design of Single Adhesive Anchors under Tensile Load in Uncracked Concrete," *ACI Structural Journal*, V. 95, No. 1, Jan.-Feb., pp. 9-26. doi: [10.14359/522](https://doi.org/10.14359/522)
- Cook, R. A., and Michler, H., 2017, "Behavior and Design of Anchorages with Shear Lugs," 3rd International Symposium on Connections between Steel and Concrete, Stuttgart, Germany, pp. 560-570.
- Corley, W. G., and Jirsa, J. O., 1970, "Equivalent Frame Analysis for Slab Design," *ACI Journal Proceedings*, V. 67, No. 11, Nov., pp. 875-884. doi: [10.14359/7317](https://doi.org/10.14359/7317)
- Corley, W. G.; Sozen, M. A.; and Siess, C. P., 1961, "Equivalent-Frame Analysis for Reinforced Concrete Slabs," *Structural Research Series* No. 218, Civil Engineering Studies, University of Illinois, June, 166 pp. doi: [10.14359/16677](https://doi.org/10.14359/16677)
- Crist, R. A., 1966, "Shear Behavior of Deep Reinforced Concrete Beams," *Proceedings, Symposium on the Effects of Repeated Loading of Materials and Structural Elements (Mexico City)*, V. 4, RILEM, Paris, France, 31 pp.
- CRSI Handbook, 1984, sixth edition, Concrete Reinforcing Steel Institute, Schaumburg, IL.
- Dam, T. X.; Wight, J. K.; and Parra-Montesinos, G. J., 2017, "Behavior of Monotonically Loaded Slab-Column Connections Reinforced with Shear Studs," *ACI Structural Journal*, V. 114, No. 1, Jan.-Feb., pp. 221-232. doi: [10.14359/51689165](https://doi.org/10.14359/51689165)
- Data.gov, <http://www.data.gov/climate/coastalflooding/coastalflooding-tools> (accessed August 12, 2024)

Darwin, D.; Manning, D. G.; and Hognestad, E., 1985, "Debate: Crack Width, Cover, and Corrosion," *Concrete International*, V. 7, No. 5, May, pp. 20-35. doi: [10.14359/16539](https://doi.org/10.14359/16539)

Darwin, D.; Zuo, J.; Tholen, M. L.; and Idun, E. K., 1996, "Development Length Criteria for Conventional and High Relative Rib Area Reinforcing Bars," *ACI Structural Journal*, V. 93, No. 3, May-June, pp. 347-359. doi: [10.14359/9694](https://doi.org/10.14359/9694)

Day, R. L., 1994, "Strength Measurement of Concrete Using Different Cylinder Sizes: A Statistical Analysis," *Cement, Concrete, and Aggregates*, V. 16, No. 1, June, pp. 21-30. doi: [10.1520/CCA10557J](https://doi.org/10.1520/CCA10557J)

Deatherage, J. H.; Burdette, E. G.; and Chew, C. K., 1994, "Development Length and Lateral Spacing Requirements of Prestressing Strand for Prestressed Concrete Bridge Girders," *PCI Journal*, V. 39, No. 1, Jan.-Feb., pp. 70-83. doi: [10.15554/pcij.01011994.70.83](https://doi.org/10.15554/pcij.01011994.70.83)

Department of Health and Human Services (DHS), Centers for Disease Control and Prevention (CDC), and National Institute for Occupational Safety and Health (NIOSH), 2016, "Criteria for a Recommended Standard: Occupational Exposure to Heat and Hot Environments," 192 pp., <https://www.cdc.gov/niosh/docs/2016-106/pdfs/2016-106.pdf>

Detwiler, R. J.; Swor, T. E.; and Thomas, W., 2006, "Acceptance Testing Using 4 x 8 in. Cylinders," *Concrete International*, V. 28, No. 1, Jan., pp. 81-88.

Detwiler, R. J.; Thomas, W.; Stangebye, T.; and Urahn, M., 2009, "Variability of 4 x 8 in. Cylinder Tests," *Concrete International*, V. 31, No. 5, May, pp. 57-61.

Dinh, H. H.; Parra-Montesinos, G. J.; and Wight, J. K., 2010, "Shear Behavior of Steel Fiber Reinforced Concrete Beams without Stirrup Reinforcement," *ACI Structural Journal*, V. 107, No. 5, Sept.-Oct., pp. 597-606. doi: [10.14359/51663913](https://doi.org/10.14359/51663913)

Dolan, C. W., and Krohn, J. J., 2007, "A Case for Increasing the Allowable Compressive Release Stress for Prestressed Concrete," *PCI Journal*, V. 52, No. 1, Jan.-Feb., pp. 102-105. doi: [10.15554/pcij.01012007.102.105](https://doi.org/10.15554/pcij.01012007.102.105)

Dönmez, A., and Bažant, Z. P., 2017, "Size Effect on Punching Strength of Reinforced Concrete Slabs Without and With Shear Reinforcement," *ACI Structural Journal*, V. 114, No. 4, July-Aug., pp. 876-886. doi: [10.14359/51689719](https://doi.org/10.14359/51689719)

Dovich, L. M., and Wight, J. K., 2005, "Effective Slab Width Model for Seismic Analysis of Flat Slab Frames," *ACI Structural Journal*, V. 102, No. 6, Nov.-Dec., pp. 868-875. doi: [10.14359/14795](https://doi.org/10.14359/14795)

Durrani, A. J., and Wight, J. K., 1982, "Experimental and Analytical Study of Internal Beam to Column Connections Subjected to Reversed Cyclic Loading," *Report No. UMEE 82R3*, Department of Civil Engineering, University of Michigan, Ann Arbor, MI, July, 275 pp. doi: [10.14359/16809](https://doi.org/10.14359/16809)

Ehsani, M. R., 1982, "Behavior of Exterior Reinforced Concrete Beam to Column Connections Subjected to Earthquake Type Loading," *Report No. UMEE 82R5*,

Department of Civil Engineering, University of Michigan, Ann Arbor, MI, July, 275 pp.

Elgabry, A. A., and Ghali, A., 1987, "Tests on Concrete Slab-Column Connections with Stud Shear Reinforcement Subjected to Shear-Moment Transfer," *ACI Structural Journal*, V. 84, No. 5, Sept.-Oct., pp. 433-442. doi: [10.14359/1656](https://doi.org/10.14359/1656)

Eligehausen, R., and Balogh, T., 1995, "Behavior of Fasteners Loaded in Tension in Cracked Reinforced Concrete," *ACI Structural Journal*, V. 92, No. 3, May-June, pp. 365-379. doi: [10.14359/1137](https://doi.org/10.14359/1137)

Eligehausen, R., and Fuchs, W., 1988, "Load Bearing Behavior of Anchor Fastenings under Shear, Combined Tension and Shear or Flexural Loadings," *Betonwerk + Fertigteil-Technik*, V. 54, pp. 48-56. doi: [10.14359/16854](https://doi.org/10.14359/16854)

Eligehausen, R.; Cook, R. A.; and Appl, J., 2006a, "Behavior and Design of Adhesive Bonded Anchors," *ACI Structural Journal*, V. 103, No. 6, Nov.-Dec., pp. 822-831. doi: [10.14359/18234](https://doi.org/10.14359/18234)

Eligehausen, R.; Fuchs, W.; and Mayer, B., 1987, "Load Bearing Behavior of Anchor Fastenings in Tension," *Betonwerk + Fertigteiltechnik*, V. 12, pp. 826-832, and 1988, V. 1, pp. 29-35. doi: [10.14359/19643](https://doi.org/10.14359/19643)

Eligehausen, R.; Mallée, R.; and Silva, J., 2006b, *Anchorage in Concrete Construction*, Ernst & Sohn (J. T. Wiley), Berlin, Germany, May, 380 pp.

Elwood, K. J.; Maffei, J. M.; Riederer, K. A.; and Telleen, K., 2009, "Improving Column Confinement—Part 2: Proposed New Provisions for the ACI 318 Building Code," *Concrete International*, V. 31, No. 12, Dec., pp. 41-48.

Elwood, K. J.; Matamoros, A. B.; Wallace, J. W.; Lehman, D. E.; Heintz, J. A.; Mitchell, A. D.; Moore, M. A.; Valley, M. T.; Lowes, L. N.; Comartin, C. D.; and Moehle, J. P., 2007, "Update to ASCE/SEI 41 Concrete Provisions," *Earthquake Spectra*, V. 23, No. 3, pp. 493-523, doi: [10.1193/1.2757714](https://doi.org/10.1193/1.2757714)

Elzanaty, A. H.; Nilson, A. H.; and Slate, F. O., 1986, "Shear Capacity of Reinforced Concrete Beams Using High Strength Concrete," *ACI Journal Proceedings*, V. 83, No. 2, Mar.-Apr., pp. 290-296. doi: [10.14359/10433](https://doi.org/10.14359/10433)

Fanella, D. A., and Mota, M., 2014, *Design Guide for Vibrations of Reinforced Concrete Floor Systems*, 10-DG-Vibration, Concrete Reinforcing Steel Institute, Schaumburg, IL, 60 pp.

Faradji, M. J., and Diaz de Cossio, R., 1965, "Diagonal Tension in Concrete Members of Circular Section," Institut de Ingenieria, Mexico (in Spanish; translation by Portland Cement Association, Foreign Literature Study No. 466), 61 pp. doi: [10.14359/19496](https://doi.org/10.14359/19496)

Farrow, C. B., and Klingner, R. E., 1995, "Tensile Capacity of Anchors with Partial or Overlapping Failure Surfaces: Evaluation of Existing Formulas on an LRFD Basis," *ACI Structural Journal*, V. 92, No. 6, Nov.-Dec., pp. 698-710. doi: [10.14359/9664](https://doi.org/10.14359/9664)

FEMA Flood Map Service Center, <https://msc.fema.gov/portal/home> (accessed August 12, 2024)

- FEMA Federal Fire Occurrence Map Viewer, <https://www.fema.gov/data-visualization/fire-incidents-states-and-counties> (accessed August 12, 2024)
- FEMA National Risk Index, Strong Wind, <https://hazards.fema.gov/nri/strong-wind> (accessed August 12, 2024)
- FEMA Wildfire Activity, <https://www.usfa.fema.gov/wui/research-technology/>
- FEMA Wind Zone Map, <https://www.fema.gov/safe-rooms/wind-zones-unitedstates> (accessed October 15, 2021)
- Fennel, A. W.; Line, P.; Mochizuki, G. L.; Moore, K. S.; Van Dorpe, T. D.; and Voss, T. A., 2009, "Report on Laboratory Testing of Anchor Bolts Connecting Wood Sill Plates to Concrete with Minimum Edge Distances," SEAONC, San Francisco, CA, Mar., 50 pp.
- Ferguson, P. M., and Matloob, F. N., 1959, "Effect of Bar Cutoff on Bond and Shear Strength of Reinforced Concrete Beams," *ACI Journal Proceedings*, V. 56, No. 5, July, pp. 5-24. doi: [10.14359/8081](https://doi.org/10.14359/8081)
- Fintel, M.; Ghosh, S. K.; and Iyengar, H., 1986, Column Shortening in Tall Buildings—Prediction and Compensation, EB108D, Portland Cement Association, Skokie, IL, 34 pp. doi: [10.14359/51685083](https://doi.org/10.14359/51685083)
- fib, 2011, "Design of Anchorages in Concrete. Guide to Good Practice," *Bulletin No.58*, International Federation for Structural Concrete, Lausanne, Switzerland, 280 pp.
- FIP, 1999, FIP Recommendations, Practical Design of Structural Concrete, FIP-Commission 3, "Practical Design," Pub.: SETO, London, UK, Sept., 112 pp.
- Fling, R. S., 1987, *Practical Design of Reinforced Concrete*, John Wiley & Sons, Inc., New York, 536 pp.
- Ford, J. S.; Chang, D. C.; and Breen, J. E., 1981, "Design Indications from Tests of Unbraced Multipanel Concrete Frames," *Concrete International*, V. 3, No. 3, Mar., pp. 37-47. doi: [10.14359/16551](https://doi.org/10.14359/16551)
- Foutch, D. A.; Gamble, W. L.; and Sunidja, H., 1990, "Tests of Post-Tensioned Concrete Slab-Edge Column Connections," *ACI Structural Journal*, V. 87, No. 2, Mar.-Apr., pp. 167-179. doi: [10.14359/2689](https://doi.org/10.14359/2689)
- Frantz, G. C., and Breen, J. E., 1980, "Cracking on the Side Faces of Large Reinforced Concrete Beams," *ACI Journal Proceedings*, V. 77, No. 5, Sept.-Oct., pp. 307-313. doi: [10.14359/7007](https://doi.org/10.14359/7007)
- French, C. W., and Moehle, J. P., 1991, "Effect of Floor Slab on Behavior of Slab-Beam-Column Connections," *Design of Beam-Column Joints for Seismic Resistance*, SP-123, J. O. Jirsa, ed., American Concrete Institute, Farmington Hills, MI, pp. 225-258. doi: [10.14359/19328](https://doi.org/10.14359/19328)
- Frosch, R. J., 1999, "Another Look at Cracking and Crack Control in Reinforced Concrete," *ACI Structural Journal*, V. 96, No. 3, May-June, pp. 437-442. doi: [10.14359/679](https://doi.org/10.14359/679)
- Frosch, R. J., 2002, "Modeling and Control of Side Face Beam Cracking," *ACI Structural Journal*, V. 99, No. 3, May-June, pp. 376-385. doi: [10.14359/11922](https://doi.org/10.14359/11922)
- Frosch, R. J.; Labi, S.; and Sim, C., 2014, "Increasing Bridge Deck Service Life: Volume 1 – Technical Evaluation," *Publication No. FHWA/IN/JTRP-2014/16*. Joint Transportation Research Program, Indiana Department of Transportation and Purdue University, West Lafayette, IN.
- Frosch, R. J.; Yu, Q.; Cusatis, G.; and Bažant, Z. P., 2017, "A Unified Approach to Shear Design," *Concrete International*, V. 39, No. 9, Sept., pp. 47-52. doi: [10.14359/51701014](https://doi.org/10.14359/51701014)
- Fuchs, W.; Eligehausen, R.; and Breen, J., 1995, "Concrete Capacity Design (CCD) Approach for Fastening to Concrete," *ACI Structural Journal*, V. 92, No. 1, Jan.-Feb. 1995, pp. 73-93. Also discussion, *ACI Structural Journal*, V. 92, No. 6, Nov.-Dec., pp. 787-802. doi: [10.14359/1533](https://doi.org/10.14359/1533)
- Furche, J., and Eligehausen, R., 1991, "Lateral Blow-out Failure of Headed Studs Near a Free Edge," *Anchors in Concrete—Design and Behavior*, SP-130, G. A. Senkiw and H. B. Lancelot III, eds., American Concrete Institute, Farmington Hills, MI, pp. 235-252. doi: [10.14359/1276](https://doi.org/10.14359/1276)
- Furlong, R. W.; Fenves, G. L.; and Kasl, E. P., 1991, "Welded Structural Wire Reinforcement for Columns," *ACI Structural Journal*, V. 88, No. 5, Sept.-Oct., pp. 585-591. doi: [10.14359/9452](https://doi.org/10.14359/9452)
- Furlong, R. W.; Hsu, C.-T. T.; and Mirza, S. A., 2004, "Analysis and Design of Concrete Columns for Biaxial Bending—Overview," *ACI Structural Journal*, V. 101, No. 3, May-June, pp. 413-423. doi: [10.14359/13101](https://doi.org/10.14359/13101)
- Gajda, J. and Dowell, A. M., 2003, "Concrete Consolidation and Potential for Voids in ICF Walls," *PCA Research and Development Bulletin RD134*, Portland Cement Association, Skokie, IL, 20 pp.
- Gamble, W. L., 1972, "Moments in Beam Supported Slabs," *ACI Journal Proceedings*, V. 69, No. 3, Mar., pp. 149-157. doi: [10.14359/11258](https://doi.org/10.14359/11258)
- Gamble, W. L.; Sozen, M. A.; and Siess, C. P., 1969, "Tests of a Two-Way Reinforced Concrete Floor Slab," *Journal of the Structural Division*, V. 95, June, pp. 1073-1096. doi: [10.14359/19673](https://doi.org/10.14359/19673)
- Gajda, J., and VanGeem, M. G., 2000, "Energy Use in Residential Housing: A Comparison of Concrete Masonry and Wood Framed Walls," *PCA R&D Serial No. 2429*, 20 pp.
- Genikomsou, A. S., and Polak, M. A., 2017, "Effect of Openings on Punching Shear Strength of Reinforced Concrete Slabs—Finite Element Investigation," *ACI Structural Journal*, V. 114, No. 5, Sept.-Oct., pp. 1249-1261. doi: [10.14359/51689871](https://doi.org/10.14359/51689871)
- Gerber, L. L., and Burns, N. H., 1971, "Ultimate Strength Tests of Post-Tensioned Flat Plates," *PCI Journal*, V. 16, No. 6, Nov.-Dec., pp. 40-58. doi: [10.15554/pcj.11011971.40.58](https://doi.org/10.15554/pcj.11011971.40.58)
- Gergely, P., and Lutz, L. A., 1968, "Maximum Crack Width in Reinforced Concrete Flexural Members," *Causes, Mechanism, and Control of Cracking in Concrete*, SP-20, American Concrete Institute, Farmington Hills, MI, pp. 87-117. doi: [10.14359/17348](https://doi.org/10.14359/17348)
- Ghali, A., and Favre, R., 1986, *Concrete Structures: Stresses and Deformations*, Chapman and Hall, New York, 348 pp.

Ghannoum, W. M., and Slavin, C. M., 2016, “Low-Cycle Fatigue Performance of High-Strength Steel Reinforcing Bars,” *ACI Materials Journal*, V. 113, No. 6, Nov.-Dec., pp. 803-814. doi: [10.14359/51689116](https://doi.org/10.14359/51689116)

Ghimire, K.; Darwin, D.; and O'Reilly, M., 2018, “Anchorage of Headed Reinforcing Bars,” *SM Report No. 127*, University of Kansas Center for Research, Lawrence, KS, Jan., 278 pp.

Ghimire, K. P.; Shao, Y.; Darwin, D.; and O'Reilly, M., 2019a, “Conventional and High-Strength Headed Bars – Part 1: Anchorage Tests,” *ACI Structural Journal*, V. 116, No. 3, May, pp. 255-264. doi: [10.14359/51714479](https://doi.org/10.14359/51714479)

Ghimire, K. P.; Shao, Y.; Darwin, D.; and O'Reilly, M., 2019b, “Conventional and High-Strength Headed Bars – Part 2: Data Analysis,” *ACI Structural Journal*, V. 116, No. 3, May, pp. 265-272. doi: [10.14359/51714480](https://doi.org/10.14359/51714480)

Gilbert, R. I., 1992, “Shrinkage Cracking in Fully Restrained Concrete Members,” *ACI Structural Journal*, V. 89, No. 2, Mar.-Apr., pp. 141-149. doi: [10.14359/2917](https://doi.org/10.14359/2917)

Gomez, I. R.; Kanvinde, A. M.; Smith, C.; and Deierlein, G. G., 2009, “Shear Transfer in Exposed Column Base Plates,” Report Presented to American Institute of Steel Construction, Chicago, IL, Mar., 159 pp.

Goto, Y., 1971, “Cracks Formed in Concrete around Deformed Tension Bars in Concrete,” *ACI Journal Proceedings*, V. 68, No. 4, Apr., pp. 244-251. doi: [10.14359/11325](https://doi.org/10.14359/11325)

Graybeal, B., 2014, “Lightweight Concrete: Development of Mild Steel in Tension,” *Technical Brief No. FHWA-HRT-14-030*, Federal Highway Administration, Washington, DC.

Greene, G., and Graybeal, B., 2013, “Lightweight Concrete: Mechanical Properties,” *Report No. FHWA-HRT-13-062*, Federal Highway Administration, Washington, DC, 12 pp.

Greene, G., and Graybeal, B., 2015, “Lightweight Concrete: Shear Performance,” *Report No. FHWA-HRT-15-022*, Federal Highway Administration, Washington, DC, 20 pp.

Griezic, A.; Cook, W. D.; and Mitchell, D., 1994, “Tests to Determine Performance of Deformed Welded-Wire Fabric Stirrups,” *ACI Structural Journal*, V. 91, No. 2, Mar.-Apr., pp. 211-220. doi: [10.14359/4597](https://doi.org/10.14359/4597)

Grossfield, B., and Birnstiel, C., 1962, “Tests of T-Beams with Precast Webs and Cast-in-Place Flanges,” *ACI Journal Proceedings*, V. 59, No. 6, June, pp. 843-851. doi: [10.14359/16709](https://doi.org/10.14359/16709)

Grossman, J. S., 1987, “Reinforced Concrete Design,” *Building Structural Design Handbook*, R. N. White and C. G. Salmon, eds., John Wiley and Sons, Inc., New York.

Grossman, J. S., 1990, “Slender Concrete Structures—The New Edge,” *ACI Structural Journal*, V. 87, No. 1, Jan.-Feb., pp. 39-52. doi: [10.14359/3212](https://doi.org/10.14359/3212)

Guimares, G. N.; Kreger, M. E.; and Jirsa, J. O., 1992, “Evaluation of Joint-Shear Provisions for Interior Beam-Column-Slab Connections Using High Strength Materials,”

ACI Structural Journal, V. 89, No. 1, Jan.-Feb., pp. 89-98. doi: [10.14359/1299](https://doi.org/10.14359/1299)

Gulkan, P., and Sozen, M. A., 1974, “Inelastic Response of Reinforced Concrete Structures to Earthquake Motions,” *ACI Journal Proceedings*, V. 71, No. 12, Dec., pp. 604-610. doi: [10.14359/7110](https://doi.org/10.14359/7110)

Guralnick, S. A., and LaFraugh, R. W., 1963, “Laboratory Study of a 45-Foot Square Flat Plate Structure,” *ACI Journal Proceedings*, V. 60, No. 9, Sept., pp. 1107-1185. doi: [10.14359/7893](https://doi.org/10.14359/7893)

Gustafson, D. P., and Felder, A. L., 1991, “Questions and Answers on ASTM A706 Reinforcing Bars,” *Concrete International*, V. 13, No. 7, July, pp. 54-57. doi: [10.14359/51685022](https://doi.org/10.14359/51685022)

Hale, W. M., and Russell, B. W., 2006, “Effect of Allowable Compressive Stress at Release on Prestress Losses and on the Performance of Precast, Prestressed Concrete Bridge Girders,” *PCI Journal*, V. 51, No. 2, Mar.-Apr., pp. 14-25. doi: [10.15554/pcij.03012006.14.25](https://doi.org/10.15554/pcij.03012006.14.25)

Hamad, B. S.; Jirsa, J. O.; and D'Abreu, N. I., 1993, “Anchorage Strength of Epoxy-Coated Hooked Bars,” *ACI Structural Journal*, V. 90, No. 2, Mar.-Apr., pp. 210-217. doi: [10.14359/4127](https://doi.org/10.14359/4127)

Hansell, W., and Winter, G., 1959, “Lateral Stability of Reinforced Concrete Beams,” *ACI Journal Proceedings*, V. 56, No. 3, Sept., pp. 193-214. doi: [10.14359/8091](https://doi.org/10.14359/8091)

Hanson, J. A., 1961, “Tensile Strength and Diagonal Tension Resistance of Structural Lightweight Concrete,” *ACI Journal Proceedings*, V. 58, No. 1, July, pp. 1-40. doi: [10.14359/7972](https://doi.org/10.14359/7972)

Hanson, N. W., 1960, “Precast-Prestressed Concrete Bridges: Horizontal Shear Connections,” *Bulletin*, PCA Research and Development Laboratories, V. 2, No. 2, May, pp. 38-58. doi: [10.14359/16708](https://doi.org/10.14359/16708)

Hanson, N. W., and Connor, H. W., 1967, “Seismic Resistance of Reinforced Concrete Beam-Column Joints,” *Journal of the Structural Division*, V. 93, No. ST5 Oct., pp. 533-560. doi: [10.14359/19667](https://doi.org/10.14359/19667)

Hanson, N. W., and Hanson, J. M., 1968, “Shear and Moment Transfer between Concrete Slabs and Columns,” *Bulletin*, PCA Research and Development Laboratories, V. 10, No. 1, Jan., pp. 2-16. doi: [10.14359/19463](https://doi.org/10.14359/19463)

Hanson, N. W., and Kaar, P. H., 1959, “Flexural Bond Tests Pretensioned Beams,” *ACI Journal Proceedings*, V. 55, No. 7, Jan., pp. 783-802. doi: [10.14359/11389](https://doi.org/10.14359/11389)

Hardisty, J.; Villalobos, E.; Richter, B.; and Pujol, S., 2015, “Lap Splices in Unconfined Boundary Elements,” *Concrete International*, V. 37, No. 1, Jan., pp. 51-58.

Hatcher, D. S.; Sozen, M. A.; and Siess, C. P., 1965, “Test of a Reinforced Concrete Flat Plate,” *Journal of the Structural Division*, V. 91, May, pp. 205-232.

Hatcher, D. S.; Sozen, M. A.; and Siess, C. P., 1969, “Test of a Reinforced Concrete Flat Slab,” *Journal of the Structural Division*, V. 95, June, pp. 1051-1072. doi: [10.14359/51685284](https://doi.org/10.14359/51685284)

- Hawkins, N. M., 1968, "Bearing Strength of Concrete Loaded through Rigid Plates," *Magazine of Concrete Research*, V. 20, No. 62, Mar., pp. 31-40. doi: [10.1680/mac.1968.20.62.31](https://doi.org/10.1680/mac.1968.20.62.31)
- Hawkins, N. M., 1974, "Shear Strength of Slabs with Shear Reinforcement," *Shear in Reinforced Concrete*, SP-42, American Concrete Institute, Farmington Hills, MI, pp. 785-815. doi: [10.14359/17306](https://doi.org/10.14359/17306)
- Hawkins, N. M., 1981, "Lateral Load Resistance of Unbonded Post-Tensioned Flat Plate Construction," *PCI Journal*, V. 26, No. 1, Jan.-Feb., pp. 94-116. doi: [10.15554/pci.01011981.94.117](https://doi.org/10.15554/pci.01011981.94.117)
- Hawkins, N. M., and Ghosh, S. K., 2006, "Shear Strength of Hollow-Core Slabs," *PCI Journal*, V. 51, No. 1, Jan.-Feb., pp. 110-115.
- Hawkins, N. M.; Mitchell, D.; and Hanna, S. N., 1975, "The Effects of Shear Reinforcement on Reversed Cyclic Loading Behavior of Flat Plate Structures," *Canadian Journal of Civil Engineering*, V. 2, No. 4, pp. 572-582. doi: [10.1139/175-052](https://doi.org/10.1139/175-052)
- Hawkins, N. M., and Ospina, C. E., 2017, "Effect of Slab Flexural Reinforcement and Depth on Punching Strength," *Joint ACI-fib International Symposium on Punching Shear of Structural Concrete Slabs*, SP-315, American Concrete Institute, Farmington Hills, MI, pp. 117-140. doi: [10.14359/51700935](https://doi.org/10.14359/51700935)
- Henry, R. E.; Dizhur, D.; Elwood, K. J.; Hare, J.; and Brunsdon, D., 2017, "Damage to Concrete Buildings with Precast Floors During the 2016 Kaikoura Earthquake," *Bulletin of New Zealand Society for Earthquake Engineering*, V. 50, No. 2, pp. 174-187. [http://www.nzsee.org.nz/db/Bulletin/Archive/50\(2\)0174.pdf](http://www.nzsee.org.nz/db/Bulletin/Archive/50(2)0174.pdf)
- Hirosawa, M., 1977, "Strength and Ductility of Reinforced Concrete Members," *Report No. 76*, Building Research Institute, Ministry of Construction, Tokyo, Mar. (in Japanese). Also, data in Civil Engineering Studies, 1978, *Structural Research Series No. 452*, University of Illinois, Champaign, IL, 141 pp. doi: [10.14359/19325](https://doi.org/10.14359/19325)
- Hoehler, M., and Eligehausen, R., 2008, "Behavior and Testing of Anchors in Simulated Seismic Cracks," *ACI Structural Journal*, V. 105, No. 3, May-June, pp. 348-357. doi: [10.14359/19794](https://doi.org/10.14359/19794)
- Horvilleur, J. F.; Patel, V. B.; and Young, K.A., 2006, "Modeling Assumptions for Lateral Analysis," *Performance-Based Design of Concrete Building for Wind Loads*, SP-240, American Concrete Institute, Farmington Hills, MI pp. 73-100. doi: [10.14359/18292](https://doi.org/10.14359/18292)
- Hsu, T. T. C., 1968, "Torsion of Structural Concrete—Behavior of Reinforced Concrete Rectangular Members," *Torsion of Structural Concrete*, SP-18, American Concrete Institute, Farmington Hills, MI, pp. 291-306. doi: [10.14359/17572](https://doi.org/10.14359/17572)
- Hsu, T. T. C., 1990, "Shear Flow Zone in Torsion of Reinforced Concrete," *Journal of Structural Engineering*, V. 116, No. 11, Nov., pp. 3206-3226. doi: [10.1061/\(ASCE\)0733-9445\(1990\)116:11\(3206\)](https://doi.org/10.1061/(ASCE)0733-9445(1990)116:11(3206))
- Hsu, T. T. C., 1997, "ACI Shear and Torsion Provisions for Prestressed Hollow Girders," *ACI Structural Journal*, V. 94, No. 6, Nov.-Dec., pp. 787-799. doi: [10.14359/9738](https://doi.org/10.14359/9738)
- Hsu, T. T. C., and Burton, K. T., 1974, "Design of Reinforced Concrete Spandrel Beams," *Journal of the Structural Division*, V. 100, Jan., pp. 209-229. doi: [10.14359/16866](https://doi.org/10.14359/16866)
- Huq, M. S.; Burgos, E. A.; Lequesne, R. D.; and Lepage, A., 2018, "High-Strength Steel Bars in T-Shaped Concrete Walls," Eleventh U.S. National Conference on Earthquake Engineering, Los Angeles, CA.
- Hwang, S., and Moehle, J. P., 2000, "Models for Laterally Loaded Slab-Column Frames," *ACI Structural Journal*, V. 97, No. 2, Mar.-Apr., pp. 345-353. doi: [10.14359/866](https://doi.org/10.14359/866)
- ICBO, 1997, "Uniform Building Code," V. 2, Structural Engineering Design Provisions, International Conference of Building Officials, Whittier, CA, 492 pp.
- Ichinose, T., 1995, "Splitting Bond Failure of Columns under Seismic Action," *ACI Structural Journal*, V. 92, No. 5, pp. 535-541. doi: [10.14359/904](https://doi.org/10.14359/904)
- Iguro, M.; Shioya, T.; Nojiri, Y.; and Akiyama, H.; 1985, "Experimental Studies on Shear Strength of Large Reinforced Concrete Beams under Uniformly Distributed Load," *Concrete Library International*, Japan Society of Civil Engineers, Tokyo, No. 5, pp. 137-154. doi: [10.2208/jscej.1984.348_175](https://doi.org/10.2208/jscej.1984.348_175)
- IIBHS, 2020, "Fortified Commercial Wind Standards," Insurance Institute for Building and Home Safety, Richburg, SC, 55 pp.
- Ishizuka, T., and Hawkins, N. M., 1987, "Effect of Bond Deterioration on the Seismic Response of Reinforced and Partially Prestressed Concrete Ductile Moment Resistant Frames," *Report SM 87-2*, Department of Civil Engineering, University of Washington, Seattle, WA.
- Ivey, D. L., and Buth, E., 1967, "Shear Capacity of Lightweight Concrete Beams," *ACI Journal Proceedings*, V. 64, No. 10, Oct., pp. 634-643. doi: [10.14359/7591](https://doi.org/10.14359/7591)
- Jeanty, P. R.; Mitchell, D.; and Mirza, M. S., 1988, "Investigation of 'Top Bar' Effects in Beams," *ACI Structural Journal*, V. 85, No. 3, May-June, pp. 251-257. doi: [10.14359/2613](https://doi.org/10.14359/2613)
- Jirsa, J. O., and Breen, J. E., 1981, "Influence of Casting Position and Shear on Development and Splice Length—Design Recommendations," *Research Report 242-3F*, Center for Transportation Research, Bureau of Engineering Research, University of Texas at Austin, Austin, TX, Nov., 50 pp. doi: [10.14359/19469](https://doi.org/10.14359/19469)
- Jirsa, J. O., and Marques, J. L. G., 1975, "A Study of Hooked Bar Anchorages in Beam-Column Joints," *ACI Journal Proceedings*, V. 72, No. 5, May-June, pp. 198-200. doi: [10.14359/11131](https://doi.org/10.14359/11131)
- Jirsa, J. O.; Lutz, L. A.; and Gergely, P., 1979, "Rationale for Suggested Development, Splice, and

Standard Hook Provisions for Deformed Bars in Tension,” *Concrete International*, V. 1, No. 7, July, pp. 47-61. doi: [10.14359/15038](https://doi.org/10.14359/15038)

Jirsa, J. O.; Sozen, M. A.; and Siess, C. P., 1963, “Effects of Pattern Loadings on Reinforced Concrete Floor Slabs,” *Structural Research Series* No. 269, Civil Engineering Studies, University of Illinois, Urbana, IL, July. doi: [10.14359/51685300](https://doi.org/10.14359/51685300)

Jirsa, J. O.; Sozen, M. A.; and Siess, C. P., 1966, “Test of a Flat Slab Reinforced with Welded Wire Fabric,” *Journal of the Structural Division*, V. 92, June, pp. 199-224. doi: [10.14359/16861](https://doi.org/10.14359/16861)

Jirsa, J. O.; Sozen, M. A.; and Siess, C. P., 1969, “Pattern Loadings on Reinforced Concrete Floor Slabs,” *Journal of the Structural Division*, V. 95, No. ST6, June, pp. 1117-1137.

Johnson, L. A., and Jirsa, J. O., 1981, “The Influence of Short Embedment and Close Spacing on the Strength of Hooked Bar Anchorages,” *PMFSEL Report* No. 81-2, Department of Civil Engineering-Structures Research Laboratory, University of Texas, Austin, TX, 93 pp.

Johnson, M. K., and Ramirez, J. A., 1989, “Minimum Amount of Shear Reinforcement in High Strength Concrete Members,” *ACI Structural Journal*, V. 86, No. 4, July-Aug., pp. 376-382. doi: [10.14359/2896](https://doi.org/10.14359/2896)

Johnson, T., and Ghadiali, Z., 1972, “Load Distribution Test on Precast Hollow Core Slabs with Openings,” *PCI Journal*, V. 17, No. 5, Sept.-Oct., pp. 9-19. doi: [10.15554/pcij.09011972.9.19](https://doi.org/10.15554/pcij.09011972.9.19)

Johnston, D. W., and Zia, P., 1982, “Bond Characteristics of Epoxy-Coated Reinforcing Bars,” *Report* No. FHWA/NC/82-002, Department of Civil Engineering, North Carolina State University, Raleigh, NC, Aug., 176 pp. doi: [10.14359/16632](https://doi.org/10.14359/16632)

Joint ACI-ASCE Committee 326, 1962, “Shear and Diagonal Tension,” *ACI Journal Proceedings*, V. 59, No. 1, Jan. 1962, pp. 1-30; No. 2, Feb. 1962, pp. 277-334; and No. 3, Mar., pp. 352-396. doi: [10.14359/18461](https://doi.org/10.14359/18461)

Joint ACI-ASCE Committee 423, 1958, “Tentative Recommendations for Prestressed Concrete,” *ACI Journal Proceedings*, V. 54, No. 7, Jan., pp. 545-578. doi: [10.14359/11455](https://doi.org/10.14359/11455)

Joint ACI-ASCE Committee 423, 1974, “Tentative Recommendations for Prestressed Concrete Flat Plates,” *ACI Journal Proceedings*, V. 71, No. 2, Feb., pp. 67-71. doi: [10.14359/7344](https://doi.org/10.14359/7344)

Joint ACI-ASCE Committee 426, 1973, “Shear Strength of Reinforced Concrete Members (ACI 426R-74),” *Proceedings*, ASCE, V. 99, No. ST6, June, pp. 1148-1157.

Joint ACI-ASCE Committee 426, 1974, “The Shear Strength of Reinforced Concrete Members—Slabs,” *Journal of the Structural Division*, V. 100, Aug., pp. 1543-1591.

Joint PCI/WRI Ad Hoc Committee on Welded Wire Fabric for Shear Reinforcement, 1980, “Welded Wire Fabric for Shear Reinforcement,” *PCI Journal*, V. 25, No. 4, July-Aug., pp. 32-36. doi: [10.14359/16661](https://doi.org/10.14359/16661)

Kaar, P. H., 1966, “High Strength Bars as Concrete Reinforcement, Part 8: Similitude in Flexural Cracking of T-Beam Flanges,” *PCA Research and Development Laboratories Bulletin*, V. 8, No. 2, May, pp. 2-12. doi: [10.14359/51685141](https://doi.org/10.14359/51685141)

Kaar, P. H.; Hanson, N. W.; and Capell, H. T., 1978, “Stress-Strain Characteristics of High Strength Concrete,” *Douglas McHenry International Symposium on Concrete and Concrete Structures*, SP-55, American Concrete Institute, Farmington Hills, MI, pp. 161-185. doi: [10.14359/6613](https://doi.org/10.14359/6613)

Kaar, P. H.; Kriz, L. B.; and Hognestad, E., 1960, “Precast-Prestressed Concrete Bridges: (1) Pilot Tests of Continuous Girders,” *PCA Research and Development Laboratories Bulletin*, V. 2, No. 2, May, pp. 21-37. doi: [10.14359/51685340](https://doi.org/10.14359/51685340)

Kaar, P. H.; La Fraugh, R. W.; and Mass, M. A., 1963, “Influence of Concrete Strength on Strand Transfer Length,” *PCI Journal*, V. 8, No. 5, Oct., pp. 47-67. doi: [10.15554/pcij.10011963.47.67](https://doi.org/10.15554/pcij.10011963.47.67)

Kaar, P., and Magura, D., 1965, “Effect of Strand Blanketing on Performance of Pretensioned Girders,” *PCI Journal*, V. 10, No. 6, Dec., pp. 20-34. doi: [10.15554/pcij.12011965.20.34](https://doi.org/10.15554/pcij.12011965.20.34)

Kahn, L. F., and Mitchell, A. D., 2002, “Shear Friction Tests with High-Strength Concrete,” *ACI Structural Journal*, V. 99, No. 1, Jan.-Feb., pp. 98-103. doi: [10.14359/11040](https://doi.org/10.14359/11040)

Kang, T. H.-K.; LaFave, J. M.; Robertson, I. N.; and Hawkins, N. M., 2007, “Post-Tensioned Slab-Column Connections—Drift Capacity at Punching of Connections Subjected to Lateral Loading,” *Concrete International*, V. 29, No. 4, Apr., pp. 61-68. doi: [10.14359/18569](https://doi.org/10.14359/18569)

Kang, T. H.-K.; Shin, M.; Mitra, N.; and Bonacci, J. F., 2009, “Seismic Design of Reinforced Concrete Beam-Column Joints with Headed Bars,” *ACI Structural Journal*, V. 106, No. 6, Nov.-Dec., pp. 868-877. doi: [10.14359/51663188](https://doi.org/10.14359/51663188)

Kang, T. H.-K., and Wallace, J. W., 2006, “Punching of Reinforced and Post-Tensioned Concrete Slab-Column Connections,” *ACI Structural Journal*, V. 103, No. 4, July-Aug., pp. 531-540. doi: [10.14359/16429](https://doi.org/10.14359/16429)

Kemp, E. L.; Brezny, F. S.; and Unterspan, J. A., 1968, “Effect of Rust and Scale on the Bond Characteristics of Deformed Reinforcing Bars,” *ACI Journal Proceedings*, V. 65, No. 9, Sept., pp. 743-756. doi: [10.14359/7509](https://doi.org/10.14359/7509)

Kestner, D. M.; Goupil, J.; and Lorenz, E., eds., 2010, *Sustainability Guidelines for the Structural Engineer*, American Society of Civil Engineers, Reston, VA, 315 pp. doi: [10.1061/9780784411193](https://doi.org/10.1061/9780784411193)

Khalifa, J. U., and Collins, M. P., 1981, “Circular Reinforced Concrete Members Subjected to Shear,” *Publication* No. 81-08, Department of Civil Engineering, University of Toronto, Toronto, ON, Canada, Dec., 117 pp. doi: [10.14359/16572](https://doi.org/10.14359/16572)

Khuntia, M., and Ghosh, S. K., 2004a, “Flexural Stiffness of Reinforced Concrete Columns and Beams: Analytical Approach,” *ACI Structural Journal*, V. 101, No. 3, May-June, pp. 351-363. doi: [10.14359/13095](https://doi.org/10.14359/13095)

- Khuntia, M., and Ghosh, S. K., 2004b, "Flexural Stiffness of Reinforced Concrete Columns and Beams: Experimental Verification," *ACI Structural Journal*, V. 101, No. 3, May-June, pp. 364-374. doi: [10.14359/13096](https://doi.org/10.14359/13096)
- Kim, M.-G., and Chun, S.-C., 2022, "Group Behavior and Concrete Breakout Strength of 16 mm Deformed Wire Anchors in Tension," *ACI Structural Journal*, V. 119, No. 5, Sept., pp. 299-310. doi: [10.14359/51734669](https://doi.org/10.14359/51734669)
- Kim, S., and Wallace, J., 2017, "Shear Design of Structural Walls for Tall Reinforced Concrete Core Wall Buildings," 16th World Conference on Earthquake Engineering, Santiago, Chile, 10 pp.
- Klein, G. J., 1986, "Design of Spandrel Beams," PCI Specially Funded Research Project No. 5, Precast/Prestressed Concrete Institute, Chicago, IL, 104 pp. doi: [10.14359/51685218](https://doi.org/10.14359/51685218)
- Klein, G. J., 2008, "Curved-Bar Nodes: A Detailing Tool for Strut-and-Tie Models," *Concrete International*, V. 30, No. 9, Sept., pp. 42-47. doi: [10.14359/19949](https://doi.org/10.14359/19949)
- Klein, G. J., and Lindenberg, R. J., 2009, "Volume Change Response of Precast Concrete Buildings," *PCI Journal*, V. 54, No. 4, Fall, pp. 112-131. doi: [10.15554/pcij.09012009.112.131](https://doi.org/10.15554/pcij.09012009.112.131)
- Klemencic, R.; McFarlane, I. S.; Hawkins, N. M.; and Nikolau, S., 2012, "Seismic Design of Reinforcing Concrete Mat Foundations: A Guide for Practicing Engineers," NEHRP Seismic Design Technical Brief No. 7, National Institute of Standards and Technology, Gaithersburg, MD, pp. 11-12.
- Klingner, R.; Mendonca, J.; and Malik, J., 1982, "Effect of Reinforcing Details on the Shear Resistance of Anchor Bolts under Reversed Cyclic Loading," *ACI Journal Proceedings*, V. 79, No. 1, Jan.-Feb., pp. 3-12. doi: [10.14359/10455](https://doi.org/10.14359/10455)
- Kopp, G. A.; Li, S. H.; and Hong, H. P., 2021, "Analysis of the Duration of High Winds During Landfalling Hurricanes," *Frontiers in Built Environment*, V. 7, pp. 1-10. doi: [10.3389/fbuilt.2021.632069](https://doi.org/10.3389/fbuilt.2021.632069)
- Kramrisch, F., and Rogers, P., 1961, "Simplified Design of Combined Footings," *Journal of the Soil Mechanics and Foundations Division*, V. 87, Oct., pp. 19-44.
- Krc, K.; Wermager, S.; Sneed, L.; and Meinheit, D., 2016, "Examination of the Effective Coefficient of Friction for Shear-Friction Design," *PCI Journal*, Nov.-Dec., pp. 44-67. doi: [10.15554/pcij61.6-01](https://doi.org/10.15554/pcij61.6-01)
- Kriz, L. B., and Rath, C. H., 1965, "Connections in Precast Concrete Structures—Strength of Corbels," *PCI Journal*, V. 10, No. 1, Feb., pp. 47-61. doi: [10.15554/pcij.02011965.16.61](https://doi.org/10.15554/pcij.02011965.16.61)
- Kuchma, D.; Wei, S.; Sanders, D.; Belarbi, A.; and Novak, L., 2019, "The Development of the One-Way Shear Design Provisions of ACI 318-19," *ACI Structural Journal*, V. 116 No. 4, July, doi: [10.14359/51716739](https://doi.org/10.14359/51716739)
- Kuhn, D., and Shaikh, F., 1996, "Slip-Pullout Strength of Hooked Anchors," *Research Report*, University of Wisconsin-Milwaukee, submitted to the National Codes and Standards Council, 55 pp. doi: [10.14359/51685520](https://doi.org/10.14359/51685520)
- Kurose, Y.; Nagami, K.; and Saito, Y., 1991, "Beam-Column Joints in Precast Concrete Construction in Japan," *Design of Beam-Column Joints for Seismic Resistance*, SP-123, J. O. Jirsa, ed., American Concrete Institute, Farmington Hills, MI, pp. 493-514. doi: [10.14359/2907](https://doi.org/10.14359/2907)
- Kwon, K., and Ghannoum, W. M., 2016, "Assessment of International Standard Provisions on Stiffness of Reinforced Concrete Moment Frame and Shear Wall Buildings," *Engineering Structures*, V. 128, pp. 149-160. doi: [10.1016/j.engstruct.2016.09.025](https://doi.org/10.1016/j.engstruct.2016.09.025)
- LaGue, D. J., 1971, "Load Distribution Tests on Precast Prestressed Hollow-Core Slab Construction," *PCI Journal*, V. 16, No. 6, Nov.-Dec., pp. 10-18. doi: [10.15554/pcij.11011971.10.18](https://doi.org/10.15554/pcij.11011971.10.18)
- Lai, S. M. A., and MacGregor, J. G., 1983, "Geometric Nonlinearities in Unbraced Multistory Frames," *Journal of Structural Engineering*, V. 109, No. 11, Nov., pp. 2528-2545. doi: [10.1061/\(ASCE\)0733-9445\(1983\)109:11\(2528\)](https://doi.org/10.1061/(ASCE)0733-9445(1983)109:11(2528))
- LATBSDC, 2023, "An Alternative Procedure For Seismic Analysis and Design of Tall Buildings," Los Angeles Tall Buildings Structural Design Council, with 2024 Supplements, 92 pp.
- Laughery, L., and Pujol, S., 2015, "Compressive Strength of Unreinforced Struts," *ACI Structural Journal*, V. 112, No. 5, Sept.-Oct., pp. 617-624. doi: [10.14359/51687711](https://doi.org/10.14359/51687711)
- Lee, N. H.; Kim, K. S.; Bang, C. J.; and Park, K. R., 2007, "Tensile-Headed Anchors with Large Diameter and Deep Embedment in Concrete," *ACI Structural Journal*, V. 104, No. 4, July-Aug., pp. 479-486. doi: [10.14359/18778](https://doi.org/10.14359/18778)
- Lee, N. H.; Park, K. R.; and Suh, Y. P., 2010, "Shear Behavior of Headed Anchors with Large Diameters and Deep Embedments," *ACI Structural Journal*, V. 107, No. 2, Mar.-Apr., pp. 146-156. doi: [10.14359/51663530](https://doi.org/10.14359/51663530)
- Lee, H.-J.; Yu, F.-C.; Lin, K.-C.; Wang, J.-C.; Worsfold, B. L.; and Silva, J. F., 2024, "High-Strength Headed Bars in Joints of Special Moment Frames under Cyclic Loading," *ACI Structural Journal*, V. 121, No. 6, Nov., pp. 105-120. doi: [10.14359/51740866](https://doi.org/10.14359/51740866)
- Lenz, K. A., 1992, "Concrete Materials Investigation for Gardiner Dam: Final Report," Canada Department of Agriculture, Prairie Farm Rehabilitation Administration Development Service, Geotechnical Division, Saskatoon, SK, Canada, Mar., 56 pp.
- Leon, R. T., 1989, "Interior Joints with Variable Anchorage Lengths," *Journal of Structural Engineering*, V. 115, No. 9, Sept., pp. 2261-2275. doi: [10.1061/\(ASCE\)0733-9445\(1989\)115:9\(2261\)](https://doi.org/10.1061/(ASCE)0733-9445(1989)115:9(2261))
- Leonhardt, F., 1961, "Die Mindestbewehrung im Stahlbetonbau," 56. Jahrgang. Heft 9, Verlag von Wilhelm Ernst und Sohn, Berlin.
- Leonhardt, F., and Walther, R., 1964, "The Stuttgart Shear Tests," C&CA Translation, No. 111, Cement and Concrete Association, London, UK, 134 pp. doi: [10.14359/19344](https://doi.org/10.14359/19344)

Lepage, A., 1998, "Nonlinear Drift of Multistory RC Structures during Earthquakes," Sixth National Conference on Earthquake Engineering, Seattle, WA.

Lequesne, R. D., and Pincheira, J. A., 2014, "Proposed Revisions to the Strength-reduction Factor for Axially Loaded Members," *Concrete International*, V. 36, No. 9, Sept., pp. 43-49.

Leslie, K. E.; Rajagopalan, K. S.; and Everard, N. J., 1976, "Flexural Behavior of High-Strength Concrete Beams," *ACI Journal Proceedings*, V. 73, No. 9, Sept., pp. 517-521. doi: [10.14359/11093](https://doi.org/10.14359/11093)

Lew, H. S.; Bao, Y.; Pujol, S.; and Sozen, M. A., 2014, "Experimental Study of Reinforced Concrete Assemblies under Column Removal Scenario," *ACI Structural Journal*, V. 111, No. 4, July-Aug., pp. 881-892. doi: [10.14359/51686739](https://doi.org/10.14359/51686739)

Lew, M.; Sitar, N.; Al Atik, L.; Pourzanjani, M.; and Hudson, M. B., 2010, "Seismic Earth Pressures on Deep Building Basements," *SEAOC 2010 Convention Proceedings*, pp. 1-12.

Li, S., and Roy, D. M., 1986, "Investigation of Relations between Porosity, Pore Structure and CL Diffusion of Fly Ash and Blended Cement Pastes," *Cement and Concrete Research*, V. 16, No. 5, Sept., pp. 749-759. doi: [10.1016/0008-8846\(86\)90049-9](https://doi.org/10.1016/0008-8846(86)90049-9)

Lin, C. M.; Restrepo, J. I.; and Park, R., 2000, "Seismic Behaviour and Design of Reinforced Concrete Interior Beam Column Joints," *Research Report 2000-1*, Department of Civil Engineering, University of Canterbury, Christchurch, New Zealand, 471 pp. <http://hdl.handle.net/10092/15092>

Lin, T. Y., and Thornton, K., 1972, "Secondary Moment and Moment Redistribution in Continuous Prestressed Beams," *PCI Journal*, V. 17, No. 1, Jan.-Feb., pp. 8-20 and comments by A. H. Mattock and author's closure, *PCI Journal*, V. 17, No. 4, July-Aug., pp. 86-88. doi: [10.14359/19321](https://doi.org/10.14359/19321)

Lloyd, J. P., 1971, "Splice Requirements for One-Way Slabs Reinforced with Smooth Welded Wire Fabric," Publication No. R(S)4, Civil Engineering, Oklahoma State University, Stillwater, OK, June, 37 pp. doi: [10.14359/19630](https://doi.org/10.14359/19630)

Lloyd, J. P., and Kesler, C. E., 1969, "Behavior of One-Way Slabs Reinforced with Deformed Wire and Deformed Wire Fabric," *T&AM Report No. 323*, University of Illinois, Urbana, IL, 129 pp. doi: [10.14359/16663](https://doi.org/10.14359/16663)

Logan, D. R., 1997, "Acceptance Criteria for Bond Quality of Strand for Pretensioned Prestressed Concrete Applications," *PCI Journal*, V. 42, No. 2, Mar.-Apr., pp. 52-90. doi: [10.15554/pci.03011997.52.90](https://doi.org/10.15554/pci.03011997.52.90)

Lotze, D.; Klingner, R. E.; and Graves, H. L. III, 2001, "Static Behavior of Anchors under Combinations of Tension and Shear Loading," *ACI Structural Journal*, V. 98, No. 4, July-Aug., pp. 525-536. doi: [10.14359/10295](https://doi.org/10.14359/10295)

Lu, Y.; Henry, R. S.; Gultom, R.; and Ma, Q. T., 2017, "Cyclic Testing of Reinforced Concrete Walls with Distributed Minimum Vertical Reinforcement," *Journal of Structural Engineering*, V. 143, No. 5, p. 04016225. doi: [10.1061/\(ASCE\)ST.1943-541X.0001723](https://doi.org/10.1061/(ASCE)ST.1943-541X.0001723)

Lubell, A. S.; Bentz, E. C.; and Collins, M. P., 2009, "Shear Reinforcement Spacing in Wide Members," *ACI Structural Journal*, V. 106, No. 2, Mar.-Apr., pp. 205-214. doi: [10.14359/56359](https://doi.org/10.14359/56359)

Lubell, A. S.; Sherwood, E. G.; Bentz, E. C.; and Collins, M. P., 2004, "Safe Shear Design of Large Wide Beams," *Concrete International*, V. 26, No. 1, Jan., pp. 66-78. doi: [10.14359/19136](https://doi.org/10.14359/19136)

Lucier, G.; Walter, C.; Rizkalla, S.; Zia, P.; and Klein, G., 2011a, "Development of a Rational Design Methodology for Precast Concrete Slender Spandrel Beams, Part 1: Experimental Results," *PCI Journal*, V. 56, No. 2, Spring, pp. 88-112. doi: [10.15554/pci.03012011.88.112](https://doi.org/10.15554/pci.03012011.88.112)

Lucier, G.; Walter, C.; Rizkalla, S.; Zia, P.; and Klein, G., 2011b, "Development of a Rational Design Methodology for Precast Concrete Slender Spandrel Beams, Part 2: Analysis and Design Guidelines," *PCI Journal*, V. 56, No. 4, Fall, pp. 106-133. doi: [10.15554/pci.09012011.106.133](https://doi.org/10.15554/pci.09012011.106.133)

Lutz, L., 1995, discussion to "Concrete Capacity Design (CCD) Approach for Fastening to Concrete," *ACI Structural Journal*, Nov.-Dec., pp. 791-792. Also, authors' closure, pp. 798-799. doi: [10.14359/5165518](https://doi.org/10.14359/5165518)

MacGregor, J. G., 1976, "Safety and Limit States Design for Reinforced Concrete," *Canadian Journal of Civil Engineering*, V. 3, No. 4, Dec., pp. 484-513. doi: [10.1139/l76-055](https://doi.org/10.1139/l76-055)

MacGregor, J. G., 1993, "Design of Slender Concrete Columns—Revisited," *ACI Structural Journal*, V. 90, No. 3, May-June, pp. 302-309. doi: [10.14359/4237](https://doi.org/10.14359/4237)

MacGregor, J. G., 1997, *Reinforced Concrete: Mechanics and Design*, third edition, Prentice Hall, Englewood Cliffs, NJ, 939 pp.

MacGregor, J. G., and Ghoneim, M. G., 1995, "Design for Torsion," *ACI Structural Journal*, V. 92, No. 2, Mar.-Apr., pp. 211-218. doi: [10.14359/1152](https://doi.org/10.14359/1152)

MacGregor, J. G., and Hage, S. E., 1977, "Stability Analysis and Design of Concrete Frames," *Journal of the Structural Division*, V. 103, Oct., pp. 1953-1970. doi: [10.14359/51685164](https://doi.org/10.14359/51685164)

MacGregor, J. G., and Hanson, J. M., 1969, "Proposed Changes in Shear Provisions for Reinforced and Prestressed Concrete Beams," *ACI Journal Proceedings*, V. 66, No. 4, Apr., pp. 276-288. doi: [10.14359/7360](https://doi.org/10.14359/7360)

MacGregor, J. G.; Breen, J. E.; and Pfrang, E. O., 1970, "Design of Slender Concrete Columns," *ACI Journal Proceedings*, V. 67, No. 1, Jan., pp. 6-28. doi: [10.14359/7254](https://doi.org/10.14359/7254)

Malhotra, V. M., 1976, *Testing Hardened Concrete: Nondestructive Methods*, *ACI Monograph No. 9*, American Concrete Institute/Iowa State University Press, Farmington Hills, MI, 188 pp.

Malhotra, V. M., 1977, "Contract Strength Requirements—Cores Versus In Situ Evaluation," *ACI Journal Proceedings*, V. 74, No. 4, Apr., pp. 163-172. doi: [10.14359/10998](https://doi.org/10.14359/10998)

Mander, T. J., and Matamoros, A. B., 2019, "Constitutive Modeling and Overstrength Factors for Reinforcing Steel,"

- ACI Structural Journal*, V. 116, No. 3, May-June, pp. 219-232. doi: [10.14359/51713320](https://doi.org/10.14359/51713320)
- Mansour, M., and Hsu, T., 2005, "Behavior of Reinforced Concrete Elements under Cyclic Shear. II: Theoretical Model," *Journal of Structural Engineering*, V. 131, No. 11, pp. 54-65. doi: [10.1061/\(ASCE\)0733-9445\(2005\)131:1\(54\)](https://doi.org/10.1061/(ASCE)0733-9445(2005)131:1(54))
- Manuals and Reports on Engineering Practice, 2020, "Design and Performance of Tall Buildings for Wind," MOP 143, American Society of Civil Engineers. doi: [10.1061/9780784415658](https://doi.org/10.1061/9780784415658)
- Marti, P., 1985, "Basic Tools of Reinforced Concrete Beam Design," *ACI Journal Proceedings*, V. 82, No. 1, Jan.-Feb., pp. 46-56. doi: [10.14359/10314](https://doi.org/10.14359/10314)
- Martin, L., and Korkosz, W., 1995, "Strength of Prestressed Concrete Members at Sections Where Strands Are Not Fully Developed," *PCI Journal*, V. 40, No. 5, Sept.-Oct., pp. 58-66. doi: [10.15554/pcij.09011995.58.66](https://doi.org/10.15554/pcij.09011995.58.66)
- Mast, R. F., 1968, "Auxiliary Reinforcement in Concrete Connections," *Journal of the Structural Division*, V. 94, June, pp. 1485-1504. doi: [10.14359/16710](https://doi.org/10.14359/16710)
- Mast, R. F., 1992, "Unified Design Provision for Reinforced and Prestressed Concrete Flexural and Compression Members," *ACI Structural Journal*, V. 89, No. 2, Mar.-Apr., pp. 185-199. doi: [10.14359/3209](https://doi.org/10.14359/3209)
- Mast, R. F., 1998, "Analysis of Cracked Prestressed Concrete Sections: A Practical Approach," *PCI Journal*, V. 43, No. 4, July-Aug., pp. 80-91. doi: [10.15554/pcij.07011998.80.91](https://doi.org/10.15554/pcij.07011998.80.91)
- Mast, R. F., 2001, "Vibration of Precast Prestressed Concrete Floors," *PCI Journal*, V. 46, No. 6, pp. 76-86. doi: [10.15554/pcij.11012001.76.86](https://doi.org/10.15554/pcij.11012001.76.86)
- Mathey, R. G., and Clifton, J. R., 1976, "Bond of Coated Reinforcing Bars in Concrete," *Journal of the Structural Division*, V. 102, Jan., pp. 215-228. doi: [10.14359/16871](https://doi.org/10.14359/16871)
- Mattock, A. H., 1959, "Redistribution of Design Bending Moments in Reinforced Concrete Continuous Beams," *Proceedings—Institution of Civil Engineers*, V. 13, No. 1, pp. 35-46. doi: [10.1680/jicep.1959.12087](https://doi.org/10.1680/jicep.1959.12087)
- Mattock, A. H., 1974, "Shear Transfer in Concrete Having Reinforcement at an Angle to the Shear Plane," *Shear in Reinforced Concrete*, SP-42, American Concrete Institute, Farmington Hills, MI, pp. 17-42. doi: [10.14359/18149](https://doi.org/10.14359/18149)
- Mattock, A. H., 1977, discussion of "Considerations for the Design of Precast Concrete Bearing Wall Buildings to Withstand Abnormal Loads," by PCI Committee on Precast Concrete Bearing Wall Buildings, *PCI Journal*, V. 22, No. 3, May-June, pp. 105-106. doi: [10.14359/51685223](https://doi.org/10.14359/51685223)
- Mattock, A., 1987, "Anchorage of Stirrups in a Thin Cast-in-Place Topping," *PCI Journal*, V. 32, No. 6, Nov.-Dec., pp. 70-85. doi: [10.15554/pcij.11011987.70.85](https://doi.org/10.15554/pcij.11011987.70.85)
- Mattock, A. H., 2001, "Shear Friction and High-Strength Concrete," *ACI Structural Journal*, V. 98, No. 1, Jan.-Feb., pp. 50-59. doi: [10.14359/10146](https://doi.org/10.14359/10146)
- Mattock, A. H., and Hawkins, N. M., 1972, "Shear Transfer in Reinforced Concrete—Recent Research," *PCI Journal*, V. 17, No. 2, Mar.-Apr., pp. 55-75. doi: [10.15554/pcij.03011972.55.75](https://doi.org/10.15554/pcij.03011972.55.75)
- Mattock, A. H., and Shen, J. F., 1992, "Joints between Reinforced Concrete Members of Similar Depth," *ACI Structural Journal*, V. 89, No. 3, pp. 290-295. doi: [10.14359/3235](https://doi.org/10.14359/3235)
- Mattock, A. H.; Chen, K. C.; and Soongswang, K., 1976a, "The Behavior of Reinforced Concrete Corbels," *PCI Journal*, V. 21, No. 2, Mar.-Apr., pp. 52-77. doi: [10.15554/pcij.03011976.52.77](https://doi.org/10.15554/pcij.03011976.52.77)
- Mattock, A. H.; Johal, L.; and Chow, H. C., 1975, "Shear Transfer in Reinforced Concrete with Moment or Tension Acting Across the Shear Plane," *PCI Journal*, V. 20, No. 4, July-Aug., pp. 76-93. doi: [10.15554/pcij.07011975.76.93](https://doi.org/10.15554/pcij.07011975.76.93)
- Mattock, A. H.; Kriz, L. B.; and Hognestad, E., 1961, "Rectangular Concrete Stress Distribution in Ultimate Strength Design," *ACI Journal Proceedings*, V. 57, No. 8, Feb., pp. 875-928. doi: [10.14359/8051](https://doi.org/10.14359/8051)
- Mattock, A. H.; Li, W. K.; and Wang, T. C., 1976b, "Shear Transfer in Lightweight Reinforced Concrete," *PCI Journal*, V. 21, No. 1, Jan.-Feb., pp. 20-39. doi: [10.15554/pcij.01011976.20.39](https://doi.org/10.15554/pcij.01011976.20.39)
- Mattock, A. H.; Yamazaki, J.; and Kattula, B. T., 1971, "Comparative Study of Prestressed Concrete Beams, with and without Bond," *ACI Journal Proceedings*, V. 68, No. 2, Feb., pp. 116-125. doi: [10.14359/11298](https://doi.org/10.14359/11298)
- Megally, S., and Ghali, A., 2002, "Punching Shear Design of Earthquake-Resistant Slab-Column Connections," *ACI Structural Journal*, V. 97, No. 5, Sept.-Oct., pp. 720-730. doi: [10.14359/8807](https://doi.org/10.14359/8807)
- Meinheit, D. F., and Jirsa, J. O., 1977, "Shear Strength of Reinforced Concrete Beam-Column Joints," *Report No. 77-1*, Department of Civil Engineering, Structures Research Laboratory, University of Texas at Austin, Austin, TX, Jan., 291 pp. doi: [10.14359/51685433](https://doi.org/10.14359/51685433)
- Meinheit, D. F., and Jirsa, J. O., 1981, "Shear Strength of R/C Beam-Column Connections," *Journal of the Structural Division*, V. 107, Nov., pp. 2227-2244.
- Menn, C., 1986, *Prestressed Concrete Bridges*, Birkhäuser, 535 pp.
- Mirza, S. A., 1990, "Flexural Stiffness of Rectangular Reinforced Concrete Columns," *ACI Structural Journal*, V. 87, No. 4, July-Aug., pp. 425-435. doi: [10.14359/3056](https://doi.org/10.14359/3056)
- Mirza, S. A.; Lee, P. M.; and Morgan, D. L., 1987, "ACI Stability Resistance Factor for RC Columns," *Journal of Structural Engineering*, V. 113, No. 9, Sept., pp. 1963-1976. doi: [10.1061/\(ASCE\)0733-9445\(1987\)113:9\(1963\)](https://doi.org/10.1061/(ASCE)0733-9445(1987)113:9(1963))
- Moehle, J. P., 1996, "Seismic Design Considerations for Flat Plate Construction," *Mete A. Sozen Symposium: A Tribute from his Students*, SP-162, J. K. Wight and M. E. Kreger, eds., American Concrete Institute, Farmington Hills, MI, pp. 1-35. doi: [10.14359/1509](https://doi.org/10.14359/1509)
- Moehle, J. P., 1988, "Strength of Slab-Column Edge Connections," *ACI Structural Journal*, V. 85, No. 1, Jan.-Feb., pp. 89-98. doi: [10.14359/2995](https://doi.org/10.14359/2995)

Moehle, J. P., 1992, "Displacement-Based Design of RC Structures Subjected to Earthquakes," *Earthquake Spectra*, V. 8, No. 3, Aug., pp. 403-428. doi: [10.1193/1.1585688](https://doi.org/10.1193/1.1585688)

Moehle, J. P., and Cavanagh, T., 1985, "Confinement Effectiveness of Cross-ties in RC," *Journal of Structural Engineering*, V. 111, No. 10, pp. 2105-2120. doi: [10.1061/\(ASCE\)0733-9445\(1985\)111:10\(2105\)](https://doi.org/10.1061/(ASCE)0733-9445(1985)111:10(2105))

Moehle, J. P.; Ghodsi, T.; Hooper, J. D.; Fields, D. C.; and Gedhada, R., 2011, "Seismic Design of Cast-in-Place Concrete Special Structural Walls and Coupling Beams: A Guide for Practicing Engineers," *NEHRP Seismic Design Technical Brief No. 6*, National Institute of Standards and Technology, Gaithersburg, MD, 41 pp.

Moehle, J. P.; Hooper, J. D.; Kelly, D. J.; and Meyer, T. R., 2010, "Seismic Design of Cast-in-Place Concrete Diaphragms, Chords, and Collectors: A Guide for Practicing Engineers," *NEHRP Seismic Design Technical Brief No. 3*, National Institute of Standards and Technology, Gaithersburg, MD, 33 pp.

Mitchell, D., and Collins, M. P., 1976, "Detailing for Torsion," *ACI Journal Proceedings*, V. 73, No. 9, Sept., pp. 506-511. doi: [10.14359/11091](https://doi.org/10.14359/11091)

Mitchell, D., and Cook, W. D., 1984, "Preventing Progressive Collapse of Slab Structures," *Journal of Structural Engineering*, V. 110, No. 7, July, pp. 1513-1532. doi: [10.1061/\(ASCE\)0733-9445\(1984\)110:7\(1513\)](https://doi.org/10.1061/(ASCE)0733-9445(1984)110:7(1513))

Mojtahedi, S., and Gamble, W. L., 1978, "Ultimate Steel Stresses in Unbonded Prestressed Concrete," *Journal of the Structural Division*, V. 104, No. ST7, July, pp. 1159-1165. doi: [10.14359/19419](https://doi.org/10.14359/19419)

Mones, R., and Brena, S., 2013, "Hollow-Core Slabs with Cast-in-Place Concrete Toppings: A Study of Interfacial Shear Strength," *PCI Journal*, V. 58, No. 3, Summer, pp. 124-141. doi: [10.15554/pcij.06012013.124.141](https://doi.org/10.15554/pcij.06012013.124.141)

Mphonde, A. G., and Frantz, G. C., 1984, "Shear Tests of High- and Low-Strength Concrete Beams without Stirrups," *ACI Journal Proceedings*, V. 81, No. 4, July-Aug., pp. 350-357. doi: [10.14359/10690](https://doi.org/10.14359/10690)

Muguruma, H., and Watanabe, F., 1990, "Ductility Improvement of High-Strength Concrete Columns with Lateral Confinement," *Proceedings of the Second International Symposium on High-Strength Concrete*, SP-121, American Concrete Institute, Farmington Hills, MI, pp. 47-60. doi: [10.14359/2783](https://doi.org/10.14359/2783)

Mullins, D. and Parker, D., 2019, "Recommendations for Structural Grouting," *Structure Magazine*, Sept., pp. 20-22

Muttoni, A., 2008, "Punching Shear Strength of Reinforced Concrete Slabs without Shear Reinforcement," *ACI Structural Journal*, V. 105, No. 4, July-Aug., pp. 440-450. doi: [10.14359/19858](https://doi.org/10.14359/19858)

Muttoni, A.; Schwartz, J.; and Thürlimann, B., 1997, *Design of Concrete Structures with Stress Fields*, Birkhauser, Boston, MA, 143 pp.

Nakaki, S. D.; Stanton, J. F.; and Sritharan, S., 1999, "An Overview of the PRESS Five-Story Precast Test Building,"

PCI Journal, V. 44, No. 2, Apr., pp. 26-39. doi: [10.15554/pcij.03011999.26.39](https://doi.org/10.15554/pcij.03011999.26.39)

National Oceanic and Atmospheric Administration, National Hurricane Center, <https://www.nhc.noaa.gov> (accessed August 12, 2024)

National Oceanic and Atmospheric Administration, U.S. Tornadoes, <https://www.ncei.noaa.gov/access/monitoring/tornadoes/> (accessed August 12, 2024)

National Transportation Safety Board (NTSB), 2007, "Ceiling Collapse in the Interstate 90 Connector Tunnel, Boston, Massachusetts, July 10, 2006," Highway Accident Report NTSB/HAR-07/02, Washington, DC, 120 pp.

NEHRP, 1994, "The NEHRP Recommended Provisions for Seismic Regulations for New Buildings," Building Seismic Safety Council, Washington, DC.

Newlon, H. J., and Ozol, A., 1969, "Delayed Expansion of Concrete Delivered by Pumping through Aluminum Pipe Line," Concrete Case Study No. 20; Virginia Highway Research Council, Charlottesville, VA, Oct., 39 pp. doi: [10.14359/16493](https://doi.org/10.14359/16493)

Nichols, J. R., 1914, "Static Limitations upon the Steel Requirement in Reinforced Concrete Flat Slab Floors," *Transactions of the American Society of Civil Engineers*, V. 77, pp. 1670-1736.

Nilsson, I. H. E., and Losberg, A., 1976, "Reinforced Concrete Corners and Joints Subjected to Bending Moment," *Journal of the Structural Division*, V. 102, June, pp. 1229-1254. doi: [10.14359/51685465](https://doi.org/10.14359/51685465)

NIST, 2014, "Use of High-Strength Reinforcement in Earthquake-Resistant Concrete Structures," NIST GCR 14-917-30, National Institute of Standards and Technology, Gaithersburg, MD.

NIST, 2016a, "Community Resilience Planning Guide for Buildings and Infrastructure Systems," Special Publication 1190, V. I, <http://dx.doi.org/10.6028/NIST.SP.1190v1>, accessed August 12, 2024. 126 pp.

NIST, 2016b, "Community Resilience Planning Guide for Buildings and Infrastructure Systems," Special Publication 1190, V. II, <http://dx.doi.org/10.6028/NIST.SP.1190v2>, accessed August 12, 2024. 274 pp.

NIST, 2017a, "Guidelines for Nonlinear Structural Analysis for Design of Buildings, Part I—General," NIST GCR 17-917-46v1, prepared by the Applied Technology Council for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST, 2017b, "Guidelines for Nonlinear Structural Analysis for Design of Buildings, Part IIb—Concrete Moment Frames," NIST GCR 17-917-46v3, prepared by the Applied Technology Council for the National Institute of Standards and Technology, Gaithersburg, MD.

Nowak, A. S.; Rakoczy, A. M.; and Szeliga, E. K., 2011, "Revised Statistical Resistance Models for R/C Structural Components," *Andy Scanlon Symposium on Serviceability and Safety of Concrete Structures, Research to Practice*,

- SP-284, American Concrete Institute, Farmington Hills, MI, pp. 1-16. doi: [10.14359/51683801](https://doi.org/10.14359/51683801)
- Odello, R. J., and Mehta, B. M., 1967, "Behavior of a Continuous Prestressed Concrete Slab with Drop Panels," *Graduate Student Research Report*, Division of Structural Engineering and Structural Mechanics, University of California, Berkeley, CA, 63 pp. doi: [10.14359/19581](https://doi.org/10.14359/19581)
- Oesterle, R. G., 1997, "The Role of Concrete Cover in Crack Control Criteria and Corrosion Protection," PCA R&D Serial No. 2054, Portland Cement Association, Skokie, IL, 87 pp. doi: [10.14359/16540](https://doi.org/10.14359/16540)
- Olesen, S. E.; Sozen, M. A.; and Siess, C. P., 1967, "Investigation of Prestressed Reinforced Concrete for Highway Bridges, Part IV: Strength in Shear of Beams with Web Reinforcement," *Bulletin* No. 493, Engineering Experiment Station, University of Illinois, Urbana, IL, 115 pp. doi: [10.14359/16580](https://doi.org/10.14359/16580)
- Olsen, J.; Pregartner, T.; and Lamanna, A. J., 2012, "Basis for Design of Screw Anchors in Concrete," *ACI Structural Journal*, V. 109, No. 4, July-Aug., pp. 559-568. doi: [10.14359/51683875](https://doi.org/10.14359/51683875)
- Orangun, C. O.; Jirsa, J. O.; and Breen, J. E., 1977, "A Reevaluation of Test Data on Development Length and Splices," *ACI Journal Proceedings*, V. 74, No. 3, Mar., pp. 114-122. doi: [10.14359/10993](https://doi.org/10.14359/10993)
- Ospina, C. E., and Alexander, S. D. B., 1998, "Transmission of Interior Concrete Column Loads through Floors," *Journal of Structural Engineering*, V. 124, No. 6, June, pp. 602-610. doi: [10.1061/\(ASCE\)0733-9445\(1998\)124:6\(602\)](https://doi.org/10.1061/(ASCE)0733-9445(1998)124:6(602))
- Ožbolt, J.; Eligehausen, R.; Periškić, G.; and Mayer, U., 2007, "3D FE Analysis of Anchor Bolts with Large Embedment Depths," *Engineering Fracture Mechanics*, V. 74, No. 1-2, Jan., pp. 168-178. doi: [10.1016/j.engfracmech.2006.01.019](https://doi.org/10.1016/j.engfracmech.2006.01.019)
- Ozcebe, G.; Ersoy, U.; and Tankut, T., 1999, "Evaluation of Minimum Shear Reinforcement for Higher Strength Concrete," *ACI Structural Journal*, V. 96, No. 3, May-June, pp. 361-368. doi: [10.14359/51701132](https://doi.org/10.14359/51701132)
- Ozyildirim, C., and Halstead, W., 1988, "Resistance to Chloride Ion Penetration of Concretes Containing Fly Ash, Silica Fume, or Slag," *Permeability of Concrete*, SP-108, American Concrete Institute, Farmington Hills, MI, pp. 35-61. doi: [10.14359/2158](https://doi.org/10.14359/2158)
- Pacific Earthquake Engineering Center, 2017, "Guidelines for Performance-Based Seismic Design of Tall Buildings," Report No. 2017/06, University of California, Berkeley, CA.
- Palieraki, V.; Vintzileou, E.; and Silva, J., 2022, "Interface Shear Strength under Monotonic and Cyclic Loading," *ACI Structural Journal*, V. 119, No. 3, May, pp. 17-26. doi: [10.14359/51734519](https://doi.org/10.14359/51734519)
- Palmieri, L.; Saqan, E.; French, C.; and Kreger, M., 1996, "Ductile Connections for Precast Concrete Frame Systems," *Mete A. Sozen Symposium: A Tribute from his Students*, SP-162, American Concrete Institute, Farmington Hills, MI, pp. 315-335. doi: [10.14359/1515](https://doi.org/10.14359/1515)
- Pan, A., and Moehle, J. P., 1989, "Lateral Displacement Ductility of Reinforced Concrete Flat Plates," *ACI Structural Journal*, V. 86, No. 3, May-June, pp. 250-258. doi: [10.14359/2889](https://doi.org/10.14359/2889)
- Park, R., and Paulay, T., 1975, *Reinforced Concrete Structures*, Wiley-Interscience, New York, 769 pp.
- Park, R., and Thompson, K. J., 1977, "Cyclic Load Tests on Prestressed and Partially Prestressed Beam-Column Joints," *PCI Journal*, V. 22, No. 5, pp. 84-110. doi: [10.15554/pcij.09011977.84.110](https://doi.org/10.15554/pcij.09011977.84.110)
- Parra-Montesinos, G. J., 2006, "Shear Strength of Beams with Deformed Steel Fibers," *Concrete International*, V. 28, No. 11, Nov., pp. 57-66. doi: [10.14359/18323](https://doi.org/10.14359/18323)
- Paulay, T., and Binney, J. R., 1974, "Diagonally Reinforced Coupling Beams of Shear Walls," *Shear in Reinforced Concrete*, SP-42, American Concrete Institute, Farmington Hills, MI, pp. 579-598. doi: [10.14359/17302](https://doi.org/10.14359/17302)
- Paulay, T., and Priestley, M. J. N., 1992, *Seismic Design of Reinforced Concrete and Masonry Buildings*, John Wiley and Sons, New York, 768 pp.
- Paulson, C.; Graham, S. K.; and Rautenberg, J. M., 2013, "Determination of Yield Strength for Nonprestressed Steel Reinforcement," Charles Pankow Foundation RGA #04-13, WJE No. 2013.4171, Wiss, Janney, Elstner Associates, Inc., Pasadena, CA, Dec. 31, 100 pp. doi: [10.14359/51702081](https://doi.org/10.14359/51702081)
- Paultre, P., and Légeron, F., 2008, "Confinement Reinforcement Design for Reinforced Concrete Columns," *Journal of Structural Engineering*, V. 134, No. 5, pp. 738-749. doi: [10.1061/\(ASCE\)0733-9445\(2008\)134:5\(738\)](https://doi.org/10.1061/(ASCE)0733-9445(2008)134:5(738))
- Pauw, A., 1960, "Static Modulus of Elasticity of Concrete as Affected by Density," *ACI Journal Proceedings*, V. 57, No. 6, Dec., pp. 679-687. doi: [10.14359/17302](https://doi.org/10.14359/17302)
- PCA, 1946, "Design of Deep Girders," IS079D, Portland Cement Association, Skokie, IL, 10 pp. doi: [10.14359/51685151](https://doi.org/10.14359/51685151)
- PCA, 1972, *Handbook of Frame Constants*, Portland Cement Association, Skokie, IL, 1972, 34 pp. doi: [10.14359/16511](https://doi.org/10.14359/16511)
- PCA, 1980, "Design and Construction of Large-Panel Concrete Structures," six reports, 762 pp., EB 100D; three studies, 300 pp., 1980, EB 102D, 1976-1980, Portland Cement Association, Skokie, IL.
- PCA, 2011, *Design and Control of Concrete Mixtures*, 15th edition, Portland Cement Association, Skokie, IL, 444 pp.
- PCA, n.d., "Protecting Lives and Property: Making Green Buildings 'Functionally Resilient,'" Portland Cement Association, Skokie, IL, 19 pp.
- PCI, 2019, "Recommended Practice for Design, Manufacture, and Installation of Prestressed Concrete Piling," *PCI Journal*, V. 64, No. 4, July-Aug., pp. 124-141.
- PCI Committee on Precast Concrete Bearing Wall Buildings, 1976, "Considerations for the Design of Precast

Concrete Bearing Wall Buildings to Withstand Abnormal Loads,” *PCI Journal*, V. 21, No. 2, Mar.-Apr., pp. 18-51. doi: [10.14359/16702](https://doi.org/10.14359/16702)

Peiris, C., and Ghali, A., 2012, “Flexural Reinforcement Essential for Punching Shear Resistance of Slabs,” *Recent Developments in Reinforced Concrete Slab Analysis, Design and Serviceability*, SP-287, American Concrete Institute, Farmington Hills, MI, May, pp. 1-16. doi: [10.14359/51683860](https://doi.org/10.14359/51683860)

Perez, F. J.; Pessiki, S.; Sause, R.; and Lu, L.-W., 2003, “Lateral Load Tests of Unbonded Post-Tensioned Precast Concrete Walls,” *Large Scale Structural Testing*, SP-211, American Concrete Institute, Farmington Hills, MI, pp. 161-182. doi: [10.14359/12589](https://doi.org/10.14359/12589)

Pessiki, S.; Graybeal, B.; and Mudlock, M., 2001, “Proposed Design of High-Strength Spiral Reinforcement in Compression Members,” *ACI Structural Journal*, V. 98, No. 6, Nov.-Dec., pp. 799-810. doi: [10.14359/10747](https://doi.org/10.14359/10747)

Pfeifer, D. W., and Nelson, T. A., 1983, “Tests to Determine the Lateral Distribution of Vertical Loads in a Long-Span Hollow-Core Floor Assembly,” *PCI Journal*, V. 28, No. 6, Nov.-Dec., pp. 42-57. doi: [10.15554/pcij.11011983.42.57](https://doi.org/10.15554/pcij.11011983.42.57)

Pfister, J. F., 1964, “Influence of Ties on the Behavior of Reinforced Concrete Columns,” *ACI Journal Proceedings*, V. 61, No. 5, May, pp. 521-537. doi: [10.14359/7795](https://doi.org/10.14359/7795)

Pfister, J. F., and Mattock, A. H., 1963, “High Strength Bars as Concrete Reinforcement, Part 5: Lapped Splices in Concentrically Loaded Columns,” *PCA Research and Development Laboratories Bulletin*, V. 5, No. 2, May, pp. 27-40. doi: [10.14359/51685279](https://doi.org/10.14359/51685279)

Popov, E. P.; Bertero, V. V.; and Krawinkler, H., 1972, “Cyclic Behavior of Three R/C Flexural Members with High Shear,” *EERC Report No. 72-5*, Earthquake Engineering Research Center, University of California, Berkeley, Berkeley, CA, Oct., 91 pp. doi: [10.14359/19326](https://doi.org/10.14359/19326)

Primavera, E. J.; Pinelli, J.-P.; and Kalajian, E. H., 1997, “Tensile Behavior of Cast-in-Place and Undercut Anchors in High-Strength Concrete,” *ACI Structural Journal*, V. 94, No. 5, Sept.-Oct., pp. 583-594. doi: [10.14359/507](https://doi.org/10.14359/507)

Priestley, M.; Calvi, G.; and Kowalsky, M., 2007, *Displacement-Based Seismic Design of Structures*, IUSS Press, Italy.

Priestley, M. J. N.; Sritharan, S.; Conley, J.; and Pampanin, S., 1999, “Preliminary Results and Conclusions from the PRESSS Five-Story Precast Concrete Test Building,” *PCI Journal*, V. 44, No. 6, Nov.-Dec., pp. 42-67. doi: [10.15554/pcij.11011999.42.67](https://doi.org/10.15554/pcij.11011999.42.67)

Powers, T. C., 1975, “Freezing Effects in Concrete,” *Durability of Concrete*, SP-47, American Concrete Institute, Farmington Hills, MI, pp. 1-11. doi: [10.14359/17603](https://doi.org/10.14359/17603)

Pugh, J. S.; Lowes, L. N.; and Lehman, D. E., 2017, “Accurate Methods for Elastic Seismic Demand Analysis of Reinforced Concrete Walled Buildings,” *Journal of Structural Engineering*, V. 143, No. 8, Aug., pp. 1-10. doi: [10.1061/\(ASCE\)ST.1943-541X.0001669](https://doi.org/10.1061/(ASCE)ST.1943-541X.0001669)

Puranam, A., 2018, “Strength and Serviceability of Concrete Elements Reinforced with High-Strength Steel,” PhD dissertation, Purdue University, West Lafayette, IN.

Puranam, A., and Pujol, S., 2017, “Minimum Flexural Reinforcement in Reinforced Concrete Walls,” 16th WCEE, Santiago, Chile.

Rabbat, B. G.; Kaar, P. H.; Russell, H. G.; and Bruce Jr., R. N., 1979, “Fatigue Tests of Pretensioned Girders with Blanketed and Draped Strands,” *PCI Journal*, V. 24, No. 4, July-Aug., pp. 88-114. doi: [10.15554/pcij.07011979.88.114](https://doi.org/10.15554/pcij.07011979.88.114)

Reineck, K.-H., ed., 2002, *Strut-and-Tie Models*, SP-208, American Concrete Institute, Farmington Hills, MI, 250 pp.

Reineck, K.-H., and Novak, L., C., eds., 2010, *Further Examples for the Design of Structural Concrete with Strut-and-Tie Models*, SP-273, American Concrete Institute, Farmington Hills, MI, 288 pp.

Reineck, K., and Todisco, L., 2014, “Database of Shear Tests for Non-slender Reinforced Concrete Beams without Stirrups,” *ACI Structural Journal*, V. 111, No. 6, Nov.-Dec., pp. 1363-1372. doi: [10.14359/51686820](https://doi.org/10.14359/51686820)

Restrepo, J. I., 2002, “New Generation of Earthquake Resisting Systems,” *Proceedings*, First fib Congress, Session 6, Osaka, Japan, Oct., pp. 41-60.

Restrepo, J. I.; Park, R.; and Buchanan, A. H., 1995a, “Tests on Connections of Earthquake Resisting Precast Reinforced Concrete Perimeter Frames of Buildings,” *PCI Journal*, V. 40, No. 4, July-Aug., pp. 44-61. doi: [10.15554/pcij.07011995.44.61](https://doi.org/10.15554/pcij.07011995.44.61)

Restrepo, J.; Park, R.; and Buchanan, A. H., 1995b, “Design of Connections of Earthquake Resisting Precast Reinforced Concrete Perimeter Frames,” *PCI Journal*, V. 40, No. 5, pp. 68-80. doi: [10.15554/pcij.09011995.68.80](https://doi.org/10.15554/pcij.09011995.68.80)

Richart, F. E., 1933, “Reinforced Concrete Column Investigation—Tentative Final Report of Committee 105,” *ACI Journal Proceedings*, V. 29, No. 2, Feb., pp. 275-282. doi: [10.14359/8273](https://doi.org/10.14359/8273)

Richart, F. E.; Brandzaeg, A.; and Brown, R. L., 1929, “The Failure of Plain and Spirally Reinforced Concrete in Compression,” *Bulletin No. 190*, University of Illinois Engineering Experiment Station, Urbana, IL, Apr., 74 pp. doi: [10.14359/19264](https://doi.org/10.14359/19264)

Rivera-Cruz, J. A.; Breña, S. F.; Gerasimidis, S.; and Clouston, P. L., 2021, “Behavior of Perimeter Beams with Integrity Reinforcing Details of Low Seismic Regions,” *ACI Structural Journal*, V. 118, No. 6, Nov., pp. 203-214. doi: [10.14359/51732997](https://doi.org/10.14359/51732997)

Roberts-Wollmann, C. L., and Wollmann, G. P., 2008, “Bearing Strength of Unbonded Monostrand Post-Tensioning Anchors in Slab Edges,” *PTI Journal*, V. 6, No. 2, Aug., pp. 29-39.

Rodriguez, M.; Restrepo, J. I.; and Carr, A. J., 2002, “Earthquake Induced Floor Horizontal Accelerations in Buildings,” *Earthquake Engineering & Structural Dynamics*, V. 31, No. 3, Mar., pp. 693-718. doi: [10.1002/eqe.149](https://doi.org/10.1002/eqe.149)

Rogowsky, D. M., and MacGregor, J. G., 1986, "Design of Reinforced Concrete Deep Beams," *Concrete International*, V. 8, No. 8, Aug., pp. 46-58. doi: [10.14359/51685228](https://doi.org/10.14359/51685228)

Rogowsky, D., and Wight, K., 2010, "Load Factors are Load Factors," *Concrete International*, V. 32, No. 7, July, pp. 75-76.

Rojas-Leon, M.; Abdullah, S.; Kolozvari, K.; and Wallace, J., 2024, "New Equations to Estimate Reinforced Concrete Wall Shear Strength Derived from Machine Learning and Statistical Methods," *ACI Structural Journal*, V. 121, No. 1, Jan.-Feb., pp. 89-104. doi: [10.14359/51739187](https://doi.org/10.14359/51739187)

Roller, J. J., and Russell, H. G., 1990, "Shear Strength of High-Strength Concrete Beams with Web Reinforcement," *ACI Structural Journal*, V. 87, No. 2, Mar.-Apr., pp. 191-198. doi: [10.14359/2682](https://doi.org/10.14359/2682)

Rose, D. R., and Russell, B. W., 1997, "Investigation of Standardized Tests to Measure the Bond Performance of Prestressing Strand," *PCI Journal*, V. 42, No. 4, July-Aug., pp. 56-80. doi: [10.15554/pci.07011997.56.80](https://doi.org/10.15554/pci.07011997.56.80)

Rotz and Reifschneider, 1984, "Experimental Evaluation of Steel Embedments Subjected to Combined Axial and Shear," Bechtel Power Corp., Ann Arbor, MI, 100 pp.

Ruggiero, D. M.; Bentz, E. C.; Calvi, G. M.; and Collins, M. P., 2016, "Shear Response under Reversed Cyclic Loading," *ACI Structural Journal*, V. 113, No. 6, Nov.-Dec., pp. 1313-1324. doi: [10.14359/51689033](https://doi.org/10.14359/51689033)

Russell, B. W., and Burns, N. H., 1996, "Measured Transfer Lengths of 0.5 and 0.6 in. Strands in Pretensioned Concrete," *PCI Journal*, V. 41, No. 5, Sept.-Oct., pp. 44-65. doi: [10.15554/pci.09011996.44.65](https://doi.org/10.15554/pci.09011996.44.65)

Rutledge, S., and DeVries, R. A., 2002, "Development of D45 Wire in Concrete," *Report*, School of Civil and Environmental Engineering, Oklahoma State University, Stillwater, OK, Jan., 28 pp.

Ryan, J. C., and Mays, T., 2021, "Axial Load Limit Considerations for 14 in. Square Prestressed Concrete Piles," *PCI Journal*, V. 66, No. 6, pp. 33-50. doi: [10.15554/pci.66.6-02](https://doi.org/10.15554/pci.66.6-02)

Saatcioglu, M., and Razvi, S. R., 2002, "Displacement-Based Design of Reinforced Concrete Columns for Confinement," *ACI Structural Journal*, V. 99, No. 1, Jan.-Feb., pp. 3-11. doi: [10.14359/11030](https://doi.org/10.14359/11030)

Sabnis, G. M., Meyers, B. L.; and Roll, F., eds., 1974, *Deflections of Concrete Structures*, SP-43, American Concrete Institute, Farmington Hills, MI, 637 pp.

Saemann, J. C., and Washa, G. W., 1964, "Horizontal Shear Connections between Precast Beams and Cast-in-Place Slabs," *ACI Journal Proceedings*, V. 61, No. 11, Nov., pp. 1383-1409. doi: [10.14359/7832](https://doi.org/10.14359/7832). Also see discussion," *ACI Journal Proceedings*, V. 62, June 1965, pp. 1807-1810.

Sakai, K., and Sheikh, S. A., 1989, "What Do We Know about Confinement in Reinforced Concrete Columns? (A Critical Review of Previous Work and Code Provisions)," *ACI Structural Journal*, V. 86, No. 2, Mar.-Apr., pp. 192-207. doi: [10.14359/2705](https://doi.org/10.14359/2705)

Salmons, J. R., and McCrate, T. E., 1977, "Bond Characteristics of Untensioned Prestressing Strand," *PCI Journal*, V. 22, No. 1, Jan.-Feb., pp. 52-65. doi: [10.15554/pci.01011977.52.65](https://doi.org/10.15554/pci.01011977.52.65)

Sant, J. K., and Bletzacker, R. W., 1961, "Experimental Study of Lateral Stability of Reinforced Concrete Beams," *ACI Journal Proceedings*, V. 58, No. 6, Dec., pp. 713-736. doi: [10.14359/8004](https://doi.org/10.14359/8004)

Sason, A. S., 1992, "Evaluation of Degree of Rusting on Prestressed Concrete Strand," *PCI Journal*, V. 37, No. 3, May-June, pp. 25-30. doi: [10.15554/pci.05011992.25.30](https://doi.org/10.15554/pci.05011992.25.30)

SBC, 1999, "Standard Building Code," Southern Building Code Congress International, Inc., Birmingham, AL.

Scanlon, A., and Bischoff, P. H., 2008, "Shrinkage Restraint and Loading History Effects on Deflections of Flexural Members," *ACI Structural Journal*, V. 105, No. 4, July-Aug., pp. 498-506. doi: [10.14359/19864](https://doi.org/10.14359/19864)

Schießl, P., and Raupach, M., 1997, "Laboratory Studies and Calculations on the Influence of Crack Widths on Chloride-Induced Corrosion of Steel in Concrete," *ACI Materials Journal*, V. 94, No. 1, Jan.-Feb., pp. 56-62. doi: [10.14359/285](https://doi.org/10.14359/285)

Schlaich, J.; Schafer, K.; and Jennewein, M., 1987, "Toward a Consistent Design of Structural Concrete," *PCI Journal*, V. 32, No. 3, May-June, pp. 74-150. doi: [10.15554/pci.05011987.74.150](https://doi.org/10.15554/pci.05011987.74.150)

Scordelis, A. C., 1990, "Non-Linear Material, Geometric, and Time Dependent Analysis of Reinforced and Prestressed Concrete Shells," *Bulletin*, International Association for Shells and Spatial Structures, Madrid, Spain, No. 102, Apr., pp. 57-90. doi: [10.14359/51685392](https://doi.org/10.14359/51685392)

Scordelis, A. C.; Lin, T. Y.; and Itaya, R., 1959, "Behavior of a Continuous Slab Prestressed in Two Directions," *ACI Journal Proceedings*, V. 56, No. 6, Dec., pp. 441-459. doi: [10.14359/8105](https://doi.org/10.14359/8105)

Seegebrecht, G. W.; Litvan, A.; and And Gebler, S. H., 1989, "Durability of Dry-Mix Shotcrete," *Concrete International*, V. 11, No. 10, Oct., pp. 47-50. doi: [10.14359/2481](https://doi.org/10.14359/2481)

Segura, C. L., and Wallace, W. J., 2017, "Seismic Performance Limitations and Detailing of Slender RC Walls," *ACI Structural Journal*, V. 115, No. 3, May-June, pp. 849-859. doi: [10.14359/51701918](https://doi.org/10.14359/51701918)

Segura, C. L., and Wallace, J. W., 2018, "Impact of Geometry and Detailing on Drift Capacity of Slender Walls," *ACI Structural Journal*, V. 115, No. 3, May, pp. 885-895. doi: [10.14359/51702046](https://doi.org/10.14359/51702046)

SEAOC, 1996, "Recommended Lateral Force Requirements and Commentary," sixth edition, Seismology Committee of the Structural Engineers Association of California, Sacramento, CA, 504 pp.

Sezen, H.; Alcocer, S. M.; and Moehle, J. P., 2021, "Effective Depth of Rectangular and Circular Columns for Shear Strength Calculations," *Concrete International*, V. 43, No. 7, July, pp. 37-41.

Shaikh, A. F., and Branson, D. E., 1970, "Non-Tensioned Steel in Prestressed Concrete Beams," *PCI Journal*, V. 15, No. 1, Feb., pp. 14-36. doi: [10.15554/pcij.02011970.14.36](https://doi.org/10.15554/pcij.02011970.14.36)

Shaikh, A. F., and Yi, W., 1985, "In-Place Strength of Welded Headed Studs," *PCI Journal*, V. 30, No. 2, Mar.-Apr., pp. 56-81. doi: [10.15554/pcij.03011985.56.81](https://doi.org/10.15554/pcij.03011985.56.81)

Shao, Y.; Darwin, D.; O'Reilly, M.; Lequesne, R. D.; Ghimire, K.; and Hano, M., 2016, "Anchorage of Conventional and High-Strength Headed Reinforcing Bars," SM Report No. 117, University of Kansas Center for Research, Lawrence, KS, Aug., 334 pp. <https://kuscholarworks.ku.edu/handle/1808/21738>

Sharma, L. K.; Abdullah, W.; Niroula, S.; Budhathoki, N.; and Ghannoum, W. M., 2025, "Performance of Mechanical Couplers of High-Strength Reinforcing Bars under Inelastic Strain Demands," *ACI Structural Journal*, V. 122, No. 1, Jan., pp. 225-238. doi: [10.14359/51743341](https://doi.org/10.14359/51743341)

Shoaib, A.; Lubell, A. S.; and Bindiganavile, V. S., 2014, "Size Effect in Shear for Steel Fiber-Reinforced Concrete Members without Stirrups," *ACI Structural Journal*, V. 111, No. 5, Sept.-Oct., pp. 1081-1089. doi: [10.14359/51686813](https://doi.org/10.14359/51686813)

Simonen, K., 2014, *Life Cycle Assessment*, Routledge, Abingdon, Oxfordshire, 182 pp.

Sivakumar, B.; Gergely, P.; and White, R. N., 1983, "Suggestions for the Design of R/C Lapped Splices for Seismic Loading," *Concrete International*, V. 5, No. 2, Feb., pp. 46-50. doi: [10.14359/9145](https://doi.org/10.14359/9145)

Slavin, C. M., and Ghannoum, W. M., 2015, "Defining Structurally Acceptable Properties of High-Strength Steel Bars through Material and Column Testing, Part I: Material Testing Report," Charles Pankow Foundation RGA #05-14, Aug., 135 pp. doi: [10.14359/51702075](https://doi.org/10.14359/51702075)

Smith, K. N., and Vantsiotis, A. S., 1982, "Shear Strength of Deep Beams," *ACI Journal Proceedings*, V. 79, No. 3, May-June 1982, pp. 201-213. doi: [10.14359/10899](https://doi.org/10.14359/10899)

Smith, S. W., and Burns, N. H., 1974, "Post-Tensioned Flat Plate to Column Connection Behavior," *PCI Journal*, V. 19, No. 3, May-June, pp. 74-91. doi: [10.15554/pcij.05011974.74.91](https://doi.org/10.15554/pcij.05011974.74.91)

Sneed, L. H., and Ramirez, J. A., 2010, "Influence of Effective Depth on Shear Strength of Concrete Beams—Experimental Study," *ACI Structural Journal*, V. 107, No. 5, Sept.-Oct., pp. 554-562. doi: [10.14359/51663906](https://doi.org/10.14359/51663906)

Sokoli, D., and Ghannoum, W. M., 2016, "High-Strength Reinforcement in Columns under High Shear Stresses," *ACI Structural Journal*, V. 113, No. 3, May-June, pp. 605-614. doi: [10.14359/51688203](https://doi.org/10.14359/51688203)

Sokoli, D.; Hogsett, G.; Limantono, A.; Suselo, A.; Al-Tarafany, D.; and Ghannoum, W. M., 2019, "Acceptable Elongations and Low-Cycle Fatigue Performance for High-Strength Reinforcing Bars," *Final Report*, CPF Research Grant Agreement #03-16, Charles Pankow Foundation, Vancouver, WA, 213 pp.

Sperry, J.; Darwin, D.; O'Reilly, M.; Lepage, A.; Lequesne, R. D.; Matamoros, A.; Feldman, L. R.; Yasso, S.; Searle, N.;

DeRubeis, M.; and Ajaam, A., 2018, "Conventional and High-Strength Steel Hooked Bars: Detailing Effects," *ACI Structural Journal*, V. 115, No. 1, Jan., pp. 247-257. doi: [10.14359/51700920](https://doi.org/10.14359/51700920)

Sperry, J.; Darwin, D.; O'Reilly, M.; Lequesne, R. D.; Yasso, S.; Matamoros, A.; Feldman, L. R.; and Lepage, A., 2017b, "Conventional and High-Strength Hooked Bars—Part 2: Data Analysis," *ACI Structural Journal*, V. 114, No. 1, Jan.-Feb., pp. 267-276. doi: [10.14359/51689457](https://doi.org/10.14359/51689457)

Sperry, J.; Yasso, S.; Searle, N.; DeRubeis, M.; Darwin, D.; O'Reilly, M.; Matamoros, A.; Feldman, L.; Lepage, A.; Lequesne, R.; and Ajaam, A., 2017a, "Conventional and High-Strength Hooked Bars—Part 1: Anchorage Tests," *ACI Structural Journal*, V. 114, No. 1, Jan.-Feb., pp. 255-266. doi: [10.14359/51689456](https://doi.org/10.14359/51689456)

Spragg, R. P.; Castro, J.; Li, W.; Pour-Ghaz, M.; Huang, P.-T.; and Weiss, J., 2011, "Wetting and Drying of Concrete in the Using Aqueous Solutions Containing Deicing Salt," *Cement and Concrete Composites*, V. 33, No. 5, May, pp. 535-542. doi: [10.1016/j.cemconcomp.2011.02.009](https://doi.org/10.1016/j.cemconcomp.2011.02.009)

Sritharan, S.; Beyer, K.; Henry, R. S.; Chai, Y. H.; Kowalsky, M.; and Bull, D., 2014, "Understanding Poor Seismic Performance of Concrete Walls and Design Implications," *Earthquake Spectra*, V. 30, No. 1, pp. 307-334. doi: [10.1193/021713EQS036M](https://doi.org/10.1193/021713EQS036M)

Sritharan, S.; Cox, A. M.; Huang, J.; Suleiman, M.; and Arulmoli, K., 2016, "Minimum Confinement Reinforcement for Prestressed Concrete Piles and a Rational Seismic Design Framework," *PCI Journal*, V. 61, No. 1, pp. 51-69. doi: [10.15554/pcij.01012016.51.69](https://doi.org/10.15554/pcij.01012016.51.69)

Stanton, J. F., 1987, "Proposed Design Rules for Load Distribution in Precast Concrete Decks," *ACI Structural Journal*, V. 84, No. 5, Sept.-Oct., pp. 371-382. doi: [10.14359/1683](https://doi.org/10.14359/1683)

Stanton, J. F., 1992, "Response of Hollow-Core Floors to Concentrated Loads," *PCI Journal*, V. 37, No. 4, July-Aug., pp. 98-113. doi: [10.15554/pcij.07011992.98.113](https://doi.org/10.15554/pcij.07011992.98.113)

Stecich, J.; Hanson, J. M.; and Rice, P. F., 1984, "Bending and Straightening of Grade 60 Reinforcing Bars," *Concrete International*, V. 6, No. 8, Aug., pp. 14-23. doi: [10.14359/16496](https://doi.org/10.14359/16496)

Stone, W.; Cheok, G.; and Stanton, J., 1995, "Performance of Hybrid Moment-Resisting Precast Beam-Column Concrete Connections Subjected to Cyclic Loading," *ACI Structural Journal*, V. 92, No. 2, Mar.-Apr., pp. 229-249. doi: [10.14359/1145](https://doi.org/10.14359/1145)

Sugano, S.; Nagashima, T.; Kimura, H.; Tamura, A.; and Ichikawa, A., 1990, "Experimental Studies on Seismic Behavior of Reinforced Concrete Members of High Strength Concrete," *Proceedings of the Second International Symposium on High-Strength Concrete*, SP-121, American Concrete Institute, Farmington Hills, MI, pp. 61-87. doi: [10.14359/2791](https://doi.org/10.14359/2791)

Tan, K. H.; Kong, F. K.; Teng, S.; and Wang, L. W., 1997, "Effect of Web Reinforcement on High Strength Concrete

Deep Beams,” *ACI Structural Journal*, V. 94, No. 5, Sept.-Oct., pp 572-582. doi: [10.14359/506](https://doi.org/10.14359/506)

Taylor, C. P.; Cote, P. A.; and Wallace, J. W., 1998, “Design of Slender Reinforced Concrete Walls with Openings,” *ACI Structural Journal*, V. 95, No. 4, July-Aug., pp. 420-433. doi: [10.14359/558](https://doi.org/10.14359/558)

TBI, 2017, “Guidelines for Performance-Based Seismic Design of Tall Buildings,” *Report No. 2017/06*, Pacific Earthquake Engineering Center, University of California, Berkeley, Berkeley, CA, May, 147 pp.

Tepke, D.; Trejo, D.; and Isgor, B., eds., 2016, *Chloride Thresholds and Limits for New Construction*, SP-308, American Concrete Institute, Farmington Hills, MI.

Thompson, K. J., and Park, R., 1980, “Seismic Response of Partially Prestressed Concrete,” *Journal of the Structural Division*, V. 106, pp. 1755-1775.

Thompson, M. K.; Jirsa, J. O.; and Breen, J. E., 2006a, “CCT Nodes Anchored by Headed Bars—Part 2: Capacity of Nodes,” *ACI Structural Journal*, V. 103, No. 1, Jan.-Feb., pp. 65-73. doi: [10.14359/15087](https://doi.org/10.14359/15087)

Thompson, M. K.; Ledesma, A.; Jirsa, J. O.; and Breen, J. E., 2006b, “Lap Splices Anchored by Headed Bars,” *ACI Structural Journal*, V. 103, No. 2, Mar.-Apr., pp. 271-279. doi: [10.14359/15185](https://doi.org/10.14359/15185)

Thompson, M. K.; Ziehl, M. J.; Jirsa, J. O.; and Breen, J. E., 2005, “CCT Nodes Anchored by Headed Bars—Part 1: Behavior of Nodes,” *ACI Structural Journal*, V. 102, No. 6, Nov.-Dec., pp. 808-815. doi: [10.14359/14788](https://doi.org/10.14359/14788)

Thomsen, J. H. IV, and Wallace, J. W., 2004, “Displacement-Based Design of Slender Reinforced Concrete Structural Walls—Experimental Verification,” *Journal of Structural Engineering*, V. 130, No. 4, pp. 618-630. doi: [10.1061/\(ASCE\)0733-9445\(2004\)130:4\(618\)](https://doi.org/10.1061/(ASCE)0733-9445(2004)130:4(618))

To, N. H. T.; Sritharan, S.; and Ingham, J., 2009, “Strut-and-Tie Nonlinear Cyclic Analysis of Concrete Frames,” *Journal of Structural Engineering*, V. 135, No. 10, pp. 1259-1268. doi: [10.1061/\(ASCE\)0733-9445\(2009\)135:10\(1259\)](https://doi.org/10.1061/(ASCE)0733-9445(2009)135:10(1259))

Treese, R. A., and Jirsa, J. O., 1989, “Bond Strength of Epoxy-Coated Reinforcing Bars,” *ACI Materials Journal*, V. 86, No. 2, Mar.-Apr., pp. 167-174. doi: [10.14359/2341](https://doi.org/10.14359/2341)

Tuchscherer, R. G.; Birrcher, D. B.; Huizinga, M. H.; and Bayrak, O., 2010, “Confinement of Deep Beam Nodal Regions,” *ACI Structural Journal*, V. 107, No. 6, Nov.-Dec., pp. 709-717. doi: [10.14359/51664019](https://doi.org/10.14359/51664019)

Umehara, H., and Jirsa, J. O., 1984, “Short Rectangular RC Columns Under Bidirectional Loadings,” *Journal of Structural Engineering*, V. 110, No. 3, pp. 605-618. doi: [10.1061/\(ASCE\)0733-9445\(1984\)110:3\(605\)](https://doi.org/10.1061/(ASCE)0733-9445(1984)110:3(605))

U.S. Department of Energy (DOE), n.d., Resilience, <https://betterbuildingssolutioncenter.energy.gov/resilience/about> (accessed August 12, 2024)

U.S. Drought Monitor, n.d., <https://droughtmonitor.unl.edu> (accessed August 12, 2024)

USGBC, 2021, “RELi 2.0 Rating Guidelines for Resilient Design and Construction,” U.S. Green Building Council, Washington, DC, 116 pp.

USGS, n.d., Earthquake Hazard Program, <https://www.usgs.gov/programs/earthquake-hazards/earthquakes> (accessed August 12, 2024)

USRC, 2019, *Implementation Manual for the USRC Building Rating System for Earthquake Hazards*, U.S. Resiliency Council, Atherton, CA, 54 pp.

Uzel, A.; Podgorniak, B.; Bentz, E.; and Collins, M., 2011, “Design of Large Footings for One-Way Shear,” *ACI Structural Journal*, V. 108, No. 2, pp. 131-138. doi: [10.14359/51664247](https://doi.org/10.14359/51664247)

Uzumeri, S. M., and Seckin, M., 1974, “Behavior of Reinforced Concrete Beam-Column Joints Subjected to Slow Load Reversals,” Publication No. 74-05, Department of Civil Engineering, University of Toronto, Toronto, ON, Canada, 93 pp.

Vanderbilt, M. D., 1972, “Shear Strength of Continuous Plates,” *Journal of the Structural Division*, V. 98, May, pp. 961-973. doi: [10.14359/51685238](https://doi.org/10.14359/51685238)

Vanderbilt, M. D., and Corley, W. G., 1983, “Frame Analysis of Concrete Buildings,” *Concrete International*, V. 5, No. 12, Dec., pp. 33-43. doi: [10.14359/9202](https://doi.org/10.14359/9202)

Vanderbilt, M. D.; Sozen, M. A.; and Siess, C. P., 1969, “Test of a Modified Reinforced Concrete Two-Way Slab,” *Journal of the Structural Division*, V. 95, No. ST6, June, pp. 1097-1116.

VanGeem, M. G., 1987, “Measuring Thermal Performance of Wall Assemblies under Dynamic Temperature Conditions,” *Journal of Testing and Evaluation*, V. 15, No. 3, May, pp. 78-187. doi: [10.1520/JTE11004J](https://doi.org/10.1520/JTE11004J)

VanGeem, M. G.; Fiorato, A. E.; and Musser, D. W., 1983, “Calibrated Hot Box Tests of Thermal Performance of Concrete Walls,” *Proceedings of the ASHRAE/DOE Conference on Thermal Performance of the Exterior Envelopes of Buildings II*, SP-38, ASHRAE, pp. 108-130.

Vintzileou, E., and Eligehausen, R., 1992, “Behavior of Fasteners under Monotonic or Cyclic Shear Displacements,” *Anchors in Concrete: Design and Behavior*, SP-130, American Concrete Institute, Farmington Hills, MI, pp. 181-203. doi: [10.14359/1272](https://doi.org/10.14359/1272)

Vu, S.; Li, N. B.; and Beyer, K., 2014, “Effective Stiffness of Reinforced Concrete Coupling Beams,” *Engineering Structures*, V. 76, pp. 371-382. doi: [10.1016/j.engstruct.2014.07.014](https://doi.org/10.1016/j.engstruct.2014.07.014)

Wallace, J. W., 1996, “Evaluation of UBC-94 Provisions for Seismic Design of RC Structural Walls,” *Earthquake Spectra*, V. 12, No. 2, May, pp. 327-348. doi: [10.1193/1.1585883](https://doi.org/10.1193/1.1585883)

Wallace, J. W., 1998, “Behavior and Design of High-Strength RC Walls,” *High-Strength Concrete in Seismic Regions*, SP-176, C. W. French and M. E. Kreger, eds., American Concrete Institute, Farmington Hills, MI, pp. 259-279. doi: [10.14359/5903](https://doi.org/10.14359/5903)

Wallace, J. W., 2012, "Behavior, Design, and Modeling of Structural Walls and Coupling Beams—Lessons from Recent Laboratory Tests and Earthquakes," *International Journal of Concrete Structures and Materials*, V. 6, No. 1, pp. 3-18. doi: [10.1007/s40069-012-0001-4](https://doi.org/10.1007/s40069-012-0001-4)

Wallace, J. W., and Orakcal, K., 2002, "ACI 318-99 Provisions for Seismic Design of Structural Walls," *ACI Structural Journal*, V. 99, No. 4, July-Aug., pp. 499-508. doi: [10.14359/12119](https://doi.org/10.14359/12119)

Wallace, J. W.; Massone, L. M.; Bonelli, P.; Dragovich, J.; Lagos, R.; Lüders, C.; and Moehle, J. P., 2012, "Damage and Implications for Seismic Design of RC Structural Wall Buildings," *Earthquake Spectra*, V. 28, pp. 281-299. doi: [10.1193/1.4000047](https://doi.org/10.1193/1.4000047)

Wallace, J.; Segura, C.; and Tran, T., 2013, "Shear Design of Structural Walls," Los Angeles Tall Buildings Structural Design Council Annual Meeting, 13 pp.

Wang, H.-C., 2020, "Behavior and Design of Concrete Frame Corners: Strut-and-Tie Method Approach," PhD dissertation, Purdue University, West Lafayette, IN, 336 pp.

Wang, H., and Wu, T., 2022, "Statistical Investigation of Wind Duration using a Refined Hurricane Track Model," *Journal of Wind Engineering and Industrial Aerodynamics*, V. 221, No. 7, Feb., pp. 1-10. doi: [10.1016/j.jweia.2022.104908](https://doi.org/10.1016/j.jweia.2022.104908)

Watson, S.; Zahn, F. A.; and Park, R., 1994, "Confining Reinforcement for Concrete Columns," *Journal of Structural Engineering*, V. 120, No. 6, June, pp. 1798-1824. doi: [10.1061/\(ASCE\)0733-9445\(1994\)120:6\(1798\)](https://doi.org/10.1061/(ASCE)0733-9445(1994)120:6(1798))

Waweru, R. N.; Palacios, G.; and Chao, S. H., 2018, "Strength of Interface Reinforcement with Limited Development Length," *ACI Structural Journal*, V. 115, No. 4, July-Aug., pp. 983-996. doi: [10.14359/51702061](https://doi.org/10.14359/51702061)

Weber-Kamin, A. S.; Lequesne, R. D.; and Lepage, A., 2020, "Reinforced Concrete Coupling Beams with High-Strength Steel Bars," *SM Report No. 143*, The University of Kansas Center for Research, Inc., Lawrence, KS, 598 pp.

Welt, T. S., 2015, "Detailing for Compression in Reinforced Concrete Wall Boundary Elements: Experiments, Simulations, and Design Recommendations," PhD dissertation, University of Illinois at Urbana-Champaign, Champaign, IL, 530 pp.

Welt, T. S.; Massone, L. M.; LaFave, J. M.; Lehman, D. E.; McCabe, S. L.; and Polanco, P., 2017, "Confinement Behavior of Rectangular Reinforced Concrete Prisms Simulating Wall Boundary Elements," *Journal of Structural Engineering*, V. 143, No. 4, p. 04016204. doi: [10.1061/\(ASCE\)ST.1943-541X.0001682](https://doi.org/10.1061/(ASCE)ST.1943-541X.0001682)

West, J. S.; Innocenzi, M. J.; Ulloa, F. V.; and Poston, R. W., 2008, "Assessing Vibrations," *Concrete International*, V. 30, No. 10, Oct., pp. 43-49. doi: [10.14359/19985](https://doi.org/10.14359/19985)

Widianto; Bayrak, O.; and Jirsa, J. O., 2009, "Two-Way Shear Strength of Slab-Column Connections: Reexamination of ACI 318 Provisions," *ACI Structural Journal*, V. 106, No. 2, Mar.-Apr., pp. 160-170. doi: [10.14359/56354](https://doi.org/10.14359/56354)

Wilford, M. R., and Young, P., 2006, *A Design Guide for Footfall Induced Vibration of Structures*, The Concrete Centre, Surrey, UK, 83 pp.

Wilson, E. L., 1997, "Three-Dimensional Dynamic Analysis of Structures—With Emphasis on Earthquake Engineering," Computers and Structures, Inc., Berkeley, CA.

Wilson, M. L., and Tennis, P. D., 2021, *Design and Control of Concrete Mixtures*, EB001, 17th edition, Portland Cement Association, Skokie, IL, 585 pp.

Winter, G., 1979, "Safety and Serviceability Provisions in the ACI Building Code," *Concrete Design: U.S. and European Practices*, SP-59, American Concrete Institute, Farmington Hills, MI, pp. 35-49. doi: [10.14359/17764](https://doi.org/10.14359/17764)

Wire Reinforcement Institute, 2001, *Structural Welded Wire Reinforcement Manual of Standard Practice*, sixth edition, Hartford, CT, Apr., 38 pp.

Wood, S. L.; Stanton, J. F.; and Hawkins, N. M., 2000, "Development of New Seismic Design Provisions for Diaphragms Based on the Observed Behavior of Precast Concrete Parking Garages during the 1994 Northridge Earthquake," *PCI Journal*, V. 45, No. 1, Jan.-Feb., pp. 50-65. doi: [10.15554/pcij.01012000.50.65](https://doi.org/10.15554/pcij.01012000.50.65)

Woods, H., 1966, "Corrosion of Embedded Material Other than Reinforcing Steel," *Bulletin 198*, Portland Cement Association, Skokie, IL.

Worsfold, B., and Moehle, J., 2022, "Laboratory Tests of Column-Foundation Moment Transfer Connections with Shear Reinforcement," *Structural Engineering, Mechanics, and Materials (SEMM) Report UCB/SEMM-2022/01*, University of California, Berkeley, Berkeley, CA, 243 pp.

Worsfold, B., and Moehle, J., 2023a, "Moment Transfer at Column-to-Footing Connections: Analytical Studies," *ACI Structural Journal*, V. 120, No. 2, Mar., pp. 205-216. doi: [10.14359/51737146](https://doi.org/10.14359/51737146)

Worsfold, B., and Moehle, J., 2023b, "Shear-Reinforced Concrete Breakout Design Methodology for Moment Transfer at Column-Foundation Connections," *Engineering Structures*, V. 283, May, pp. 1-10. doi: [10.1016/j.engstruct.2023.115783](https://doi.org/10.1016/j.engstruct.2023.115783)

Worsfold, B.; Moehle, J.; and Silva, J., 2022, "Moment Transfer at Column-Foundation Connections: Physical Tests," *ACI Structural Journal*, V. 119, No. 5, Sept., p. 95-110. doi: [10.14359/51734799](https://doi.org/10.14359/51734799)

Wyllie Jr., L. A., 1987, "Structural Walls and Diaphragms—How They Function," *Building Structural Design Handbook*, R. N. White and C. G. Salmon, eds., John Wiley & Sons, Inc., New York, pp. 188-215.

Xanthakis, M., and Sozen, M. A., 1963, "An Experimental Study of Limit Design in Reinforced Concrete Flat Slabs," *Structural Research Series No. 277*, Civil Engineering Studies, University of Illinois, Urbana, IL, Dec., 159 pp. doi: [10.14359/16666](https://doi.org/10.14359/16666)

Yamada, T.; Nanni, A.; and Endo, K., 1991, "Punching Shear Resistance of Flat Slabs: Influence of Reinforcement

Type and Ratio,” *ACI Structural Journal*, V. 88, No. 4, July-Aug., pp. 555-563. doi: [10.14359/2984](https://doi.org/10.14359/2984)

Yang, F., ed., 2018, *Whole Building Life Cycle Assessment: Reference Building Structure and Strategies*, American Society of Civil Engineers, Reston, VA, 80 pp.

Yang, Y.; Varma, A.; Kreger, M. E.; Wang, Y.; and Zhang, K., 2021, “Shear Strength of Reinforced Concrete Beams with T-Headed Bars for Safety-Related Nuclear Structures,” *Engineering Structures*, V. 230, Article 111705, pp. 1-14. doi: [10.1016/j.engstruct.2020.111705](https://doi.org/10.1016/j.engstruct.2020.111705)

Yoshioka, K., and Sekine, M., 1991, “Experimental Study of Prefabricated Beam-Column Subassemblages,” *Design of Beam-Column Joints for Seismic Resistance*, SP-123, J. O. Jirsa, ed., American Concrete Institute, Farmington Hills, MI, pp. 465-492. doi: [10.14359/2876](https://doi.org/10.14359/2876)

Zarrinpour, M. R., and Chao, S.-H., 2017, “Shear Strength Enhancement Mechanisms of Steel Fiber- Reinforced Concrete Slender Beams,” *ACI Structural Journal*, V. 114, No. 3, May-June, pp. 729-742. doi: [10.14359/51689449](https://doi.org/10.14359/51689449)

Zhang, L., 2015, “Testing Air Content of Dry-Mix Shotcrete,” *Shotcrete*, V. 17, No. 2, pp. 22-24.

Zhang, Y.; Klingner, R. E.; and Graves III, H. L., 2001, “Seismic Response of Multiple-Anchor Connections to Concrete,” *ACI Structural Journal*, V. 98, No. 6, Nov.-Dec., pp. 811-822. doi: [10.14359/10748](https://doi.org/10.14359/10748)

Zhu, S., and Jirsa, J. O., 1983, “Study of Bond Deterioration in Reinforced Concrete Beam-Column Joints,” *PMFSEL Report No. 83-1*, Department of Civil Engineering, University of Texas at Austin, Austin, TX, July, 79 pp. doi: [10.14359/51685438](https://doi.org/10.14359/51685438)

Zia, P., and Hsu, T. T. C., 2004, “Design for Torsion and Shear in Prestressed Concrete Flexural Members,” *PCI Journal*, V. 49, No. 3, May-June, pp. 34-42. doi: [10.15554/pcij.05012004.34.42](https://doi.org/10.15554/pcij.05012004.34.42)

Zsutty, T. C., 1971, “Shear Strength Prediction for Separate Categories of Simple Beams Tests,” *ACI Journal Proceedings*, V. 68, No. 2, Feb., pp. 138-143. doi: [10.14359/11300](https://doi.org/10.14359/11300)



Notes



INDEX

Acceptance criteria

- density of lightweight concrete, 26.12.6
- load test, 27.5.3, 27.6.2
- shotcrete, 26.12.5
- standard-cured specimens, 26.12.3
- steel fiber-reinforced concrete, 26.12.8

Adhesive anchors

- bond strength, 17.6.5
- embedment depth limits, 17.3.3
- inspection, 26.13.1.6, 26.13.2.5
- proof loading, 26.7.1(k)
- qualified installer, 26.7.2(d), 26.7.2(e)
- seismic, 17.10
- sustained tension, 17.5.1.3, 17.5.2, 26.7.1(l), 26.13.3.2(e)

Admixtures, 26.4.1.5

Aggregates, 26.4.1.2

Alternative construction materials, 1.10

Aluminum embedments, 20.6.3

Analysis, structural, See Structural analysis

Anchorage of bar groups in tension, 25.4.11

Anchorage zone, 25.9

Anchoring to concrete, 26.7, Ch. 17, 18.2.3

- adhesive bond strength, 17.6.5
- anchor failure modes, 17.5.1.3
- anchor strength, 17.6, 17.7
- breakout strength in shear, 17.7.2
- construction documents, 26.7
- ductile steel element, 21.2.1
- edge distances to preclude splitting, 17.9
- inspection, 26.13
- installation, 26.7
- lightweight concrete, 17.2.4
- nonductile steel element, 21.2.1
- pryout, 21.2.1, 17.7.3
- pullout strength, 17.6.3
- reduction factors, 21.2.1
- scope, 17.1
- seismic design, 17.10
- shear loading, 17.7
- side-face blowout, 17.6.4
- spacings to preclude splitting, 17.9
- strength of anchors, general requirements, 17.5
- stretch length, 17.10.5.3
- sustained tension load, 17.5.2.2
- tensile and shear interaction, 17.8
- tensile loading, 17.6
- thicknesses to preclude splitting, 17.9

Anchor reinforcement, 17.5.2.1

Axial force through the floor system, 15.8

Axial strength, 22.4

Bar bending, 26.6.3

Beam-column joints, Ch. 15

- axial force through slab system, 15.8
- confined, 15.5.2.5

- detailing, 15.7

- intermediate moment frames, 18.4.4
- not participating in the SFRS, 18.14.3
- ordinary moment frames, 18.3.4
- puddling, 15.8
- scope, 15.1
- special moment frames, 18.8

Beams, Ch. 9

- coupling beams, 18.10.7
- deflection limits, 9.3.2
- design limits, 9.3
- design strength, 9.5
- intermediate moment frames, 18.4.2
- minimum depth, 9.3.1
- not participating in the SFRS, 18.14.3, 18.14.4
- ordinary moment frames, 18.3.2
- reinforcement details, 9.7
- reinforcement limits, 9.6
- required strength, 9.4
- scope, 9.1
- simplified method of analysis, 6.5
- special moment frames, 18.6
- stability, 9.2.3
- strain limit, 9.3.3
- stress limit, 9.3.4
- structural integrity, 9.7.7

Bearing, 22.8

- plain concrete, 14.5.6
- reinforced concrete, 22.8

Bend diameters, 25.3

Boundary elements, 18.10.6, 25.2.3

Brackets and corbels, 16.5, 23.2.11

- construction tolerance, 26.6.2
- design strength, 16.5.4
- dimensional limits, 16.5.2
- limits, 16.5.1.1
- reinforcement detailing, 16.5.6
- reinforcement limits, 16.5.5, 23.2.11
- required strength, 16.5.3

Building official, 1.6, 1.8.2, 1.10.1

Bundled reinforcement, 25.6

Caissons, 13.4, 18.13

Cantilever retaining walls, 11.1.4, 13.3.6

Cementitious materials, 26.4.1.1, 26.4.2.2

Classification of prestressed flexural members, 24.5.2

Closed stirrups, 25.7.1.6

Cold weather, 26.5.4

Collector reinforcement, 12.5.1.5, 12.7.3

Collectors, 4.4.7, 12.4.1, 12.5.1, 12.5.3, 12.5.4, 18.12.3, 18.12.7

Columns, Ch. 10

- design limits, 10.3
- design strength, 10.5
- intermediate moment frames, 18.4.3
- not participating in the SFRS, 18.14.3, 18.14.4

- ordinary moment frames, 18.3.3
- reinforcement detailing, 10.7
- reinforcement limits, 10.6
- required strength, 10.4
- scope, 10.1
- special moment frames, 18.7

Combined flexural and axial strength, 22.4

- maximum axial compressive strength, 22.4.2
- maximum axial tensile strength, 22.4.3

Compliance requirements, 26.1.1(b)

Composite flexural members

- flexure, 22.3.3
- general, 4.12.3
- horizontal shear, 16.4
- vertical shear, 22.5.4

Composite steel deck, 1.4.11

Composite systems, 4.12.3

Concrete

- acceptance criteria, 26.12.3
- characteristics, 26.4.4
- consolidation, 26.5.2
- cover, 20.5.1
- low-strength results, 26.12.7
- materials, 26.4.1
- mixture requirements, 19.3.2, 26.4.2
- modulus of elasticity, 19.2.2
- modulus of rupture, 19.2.3
- placement, 26.5.2
- production, 26.5.1
- proportioning, 26.4.3
- testing frequency, 26.12.2

Concrete breakout, anchors, 17.6.2, 17.7.2

Concrete properties, Ch. 19

- design properties, 19.2
- durability requirements, 19.3
- grout durability requirements, 19.4
- maximum compressive strength, 19.2.1.1
- minimum compressive strength, 19.2.1.1, 19.3.2.1
- scope, 19.1

Concrete pryout, anchors, 17.7.3

Concrete side-face blowout, headed anchors, 17.6.4

Confined joint

- beam-column joint, 15.7.1
- slab-column joint, 15.7.2

Connections

- cast-in-place, Ch. 15
- precast, Ch. 16

Connections between members, Ch. 16

- brackets, 16.5
- corbels, 16.5
- foundations, 16.3
- horizontal shear, 16.4
- precast members, 16.2
- scope, 16.1

Connections to foundations, 16.3

- design strength, 16.3.3
- detailing, cast-in-place members, 16.3.5

- detailing, precast members, 16.3.6
- minimum reinforcement, 16.3.4
- required strength, 16.3.2

Consolidation, 26.5.2

Construction, 4.13, Ch. 26

Construction documents and inspection, 1.8, Ch. 26

- anchoring to concrete, 26.7
- concrete acceptance, 26.12
- concrete construction, 26.5
- concrete evaluation, 26.12
- concrete materials, 26.4
- concrete production, 26.5
- design criteria, 26.2
- embedments, 26.8
- formwork, 26.11
- inspection, 26.13
- member information, 26.3
- mixture requirements, 26.4
- precast concrete, 26.9
- prestressed concrete, 26.10
- reinforcement materials, 26.6
- scope, 26.1
- special moment frames, 26.13.1.3, 26.13.3.2

Construction joint, 18.10.10, 26.5.6

Contraction joint, 14.3.4, 26.5.6

Corbels, See Brackets and corbels

Cores, 26.12.7

Corrosion

- concrete requirements, 19.3.2
- corrosive environment, 19.3.1

Corrosion, reinforcement

- external post-tensioning, 20.5.6
- grouted tendons, 20.5.4
- post-tensioning hardware, 20.5.5
- unbonded prestressing reinforcement, 20.5.3

Coupling beams, 18.10.7

- strength limit, 18.10.7.4

Cover, concrete, 20.5.1

Cracking torsion, 22.7.5

Critical section

- beams factored moment, 9.4.2
- beams factored shear, 9.4.3
- beams factored torsion, 9.4.4
- one-way slabs moment, 7.4.2
- one-way slabs shear, 7.4.3
- two-way shear perimeter, 22.6.4
- two-way slabs shear, 8.4.4.1

Critical spacing, anchor groups, 17.2.1.1

Crossties, 18.6.4.3, 18.7.5.2, 18.10.7.4, 18.13.5.10.5, 23.6.3.3, 25.3

Curing, 26.5.3

Deep beams, 9.9, 23.2.9

- dimensional limits, 9.9.2
- reinforcement detailing, 9.9.4
- reinforcement limits, 9.9.3

Deep foundations, 13.4, 18.13

- allowable axial strength, 13.4.2

- cast-in-place, 13.4.4
- pile caps, 13.4.6
- precast, 13.4.5
- strength design, 13.4.3

Definitions, Ch. 2

Deflection limits, 24.2.2

- beams, 9.3.2
- load testing, 27.5.3
- one-way slabs, 7.3.2
- two-way slabs, 8.3.2

Deflections, 24.2

- composite construction, 24.2.5
- immediate, 24.2.3
- time-dependent, 24.2.4

Design information, 26.1.1(a)

Design limits

- beams, 9.3
- columns, 10.3
- diaphragms, 12.3
- one-way slabs, 7.3
- plain concrete, 14.3
- two-way slabs, 8.3
- walls, 11.3

Design loads, 4.3, Ch. 5

Design properties, concrete, 19.2

- lightweight, 19.2.4
- modulus of elasticity, 19.2.2
- modulus of rupture, 19.2.3
- specified compressive strength, 19.2.1

Design properties, reinforcement

- nonprestressed, 20.2.2
- prestressing strand, 20.3.2

Design records, 1.8

Design strength

- beams, 9.5
- brackets and corbels, 16.5.4
- columns, 10.5
- connections to foundations, 16.3.3
- corbels, 16.5.4
- diaphragms, 12.5
- horizontal shear, 16.4.3
- one-way slabs, 7.5
- plain concrete, 14.5
- precast connections, 16.2.3
- strength reduction factors, Ch. 21, 17.5.1.1
- two-way slabs, 8.5
- walls, 11.5

Detailing

- beam, 9.7
- beam-column joint, 15.7
- brackets, 16.5.6
- collector, 18.12.7.6
- column, 10.7
- connections to foundations, 16.3.5, 16.3.6
- corbels, 16.5.6
- diaphragm, 12.7

- horizontal shear, 16.4.7
- one-way slab, 7.7
- plain concrete, 14.6
- shear-friction, 22.9.5
- slab-column joint, 15.7
- strut-and-tie, 23.6, 23.8
- two-way slab, 8.7
- wall, 11.7

Development length, 25.4

- deformed bars, 25.4.2, 25.4.9
- deformed wires, 25.4.2, 25.4.9
- earthquake-resistant structures, 18.8.5, 18.10.2.3(b), 18.13.2.3
- excess reinforcement reduction factor, 25.4.10
- headed deformed bars, 25.4.4
- mechanical anchors, 25.4.5
- pretensioned seven-wire strand, 25.4.8
- special moment frames, joints, 18.8.5.1
- special structural walls, 18.10.2.3
- standard hooks, 25.4.3
- welded deformed wires, 25.4.6
- welded plain wires, 25.4.7

Diaphragms, 4.4.7, 6.2.4.3, Ch. 12

- collector, 12.5.4
- design limits, 12.3
- design strength, 12.5
- reinforcement detailing, 12.7
- reinforcement limits, 12.6
- required strength, 12.4
- scope, 12.1
- shrinkage and temperature reinforcement, 12.6

Diaphragms and trusses, earthquake-resistant structures, 18.12

- cast-in-place topping, 18.12.4, 18.12.5
- construction joints, 18.12.10
- design forces, 18.12.2
- flexural strength, 18.12.8
- minimum thickness, 18.12.6
- precast, 18.12.11
- reinforcement, 18.12.7
- scope, 18.12.1
- seismic load path, 18.12.3
- shear strength, 18.12.9
- structural trusses, 18.12.12

Drilled piers, 1.4.7, 13.4, 18.13.5

Drop panel, 8.2.4

Dual-coated reinforcement, 25.4, 25.7.3.6

Durability, 4.8, 19.3.2, 26.4, 20.5

Durability requirements, 19.3

- additional requirements for chloride ion content, 19.3.4
- exposure categories and classes, 19.3.1
- freezing-and-thawing, 19.3.3
- requirements for concrete mixtures, 19.3.2

Earthquake-resistant structures, Ch. 18

- beams of special moment frames, 18.6
- columns of special moment frames, 18.7
- diaphragms, 18.12

- foundations, 18.13
- intermediate moment frames, 18.4
- intermediate precast structural walls, 18.5
- joints of special moment frames, 18.8
- members not designated as part of the SFRS, 18.14
- ordinary moment frames, 18.3
- precast intermediate structural walls, 18.5
- precast special moment frames, 18.9
- precast special structural walls, 18.11
- scope, 18.1
- special moment frames, 18.6, 18.7, 18.8
- special structural walls, 18.10
- strut-and-tie, 23.11
- trusses, 18.12

Elastic second-order analysis, 6.7

- section properties, 6.7.2
- section properties, factored load analysis, 6.7.2.1, 6.6.3.1
- section properties, service load analysis, 6.7.2.2

Embedments, 20.6, 26.8

End-bearing splices, 25.5.6

Epoxy-coated reinforcement, 20.5.2

Equilibrium, 22.2.1

Equivalent stress block, 22.2.2.4

Existing structures, 4.14, Ch. 27

- acceptance criteria, 27.5.3, 27.6.2
- analytical strength evaluation, 27.3
- as-built condition, 27.3.1
- load factors, test load, 27.4.6
- response measurements, 27.5.2
- strength evaluation, Ch. 27
- strength reduction factors, existing building, 27.3.2
- test load application, 27.5.1
- test load arrangement, 27.4.6.1

Exposure category, 19.3.1

Exposure class, 19.3.1

f'_c limits, anchors, 17.3.1

Finite element analysis, 6.9

Fire resistance, 4.11

First-order analysis, 6.6

- moment magnification method, 6.6.4
- section properties, 6.6.3
- slenderness effects, 6.6.4
- redistribution of moments, 6.6.5

Flexural and axial strength, See Combined flexural and axial strength

Flexural strength, 22.3

- composite members, 22.3.3
- prestressed members, 22.3.2

Flood load, 5.3.9

Fluid load, 5.3.7

Folded plates, 1.4.4

Formwork, 26.11

Formwork removal, 26.11.2

Foundations, Ch. 13, 14.4.3, 18.13

- critical sections, 13.2.7
- deep foundations, 13.4
- design criteria, 13.2.6

- earthquake effects, 13.2.3
- scope, 13.1
- shallow foundations, 13.3
- slabs-on-ground, 13.2.4

Foundations, earthquake-resistant structures, 18.13

- anchorage of deep foundations, 18.13.6
- caissons, 18.13.5
- footings, 18.13.2
- foundation mats, 18.13.2
- grade beams, 18.13.3
- piers, 18.13.5
- pile caps, 18.13.2
- piles, 18.13.5
- seismic ties, 18.13.4
- slabs-on-ground, 18.13.3

Freezing and thawing, 19.3.3

General ACI 318, Ch. 1

- applicability, 1.4
- approval of special systems of design, 1.10
- building official, 1.6
- caissons, 1.4.7
- composite steel deck, 1.4.11
- construction documents, 1.8
- drilled piers, 1.4.7
- fiber-reinforced polymer (FRP), 1.4.9
- interpretation, 1.5
- jurisdiction, 1.2
- licensed design professional, 1.7
- modifications, 1.2.6
- multiple single-family dwellings, 1.4.6
- noncomposite steel decks, 1.4.5
- official version, 1.2.3
- one-family dwellings, 1.4.6
- piles, 1.4.7
- purpose, 1.3
- reservoirs, 1.4.10
- scope of 318, 1.1
- slabs-on-ground, 1.4.8
- tanks, 1.4.10
- testing and inspection, 1.9
- thin shells, 1.4.4
- townhouses, 1.4.6
- two-family dwellings, 1.4.6

General building code, 1.2.2, 1.2.5, 1.2.7, 1.4.1, 1.4.3, 1.9.2

Grade beams, 13.3.2, 18.13.3

Headed shear stud reinforcement, 8.7.7, 20.4

Hooks, 25.3

Hoops, 25.7.4

Horizontal shear, 16.4

- alternative method, 16.4.5
- design strength, 16.4.3
- detailing, 16.4.7
- minimum reinforcement, 16.4.6
- nominal strength, 16.4.4
- required strength, 16.4.2

Hot weather, 26.5.5

Ice load, 5.3.10

Inelastic analysis, 6.8**Inspection, 1.9, 4.13, 26.13, Ch. 26**

- items to be inspected, 26.13.3
- reports, 26.13.2
- requirements, 26.1.1(c)

Inspector qualifications, 26.13.1.2, R26.13.1.2**Integrity ties, 16.2, 16.2.1.8, 16.2.4, 16.2.5****Interaction effects, anchors, 17.5.2.3, 17.8****Intermediate moment frames, 18.4**

- beams, 18.4.2
- columns, 18.4.3
- joints, 18.4.4
- two-way slabs, 18.4.5

Intermediate precast structural walls, 18.5**Investigation of strength-tests, 26.12.7****Isolation joint, 26.5.6****Joints**

- beam-column, Ch. 15
- construction, 26.5.6
- construction documents, 26.5.6
- contraction, 26.5.6
- isolation, 26.5.6
- slab-column, Ch. 15

Jurisdiction, 1.2.2, 1.2.6, 1.5.7, 1.6.2, 1.8.1**Lap splices**

- deformed bars and deformed wires in tension, 25.5.2
- deformed bars in compression, 25.5.5
- welded deformed wire reinforcement in tension, 25.5.3
- welded plain wire reinforcement in tension, 25.5.4

Lateral earth pressure load, 5.3.8**Licensed design professional, 1.7****Lift-slab construction, 8.9****Lightweight concrete, 19.2.4****Lightweight concrete, anchors, 17.2.4****Live load, arrangement, 6.4****Live load reductions, 5.2.3****Load combinations, 5.3****Load factors, 5.3****Load paths, 4.4, 18.12.3****Load test, 27.4****Loads, Ch. 5**

- earthquake, 5.2.2
- flood load, 5.3.9
- fluid load, 5.3.7
- ice load, 5.3.10
- lateral earth pressure load, 5.3.8
- live load reductions, 5.2.3
- load combinations, 5.3
- load factors, 5.3
- post-tensioned anchorage zone load, 5.3.15
- prestressing load, 5.3.14
- restraint load, 5.3.6
- Seismic Design Categories, 5.2.2
- strut-and-tie method, prestressing, 5.3.16
- tornado, 5.3.11
- tsunami, 5.3.12

- water in soil, 5.3.13

- wind load, 5.3.5

Low strength-test results, 26.12.7**Mat foundations, 13.3.4, 18.13.2****Materials, 4.2**

- concrete, Ch. 19
- embedment, 20.6
- nonprestressed reinforcement, 20.2
- prestressing reinforcement, 20.3
- steel reinforcement, Ch. 20

Maximum anchor diameter, 17.3.2**Mechanical splices, 18.2.7, 25.5.7****Members not designated as part of the SFRS, 18.14**

- beams, 18.14.3
- columns, 18.14.3
- design actions, 18.14.2
- joints, 18.14.3
- precast beams, 18.14.4
- precast columns, 18.14.4
- slab-column connections, 18.14.5
- wall piers, 18.14.6

Minimum beam depth, 9.3.1, 18.6.2.1**Minimum bend diameters, 25.3****Minimum flexural reinforcement**

- beams, 9.6.1, 9.6.2
- one-way slabs, 7.6.1, 7.6.2
- two-way slabs, 8.6.1, 8.6.2

Minimum reinforcement

- connections to foundations, 16.3.4
- horizontal shear, 16.4.6
- special moment frames, 18.7.4
- special structural walls, 18.10.2

Minimum shear reinforcement

- beams, 9.6.3
- one-way slabs, 7.6.3

Minimum size, precast bearing connections, 16.2.6**Minimum spacing, reinforcement, 25.2****Minimum thickness**

- diaphragm, 12.3.1
- diaphragm, earthquake-resistant structures, 18.12.6
- one-way slabs, 7.3.1
- two-way slabs, 8.3.1
- walls, 11.3.1, 18.10

Mixture proportioning, 26.4.3**Modeling assumptions, 6.3****Modulus of elasticity**

- concrete, 19.2.2
- nonprestressed reinforcement, 20.2.2.2
- prestressed reinforcement, 20.3.2.1

Modulus of rupture, 19.2.3**Moment magnification, 6.6.4****Moment of inertia, effective, 24.2.3.5****Moment redistribution, 6.6.5****Noncomposite steel decks, 1.4.5****Nonprestressed reinforcement**

- design properties, 20.2.2

- material properties, 20.2.1

Nonsway frame, 6.6.4.5

Notation, 2.2

Offset bent longitudinal reinforcement, 10.7.4, 10.7.6.4

One-way joist systems, 9.8

One-way shallow foundations, 13.3.2

One-way shear, 22.5

- composite members, 22.5.4
- concrete strength, 22.5.5, 22.5.6, 22.5.7
- effective depth, 22.5.2
- material strength limits, 22.5.3
- reinforcement, 22.5.8

One-way slabs, Ch. 7

- deflection limits, 7.3.2
- design limits, 7.3
- design strength, 7.5
- minimum slab thickness, 7.3.1
- reinforcement detailing, 7.7
- reinforcement limits, 7.6
- required strength, 7.4
- scope, 7.1
- simplified method of analysis, 6.5
- strain limit, 7.3.3
- stress limits, 7.3.4

Ordinary moment frames, 18.3

Pedestals, 14.3.3

Piers, 18.13.5

Pile caps, 13.4.6, 18.13.2

Piles, 1.4.7, 13.4.4, 13.4.5, 18.13.5

Placement

- concrete, 26.5.2
- reinforcement, 26.6.2

Plain concrete, 4.12.4, Ch. 14

- design limits, 14.3
- design strength, 14.5
- precast, 14.2.3
- reinforcement detailing, 14.6
- required strength, 14.4
- scope, 14.1

Post-tensioned anchorage zone, 7.7.4.3.1, 8.7.5.4.1, 9.7.4.3.1, 25.9

Post-tensioned anchorage zone load, 5.3.15

Post-tensioning anchorage, 7.7.4.3.2, 8.7.5.4.2, 9.7.4.3.2, 25.8

Post-tensioning coupler, 7.7.4.3.2, 8.7.5.4.2, 9.7.4.3.2, 25.8

Precast concrete

- connections, 16.2.4
- construction documents, 26.9
- intermediate structural walls, 18.5
- plain concrete, 14.2.3
- special moment frames, 18.9
- special structural walls, 18.11
- structural integrity, 16.2.5

Precast connections, 16.2

- bearing connections, minimum size, 16.2.6
- connection strength, 16.2.4

- design strength, 16.2.3

- diaphragms, Ch. 12

- integrity ties, 16.2.1.8, 16.2.4, 16.2.5

- required strength, 16.2.2

Precast intermediate structural walls, 18.5

Precast special moment frames, 18.9

Precast special structural walls, 18.11

Precast systems, 4.12.1

Prestress losses, 20.3.2.6

Prestressed concrete

- construction documents, 26.10
- member classification, 24.5.2
- permissible stresses, 24.5

Prestressed members, classification, 24.5.2

Prestressed systems, 4.12.2

Prestressed T-beams, 6.3.2.3

Prestressed, two-way slabs, 8.2.3

Prestressing load, 5.3.14

Prestressing reinforcement, 20.3

- corrosion protection, 20.5.3, 20.5.4, 20.5.5, 20.5.6
- design properties, 20.3.2
- material properties, 20.3.1
- permissible tensile stresses, 20.3.2.5
- prestress losses, 20.3.2.6
- shrinkage and temperature, 24.4.4

Protective coatings, nonprestressed reinforcement, 20.5.2

Puddling, 15.8

Pullout strength

- cast-in anchors, 17.6.3
- post-installed expansion, 17.6.3
- undercut anchors, 17.6.3

Radius of gyration, 6.2.5.2

Redistribution of moments, 6.5

Reduced load rating, 27.2.5

Referenced standards, Ch. 3

Reinforcement materials, Ch. 20, 26.6

- bending, 26.6.3
- placement, 26.6.2
- welding, 26.6.4

Reinforcement detailing

- beams, 9.7
- columns, 10.7
- diaphragms, 12.7
- one-way slabs, 7.7, 24.4.3.5
- plain concrete, 14.6
- shrinkage and temperature, 24.4
- two-way slabs, 8.7
- walls, 11.7

Reinforcement details, Ch. 25

- bundled reinforcement, 25.6
- crossties, 25.3
- development, 25.4
- headed deformed bars, 18.8.5.2, 20.2.1.6, 25.4.4
- minimum bend diameters, 25.3
- minimum spacing, 25.2

- post-tensioned tendons, anchorage zones, 25.9
- post-tensioning anchorages, 25.8
- post-tensioning couplers, 25.8
- scope, 25.1
- seismic hooks, 25.3
- splices, 25.5
- standard hooks, 25.3
- transverse reinforcement, 25.7
- Reinforcement limits**
 - beams, 9.6
 - brackets, 16.5.5
 - columns, 10.6, 18.7.4
 - corbels, 16.5.5
 - diaphragms, 12.6
 - one-way slabs, 7.6
 - two-way slabs, 8.6
 - walls, 11.6, 18.10.2.1
- Required strength**
 - beams, 9.4
 - brackets and corbels, 16.5.3
 - columns, 10.4
 - connections to foundations, 16.3.2
 - corbels, 16.5.3
 - diaphragm, 12.4
 - horizontal shear, 16.4.2
 - load factors and combinations, 5.3
 - one-way slabs, 7.4
 - plain concrete, 14.4
 - precast connections, 16.2.2
 - two-way slabs, 8.4
 - walls, 11.4
- Reservoirs, 1.4.10**
- Residential**
 - multiple single-family dwellings, 1.4.6
 - single-family dwellings, 1.4.6
 - townhouses, 1.4.6
 - two-family dwellings, 1.4.6
- Restraint load, 5.3.6**
- Second-order analysis**
 - elastic, 6.7
 - inelastic, 6.8
- Second-order effects, 6.2.3, 6.2.5.3, 6.6.4, 6.7, 6.8**
- Sectional strength, Ch. 22**
 - design assumptions, 22.2
 - scope, 22.1
- Seismic design, anchoring to concrete, 17.10**
- Seismic Design Categories, 4.4.6, 5.2.2**
- Seismic-force-resisting system, 4.4.6**
- Seismic hooks, 25.3**
- Service load analysis, 6.6.3.2, 6.7.2.2**
- Serviceability requirements, 4.7, Ch. 24**
 - gravity service-level deflections, 24.2
 - permissible stresses, prestressed, 24.5
 - reinforcement distribution, beam, 24.3
 - reinforcement distribution, one-way slabs, 24.3
 - scope, 24.1
 - shrinkage and temperature, 24.4
- Shallow foundations, 13.3**
 - basement walls, 13.3.7
 - cantilever retaining wall components, 13.3.6
 - mat, 13.3.4
 - one-way, 13.3.2
 - two-way combined, 13.3.4
 - two-way isolated, 13.3.3
 - walls as grade beams, 13.3.5
- Shear cap, 8.2.5**
- Shear friction, 22.9**
- Shear reinforcement, two-way slabs**
 - headed studs, 8.7.7
 - stirrups, 8.7.6
- Shells, 1.4.4**
- Shrinkage and temperature reinforcement, 24.4**
 - diaphragm, 12.6
 - nonprestressed, 24.4.3
 - one-way slab, 7.6.4
 - prestressed, 24.4.4
 - two-way slab, 8.8.1.7
- Simplified method, analysis, 6.5**
- Skin reinforcement, 9.7.2.3**
- Slab-column joints, Ch. 15, 18.14.5**
 - axial force through slab system, 15.8
 - confined, 15.5.2.5, 15.7.2
 - detailing, 15.7
 - puddling, 15.8
 - scope, 15.1
- Slabs-on-ground, 1.4.8, 13.2.4, 18.13.3**
- Slender walls, 6.2.4.2, 11.8**
- Slenderness effects, 6.2.5, 6.2.5.3, 6.6.4.5, 6.7.1.2, 6.8.1.3**
- Special moment frames**
 - beams, 18.6
 - columns, 18.7
 - joints, 18.8
 - precast, 18.9
- Special structural systems**
 - reinforcement properties, 20.2.2.5, 20.3.1.3
- Special structural walls, 18.10**
 - boundary elements, 18.10.6
 - construction joints, 18.10.10
 - coupling beams, 18.10.7
 - design forces, 18.10.3
 - ductile coupled walls, 18.10.9
 - flexure and axial force, 18.10.5
 - precast, 18.11
 - reinforcement, 18.10.2
 - shear strength, 18.10.4
 - wall piers, 18.10.8
- Special systems of design, 1.10**
- Specified compressive strength, 19.2.1**
- Specified concrete cover, 20.5.1**
- Spirals, 25.7.3**

Splices, 25.5

- deformed bars, 25.5.2, 25.5.5, 25.5.6
- deformed wires, 25.5.2
- mechanical, 25.5.7
- welded, 25.5.7
- welded deformed bars, 25.5.3
- welded plain wire, 25.5.4

Stability

- beams, 9.2.3
- properties, 6.6.4.4

Stainless-steel reinforcement, 20.2.1.3**Standard hooks, 25.3****Standards, Ch. 3****Steel fibers, 26.4.1.6, 26.12.8****Steel reinforcement properties, Ch. 20**

- durability provisions, 20.5
- embedments, 20.6
- headed shear studs, 20.4
- nonprestressed bars, 20.2
- nonprestressed wires, 20.2
- prestressing bars, 20.3
- prestressing strands, 20.3
- prestressing wires, 20.3
- scope, 20.1

Steel strength, anchors, 17.6.1, 17.7.1**Stirrups, 25.7.1****Strain compatibility, 22.2.1****Strain limit**

- nonprestressed beams, 9.3.3
- nonprestressed one-way slabs, 7.3.3
- nonprestressed two-way slabs, 8.3.3

Strength, 4.6**Strength evaluation of existing structures, 4.14, Ch. 27**

- analytical, 27.3
- cyclic load test procedure, 27.6
- load test, 27.4
- monotonic load test procedure, 27.5
- reduced load rating, 27.2.5
- scope, 27.1

Strength reduction factors, Ch. 21**Strength reduction factors, anchors, 17.5.3, Ch. 21****Strength, specified compressive, 19.2.1****Strength test, 26.12.1.1(a)****Stress limit**

- prestressed beams, 9.3.4
- prestressed one-way slabs, 7.3.4
- prestressed two-way slabs, 8.3.4

Stress, prestressing reinforcement, 20.3.2.3, 20.3.2.4, 20.3.2.5**Structural analysis, 4.5, Ch. 6, 18.2.2**

- arrangement of live load, 6.4
- diaphragms, 6.2.4.3, 12.4.2
- elastic first-order analysis, 6.6
- elastic second-order analysis, 6.7
- finite element analysis, 6.9
- inelastic analysis, 6.8
- modeling assumptions, 6.3

- second-order effects, 6.2.5.3, 6.6.4, 6.7, 6.8
- simplified method, 6.5
- slender walls, 6.2.4.2, 11.8
- slenderness effects, 6.2.5
- strut-and-tie, Ch. 23, 6.2.4.4
- T-beams, 6.3.2

Structural integrity, 4.10

- beams, 9.7.7
- nonprestressed one-way joists, 9.8.1.6
- one-way slabs, 7.7.7
- precast connections, 16.2.1.8
- two-way slabs, 8.7.4.2, 8.7.5.6, 8.8.1.6

Structural systems, Ch. 4

- composite, 4.12.3, 4.12.4
- construction, 4.13, Ch. 26
- design loads, 4.3
- diaphragms, 4.4.7
- durability, 4.8
- fire resistance, 4.11
- inspection, 4.13, Ch. 26
- load paths, 4.4
- materials, 4.2
- plain, 4.12.5
- precast concrete, 4.12.1
- prestressed concrete, 4.12.2
- scope, 4.1
- seismic-force-resisting system, 4.4.6, 18.2.1
- serviceability, 4.7
- strength, 4.6
- strength evaluation of existing structures, 4.14, Ch. 27
- structural analysis, 4.5
- structural integrity, 4.10
- sustainability, 4.9

Strut-and-tie models, 6.2.4.4, Ch. 23

- curved-bar nodes, 23.10
- design strength, 23.3
- discontinuity, 23.1.2
- earthquake-resistant design, 23.11
- minimum distributed reinforcement, 23.5
- scope, 23.1
- strength of nodal zones, 23.9
- strength of struts, 23.4
- strength of ties, 23.7
- strut detailing, 23.6
- tie detailing, 23.8

Sulfate exposure, 26.4.2.2**Sustainability, 4.9, Appendix C****Sway frame, 6.6.4.6****T-beams, 6.3.2, 9.2.4**

- construction, 9.2.4
- geometry, 6.3.2
- one-way slab, 7.5.2.3
- reinforcement distribution, 24.3.4
- seismic, 18.6.2

Tanks, 1.4.10**Tensile strength, prestressed reinforcement, 20.3.2.2**

Terminology, 2.3**Thin shells, 1.4.4****Ties, 25.7.2****Tornado load, 5.3.11****Torsion, 22.7**

- beam, 9.5.4
- column, 10.5.4
- cracking torsion, 22.7.5
- factored design torsion, 22.7.3
- materials, 22.7.2
- section limits, 22.7.7
- threshold torsion, 22.7.4
- torsional strength, 22.7.6

Transfer of column axial force through the floor system, 15.8**Transverse reinforcement, 25.7****Trusses, 18.12.12****Tsunami load, 5.3.12****Two-way combined footings, 13.3.4****Two-way isolated footings, 13.3.3****Two-way joist systems, 8.8****Two-way shear, 22.6**

- concrete strength, 22.6.5
- critical perimeter, 22.6.4
- effective depth, 22.6.1.4
- headed shear studs, 22.6.8
- maximum strength, 22.6.6
- openings, 22.6.4.3
- stirrups, 22.6.7

Two-way slabs, 6.2.4.1, 6.4.3, Ch. 8, 18.4.5

- deflection limits, 8.3.2
- design limits, 8.3
- design strength, 8.5
- minimum slab thickness, 8.3.1
- nonprestressed two-way joist, 8.8
- openings, 8.5.4

- reinforcement detailing, 8.7

- reinforcement limits, 8.6

- required strength, 8.4

- scope, 8.1

- strain limit, 8.3.3

- stress limits, 8.3.4

Wall piers, 18.5.2.3, 18.10.8, 18.14.6**Walls, Ch. 11**

- alternative method, 11.8

- boundary element of special structural wall, 18.10.6

- construction joints, 18.10.10

- design limits, 11.3

- design strength, 11.5

- discontinuous walls, 18.10.11

- ductile coupled walls, 18.10.9

- effective length, 11.5.3.2

- load distribution, 11.2.3

- minimum thickness, 11.3.1

- pier, 18.10.8

- plain concrete, 14.3.1, 14.4.2

- precast intermediate structural, 18.5

- precast special structural, 18.11

- reinforcement around openings, 11.7.6

- reinforcement detailing, 11.7

- reinforcement limits, 11.6

- required strength, 11.4

- scope, 11.1

- simplified design method, 11.5.3

Water, 26.4.1.4**Water in soil load, 5.3.13****Welded splices, 18.2.8, 25.5.7****Welding, 26.6.4****Wind load, 5.3.5****Yield strength, nonprestressed reinforcement, 20.2.2.3****Zinc-coated reinforcement, 20.5.2**



American Concrete Institute
Always advancing

The American Concrete Institute envisions a future where our stakeholders have the knowledge and skills necessary to use concrete effectively in a changing world.

Founded in 1904 with a headquarters in Farmington Hills, Michigan, USA, and a regional office in Dubai, UAE, the American Concrete Institute is always advancing by developing educational programs, publishing technical documents, managing various certification programs, and hosting industry-wide events. With 100 chapters, 215 student chapters, and over 35,000 members spanning over 120 countries, the American Concrete Institute has always retained the same basic mission — to advance knowledge of concrete and its use.

In today's market, it is imperative to be knowledgeable and have an edge over the competition. ACI membership provides concrete industry professionals the chance to save money and time, while increasing productivity, competitiveness, and awareness of new technology and cutting-edge research.

ACI CODE-318-25 Resources

ACI offers a comprehensive slate of resources for designing and constructing according to *ACI CODE-318-25 Building Code for Structural Concrete—Code Requirements and Commentary*. These resources include:



CODE-318-25 Seminars that provide technical updates through comprehensive day-long seminars at your office or a location near you;



CODE-318-25 Webinars that provide technical updates from your desktop;



ACI's *Reinforced Concrete Design Manual* including explanations, analyses, examples, and design aids for reinforced concrete structures;



ACI's *Detailing Manual* providing examples and considerations for conveying your design intent through structural details; and



ACI 318 PLUS offering digital interactive access to ACI CODE-318-19 and ACI CODE-318-25, along with related resources, robust digital notetaking, enhanced search capabilities, and access to the *ACI Detailing Manual* and the *ACI Reinforced Concrete Design Handbook*.

Learn more about these resources at <http://www.concrete.org>.

American Concrete Institute
38800 Country Club Drive
Farmington Hills, MI 48331
Phone: +1.248.848.3700
www.concrete.org



American Concrete Institute
Always advancing

38800 Country Club Drive
Farmington Hills, MI 48331 USA
+1.248.848.3700
www.concrete.org

The American Concrete Institute (ACI) is a leading authority and resource worldwide for the development and distribution of consensus-based standards and technical resources, educational programs, and certifications for individuals and organizations involved in concrete design, construction, and materials, who share a commitment to pursuing the best use of concrete.

Individuals interested in the activities of ACI are encouraged to explore the ACI website for membership opportunities, committee activities, and a wide variety of concrete resources. As a volunteer member-driven organization, ACI invites partnerships and welcomes all concrete professionals who wish to be part of a respected, connected, social group that provides an opportunity for professional growth, networking and enjoyment.



9 781641 953092 >